

File No. 160851

Committee Item No. 5

Board Item No. 1

COMMITTEE/BOARD OF SUPERVISORS

AGENDA PACKET CONTENTS LIST

Committee: Land Use and Transportation

Date August 1, 2016

Board of Supervisors Meeting

Date SEPTEMBER 20, 2016

Cmte Board

- | | | |
|-------------------------------------|-------------------------------------|--|
| <input type="checkbox"/> | <input type="checkbox"/> | Motion |
| <input type="checkbox"/> | <input type="checkbox"/> | Resolution |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | Ordinance |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | Legislative Digest |
| <input type="checkbox"/> | <input type="checkbox"/> | Budget and Legislative Analyst Report |
| <input type="checkbox"/> | <input type="checkbox"/> | Youth Commission Report |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | Introduction Form |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | Department/Agency Cover Letter and/or Report |
| <input type="checkbox"/> | <input type="checkbox"/> | Memorandum of Understanding (MOU) |
| <input type="checkbox"/> | <input type="checkbox"/> | Grant Information Form |
| <input type="checkbox"/> | <input type="checkbox"/> | Grant Budget |
| <input type="checkbox"/> | <input type="checkbox"/> | Subcontract Budget |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | Contract/Agreement |
| <input type="checkbox"/> | <input type="checkbox"/> | Form 126 - Ethics Commission |
| <input type="checkbox"/> | <input type="checkbox"/> | Award Letter |
| <input type="checkbox"/> | <input type="checkbox"/> | Application |
| <input type="checkbox"/> | <input type="checkbox"/> | Form 700 |
| <input type="checkbox"/> | <input type="checkbox"/> | Vacancy Notice |
| <input type="checkbox"/> | <input type="checkbox"/> | Information Sheet |
| <input type="checkbox"/> | <input type="checkbox"/> | Public Correspondence |

OTHER

(Use back side if additional space is needed)

- | | | |
|-------------------------------------|-------------------------------------|----------------------------------|
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <u>Planning Resolution 18271</u> |
| <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <u>Planning Motion 18270</u> |
| <input type="checkbox"/> | <input type="checkbox"/> | |

Completed by: Alisa Somera Date July 29, 2016

Completed by: MM 3 Date 08/03/16

1 [Street Vacation Order - Parkmerced Development Project]

2
3 **Ordinance ordering the conditional vacation of portions of streets (along with public**
4 **service easements within those streets) that exist within the Subphases 1A and 1B of**
5 **the Parkmerced Development Project area, an approximately 152 acre site located in**
6 **the Lake Merced District in the southwest corner of San Francisco and generally**
7 **bounded by Vidal Drive, Font Boulevard, Pinto Avenue, and Serrano Drive to the north,**
8 **19th Avenue and Junipero Serra Boulevard to the east, Brotherhood Way to the south,**
9 **and Lake Merced Boulevard to the west; reserving various easement rights in favor of**
10 **the City and third party utilities, subject to conditions specified in this ordinance;**
11 **delegating authority to the Director of Real Estate to execute certain quit claim deeds;**
12 **adopting findings under the California Environmental Quality Act; adopting findings**
13 **that the vacations are consistent with the Parkmerced Development Agreement, the**
14 **General Plan, and the eight priority policies of Planning Code, Section 101.1; directing**
15 **the Clerk of the Board of Supervisors to make certain transmittals; and authorizing**
16 **actions by City officials in furtherance of this Ordinance, as defined herein.**

17 **NOTE:** **Unchanged Code text and uncodified text** are in plain Arial font.
18 **Additions to Codes** are in *single-underline italics Times New Roman font*.
19 **Deletions to Codes** are in *strikethrough italics Times New Roman font*.
20 **Board amendment additions** are in double-underlined Arial font.
21 **Board amendment deletions** are in ~~strikethrough Arial font~~.
22 **Asterisks (* * * *)** indicate the omission of unchanged Code
23 subsections or parts of tables.

24 Be it ordained by the People of the City and County of San Francisco:

25 Section 1. Findings.

1 (a) On February 10, 2011, at a duly noticed public hearing, the Planning Commission
2 certified the Final Environmental Impact Report ("Final EIR") for the Parkmerced Mixed-Use
3 Development Project (the "Project"), by Motion No. 18269, finding that the Final EIR reflects
4 the independent judgment and analysis of the City and County of San Francisco, is adequate,
5 accurate and objective, contains no significant revisions to the Draft EIR, and the content of
6 the FEIR and the procedures through which the Final EIR was prepared, publicized and
7 reviewed comply with the provisions of the California Environmental Quality Act (California
8 Public Resources Code Sections 21000 et seq., "CEQA"), the State CEQA Guidelines
9 (California Code of Regulations Title 14 Sections 15000 et seq.), and Chapter 31 of the San
10 Francisco Administrative Code ("Chapter 31").

11 (b) At the same hearing at which the Planning Commission certified the Final EIR, the
12 Planning Commission by Motion No. 18270 adopted findings, as required by CEQA, regarding
13 the alternatives, mitigation measures, and significant environmental effects analyzed in the
14 Final EIR, a statement of overriding considerations for approval of the Project, and a proposed
15 mitigation monitoring and reporting program (collectively, "CEQA Findings").

16 (c) On May 24, 2011, at a duly noticed public hearing, the Board of Supervisors
17 reviewed and considered the Final EIR on appeal. By Motion No. M11-83, the Board of
18 Supervisors upheld the Planning Commission's certification of the Final EIR and found the
19 Final EIR to be complete, adequate and objective and reflecting the independent judgment of
20 the City and in compliance with CEQA and the State CEQA Guidelines.

21 (d) On June 7, 2011, at a duly noticed public hearing, the Board of Supervisors
22 considered the Project's approvals, which included amendments to the City's General Plan
23 (approved by Ordinance No. 92-11), Zoning Map (approved by Ordinance No. 91-11), and
24 Planning Code (approved by Ordinance No. 90-11), as well as approval of a Development
5 Agreement, approved on June 7, 2011 by Ordinance No. 89-11 (the "Development

1 Agreement”) (collectively, the “Project Approvals”). Ordinance No. 89-11 is on file with the
2 Clerk of the Board in File No. 110300 and is incorporated herein by reference.

3 (e) In approving the Project, including in its approval of the Development Agreement
4 by Ordinance No. 89-11, the Board of Supervisors adopted the Planning Commission's CEQA
5 Findings as its own and incorporated them by reference. In so doing, the Board of Supervisors
6 approved and endorsed the Mitigation Monitoring and Reporting Program (“MMRP”) for
7 implementation by other City departments and recommended for adoption those mitigation
8 measures that are enforceable by agencies other than City departments. A copy of the CEQA
9 Findings and the Mitigation Monitoring and Reporting Program is on file with the Clerk of the
10 Board in File No. 110300 and is incorporated herein by reference.

11 (f) Section 6.1.1 of the Development Agreement requires that the City vacate portions
12 of streets along with public service easements at the locations generally shown in Exhibit J of
13 the Development Agreement, as and when needed in connection with the development of an
14 approved Development Phase for the Project. The Planning Director approved Development
15 Phase 1 of the Project on June 3, 2015. Development Phase 1 is comprised of four
16 Subphases (1A, 1B, 1C, and 1D).

17 (g) On February 20, 2015, Parkmerced Owner, LLC (together, with its successors and
18 assigns, the “Project Sponsor”) submitted three applications for tentative subdivision maps
19 pursuant to the requirements of the California Subdivision Map Act for Subphases 1A and 1B
20 of the Project. On August 21, 2015, Public Works (“PW”) pursuant to PW Order No. 183946
21 conditionally approved such tentative maps: (1) Tentative Map No. 8530 requested approval
22 to subdivide Assessor's Blocks 7326, 7330, 7331, 7364, 7365, 7366 and 7370 (Parkmerced
23 Planning Blocks 20, 21S, and 22); (2) Tentative Map No. 8531 requested approval to
24 subdivide Assessor's Block 7335 (Parkmerced Planning Block 6); and (3) Tentative Map No.
25 8532 requested approval to subdivide Assessor's Block 7308 (Parkmerced Planning Block 1)

1 (collectively, the "Subphase 1A and 1B Tentative Maps"). The Project Sponsor is currently
2 processing with PW the approval of a final subdivision map for each of the Subphase 1A and
3 1B Tentative Maps (each, a "Final Map").

4 (h) Subphases 1A and 1B of the Project involve the conditional vacation of portions of
5 the following streets within Parkmerced along with public service easements in the streets to
6 be vacated: Vidal Drive, Galindo Avenue, Chumasero Drive, Acevedo Avenue, Serrano Drive,
7 Gonzalez Drive, Cambon Drive, and Font Boulevard. Together, the streets and public service
8 easements described in this Section 1(h) are the "Street Vacation Area." The Street Vacation
9 Area is shown in PW's SUR Map No. 2015-006, sheets 1 through 10. Copies of such maps
10 are on file with the Clerk of the Board in File No. 160851 and are incorporated herein by
11 reference.

12 (i) On August 2, 2016, the Board of Supervisors adopted Resolution No. 360-16 (the
13 "Resolution of Intention"), a copy of which is on file with the Clerk of the Board of Supervisors
14 in File No. 160870, declaring the intention of the Board to conditionally vacate the Street
15 Vacation Area.

16 (j) The Clerk of the Board of Supervisors published the Resolution of Intent in the
17 manner required by law, and the Director of PW posted the Resolution of Intent in the manner
18 required by law.

19 (k) When the Board of Supervisors held a duly noticed public hearing on this street
20 vacation order on September 6, 2016, the Board received public comment regarding the
21 vacation of the Street Vacation Area.

22 (l) The vacation of the Street Vacation Area is necessary to implement the Project, to
23 fulfill the objectives and requirements of the Development Agreement, and to fulfill the
24 objectives of the Parkmerced Special Use District (Planning Code Section 249.64). The
proposed vacations and other actions contemplated herein implement the Project vested by

1 the Project Approvals, including the construction of buildings and streets consistent with the
2 Parkmerced Design Standards and Guidelines, the Parkmerced Transportation Plan, and the
3 Parkmerced Infrastructure Report, all of which are incorporated by reference into the
4 Development Agreement.

5 (m) The City proposes to quitclaim its interest in the Street Vacation Area to the
6 Project Sponsor, consistent with Development Agreement Section 6.1.1.

7 (n) Because many of these streets and easements will remain in use until specified
8 times, no portion of the Street Vacation Area shall be vacated until certain conditions are
9 satisfied, as follows:

10 (1) The Project Sponsor shall provide an irrevocable offer of dedication to the
11 City in form substantially similar to that provided in Exhibit L of the Development Agreement
12 for all lands needed for construction of proposed improvements shown on the Street
13 Improvement Permit for Subphases 1A and 1B of the Project. Subdivider shall make such
14 irrevocable offers of dedication prior to City approval of the Final Subdivision Maps or
15 issuance of a Street Improvement Permit for Subphases 1A or 1B of the Project, whichever is
16 earlier. The offer of dedication shall be subject to the reservation of an easement in favor of
17 Project Sponsor for all domestic water utilities within the dedicated area, which easement
18 shall be extinguished upon completion of all Development Phases of the Project and formal
19 acceptance of the domestic water utilities by the City pursuant to the Development
20 Agreement. The sum total of the square footage of the land proposed for dedication to the
21 City shall be equal to or exceed the square footage of the Street Vacation Area.

22 (2) The Project Sponsor shall provide PW with an acceptable Public
23 Improvement Agreement ("PIA") pursuant to Section 1351 of the San Francisco Subdivision
24 Code and the Subdivision Map Act for all improvements within the Final Map or required for
25 development of the area shown in the Final Map prior to approval of a Final Map or issuance

1 of a Street Improvement Permit for Subphases 1A or 1B of the Project, whichever is earlier.
2 Such PIA shall address security provisions and provide interim easements or licenses via
3 separate offer, such that the City can complete the improvements if the Subdivider fails to do
4 so.

5 (o) In a letter dated July 5, 2016 (the "DRE Letter"), the Director of the Department of
6 Real Estate determined that: the Development Agreement contemplates the vacation of the
7 Street Vacation Area; Exhibit J of the Development Agreement shows the general locations of
8 the property vacations and dedications required by the Project; Section 6.1.2 of the
9 Development Agreement requires that (1) all real property exchanged under the Development
10 Agreement be valued on a square foot basis and shall be deemed equal in value per square
11 foot, (2) if any real property exchange under the Development Agreement results in a net loss
12 of acreage for the City, then the Project Sponsor must pay to the City the fair market value of
13 the real property loss at the time of transfer based on the then-current use of the property so
14 transferred, and (3) the City shall not be required to pay for any net gain in real property;
15 provided, however, such gain can be applied against future real property transfers for
16 purposes of determining whether there has been a net loss as described above. The Director
17 of Real Estate also determined in the DRE Letter that: the proposed vacations and
18 dedications associated with Subdivision Maps 8350, 8351, and 8352 result in a net gain in
19 real property owned by the City; therefore, no payment is owed by the Project for the vacation
20 of the Street Vacation Area; and this net gain should be credited against future public right of
21 way vacations for the Project. A copy of said letter is on file with the Clerk of the Board in File
22 No. 160851.

23 (p) The Board of Supervisors finds that the actions proposed herein are consistent with
24 and within the scope of the Project analyzed in the Final EIR and subject to the CEQA
5 Findings. The Board of Supervisors further finds that no substantial changes are proposed in

1 the Project and no substantial changes have occurred with respect to the circumstances
2 under which this Project will be undertaken that would cause new significant environmental
3 effects or a substantial increase in the severity of previously identified effects, and there is no
4 new information of substantial importance showing that the Project would have any significant
5 effects not discussed in the Project environmental impact report, that significant effects would
6 be substantially more severe, or that new or different mitigation measures or alternatives
7 would substantially reduce one or more significant effects of the Project. The Board affirms
8 the Planning Department's determination that an addendum to the Final EIR is not required
9 due to any changes in the Project or the Project's circumstances.

10 (q) In a letter dated August 3, 2015 (the "Planning Letter"), the Planning Department
11 determined that the proposed vacations and other actions contemplated herein are on
12 balance consistent with the General Plan and with the Eight Priority Policies of City Planning
13 Code Section 101.1, comply with applicable provisions of the Planning Code, and are
14 consistent with the Project as defined in the Development Agreement and the Project
15 Approvals. A copy of said letter is on file with the Clerk of the Board in File No. 160851 and is
16 incorporated herein by reference. The Board of Supervisors adopts as its own the consistency
17 findings of the Planning Letter.

18 (r) These street and public easement vacation actions are conducted under the general
19 vacation procedures of the California Public Streets, Highways and Service Easements
20 Vacation Law (California Streets and Highways Code Sections 8300 et seq.) and San
21 Francisco Public Works Code Section 787(a).

22 (s) The Director of PW has prepared PW Order No. 18513, dated July 22, 2016, in
23 regard to the vacations and other actions contemplated herein and makes the following
24 determinations: (1) upon satisfaction of the applicable condition or conditions provided in
25 Section 1(n), the respective Street Vacation Area will no longer be necessary for the City's

1 present or prospective future public street, sidewalk, and public service easement purposes
2 as all existing physical public or private utilities located in the Street Vacation Area will be
3 relocated to the satisfaction of the City as part of the construction of the Project; (2) with the
4 exception of those public easements noted in Sections 3(a) and (b) below, the public interest,
5 convenience, and necessity do not require any easements or other rights be reserved for any
6 public or private utility facilities that are in place in the Street Vacation Area and that any rights
7 based upon any such public or private utility facilities shall be extinguished automatically upon
8 the effectiveness of the vacation; (3) in accordance with California Streets and Highways
9 Code Section 892, for those portions of the Street Vacation Area to be conditionally vacated
10 identified in Section 1(n) above, upon satisfaction of the applicable condition or conditions, the
11 rights-of-way and parts thereof proposed within the respective Street Vacation Areas will no
12 longer be useful as a nonmotorized transportation facility, as defined in Section 887, because
13 the Development Agreement requires the dedication and construction of an extensive street,
14 bicycle path, pedestrian path, park, and trail system that is more extensive than the areas
15 being vacated hereby and that is designed to integrate with existing built streets in the
16 adjacent neighborhoods; and (4) it is a policy matter for the Board of Supervisors to quitclaim
17 the City's interest in the Street Vacation Area to the Buyer, subject to the requirements of the
18 Development Agreement. A copy of the PW Order is on file with the Clerk of the Board of
19 Supervisors in File No. 160851 and is incorporated herein by reference.

20 (t) In addition, in the PW Order the PW Director recommended: (1) that the Board of
21 Supervisors adopt the legislation to vacate the Street Vacation Area; (2) that the Board of
22 Supervisors approve all actions set forth herein and previously taken by the Officers of the
23 City with respect to this vacation; (3) although the consent of all property owners adjacent to
24 the Street Vacation Area was not obtained, the applicant made reasonable attempts to notify
5 and obtain consent from all property owners adjacent to the Street Vacation Area and the

1 proposed street vacations do not deprive any private landowner of access to the built public
2 street grid; and (4) that the Board of Supervisors authorize the Mayor, Clerk of the Board,
3 Director of Property, County Surveyor, and Director of PW to take any and all actions which
4 they or the City Attorney may deem necessary or advisable to effectuate the purpose and
5 intent of this ordinance.

6 (u) In addition, in the PW Order the PW Director determined that the public interest,
7 convenience, and necessity require that the City reserve from the vacation of the Street
8 Vacation Area non-exclusive easements for the benefit of the City (and subject to possible
9 grants by the City of temporary, immediately revocable licenses by the City in favor of AT&T,
10 PG&E, and any other utilities) for any utilities, telecommunications facilities, or power and gas
11 transmission facilities, respectively, located in, upon, and over any portion of the Street
12 Vacation Area in which their respective in-place and functioning utilities are located as of the
13 effective date of this ordinance, to the extent necessary to maintain, operate, repair, and
14 remove existing lines of pipe, conduits, cables, wires, poles, and other convenient structures,
15 equipment and fixtures for the operation by City of City utilities, by AT&T of
16 telecommunications facilities, by PG&E of power and gas transmission facilities, or for other
17 public utilities. This reservation, and any subsequent grant of easements or licenses is subject
18 to the City's authority to require AT&T, PG&E, and any other utilities to remove or relocate
19 their facilities at no expense to the City when necessary to accommodate a project done
20 under the governmental authority of the City. This reservation and the automatic
21 extinguishment of the reservation to occur upon satisfaction of certain conditions are
22 described in Section 3 below.

23 (v) Furthermore, in the PW Order the PW Director determined that the public interest,
24 convenience, and necessity require that the City reserve from the vacation of the Street
25 Vacation Area temporary access for the benefit of the public over any portion of the Street

1 Vacation Area where required to preserve access between a private property and the existing
2 street grid as of the effective date of this ordinance. This reservation and the automatic
3 extinguishment of the reservation shall occur upon satisfaction of certain conditions that are
4 described Section 3 in below. The Board adopts the findings of the PW Director as its own.
5

6 Section 2. Street Vacation and Conditions.

7 (a) Except as set forth in Sections 3 and 4 below, the Board of Supervisors hereby
8 vacates the Street Vacation Area, as shown on PW SUR Map No. 2015-006, sheets 1 through
9 10 (to the extent referring to streets and public service easements to be conditionally
10 vacated), in the manner described in Section (1)(m), upon satisfaction of the conditions
11 described in this ordinance and pursuant to California Streets and Highways Code Sections
8300 et seq. and San Francisco Public Works Code Section 787(a).

13 (b) The Board of Supervisors hereby finds that the Street Vacation Area is
14 unnecessary for present or prospective public use, subject to the conditions described in this
15 ordinance.

16 (c) The Board finds that the public interest, convenience, and necessity require that
17 the Street Vacation be done as declared in this ordinance.

18 (d) The Street Vacation shall be effective as to all of the Street Vacation Area upon
19 satisfaction of the conditions in Sections 3 and 4 and recording of the City's quitclaim deed in
20 substantially the same form as the draft quitclaim deed on file with the Clerk of the Board of
21 Supervisors in File No. 160851.
22

23 Section 3. Conditions to the Street Vacation; Reservation and Easements.

24 (a) The vacation of the Street Vacation Area is subject to the reservation of non-
5 exclusive easements on the terms and conditions described in Section 1(n) above for the

1 benefit of the City (and subject to possible grants by the City of temporary, ~~immediately~~
2 ~~revocable licenses~~ easements by the City in favor of AT&T, PG&E, and any other utilities) for
3 any City utilities, telecommunications facilities, power and gas transmission utilities, or other
4 public facilities that are located in, upon, or over any portion of the Street Vacation Area in
5 which their respective in-place and functioning utilities are located, to the extent necessary to
6 maintain, operate, repair, and remove existing lines of pipe, conduits, cables, wires, poles,
7 and other convenient structures, equipment and fixtures for the operation of such utilities and
8 also the rights to trim and cut down trees and brush that may be a hazard to the utilities. To
9 the extent the non-exclusive easements described in this Section 3(a) have not previously
10 merged into a fee interest held by the City, such non-exclusive easements reserved in this
11 Section 3(a) shall be automatically extinguished when such alternative replacement facilities
12 are completed to the satisfaction of the City Engineer and the Board of Supervisors accepts
13 the facilities. The City shall execute a quitclaim of any interest in any easement reserved
14 under this Section 3(a) and shall cause such quitclaim to be recorded against the subject
15 property upon the fee title owner demonstrating to the City that replacement utilities serving
16 the affected area have been substantially completed and operable. In the event a non-
17 exclusive easement described in this Section 3(a) has merged into the fee interest held by the
18 City, such interest shall be deemed to be automatically extinguished and conveyed at the time
19 the fee interest is conveyed by the City to the Project Sponsor or any other transferee
20 pursuant to the Development Agreement.

21 (b) The vacation of the Street Vacation Area is subject to the reservation of temporary
22 access for the benefit of the public over any portion of the Street Vacation Area where
23 required to preserve access between a private property and the existing street grid as of the
24 effective date of this ordinance. To the extent the access rights described in this Section 3(b)
25 have not previously merged into a fee interest held by the City, such access reserved in this

1 Section 3(b) shall be automatically extinguished when replacement access serving the
2 affected area has been substantially completed and is open to the public as certified by PW.
3 In the event a non-exclusive easement described in this Section 3(b) has merged into the fee
4 interest held by the City, such interest shall be deemed to be automatically extinguished and
5 conveyed at the time the fee interest is conveyed by the City to the Project Sponsor or any
6 other transferee pursuant to the Development Agreement.

7 (c) The PIA shall provide that, prior the issuance of the First Certificate of Occupancy
8 for the first building constructed as part of Development Phase 1 of the Project, the Project
9 Sponsor shall perform those actions as reasonably required by the City (which, for purposes
10 of clarity, may include execution of a quitclaim deed or performance of a quiet title action) to
11 clarify that the City owns fee title to the public streets in the Parkmerced Development Project
area in existence as of the effective date of this ordinance.

13 (d) Where a future Development Phase of the Project (Development Phase 2 and
14 onward) anticipates a future dedication of right of way adjacent to a street shown on a
15 tentative map as being partially improved, PW shall require Project Sponsor, prior to submittal
16 of a Final Map mylar, but after acceptance and recordation of the quitclaim deeds for the
17 Street Vacation Area contemplated by this ordinance, to record a Notice of Restrictions on
18 those strips of land anticipated to be needed for the ultimate street construction as agreed
19 upon in the Development Agreement, subject to the review and approval of the City Attorney.

20 (e) Except as specifically provided in this ordinance above and subject to the
21 conditions set forth in Section 3 and Section 4 of this ordinance, no easements or other rights
22 are reserved for any public utility facilities that are in place in the Street Vacation Area and
23 any rights based upon any such public utility facilities shall be extinguished upon the
24 effectiveness of the vacation hereunder.

1 Section 4. Execution of Quitclaim Deeds and Delegation to Director of Real Estate.

2 (a) The Board of Supervisors hereby authorizes the Director of Real Estate to execute
3 City quitclaim deeds to the Project Sponsor for those portions of the Street Vacation Area to
4 be conditionally vacated (as described in Section (1)(n)) upon satisfaction of the applicable
5 conditions set forth in that section.

6 (b) The quitclaim deeds executed pursuant to this Section 4 shall include the
7 reservations of: (1) the non-exclusive easements to AT&T for telecommunications purposes,
8 to PG&E for power and gas transmission purposes, and to the City for City utilities described
9 in Section 3; and (2) the temporary access to the extent necessary as described in Section 3.
10 The Board hereby delegates to the Director of Real Estate, in cooperation with the County
11 Surveyor, the authority to determine precise locations of the boundaries of quitclaims to be
12 prepared and recorded pursuant to this ordinance so as to fully implement the intent of this
13 ordinance and to fully implement the Project.

14
15 Section 5. The Board of Supervisors hereby directs the Clerk of the Board of
16 Supervisors to transmit to the Director of PW certified copies of this ordinance, and the Board
17 of Supervisors hereby urges the Director of PW to proceed in the manner required by law.
18 The Clerk of the Board also is hereby directed to transmit to the Director of PW certified
19 copies of this ordinance so that this ordinance may be recorded together with any other
20 documents necessary to effectuate this ordinance.

21
22 Section 6. The Mayor, Clerk of the Board, Director of Property, and Director of PW are
23 hereby authorized and directed to take any and all actions which they or the City Attorney may
24 deem necessary or advisable in order to effectuate the purpose and intent of this ordinance
25

1 (including, without limitation, the filing of the ordinance in the Official Records of the City and
2 County of San Francisco, determination of the precise locations of the boundaries of
3 quitclaims to be prepared and recorded pursuant to this ordinance, confirmation of satisfaction
4 of any of the conditions to the effectiveness of the vacation of any portion of the Street
5 Vacation Area hereunder, and confirmation of the reservation of easements and of temporary
6 access pursuant to Sections 3(a) and (b) of this ordinance and execution and delivery of any
7 evidence of same, which shall be conclusive as to the satisfaction of such conditions upon
8 signature by any such City official or his or her designee).

9
10 Section 7. Effective Date. This ordinance shall become effective 30 days after
11 enactment. Enactment occurs when the Mayor signs the ordinance, the Mayor returns the
12 ordinance unsigned or does not sign the ordinance within ten days of receiving it, or the Board
13 of Supervisors overrides the Mayor's veto of the ordinance.

14
15 APPROVED AS TO FORM:
16 DENNIS J. HERRERA, City Attorney

17 By: 
18 MARLENA BYRNE
19 Deputy City Attorney

20 n:\land\as2016\1500790\01121539.docx

REVISED LEGISLATIVE DIGEST

(9/13/2016, Amended in Board)

[Street Vacation Order - Parkmerced Development Project]

Ordinance ordering the conditional vacation of portions of streets (along with public service easements within those streets) that exist within the Subphases 1A and 1B of the Parkmerced Development Project area, an approximately 152 acre site located in the Lake Merced District in the southwest corner of San Francisco and generally bounded by Vidal Drive, Font Boulevard, Pinto Avenue, and Serrano Drive to the north, 19th Avenue and Junipero Serra Boulevard to the east, Brotherhood Way to the south, and Lake Merced Boulevard to the west; reserving various easement rights in favor of the City and third party utilities, subject to conditions specified in this ordinance; delegating authority to the Director of Real Estate to execute certain quit claim deeds; adopting findings under the California Environmental Quality Act; adopting findings that the vacations are consistent with the Parkmerced Development Agreement, the General Plan, and the eight priority policies of Planning Code, Section 101.1; directing the Clerk of the Board of Supervisors to make certain transmittals; and authorizing actions by City officials in furtherance of this Ordinance, as defined herein.

Existing Law

The Parkmerced Development Project ("Project") is a large, multi-phased project to redevelop an approximately 152-acre site located in the Lake Merced District in the southwest corner of San Francisco, generally bounded by Vidal Drive, Font Boulevard, Pinto Avenue, and Serrano Drive to the north, 19th Avenue and Junipero Serra Boulevard to the east, Brotherhood Way to the south, and Lake Merced Boulevard to the west. Among other things, the Project involves the realignment of various streets and public rights-of-way.

Amendments to Current Law

The proposed ordinance would conditionally vacate portions of certain streets for the first two subphases of the Project. Specifically, Subphases 1A and 1B of the Project involve the conditional vacation of portions of the following streets within Parkmerced along with the vacation of public service easements in those streets: Vidal Drive, Galindo Avenue, Chumasero Drive, Acevedo Avenue, Serrano Drive, Gonzalez Drive, Cambon Drive, and Font Boulevard.

The proposed vacations implement the Project, which was approved by the Board of Supervisors in 2011, by, among other approvals, approval of a Development Agreement for the Project by Ordinance No. 89-11. For the street vacation to become final, the Project Sponsor must dedicate certain other land to the City to be used for streets and rights-of-way and must enter into a Public Improvement Agreement with the City for all the improvements required by the Final Map for these phases of the Project.

n:\land\as2016\1500790\01123623.docx

RECORDING REQUESTED BY
CLERK OF THE BOARD OF SUPERVISORS
OF THE CITY AND COUNTY OF SAN FRANCISCO

(Exempt from Recording Fees
Pursuant to Government Code
Section 27383)

AND WHEN RECORDED MAIL TO:

Angela Calvillo
Clerk of the Board of Supervisors
City Hall, Room 244
1 Dr. Carlton B. Goodlett Place
San Francisco, CA 94102

APN: Blocks 7308, 7303-A, and 7308

SPACE ABOVE THIS LINE FOR RECORDER'S USE

QUITCLAIM DEED

THE UNDERSIGNED GRANTOR DECLARES:

DOCUMENTARY TRANSFER TAX is \$ 0

- computed on full value of property conveyed, or
 computed on full value less value of liens or encumbrances remaining at time of sale.

- unincorporated area
 city and county of SAN FRANCISCO

FOR A VALUABLE CONSIDERATION, receipt of which is hereby acknowledged,
CITY AND COUNTY OF SAN FRANCISCO, a municipal corporation, acting by and through
its Department of Real Estate ("Grantor"),

does hereby REMISE, RELEASE and forever QUITCLAIM to

PARKMERCED OWNER LLC, a Delaware limited liability company,

the following described real property in the City and County of San Francisco, State of California:

See Exhibit "A" attached hereto and made a part hereof.

[SIGNATURE PAGE FOLLOWS]

Executed as of _____, 2016.

CITY
CITY AND COUNTY OF
SAN FRANCISCO,
a municipal corporation

Approved as to form
_____, City Attorney

By: _____

By: _____
Deputy City Attorney

Director of Real Estate

Approved on _____
Board of Supervisors Ordinance No. _____

State of California)
County of San Francisco)

On _____, before me, _____, a Notary Public, personally appeared _____, who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature

(Affix Seal)



ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

LEGAL DESCRIPTION
EXHIBIT A
VACATION PARCEL 1

All that certain real property situated in the City and County of San Francisco, State of California, being a portion of Vidal Drive as shown on that certain map entitled "RECORD OF SURVEY MAP NO. 8641" filed August 24, 2015, as Document Number 2015K114105, in the Office of the Recorder of the City and County of San Francisco, State of California, and being more particularly described as follows:

BEGINNING at the easterly terminus of the course labeled "S87°34'02"E 296.060 feet" on the northerly line of Block 7308 as said course and said block are shown on said map (see sheet 6 of 20), said point being the **TRUE POINT OF BEGINNING** of this description;

Thence along the northerly and westerly lines of said block the following four courses:

- 1) North 87°34'02" West, 296.060 feet to the beginning of a tangent curve to the left;
- 2) Southwesterly along said curve having a radius of 132.000 feet, through a central angle of 92°35'59", for an arc length of 213.334 feet;
- 3) South 00°10'01" East, 305.900 feet to the beginning of a tangent curve to the left;
- 4) Southeasterly along said curve having a radius of 10.000 feet, through a central angle of 44°41'19", for an arc length of 7.800 feet;

Thence leaving said westerly line of said Block 7308, North 87°34'02" West, 11.958 feet;

Thence North 00°10'01" West, 398.335 feet to the beginning of a tangent curve to the right;

Thence along said curve having a radius of 55.000 feet, through a central angle of 10°55'58", for an arc length of 10.495 feet to the southeasterly line of Block 7303-A as shown on said map and the beginning of a non-tangent curve to the right whose radius point bears South 53°44'05" East;

Thence along said southeasterly line of said Block 7303-A and along said curve having a radius of 166.000 feet, through a central angle of 23°00'15", for an arc length of 66.649 to the beginning of a non-tangent curve to the right whose radius point bears South 05°13'52" East;

Thence leaving said southeasterly line of said Block 7303-A and along said curve having a radius of 55.000 feet, through a central angle of 07°39'50", for an arc length of 7.357 feet;



ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

Thence South $87^{\circ}34'02''$ East, 400.836 feet;

Thence South $02^{\circ}25'58''$ West, 10.777 feet to the northeasterly line of said Block 7308 and the beginning of a non-tangent curve to the left whose radius point bears South $45^{\circ}06'14''$ West;

Thence along said curve having a radius of 22.000 feet, through a central angle of $42^{\circ}40'16''$, for an arc length of 16.385 feet to the **TRUE POINT OF BEGINNING**;


Containing an area of 9,466 square feet, more or less.


Horizontal Datum & Reference System

The horizontal datum is the North American Datum of 1983: NAD 83 (2011) Epoch 2010.00 referenced by the "CCSF-2013 High Precision Network" (CCSF-HPN). Plane coordinates are based on the "City & County of San Francisco 2013 coordinate system (CCSF-CS13). CCSF-CS13 is a low distortion projection designed for CCSF to provide plane coordinates in a ground system. See ROS 8080, filed April 4, 2014, in Book EE of Survey Maps at pages 147-157 in the Office of the Recorder of the City and County of San Francisco.

A plat showing the above-described parcel is attached herein and made a part hereof.


This description was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act.


Alex M. Calder, LLS 8863






10-19-2015
Dated

END OF DESCRIPTION



Jeff Coll
10-19-2015



255 SHORELINE DR
SUITE 200
REDWOOD CITY, CA 94065
650-482-6300
650-482-6399 (FAX)

Subject EXHIBIT A
 PLAT TO ACCOMPANY DESCRIPTION
 Job No. 20090086-51
 By DCJ Date 10/19/15 Chkd. AMC
 SHEET 3 OF 3

RECORDING REQUESTED BY
CLERK OF THE BOARD OF SUPERVISORS
OF THE CITY AND COUNTY OF SAN FRANCISCO

(Exempt from Recording Fees
Pursuant to Government Code
Section 27383)

AND WHEN RECORDED MAIL TO:

Angela Calvillo
Clerk of the Board of Supervisors
City Hall, Room 244
1 Dr. Carlton B. Goodlett Place
San Francisco, CA 94102

APN: Block 7308

SPACE ABOVE THIS LINE FOR RECORDER'S USE

QUITCLAIM DEED

THE UNDERSIGNED GRANTOR DECLARES:

DOCUMENTARY TRANSFER TAX is \$ 0

computed on full value of property conveyed, or

computed on full value less value of liens or encumbrances remaining at time of sale.

unincorporated area

city and county of SAN FRANCISCO

FOR A VALUABLE CONSIDERATION, receipt of which is hereby acknowledged,
CITY AND COUNTY OF SAN FRANCISCO, a municipal corporation, acting by and through
its Department of Real Estate ("Grantor"),

does hereby REMISE, RELEASE and forever QUITCLAIM to

PARKMERCED OWNER LLC, a Delaware limited liability company,

the following described real property in the City and County of San Francisco, State of California:

See Exhibit "A" attached hereto and made a part hereof.

[SIGNATURE PAGE FOLLOWS]

Executed as of _____, 2016.

CITY
CITY AND COUNTY OF
SAN FRANCISCO,
a municipal corporation

Approved as to form
_____, City Attorney

By: _____

By: _____
Deputy City Attorney

Director of Real Estate

Approved on _____
Board of Supervisors Ordinance No. _____

State of California)
County of San Francisco)

On _____, before me, _____, a Notary
Public, personally appeared _____, who proved to me on the
basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within
instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized
capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity
upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the
foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature

(Affix Seal)



ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

LEGAL DESCRIPTION
EXHIBIT A
VACATION PARCEL 2

All that certain real property situated in the City and County of San Francisco, State of California, being a portion of Acevedo Avenue as shown on that certain map entitled "RECORD OF SURVEY MAP NO. 8641" filed August 24, 2015, as Document Number 2015K114105, in the Office of the Recorder of the City and County of San Francisco, State of California, and being more particularly described as follows:

BEGINNING at the easterly terminus of the course labeled "S87°34'02"E 404.059 feet" on the southerly line of Block 7308 as said course and said block are shown on said map (see sheet 5 of 20); thence along the southeasterly line of said block along a tangent curve to the left having a radius of 22.000 feet, through a central angle of 28°25'29", for an arc length of 10.914 feet to the **TRUE POINT OF BEGINNING** of this description;

Thence continuing on along last said curve, through a central angle of 14°14'47", for an arc length of 5.470 feet;

Thence leaving said southeasterly line of said Block 7308 the following two courses:

- 1) South 02°25'58" West, 3.172 feet;
- 2) North 87°34'02" West, 4.439 feet to the **TRUE POINT OF BEGINNING**.

Containing an area of 6 square feet, more or less.


Horizontal Datum & Reference System

The horizontal datum is the North American Datum of 1983: NAD 83 (2011) Epoch 2010.00 referenced by the "CCSF-2013 High Precision Network" (CCSF-HPN). Plane coordinates are based on the "City & County of San Francisco 2013 coordinate system (CCSF-CS13). CCSF-CS13 is a low distortion projection designed for CCSF to provide plane coordinates in a ground system. See ROS 8080, filed April 4, 2014, in Book EE of Survey Maps at pages 147-157 in the Office of the Recorder of the City and County of San Francisco.

A plat showing the above-described parcel is attached herein and made a part hereof.

This description was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act.



Alex M. Calder, LLS 8863



10-19-2015
Dated

END OF DESCRIPTION

EXHIBIT A



VACATION PARCEL 2
(PHASE 1A - TENTATIVE MAP 8532)

7308


D=28°25'29"
L=10.914'
R=22.000'
POINT OF
BEGINNING

S87°34'02"E
404.059'

ACEVEDO AVENUE
(51' WIDE)

SEE DETAIL

ARBALLO DRIVE
(51' WIDE)





7310



AREA TO BE VACATED
6 SQ.FT.±

EXISTING BOUNDARY

Alex Calder
10-19-15



7309



255 SHORELINE DR.
SUITE 200
REDWOOD CITY, CA 94065
650-482-6300
650-482-6399 (FAX)

Subject EXHIBIT A
PLAT TO ACCOMPANY DESCRIPTION
Job No. 20090086-51
By DCJ Date 10/19/15 Chkd. AMC
SHEET 2 OF 2

RECORDING REQUESTED BY
CLERK OF THE BOARD OF SUPERVISORS
OF THE CITY AND COUNTY OF SAN FRANCISCO

(Exempt from Recording Fees
Pursuant to Government Code
Section 27383)

AND WHEN RECORDED MAIL TO:

Angela Calvillo
Clerk of the Board of Supervisors
City Hall, Room 244
1 Dr. Carlton B. Goodlett Place
San Francisco, CA 94102

APN: Block 7335

SPACE ABOVE THIS LINE FOR RECORDER'S USE

QUITCLAIM DEED

THE UNDERSIGNED GRANTOR DECLARES:

DOCUMENTARY TRANSFER TAX is \$ 0

- computed on full value of property conveyed, or
 computed on full value less value of liens or encumbrances remaining at time of sale.

- unincorporated area
 city and county of SAN FRANCISCO

FOR A VALUABLE CONSIDERATION, receipt of which is hereby acknowledged,
CITY AND COUNTY OF SAN FRANCISCO, a municipal corporation, acting by and through
its Department of Real Estate ("Grantor"),

does hereby REMISE, RELEASE and forever QUITCLAIM to

PARKMERCED OWNER LLC, a Delaware limited liability company,

the following described real property in the City and County of San Francisco, State of California:

See Exhibit "A" attached hereto and made a part hereof.

[SIGNATURE PAGE FOLLOWS]

Executed as of _____, 2016.

CITY
CITY AND COUNTY OF
SAN FRANCISCO,
a municipal corporation

Approved as to form
_____, City Attorney

By: _____

By: _____
Deputy City Attorney

Director of Real Estate

Approved on _____
Board of Supervisors Ordinance No. _____

State of California)
County of San Francisco)

On _____, before me, _____, a Notary
Public, personally appeared _____, who proved to me on the
basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within
instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized
capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity
upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the
foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature

(Affix Seal)



ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

LEGAL DESCRIPTION
EXHIBIT A
VACATION PARCEL 3

All that certain real property situated in the City and County of San Francisco, State of California, being a portion of Serrano Drive as shown on that certain map entitled "RECORD OF SURVEY MAP NO. 8641" filed August 24, 2015, as Document Number 2015K114105, in the Office of the Recorder of the City and County of San Francisco, State of California, and being more particularly described as follows:

BEGINNING at the northerly terminus of the course labeled "N2°25'58"E 119.626 feet" on the westerly line of Block 7335 as said course and said block are shown on said map (see sheet 4 of 20); thence along said westerly line of said Block 7335 along a curve to the right having a radius of 22,000 feet, through a central angle of 53°29'30", for an arc length of 20.539 feet to the **TRUE POINT OF BEGINNING** of this description;

Thence continuing on along the northerly lines of said Block 7335 the following two courses:

- 1) Along last said curve with said radius, through a central angle of 36°30'30", for an arc length of 14.018 feet;
- 2) South 87°34'02" East, 387.924 feet;

Thence leaving said northerly line of Block 7335 the following three courses:

- 1) North 02°25'52" East, 0.833 feet;
- 2) North 87°34'02" West, 401.012 feet;
- 3) South 02°25'58" West, 5.150 feet to the **TRUE POINT OF BEGINNING**.

Containing an area of 352 square feet, more or less.

Horizontal Datum & Reference System

The horizontal datum is the North American Datum of 1983: NAD 83 (2011) Epoch 2010.00 referenced by the "CCSF-2013 High Precision Network" (CCSF-HPN). Plane coordinates are based on the "City & County of San Francisco 2013 coordinate system (CCSF-CS13). CCSF-CS13 is a low distortion projection designed for CCSF to provide plane coordinates in a ground system. See ROS 8080, filed April 4, 2014, in Book EE of Survey Maps at pages 147-157 in the Office of the Recorder of the City and County of San Francisco.




BKF

ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

A plat showing the above-described parcel is attached herein and made a part hereof.

This description was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act.



Alex Calder
Alex M. Calder, LLS 8863

10-19-2015
Dated.

END OF DESCRIPTION

EXHIBIT A

7310

SERRANO DRIVE
(67' WIDE)

TAPIA DRIVE
(51' WIDE)

VACATION PARCEL 3

(PHASE 1A - TENTATIVE MAP 8531)

S02°25'58"W

N02°25'52"E

5.150'

0.833'

D=36°30'30"
L=14.018'
R=22,000'

N87°34'02"W 401.012'

S87°34'02"E 387.924'


TRUE POINT OF BEGINNING

D=53°29'30"
L=20.539'
R=22,000'

POINT OF BEGINNING

7335

Alex Calder
10-19-2015



ARBALLO DRIVE
(51' WIDE)


N02°25'58"E

119.626'



= AREA TO BE VACATED
352 SQ.FT.±

--- EXISTING BOUNDARY



255 SHORELINE DR.
SUITE 200
REDWOOD CITY, CA 94065
650-482-6300
650-482-6399 (FAX)

Subject EXHIBIT A
PLAT TO ACCOMPANY DESCRIPTION
Job No: 20090086-51
By DCJ Date 10/19/15 Chkd. AMC
SHEET 3 OF 3

RECORDING REQUESTED BY
CLERK OF THE BOARD OF SUPERVISORS
OF THE CITY AND COUNTY OF SAN FRANCISCO

(Exempt from Recording Fees
Pursuant to Government Code
Section 27383)

AND WHEN RECORDED MAIL TO:

Angela Calvillo
Clerk of the Board of Supervisors
City Hall, Room 244
1 Dr. Carlton B. Goodlett Place
San Francisco, CA 94102

APN: Block 7335

SPACE ABOVE THIS LINE FOR RECORDER'S USE

QUITCLAIM DEED

THE UNDERSIGNED GRANTOR DECLARES:

DOCUMENTARY TRANSFER TAX is \$ 0

- computed on full value of property conveyed, or
 computed on full value less value of liens or encumbrances remaining at time of sale.

- unincorporated area
 city and county of SAN FRANCISCO

FOR A VALUABLE CONSIDERATION, receipt of which is hereby acknowledged,
CITY AND COUNTY OF SAN FRANCISCO, a municipal corporation, acting by and through
its Department of Real Estate ("Grantor"),

does hereby REMISE, RELEASE and forever QUITCLAIM to

PARKMERCED OWNER LLC, a Delaware limited liability company,

the following described real property in the City and County of San Francisco, State of California:

See Exhibit "A" attached hereto and made a part hereof.

[SIGNATURE PAGE FOLLOWS]

Executed as of _____, 2016.

CITY
CITY AND COUNTY OF
SAN FRANCISCO,
a municipal corporation

Approved as to form
_____, City Attorney

By: _____

By: _____
Deputy City Attorney

Director of Real Estate

Approved on _____
Board of Supervisors Ordinance No. _____

State of California)
County of San Francisco)

On _____, before me, _____, a Notary Public, personally appeared _____, who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature

(Affix Seal)



ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

**LEGAL DESCRIPTION
EXHIBIT A
VACATION PARCEL 4**

All that certain real property situated in the City and County of San Francisco, State of California, being a portion of Gonzalez Drive as shown on that certain map entitled "RECORD OF SURVEY MAP NO. 8641" filed August 24, 2015, as Document Number 2015K114105, in the Office of the Recorder of the City and County of San Francisco, State of California, and being more particularly described as follows:

BEGINNING at the westerly terminus of the course labeled "N87°33'55"W 659.561 feet" on the southerly line of Block 7335 as said course and block are shown on said map (see sheet 4 of 20), said point being the **TRUE POINT OF BEGINNING** of this description;

Thence westerly along the southerly line of said Block 7335 along a curve to the right having a radius of 22.000 feet, through a central angle of 11°14'03", for an arc length of 4.314 feet;

Thence leaving said southerly line of Block 7335 the following three courses:

- 1) South 02°25'58" West, 9.988 feet;
- 2) South 87°33'55" East, 401.027 feet;
- 3) North 02°25'52" East, 9.567 feet to said southerly line of Block 7335;

Thence along said southerly line of Block 7335, North 87°33'55" West, 396.741 feet to the **TRUE POINT OF BEGINNING**

Containing an area of 3,837 square feet, more or less.

Horizontal Datum & Reference System


The horizontal datum is the North American Datum of 1983: NAD 83 (2011) Epoch 2010.00 referenced by the "CCSF-2013 High Precision Network" (CCSF-HPN). Plane coordinates are based on the "City & County of San Francisco 2013 coordinate system (CCSF-CS13). CCSF-CS13 is a low distortion projection designed for CCSF to provide plane coordinates in a ground system. See ROS 8080, filed April 4, 2014, in Book EE of Survey Maps at pages 147-157 in the Office of the Recorder of the City and County of San Francisco.



October 19, 2015
BKF No. 20090086-51

A plat showing the above-described parcel is attached herein and made a part hereof.

This description was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act.



Alex Calder
Alex M. Calder, LLS 8863

10-19-2015
Dated

END OF DESCRIPTION

EXHIBIT A

7335

ARBALLO DRIVE
(51' WIDE)

D=90°16'20"
L=34.662'
R=22.000'
TOTAL


D=11°14'03"
L=4.314'
R=22.000'

TRUE POINT OF BEGINNING

S02°25'58"W
9.988'

N87°33'55"W 396.741'
S87°33'55"E 401.027'

VACATION PARCEL 4
(PHASE 1A - TENTATIVE MAP 8531)



N02°25'52"E
9.567'

RIVAS AVENUE
(51' WIDE)

GONZALEZ DRIVE
(67' WIDE)


7336

Alex Calder
10-19-2015
LICENSED LAND SURVEYOR
ALEX CALDER
LLS: 8863
STATE OF CALIFORNIA

 = AREA TO BE VACATED
3,837 SQ.FT.±

--- EXISTING BOUNDARY

SHEET LOCATION DETAIL
NOT TO SCALE



255 SHORELINE DR.
SUITE 200
REDWOOD CITY, CA 94065
650-482-6300
650-482-6399 (FAX)

Subject EXHIBIT A
PLAT TO ACCOMPANY DESCRIPTION
Job No. 20090086-51
By DCJ Date 10/19/15 Chkd. AMC
SHEET 3 OF 3

RECORDING REQUESTED BY
CLERK OF THE BOARD OF SUPERVISORS
OF THE CITY AND COUNTY OF SAN FRANCISCO

(Exempt from Recording Fees
Pursuant to Government Code
Section 27383)

AND WHEN RECORDED MAIL TO:

Angela Calvillo
Clerk of the Board of Supervisors
City Hall, Room 244
1 Dr. Carlton B. Goodlett Place
San Francisco, CA 94102

APN: Block 7326

SPACE ABOVE THIS LINE FOR RECORDER'S USE

QUITCLAIM DEED

THE UNDERSIGNED GRANTOR DECLARES:

DOCUMENTARY TRANSFER TAX is \$ 0

- computed on full value of property conveyed, or
 computed on full value less value of liens or encumbrances remaining at time of sale.

- unincorporated area
 city and county of SAN FRANCISCO

FOR A VALUABLE CONSIDERATION, receipt of which is hereby acknowledged,
CITY AND COUNTY OF SAN FRANCISCO, a municipal corporation, acting by and through
its Department of Real Estate ("Grantor"),

does hereby REMISE, RELEASE and forever QUITCLAIM to

PARKMERCED OWNER LLC, a Delaware limited liability company,

the following described real property in the City and County of San Francisco, State of California:

See Exhibit "A" attached hereto and made a part hereof.

[SIGNATURE PAGE FOLLOWS]

Executed as of _____, 2016.

CITY
CITY AND COUNTY OF
SAN FRANCISCO,
a municipal corporation

Approved as to form
_____, City Attorney

By: _____

By: _____
Deputy City Attorney

Director of Real Estate

Approved on _____
Board of Supervisors Ordinance No. _____

State of California)
County of San Francisco)

On _____, before me, _____, a Notary
Public, personally appeared _____, who proved to me on the
basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within
instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized
capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity
upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the
foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature

(Affix Seal)



ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

LEGAL DESCRIPTION
EXHIBIT A
VACATION PARCEL 5

All that certain real property situated in the City and County of San Francisco, State of California, being a portion of Cambon Drive as shown on that certain map entitled "RECORD OF SURVEY MAP NO. 8641" filed August 24, 2015, as Document Number 2015K114105, in the Office of the Recorder of the City and County of San Francisco, State of California, and being more particularly described as follows:

BEGINNING at the northwesterly corner of Block 7326 as shown on said map (see sheet 13 of 20), said point being the **TRUE POINT OF BEGINNING** of this description;

Thence leaving said Block 7326 the following two courses:

- 1) South $82^{\circ}26'18''$ West, 3.855 feet;
- 2) South $07^{\circ}33'42''$ East, 54.157 feet to the westerly line of said Block 7326, said point being the beginning of a non-tangent curve concave southeasterly whose radius point bears South $38^{\circ}38'06''$ East;

Thence along the westerly lines of Block 7326 the following two courses:

- 1) Northeasterly along said non-tangent curve having a radius of 22.000 feet, through a central angle of $11^{\circ}08'28''$, for an arc length of 4.278 feet to an angle point in said Block 7326;
- 2) North $07^{\circ}33'42''$ West, 52.318 feet to the **TRUE POINT OF BEGINNING**.

Containing an area of 205 square feet, more or less.

Horizontal Datum & Reference System

The horizontal datum is the North American Datum of 1983: NAD 83 (2011) Epoch 2010.00 referenced by the "CCSF-2013 High Precision Network" (CCSF-HPN). Plane coordinates are based on the "City & County of San Francisco 2013 coordinate system (CCSF-CS13). CCSF-CS13 is a low distortion projection designed for CCSF to provide plane coordinates in a ground system. See ROS 8080, filed April 4, 2014, in Book EE of Survey Maps at pages 147-157 in the Office of the Recorder of the City and County of San Francisco.




ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

A plat showing the above-described parcel is attached herein and made a part hereof.

This description was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act.





Alex Calder
Alex M. Calder, LLS 8863

10-19-2015
Dated

END OF DESCRIPTION

EXHIBIT A



AREA TO BE VACATED
205. SQ.FT.±

EXISTING BOUNDARY

CARBON DRIVE
(65.5' WIDE)

S82°26'18"W
3.855'

TRUE POINT OF BEGINNING

S07°33'42"E
54.157'


N07°33'42"W
52.318'

VACATION PARCEL 5
(PHASE 1B - TENTATIVE MAP 8530)


D=11°08'28"
L=4.278'
R=22.000'

S38°38'06"E(R)

Alex Calder
10-19-2015



7326



255 SHORELINE DR
SUITE 200
REDWOOD CITY, CA 94065
650-482-6300
650-482-6399 (FAX)

Subject EXHIBIT A
PLAT TO ACCOMPANY DESCRIPTION
Job No. 20090086-51
By DCJ Date 10/19/15 Chkd: AMC
SHEET 3 OF 3

RECORDING REQUESTED BY
CLERK OF THE BOARD OF SUPERVISORS
OF THE CITY AND COUNTY OF SAN FRANCISCO

(Exempt from Recording Fees
Pursuant to Government Code
Section 27383)

AND WHEN RECORDED MAIL TO:

Angela Calvillo
Clerk of the Board of Supervisors
City Hall, Room 244
1 Dr. Carlton B. Goodlett Place
San Francisco, CA 94102

APN: Block 7326

SPACE ABOVE THIS LINE FOR RECORDER'S USE

QUITCLAIM DEED

THE UNDERSIGNED GRANTOR DECLARES:

DOCUMENTARY TRANSFER TAX is \$ 0

- computed on full value of property conveyed, or
 computed on full value less value of liens or encumbrances remaining at time of sale.

- unincorporated area
 city and county of SAN FRANCISCO

FOR A VALUABLE CONSIDERATION, receipt of which is hereby acknowledged,
CITY AND COUNTY OF SAN FRANCISCO, a municipal corporation, acting by and through
its Department of Real Estate ("Grantor"),

does hereby REMISE, RELEASE and forever QUITCLAIM to

PARKMERCED OWNER LLC, a Delaware limited liability company,

the following described real property in the City and County of San Francisco, State of California:

See Exhibit "A" attached hereto and made a part hereof.

[SIGNATURE PAGE FOLLOWS]

Executed as of _____, 2016.

CITY
CITY AND COUNTY OF
SAN FRANCISCO,
a municipal corporation

Approved as to form
_____, City Attorney

By: _____

By: _____
Deputy City Attorney

Director of Real Estate

Approved on _____
Board of Supervisors Ordinance No. _____

State of California)
County of San Francisco)

On _____, before me, _____, a Notary Public, personally appeared _____, who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature

(Affix Seal)



ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

**LEGAL DESCRIPTION
EXHIBIT A
VACATION PARCEL 6**

All that certain real property situated in the City and County of San Francisco, State of California, being a portion of Font Blvd as shown on that certain map entitled "RECORD OF SURVEY MAP NO. 8641" filed August 24, 2015, as Document Number 2015K114105, in the Office of the Recorder of the City and County of San Francisco, State of California, and being more particularly described as follows:

BEGINNING at the northwesterly terminus of the course labeled "S52°33'48"E 489.071 feet" on the westerly line of Block 7326 as said course and block are shown on said map (see sheet 17 of 20), said point being the **TRUE POINT OF BEGINNING** of this description;

Thence along the westerly lines of said Block 7326 the following three courses:

- 1) South 52°33'48" East, 489.071 feet to the beginning of a non-tangent curve concave northeasterly whose radius point bears North 89°35'02" East;
- 2) Southerly along said non-tangent curve having a radius of 22.000 feet, through a central angle of 52°08'50", for an arc length of 20.023 feet;
- 3) South 52°33'48" East, 33.174 feet;

Thence leaving said westerly line of said Block 7326 the following four courses:

- 1) North 69°24'12" West, 13.807 feet;
- 2) North 52°33'48" West, 546.418 feet to the beginning of a tangent curve to the right;
- 3) Along said tangent curve having a radius of 15.000 feet, through a central angle of 90°00'00", for an arc length of 23.562 feet;
- 4) North 37°26'12" East, 18.167 feet to the westerly line of said Block 7326 and the beginning of a non-tangent curve concave easterly whose radius point bears South 81°27'58" East;

Thence along said westerly line of said Block 7326 along last said non-tangent curve having a radius of 40.000 feet, through a central angle of 61°05'50", for an arc length of 42.654 feet to the **TRUE POINT OF BEGINNING**.

Containing an area of 6,932 square feet, more or less.



ENGINEERS
SURVEYORS
PLANNERS


October 19, 2015
BKF No. 20090086-51

Horizontal Datum & Reference System

The horizontal datum is the North American Datum of 1983: NAD 83 (2011) Epoch 2010.00 referenced by the "CCSF-2013 High Precision Network" (CCSF-HPN). Plane coordinates are based on the "City & County of San Francisco 2013 coordinate system" (CCSF-CS13). CCSF-CS13 is a low distortion projection designed for CCSF to provide plane coordinates in a ground system. See ROS 8080, filed April 4, 2014, in Book EE of Survey Maps at pages 147-157 in the Office of the Recorder of the City and County of San Francisco.

A plat showing the above-described parcel is attached herein and made a part hereof.

This description was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act.




Alex Calder
Alex M. Calder, ELS 8863

10-19-2015
Dated

END OF DESCRIPTION

EXHIBIT A



Subject EXHIBIT A
 PLAT TO ACCOMPANY DESCRIPTION
 Job No. 20090086-51
 By DCJ Date: 10/19/15 Chkd. AMC
 SHEET 3 OF 3



255. SHORELINE DR
 SUITE 200
 REDWOOD CITY, CA 94065
 650-482-6300
 650-482-6399 (FAX)

RECORDING REQUESTED BY
CLERK OF THE BOARD OF SUPERVISORS
OF THE CITY AND COUNTY OF SAN FRANCISCO

(Exempt from Recording Fees
Pursuant to Government Code
Section 27383)

AND WHEN RECORDED MAIL TO:

Angela Calvillo
Clerk of the Board of Supervisors
City Hall, Room 244
1 Dr. Carlton B. Goodlett Place
San Francisco, CA 94102

APN: Blocks 7330 and 7370

SPACE ABOVE THIS LINE FOR RECORDER'S USE

QUITCLAIM DEED

THE UNDERSIGNED GRANTOR DECLARES:

DOCUMENTARY TRANSFER TAX is \$ 0

- computed on full value of property conveyed, or
 computed on full value less value of liens or encumbrances remaining at time of sale.

- unincorporated area
 city and county of SAN FRANCISCO

FOR A VALUABLE CONSIDERATION, receipt of which is hereby acknowledged,
CITY AND COUNTY OF SAN FRANCISCO, a municipal corporation, acting by and through
its Department of Real Estate ("Grantor"),

does hereby REMISE, RELEASE and forever QUITCLAIM to

PARKMERCED OWNER LLC, a Delaware limited liability company,

the following described real property in the City and County of San Francisco, State of California:

See Exhibit "A" attached hereto and made a part hereof.

[SIGNATURE PAGE FOLLOWS]

Executed as of _____, 2016.

CITY
CITY AND COUNTY OF
SAN FRANCISCO,
a municipal corporation

Approved as to form
_____, City Attorney

By: _____

By: _____
Deputy City Attorney

Director of Real Estate

Approved on _____
Board of Supervisors Ordinance No. _____

State of California)
County of San Francisco)

On _____, before me, _____, a Notary
Public, personally appeared _____, who proved to me on the
basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within
instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized
capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity
upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the
foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature

(Affix Seal)



ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

LEGAL DESCRIPTION
EXHIBIT A
VACATION PARCEL 7

All that certain real property situated in the City and County of San Francisco, State of California, being a portion of Chumasero Drive as shown on that certain map entitled "RECORD OF SURVEY MAP NO. 8641" filed August 24, 2015, as Document Number 2015K114105, in the Office of the Recorder of the City and County of San Francisco, State of California, and being more particularly described as follows:

BEGINNING at the northeasterly terminus of the course labeled "N37°26'12"E 41.139 feet" on the westerly line of Block 7330 as said course and block are shown on said map (see sheet 17 of 20), said point being the **TRUE POINT OF BEGINNING** of this description;

Thence along the westerly line of Block 7330, northeasterly along a tangent curve to the right having a radius of 22.000 feet, through a central angle of 07°50'15", for an arc length of 3.009 feet;

Thence leaving said westerly line of Block 7330, North 52°33'48" West, 31.706 feet to the easterly line of Block 7370;

Thence along the easterly, southerly, and westerly lines of Block 7330 the following six courses:

- 1) South 37°26'12" West, 57.499 feet to the beginning of a tangent curve to the left;
- 2) Along said tangent curve having a radius of 56.000 feet, through a central angle of 19°03'17", for an arc length of 18.624 feet to a point of reverse curvature;
- 3) Along said reverse curve having a radius of 2.000 feet, through a central angle of 180°00'00", for an arc length of 6.283 feet to a point of compound curvature;
- 4) Along said compound curve having a radius of 60.000 feet, through a central angle of 19°03'17", for an arc length of 19.954 feet;
- 5) North 37°26'12" East, 40.498 feet to the beginning of a tangent curve to the left;
- 6) Along said tangent curve having a radius of 73.000 feet, through a central angle of 13°28'02", for an arc length of 17.158 feet;

Thence leaving the westerly line of Block 7370, North 52°33'48" West, 32.738 feet to the westerly line of Chumasero Drive as shown on said map and the beginning of a non-tangent curve concave westerly whose radius point bears North 84°04'43" West;

Thence along the westerly lines of Chumasero Drive as shown on said map the following four courses:

- 1) Southwesterly along last said non-tangent curve having a radius of 22,000 feet, through a central angle of 31°30'55", for an arc length of 12.101 feet;
- 2) South 37°26'12" West, 37.764 feet to the beginning of a tangent curve to the left;



ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

- 3) Along said tangent curve having a radius of 100.000 feet, through a central angle of $45^{\circ}00'00''$, for an arc length of 78.540 feet;
- 4) South $07^{\circ}33'48''$ East, 170.955 feet to the beginning of a non-tangent curve concave southeasterly whose radius point bears South $81^{\circ}58'24''$ East;

Thence leaving said westerly line of Chumasero Drive along said non-tangent curve having a radius of 81.500 feet, through a central angle of $29^{\circ}24'36''$, for an arc length of 41.834 feet;

Thence North $37^{\circ}26'12''$ East, 42.607 feet to the westerly line of said Block 7330;

Thence along the westerly lines of Block 7330 the following three courses:

- 1) North $07^{\circ}33'48''$ West, 61.349 feet to the beginning of a tangent curve to the right;
- 2) Along said tangent curve having a radius of 100.000 feet, through a central angle of $45^{\circ}00'00''$, for an arc length of 78.540 feet;
- 3) North $37^{\circ}26'12''$ East, 41.139 feet to the **TRUE POINT OF BEGINNING**.

Containing an area of 13,330 square feet, more or less.


Horizontal Datum & Reference System

The horizontal datum is the North American Datum of 1983: NAD 83 (2011) Epoch 2010.00 referenced by the "CCSF-2013 High Precision Network" (CCSF-HPN). Plane coordinates are based on the "City & County of San Francisco 2013 coordinate system (CCSF-CS13). CCSF-CS13 is a low distortion projection designed for CCSF to provide plane coordinates in a ground system. See ROS 8080, filed April 4, 2014, in Book EE of Survey Maps at pages 147-157 in the Office of the Recorder of the City and County of San Francisco.

A plat showing the above-described parcel is attached herein and made a part hereof.

This description was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act.

Alex Calder
Alex M. Calder, LLS 8863



10-19-2015
Dated

END OF DESCRIPTION

EXHIBIT A

N84°04'43"W(R)

S37°26'12"W
37.764'

7370

D=45°00'00"
L=78.540'
R=100.00'

N52°33'48"W
32.738'

31.706'

41.139'


TRUE POINT OF BEGINNING

VACATION PARCEL 7
(PHASE 1B - TENTATIVE MAP 8530)

D=45°00'00"
L=78.540'
R=100.000'


 = AREA TO BE VACATED
13,330 SQ.FT.±

 = EXISTING BOUNDARY






LINE TABLE		
LINE	LENGTH	BEARING
L1	57.499'	S37°26'12"W
L2	40.498'	N37°26'12"E

CURVE TABLE			
CURVE	LENGTH	RADIUS	ANGLE
C1	12.101'	22.000'	31°30'55"
C2	41.834'	81.500'	29°24'36"
C3	3.009'	22.000'	7°50'15"
C4	18.624'	56.000'	19°03'17"
C5	6.283'	2.000'	180°00'00"
C6	19.954'	60.000'	19°03'17"
C7	17.158'	73.000'	13°28'02"



7330

Alex Calder
10-19-2015



255 SHORELINE DR.
SUITE 200
REDWOOD CITY, CA 94065
650-482-6300
650-482-6399 (FAX)

Subject EXHIBIT A
PLAT TO ACCOMPANY DESCRIPTION
 Job No. 20090086-51
 By DCJ Date 10/19/15 Chkd. AMG
 SHEET 3 OF 3

RECORDING REQUESTED BY
CLERK OF THE BOARD OF SUPERVISORS
OF THE CITY AND COUNTY OF SAN FRANCISCO

(Exempt from Recording Fees
Pursuant to Government Code
Section 27383)

AND WHEN RECORDED MAIL TO:

Angela Calvillo
Clerk of the Board of Supervisors
City Hall, Room 244
1 Dr. Carlton B. Goodlett Place
San Francisco, CA 94102

APN: Block 7330

SPACE ABOVE THIS LINE FOR RECORDER'S USE

QUITCLAIM DEED

THE UNDERSIGNED GRANTOR DECLARES:

DOCUMENTARY TRANSFER TAX is \$ 0

- computed on full value of property conveyed, or
 computed on full value less value of liens or encumbrances remaining at time of sale.

- unincorporated area
 city and county of SAN FRANCISCO

FOR A VALUABLE CONSIDERATION, receipt of which is hereby acknowledged,
CITY AND COUNTY OF SAN FRANCISCO, a municipal corporation, acting by and through
its Department of Real Estate ("Grantor"),

does hereby REMISE, RELEASE and forever QUITCLAIM to

PARKMERCED OWNER LLC, a Delaware limited liability company,

the following described real property in the City and County of San Francisco, State of California:

See Exhibit "A" attached hereto and made a part hereof.

[SIGNATURE PAGE FOLLOWS]

Executed as of _____, 2016.

CITY
CITY AND COUNTY OF
SAN FRANCISCO,
a municipal corporation

Approved as to form
_____, City Attorney

By: _____

By: _____
Deputy City Attorney

Director of Real Estate

Approved on _____
Board of Supervisors Ordinance No. _____

State of California)
County of San Francisco)

On _____, before me, _____, a Notary Public, personally appeared _____, who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature

(Affix Seal)



ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

LEGAL DESCRIPTION
EXHIBIT A
VACATION PARCEL 8

All that certain real property situated in the City and County of San Francisco, State of California, being a portion of Galindo Avenue as shown on that certain map entitled "RECORD OF SURVEY MAP NO. 8641" filed August 24, 2015, as Document Number 2015K114105, in the Office of the Recorder of the City and County of San Francisco, State of California, and being more particularly described as follows:

BEGINNING at the westerly terminus of the course labeled "S82°26'12"W 121.788 feet" on the westerly line of Block 7330 as said course and said block are shown on said map (see sheet 18 of 20), said point being the **TRUE POINT OF BEGINNING** of this description;

Thence along the westerly lines of said Block 7330 the following four courses:

- 1) North 82°26'12" East, 121.788 feet;
- 2) South 07°33'48" East, 67.000 feet;
- 3) South 82°26'12" West, 120.000 feet to the beginning of a tangent curve to the left;
- 4) Along said tangent curve having a radius of 22.000 feet, through a central angle of 39°44'56", for an arc length of 15.262 feet to the beginning of a non-tangent curve concave westerly whose radius point bears South 87°09'09" West;

Thence leaving said westerly line of Block 7330 along said non-tangent curve having a radius of 83.000 feet, through a central angle of 04°42'57", for an arc length of 6.831 feet;

Thence North 07°33'48" West, 68.822 feet to the westerly line of said Block 7330 and the beginning of a non-tangent curve concave northerly whose radius point bears North 25°29'15" East;

Thence along said westerly line along said non-tangent curve having a radius of 22.000 feet, through a central angle of 33°03'03", for an arc length of 12.691 feet to the **TRUE POINT OF BEGINNING**.

Containing an area of 8,999 square feet, more or less.



ENGINEERS
SURVEYORS
PLANNERS


October 19, 2015
BKF No. 20090086-51

Horizontal Datum & Reference System

The horizontal datum is the North American Datum of 1983: NAD 83 (2011). Epoch 2010.00 referenced by the "CCSF-2013 High Precision Network" (CCSF-HPN). Plane coordinates are based on the "City & County of San Francisco 2013 coordinate system (CCSF-CS13). CCSF-CS13 is a low distortion projection designed for CCSF to provide plane coordinates in a ground system. See ROS 8080, filed April 4, 2014, in Book EE of Survey Maps at pages 147-157 in the Office of the Recorder of the City and County of San Francisco.

A plat showing the above-described parcel is attached herein and made a part hereof.

This description was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act.



Alex Calder
Alex M. Calder, LLS 8863

10-19-2015
Dated




END OF DESCRIPTION

EXHIBIT A

 AREA TO BE VACATED
8,999 SQ.FT. ±

--- EXISTING BOUNDARY



VACATION PARCEL 8
(PHASE 1B - TENTATIVE MAP 8530)



57

BROTHERHOOD WAY

Alex Calder
10-19-2015



255 SHORELINE DR.
SUITE 200
REDWOOD CITY, CA 94065
650-482-6300
650-482-6399 (FAX)

Subject EXHIBIT A
PLAT TO ACCOMPANY DESCRIPTION
Job No. 20090086-51
By DCJ Date 10/19/15 Chkd. AMC
SHEET 3 OF 3

RECORDING REQUESTED BY
CLERK OF THE BOARD OF SUPERVISORS
OF THE CITY AND COUNTY OF SAN FRANCISCO

(Exempt from Recording Fees
Pursuant to Government Code
Section 27383)

AND WHEN RECORDED MAIL TO:

Angela Calvillo
Clerk of the Board of Supervisors
City Hall, Room 244
1 Dr. Carlton B. Goodlett Place
San Francisco, CA 94102

APN: Block 7330

SPACE ABOVE THIS LINE FOR RECORDER'S USE

QUITCLAIM DEED

THE UNDERSIGNED GRANTOR DECLARES:

DOCUMENTARY TRANSFER TAX is \$ 0

- computed on full value of property conveyed, or
 computed on full value less value of liens or encumbrances remaining at time of sale.

- unincorporated area
 city and county of SAN FRANCISCO

FOR A VALUABLE CONSIDERATION, receipt of which is hereby acknowledged,
CITY AND COUNTY OF SAN FRANCISCO, a municipal corporation, acting by and through
its Department of Real Estate ("Grantor"),

does hereby REMISE, RELEASE and forever QUITCLAIM to

PARKMERCED OWNER LLC, a Delaware limited liability company,

the following described real property in the City and County of San Francisco, State of California:

See Exhibit "A" attached hereto and made a part hereof.

[SIGNATURE PAGE FOLLOWS]

Executed as of _____, 2016.

CITY
CITY AND COUNTY OF
SAN FRANCISCO,
a municipal corporation

Approved as to form
_____, City Attorney

By: _____

By: _____
Deputy City Attorney

Director of Real Estate

Approved on _____
Board of Supervisors Ordinance No. _____

State of California)
County of San Francisco)

On _____, before me, _____, a Notary Public, personally appeared _____, who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature

(Affix Seal)



ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

LEGAL DESCRIPTION
EXHIBIT A
VACATION PARCEL 9

All that certain real property situated in the City and County of San Francisco, State of California, being a portion of Chumasero Drive as shown on that certain map entitled "RECORD OF SURVEY MAP NO. 8641" filed August 24, 2015, as Document Number 2015K114105, in the Office of the Recorder of the City and County of San Francisco, State of California, and being more particularly described as follows:

BEGINNING at the southwesterly terminus of the course labeled "N46°15'12"E 186.950 feet" on the southerly line of Block 7330 as said course and said block are shown on said map (see sheet 18 of 20), said point being the **TRUE POINT OF BEGINNING** of this description;

Thence leaving said southerly line the following three courses:

- 1) South 46°15'12" West, 11.852 feet to the beginning of a tangent curve to the right;
- 2) Along said tangent curve having a radius of 42.750 feet, through a central angle of 69°06'15", for an arc length of 51.561 feet;
- 3) North 64°38'33" West, 169.798 feet to the westerly line of Chumasero Drive as shown on said map and the beginning of a non-tangent curve concave northwesterly whose radius point bears North 25°21'27" East;

Thence along said westerly lines of Chumasero Drive the following three courses:

- 1) Along said non-tangent curve having a radius of 5.000 feet, through a central angle of 162°33'15", for an arc length of 14.186 feet;
- 2) North 47°11'48" West, 13.557 feet to the beginning of a tangent curve to the right;
- 3) Along said tangent curve having a radius of 200.000 feet, through a central angle of 13°33'00", for an arc length of 47.298 feet;

Thence leaving said westerly line of Chumasero Drive, North 23°32'41" East, 55.544 feet to the beginning of a tangent curve to the left;

Thence along said tangent curve having a radius of 83.000 feet, through a central angle of 07°40'29", for an arc length of 11.118 feet to the westerly line of said Block 7330 and the beginning of a non-tangent curve concave northeasterly whose radius point bears North 70°37'22" East;

Thence along said westerly lines of said Block 7330 the following three courses:

- 1) Along said non-tangent curve having a radius of 149.000 feet, through a central angle of 27°49'10", for an arc length of 72.346 feet;
- 2) South 47°11'48" East, 164.940 feet to the beginning of a tangent curve to the left;



BKF

ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

3) Along said tangent curve having a radius of 42,750 feet, through a central angle of 86°33'00", for an arc length of 64,577 feet to the **TRUE POINT OF BEGINNING**.


Containing an area of 9,792 square feet, more or less.

Horizontal Datum & Reference System

The horizontal datum is the North American Datum of 1983: NAD 83 (2011) Epoch 2010.00 referenced by the "CCSF-2013 High Precision Network" (CCSF-HPN). Plane coordinates are based on the "City & County of San Francisco 2013 coordinate system (CCSF-CS13). CCSF-CS13 is a low distortion projection designed for CCSF to provide plane coordinates in a ground system. See ROS 8080, filed April 4, 2014, in Book EE of Survey Maps at pages 147-157 in the Office of the Recorder of the City and County of San Francisco.

A plat showing the above-described parcel is attached herein and made a part hereof.

This description was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act.






Alex Calder
Alex M. Calder, LLS 8863

10-19-2015
Dated


END OF DESCRIPTION

EXHIBIT A




CURVE TABLE			
CURVE	LENGTH	RADIUS	ANGLE
C1	51.561'	42.750'	69°06'15"
C2	14.186'	5.000'	162°33'15"
C3	47.298'	200.000'	13°33'00"
C4	11.118'	83.000'	7°40'29"
C5	72.346'	149.000'	27°49'10"
C6	64.577'	42.750'	86°33'00"

LINE TABLE		
LINE	LENGTH	BEARING
L1	11.852'	S46°15'12\"W
L2	13.557'	N47°11'48\"W
L3	55.544'	N23°32'41\"E



Alex Calder
10-19-2015

 = AREA TO BE VACATED
9,792 SQ.FT.±

— — — — — EXISTING BOUNDARY



255 SHORELINE DR
SUITE 200
REDWOOD CITY, CA 94065
650-482-6300
650-482-6399 (FAX)

Subject: EXHIBIT A
PLAT TO ACCOMPANY DESCRIPTION
Job No. 20090086-51
By DCJ Date 10/19/15 Chkd AMC
SHEET 3 OF 3

RECORDING REQUESTED BY
CLERK OF THE BOARD OF SUPERVISORS
OF THE CITY AND COUNTY OF SAN FRANCISCO

(Exempt from Recording Fees
Pursuant to Government Code
Section 27383)

AND WHEN RECORDED MAIL TO:

Angela Calvillo
Clerk of the Board of Supervisors
City Hall, Room 244
1 Dr. Carlton B. Goodlett Place
San Francisco, CA 94102

APN: Blocks 7326 and 7330

SPACE ABOVE THIS LINE FOR RECORDER'S USE

QUITCLAIM DEED

THE UNDERSIGNED GRANTOR DECLARES:

DOCUMENTARY TRANSFER TAX is \$ 0

- computed on full value of property conveyed, or
 computed on full value less value of liens or encumbrances remaining at time of sale.

- unincorporated area
 city and county of SAN FRANCISCO

FOR A VALUABLE CONSIDERATION, receipt of which is hereby acknowledged,
CITY AND COUNTY OF SAN FRANCISCO, a municipal corporation, acting by and through
its Department of Real Estate ("Grantor"),

does hereby REMISE, RELEASE and forever QUITCLAIM to

PARKMERCED OWNER LLC, a Delaware limited liability company,

the following described real property in the City and County of San Francisco, State of California:

See Exhibit "A" attached hereto and made a part hereof.

[SIGNATURE PAGE FOLLOWS]

Executed as of _____, 2016.

CITY
CITY AND COUNTY OF
SAN FRANCISCO,
a municipal corporation

Approved as to form
_____, City Attorney

By: _____

By: _____
Deputy City Attorney

Director of Real Estate

Approved on _____
Board of Supervisors Ordinance No. _____

State of California)
County of San Francisco)

On _____, before me, _____, a Notary Public, personally appeared _____, who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature

(Affix Seal)



ENGINEERS
SURVEYORS
PLANNERS

October 19, 2015
BKF No. 20090086-51

**LEGAL DESCRIPTION
EXHIBIT A
VACATION PARCEL 10**

All that certain real property situated in the City and County of San Francisco, State of California, being a portion of Font Blvd. as shown on that certain map entitled "RECORD OF SURVEY MAP NO. 8641" filed August 24, 2015, as Document Number 2015K114105, in the Office of the Recorder of the City and County of San Francisco, State of California, and being more particularly described as follows:

BEGINNING at the southerly terminus of the course labeled "N16°30'49"W 898.746 feet" on the easterly line of Block 7326 as said course and said block are shown on said map (see sheet 17 of 20), said point being the **TRUE POINT OF BEGINNING** of this description;

Thence leaving Block 7326, South 16°30'49" East, 229.181 feet to the easterly line of Block 7330 as shown on said map and the beginning of a non-tangent curve concave southwesterly whose radius point bears South 42°25'05" West;

Thence along said easterly lines of said Block 7330 the following two courses:

- 1) Along said non-tangent curve having a radius of 22.000 feet, through a central angle of 04°58'53", for an arc length of 1.913 feet;
- 2) North 52°33'48" West, 295.652 feet;

Thence leaving Block 7330, North 37°26'12" East, 45.500 feet to the westerly line of Block 7366 as shown on said map;

Thence along the westerly, southerly, and easterly lines of said Block 7366 the following three courses:

- 1) South 52°33'48" East, 123.107 feet to the beginning of a tangent curve to the left;
- 2) Along said tangent curve having a radius of 2.000 feet, through a central angle of 180°00'00", for an arc length of 6.283 feet;
- 3) North 52°33'48" West, 123.107 feet;

Thence leaving said Block 7366 the following two courses:

- 1) North 37°26'12" East, 3.660 feet;
- 2) North 73°28'51" East, 51.746 feet to the westerly line of said Block 7326 as shown on said map;

Thence along the westerly and southerly line of said Block 7326 the following two courses:



October 19, 2015
BKF No. 20090086-51

- 1) South 52°33'48" East, 68.873 feet to the beginning of a tangent curve to the left;
- 2) Along said tangent curve having a radius of 22.000 feet, through a central angle of 143°57'01", for an arc length of 55.273 feet to the **TRUE POINT OF BEGINNING.**

Containing an area of 21,802 square feet, more or less.


Horizontal Datum & Reference System

The horizontal datum is the North American Datum of 1983: NAD 83 (2011) Epoch 2010.00 referenced by the "CCSF-2013 High Precision Network" (CCSF-HPN). Plane coordinates are based on the "City & County of San Francisco 2013 coordinate system (CCSF-CS13). CCSF-CS13 is a low distortion projection designed for CCSF to provide plane coordinates in a ground system. See ROS 8080, filed April 4, 2014, in Book EE of Survey Maps at pages 147-157 in the Office of the Recorder of the City and County of San Francisco.

A plat showing the above-described parcel is attached herein and made a part hereof.

This description was prepared by me or under my direction in conformance with the Professional Land Surveyors' Act.

Alex Calder
Alex M. Calder, LLS 8863




10-19-2015
Dated

END OF DESCRIPTION

EXHIBIT A

LINE TABLE		
LINE	LENGTH	BEARING
L1	45.500'	N37°26'12"E
L2	3.660'	N37°26'12"E



7326

L-7366

D=143°57'01"
L=55.273'
R=22.000'

TRUE POINT OF BEGINNING

N73°28'51"E
51.746'

S52°33'48"E
68.873'

L1
S52°33'48"E

D=180°00'00"
L=6.283'
R=2.000'

123.107'


JUNIPERO SERRA BOULEVARD
S16°30'49"E
228.181'

VACATION PARCEL 10
(PHASE 1B - TENTATIVE MAP 8530)

7330

95' WIDE
FRONT BOULEVARD
N52°33'48"W
295.652'

Alex Calder
10-19-2015




D=4°58'53"
L=1.913'
R=22.000'

S42°25'05"W(R)

= AREA TO BE VACATED
21,802 SQ.FT.±

EXISTING BOUNDARY



67



255 SHORELINE DR
SUITE 200
REDWOOD CITY, CA 94065
650-482-6300
650-482-6399 (FAX)

Subject EXHIBIT A
PLAT TO ACCOMPANY DESCRIPTION
Job No. 20090086-51
By: DCJ Date 10/19/15 Chkd: AMC
SHEET 3 OF 3



Office of the City and County Surveyor
1155 Market Street, 3rd Floor
San Francisco, Ca 94103
(415) 554-5827 ■ www.sfdpw.org



Edwin M. Lee, Mayor
Mohammed Nuru, Director

Bruce R. Storrs, City and County Surveyor

DPW Order No: 185138

Determination to recommend vacating portions of streets within the Parkmerced Development Project area, an approximately 152 acre site located in the Lake Merced District in the southwest corner of San Francisco and generally bounded by Vidal Drive, Font Boulevard, Pinto Avenue, and Serrano Drive to the north, 19th Avenue and Junipero Serra Boulevard to the east, Brotherhood Way to the south, and Lake Merced Boulevard to the west, pursuant to California Streets and Highways Code Sections 8300 *et seq.* and Public Works Code Section 787 subject to certain conditions.

WHEREAS, The City and County of San Francisco owns most public streets and sidewalks as public right-of-way; and

WHEREAS, The portions of the streets to be vacated are in the Parkmerced Development Project area, an approximately 152 acre site located in the Lake Merced District in the southwest corner of San Francisco and generally bounded by Vidal Drive, Font Boulevard, Pinto Avenue, and Serrano Drive to the north, 19th Avenue and Junipero Serra Boulevard to the east, Brotherhood Way to the south, and Lake Merced Boulevard to the west, the areas to be vacated ("the Vacation Area"), are specifically shown on SUR Map 2015-006, dated June 10, 2016; and

WHEREAS, The vacation of the Vacation Area is necessary to implement the Project, to fulfill the objectives and requirements of the Development Agreement and fulfill the objectives of the Parkmerced Special Use District (Planning Code section 249.64). The proposed vacations and other actions contemplated herein implement the Project vested by the Project Approvals, including the construction of buildings and streets consistent with the Parkmerced Design Standards and Guidelines, the Parkmerced Transportation Plan, and the Parkmerced Infrastructure Report, all of which are incorporated by reference into the Development Agreement; and

WHEREAS, The City proposes to quitclaim its interest in the Vacation Area to the Project Sponsor, consistent with Development Agreement Section 6.1.1; and

WHEREAS, On February 10, 2011, at a duly noticed public hearing, the Planning Commission certified the Final Environmental Impact Report ("Final EIR") for the Parkmerced Mixed-Use Development Project (the "Project"), by Motion No. 18269, finding that the Final EIR reflects the independent judgment and analysis of the City and County of San Francisco, is adequate, accurate and objective, contains no significant revisions to the Draft EIR, and the content of the report and the procedures through which the Final EIR was prepared, publicized and reviewed comply with the provisions of the California Environmental Quality Act (California Public



Resources Code Section 21000 et seq., "CEQA"), the State CEQA Guidelines (California Code of Regulations Title 14 Section 15000 et seq.), and Chapter 31 of the San Francisco Administrative Code ("Chapter 31"); and

WHEREAS, At the same hearing during which the Planning Commission certified the Final EIR, the Planning Commission by Motion No. 18629 adopted findings, as required by CEQA, regarding the alternatives, mitigation measures, and significant environmental effects analyzed in the Final EIR, a statement of overriding considerations for approval of the Project, and a proposed mitigation monitoring and reporting program (collectively, "CEQA Findings"); and

WHEREAS, On May 24, 2011, at a duly noticed public hearing, the San Francisco Board of Supervisors reviewed and considered the Final EIR on appeal. By Motion M11-83, the Board of Supervisors upheld the Planning Commission's certification of the Final EIR and found the Final EIR to be complete, adequate and objective and reflecting the independent judgment of the City and in compliance with CEQA and the State CEQA Guidelines; and

WHEREAS, On June 7, 2011, at a duly noticed public hearing, the Board of Supervisors considered the Project's approvals, which included amendments to the City's General Plan (approved by Ordinance No. 92-11), Zoning Map (approved by Ordinance No. 91-11), and Planning Code (approved by Ordinance No. 90-11), as well as approval of a Development Agreement, approved on June 7, 2011 by Ordinance No. 89-11 (the "Development Agreement") (collectively, the "Project Approvals"); and

WHEREAS, In approving the Project, including in its approval of the Development Agreement by Ordinance No. 89-11, the Board of Supervisors adopted the Planning Commission's CEQA Findings as its own and incorporated them by reference. In so doing, the Board of Supervisors approved and endorsed the Mitigation Monitoring and Reporting Program for implementation by other City departments and recommended for adoption those mitigation measures that are enforceable by agencies other than City departments. A copy of the CEQA Findings and the Mitigation Monitoring and Reporting Program is on file with the Clerk of the Board in File No. _____ and is incorporated by reference.

WHEREAS, In a letter (the "DRE Letter"), the Director of the Department of Real Estate determined that (i) the Development Agreement contemplates the vacation of the Street Vacation Area, (ii) Exhibit J of the Development Agreement shows the general locations of the property vacations and dedications required by the Project, (iii) section 6.1.2 of the Development Agreement requires that (a) all real property exchanged under the Development Agreement be valued on a square foot basis, and shall be deemed equal in value per square foot, (b) if any real property exchange under the Development Agreement results in a net loss of acreage for the City, then the project sponsor must pay to the City the fair market value of the real property loss at the time of transfer based on the then-current use of the property so transferred, and (c) the City shall not be required to pay for any net gain in real property; provided, however, such gain can be applied against future real property transfers for purposes of determining whether there has been a net loss as described above. The Director Real Estate also determined in the DRE Letter that (i) the proposed vacations and dedications associated with Subdivision Maps 8350, 8351, and 8352 result in a net gain in real property owned by the City and therefore that (ii) no payment is owed by the Project for the vacation of the Street Vacation Area, and (iii) this net gain should be credited against future public right of way vacations for the Project; and



WHEREAS, Pursuant to the California Streets and Highway Code, the Department of Public Works, Bureau of Street Use and Mapping (the "Department") has initiated the process to vacate the Vacation Area; and

WHEREAS, The Department sent notice of the proposed street vacation, draft SUR drawing, a copy of the petition letter, and a PW referral letter to the Department of Technology, San Francisco Municipal Transportation Agency, AT&T, Sprint, San Francisco Fire Department, San Francisco Water Department, Pacific Gas and Electric ("PG&E"), Bureau of Light, Heat and Power, Bureau of Engineering, Department of Parking and Traffic, Utility Engineering Bureau, and the Public Utility Commission ("PUC"). No utility company or agency objected to the proposed vacation, and the Vacation Area is unnecessary for the City's present or prospective public street purposes; and

WHEREAS, The applicant made reasonable attempts to notify and obtain consent from all property owners adjacent to the Vacation Area and the proposed street vacations do not deprive any private landowner of access to the built public street grid; and

WHEREAS, The public interest, convenience, and necessity require that, except as specifically provided herein, no other easements or other rights should be reserved by City for any public or private utilities or facilities that may be in place in the Vacation Area and that any rights based upon any such public or private utilities or facilities are unnecessary and should be extinguished; and

WHEREAS, Because many of these streets and easements will remain in use until specified times, no portion of the Street Vacation Area shall be vacated until certain conditions are satisfied, as follows:

1. The Project Sponsor shall provide an irrevocable offer of dedication to the City in form substantially similar to that provided in Exhibit L of the Development Agreement for all lands needed for construction of proposed improvements shown on the Street Improvement Permit for Subphases 1A and 1B of the Project. Subdivider shall make such irrevocable offers of dedication prior to City approval of the Final Subdivision Maps or issuance of a Street Improvement Permit for Subphases 1A or 1B of the Project, whichever is earlier. The offer of dedication shall be subject to the reservation of an easement in favor of Project Sponsor for all domestic water utilities within the dedicated area, which easement shall be extinguished upon completion of all Development Phases of the Project. The sum total of the square footage of the land proposed for dedication to the City shall be equal to or exceed the square footage of the Street Vacation Area.
2. Project Sponsor shall provide PW with an acceptable Public Improvement Agreement ("PIA") pursuant to Section 1351 of the San Francisco Subdivision Code and the Subdivision Map Act for all improvements within the Final Map or required for development of area shown in the Final Map prior to recording a Final Map or issuance of a Street Improvement Permit for Subphases 1A or 1B of the Project, whichever is earlier. Such PIA shall address security provisions and provide interim easements or licenses via separate offer, such that the City can complete the improvements if Subdivider fails to do so; and

WHEREAS, Pursuant to the Streets and Highways Code Section 892, the Department determines that the Vacation Area is unnecessary for non-motorized transportation because the Development



Agreement requires the dedication and construction of an extensive street, bicycle path, pedestrian path, park, and trail system that is more extensive than the areas being vacated and that is designed to integrate with existing built streets in the adjacent neighborhoods; and

WHEREAS, The Director of Public Works for the City and County of San Francisco has determined the following:

1. The vacation is being carried out pursuant to the California Streets and Highways Code Sections 8300 et seq.
2. The vacation is being carried out pursuant to San Francisco Public Works Code Section 787.
3. The Vacation Area to be vacated is shown on the SUR Map No. 2015-006.
4. These vacations are necessary to implement the Project, to fulfill the objectives and requirements of the Development Agreement and fulfill the objectives of the Parkmerced Special Use District (Planning Code section 249.64).
5. In exchange for the vacated areas, the Project Sponsor shall provide an irrevocable offer of dedication to the City in form substantially similar to that provided in Exhibit L of the Development Agreement for all lands needed for construction of proposed improvements shown on the Street Improvement Permit for Subphases 1A and 1B of the Project. Subdivider shall make such irrevocable offers of dedication prior to City approval of the Final Subdivision Maps or issuance of a Street Improvement Permit for Subphases 1A or 1B of the Project, whichever is earlier. The offer of dedication shall be subject to the reservation of an easement in favor of Project Sponsor for all domestic water utilities within the dedicated area, which easement shall extinguished upon completion of all Development Phases of the Project. The sum total of the square footage of the land proposed for dedication to the City shall be equal to or exceed the square footage of the Street Vacation Area.
6. Project Sponsor shall provide PW with an acceptable Public Improvement Agreement ("PIA") pursuant to Section 1351 of the San Francisco Subdivision Code and the Subdivision Map Act for all improvements within the Final Map or required for development of area shown in the Final Map prior to recording a Final Map or issuance of a Street Improvement Permit for Subphases 1A or 1B of the Project, whichever is earlier. Such PIA shall address security provisions and provide interim easements or licenses via separate offer, such that the City can complete the improvements if Subdivider fails to do so.
7. The public interest, convenience, and necessity require that the City reserve from the vacation of the Street Vacation Area non-exclusive easements for the benefit of the City (and subject to possible grants by the City of temporary, immediately revocable licenses by the City in favor of AT&T, PG&E, and any other utilities) for any utilities, telecommunications facilities, or power and gas transmission facilities, respectively, located in, upon, and over any portion of the Street Vacation Area in which their respective in-place and functioning utilities are located as of the effective date of this ordinance, to the extent necessary to maintain, operate, repair, and remove existing lines of pipe, conduits, cables, wires, poles, and other convenient structures, equipment and fixtures for the operation by City of City utilities, by AT&T of telecommunications facilities, by PG&E of power and gas transmission facilities, or for other public utilities. This reservation, and any subsequent grant of easements or licenses would be subject to the City's authority to require AT&T, PG&E, and any other utilities to remove or relocate their facilities at no expense



to the City when necessary to accommodate a project done under the governmental authority of the City. To the extent such non-exclusive easements have not previously merged into a fee interest held by the City, such non-exclusive easements would be automatically extinguished when such alternative replacement facilities are completed to the satisfaction of the City Engineer and the Board of Supervisors accepts the facilities. The City would execute a quitclaim of any interest in any such easement and would cause such quitclaim to be recorded against the subject property upon the fee title owner demonstrating to the City that replacement utilities serving the affected area have been substantially completed and operable. In the event a non-exclusive easement described in this section has merged into the fee interest held by the City, such interest would be deemed to be automatically extinguished and conveyed at the time the fee interest is conveyed by the City to Project Sponsor or any other transferee pursuant to the Development Agreement.

8. The public interest, convenience, and necessity require that the City reserve from the vacation of the Street Vacation Area temporary access for the benefit of the public over any portion of the Street Vacation Area where required to preserve access between a private property and the existing street grid as of the effective date of this ordinance. To the extent the access rights described in this section have not previously merged into a fee interest held by the City, such access would be automatically extinguished when replacement access serving the affected area has been substantially completed and is open to the public as certified by PW. In the event a non-exclusive easement described in this section has merged into the fee interest held by the City, such interest would be deemed to be automatically extinguished and conveyed at the time the fee interest is conveyed by the City to Project Sponsor or any other transferee pursuant to the Development Agreement.

9. Pursuant to the Streets and Highways Code Section 892, the Vacation Area is not useful as a non-motorized transportation facility for the reasons set forth herein.

10. The Director of the Real Estate Division has negotiated a purchase and sale agreement and a quitclaim for the Vacation Area. Approval of the real estate transaction is a policy matter for the Board of Supervisors, subject to the requirements of the Development Agreement.

NOW THEREFORE BE IT ORDERED THAT,

The Director approves all of the following documents either attached hereto or referenced herein:

1. Ordinance to vacate the Vacation Area;
2. Vacation Area SUR Map No. 2015-006

The Director recommends that the Board of Supervisors move forward with the legislation to vacate said Vacation Area subject to obtaining a finding of General Plan consistency from the City Planning Department.

The Director recommends the Board of Supervisors approve all actions set forth herein with respect to this vacation. The Director further recommends the Board of Supervisors authorize the Mayor, Clerk of the Board, Director of Property, County Surveyor, and Director of Public Works to take any and all actions which they or the City Attorney may deem necessary or advisable in order to effectuate the purpose and intent of this Ordinance.



7/22/2016

7/22/2016

X Bruce R. Storrs

Storrs, Bruce
City and County Surveyor
Signed by: Storrs, Bruce


X Mohammed Nuru

Nuru, Mohammed
Director
Signed by: Nuru, Mohammed





Edwin M. Lee, Mayor
Naomi M. Kelly, City Administrator



John Updike
Director of Real Estate

July 5, 2016

Mr. Bruce Storrs
City and County Surveyor
San Francisco Department of Public Works
City Hall, Room 348
1 Dr. Carlton B. Goodlett Place
San Francisco, CA 94102

Re: Street Vacations for Parkmerced Subphases 1A and 1B

Dear Mr. Storrs:

The Parkmerced Development Agreement approved and adopted by the San Francisco Board of Supervisors and Mayor in 2011 by Ordinance No. 0089-11 ("Development Agreement") provides for certain street or right-of-way vacations ("Street Vacations") and dedications ("Street Dedications") as part of the Parkmerced Project. Parkmerced Owner LLC (the project sponsor of the Parkmerced Project) filed an application for the required street vacations on April 24, 2015.

I am informed that Subdivision Maps 8530, 8531, and 8532 implement Subphases 1A and 1B of the Parkmerced Project. I have received and reviewed the Street Vacations as depicted in San Francisco Public Works' SUR Map No. 2015-006, sheets 1 through 10, dated June 10, 2016, and the Street Dedications as depicted on Subdivision Maps 8530, 8531, and 8532.

The Street Vacations include portions of the following streets within Parkmerced along with public service easements in the vacated streets or between them: Vidal Drive, Galindo Avenue, Chumasero Drive, Acevedo Avenue, Serrano Drive, Gonzalez Drive, Carbon Drive, and Font Boulevard.

Parkmerced Development Agreement

The Development Agreement contemplates the Street Vacations and Street Dedications required by the Project, including those anticipated by Subdivision Maps 8350, 8351, and 8352.

Section 6.1.1 of the Development Agreement provides that the City vacate portions of streets along with public service easements at the locations generally shown in Exhibit J of the

I:\Managers\1-Admin\JUA\Admin Corresp\RED edits\DRE to DPW Letter (Street Vacations).docx.doc
Office of the Director of Real Estate • 25 Van Ness Avenue, Suite 400 • San Francisco, CA 94102
(415) 554-9850 FAX: (415) 552-9216

Development Agreement, as and when needed in connection with the development of an approved Development Phase for the Project.

The Development Agreement, Section 6.1.2, further provides that:

- All real property exchanged under the Development Agreement be valued on a square foot basis, and shall be deemed equal in value per square foot.
- If any real property exchange under the Development Agreement results in a net loss of acreage for the City, then the project sponsor must pay to the City the fair market value of the real property loss at the time of transfer based on the then-current use of the property so transferred.
- The City shall not be required to pay for any net gain in real property; provided, however, such gain can be applied against future real property transfers for purposes of determining whether there has been a net loss as described above.

Sub-Phases 1A and 1B Proposed Street Vacations and Street Dedications

As shown on the enclosed exhibit prepared by BKF Engineers, upon the completion of the proposed Street Vacations and Street Dedications of Sub-phases 1A and 1B of the Project, and excluding any vacated or dedicated easements to the SFPUC which are not at issue for the purposes of this letter, the proposed Street Vacations and Street Dedications of Sub-phases 1A and 1B result in a net gain of 3,653 square feet of real property to City.

Per the language of the Development Agreement, set forth above, and based upon the agreed upon and approved equal square foot value for vacations as for dedications, it is my opinion that no payment by the project sponsor is now due to the City for the Street Vacations of Sub-phases 1A and 1B. This conclusion solely pertains to the Street Vacations and the Street Dedications as set forth in the enclosed exhibit and as defined and depicted in Subdivision Maps 8530, 8531, and 8532 and depicted in San Francisco Public Works' SUR Map No. 2015-006, sheets 1 through 10, dated June 10, 2016.


Respectfully,



John Updike
Director of Real Estate

Enc: Phase 1A and 1B Street Vacations and Dedications

JU/CG/mc



VACATION PARCELS (SHEET 2015-0001)

1. VACATION PARCEL 1
2. VACATION PARCEL 2
3. VACATION PARCEL 3
4. VACATION PARCEL 4
5. VACATION PARCEL 5
6. VACATION PARCEL 6
7. VACATION PARCEL 7
8. VACATION PARCEL 8
9. VACATION PARCEL 9
10. VACATION PARCEL 10
11. VACATION PARCEL 11
12. VACATION PARCEL 12
13. VACATION PARCEL 13
14. VACATION PARCEL 14
15. VACATION PARCEL 15
16. VACATION PARCEL 16
17. VACATION PARCEL 17
18. VACATION PARCEL 18
19. VACATION PARCEL 19
20. VACATION PARCEL 20
21. VACATION PARCEL 21
22. VACATION PARCEL 22
23. VACATION PARCEL 23
24. VACATION PARCEL 24
25. VACATION PARCEL 25
26. VACATION PARCEL 26
27. VACATION PARCEL 27
28. VACATION PARCEL 28
29. VACATION PARCEL 29
30. VACATION PARCEL 30
31. VACATION PARCEL 31
32. VACATION PARCEL 32
33. VACATION PARCEL 33
34. VACATION PARCEL 34
35. VACATION PARCEL 35
36. VACATION PARCEL 36
37. VACATION PARCEL 37
38. VACATION PARCEL 38
39. VACATION PARCEL 39
40. VACATION PARCEL 40
41. VACATION PARCEL 41
42. VACATION PARCEL 42
43. VACATION PARCEL 43
44. VACATION PARCEL 44
45. VACATION PARCEL 45
46. VACATION PARCEL 46
47. VACATION PARCEL 47
48. VACATION PARCEL 48
49. VACATION PARCEL 49
50. VACATION PARCEL 50
51. VACATION PARCEL 51
52. VACATION PARCEL 52
53. VACATION PARCEL 53
54. VACATION PARCEL 54
55. VACATION PARCEL 55
56. VACATION PARCEL 56
57. VACATION PARCEL 57
58. VACATION PARCEL 58
59. VACATION PARCEL 59
60. VACATION PARCEL 60
61. VACATION PARCEL 61
62. VACATION PARCEL 62
63. VACATION PARCEL 63
64. VACATION PARCEL 64
65. VACATION PARCEL 65
66. VACATION PARCEL 66
67. VACATION PARCEL 67
68. VACATION PARCEL 68
69. VACATION PARCEL 69
70. VACATION PARCEL 70
71. VACATION PARCEL 71
72. VACATION PARCEL 72
73. VACATION PARCEL 73
74. VACATION PARCEL 74
75. VACATION PARCEL 75
76. VACATION PARCEL 76
77. VACATION PARCEL 77
78. VACATION PARCEL 78
79. VACATION PARCEL 79
80. VACATION PARCEL 80
81. VACATION PARCEL 81
82. VACATION PARCEL 82
83. VACATION PARCEL 83
84. VACATION PARCEL 84
85. VACATION PARCEL 85
86. VACATION PARCEL 86
87. VACATION PARCEL 87
88. VACATION PARCEL 88
89. VACATION PARCEL 89
90. VACATION PARCEL 90
91. VACATION PARCEL 91
92. VACATION PARCEL 92
93. VACATION PARCEL 93
94. VACATION PARCEL 94
95. VACATION PARCEL 95
96. VACATION PARCEL 96
97. VACATION PARCEL 97
98. VACATION PARCEL 98
99. VACATION PARCEL 99
100. VACATION PARCEL 100

DEDICATION PARCELS

1. DEDICATION PARCEL 1
2. DEDICATION PARCEL 2
3. DEDICATION PARCEL 3
4. DEDICATION PARCEL 4
5. DEDICATION PARCEL 5
6. DEDICATION PARCEL 6
7. DEDICATION PARCEL 7
8. DEDICATION PARCEL 8
9. DEDICATION PARCEL 9
10. DEDICATION PARCEL 10
11. DEDICATION PARCEL 11
12. DEDICATION PARCEL 12
13. DEDICATION PARCEL 13
14. DEDICATION PARCEL 14
15. DEDICATION PARCEL 15
16. DEDICATION PARCEL 16
17. DEDICATION PARCEL 17
18. DEDICATION PARCEL 18
19. DEDICATION PARCEL 19
20. DEDICATION PARCEL 20
21. DEDICATION PARCEL 21
22. DEDICATION PARCEL 22
23. DEDICATION PARCEL 23
24. DEDICATION PARCEL 24
25. DEDICATION PARCEL 25
26. DEDICATION PARCEL 26
27. DEDICATION PARCEL 27
28. DEDICATION PARCEL 28
29. DEDICATION PARCEL 29
30. DEDICATION PARCEL 30
31. DEDICATION PARCEL 31
32. DEDICATION PARCEL 32
33. DEDICATION PARCEL 33
34. DEDICATION PARCEL 34
35. DEDICATION PARCEL 35
36. DEDICATION PARCEL 36
37. DEDICATION PARCEL 37
38. DEDICATION PARCEL 38
39. DEDICATION PARCEL 39
40. DEDICATION PARCEL 40
41. DEDICATION PARCEL 41
42. DEDICATION PARCEL 42
43. DEDICATION PARCEL 43
44. DEDICATION PARCEL 44
45. DEDICATION PARCEL 45
46. DEDICATION PARCEL 46
47. DEDICATION PARCEL 47
48. DEDICATION PARCEL 48
49. DEDICATION PARCEL 49
50. DEDICATION PARCEL 50
51. DEDICATION PARCEL 51
52. DEDICATION PARCEL 52
53. DEDICATION PARCEL 53
54. DEDICATION PARCEL 54
55. DEDICATION PARCEL 55
56. DEDICATION PARCEL 56
57. DEDICATION PARCEL 57
58. DEDICATION PARCEL 58
59. DEDICATION PARCEL 59
60. DEDICATION PARCEL 60
61. DEDICATION PARCEL 61
62. DEDICATION PARCEL 62
63. DEDICATION PARCEL 63
64. DEDICATION PARCEL 64
65. DEDICATION PARCEL 65
66. DEDICATION PARCEL 66
67. DEDICATION PARCEL 67
68. DEDICATION PARCEL 68
69. DEDICATION PARCEL 69
70. DEDICATION PARCEL 70
71. DEDICATION PARCEL 71
72. DEDICATION PARCEL 72
73. DEDICATION PARCEL 73
74. DEDICATION PARCEL 74
75. DEDICATION PARCEL 75
76. DEDICATION PARCEL 76
77. DEDICATION PARCEL 77
78. DEDICATION PARCEL 78
79. DEDICATION PARCEL 79
80. DEDICATION PARCEL 80
81. DEDICATION PARCEL 81
82. DEDICATION PARCEL 82
83. DEDICATION PARCEL 83
84. DEDICATION PARCEL 84
85. DEDICATION PARCEL 85
86. DEDICATION PARCEL 86
87. DEDICATION PARCEL 87
88. DEDICATION PARCEL 88
89. DEDICATION PARCEL 89
90. DEDICATION PARCEL 90
91. DEDICATION PARCEL 91
92. DEDICATION PARCEL 92
93. DEDICATION PARCEL 93
94. DEDICATION PARCEL 94
95. DEDICATION PARCEL 95
96. DEDICATION PARCEL 96
97. DEDICATION PARCEL 97
98. DEDICATION PARCEL 98
99. DEDICATION PARCEL 99
100. DEDICATION PARCEL 100

STREET VACATIONS TO BE VACATED

STREET	SECTION	FROM	TO	REMARKS
PARKMERCED BLVD	10	2101	2155	
PARKMERCED AVE	10	2101	2155	
21ST ST	10	2101	2155	
22ND ST	10	2101	2155	
23RD ST	10	2101	2155	
24TH ST	10	2101	2155	
25TH ST	10	2101	2155	
26TH ST	10	2101	2155	
27TH ST	10	2101	2155	
28TH ST	10	2101	2155	
29TH ST	10	2101	2155	
30TH ST	10	2101	2155	
31ST ST	10	2101	2155	
32ND ST	10	2101	2155	
33RD ST	10	2101	2155	
34TH ST	10	2101	2155	
35TH ST	10	2101	2155	
36TH ST	10	2101	2155	
37TH ST	10	2101	2155	
38TH ST	10	2101	2155	
39TH ST	10	2101	2155	
40TH ST	10	2101	2155	
41ST ST	10	2101	2155	
42ND ST	10	2101	2155	
43RD ST	10	2101	2155	
44TH ST	10	2101	2155	
45TH ST	10	2101	2155	
46TH ST	10	2101	2155	
47TH ST	10	2101	2155	
48TH ST	10	2101	2155	
49TH ST	10	2101	2155	
50TH ST	10	2101	2155	
51ST ST	10	2101	2155	
52ND ST	10	2101	2155	
53RD ST	10	2101	2155	
54TH ST	10	2101	2155	
55TH ST	10	2101	2155	
56TH ST	10	2101	2155	
57TH ST	10	2101	2155	
58TH ST	10	2101	2155	
59TH ST	10	2101	2155	
60TH ST	10	2101	2155	
61ST ST	10	2101	2155	
62ND ST	10	2101	2155	
63RD ST	10	2101	2155	
64TH ST	10	2101	2155	
65TH ST	10	2101	2155	
66TH ST	10	2101	2155	
67TH ST	10	2101	2155	
68TH ST	10	2101	2155	
69TH ST	10	2101	2155	
70TH ST	10	2101	2155	
71ST ST	10	2101	2155	
72ND ST	10	2101	2155	
73RD ST	10	2101	2155	
74TH ST	10	2101	2155	
75TH ST	10	2101	2155	
76TH ST	10	2101	2155	
77TH ST	10	2101	2155	
78TH ST	10	2101	2155	
79TH ST	10	2101	2155	
80TH ST	10	2101	2155	
81ST ST	10	2101	2155	
82ND ST	10	2101	2155	
83RD ST	10	2101	2155	
84TH ST	10	2101	2155	
85TH ST	10	2101	2155	
86TH ST	10	2101	2155	
87TH ST	10	2101	2155	
88TH ST	10	2101	2155	
89TH ST	10	2101	2155	
90TH ST	10	2101	2155	
91ST ST	10	2101	2155	
92ND ST	10	2101	2155	
93RD ST	10	2101	2155	
94TH ST	10	2101	2155	
95TH ST	10	2101	2155	
96TH ST	10	2101	2155	
97TH ST	10	2101	2155	
98TH ST	10	2101	2155	
99TH ST	10	2101	2155	
100TH ST	10	2101	2155	

LEGEND

- 2101 LOT NUMBER
- 2102 EXISTING LOT LINE
- 2103 PROPOSED LOT LINE
- 2104 EXISTING
- 2105 EXISTING TO BE VACATED BY SWMS
- 2106 AREA OF STREET DEDICATION
- 2107 AREA OF STREET VACATION

GRAPHIC SCALE


0 100 200 300

PARKMERCED PHASE 1A AND 1B STREET VACATIONS AND DEDICATIONS

SAN FRANCISCO SAN FRANCISCO COUNTY CALIFORNIA

BKF 255 SHORELINE DR SUITE 200 REDWOOD CITY, CA 94065 650-482-6300 650-482-6300 (FAX)

DATE: 11/11/11
 DRAWN BY: [Name]
 CHECKED BY: [Name]
 APPROVED BY: [Name]




VACATION PARCEL 2
(PHASE 1A - TENTATIVE MAP 8532)

7308

D=90°00'00"
L=34.56'
R=22.00'

SEE DETAIL

ARBALLO DRIVE
(51' WIDE)




ACEVEDO AVENUE
(51' WIDE)

7309

7310

 AREA TO BE VACATED
6 SQ.FT.±

EXISTING BOUNDARY



REFERENCES:

-BOOK "R", PAGES
15-19, AUG. 21, 1951

See Sheet 1  6/10/16
BRUCE R. STORRS
CITY AND COUNTY SURVEYOR

DATE

CITY AND COUNTY OF SAN FRANCISCO
DEPARTMENT OF PUBLIC WORKS

PROPOSED STREET VACATION OF ACEVEDO AVENUE AT THE NORTHWEST CORNER OF
THE INTERSECTION OF ACEVEDO AVENUE WITH ARBALLO DRIVE, FRONTING BLOCK 7308

FILE
SUR: 2015-006

SHEET 2 OF 10 SCALE 1"=50'

7310

SERRANO DRIVE
(67' WIDE)

TAPIA DRIVE
(51' WIDE)

VACATION PARCEL 3
(PHASE 1A - TENTATIVE MAP 8531)

S02°25'58"W

N02°25'52"E

5.150'

0.833'

D=36°30'30"
L=14.018'
R=22.000'


N87°34'02"W 401.012'

S87°34'02"E 387.924'

7335


Alex Calder

11-30-15




ARBALLO DRIVE
(51' WIDE)

SHEET LOCATION DETAIL
NOT TO SCALE



= AREA TO BE VACATED
352 SQ.FT.±

----- EXISTING BOUNDARY



REFERENCES:

-BOOK "R", PAGES
15-19, AUG. 21, 1951

CITY AND COUNTY OF SAN FRANCISCO
DEPARTMENT OF PUBLIC WORKS

PROPOSED STREET VACATION OF SERRANO DRIVE BETWEEN
ARBALLO DRIVE AND TAPIA DRIVE, FRONTING BLOCK 7335

See Sheet 1  *6/10/16*

BRUCE R. STORRS
CITY AND COUNTY SURVEYOR

DATE

FILE

SUR: 2015-006

SHEET 3 OF 10 SCALE 1"=50'

ARBALLO DRIVE
(51' WIDE)

7335

D=11'14'03"
L=4.314'
R=22.000'

VACATION PARCEL 4
(PHASE 1A - TENTATIVE MAP 8531)


S02°25'58"W
9.988'

N87°33'55"W 396.741'
S87°33'55"E 401.027'

N02°25'52"E
9.567'

GONZALEZ DRIVE
(67' WIDE)

RIVAS AVENUE
(51' WIDE)



7336

Alex Calder
11-30-15

LICENSED LAND SURVEYOR
ALEX CALDER
LLS 8863
STATE OF CALIFORNIA

= AREA TO BE VACATED
3,837 SQ.FT.±

----- EXISTING BOUNDARY

REFERENCES:

-BOOK "R", PAGES
15-19, AUG. 21, 1951

See Sheet 1
BRUCE R. STORRS
CITY AND COUNTY SURVEYOR


6/10/16
DATE

CITY AND COUNTY OF SAN FRANCISCO
DEPARTMENT OF PUBLIC WORKS

PROPOSED STREET VACATION OF GONZALEZ DRIVE BETWEEN
ARBALLO DRIVE AND RIVAS AVENUE, FRONTING BLOCK 7335

FILED
SUR: 2015-006

SHEET 4 OF 10 SCALE 1"=50'



= AREA TO BE VACATED
205 SQ.FT.±

----- EXISTING BOUNDARY

← GONZALEZ DRIVE
(67' WIDE)

CAMBON DRIVE
(65.5' WIDE)

FONT BOULEVARD
(112' WIDE)


S82°26'18"W
3.855'

52.318'
N07°33'42"W
54.157'
S07°33'42"E

VACATION PARCEL 5
(PHASE 1B - TENTATIVE MAP 8530)


D=11°08'28"
L=4.278'
R=22.000'

Alex Calder
11-30-15



7326

SHEET LOCATION DETAIL
NOT TO SCALE



REFERENCES:

-BOOK "R", PAGES
15-19, AUG. 21, 1951

See Sheet 1

BRUCE R. STORRS
CITY AND COUNTY SURVEYOR

R. Polidoro

DATE



CITY AND COUNTY OF SAN FRANCISCO
DEPARTMENT OF PUBLIC WORKS

PROPOSED STREET VACATION OF CAMBON DRIVE BETWEEN
FONT BOULEVARD AND GONZALEZ DRIVE, FRONTING BLOCK 7326

FILE
SUR: 2015-006

SHEET 5 OF 10

SCALE 1"=50'



Alex Calder
11-30-15

LICENSED LAND SURVEYOR
ALEX CALDER
LLS 8863
STATE OF CALIFORNIA

REFERENCES:
-BOOK "R", PAGES
15-19, AUG. 21, 1951

See Sheet 1 of 16

BRUCE R. STORRS
CITY AND COUNTY SURVEYOR

DATE

CITY AND COUNTY OF SAN FRANCISCO
DEPARTMENT OF PUBLIC WORKS

PROPOSED STREET VACATION OF FONT BOULEVARD BETWEEN
CAMBON DRIVE AND JUNIPERO SERRA BOULEVARD, FRONTING BLOCK 7326

FILE:
SUR: 2015-006

SHEET 6 OF 10 **SCALE 1"=60'**



D=45°00'00"
L=78.540'
R=100.00'

S37°26'12"W
37.764'

7370

N2°33'48"W
31.706'

N37°26'12"E
41.139'

7326
L7366

VACATION PARCEL 7
(PHASE 1B - TENTATIVE MAP 8530)

D=45°00'00"
L=78.540'
R=100.000'

LINE TABLE		
LINE	LENGTH	BEARING
L1	57.499'	S37°26'12"W
L2	40.498'	N37°26'12"E

CURVE TABLE			
CURVE	LENGTH	RADIUS	ANGLE
C1	12.101'	22.000'	31°30'55"
C2	41.834'	81.500'	29°24'36"
C3	3.009'	22.000'	7°50'15"
C4	18.624'	56.000'	19°03'17"
C5	6.283'	2.000'	180°00'00"
C6	19.954'	60.000'	19°03'17"
C7	17.158'	73.000'	13°28'02"


 = AREA TO BE VACATED
13,330 SQ.FT.±

--- EXISTING BOUNDARY


507°33'48"E 170.955'
61.349'
N07°33'48"W
42.609'
N37°26'12"E
CHUMASERO DRIVE
(51' WIDE)

7330

Alex Calder
11-30-15



SHEET LOCATION DETAIL
NOT TO SCALE



REFERENCES:

-BOOK "R", PAGES
15-19, AUG. 21, 1951



See Sheet 1
BRUCE R. STORRS
CITY AND COUNTY SURVEYOR
DATE *6/10/16*

CITY AND COUNTY OF SAN FRANCISCO
DEPARTMENT OF PUBLIC WORKS

PROPOSED STREET VACATION OF CHUMASERO DRIVE BETWEEN
FONT BOULEVARD AND BROTHERHOOD WAY, FRONTING BLOCK 7330 AND BLOCK 7370

FILE
SUR: 2015-006

SHEET 7 OF 10 SCALE 1"=50'



REFERENCES: -BOOK "R", PAGES 15-19, AUG. 21, 1951	See sheet 1 <i>6/10/16</i> BRUCE R. STORRS CITY AND COUNTY SURVEYOR	CITY AND COUNTY OF SAN FRANCISCO DEPARTMENT OF PUBLIC WORKS		
		PROPOSED STREET VACATION OF CHUMASERO DRIVE BETWEEN FONT BOULEVARD AND BROTHERHOOD WAY, FRONTING BLOCK 7330		
	DATE	FILE SUR: 2015-006	SHEET 8 OF 10	SCALE 1"=50'

GALINDO AVENUE
(67' WIDE)


7330

VACATION PARCEL 9
(PHASE 1B - TENTATIVE MAP 8530)

CHUMASERO DRIVE
(51' WIDE)


BROTHERHOOD WAY

Alex Calder
11-30-15



= AREA TO BE VACATED
9,792 SQ.FT.±

--- EXISTING BOUNDARY



CURVE TABLE			
CURVE	LENGTH	RADIUS	ANGLE
C1	51.561'	42.750'	69°06'15"
C2	14.186'	5.000'	162°33'15"
C3	47.298'	200.000'	13°33'00"
C4	11.118'	83.000'	7°40'29"
C5	72.346'	149.000'	27°49'10"
C6	64.577'	42.750'	86°33'00"

LINE TABLE		
LINE	LENGTH	BEARING
L1	11.852'	S46°15'12"W
L2	13.557'	N47°11'48"W
L3	55.544'	N23°32'41"E

REFERENCES:

-BOOK "R", PAGES
15-19, AUG. 21, 1951

See Sheet 1 *Q* 6/10/16

BRUCE R. STORRS
CITY AND COUNTY SURVEYOR

DATE

CITY AND COUNTY OF SAN FRANCISCO
DEPARTMENT OF PUBLIC WORKS


PROPOSED STREET VACATION OF CHUMASERO DRIVE BETWEEN
BROTHERHOOD WAY AND FONT BOULEVARD, FRONTING BLOCK 7330

JR: 2015-006


SHEET 9 OF 10

SC/

"=50'



LINE TABLE		
LINE	LENGTH	BEARING
L1	45.500'	N37°26'12"E
L2	3.660'	N37°26'12"E



Alex Calder
11-30-15

LICENSED LAND SURVEYOR
ALEX. CALDER
LLS 8863
STATE OF CALIFORNIA

REFERENCES:
-BOOK "R", PAGES
15-19, AUG. 21, 1951

See Sheet I *[Signature]* 6/10/16
BRUCE R. STORRS
CITY AND COUNTY SURVEYOR

DATE

CITY AND COUNTY OF SAN FRANCISCO
DEPARTMENT OF PUBLIC WORKS

PROPOSED STREET VACATION OF FONT BOULEVARD BETWEEN CHUMASERO DRIVE AND JUNIPERO SERRA BOULEVARD, FRONTING BLOCK 7326, BLOCK 7330 AND BLOCK 7366

FILE SUP: 2015-006

SHEET 10 OF 10 SCALE 1"=50'

SHEET 1

VIDAL DRIVE

7308

SHEET 2

7310

ACEVEDO AVENUE

7309

HIGUERA AVENUE

7334

SHEET 4

7338

GARCÉS DRIVE

7337

7338

VIDAL DRIVE

7333

BROTHERHOOD WAY

SHEET 3

7335

GONZALEZ DRIVE

7339

RIVAS AVENUE

7340

GRUJANA DRIVE

7341

GARCÉS DRIVE

7342

7343

JOSEPIA AVENUE

7344

7345

DIAZ AVENUE

7322

7321

CRESTI DRIVE

7319

CARDENAS AVENUE

7316

SERRANO DRIVE

7317

7318

HOLLOWAY AVENUE

7315

VARELA AVENUE

GONZALEZ DRIVE

SHEET 5

7323

GONZALEZ DRIVE

7325

FONT BOULEVARD

SHEET 6

7326

SHEET 7

7330

SHEET 8

SHEET 9

SHEET 10


JURRERO BOULEVARD

CHUMASERO DRIVE

PHASE	VACATION PARCEL I.D.	Area SQ.FT.
1A--TENTATIVE MAP. 8531 & 8532	PARCEL 1	9,466
	PARCEL 2	6
	PARCEL 3	352
	PARCEL 4	3,837
1B--TENTATIVE MAP 8530	PARCEL 5	205
	PARCEL 6	6,932
	PARCEL 7	13,330
	PARCEL 8	8,999
	PARCEL 9	9,792
	PARCEL 10	21,802
1A AND 1B	TOTAL	74,721



Alex Calder
11-30-15



**PARKMERCED
PHASE 1A & 1B
VACATIONS
KEY MAP SHEET**

**PHASE - 1A (TENTATIVE MAP 8532 - BLOCK 1)
PHASE - 1A (TENTATIVE MAP 8531 - BLOCK 6)
PHASE - 1B (TENTATIVE MAP 8530 -
BLOCKS 20, 21 AND 22)**

SHEET 1 OF 1

SCALE 1"=500'

87

Date: 03/20/2015



Department of City Planning
1650 Mission Street, Suite 400
San Francisco, CA 94103

TENTATIVE MAP DECISION

Edwin M. Lee
Mayor

Mohammed Nuru
Director

Jerry Sanguinetti
Bureau of Street Use & Mapping
Manager

Project ID:	8530		
Project Type:	7 development lots, one airspace lot, three open space lots, three transit lots, one private street lot and realignment of existing public streets.		
Address #	Street Names	Blocks	Lot
Various	Junipero Serra Blvd, Brotherhood Way, Font Drive, Chumaseo Drive and Cambon Drive	7326, 7330, 7331, 7364, 7365, 7366 and 7370	001
Tentative Map Referral			

Bruce R. Storrs P.L.S.
City and County Surveyor

Bureau of Street Use & Mapping
1155 Market St., 3rd floor
San Francisco, CA 94103
tel (415) 554-5827
Subdivision.Mapping@sfdpw.org

sfpublicworks.org
facebook.com/sfpublicworks
twitter.com/sfpublicworks

Attention: Scott F. Sanchez

- The subject Tentative Map has been reviewed by the Planning Department and does comply with applicable provisions of the Planning Code. The Tentative Subdivision Map (Map) is within the scope of the Final Environmental Impact Report for Parkmerced Mixed-Use Development Program (FEIR) prepared pursuant to the California Environmental Quality Act, which was certified by the San Francisco Planning Commission on February 10, 2011 by Motion No. 18269 and approved on June 9, 2011, by the Board of Supervisors in Ordinance No. 0089-11, Development Agreement - Parkmerced. On balance, the Tentative Map, including proposed street vacations, dedications and CCSF acceptance of the same is consistent with the General Plan and the Priority Policies of Planning Code Section 101.1 based on the attached findings.

- The subject Tentative Map has been reviewed by the Planning Department and does comply with applicable provisions of the Planning Code subject to the following conditions:

See Attached

- The subject Tentative Map has been reviewed by the Planning Department and does not comply with applicable provisions of the Planning Code. Due to the following reasons:

[Empty box for reasons]

PLANNING DEPARTMENT

Signed  Digitally signed by Joshua Switzky
DN: c=org, o=sf.gov, ou=cityplanning,
ou=CityPlanning, ou=CityWide Policy, cn=Joshua
Switzky, email=joshua.switzky@sfgov.org
Date: 2015.08.03 09:51:16 -0700

Date **August 3, 2015**

Planner's Name **Joshua Switzky**

For Scott F. Sanchez, Zoning Administrator
Enclosures: Application and Tentative Map

Date: 03/20/2015



Department of City Planning
1650 Mission Street, Suite 400
San Francisco, CA 94103

TENTATIVE MAP DECISION

Edwin M. Lee
Mayor

Mohammed Nuru
Director

Jerry Sanguinetti
Bureau of Street Use & Mapping
Manager

Bruce R. Storrs P.L.S.
City and County Surveyor

Bureau of Street Use & Mapping
1155 Market St., 3rd floor
San Francisco, CA 94103
tel (415) 554-5827
Subdivision.Mapping@sfdpw.org

sfpublicworks.org
facebook.com/sfpublicworks
twitter.com/sfpublicworks

Project ID:	8531		
Project Type:	4 development lots, one airspace lot, two open space lots and realignment of existing public streets.		
Address #	Street Names	Block	Lot
Various	Arballo Drive, Gonzalez Drive and Serrano Drive	7335	001
Tentative Map Referral			

Attention: Scott F. Sanchez


The subject Tentative Map has been reviewed by the Planning Department and does comply with applicable provisions of the Planning Code. The Tentative Subdivision Map (Map) is within the scope of the Final Environmental Impact Report for Parkmerced Mixed-Use Development Program (FEIR) prepared pursuant to the California Environmental Quality Act, which was certified by the San Francisco Planning Commission on February 10, 2011 by Motion No. 18269 and approved on June 9, 2011, by the Board of Supervisors in Ordinance No. 0089-11, Development Agreement - Parkmerced. On balance, the Tentative Map, including proposed street vacations, dedications and CCSF acceptance of the same is consistent with the General Plan and the Priority Policies of Planning Code Section 101.1 based on the attached findings.

The subject Tentative Map has been reviewed by the Planning Department and does comply with applicable provisions of the Planning Code subject to the following conditions:

See Attached

The subject Tentative Map has been reviewed by the Planning Department and does not comply with applicable provisions of the Planning Code. Due to the following reasons:

PLANNING DEPARTMENT

Signed  Digitally signed by Joshua Switzky
DN: dc=org, dc=sfgov, dc=cityplanning,
ou=CityPlanning, ou=CityWide Policy, cn=Joshua
Switzky, email=joshua.switzky@sfgov.org
Date: 2015.08.03 09:52:11 -0700

Date **August 3, 2015**

Planner's Name **Joshua Switzky**

For Scott F. Sanchez, Zoning Administrator
Enclosures: Application and Tentative Map



Department of City Planning
 1650 Mission Street, Suite 400
 San Francisco, CA 94103

TENTATIVE MAP DECISION

Edwin M. Lee
 Mayor

Mohammed Nuru
 Director

Jerry Sanguinetti
 Bureau of Street Use & Mapping
 Manager

Bruce R. Storrs P.L.S.
 City and County Surveyor

Bureau of Street Use & Mapping
 1155 Market St., 3rd floor
 San Francisco, CA 94103
 tel (415) 554-5827
 Subdivision.Mapping@sfdpw.org

sfpublicworks.org
 facebook.com/sfpublicworks
 twitter.com/sfpublicworks

Project ID:	8532		
Project Type:	4-lot subdivision with condominium units, private street, and realignment of public streets		
Address #	Street Name	Block	Lot
310 - 350	Arballo Drive	7308	001
Tentative Map Referral			

Attention: Scott F. Sanchez

The subject Tentative Map has been reviewed by the Planning Department and does comply with applicable provisions of the Planning Code. The Tentative Subdivision Map (Map) is within the scope of the Final Environmental Impact Report for Parkmerced Mixed-Use Development Program (FEIR) prepared pursuant to the California Environmental Quality Act, which was certified by the San Francisco Planning Commission on February 10, 2011 by Motion No. 18269 and approved on June 9, 2011, by the Board of Supervisors in Ordinance No. 0089-11, Development Agreement - Parkmerced. On balance, the Tentative Map, including proposed street vacations, dedications and CCSF acceptance of the same is consistent with the General Plan and the Priority Policies of Planning Code Section 101.1 based on the attached findings.

The subject Tentative Map has been reviewed by the Planning Department and does comply with applicable provisions of the Planning Code subject to the following conditions:

See Attached

The subject Tentative Map has been reviewed by the Planning Department and does not comply with applicable provisions of the Planning Code. Due to the following reasons:

[Empty box for reasons]

PLANNING DEPARTMENT

Signed  Digitally signed by Joshua Switzky
 DN: cn=org, dc=sfgov, dc=cityplanning,
 ou=CityPlanning, ou=CityWide Policy, cn=Joshua
 Switzky, email=joshua.switzky@sfgov.org
 Date: 2015.08.03 09:52:57 -0700

Date **August 3, 2015**

Planner's Name **Joshua Switzky**

For Scott F. Sanchez, Zoning Administrator
 Enclosures: Application and Tentative Map



SAN FRANCISCO PLANNING DEPARTMENT

Date: August 4, 2015
To: Department of Public Works, Paul Mabry
From: Joshua Switzky, Planning Department
Re: Conditions of Approval
Parkmerced Project Subphases 1A and 1B
Tentative Maps 8530, 8531, and 8532

1650 Mission St.
Suite 400
San Francisco,
CA 94103-2479

Reception:
415.558.6378

Fax:
415.558.6409

Planning
Information:
415.558.6377

The Planning Department approves the Tentative Subdivision Maps for the Parkmerced Project Subphases 1A and 1B as submitted subject to the below conditions. Attached to this are findings of General Plan consistency and CEQA compliance.

Condition #1:

For PID 8530, 8531 and 8532, Private street parcels, as shown on the Tentative Map shall be modified to include abutting sidewalk improvements that are currently shown as part of the development lot(s). The development lots may be adjusted to accomplish this requirement, but no additional public right-of-way or right-of-way proposed to be public right-of-way shall be required to accommodate this modification of the private lots. The Subdivider shall provide written proof to the Director of Public Works, prior to the earlier of either application of any Street Improvement Permit or Final Map Checkprint, that the Planning Department has reviewed and approved any revisions that will appear on a Final Map and that any other affected city agency has also reviewed and approved the proposed changes.

Condition #2:

For PID 8530, The design of Font Blvd adjacent to Block 21 is not sufficiently advanced to approve without reservation. Additional review shall be required after sufficiently detailed engineered design has been presented to meet the concerns of affected city agencies such as but not limited to Planning, SFMTA, and SF Fire Department. Additional dedication of street right-of-way may be required in compliance with this Tentative Map, but in no case shall a Final Map result in less public right-of-way being offered for dedication.



SAN FRANCISCO PLANNING DEPARTMENT

Date: August 4, 2015
To: Department of Public Works, Paul Mabry
From: Joshua Switzky, Planning Department
Re: Determination of General Plan Compliance
Parkmerced Project Subphases 1A and 1B
Tentative Maps 8530, 8531, and 8532

1650 Mission St.
Suite 400
San Francisco,
CA 94103-2479

Reception:
415.558.6378

Fax:
415.558.6409

Planning
Information:
415.558.6377

On June 7, 2011, at a duly noticed public hearing, the San Francisco Board of Supervisors adopted Ordinance No. 89-11, approving a Development Agreement for the Parkmerced Mixed-Use Development Project (the "Project") and authorizing the Planning Director to execute the Development Agreement on behalf of the City (the "Enacting Ordinance"). The Enacting Ordinance took effect on July 9, 2011. The following land use approvals, entitlements, and permits relating to the Project were approved by the Board of Supervisors concurrently with the Development Agreement: the General Plan amendment (Board of Supervisors Ord. No. 92-11), the Planning Code text amendment (Board of Supervisors Ord. No. 90-11), the Zoning Map amendments (Board of Supervisors Ord. No. 91-11), the Coastal Zone Permit (Planning Commission Resolution Motion No. 19272); Board of Supervisors Ord. No. 89-11), and the Parkmerced Plan Documents (collectively, the "Project Approvals").

On June 7, 2011, at the same duly noticed public hearing, incorporating by reference and adopting General Plan consistency findings adopted by the San Francisco Planning Commission on February 10, 2011 (attached hereto), the Board of Supervisors determined that the Project as defined in the Development Agreement and the Project Approvals were, as a whole and taken in their entirety, consistent with the objectives, policies, general land uses and programs specified in the General Plan and the Planning Principles set forth in Section 101.1 of the Planning Code (together, the "General Plan Consistency Findings").

Pursuant to Recital H of the Development Agreement and incorporating the General Plan Consistency Findings by reference, the Planning Department hereby finds that the proposed Tentative Subdivision Maps 8530, 8531, and 8532 are consistent with the Project as defined in the Development Agreement and the Project Approvals, and that each map is, on balance, consistent with the following Objectives and Policies of the General Plan and the Priority Policies of Planning Code Section 101.1, pursuant to the General Plan Consistency Findings.



SAN FRANCISCO PLANNING DEPARTMENT

Date: August 4, 2015
To: Department of Public Works, Paul Mabry
From: Joshua Switzky, Planning Department
Re: Determination of Compliance with CEQA
Parkmerced Project Subphases 1A and 1B
Tentative Maps 8530, 8531, and 8532

1650 Mission St.
Suite 400
San Francisco,
CA 94103-2479

Reception:
415.558.6378

Fax:
415.558.6409

Planning
Information:
415.558.6377

On February 10, 2011, at a duly noticed public hearing, the Planning Commission certified the Final Environmental Impact Report ("Final EIR") for the Parkmerced Mixed-Use Development Project (the "Project"), by Motion No. 18269, finding that the Final EIR reflects the independent judgment and analysis of the City and County of San Francisco, is adequate, accurate and objective, contains no significant revisions to the Draft EIR, and the content of the report and the procedures through which the Final EIR was prepared, publicized and reviewed comply with the provisions of the California Environmental Quality Act (California Public Resources Code Section 21000 et seq., "CEQA"), the State CEQA Guidelines (California Code of Regulations Title 14 Section 15000 et seq.), and Chapter 31 of the San Francisco Administrative Code ("Chapter 31").

At the same hearing during which the Planning Commission certified the Final EIR, the Planning Commission adopted findings, as required by CEQA, regarding the alternatives, mitigation measures, and significant environmental effects analyzed in the Final EIR, a statement of overriding considerations for approval of the Project, and a proposed mitigation monitoring and reporting program (collectively, "CEQA Findings", attached hereto).

On June 7, 2011, at a duly noticed public hearing, the San Francisco Board of Supervisors reviewed and considered the Final EIR and the CEQA Findings. The Board of Supervisors adopted the Planning Commission's CEQA Findings as its own and incorporated them by reference. The Board of Supervisors approved and endorsed the implementation of the mitigation measures for implementation by other City departments and recommended for adoption those mitigation measures that are enforceable by agencies other than City departments.

In addition to the Final Environmental Impact Report, approval of the Project involved amendments to the City's General Plan, Zoning Map, and Planning Code, as well as approval of a Development Agreement (San Francisco Board of Supervisors in

Ordinance No. 0089-11) (the "Development Agreement") (collectively, the "Project Approvals").

The subject Tentative Map has been reviewed by the Planning Department and does comply with applicable provisions of the Planning Code and is consistent with the Project as defined in the Development Agreement and the Project Approvals. The subject Tentative Map implements the anticipated development of the subject property vested by the Project Approvals, including the construction of buildings and streets consistent with the Parkmerced Design Standards and Guidelines, the Parkmerced Transportation Plan, and the Parkmerced Infrastructure Plan. The CEQA Findings attached hereto are hereby incorporated by reference. The Planning Department finds that the proposed actions before the Department are consistent with and within the scope of the Project analyzed in the FEIR and subject to the CEQA Findings.

Pursuant to CEQA Guidelines Section 15162, the Planning Department finds that the proposed actions before the Department are consistent with and within the scope of the Project analyzed in the FEIR and (1) that no substantial changes are proposed in the Project and no substantial changes have occurred with respect to the circumstances under which this Project will be undertaken that would require major revisions to the FEIR due to the involvement of any new significant environmental effects or a substantial increase in the severity of previously identified effects and (2) no new information that was not known and could not have been known shows that the project will have any new significant effects not analyzed in the FEIR or a substantial increase in the severity of any effect analyzed or that new mitigation measures should be included that have not. The Department further finds that an addendum to the FEIR is not required due to any changes in the Project or the Project's circumstances.



SAN FRANCISCO PLANNING DEPARTMENT

Planning Commission Resolution No. 18271

Planning Code Text Amendment, Zoning Map Amendment, and General Plan Amendment

HEARING DATE: FEBRUARY 10, 2011

1650 Mission St.
Suite 400
San Francisco,
CA 94103-2479

Reception:
415.558.6378

Fax:
415.558.6409

Planning
Information:
415.558.6377

Project Name: Parkmerced Mixed-Use Development Program
 T Case: Add Section 249.64; Amend Sections 102.5, 201, and 270
 Z Case: Rezone the Subject Property
 M Case: Amend the General Plan Urban Design Element Map 4

Case Number: 2008.0021EPMTZW

Initiated by: Seth Maller, Parkmerced Investors, LLC
 3711 – 19th Avenue
 San Francisco, CA 94132

Staff Contact: Elizabeth Watty, Planner
Elizabeth.Watty@sfgov.org, 415-558-6620

Reviewed By: David Alumbaugh, Acting Director Citywide Planning
David.Alumbaugh@sfgov.org, 415-558-6601

90-Day Deadline: N/A – Sponsor Initiated

Recommendation: Recommend Approval

RECOMMENDING THAT THE BOARD OF SUPERVISORS ADOPT AN ORDINANCE THAT WOULD (1) AMEND THE SAN FRANCISCO PLANNING CODE TEXT TO CREATE PLANNING CODE SECTION 249.64, THE "PARKMERCED SPECIAL USE DISTRICT" (PMSUD), AMEND PLANNING CODE SECTION 270 TO CREATE A NEW BULK DISTRICT ("PM") FOR THE PROPOSED PARKMERCED SPECIAL USE DISTRICT, AMEND PLANNING CODE SECTION 102.5 AND 201 TO INCLUDE THE PARKMERCED ZONING DISTRICTS; (2) AMEND THE PLANNING CODE ZONING MAP SHEETS ZN13, HT13, AND SU13 TO RECLASSIFY PARKMERCED, BEING ALL OF ASSESSOR'S BLOCKS 7303-001, 7303-A-001, 7308-001, 7309-001, 7309-A-001, 7310-001, 7311-001, 7315-001, 7316-001, 7317-001, 7318-001, 7319-001, 7320-003, 7321-001, 7322-001, 7323-001, 7325-001, 7326-001, 7330-001, 7331-004, 7332-004, 7333-001, 7333-003, 7333-A-001, 7333-B-001, 7333-C-001, 7333-D-001, 7333-E-001, 7334-001, 7335-001, 7336-001, 7337-001, 7338-001, 7339-001, 7340-001, 7341-001, 7342-001, 7343-001, 7344-001, 7345-001, 7345-A-001, 7345-B-001, 7345-C-001, 7356-001, 7357-001, 7358-001, 7359-001, 7360-001, 7361-001, 7362-001, 7363-001, 7364-001, 7365-001, 7366-001, 7367-001, 7368-001, 7369-001, AND 7370-001 FROM RM-1 (RESIDENTIAL MIXED, LOW DENSITY), RM-4 (RESIDENTIAL MIXED, HIGH DENSITY), & RH-1(D) (RESIDENTIAL HOUSE, ONE-FAMILY, DETACHED) DISTRICTS, TO PM [PARKMERCED RESIDENTIAL (PM-R), PARKMERCED MIXED USE – SOCIAL HEART (PM-MU1), PARKMERCED MIXED USE – NEIGHBORHOOD COMMONS (PM-MU2), PARKMERCED SCHOOL (PM-S), PARKMERCED COMMUNITY/FITNESS (PM-CF), AND PARKMERCED OPEN SPACE (PM-OS)], AND TO MAKE CONFORMING MAP AMENDMENTS TO FACILITATE THE LONG-RANGE DEVELOPMENT PLANS OUTLINED IN THE PARKMERCED MIXED-USE

Hearing Date: February 10, 2011

Parkmerced Mixed-Use Development Program

DEVELOPMENT PROGRAM; (3) AMEND THE SAN FRANCISCO GENERAL PLAN URBAN DESIGN ELEMENT MAP 4 TO MAKE CONFORMING MAP AMENEDMENTS; (4) ADOPT A RESOLUTION URGING THE CALIFORNIA COASTAL COMMISSION TO AMEND THE LOCAL COASTAL PROGRAM TO INCORPORATE THE AMENDMENTS HEREIN; AND (5) MAKE AND ADOPT FINDINGS, INCLUDING ENVIRONMENTAL FINDINGS AND FINDINGS OF CONSISTENCY WITH THE GENERAL PLAN AND THE EIGHT PRIORITY POLICIES OF PLANNING CODE SECTION 101.1.

PREAMBLE

On January 8, 2008, Seth Mallen of Steller Management (hereinafter "Project Sponsor"), submitted an Environmental Evaluation Application with the Planning Department (hereinafter "Department"), Case No. 2008.0021E; and

On May 12, 2010, the Draft Environmental Impact Report (DEIR) for the Project was prepared and published for public review; and

The Draft EIR was available for public comment until July 12, 2010; and

On February 10, 2011, the San Francisco Planning Commission (hereinafter "Commission") reviewed and considered the Final Environmental EIR (FEIR) and found that the contents of said report and the procedures through which the FEIR was prepared, publicized, and reviewed complied with the California Environmental Quality Act (California Public Resources Code Sections 21000 et seq.) (CEQA), 14 California Code of Regulations Sections 15000 et seq. (the "CEQA Guidelines") and Chapter 31 of the San Francisco Administrative Code ("Chapter 31"); and

On February 10, 2011, the Commission: certified the FEIR by Motion No. 18629, adopted approval findings pursuant to CEQA by Motion No. 18270 (Exhibit A); and adopted the Mitigation, Monitoring, and Reporting Program (MMRP) (Exhibit B to Motion No. 18270). The CEQA approval findings and the MMRP (Exhibits A and B, respectively, to Motion No. 18270) are incorporated herein by this reference thereto as if fully set forth in this Motion; and

On August 12, 2010, the Project Sponsor applied to the Planning Department for a Planning Code Text Amendment, a Zoning Reclassification and a General Plan Amendment (hereinafter Map Amendments) to allow for the creation and implementation of the Parkmerced Special Use District under Case No. 2008.0021MTZ; and

The proposed General Plan Amendments would make conforming amendments to the Urban Design Element's Map 4 to reflect the proposed rezoning; and

The proposed Zoning Reclassification would amend Zoning Map Sheets ZN13, HT13, and SU13 to rezone Parkmerced, being all of Assessor's blocks 7303-001, 7303-A-001, 7308-001, 7309-001, 7309-A-001, 7310-001, 7311-001, 7315-001, 7316-001, 7317-001, 7318-001, 7319-001, 7320-003, 7321-001, 7322-001, 7323-001, 7325-001, 7326-001, 7330-001, 7331-004, 7332-004, 7333-001, 7333-003, 7333-A-001, 7333-B-001, 7333-C-001, 7333-D-001, 7333-E-001, 7334-001, 7335-001, 7336-001, 7337-001, 7338-001, 7339-001, 7340-001, 7341-001, 7342-

Hearing Date: February 10, 2011

Parkmerced Mixed-Use Development Program

001, 7343-001, 7344-001, 7345-001, 7345-A-001, 7345-B-001, 7345-C-001, 7356-001, 7357-001, 7358-001, 7359-001, 7360-001, 7361-001, 7362-001, 7363-001, 7364-001, 7365-001, 7366-001, 7367-001, 7368-001, 7369-001, and 7370-001 from RM-1 (Residential Mixed, Low Density), RM-4 (Residential Mixed, High Density), & RH-1(D) (Residential House, One-Family, Detached) Districts, to PM [Parkmerced Residential (PM-R), Parkmerced Mixed Use – Social Heart (PM-MU1), Parkmerced Mixed Use – Neighborhood Commons (PM-MU2), Parkmerced School (PM-S), Parkmerced Community/Fitness (PM-CF), and Parkmerced Open Space (PM-OS) (hereinafter “Parkmerced Zoning Districts”)]; and

The proposed Planning Code Text Amendments would create Planning Code Section 249.64, the “Parkmerced Special Use District” (hereinafter “PMSUD”), amend Planning Code Section 270 to create a new Bulk District (PM) for the proposed Parkmerced Special Use District, and amend Planning Code Section 102.5 and 201 to include the Parkmerced Zoning Districts; and

On October 27, 2010 the Project Sponsor filed a Development Agreement Application after months of negotiations with the Mayor’s Office of Workforce and Economic Development; and

The Commission conducted informational hearings on the Parkmerced Project and considered public comment on November 4, November 18, December 9, December 16, 2010, and on January 13, 2011; and

On January 10, 2011, the Project Sponsor filed a Coastal Zone Permit Application, to authorize the rezoning and development of Assessor’s Blocks 7309, 7309-A, 7334, 7333, portions of which are located within the Local Coastal Zone Permit Area; and

On January 13, 2011, the Commission passed Resolution No. 18255, initiating amendments to the Planning Code, Zoning Maps, and General Plan related to the proposed Project; and

On February 10, 2011, the Commission conducted a duly noticed public hearing at a regularly scheduled meeting to consider the proposed Ordinances; and

Whereas, the Commission has heard and considered the testimony presented to it at the public hearing and has further considered written materials and oral testimony presented by Department staff, and other interested parties; and

All pertinent documents associated with Case No. 2008.0021EPMTZW may be found in the files of the Department, as the custodian of records, at 1650 Mission Street, Fourth Floor, San Francisco, California; and

Whereas, the Commission has reviewed the proposed Ordinances; and

MOVED, that the Commission hereby recommends that the Board of Supervisors approve the proposed Ordinances, following execution of the Development Agreement, and adopt the attached Resolution to that effect, and,

MOVED, that the Commission hereby recommends that the Board of Supervisors request amendment of the Local Coastal Program to the California Coastal Commission to reflect the adoption of these

Hearing Date: February 10, 2011

Parkmerced Mixed-Use Development Program

Ordinances and the findings herein, and further request that such amendment of the Local Coastal Program will become effective immediately upon approval by the California Coastal Commission, without further action required by the City and County of San Francisco.

MOVED, that the Commission hereby recommends that the Board of Supervisors approve both the *Connect Cambon to 19th Avenue* project variant (as described in Appendix B of the Parkmerced Design Standards + Guidelines) and the Project, with a condition placed on the Project Variant that the vehicularized Diaz Avenue, between Cambon and Gonzalez Drives, retain the strong pedestrian connection to the Diaz pedestrian plaza, reinforced in part by the elimination of the on-street parking and the widening of the sidewalks on this block.

FINDINGS

Having reviewed the materials identified in the preamble above, and having heard all testimony and arguments, this Commission finds, concludes, and determines as follows:

The Commission finds the Parkmerced Mixed-Use Development Program to be a beneficial development to the City that could not be accommodated without the actions requested.

1. Parkmerced was constructed in the 1940s and early 1950s based on a model of separation of land uses, extensive reliance on the automobile for all purposes, and an insular circulation system featuring few connections to the wider city context. These patterns of development have proven to be unsustainable and exacerbate local and regional problems of transportation, air quality, and energy consumption and embody characteristics that do not meet the needs of today and the future to support sustainable growth.
2. Assembly Bill 32 set statewide goals for greenhouse gas reductions and Senate Bill 375 further requires local regions and municipalities to coordinate land use and transportation plans to reduce greenhouse gas emissions. In the Bay Area, according to the Bay Area Air Quality Management District, 40% of greenhouse gas emissions come from transportation, primarily private vehicle travel. The average Bay Area household drives 18,000 miles per year. Low residential density and lack of mixed uses that prevent trips from being effectively served by public transit or made by walking or bicycling are the primary reasons for high Vehicle Miles Travelled (VMT) for Bay Area households. Regional growth will occur, and it is the duty of every Bay Area city to direct growth to infill areas that are supported by necessary services and well-served by public transportation and that do not expand the footprint of existing urbanized areas.
3. The proposed infill Project density of 59 units per acre, incorporation of neighborhood-serving retail into a neighborhood center, and retrofitting of the block pattern to reduce block size, is more typical of San Francisco neighborhoods with low VMT. Based on consistent data from similar neighborhoods locally and throughout the country, the VMT of households in such a neighborhood is expected to be less than 10,000 miles per year.
4. Parkmerced is already well situated with regard to public transit infrastructure, as it sits adjacent to MUNI light rail service on 19th Avenue, is served by several MUNI bus lines, and is close to the Daly City BART station. It is currently substantially underbuilt based on existing zoning. It is one

of the best situated areas on the west side of the City to absorb growth in a transit-oriented and sustainable fashion, and its ownership under a single entity provides a rare opportunity to consider a long-term master plan for reconfiguration and improvement to meet the needs of the 21st-century and beyond.

5. The proposed transportation investments as part of the Project, including MUNI rail re-alignment through the Project Site, would further improve service to the area and provide more operational options to the San Francisco Metropolitan Transit Authority (hereinafter, "SFMTA"). The proposal has been well-coordinated with SFMTA, paves the way and provides a down-payment for more long-term "Tier 5" options, and the Development Agreement paves the way for evaluating and incorporating additional Tier 5 options by the City. Without this Project, the City may not be able to achieve the necessary transportation improvements in the 19th Avenue corridor.
6. The existing Parkmerced landscape is resource consumptive in its expansive use of manicured mono-cultural lawns, and the original neighborhood and landscape design directly disrupted and degraded ecological functions, particularly by diverting rainwater flow away from the underground aquifer and Lake Merced. The proposed Parkmerced Mixed-Use Development Program will result in a landscape that is both environmentally and financially sustainable and restores degraded systems. Improvements include creation of a system of bioswales and cisterns to direct stormwater into a restored creek corridor feeding into Lake Merced and/or the underlying groundwater basin. In addition, the proposed Parkmerced Mixed-Use Development Program will result in the generation of 20% of the total estimated annual energy consumed by the Project, through the installation of renewable energy sources (such as photovoltaic cells and wind turbines) and cogeneration facilities.
7. The existing neighborhood, while giving the impression of expansive open space, has little usable public open space. Its publicly-accessible green spaces are primarily comprised of snippets and in-between spaces such as roadway medians, building setbacks and undefined planted areas separating towers. The proposed Project would re-design the open space system to create distinct public open spaces in the form of both a larger connected network of major public open spaces, including a creek corridor, athletic fields, and farm (which the Project Sponsor proposes to develop as organic and which may be managed by a professional farmer), as well as smaller dispersed neighborhood parks activated by adjacent community uses and small-scale retail.
8. The Parkmerced Mixed-Use Development Program would result in increased rental and for-sale housing of various sizes and income levels, and would provide a great diversity of housing types to meet the needs of a broad spectrum of household types. The proposal would provide a broader range of building and unit types than exist today. Whereas 7% of current units have three bedrooms, the proposed Project would include 15% 3-bedroom units. While today over 52% of existing units are in the 13-story towers, upon full build-out, fewer than 35% of all units will be in towers of 11-14 stories.
9. Under the terms of the proposed Development Agreement, the Project would replace, on a one-for-one basis, the 1,538 existing units subject to the City's Residential Rent Stabilization and Arbitration Ordinance (hereinafter, "Rent Stabilization Ordinance") that would be demolished as part of the proposed Project with 1,538 "replacement units" of comparable size in newly constructed buildings. All existing tenants in these to-be-demolished units would be offered a

replacement unit of comparable size at their existing rents, all relocation expenses would be paid for by the Project Sponsor, and, under the terms of the proposed Development Agreement, the replacement unit would be subject to the provisions of the Rent Stabilization Ordinance for the life of the building. Replacement units in the new buildings would be chosen by existing tenants on a seniority basis. To the extent that any of the 1,538 replacement units are not occupied by an existing tenant who has elected to relocate, the replacement unit will be made available to a new tenant and will also be subject to the provisions of the Rent Stabilization Ordinance for the life of the building. The Project Sponsor will pay relocation expenses to existing tenants who choose not to relocate into a replacement unit.

10. The Parkmerced Mixed-Use Development Program would result in an entire neighborhood completely built in conformity with the City's recently-adopted Better Streets Plan, providing an excellent pedestrian environment.
11. The Parkmerced Mixed-Use Development Program would result in numerous public improvements to the intersections adjacent to and surrounding Parkmerced, providing circulation benefits not just for Parkmerced but for the wider community.
12. The Parkmerced Mixed-Use Development Program would create a social heart for the community, and would create a traditional pedestrian-oriented neighborhood commercial district within close walking distance of all Parkmerced residents. The proposed Parkmerced Mixed-Use Development Program would result in 1,500 permanent jobs.
13. The proposed Project includes a comprehensive program for environmental sustainability, seeking to minimize any growth in water or energy use, to accommodate new growth by constructing infrastructure in a manner that will allow connection to future recycled water supplies, and by committing to invest in renewable energy infrastructure and efficiency measures that are above and beyond existing requirements.
14. The Parkmerced Mixed-Use Development Program establishes a detailed design review process for buildings and community improvements.
15. The Planning Code Text Amendments, Zoning Reclassifications, and General Plan Map Amendment are necessary in order to approve the Parkmerced Mixed-Use Development Program.

- 1. **General Plan Compliance.** The proposed Ordinance is, on balance, consistent with the following Objectives and Policies of the General Plan:

HOUSING ELEMENT (2004 PER WRIT)

Objectives and Policies

OBJECTIVE 1:

TO PROVIDE NEW HOUSING, ESPECIALLY PERMANENTLY AFFORDABLE HOUSING, IN APPROPRIATE LOCATIONS WHICH MEETS IDENTIFIED HOUSING NEEDS AND TAKES INTO ACCOUNT THE DEMAND FOR AFFORDABLE HOUSING CREATED BY EMPLOYMENT DEMAND.

Policy 1.4

Locate in-fill housing on appropriate sites in established residential neighborhoods.

San Francisco is expected to provide 68,000 new by 2035, in order to meet the Association of Bay Area Governments' (ABAG) projections for San Francisco's projected population growth¹. The Parkmerced Mixed-Use Development Project will help provide approximately 8% of the City's total housing goals, with a total of 5,679 new units at full Project build-out, over the next 20-30 years.

Parkmerced is currently accessible by public transit and located within an established residential neighborhood. One of the shortcomings of the existing residential neighborhood is that it does not have convenient non-vehicular access to neighborhood-serving amenities. As a result of this Project, neighborhood-serving amenities will be built, and there will be improved pedestrian and bicycle access to those amenities.

The Project will create transit infrastructure improvements, in addition to the bicycle and pedestrian improvements. Two new light rail transit stops will be added, and one light rail stop relocated to a more convenient and safer location, within the Parkmerced Site. Since proximity to transit does influence rates of auto ownership and the need for parking, locating 5,679 net new units at Parkmerced supports the City's transit first policy, which discourages car dependency.

OBJECTIVE 2:

RETAIN THE EXISTING SUPPLY OF HOUSING

Policy 2.3

Restrict the conversion of rental housing to other forms of tenure or occupancy.

¹ This number represents a recent update ABAG made to recognize the recession of 2008. Although these updated numbers have not yet been formally adopted and thus are not the "official" ABAG Projections, they are found to be more accurate based on the City and ABAG's analyses, and their use is consistent with ABAGs current regional planning work and development of the Sustainable Communities Strategy.

Existing housing stock is the City's major source of relatively affordable housing. Although it is typically difficult to replace given the cost of new construction, the Parkmerced Mixed-Use Development Program will include replacement housing for all demolished units and will provide such replacement housing to existing tenants at their current rent. Furthermore, the Parkmerced Mixed-Use Development Program will retain the existing quantity of rental units at the Site within the newly constructed buildings, so that at no time will there be less than the existing 3,221 rental units at Parkmerced. This will be memorialized through the execution of the Development Agreement.

OBJECTIVE 3:

ENHANCE THE PHYSICAL CONDITION AND SAFETY OF HOUSING WITHOUT JEOPARDIZING USE OR AFFORDABILITY.

Policy 3.5

Improve the seismic stability of existing housing without reducing the supply of affordable housing.

The Parkmerced Mixed-Use Development Program, at full build-out, will result in increased seismic stability for residents occupying the Site, while not reducing the supply of affordable housing.

The existing garden apartments that will be demolished as part of this Project cannot feasibly be rehabilitated; Parkmerced was originally constructed during the material shortages of World War II and the buildings are reaching the end of their useful life.

OBJECTIVE 4:

SUPPORT AFFORDABLE HOUSING PRODUCTION BY INCREASING SITE AVAILABILITY AND CAPACITY

Policy 4.1

Actively identify and pursue opportunity sites for permanently affordable housing.

Policy 4.2

Include affordable units in larger housing projects.

Policy 4.3

Encourage the construction of affordable units for single households in residential hotels and "efficiency" units.

Policy 4.6

Support a greater range of housing types and building techniques to promote more economical housing construction and potentially achieve greater affordable housing production.

One of the Policies in the General Plan states that "large and privately held land parcels should also be identified and actively promoted for affordable housing". The Parkmerced Site is consistent with this Policy in that the Parkmerced Mixed-Use Development Program will meet the requirements of the City's Inclusionary Affordable Housing Program with respect to net new units, with a minimum of 1/3 of such

requirement satisfied through the construction of Below-Market Rate ("BMR") units on or within 1,000 feet of the Project Site.

In addition to providing new BMR units, the Project will also include a diversity of housing typologies, including studio or "efficiency" units.

OBJECTIVE 6:

PROTECT THE AFFORDABILITY OF EXISTING HOUSING.

Policy 6.2

Ensure that housing developed to be affordable is kept affordable.

Policy 6.3

Safeguard tenants from excessive rent increases.

Under the terms of the Development Agreement, existing tenants who occupy rent-controlled units would be allowed to relocate to a replacement unit located in a newly constructed building with the same rent and same rent-control protections as their to-be-demolished unit, to ensure that those tenants who currently occupy rent control units who choose to relocate to new units are guaranteed protections from excessive rent increases and arbitrary eviction. Furthermore, under the proposed Development Agreement, all existing rent-controlled units – the physical units themselves – would be replaced with new rent-controlled, replacement units, for the life of the building. As a result, at no time will there be less than 3,221 units subject to the terms of the Rent Stabilization Ordinance.

OBJECTIVE 8:

ENSURE EQUAL ACCESS TO HOUSING OPPORTUNITIES.

Policy 8.1

Encourage sufficient and suitable rental housing opportunities and emphasize permanently affordable rental units wherever possible.

Policy 8.4

Encourage greater economic integration within housing projects and throughout San Francisco.

Policy 8.7

Eliminate discrimination against households with children.

Policy 8.8

Promote the adaptability and maximum accessibility of residential dwellings for disabled and elderly occupants.

Policy 8.9

Encourage the provision of new home ownership opportunities through new construction so that increased owner occupancy does not diminish the supply of rental housing.

This Objective of the Housing Element states that population diversity and integration is one of the City's most important assets, and in order to retain that diversity, there needs to be a variety of housing

opportunities available. The Parkmerced Mixed-Use Development Program includes a variety of integrated housing opportunities within the Project Site, including both rental and for-sale units, from efficiency studio units to family-sized three-bedroom units, as well as BMR units as required by the City's Affordable Inclusionary Housing Program and the retention of an additional 3,221 units subject to the terms of the Rent Stabilization Ordinance. Some of the units will be located closer to transit and farther from car storage, whereas other units will be located closer to car storage and farther from transit. This provides great diversity in the type of units available, which should result in population diversity at Parkmerced.

Currently, much of the existing housing at Parkmerced is reaching the end of its useful life and is not ADA accessible. The Parkmerced Mixed-Use Development Program will result in 1,538 of the existing rental units being replaced by new, well-constructed, ADA accessible rental-units. In addition, there will be 5,679 net new units added to Parkmerced, all of which will be well-constructed and ADA accessible.

OBJECTIVE 9:

AVOID OR MITIGATE HARDSHIPS IMPOSED BY DISPLACEMENT.

Policy 9.1

Minimize the hardships of displacement by providing essential relocation services.

Policy 9.2

Offer displacement households the right of first refusal to occupy replacement housing units that are comparable in size, location, cost, and rent control protection.

The Parkmerced Mixed-Use Development Program, through the Development Agreement, will mitigate hardships imposed by displacement, by providing substantial notice to tenants in advance of their unit's demolition, and guarantees them a new unit of approximately equal size in a newly constructed building, at the same rent-controlled price and with the same protections afforded to rent-controlled units. The Parkmerced Mixed-Use Development Program further mitigates hardships imposed by displacement by relocating any tenant of a to-be-demolished building to a newly constructed replacement unit at the Project Sponsor's sole cost, and by paying relocation benefits to any tenant in of a to-be-demolished building who elects not to relocate to a replacement unit at Parkmerced.

Policy 11.2

Ensure housing is provided with adequate public improvements, services, and amenities.

Policy 11.3

Encourage appropriate neighborhood-serving commercial activities in residential areas, without causing affordable housing displacement.

Policy 11.4

Avoid or minimize disruption cause by expansion of institutions, large-scale uses and auto-oriented development into residential areas.

Policy 11.10

Include energy efficient features in new residential development and encourage weatherization in existing housing to reduce the overall housing costs and the long-range cost of maintenance.

Parkmerced is currently an auto-oriented development that lacks sufficient pedestrian-oriented, neighborhood-serving commercial activities to satisfy the daily needs of its residents. At the core of the Parkmerced Mixed-Use Development Program are many new neighborhood-serving amenities and usable open spaces, such as a neighborhood-commercial commons, new restaurants, a new preschool/elementary school and daycare facility site, fitness center, new athletic fields, walking and biking paths, a new farm, and community gardens.

As part of the Parkmerced Mixed-Use Development Program, all new dwelling-units will be energy efficient. The Project's energy-efficiency features include maximizing daylight exposure in new construction, installing Tier 1 or better appliances in residential units, and designing residential and non-residential building envelopes to perform a minimum of 15% and 10%, respectively, more efficiently than current Title 24 standard.

URBAN DESIGN ELEMENT

Objectives and Policies

OBJECTIVE 1:

EMPHASIS OF THE CHARACTERISTIC PATTERN WHICH GIVES TO THE CITY AND ITS NEIGHBORHOODS AN IMAGE, A SENSE OF PURPOSE, AND A MEANS OF ORIENTATION.

Policy 1.1

Recognize and protect major views in the city, with particular attention to those of open space and water.

Policy 1.2

Recognize, protect and reinforce the existing street pattern, especially as it is related to topography.

Policy 1.3

Recognize that buildings, when seen together, produce a total effect that characterizes the city and its districts.

Policy 1.4

Protect and promote large-scale landscaping and open space that define districts and topography.

Policy 1.6

Make centers of activity more prominent through design of street features and by other means.

Policy 1.7

Recognize the natural boundaries of districts, and promote connections between districts.

Policy 1.9

Increase the clarity of routes for travelers.

The siting of new structures within the Parkmerced Mixed-Use Development Program has been designed in such a way so to cluster new towers within existing towers' sight-lines from the residential neighborhoods to the east, in order to preserve views of Lake Merced and the Pacific Ocean from the adjacent neighborhoods. While maintaining Juan Bautista Circle and the major radial streets that currently characterize Parkmerced, the street grid of Parkmerced would be redesigned to increase clarity for travelers by creating a more legible hierarchy of street types, and by providing a grid that is easier to navigate due its smaller blocks and more orthogonal orientation. With a prevailing neighborhood fabric of 4-to-6 stories, taller structures of 8-10 stories will be located at key intersections and adjacent to notable locations and spaces to define centers of activity, provide landmarks and clarity for movement, and activate public spaces. Further, denser and taller development is generally concentrated on the east half of the site, closer to 19th Avenue to emphasize connection to public transit and this major transportation corridor, while tapering down in intensity toward the west. The open space system will include major district-scale open spaces, connecting Juan Bautista Circle with the stream corridor to the athletic fields, farm, and Belvedere Garden connecting to Lake Merced; together this system will better define the edge of the neighborhood and create clear connections between adjacent districts, linking major local and regional open spaces with large-scale landscape features and providing clarity for residents and visitors.

OBJECTIVE 3:

MODERATION OF MAJOR NEW DEVELOPMENT TO COMPLEMENT THE CITY PATTERN, THE RESOURCES TO BE CONSERVED, AND THE NEIGHBORHOOD ENVIRONMENT.

Policy 3.1

Promote harmony in the visual relationships and transitions between new and older buildings.

Policy 3.2

Avoid extreme contrasts in color, shape and other characteristics which will cause new buildings to stand out in excess of their public importance.

Policy 3.3

Promote efforts to achieve high quality of design for buildings to be constructed at prominent locations.

Policy 3.4

Promote building forms that will respect and improve the integrity of open spaces and other public areas.

Policy 3.5

Relate the height of buildings to important attributes of the city pattern and to the height and character of existing development.

Policy 3.6

Relate the bulk of buildings to the prevailing scale of development to avoid an overwhelming or dominating appearance in new construction.

Policy 3.7

Recognize the special urban design problems posed in development of large properties.

The Parkmerced Mixed-Use Development Program includes the retention of the 11 existing tower buildings, and the construction of approximately 5,679 net new units. The new units will be constructed in new buildings that will be compatible with the existing structures, and will vary in height and design. The siting of new structures has been designed in such a way so to cluster new towers within existing towers' sight-lines from the residential neighborhoods to the east, in order to preserve views of Lake Merced and the Pacific Ocean from the adjacent neighborhoods. The street grid of Parkmerced would be redesigned to increase clarity for travelers by creating a more legible hierarchy of street types, and by providing a grid that is easier to navigate due its smaller blocks and more orthogonal orientation. With a prevailing neighborhood fabric of 4-to-6 stories, taller structures of 8-10 stories will be located at key intersections and adjacent to notable locations and spaces to define centers of activity, provide landmarks and clarity for movement, and activate public spaces. Further, denser and taller development is generally concentrated on the east half of the site, closer to 19th Avenue to emphasize connection to public transit and this major transportation corridor, while tapering down in intensity toward the west. The open space system will include major district-scale open spaces, to better define the edge of the neighborhood and create clear connections between adjacent districts and to link major local and regional open spaces with large-scale landscape features.

Each new building constructed as part of the Parkmerced Mixed-Use Development Program will be subject to a design review process conducted by the Planning Department and governed by the terms of the proposed Parkmerced Special Use District. The design review process is intended to ensure that all buildings within Parkmerced are designed to complement the aesthetic of the development, exhibit high quality architectural design and comply with the requirements of the Parkmerced Design Standards + Guidelines and the Parkmerced Sustainability Plan.

The Project Site is large - approximately 152 acres (including streets) – and as such, it has been given close consideration with regard to Project's urban design features, the need for neighborhood-serving amenities, and the need for improved transit. The five guiding Plan documents (including the above referenced Design Standards + Guidelines and the Sustainability Plan) together constitute a "master plan" for the Site, creating a framework and set of rules for the Site's future development. Through these guiding documents, the full build-out of this Site will be a better connected community with a fine-grain urban fabric containing small blocks and a variety of building heights and sizes; the Site's physical access to the surrounding established neighborhoods will be improved through the creation of new bicycle, pedestrian, and transit connections at the Site's periphery.

OBJECTIVE 4:

IMPROVEMENT OF THE NEIGHBORHOOD ENVIRONMENT TO INCREASE PERSONAL SAFETY, COMFORT, PRIDE AND OPPORTUNITY.

Policy 4.3

Provide adequate lighting in public areas.

Policy 4.4

Design walkways and parking facilities to minimize danger to pedestrians.

Policy 4.5

Provide adequate maintenance for public areas.

Policy 4.6:

Emphasize the importance of local centers providing commercial and government services.

Policy 4.8:

Provide convenient access to a variety of recreation opportunities.

Policy 4.9:

Maximize the use of recreation areas for recreational purposes.

Policy 4.10:

Encourage or require the provision of recreation space in private development.

Policy 4.12:

Install, promote and maintain landscaping in public and private areas.

Policy 4.13:

Improve pedestrian areas by providing human scale and interest.

The Parkmerced Mixed-Use Development Program includes numerous guidelines that enhance the public realm, livability, and character of the neighborhood. These features include ground-floor walk-up units in all new buildings, required landscaping strips at the front of all properties, uniform plantings and street trees, pedestrian-oriented lighting, 2,945,000sf of new open spaces such as athletic fields, community gardens, and an farm that will give the neighborhood an identity and provide a center for activity. The Development Agreement outlines operational standards and maintenance procedures to be followed by the Project Sponsor (or homeowners' association, as applicable) for all privately-owned public spaces.

Parking garages, which typically lack visual interest, will be underground and located on the western side of the Site, which will increase pedestrian safety by not having automobile ingress and egress crossing sidewalks throughout the neighborhood. Utility wires will also be located underground to enhance the appearance of the streets and neighborhood.

Throughout the Site there will be approximately 230,000 square feet of new neighborhood-serving retail, including a full-service grocery store. There will neighborhood-serving amenities of small and moderate scale, in order to create both a commercial core and to provide services within close proximity of every dwelling-unit. There will also be 80,000sf of office space, 25,000sf dedicated to a preschool/elementary school or daycare facility, and 64,000sf dedicated to a fitness/community center.

RECREATION AND OPEN SPACE ELEMENT**Objectives and Policies**

OBJECTIVE 1:

PROVIDE OPPORTUNITIES FOR RECREATION AND THE ENJOYMENT OF OPEN SPACE IN EVERY SAN FRANCISCO NEIGHBORHOOD.

Policy 4.4:

Acquire and develop new public open space in existing residential neighborhoods, giving priority to areas which are most deficient in open space.

Policy 4.5:

Require private usable outdoor open space in new residential development.

Policy 4.6:

Assure the provision of adequate public open space to serve new residential development.

As part of the Parkmerced Mixed-Use Development Program, there will be a total of 2,964,000sf of open space, including 2.1 acres of open space provided through six Neighborhood Commons, 2.94 acres of open space provided through the creation of new athletic fields, and over one-acre of open space provided through the creation of community gardens. In addition to the publically-accessible usable open space, each residential building will contain usable semi-private or private open space in the following ratios: 36 square feet per unit if private open space (e.g. balconies), and 48 square feet per unit if semi-private open space (e.g. roof decks).

TRANSPORTATION ELEMENT

Objectives and Policies

OBJECTIVE 1:

MEET THE NEEDS OF ALL RESIDENTS AND VISITORS FOR SAFE, CONVENIENT AND INEXPENSIVE TRAVEL WITHIN SAN FRANCISCO AND BETWEEN THE CITY AND OTHER PARTS OF THE REGION WHILE MAINTAINING THE HIGH QUALITY LIVING ENVIRONMENT OF THE BAY AREA.

Policy 1.2

Ensure the safety and comfort of pedestrians throughout the city.

Policy 1.3

Give priority to public transit and other alternatives to the private automobile as the means of meeting San Francisco's transportation needs, particularly those of commuters.

Policy 1.5

Coordinate regional and local transportation systems and provide for interline transit transfers.

Policy 1.6

Ensure choices among modes of travel and accommodate each mode when and where it is most appropriate.

Policy 1.7

Assure expanded mobility for the disadvantaged.

As part of the Parkmerced Mixed-Use Development Program, there will be substantial investment in pedestrian, bicycle, and transit improvements throughout and adjacent to the Site. The Site will be redesigned to be consistent with the City's recently-adopted Better Streets Plan, including the use of smaller blocks and new connections outside of the Site, making it more pedestrian-friendly. There will be an enhanced network of dedicated bikeways, as well as enhanced access to the Site to improve vehicular circulation. The Project will include shuttle service to Daly City BART Station, to encourage the use of public transportation. Lastly, the Project includes re-routing the MUNI M-Oceanview light-rail line through the Site, creating two new transit stops and relocating the existing Parkmerced/SFSU transit within the Site. By re-routing the MUNI M-Oceanview light-rail line and relocating the Parkmerced/SFSU stop, use of transit will be safer and more accessible, by eliminating the need to cross the busy 19th Avenue intersection to board the train. To further encourage the use of public transit, the Project Sponsor will be providing transit pass subsidies, and bike and car share opportunities.

OBJECTIVE 2:

USE THE TRANSPORTATION SYSTEM AS A MEANS FOR GUIDING DEVELOPMENT AND IMPROVING THE ENVIRONMENT.

Policy 2.1

Uses rapid transit and other transportation improvements in the city and region as the catalyst for desirable development, and coordinate new facilities with public and private development.

Policy 2.2

Reduce pollution, noise and energy consumption.

Policy 2.4

Organize the transportation system to reinforce community identity, improve linkages among interrelated activities and provide focus for community activities.

Policy 2.5

Provide incentives for use of transit, carpools, vanpools, walking and bicycling and reduce the need for new or expanded automobile and automobile parking facilities.

The Parkmerced Mixed-Use Development Program will improve public transit connections throughout the City and region by re-routing the MUNI M-Oceanview light-rail line through Parkmerced. Such re-routing will make transit stops more accessible, allow SFMTA to run "short-lines" that do not continue all the way through the low-ridership areas to Balboa Park, and provide opportunities for future connections to Daly City BART. It will also incentivize the use of public transit by providing transit subsidies to all tenants, and providing free shuttles to the Daly City BART station. There will also be improved bus service through the Site and free shuttles to local shopping centers, in addition to making bicycle and pedestrian improvements, which together, improve transit connections and accessibility.

OBJECTIVE 4:

MAINTAIN AND ENHANCE SAN FRANCISCO'S POSITION AS THE HUB OF A REGIONAL, CITY-CENTERED TRANSIT SYSTEM.

Policy 4.2

Increase transit ridership capacity in all congested regional corridors.

Policy 4.5

Provide convenient transit service that connects the regional transit network to major employment centers outside the downtown area.

The Parkmerced Mixed-Use Development Program will increase transit ridership capacity by providing funding to SFMTA to purchase an additional light-rail vehicle, which in turn will help SFMTA maintain headways. Through improved service on the MUNI M-Oceanview light-rail line and the provision of a free shuttle service to BART, residents and visitors will have more convenient access to regional transit networks including BART, regional bus lines and the Golden Gate Transit ferry service.

OBJECTIVE 18:

ESTABLISH A STREET HIERARCHY SYSTEM IN WHICH THE FUNCTION AND DESIGN OF EACH STREET ARE CONSISTENT WITH THE CHARACTER AND USE OF ADJACENT LAND.

Policy 18.2

Design streets for a level of traffic that serves, but will not cause a detrimental impact on adjacent land uses, nor eliminate the efficient and safe movement of transit vehicles and bicycles.

As a result of the Parkmerced Mixed-Use Development Program, the entire site will be redesigned to be consistent with the City's Better Streets Plan.

OBJECTIVE 20:

DEVELOP TRANSIT AS THE PRIMARY MODE OF TRAVEL TO AND FROM DOWNTOWN AND ALL MAJOR ACTIVITY CENTERS WITHIN THE REGION.

Policy 21.2

Where a high level of transit ridership or potential ridership exists along a corridor, existing transit service or technology should be upgraded to attract and accommodate riders.

Policy 21.7

Make convenient transfers between transit lines, systems and modes possible by establishing common or closely located terminals for local and regional transit systems by coordinating fares and schedules and by providing bicycle access and secure bicycle parking.

Policy 21.9

Improve pedestrian and bicycle access to transit facilities.

Policy 21.10

Ensure passenger and operator safety in the design and operation of transit vehicles and station facilities.

The Parkmerced Mixed-Use Development Program will result in the re-routing the MUNI M-Oceanview light-rail line from the middle of the busy 19th Avenue to within the Project Site, making pedestrian and bicycle access to the station safer and more accessible by eliminating the need to cross the busy 19th Avenue intersection to board the train. The Site will continue to be served by several MUNI bus lines, which will also stop in the vicinity of the new station, making transfers relatively easy.

2. The proposed long-range mixed-use development project is generally consistent with the eight General Plan priority policies set forth in Section 101.1 in that:

- A) The existing neighborhood-serving retail uses will be preserved and enhanced and future opportunities for resident employment in and ownership of such businesses will be enhanced:

The proposed Project would enhance the neighborhood-serving retail uses by creating a neighborhood-serving retail core with approximately 230,000 square feet of new retail space, thereby providing the community with services such as a grocery store and banking. The existing Parkmerced development currently has only a very small amount of neighborhood-serving retail, which is located adjacent to the Project Site. In combination with the proposed approximately 69,000 square feet of new office space, the new retail uses would provide opportunities for resident employment and business ownership. Furthermore, the proposed addition of 5,679 net new households would strengthen business at existing establishments in the vicinity of the Project Site and bolster demand for additional retail uses.

- B) The existing housing and neighborhood character will be conserved and protected in order to preserve the cultural and economic diversity of our neighborhoods:

The proposed Project would preserve the existing diversity and character of Parkmerced by maintaining the same number of rent controlled units (3,221 rent controlled units) that currently exist at Parkmerced. The Project would accomplish this by conserving 1,683 existing rent controlled apartments, which would remain subject to the Rent Stabilization Ordinance, and replacing all 1,538 existing rent controlled apartments that would be demolished by the Project with a new unit that would be subject to the same protections as contained in the Rent Stabilization Ordinance for the life of the building. In addition, under the proposed Project, residents of buildings proposed for demolition would be given the opportunity to relocate to such replacement units in a new building and would be assessed the same rent as their previous unit. The Project would also enhance the diversity of Parkmerced by constructing a large number of new BMR affordable units. Currently, Parkmerced has no BMR units. Further, the proposed Project would enhance the character of the Parkmerced neighborhood by establishing a social and commercial core, improving pedestrian accessibility, and creating open space and recreational opportunities.

- C) The City's supply of affordable housing will be preserved and enhanced:

The proposed Project will result in the construction of a significant number of BMR housing units in accordance with the Development Agreement to be executed by the Project Sponsor and the City. Such BMR units will significantly increase the City's supply of affordable housing. Moreover, the affordability of the existing rent-controlled units would be maintained for all existing residents, who, under the terms of the proposed Development Agreement, would continue to benefit from the protections of the Rent Stabilization Ordinance, including residents of units proposed for replacement who elect to relocate to a new unit. For such relocated residents, the Project proposes that the new unit be rented at the same rent controlled rate as the resident's existing unit, thereby preserving affordability of the Project for existing residents. Under the terms of the proposed Development Agreement, the replacement unit would be subject to the same rent increase restrictions as contained in the Rent Stabilization Ordinance for the life of the building, regardless of whether an existing tenant elects to relocate to the unit or the unit is occupied by a new tenant.

- D) The commuter traffic will not impede MUNI transit service or overburden our streets or neighborhood parking:

The proposed Project would enhance MUNI transit service by re-routing the MUNI M-Oceanview light-rail line through the Project Site, creating two new stations and relocating the existing Parkmerced/SFSU station. These improvements would alleviate the overcrowding issues at the existing Parkmerced/SFSU station and improve the connection to SFSU by requiring riders to cross Holloway Avenue as opposed to Nineteenth Avenue. The realignment would also reduce the walking distance to transit for residents of Parkmerced, thereby encouraging the use of public transportation. In addition, the proposed roadway re-alignments would ease the burden on City streets in the Parkmerced area by improving traffic flow. Finally, the proposed Project would add approximately 90 on-street and 6,252 off-street parking spaces, ensuring that residents of the proposed Project do not rely on parking in the adjoining neighborhoods.

- E) A diverse economic base will be maintained by protecting our industrial and service sectors from displacement due to commercial office development. And future opportunities for resident employment and ownership in these sectors will be enhanced:

The proposed Project would not displace any industrial or service sector uses because of new commercial office development since the existing buildings slated for demolition do not contain any industrial or service sector uses. The Project Site is currently occupied by residential apartment buildings.

- F) The City will achieve the greatest possible preparedness to protect against injury and loss of life in an earthquake.

The proposed Project would help the City achieve the greatest possible preparedness to protect against injury and loss of life in an earthquake because the new buildings would be constructed in accordance with all applicable building codes and regulations with regard to seismic safety.

- G) That landmark and historic buildings will be preserved:

The proposed Project would not adversely impact any City landmarks because there are no City-designated landmarks on the Project Site. Although none of the buildings on the Project Site are designated City landmarks, as mitigation for the Proposed Project's impacts to historic resources under the California Environmental Quality Act, the Project Sponsor will prepare documentation of the site based on the National Park Service's Historic American Building Survey/Historic American Engineering Record Historical Report Guidelines and provide a permanent display of interpretative materials concerning the history of the original Parkmerced complex.


- H) Parks and open space and their access to sunlight and vistas will be protected from development:

The proposed Project would provide 68 acres of open space in a network of publically accessible neighborhood parks, athletic fields, public plazas, greenways and a farm. The Project would provide significant additional open space in the form of private or semi-private open space areas such as centralized outdoor courtyards, roof decks, and balconies. These private and semi-private open spaces would be required within the development of each residential building within Parkmerced. The parks and open space would be more accessible and usable than the current open spaces. Parks and open space within, and in the vicinity of, the proposed Project would continue to receive a substantial amount of sunlight during the day when use is at its highest rate. Existing coastal views from parks located to the east and north of the Project Site would be maintained with implementation of the proposed Project.

3. The proposed long-range mixed-use development project is consistent with the requirements set forth in Planning Code Section 302, in that:
- a. The Project is necessary and desirable because it would enhance the lives of existing and future residents, and the City as a whole, by converting a single-use residential complex into a high-quality, mixed-use development that includes neighborhood-serving retail and numerous open space and recreational activities. The Project would also construct a significant amount of new housing units at an in-fill location within an existing urban environment and replace existing housing units that were constructed during the material shortages experienced during World War II and that are reaching the end of their useful life with new residential buildings that would be more energy efficient and meet current ADA requirements. The residential density that would result from the proposed in-fill housing is permitted by, and consistent with, the existing zoning of the Parkmerced site. With only 8,900 total housing units proposed, the Project would be smaller than the 10,302 units principally permitted by the existing zoning or the 11,750 housing units permitted through a Planned Unit Development. Additionally, the proposed Project would enhance alternatives to automobile use by making certain improvement to public transportation and by providing services to residents such as a shuttle to the Daly City BART station and carpool/vanpool services. Because a Special Use District is necessary in order to implement the proposed Project, and for the reasons set forth above, the Commission finds the requested amendments to the Planning Code, Zoning Maps, and General Plan to be required by public necessity, convenience and general welfare.

4. Findings under the California Environmental Quality Act (CEQA):
- a. On February 10, 2011, the Planning Commission, by Motion No. 18629, certified a Final Environmental Impact Report ("FEIR") for the Parkmerced Mixed-Use Development Program in compliance with CEQA, the CEQA Guidelines and Chapter 31, finding that the FEIR was completed in compliance with CEQA and was adequate, accurate and objective and reflected the independent judgment of the Planning Commission; a copy of the motion is on file with the Clerk of the Commission.
 - b. Also on February 10, 2011, the Commission reviewed and considered the information contained in the FEIR and by Motion No. 18270 adopted CEQA Findings for the proposed Parkmerced Mixed-Use Development Program Project under CEQA, the CEQA Guidelines and Chapter 31, including the adoption of a mitigation monitoring and reporting program (MMRP) and a statement of overriding considerations, ("CEQA Findings"). The CEQA Findings for the proposed Project are on file with the Clerk of the Commission and are incorporated into this Motion by reference.

I hereby certify that the Planning Commission ADOPTED the foregoing Resolution on February 10, 2011.



Linda D. Avery
Commission Secretary

AYES: Commissioners Antonini, Borden, Fong, and Miguel

NAYS: Commissioners Moore, Olague, and Sugaya

ABSENT:

ADOPTED: February 10, 2011



SAN FRANCISCO PLANNING DEPARTMENT

Planning Commission Motion No. 18270

CEQA Findings

HEARING DATE: FEBRUARY 10, 2011

1650 Mission St.
Suite 400
San Francisco,
CA 94103-2479

Reception:
415.558.6378

Fax:
415.558.6409

Planning
Information:
415.558.6377

Date: January 27, 2011
Project Name: Parkmerced Mixed-Use Development Program
Case Number: 2008.0021EPMTZW
Initiated by: Seth Mallen, Parkmerced Investors, LLC
3711 – 19th Avenue
San Francisco, CA 94132
Staff Contact: Elizabeth Watty, Planner
Elizabeth.Watty@sfgov.org, 415-558-6620
Reviewed By: David Alumbaugh, Acting Director Citywide Planning
David.Alumbaugh@sfgov.org, 415-558-6601
Recommendation: Adopt CEQA Findings

ADOPTING PROJECT APPROVAL FINDINGS UNDER THE CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) TO ALLOW THE FULL IMPLEMENTATION OF THE PARKMERCED MIXED-USE DEVELOPMENT PROGRAM ("PROJECT"), BEING ALL OF ASSESSOR'S BLOCKS 7303-001, 7303-A-001, 7308-001, 7309-001, 7309-A-001, 7310-001, 7311-001, 7315-001, 7316-001, 7317-001, 7318-001, 7319-001, 7320-003, 7321-001, 7322-001, 7323-001, 7325-001, 7326-001, 7330-001, 7331-004, 7332-004, 7333-001, 7333-003, 7333-A-001, 7333-B-001, 7333-C-001, 7333-D-001, 7333-E-001, 7334-001, 7335-001, 7336-001, 7337-001, 7338-001, 7339-001, 7340-001, 7341-001, 7342-001, 7343-001, 7344-001, 7345-001, 7345-A-001, 7345-B-001, 7345-C-001, 7356-001, 7357-001, 7358-001, 7359-001, 7360-001, 7361-001, 7362-001, 7363-001, 7364-001, 7365-001, 7366-001, 7367-001, 7368-001, 7369-001, and 7370-001, IN THE RM-1 (RESIDENTIAL MIXED, LOW DENSITY), RM-4 (RESIDENTIAL MIXED, HIGH DENSITY), & RH-1(D) (RESIDENTIAL HOUSE, ONE-FAMILY, DETACHED) DISTRICTS.

PREAMBLE

In determining to approve the Parkmerced Project ("Project") described in Section A, Project Description below, the San Francisco Planning Commission (hereinafter "Commission") makes and adopts the following findings of fact and decisions regarding mitigation measures and alternatives, and adopts the statement of overriding considerations, based on substantial evidence in the whole record of this proceeding and under the California Environmental Quality Act ("CEQA"), California Public Resources Code Sections 21000 et seq., particularly Sections 21081 and 21081.5, the Guidelines for Implementation of CEQA ("CEQA Guidelines"), 14 California Code of Regulations Sections 15000 et seq., particularly Sections 15091 through 15093, and Chapter 31 of the San Francisco Administration Code.

FINDINGS

The San Francisco Planning Commission hereby incorporates by reference as though fully set forth herein the findings for the Project approval of the Parkmerced Mixed-Use Development Program (hereinafter the "Project") attached hereto as Exhibit A pursuant to the California Environmental Quality Act, California Public Resources Code, Sections 21000 et seq. ("CEQA"), the Guidelines for Implementation of CEQA, Title 15 California Code of Regulations Sections 15000 et seq. ("Guidelines"), and Chapter 31 of the San Francisco Administrative Code ("Chapter 31"), entitled Environmental Quality:

A. Project Description

The Parkmerced Mixed-Use Development Program is a long-term (20-30 year) mixed-use development program to comprehensively replan and redevelop the Parkmerced Project Site—the "Project" identified in the Final EIR. The Project would increase residential density, provide a neighborhood core with new commercial and retail services, modify transit facilities, and improve utilities within the development site. A new site for a Pre-K-5 school and/or day care facility, a fitness center, and new open space uses, including athletic playing fields, walking and biking paths, an approximately 2-acre farm, and community gardens, would also be provided. About 1,683 of the existing apartments located in 11 tower buildings would be retained. Over an approximately 20-year period of phased construction, the remaining 1,538 existing apartments would be demolished in phases and fully replaced, and an additional 5,679 net new units would be added to the Project Site, resulting at full build-out in a total of about 8,900 units on the Project Site.

The Project includes construction of (or provides financing for construction of) a series of transportation improvements, which include rerouting the existing Muni Metro M Ocean View line from its current alignment along 19th Avenue. The new alignment, as currently envisioned and analyzed in the Final EIR, would leave 19th Avenue at Holloway Avenue and proceed through the neighborhood core in Parkmerced. The Muni M line trains would then travel alternately along one of two alignments: trains either would re-enter 19th Avenue south of Felix Avenue and terminate at the existing Balboa Park station, or they would terminate at a new station, with full layover and terminal facilities, constructed on the Project Site at the intersection of Font Boulevard and Chumasero Drive.

The Proposed Project also includes a series of infrastructure improvements, including the installation of a combination of renewable energy sources, such as wind turbines and photovoltaic cells, to meet a portion of the Proposed Project's energy demand. In addition, stormwater runoff from buildings and streets would be captured and filtered through a series of bioswales, ponds, and other natural filtration systems. The filtered stormwater would then either percolate into the groundwater that feeds the Upper Westside groundwater basin and Lake Merced or be released directly into Lake Merced.

Amendments to the San Francisco Planning Code and the San Francisco General Plan are also proposed as part of the Proposed Project. The Planning Code amendments would change the Height and Bulk District Zoning Map and would add a Special Use District (SUD) applicable to

the entire Project Site, which would include an overlay of density and uses within the SUD. A Development Agreement is also proposed as part of the Project, as well as adoption of the *Parkmerced Design Standards and Guidelines*, which contain specific development guidelines.

The Final EIR also evaluated a Project sub-variant, which would construct a right-turn ingress along 19th Avenue between Crespi Drive and Junipero Serra Boulevard at Cambon Drive. This new access location would provide ingress for southbound vehicles only and would not provide access out onto 19th Avenue.

B. Planning and Environmental Review Process

The Project Sponsor applied for environmental review on January 8, 2008. The Department determined that an Environmental Impact Report was required and provided public notice of the preparation of such on May 20, 2009, and held a public scoping meeting on June 8, 2009. The Department published a Draft Environmental Impact Report (DEIR) on May 12, 2010. The Commission held a public hearing to solicit testimony on the DEIR on June 17, 2010. The Department received written comments on the DEIR for 61-days, beginning on May 12, 2010. The Department published the Comments and Responses on October 28, 2010. The DEIR, together with the Comments and Responses document, constitute the Final Environmental Impact Report (FEIR) for the Parkmerced Mixed-Use Development Program. The Commission certified the FEIR on February 10, 2011, in Motion No. 18629.

Pursuant to the California Environmental Quality Act, Public Resources Code Section 21000 *et seq.*, (CEQA), Title 14 California Code of Regulations Section 15000 *et seq.* (CEQA Guidelines), and Chapter 31 of the San Francisco Administrative Code, the Planning Commission has reviewed and considered the FEIR, which is available for public review at the Planning Department's offices at 1650 Mission Street.

Pursuant to CEQA Guidelines Section 15162, the Commission finds that the proposed actions before this Commission are within the scope of the project analyzed in the FEIR and (1) that no substantial changes are proposed in the Project and no substantial changes have occurred with respect to the circumstances under which this Project will be undertaken that would require major revisions to the FEIR due to the involvement of any new significant environmental effects or a substantial increase in the severity of previously identified effects and (2) no new information that was not known and could not have been known shows that the project will have any new significant effects not analyzed in the FEIR or a substantial increase in the severity of any effect analyzed or that new mitigation measures should be included that have not. The Commission further finds that an addendum to the FEIR is not required due to any changes in the Project or the Project's circumstances.

The public hearing transcript, a copy of all letters regarding the FEIR received during the public review period, the administrative record, and background documentation for the FEIR are located at the Planning Department, 1650 Mission Street, San Francisco. The Planning Commission Secretary, Linda Avery, is the custodian of records for the Planning Department and the Planning Commission.


Motion No. 18270
Hearing Date: February 10, 2011

CASE NO. 2008.0021EPMTZW
Parkmerced Mixed-Use Development Program

DECISION

That based upon the Record, the submissions by the Applicant, the staff of the Department and other interested parties, the oral testimony presented to this Commission at the public hearings, and all other written materials submitted by all parties, the Commission hereby adopts the CEQA Findings attached hereto as Exhibit A and the Mitigation Monitoring and Reporting Program (MMRP) attached hereto as Exhibit B, which are incorporated herein by reference as though fully set forth.

I hereby certify that the Planning Commission ADOPTED the foregoing Motion on Thursday, February 10, 2011.


Linda D. Avery
Commission Secretary

AYES: Commissioners Antonini, Borden, Fong, and Miguel

NAYS: Commissioners Moore, Olague, and Sugaya

ABSENT:

ADOPTED: February 10, 2011

ATTACHMENT A

PARKMERCED PROJECT
CALIFORNIA ENVIRONMENTAL QUALITY ACT FINDINGS:
FINDINGS OF FACT, EVALUATION OF MITIGATION MEASURES AND
ALTERNATIVES, AND STATEMENT OF OVERRIDING CONSIDERATIONS
SAN FRANCISCO PLANNING COMMISSION
(Revised: February 3, 2011)

In determining to approve the Parkmerced Project ("Project") described in Section I, Project Description below, the San Francisco Planning Commission makes and adopts the following findings of fact and decisions regarding mitigation measures and alternatives, and adopts the statement of overriding considerations, based on substantial evidence in the whole record of this proceeding and under the California Environmental Quality Act ("CEQA"), California Public Resources Code Sections 21000 et seq., particularly Sections 21081 and 21081.5, the Guidelines for Implementation of CEQA ("CEQA Guidelines"), 14 California Code of Regulations Sections 15000 et seq., particularly Sections 15091 through 15093, and Chapter 31 of the San Francisco Administration Code.

This document is organized as follows:

Section I provides a description of the Project proposed for adoption, and, in the alternative, the No Muni Realignment Alternative, the environmental review process for the Project, the approval actions to be taken and the location of records;

Section II identifies the impacts found not to be significant that do not require mitigation;

Section III identifies potentially significant impacts that can be avoided or reduced to less-than-significant levels through mitigation and describes the disposition of the mitigation measures;

Section IV identifies significant impacts that cannot be avoided or reduced to less-than-significant levels and describes any applicable mitigation measures as well as the disposition of the mitigation measures;

Section V identifies mitigation measures proposed but rejected as infeasible for economic, legal, social, technological, or other considerations;

Section VI evaluates the different Project alternatives and the economic, legal, social, technological, and other considerations that support approval of the Project and the rejection of the alternatives, or elements thereof, analyzed; and

Section VII presents a statement of overriding considerations setting forth specific reasons in support of the Commission's actions and its rejection of the alternatives not incorporated into the Project.

The Mitigation Monitoring and Reporting Program ("MMRP") for the mitigation measures that have been proposed for adoption is attached with these findings as **Attachment B to Resolution No.**

_____. The MMRP is required by CEQA Section 21081.6 and CEQA Guidelines Section 15091. Attachment B provides a table setting forth each mitigation measure listed in the Final Environmental Impact Report for the Project ("Final EIR") that is required to reduce or avoid a significant adverse impact. Attachment B also specifies the agency responsible for implementation of each measure and establishes monitoring actions and a monitoring schedule. The full text of the mitigation measures is set forth in Attachment B. These findings are based upon substantial evidence in the entire record before the Commission. The references set forth in these findings to certain pages or sections of the Draft Environmental Impact Report ("Draft EIR" or "DEIR") or the Comments and Responses document ("C&R") in the Final EIR are for ease of reference and are not intended to provide an exhaustive list of the evidence relied upon for these findings.

I. APPROVAL OF THE PROJECT

A. Project Description

By this action, the San Francisco Planning Commission approves the long-term mixed-use development program to comprehensively replan and redesign the Parkmerced Project Site—the "Project" identified in the Final EIR. The Project would increase residential density, provide a neighborhood core with new commercial and retail services, modify transit facilities, and improve utilities within the development site. A new site for a Pre-K-5 school and/or day care facility, a fitness center, and new open space uses, including athletic playing fields, walking and biking paths, an approximately 2-acre farm, and community gardens, would also be provided. About 1,683 of the existing apartments located in 11 tower buildings would be retained. Over an approximately 20-year period of phased construction, the remaining 1,538 existing apartments would be demolished in phases and fully replaced, and an additional 5,679 net new units would be added to the Project Site, resulting at full build-out in a total of about 8,900 units on the Project Site.

The Project includes construction of (or provides financing for construction of) a series of transportation improvements, which include rerouting the existing Muni Metro M Ocean View line from its current alignment along 19th Avenue. The new alignment, as currently envisioned and analyzed in the Final EIR, would leave 19th Avenue at Holloway Avenue and proceed through the neighborhood core in Parkmerced. The Muni M line trains would then travel alternately along one of two alignments: trains either would re-enter 19th Avenue south of Felix Avenue and terminate at the existing Balboa Park station, or they would terminate at a new station, with full layover and terminal facilities, constructed on the Project Site at the intersection of Font Boulevard and Chumasero Drive.

The Proposed Project also includes a series of infrastructure improvements, including the installation of a combination of renewable energy sources, such as wind turbines and photovoltaic cells, to meet a portion of the Proposed Project's energy demand. In addition, stormwater runoff from buildings and streets would be captured and filtered through a series of bioswales, ponds, and other natural filtration systems. The filtered

stormwater would then either percolate into the groundwater that feeds the Upper Westside groundwater basin and Lake Merced or be released directly into Lake Merced.

Amendments to the San Francisco Planning Code and the San Francisco General Plan are also proposed as part of the Proposed Project. The Planning Code amendments would change the Height and Bulk District Zoning Map and would add a Special Use District (SUD) applicable to the entire Project Site, which would include an overlay of density and uses within the SUD. A Development Agreement is also proposed as part of the Project, as well as adoption of the *Parkmerced Design Standards and Guidelines*, which contain specific development guidelines.

The Final EIR also evaluated a Project "sub-variant", which would construct a right-turn ingress along 19th Avenue between Crespi Drive and Junipero Serra Boulevard at Cambon Drive. This new access location would provide ingress for southbound vehicles only and would not provide access out onto 19th Avenue. Although the Final EIR and these Findings refer to this as the "Project sub-variant", the Project approval documents may refer to this as the "Connect Cambon to 19th Avenue Project Variant" or "Project Variant"; both names refer to the same set of transportation improvements.

B. No Muni Realignment Alternative

The Project proposes to reroute the existing Muni Metro M Ocean View line from its current alignment along 19th Avenue, which would require the approval of the California Department of Transportation ("Caltrans") and the California Public Utilities Commission ("CPUC"). In the event that such approval is not granted, the approval granted by the San Francisco Planning Commission would permit the Project to proceed after identifying an alternate transportation improvement of equivalent value to the proposed rerouting of the existing Muni Metro M Ocean View line. In the event that Caltrans and CPUC approval is not granted, the San Francisco Planning Commission also makes and adopts the following findings of fact and decisions regarding mitigation measures and alternatives, and adopts the statement of overriding considerations, based on substantial evidence in the whole record of this proceeding and under CEQA, particularly Sections 21081 and 21081.5, the CEQA Guidelines, particularly Sections 15091 through 15093, and Chapter 31 of the San Francisco Administration Code for the No Muni Realignment Alternative described in Section I.

Under the No Muni Realignment Alternative, the 152-acre site would be replanned and redesigned as it would with the Project, except that the Muni light rail line would not be routed through the Project Site, and no new Muni stops would be constructed. Under this alternative, the M Ocean View line would continue to bypass the Project Site, and would remain in its existing alignment to its terminus at the Balboa Park Station. Traffic and circulation improvements under the No Muni Realignment Alternative would be the same as those in the Project, except that there would be no northbound left-turn at the intersection of 19th Avenue and Crespi Drive, no fourth southbound travel lane would be constructed on 19th Avenue, and the SFSU transit stop would remain in the median of 19th Avenue.

A design variant studied under the No Muni Realignment Alternative is an analysis of the Project without Muni or any of the improvements identified along 19th Avenue. There would be minimal land use changes from the No Muni Realignment Alternative as a result of having no transit improvements implemented along 19th Avenue.

As with the Project, implementation of a sustainability plan would provide for a variety of new infrastructure improvements intended to reduce the alternative's per-unit use of electricity, natural gas, water, and the City's wastewater conveyance and treatment systems. A combination of renewable energy sources, including wind turbines and photovoltaic cells, would be used to meet a portion of this alternative's energy demand. In addition, stormwater runoff from buildings and streets would be captured and filtered through a series of bioswales, ponds, and other natural filtration systems. As with the Proposed Project, the filtered stormwater would then either percolate into the groundwater that feeds the Westside groundwater basin and Lake Merced or be released directly into Lake Merced.

The Commission approves the No Muni Realignment Alternative in the alternative to the Project, in the event that any non-City agency (such as Caltrans and the CPUC) disapproves the realignment of the M Ocean View line in the manner proposed by the Project. Although the Project is preferable to the No Muni Realignment Alternative, the Commission makes such approval in the alternative, because, overall, the Muni realignment is not a mitigation measure, the No Muni Realignment Alternative is identical to the Project in all other respects and therefore provides all the other major public benefits of the Project, and the Project Development Agreement requires that an alternate transportation improvement of equivalent economic value be identified and implemented if the Project's proposed realignment of the M Ocean View light rail line is not approved by all necessary non-City agencies.

C. Project Objectives

The Final EIR discusses several Project objectives identified by the Project Sponsor. The objectives are as follows:

- Adopt a land use program for Parkmerced that provides an innovative model of environmentally sustainable design practices, to, among other things maximize walking, bicycling and use of public transportation, and minimize the impacts and use of private automobiles by implementing a land use program with increased residential density and a commercial neighborhood core located within comfortable walking distance of transit service and residences.
- Increase the supply of housing near a new neighborhood core containing new neighborhood-serving retail, office, transit,
- Reconfigure the existing open space at Parkmerced to provide larger and more usable open spaces such as a major new park, athletic playing fields, organic farm, walking and bicycling paths, and community gardens.

- Reconnect Parkmerced to the Lake Merced watershed by restoring the pre-development hydrology.
- Provide high-density, mixed-income housing, including below-market rate units, with a variety of housing types consistent with transit-oriented development to attract a diversity of household types, especially families.
- Protect and enhance the diversity of Parkmerced by protecting existing residents from displacement through a phasing plan designed to ensure that all existing residents will be able to remain at Parkmerced while having to relocate once only and into a new apartment, if necessary, and that this new apartment would be rented at the same rent-controlled rate as the resident's existing apartment prior to demolition (and also subject to the existing protections against rent increases of the San Francisco Rent Control Ordinance).
- Make possible the construction of affordable below market rate units.
- Provide housing in an urban infill location to help alleviate the effects of suburban sprawl and protect the green belt.
- Create a circulation and transportation system designed to reduce the amount of future automobile traffic originating from Parkmerced and to improve traffic flow on adjacent roadways such as 19th Avenue and Brotherhood Way, and that emphasizes transit-oriented development, and promotes the use of public transportation and car-sharing, through an innovative and comprehensive demand management program.
- Construct major infrastructure improvements intended to demonstrate leadership in sustainable engineering and to reduce the neighborhood's per capita use of the City's electrical, natural gas, water, and wastewater infrastructure while demonstrating pioneering leadership in sustainable design and through providing new benchmarks for sustainable development practices in accordance with the Project's Sustainability Plan, such as orienting street grids and open spaces to optimize solar exposure and to reduce winds; installing efficient light and HVAC systems; installing low-flow plumbing; and planting drought-tolerant species to minimize irrigation demands
- Create a development that is financially feasible, that allows for the delivery of the proposed level of infrastructure, public benefits, protections for existing tenants, and affordable housing, and that can fund the Project's capital costs and on-going operation and maintenance costs relating to the redevelopment and long-term operation of the Property.
- Create a level of development sufficient to support the costs of relocating and protecting existing tenants and sufficient to support the costs of the infrastructure improvements.

D. Environmental Review

The Project Sponsor applied for environmental review on January 8, 2008. Pursuant to and in accordance with the requirements of Section 21094 of the Public Resources and in accordance with Sections 15063

and 15082 of the CEQA Guidelines, the San Francisco Planning Department, as lead agency, prepared a Notice of Preparation ("NOP") on May 20, 2009, and held a Public Scoping Meeting on June 8, 2009.

The NOP was distributed to the State Clearinghouse and mailed to: governmental agencies with potential interest, expertise, and/or authority over the project; interested members of the public; and occupants and owners of real property surrounding the project area. The Public Scoping Meeting was held at the YMCA Annex, 3150 20th Avenue, San Francisco, CA 94132. Twenty-seven individuals spoke at the Public Scoping Meeting. During the public review period, 26 comment letters were submitted to the Planning Department by public agencies and other interested parties. The Public Scoping Summary Report is included as Appendix A of the Draft EIR. Commenters identified the following topics to be evaluated in the Draft EIR: Land Use; Aesthetics; Population and Housing; Historic Resources/Preservation; Transportation; Air Quality; Wind; Recreation and Open Space; Utilities (Water, Stormwater) and Sustainability; Biological Resources; Geology; Hazards; Hydrology and Water Quality; Hazards; and Alternatives.

The San Francisco Planning Department then prepared the Draft EIR, which describes the Project and the environmental setting, identifies potential impacts, presents mitigation measures for impacts found to be significant or potentially significant, and evaluates Project Alternatives. In assessing construction and operational impacts of the Project, the Draft EIR considers the impact of the Project and the cumulative impacts associated with the proposed Project in combination with other past, present, and future actions with potential for impacts on the same resources. Each environmental issue presented in the Draft EIR is analyzed with respect to significance criteria that are based on the San Francisco Planning Department Major Environmental Analysis Division ("MEA") guidance regarding the environmental effects to be considered significant. MEA guidance is, in turn, based on CEQA Guidelines Appendix G, with some modifications.

The Department published the Draft EIR on May 12, 2010. The Draft EIR was circulated to local, state, and federal agencies and to interested organizations and individuals for review and comment beginning on May 12, 2010 for a 61-day public review period, which ended on July 12, 2010. The San Francisco Planning Commission held a public hearing to solicit testimony on the Draft EIR on June 17, 2010. A court reporter was present at the public hearing, transcribed the oral comments verbatim, and prepared written transcripts. The Planning Department also received written comments on the Draft EIR, which were sent through mail, fax, or email.

The San Francisco Planning Department then prepared the Comments and Responses ("C&R"). This document, which provides written response to each comment received on the Draft EIR, was published on October 28, 2010 and included copies of all of the comments received on the Draft EIR and individual responses to those comments. The C&R provided additional, updated information and clarification on issues raised by commenters, as well as Planning Department staff-initiated text changes. This Commission reviewed and considered the Final EIR, which includes the Draft EIR, the C&R document and any Errata Sheets, and all of the supporting information and certified the Final EIR on February 10, 2010. In certifying the Final EIR, this Planning Commission determined that the Final EIR does not add

significant new information to the Draft EIR that would require recirculation of the Final EIR under CEQA because the Final EIR contains no information revealing (1) any new significant environmental impact that would result from the Project or from a new mitigation measure proposed to be implemented, (2) any substantial increase in the severity of a previously identified environmental impact, (3) any feasible project alternative or mitigation measure considerably different from others previously analyzed that would clearly lessen the environmental impacts of the Project, but that was rejected by the Project's proponents, or (4) that the Draft EIR was so fundamentally and basically inadequate and conclusory in nature that meaningful public review and comment were precluded.

D. Approval Actions

1. Planning Commission Actions

The Planning Commission is taking the following actions and approvals:

- Review and recommendation to the Board of Supervisors to approve an ordinance adopting a Development Agreement.
- Review and recommendation to the Board of Supervisors to approve an ordinance adopting a new Parkmerced SUD setting forth heights, bulk, density and uses.
- Review and recommendation to the Board of Supervisors to adopt an ordinance amending the San Francisco Zoning Map Height and Bulk Maps.
- Review and approval of amendments to the *General Plan* Urban Design Element height map for consistency with the proposed SUD.

2. Zoning Administrator Actions

- Determination of consistency with the Local Coastal Program and approval of a Coastal Zone Permit.

3. San Francisco Board of Supervisors Actions

The Planning Commission's certification of the Final EIR may be appealed to the Board of Supervisors. If appealed, the Board of Supervisors will determine whether to uphold the certification or to remand the Final EIR to the Planning Department for further review.

Additional actions to be taken by the Board of Supervisors include:

- Review and approval of an ordinance adopting a Development Agreement.
- Approval of amendments to the Planning Code Height and Bulk Maps and the *General Plan* Urban Design Element height map.
- Approvals to vacate existing streets and accept dedication of new streets.
- Review and approval of an ordinance adopting a new Parkmerced SUD setting forth heights, bulk, density and uses.

- Review of the proposed improvements to Brotherhood Way and other City streets and approval of those improvements.
- Request for amendment of the Local Coastal Program by the California Coastal Commission.

4. Other—Federal, State, and Local Agencies

Implementation of the Project will involve consultation with or required approvals by other local, state and federal regulatory agencies, including, but not limited to, the following:

- Department of Public Works (Approval of a subdivision map).
- Executive Director and Board of Directors of the Municipal Transit Agency (SFMTA) (Approval of the proposed realignment of the Muni M Ocean View light rail line through Parkmerced and other potential changes to the Municipal Railway system).
- California Department of Transportation [Caltrans] District 4, California Public Utilities Commission [CPUC] and San Francisco State University [SFSU] (Approval of the proposed realignment of the Muni M Ocean View light rail tracks across 19th Avenue into and out of the Project Site and other modifications to State Route 1 (Junipero Serra Boulevard), including installation of additional travel and turn lanes and reconfiguration of median landscaping).
- Department of Public Works and Planning Department (Review of the proposed improvements to Brotherhood Way and other City streets and approval of those improvements).
- SFMTA and the Transportation Advisory Staff Committee (TASC) (Coordination of all roadway and transit changes).
- California Department of Fish and Game (Issuance of an incidental take permit, if necessary, pursuant to Section 2081 of the California Endangered Species Act for operation of 51 wind turbines).
- California Coastal Commission approval of Coastal Zone Permits and for amendment of the Local Coastal Program.

U. S. Army Corps of Engineers (Issuance of a Section 404 Permit pursuant to the Clean Water Act for construction of an on-site stormwater filtration system and discharge of the filtered water to Lake Merced, if necessary). To the extent that the identified mitigation measures require consultation with or approval by these other agencies, the Planning Commission urges these agencies to assist in implementing, coordinating, or approving the mitigation measures, as appropriate to the particular measure.

E. Findings About Significant Environmental Impacts And Mitigation Measures

The following Sections II, III and IV set forth the Planning Commission's findings about the Final EIR's determinations regarding significant environmental impacts and the mitigation measures proposed to address them. These findings provide the written analysis and conclusions of the Planning Commission regarding the environmental impacts of the Project and the mitigation measures included as part of the Final EIR and adopted by the Planning Commission as part of the Project. To avoid duplication and

redundancy, and because the Planning Commission agrees with, and hereby adopts, the conclusions in the Final EIR, these findings will not repeat the analysis and conclusions in the Final EIR, but instead incorporates them by reference herein and relies upon them as substantial evidence supporting these findings.

In making these findings, the Planning Commission has considered the opinions of Department and other City staff and experts, other agencies and members of the public. The Planning Commission finds that the determination of significance thresholds is a judgment decision within the discretion of the City and County of San Francisco; the significance thresholds used in the Final EIR are supported by substantial evidence in the record, including the expert opinion of the EIR preparers and City staff; and the significance thresholds used in the Final EIR provide reasonable and appropriate means of assessing the significance of the adverse environmental effects of the Project.

These findings do not attempt to describe the full analysis of each environmental impact contained in the Final EIR. Instead, a full explanation of these environmental findings and conclusions can be found in the Final EIR and these findings hereby incorporate by reference the discussion and analysis in the Final EIR supporting the determination regarding the Project impacts and mitigation measures designed to address those impacts. In making these findings, the Planning Commission ratifies, adopts and incorporates in these findings the determinations and conclusions of the Final EIR relating to environmental impacts and mitigation measures, except to the extent any such determinations and conclusions are specifically and expressly modified by these findings.

As set forth below, the Planning Commission adopts and incorporates the mitigation measures set forth in the Final EIR and the attached MMRP, except as to mitigation measures specifically rejected in Section V below, to substantially lessen or avoid the potentially significant and significant impacts of the Project. The Planning Commission intends to adopt the mitigation measures proposed in the Final EIR, with the exception of those specifically rejected in Section V below. Accordingly, in the event a mitigation measure recommended in the Final EIR has inadvertently been omitted in these findings or the MMRP, such mitigation measure is hereby adopted and incorporated in the findings below by reference. In addition, in the event the language describing a mitigation measure set forth in these findings or the MMRP fails to accurately reflect the mitigation measures in the Final EIR due to a clerical error, the language of the policies and implementation measures as set forth in the Final EIR shall control. The impact numbers and mitigation measure numbers used in these findings reflect the information contained in the Final EIR.

In the Sections II, III and IV below, the same findings are made for a category of environmental impacts and mitigation measures. Rather than repeat the identical finding dozens of times to address each and every significant effect and mitigation measure, the initial finding obviates the need for such repetition because in no instance is the Planning Commission rejecting the conclusions of the Final EIR or the mitigation measures recommended in the Final EIR for the Project, except as specifically set forth in Section V below.

F. Location and Custodian of Records

The public hearing transcript, a copy of all letters regarding the Final EIR received during the public review period, the administrative record, and background documentation for the Final EIR are located at the Planning Department, 1650 Mission Street, San Francisco. The Planning Commission Secretary, Linda Avery, is the custodian of records for the Planning Department and the Planning Commission.

II. IMPACTS FOUND NOT TO BE SIGNIFICANT AND THUS DO NOT REQUIRE MITIGATION

Under CEQA, no mitigation measures are required for impacts that are less than significant (Pub. Resources Code, § 21002; CEQA Guidelines, §§ 15126.4, subd. (a)(3), 15091.). Based on the evidence in the whole record of this proceeding, the Planning Commission finds that implementation of the Proposed Project will not result in any significant impacts in the following areas and that these impact areas therefore do not require mitigation:

Land Use

- Physically divide an established community or have a substantial adverse impact on the character of the vicinity.
- Create incompatible cumulative land use impacts on established communities.

Aesthetics

- Transform the visual character of the Project Site.
- Affect scenic vistas from publicly accessible areas.
- Be a prominent new visual feature at the western perimeter of the Project Site (wind turbines).
- Increase the lighting requirements within the Project Site and the potential for glare.
- Contribute to cumulative impacts on visual quality and scenic vistas.

Population and Housing

- Induce substantial direct temporary population growth during project construction.
- Induce substantial employment growth in an area either directly or indirectly.
- Displace substantial numbers of people and/or existing housing units or create demand for additional housing, necessitating the construction of replacement housing.
- Induce substantial project-level or cumulative population growth in the area either directly or indirectly.

Transportation and Circulation

- Create significant traffic impacts at four study intersections (*19th Avenue/Juniper Serra Boulevard; 19th Avenue/Ocean Avenue; Brotherhood Way/West Driveway Holy Trinity Greek Orthodox and Open Bible Churches; John Muir Drive/Lake Merced Boulevard*) that operate at LOS E or LOS F under Existing Conditions.

- Add transit trips to the Downtown Screenlines in excess of available capacity (Project). (Downtown Screenlines examine the overall utilization of Muni transit capacity into and out of downtown San Francisco from the northeast, northwest, and southwest of San Francisco.)
- Add transit trips to the Downtown Screenlines, but would not increase demands in excess of available capacity (Project sub-variant).
- Add transit trips to the Regional Screenlines in excess of available capacity and contribute significantly to Regional Screenlines where overall ridership is projected to exceed available capacity (Project). (Regional Screenlines examine regional transit service for the locations where different regional transit services enter San Francisco.)
- Add transit trips to the Regional Screenlines, but would not increase demands in excess of available capacity (Project sub-variant).
- Create a significant impact due to the construction of bicycle facilities within the Project Site to serve additional users.
- Create a significant impact due to the construction of pedestrian facilities within the Project Site to serve additional users.
- Create a significant impact due to an increase the need for loading spaces.
- Affect air traffic.
- Create hazards due to any proposed design features.
- Result in significant emergency access impacts.
- Significantly contribute traffic at six study intersections (*Junipero Serra Boulevard/Ocean Avenue/Eucalyptus Drive; 19th Avenue/Junipero Serra Boulevard; 19th Avenue/Ocean Avenue; 19th Avenue/Eucalyptus Drive; Brotherhood Way/West Driveway Holy Trinity Greek Orthodox and Open Bible Churches; and Holloway Avenue/Varela Avenue*) that would operate at LOS E or F under 2030 cumulative conditions.
- Contribute to cumulative increases in transit ridership at the Downtown Screenlines so as to exceed available capacity.
- Contribute to cumulative increases in transit ridership at the Downtown Screenlines so as to exceed available capacity (Project sub-variant).
- Contribute to cumulative increases in transit ridership at the Regional Screenlines so as to increase demand in excess of available capacity or contribute significantly to Regional Screenlines where overall cumulative ridership is projected to exceed available capacity.
- Contribute to cumulative increases in transit trips to the Regional Screenlines so as to increase demand in excess of available capacity or contribute significantly to Regional Screenlines where overall cumulative ridership is projected to exceed available capacity (Project sub-variant).

Air Quality

- Result in localized construction dust-related air quality impacts.
- Affect regional air quality due to Project construction (*But see Impact AQ-II, regarding 2010 BAAQMD Guidelines, Significant and Unavoidable Impact*).

- Result in a substantial amount of vehicle trips that could cause or contribute to an exceedance of the CO ambient air quality standards due to Project operation.
- Expose sensitive receptors to substantial concentrations of toxic air contaminants due to Project operation (*But see Impact AQ-12 and Impact AQ-15, regarding 2010 BAAQMD Guidelines, Significant and Unavoidable Impact*).
- Result in operation-related impact to CO ambient air quality standards under 2010 BAAQMD Guidelines.
- Generate significant odors.
- Conflict with adopted plans related to air quality.

Greenhouse Gas Emissions

- Result in a substantial contribution to global climate change by increasing GHG emissions in a manner that conflicts with the state goal of reducing GHG emissions in California to 1990 levels by 2020 (e.g., a substantial contribution to global climate change).
- Conflict with San Francisco's Climate Action Plan or impede implementation of the local GHG reduction goals established by the San Francisco 2008 Greenhouse Gas Reduction Ordinance.

Wind and Shadow

- Result in an increase in the number of hours that the 26-mph wind hazard criterion is exceeded or an increase in the area that is subjected to winds greater than 26 mph (Representative project only, not the proposed SUD).
- Would not result in a cumulative increase in the number of hours that the 26-mph wind hazard criterion is exceeded or an increase in the area that is subjected to winds greater than 26 mph (Representative project only, not the proposed SUD).
- Adversely affect the use of any park or open space under the jurisdiction of the Recreation and Park Commission.
- Create new shadow in a manner that substantially affects outdoor recreation facilities or other public areas.
- Cumulatively adversely affect the use of any park or open space under the jurisdiction of the Recreation and Park Commission or create new shadow in a manner that substantially affects outdoor recreation facilities or other public areas.

Recreation

- Increase the use of existing park and recreational facilities to such an extent that there would be a significant adverse effect on these facilities.
- Significantly contribute to cumulative impacts on recreational use to existing public parks or recreational facilities.

Utilities and Services Systems

- Increase the demand for water to such an extent that there would be a significant adverse impact.

- Contribute considerably to significant cumulative impacts on water supply.
- Require new water delivery infrastructure to adequately serve the Project Site.
- Cumulatively result in for a need for new water delivery infrastructure.
- Require new or expansion of wastewater collection or treatment facilities to adequately serve the Project Site.
- Contribute considerably to cumulative impacts on wastewater conveyance and treatment due to Project operation.
- Exceed the solid waste disposal capacity of the Project-serving landfill.
- Contribute considerably to cumulative impacts on solid waste disposal facilities.

Public Services

- Result in a need for new or physically altered facilities in order to maintain acceptable service ratios, response times, or other performance objectives for police protection.
- Cumulatively result in a need for new or physically altered facilities in order to maintain acceptable service ratios, response times, or other performance objectives for police protection.
- Result in a need for new or physically altered facilities in order to maintain acceptable service ratios, response times, or other performance objectives for fire protection and emergency medical services.
- Cumulatively result in a need for new or physically altered facilities in order to maintain acceptable service ratios, response times, or other performance objectives for fire protection and emergency medical services.
- Result in additional demand for educational facilities, either at the project-level or cumulatively.
- Cumulatively result in the additional demand for educational facilities.

Biological Resources

- Conflict with local policies or ordinances protecting biological resources.
- Result in substantial adverse cumulative effects to biological resources.

Geology and Soils

- Expose people or structures to potential adverse effects due to ground shaking, ground failure, or liquefaction.
- Be located on unstable soil, or could become unstable as a result of the Proposed Project, and potentially result in soil instability or soil corrosivity.
- Be located on corrosive soils.
- Result in significant cumulative impacts with respect to geology, soils or seismicity.

Hydrology and Water Quality

- Result in an increase of combined sewer overflows from the City's combined sewer system.
- Result in depletion of groundwater or reduction of groundwater levels.

- Contribute runoff water due to Project operation that would exceed the capacity of the existing stormwater drainage system or create substantial additional sources of polluted runoff due to Project operation.
- Place housing or structures within a 100-year flood hazard area or expose people or structures to a significant risk involving flooding.
- Be susceptible to inundation by seiche, tsunami, or mudflow.
- Contribute significantly to cumulative impacts on hydrology and water quality due to Project construction.

Hazards and Hazardous Materials

- Create a hazard to the public or the environment through the routine transport, use, or disposal of hazardous materials.
- Result in hazardous emissions or use of hazardous or acutely hazardous materials, substances, or waste within one-quarter mile of an existing or proposed school.
- Impair implementation of or physically interfere with an adopted emergency response plan or emergency evacuation plan.
- Expose people or structures to a risk of loss, injury or death involving fires.
- Result in cumulative hazardous materials impacts.

Mineral and Energy Resources

- Result in the loss of availability of a known mineral resource and/or a locally important mineral resource recovery.
- Encourage activities that could result in the use of large amounts of fuel, water, or energy, or use these in a wasteful manner.

Agricultural Resources and Forest Lane

- Result in the conversion of farmland, or involve other changes that would result in conversion of farmland to non-agricultural use.
- Result in conflicts with existing zoning for agricultural use or Williamson Act contracts.
- Negatively affect forests or timberland.

III. FINDINGS OF POTENTIALLY SIGNIFICANT IMPACTS THAT CAN BE AVOIDED OR REDUCED TO A LESS-THAN-SIGNIFICANT LEVEL THROUGH MITIGATION AND THE DISPOSITION OF THE MITIGATION MEASURES

CEQA requires agencies to adopt mitigation measures that would avoid or substantially lessen a project's identified significant impacts or potential significant impacts if such measures are feasible (unless mitigation to such levels is achieved through adoption of a project alternative). The findings in this Section III and in Section IV concern mitigation measures set forth in the EIR. These findings discuss mitigation measures and improvement measures as identified in the Final EIR for the Proposed Project. The full text of the mitigation measures and improvement measures is contained in the Final EIR and in Attachment B, the Mitigation Monitoring and Reporting Program. The Planning Commission finds that

the impacts identified in this Section III would be reduced to a less-than-significant level through implementation of the mitigation measures contained in the Final EIR, included in the Proposed Project, or imposed as conditions of approval and set forth in Attachment B.

This Commission recognizes that some of the mitigation measures are partially within the jurisdiction of other agencies. The Commission urges these agencies to assist in implementing these mitigation measures, and finds that these agencies can and should participate in implementing these mitigation measures.

Impact CR-3: Project construction activities could disturb significant archaeological resources, if such resources are present within the Project Site.

There is a reasonable presumption that significant subsurface archaeological features are present within the Project Site. For example, Lake Merced would have provided resources for native Ohlone people, resulting in the possibility of subsurface artifacts. Historical accounts indicate that the Mission San Francisco de Asis used the Lake Merced area as a corral for mission-owned livestock. Following Mission ownership, a Spanish cattle rancher may have had a corral in the vicinity of the Project Site. The Spring Valley Water company operated a pump station at Lake Merced, and two dwellings associated with this pump station were reported to be located on the Project Site. If subsurface artifacts encountered during construction of the Proposed Project were not appropriately handled, it could be a significant impact.

Mitigation Measure M-CR-3a: Archaeological Testing, Monitoring, Data Recovery, and Reporting for Phase I

Mitigation Measure M-CR-3b: Archaeological Treatment Plan for Subsequent Project Phases

Impact CR-4: Project construction activities could disturb human remains, if such resources are present within the Project Site.

Prehistoric human burials could be encountered if Native Americans used the area near Lake Merced. Loss of these materials during construction would be a significant impact.

Mitigation Measure M-CR-4a: Archaeological Testing, Monitoring, Data Recovery, and Reporting for Phase I

Mitigation Measure M-CR-4b: Archaeological Treatment Plan for Subsequent Project Phases

Impact CR-5: Project construction activities could disturb paleontological resources.

Project construction activities could disturb significant paleontological resources, if such resources are present within the site in the sedimentary Colma Formation, which has yielded vertebrate fossils in other locations on the San Francisco peninsula. This would be a significant impact.

Mitigation Measure M-CR-5: Paleontological Resources Monitoring and Mitigation Program

Impact CR-6: Disturbance of archaeological and paleontological resources within the Project Site could contribute to a cumulative loss in the ability of the site to yield significant historic and scientific information.

When considered with other past and proposed development projects along and near the San Francisco shoreline, the disturbance of archaeological and paleontological resources within the Project Site could contribute to this cumulative loss.

Mitigation Measure M-CR-3a: Archaeological Testing, Monitoring, Data Recovery, and Reporting for Phase I

Mitigation Measure M-CR-3b: Archaeological Treatment Plan for Subsequent Project Phases

Mitigation Measure M-CR-5: Paleontological Resources Monitoring and Mitigation Program

Impact TR-2: Implementation of the Proposed Project would result in significant traffic impacts at study intersections (Less-Than-Significant with Mitigation for the intersection at 19th Avenue/Crespi Drive only)

The project's impacts at the intersection of 19th Avenue/Crespi Drive would be due primarily to the new northbound left-turn lane from 19th Avenue to Crespi Drive, proposed as part of the Project.

Mitigation Measure M-TR-2A: Do not construct the proposed northbound left-turn lane from 19th Avenue onto Crespi Drive

Impact TR-3b: Implementation of the Proposed Project would contribute to significant cumulative traffic impacts at 14 study intersections (Less-Than-Significant with Mitigation for the intersection at 19th Avenue/Crespi Drive only)

The project's contribution to a cumulative impact at the intersection of 19th Avenue/Crespi Drive would be due primarily to the new northbound left-turn lane from 19th Avenue to Crespi Drive, proposed as part of the Project.

Mitigation Measure M-TR-2A: Do not construct the proposed northbound left-turn lane from 19th Avenue onto Crespi Drive

Impact TR-21: The Proposed Project would reroute the M Ocean View light rail line into the Project Site, extending its route and imparting an additional five minutes of travel time to complete each run. Without additional light rail vehicles, Muni could not operate this longer route at current headways.

The Proposed Project's extension of the light rail route into Parkmerced would make the route longer, reducing transit capacity. This would be a significant impact. Although this impact was identified in the Draft EIR as significant and unavoidable due to uncertainty with regard to whether the proposed

mitigation measures were feasible, (see DEIR p. V.E.88) the SFMTA has subsequently determined that Mitigation Measure M-TR-21A is feasible.

M-TR-21A: Purchase an additional two-car light rail vehicle for the M Ocean View.

Or

M-TR-21B: Install Transit Signal Priority (TSP) treatments to improve transit travel times on the M Ocean View such that M-TR-21A (an additional vehicle) is not required.

Implementing either mitigation measure would maintain transit headways and reduce the impact to less-than-significant levels. Although implementation of M-TR-21A is feasible, implementation of measure M-TR-21B is preferred because it would maintain transit headways and improve travel times for riders. Implementation of measure M-TR-21B would require feasibility studies and discretionary actions by SFMTA and Caltrans and is therefore uncertain at this time. Because either mitigation measure would reduce the impact to a less-than-significant level, and because it is known at this time that M-TR-21A is feasible, this impact can be mitigated to a less-than-significant level. Because M-TR-21B appears preferable, the Commission urges SFMTA and Caltrans to perform feasibility studies and implement measure M-TR-21B if feasible, and if not feasible, requires implementation of M-TR-21A.

Impact NO-1: Project-related construction activities would increase noise levels above existing ambient conditions.

Construction noise would be substantially greater than existing ambient noise levels and would have the potential to result in significant impacts to existing sensitive receptors. Although proposed construction activities would occur over a period of approximately 20 years, the activities that would impact sensitive receptors in any one location would be temporary. Construction contractors would be required to comply with the San Francisco Noise Ordinance. Additional mitigation would be needed to reduce noise levels to a less than significant level.

Mitigation Measure M-NO 1a: Reduce Noise Levels During Construction

Mitigation Measure M-NO 1b: Pile Driving Noise-Reducing Techniques and Muffling Devices

Impact NO-2: Construction activities could expose persons and structures to excessive ground-borne vibration or ground-borne noise levels.

Impact activities such as pile driving could produce detectable vibration within nearby buildings during construction, and could be detectable by sensitive receptors. This could be a significant impact.

Mitigation Measure M-NO-2: Pre-construction Assessment to Minimize Vibration Levels Associated with Impact Activities.

Impact NO-6: Proposed residences and other sensitive uses would be located in incompatible noise environments.

Existing noise levels exceed 65 dBA (Ldn) in some locations. The Land Use Compatibility Guidelines for Community Noise (see Figure V.F.2) indicate that any new residential construction in areas with noise levels above 65 dBA (Ldn) must have a detailed analysis of noise reduction requirements is made and needed noise insulation features are included in the design. The Land Use Compatibility Guidelines indicate that analysis of noise reduction features should occur for the proposed Pre-K-5 school and day care facility. Without adequate design, these uses could be subject to significant impacts due to traffic-generated noise.

Mitigation Measure M-NO-6: Residential Use Plan Review by Qualified Acoustical Consultant

Impact NO-8: Garbage collection would occur at different locations and could increase associated noise levels at elevated receivers.

When garbage is collected, the residences nearest and overlooking refuse containers would experience higher noise levels than the more distant units. In some locations this would be a significant noise impact unless it is accounted for in building design.

Mitigation Measure M-NO-8: Residential Building Plan Review by Qualified Acoustical Consultant

Impact BI-1: Construction of an outfall for discharge of stormwater runoff into the willow basin could affect the habitat of San Francisco gumplant and other special-status plant species.

Construction activities in the willow basin south of Brotherhood Way where stormwater from the Project Site may flow prior to discharge to Lake Merced could impact an existing population of San Francisco gumplant, which is considered rare or endangered in California and elsewhere. Impacting the designated gumplant would be significant.

Mitigation Measure M-BI-1a: Pre-construction Survey for Gumplant

Mitigation Measure M-BI-1b: Avoidance During Construction

Mitigation Measure M-BI-1c: Restoration and Expansion of Gumplant Population That Is Not Avoided in Measure M-BI-1b

Impact BI-2: Construction of an outfall for stormwater runoff into Lake Merced could affect habitats of special-status animal species.

If discharge of treated stormwater to Lake Merced is implemented, construction of a new outfall or restoration of an existing outfall into the Lake could impact the habitat of the salt marsh common yellowthroat or the western pond turtle, both California Species of Special concern, which would be a significant impact.

Mitigation Measure M-BI-2a: Pre-construction Survey for Common Yellowthroat Nesting Activities and Buffer Area

Mitigation Measure M-BI-2b: Monitoring for Western Pond Turtles During Construction

Mitigation Measure M-BI-2c: SWPPP Design Details for Site Drainage and Water Quality Control in Outfall Construction Area

Impact BI-3: Construction of a new stormwater outfall, or restoration of an existing one, would affect freshwater marsh and other riparian habitat along the shore of Lake Merced and in the willow basin.

To repair the existing stormwater outfall(s) at the shoreline of Lake Merced, or to install a new one(s), marsh and riparian vegetation, such as willow and wax myrtle trees, would be removed from the construction zone. This is a potentially significant impact.

Mitigation Measure M-BI-2c: SWPPP Design Details for Site Drainage and Water Quality Control in Outfall Construction Area

Mitigation Measure M-BI-3a: Restrict Vegetation Removal Activities in Wetland and Riparian Areas During Outfall Construction

Mitigation Measure M-BI-3b: Vegetation Restoration in Outfall Construction Area

Impact BI-4: Removing trees and shrubs could remove migratory bird habitat and impede the use of nesting (nursery) sites.

Vegetation removal and/or building demolition during the breeding season (approximately March through August) could remove trees, shrubs, and/or buildings that support active nests. This is a potentially significant impact.

Mitigation Measure M-BI-4: Breeding Bird Pre-construction Surveys and Buffer Areas

Impact BI-5: The Proposed Project could have an adverse effect on wetlands as defined by Section 404 of the Clean Water Act.

To repair the existing stormwater outfall(s) at the shoreline of Lake Merced or to install a new one(s), marsh and riparian vegetation would be removed from a construction zone and directing stormwater from the Project Site to the willow basin prior to discharge to Lake Merced could affect riparian vegetation, including wetlands, which would be a significant impact.

Mitigation Measure M-BI-2c: SWPPP Design Details for Site Drainage and Water Quality Control in Outfall Construction Area

Mitigation Measure M-BI-3a: Restrict Vegetation Removal Activities in Wetland and Riparian Areas During Outfall Construction

Mitigation Measure M-BI-3b: Vegetation Restoration in Outfall Construction Area

Impact BI-7: Maintenance of the proposed stormwater treatment system (bioswales, constructed stream, wetlands, and ponds) could affect special-status animal species.

The proposed on-site stormwater treatment bioswales, stream, wetlands, and ponds would be planted with native wetland and riparian vegetation that would support native wildlife, including special-status species such as western pond turtle, and protected nesting birds. Although this would be considered a beneficial impact and an enhancement of habitat values, periodic vegetation or sediment removal for maintenance of the treatment system could adversely impact those species, which is a potentially significant impact.

Mitigation Measure M-BI-7a: Pre-maintenance Surveys for Active Bird Nests and Buffer Areas

Mitigation Measure M-BI-7b: Monitoring During Maintenance Activities

Impact BI-9: Construction of new building towers could adversely impact bird or bat movement and migration.

The proposed new high-rise towers could result in bird injuries and death from collisions with glass panels or windows. This would be a significant impact.

Mitigation Measure M-BI-9: Bird-Safe Design Practices

Impact BI-10: Changes in duration and depth of inundation in the willow basin from stormwater runoff could impact riparian vegetation.

The large specimens of wax myrtle growing in the bottom of the willow basin may not be able to withstand an increase in inundation depth or duration. Although wax myrtle is not a special-status plant species, these trees provide a locally unique component of the sensitive riparian habitat in the willow basin and an increase in inundation depth and duration may adversely affect them, which could be a significant impact.

Mitigation Measure M-BI-10: Study and Modification to Willow Basin To Control Water Level and Duration of Inundation

Impact GE-1: The Proposed Project could result in substantial soil erosion or loss of topsoil during construction.

Existing ground coverings would be removed during construction, exposing soil to wind and rainwater runoff erosion. This is a potentially significant impact.

Mitigation Measure HY-1: Best Management Practices for SWPPP

Impact HY-1: The Proposed Project could violate a water quality standard or a waste discharge requirement, or otherwise substantially degrade water quality.

During construction of the Proposed Project, existing vegetation and pavements would be temporarily removed and surface soils would be disturbed due to excavation and grading activities on the Project Site. Stormwater runoff could cause erosion and entrainment of sediments from the exposed soils. If not managed properly, the sediments would be carried in watercourses and cause sediments to be discharged to the sewer system where they would reduce the capacity of the sewer lines, potentially causing sewer overflows. The potential for releases of fuels, oils, paints, and solvents is present at most construction sites. Once released, these chemicals would flow or be carried by stormwater runoff, wash water, and dust control water to the sewer, potentially reducing the quality of the receiving waters. This would be a significant impact.

Mitigation Measure M-HY-1: Best Management Practices for SWPPP

Impact HY-4: The Proposed Project could alter the existing drainage patterns on the Project Site, resulting in substantial erosion or siltation or localized flooding.

Excavation and grading of the Project Site during the construction phases of the Proposed Project would remove existing vegetation and pavements, thus exposing the sandy soil of the Project Site to erosion by runoff, which could be a significant impact.

Mitigation Measure M-HY-1: Best Management Practices for SWPPP

Impact HZ-2: The Proposed Project could create a hazard to the public or the environment through the accidental release of hazardous materials into the environment.

A limited Phase II Environmental Site Assessment investigation was conducted, and soil samples showed minimal evidence of chemical releases from the former maintenance activities in the vicinity of the Maintenance Building and the fan room at the Higuera parking garage. The concentrations of chemicals detected do not pose a threat to human health or the environment based on U.S. Environmental Protection Agency Region IX health-based screening values. Further, the concentrations are below levels that typically may lead to a requirement for cleanup by regulatory agencies, and thus are not considered significant environmental concerns. Although soil contamination in significant amounts is not expected, if previously unidentified soil contaminants exist, hazardous materials could be released into the environment, resulting in a significant impact.

Mitigation Measure M-HZ-2A: Hazardous Materials – Testing for and Handling of Contaminated Soil

Mitigation Measure M-HZ-2B: Hazards – Decontamination of Vehicles

IV. SIGNIFICANT IMPACTS THAT CANNOT BE AVOIDED OR REDUCED TO A LESS-THAN-SIGNIFICANT LEVEL

Based on substantial evidence in the whole record of these proceedings, the Planning Commissions finds that, where feasible, changes or alterations have been required, or incorporated into, the Proposed Project to reduce the significant environmental impacts as identified in the Final EIR and listed below. The Commission finds that the mitigation measures in the Final EIR and described below are appropriate, and that changes have been required in, or incorporated into, the Proposed Project that, pursuant to Public Resources Code Section 21002 and CEQA Guidelines Section 15091, may substantially lessen, but do not avoid (i.e., reduce to less-than-significant levels), the potentially significant environmental effects associated with implementation of the Proposed Project that are described below. The Commission adopts all of the mitigation measures and improvement measures set forth in the Mitigation Monitoring and Reporting Plan (MMRP), attached as Attachment B. The Commission further finds, however, for some of the impacts listed below, despite the implementation of feasible mitigation measures and improvement measures, the effects remain significant and unavoidable.

Based on the analysis contained within the Final EIR, other considerations in the record, and the significance criteria identified in the Final EIR, the Planning Commission finds that because some aspects of the Proposed Project could cause potentially significant impacts for which feasible mitigation measures are not available to reduce the impact to a less-than-significant level, those impacts are significant and unavoidable. The Planning Commission recognizes that although mitigation measures are identified in the Final EIR that would reduce some significant impacts, the measures are uncertain or infeasible for reasons set forth below, and therefore those impacts remain significant and unavoidable or potentially significant and unavoidable.

The Planning Commission determines that the following significant impacts on the environment, as reflected in the Final EIR, are unavoidable, but under Public Resources Code Section 21081(a)(3) and (b), and CEQA Guidelines 15091(a)(3), 15092(b)(2)(B), and 15093, the Commission determines that the impacts are acceptable due to the overriding considerations described in Section VII below. This finding is supported by substantial evidence in the record of this proceeding.

Impact AE-1: The proposed demolition of the existing garden apartment buildings and the proposed removal of the existing landscaping would eliminate a visual/scenic resource of the built environment.

To implement the Proposed Project, all of the two-story garden apartment buildings within the Project Site (170 buildings) would be demolished, along with existing landscaping and mature trees throughout most of the Project Site, thereby eliminating a visual/scenic resource of the built environment. Due to extensive reconstruction and regrading on the Project Site, about 82 percent of trees would be removed from the Project Site or relocated throughout the planned 20-year phased construction period. These changes are significant impacts.

No feasible mitigation is available that would preserve most of the existing visual character of the Project Site yet allow the Proposed Project to be substantially implemented. Demolition of most of this visual/scenic resource is necessary to implement the Proposed Project and realize its objectives, which include provision of high-density housing and implementation of environmentally sustainable design practices. The Proposed Project could not be implemented without demolition of most of the existing visual/scenic resource. Therefore, this impact remains significant and unavoidable and no mitigation measures are available.

Impact CR-1: The proposed demolition of the existing garden apartment buildings and removal of existing landscape features on the Project Site would impair the historical significance of the Parkmerced historic district historical resource.

The Parkmerced residential complex is eligible for inclusion in the California Register of Historical Resources as a historic district. Demolition of all of the two-story garden apartment buildings and removal of all of the interior landscaping on the Project Site would be a significant impact.

Mitigation Measure M-CR-1: Documentation and Interpretation

Implementation of this mitigation measure would not be sufficient to reduce the significant impact to less-than-significant levels. The impact remains significant and unavoidable. No feasible mitigation is available that would preserve the essential integrity of the Parkmerced complex and still allow the Proposed Project to be implemented, as demolition of most of the historical resource is necessary for implementation.

Impact CR-2: The proposed demolition of the existing garden apartment buildings and removal of existing landscape features on the Project Site would contribute to a cumulative impact on the historic significance of the Parkmerced historic district historical resource.

The Parkmerced historic district resource encompasses the entire original Parkmerced complex, including the Project Site and three properties owned by others. The owners of the other three properties are planning for future redevelopment of their respective parcels, which, in combination with the Proposed Project, would result in a significant cumulative impact.

Mitigation Measure M-CR-1: Documentation and Interpretation

Implementation of this mitigation measure would reduce the contribution of the Proposed Project to significant cumulative impacts on historical resources, but not to a less-than-significant level. No feasible mitigation is available that would preserve the integrity of the Parkmerced complex. Therefore, the impact remains significant and unavoidable.

Impact TR-1: Construction of the Proposed Project (with or without the proposed sub-variant) would result in transportation impacts in the Proposed Project vicinity due to construction vehicle traffic and road construction associated with the realignment of the existing light rail tracks.

The primary construction truck routes in the Project Study Area would be Lake Merced Boulevard, Brotherhood Way, 19th Avenue, and Junipero Serra Boulevard. During the construction period, temporary and intermittent disruption to existing and proposed transit routes and bus stops may occur, and some bus routes may need to be temporarily rerouted. In addition, temporary and intermittent interference with transit operations caused by increased truck movements to and from the construction sites may occur. Due to the reduction in travel lanes, the remaining travel lanes would become more congested with automobiles, trucks and buses, which would pose a greater challenge for bicycle travel in the area. Given the magnitude of development proposed for the area, the Proposed Project's prolonged construction period, and the lack of certainty about the timing of other development projects in the area, significant Project-related and significant Project contributions to cumulative traffic and circulation impacts could occur on some roadways, such as Lake Merced Boulevard, Brotherhood Way, 19th Avenue, and Junipero Serra Boulevard. Implementation of individual traffic control plans would minimize impacts associated with each project and reduce each project's contribution to cumulative impacts in the Study Area.

Mitigation Measure M-TR-1: Parkmerced Construction Traffic Management Program

Given the magnitude of the proposed development and the duration of the construction period, some disruptions and increased delays could still occur even with implementation of M-TR-1, and it is possible that significant construction-related transportation impacts on local San Francisco and regional roadways could still occur. Construction-related transportation impacts therefore remain significant and unavoidable.

Impact TR-2: Implementation of the Proposed Project would result in significant traffic impacts at study intersections.

Of the 34 study intersections, 13 are projected to operate at unacceptable levels of service (LOS) under existing conditions with the Proposed Project during at least one peak hour. At 6 of the 13 study intersections with unacceptable operations, the Proposed Project would result in project-specific impacts:

- 19th Avenue/Sloat Boulevard – LOS E to LOS F in the AM peak hour;
- 19th Avenue/Winston Drive – LOS D to LOS E in the weekend midday peak hour;
- Sunset Boulevard/Lake Merced Boulevard – LOS C to LOS E in the PM peak hour;
- Lake Merced Boulevard/Winston Drive – LOS C to LOS E in the AM peak hour and LOS D to LOS F in the PM peak hour;
- Lake Merced Boulevard/Font Boulevard – LOS D to LOS F in the AM peak hour and LOS C to LOS F in the PM peak hour; and
- Lake Merced Boulevard/Brotherhood Way – LOS D to LOS E in the AM peak hour, LOS C to LOS F in the PM peak hour, and LOS C to LOS E in the weekend midday peak hour.

Mitigation measures to reduce significant impacts at the intersections of 19th Avenue/Sloat Boulevard and 19th Avenue/Winston Drive are infeasible. Additional travel lanes would be needed along 19th Avenue at both intersection, requiring acquisition of substantial additional right-of-way and demolition of existing occupied structures. In addition, 19th Avenue is under the jurisdiction of the California Department of Transportation (Caltrans) and outside of the jurisdiction or control of the Planning Commission.

Widening the 19th Avenue roadway would increase the pedestrian crossing distance at both intersections, which is inconsistent with San Francisco's goal of improving pedestrian circulation and safety in the Parkmerced Study Area. At the 19th Avenue/Winston Drive intersection, restriping the eastbound shared through-left-turn lane as a dedicated left-turn lane would result in a dual left-turn lane configuration; and would improve LOS to acceptable levels without widening the roadway and would improve LOS. However, it would present a pedestrian safety conflict by providing a dual left-turn lane operating on the same phase as a conflicting crosswalk with high pedestrian volumes at the entrance to a major shopping center. Therefore, implementation of such a measure would be inconsistent with the City's goals of promoting walking and bicycling and is infeasible.

Mitigation measures are available to reduce significant impacts to less-than-significant levels at the remainder of the identified intersections. However, in a number of cases the mitigation measure is infeasible or the feasibility of mitigation is uncertain and requires additional discretionary actions by other agencies and/or additional feasibility studies by other agencies outside of the City's jurisdiction prior to implementation.

Mitigation Measure M-TR-2B: Install a traffic signal at Sunset Boulevard/Lake Merced Boulevard

Implementation of this mitigation measure would reduce significant impacts at the intersection of Sunset Boulevard/Lake Merced Boulevard to less-than-significant levels; however, the San Francisco Municipal Transportation Agency (SFMTA) has evaluated the feasibility of this measure and has found that it is infeasible due to specific economic, legal, social, technological, and other considerations, as more fully set forth in Section V below. Because this mitigation measure is infeasible, the impact remains significant and unavoidable.

Mitigation Measure M-TR-2C: Construct a dedicated northbound right-turn lane from Lake Merced Boulevard to eastbound Winston Drive

Full implementation of this measure is uncertain due to the adjacent unsignalized intersection, approximately 75 feet south of Winston Drive, which would conflict with the northbound right-turn lane. Further study by SFMTA is required to determine whether full implementation of this mitigation measure is feasible. If feasible, implementation of this measure would reduce significant impacts at the intersection of Lake Merced Boulevard/Winston Drive to less-than-significant levels. Because the efficacy of this measure to fully reduce the impact to less-than-significant levels is currently uncertain, the impact remains significant and unavoidable.

Mitigation Measure M-TR-2D: Provide a third northbound through lane and a second southbound left-turn lane at the Lake Merced Boulevard/Font Boulevard intersection

The measure would improve operations at the intersection of Lake Merced Boulevard/Font Boulevard to acceptable levels and the impact would be less than significant. The feasibility of this measure is uncertain, as substantial roadway restriping and signal optimization and coordination at multiple additional intersections would be necessary. In addition, provision of dual left-turn lanes against a pedestrian signal may be considered a safety hazard for pedestrians. Further study by SFMTA is required

to determine feasibility of full implementation of this measure. Because the feasibility of this measure is currently uncertain, the impact remains significant and unavoidable.

Mitigation Measure M-TR-2E: Reconfigure the westbound right-turn and southbound left-turn as the primary movements of the intersection at the Lake Merced Boulevard/Brotherhood Way

The SFMTA has determined that this mitigation measure is feasible; however, the intersection would continue to operate at an unacceptable LOS F during both the AM and PM peak hours even with implementation of this measure. Therefore, although operations would be substantially improved, this impact remains significant and unavoidable even with mitigation.

Impact TR-3: Implementation of the Proposed Project would result in considerable traffic contributions at study intersections that operate at LOS E or LOS F under Existing Conditions

Vehicle trips generated by the Proposed Project would contribute significantly to critical movements at two intersections that currently operate at unacceptable LOS E or F. This is a significant traffic impact.

- Junipero Serra Boulevard/Sloat Boulevard/St. Francisco Boulevard/Portola Drive – LOS F during the weekday PM peak hour and weekend midday peak hour.
- Junipero Serra Boulevard/John Daly Boulevard/I-280 Northbound On-Ramp/I-280 Southbound Off-Ramp/SR 1 Northbound On-Ramp – LOS F during the weekday PM peak hour

No feasible mitigation measures are available to reduce the Proposed Project's contribution to unacceptable levels of service at these intersections. At the Junipero Serra/Sloat/St. Francis/Portola complex intersection, the presence of the M Ocean View and K Ingleside light rail tracks in the center median and the constrained right-of-way makes addition of more travel lanes infeasible. Acquisition of substantial right-of-way and demolition of existing privately-owned and occupied structures, reducing the City's tax base, would be required. In addition, a wider intersection would increase pedestrian crossing distances across Junipero Serra Boulevard, which is inconsistent with the City's goal of improving pedestrian circulation and safety. Therefore, the impact at this intersection is significant and unavoidable.

At the Junipero Serra/I-280 Ramps/SR-1 Ramp intersection, the complex geometry of the intersection and constrained environment make additional lanes infeasible. Considerable additional right-of-way would be necessary, requiring acquisition of private property and demolition of occupied structures. In addition, this location is in Daly City, and the I-280 Ramps are under the jurisdiction of Caltrans; both are outside the jurisdiction of the City and County of San Francisco. Therefore, the impact at this intersection is significant and unavoidable.

Impact TR-6: Implementation of the sub-variant in conjunction with the Proposed Project would result in the same traffic impacts at study intersections as identified in Impacts TR-2, TR-3, and TR-4 for conditions with the Proposed Project.

The sub-variant would include a right-turn ingress from 19th Avenue into the Project Site at Cambon Drive for southbound vehicles; no access from the Project Site to 19th Avenue would be provided. Impact TR-4 would be less-than-significant with the Proposed Project, as listed in Section II above. With the sub-variant, impacts TR-2 and TR-3 remain significant and unavoidable as discussed above.

Impact TR-8: Implementation of the Proposed Project would result in significant traffic impacts on one freeway segment.

The freeway mainline segment on southbound State Route 1 (SR 1, Junipero Serra Boulevard) between the on-ramp from Brotherhood Way and the off-ramp to John Daly Boulevard would deteriorate from LOS E in the PM peak hour to LOS F with the addition of project-generated traffic. No feasible mitigation is available to reduce this impact to a less-than-significant level. Additional mainline capacity would be necessary, requiring acquisition of considerable additional right-of-way and demolition of existing occupied structures. In addition, a portion of this segment is located in Daly City, and the freeway is under the jurisdiction of Caltrans; therefore, any mitigation would be outside the jurisdiction of the City and County of San Francisco. The impact remains significant and unavoidable.

Impact TR-9: Implementation of the Proposed Project would have significant traffic impacts at two freeway segments that operate at LOS E or LOS F under Existing Conditions.

The Proposed Project would result in a significant increase in traffic volumes in the PM peak hour on the freeway segment of northbound SR 1 (Juniper Serra Boulevard) between the on-ramp from Brotherhood Way and the off-ramp to Brotherhood Way, contributing significantly to an existing LOS F operating condition. The Proposed Project would result in a significant increase in traffic volumes in the AM and PM peak hours on the freeway segment of southbound State Route 1 (Junipero Serra Boulevard) between the on-ramp from Brotherhood Way and the direct off-ramp at John Daly Boulevard.

Mitigation Measure M-TR-9: Eliminate the weaving segment between the loop on-ramp from Brotherhood Way and the loop off-ramp to Brotherhood Way by reconfiguring the interchange

This mitigation measure would affect northbound SR1 ramps, and would improve the weaving section operations to acceptable LOS in the AM and PM peak hours. The feasibility of measure is uncertain because it requires discretionary action Caltrans to approve a design exception, which is outside the jurisdiction of the City. Therefore, because the feasibility of this mitigation measure is uncertain and outside the jurisdiction of the City, the impact remains significant and unavoidable. The Planning Commission urges CalTrans to implement this measure.

Impact TR-11: Implementation of the sub-variant, either in conjunction with the Proposed Project or the Project Variant would have significant traffic impacts at the same freeway segments expected to experience significant traffic impacts associated with the Proposed Project, as identified in Impacts TR-8 and TR-9.

The sub-variant would not change travel demand or traffic volumes generated by the Proposed Project, and the impacts would be the same as those identified for the Proposed Project. See findings for Impacts TR-8 and TR-9, above.

Impact TR-12: Implementation of the Proposed Project would exceed the available transit capacity of transit routes serving the Project Study Area.

Project-related transit trips would cause the Study Area northeast screenline to exceed Muni's capacity utilization standard of 85 percent in the outbound (toward Parkmerced) direction during the PM Peak

Hour. (The Study Area northeast screenline examines Muni capacity utilization for the M Ocean View at the perimeter of the Study Area.) This would be a significant Project impact.

Mitigation Measure M-TR-12: Contribute fair share toward purchase of additional transit vehicles (and maintenance and operating costs associated with those additional vehicles) to increase capacity on the M Ocean View

Providing additional capacity by adding additional cars to the M Ocean View line during the PM peak hour would allow the M Ocean View to operate under 85 percent capacity utilization. A potentially feasible means of increasing capacity would be to increase the frequency of service on the M Ocean View by allocating additional trains; however, the subway along Market Street currently operates at capacity and it may not be feasible to increase frequency of service on the M Ocean View without impacting service levels on other transit lines. Such a change would require a revised service plan, which is outside the scope of the impact caused by the Proposed Project. Additionally, even if it were determined to be physically possible to increase service capacity on the M Ocean View, doing so would require a funding commitment in perpetuity from the SFMTA and the Board of Supervisors. Accordingly, full implementation and the effectiveness of this measure are uncertain and this impact remains significant and unavoidable.

Impact TR-14: Implementation of the sub-variant would result in significant impacts on the same Muni Study Area Screenlines as identified in Impact TR-12 for the Proposed Project.

The sub-variant would not change travel demand or transit capacity compared to the Proposed Project. See the findings under Impact TR-12, above.

Impact TR-22: Implementation of the Proposed Project would contribute traffic to existing traffic volumes at intersections along the Lake Merced Boulevard corridor, which would increase travel times and impact operations of the 18 46th Avenue bus line.

Project-related transit delays due to congestion along Lake Merced Boulevard and passenger loading delays associated with increased ridership would result in significant impacts on the operation of the 18 46th Avenue bus line during the AM and PM peak hours. Although the 18 46th Avenue route may change in the future, it would be replaced in part by the 17 Parkmerced, with the same significant impact. Therefore, mitigation measures would apply to whichever bus route is in place at the time.

Mitigation Measure M-TR-22A: Construct intersection mitigations to reduce congestion caused by vehicular delay.

Mitigation measure M-TR-22A would construct the intersection improvements identified in measures M-TR-2C, M-TR-2D, and M-TR-2E, above. This measure alone would improve conditions but would not reduce the impact to less-than-significant levels and the impact would remain significant and unavoidable with mitigation.

Mitigation Measure M-TR-22B: Maintain the proposed headways of the 18 46th Avenue

Feasibility of this measure is uncertain due to the need for further study. In addition, it would conflict with mitigation measure M-TR-2C. Thus, even if the conflict with M-TR-2C were resolved and this

measure fully implemented, the its success at reducing the impact to less-than-significant levels remains uncertain and the impact remains significant and unavoidable with mitigation.

Mitigation Measure M-TR-22C: Purchase additional transit vehicles as necessary to mitigate the Project impacts to headways on the 18 46th Avenue.

Although this measure appears feasible, implementation of this measure alone, without either measure M-TR-2A or M-TR-2B, may not reduce the impact to a less-than-significant level. Accordingly, because implementation of this mitigation measure may not reduce the impact to less-than-significant, the feasibility and efficacy of the other mitigation measures is uncertain at this time, the impact remains significant and unavoidable.

Impact TR-23: Implementation of the Proposed Project would contribute traffic to existing traffic volumes at intersections along the 19th Avenue corridor, which would increase travel times and affect operations of the 17 Parkmerced.

Project-related transit delays due to congestion on 19th Avenue between Holloway Avenue and Winston Drive and passenger loading delays associated with increased ridership would result in significant impacts on the operation of the 17 Parkmerced bus route during the PM peak hour.

Mitigation Measure M-TR-23: Maintain the proposed headways of the 17 Parkmerced, by implementing transit-only lanes along the length of 19th Avenue between Holloway Avenue and Winston Drive if feasible.

Implementation of measure M-TR-23 would require substantial study and public outreach and would result in secondary traffic impacts associated with removal of a traffic lane. For this and other specific economic, legal, social, technological, and other considerations, as more fully set forth in Section V below, the SFMTA has determined that this measure is infeasible. Because this mitigation measure is infeasible, the impact remains significant and unavoidable.

Impact TR-24: Implementation of the Proposed Project would contribute traffic to existing traffic volumes at intersections along the 19th Avenue corridor, which would increase travel times and affect operations of the 28 19th Avenue and 28L 19th Avenue Limited.

Project-related transit delays due to congestion on 19th Avenue and passenger loading delays associated with increased ridership would result in significant impacts on the operation of the 28 19th Avenue and 28L 19th Avenue Limited bus lines.

M-TR-24: Implement the Project Variant (i.e., conversion of the fourth southbound lane to high-occupancy vehicle, toll, and transit-only use).

Implementation of the Project Variant would require substantial additional study and public outreach, and would result in secondary traffic impacts associated with the removal of a mixed-flow traffic lane on 19th Avenue. Additionally, implementation would require discretionary approval by Caltrans. For this and other specific economic, legal, social, technological, and other considerations, as more fully set forth in Section V below, the SFMTA has determined that this measure is infeasible. Because this mitigation measure is infeasible, the impact remains significant and unavoidable.

Impact TR-25: Implementation of the Proposed Project would contribute traffic to existing traffic volumes at intersections along the Sunset Boulevard, Lake Merced Boulevard, Winston Drive, and 19th Avenue corridors, which would increase travel times and affect operations of the 29 Sunset.

Project-related transit delays due to congestion along sunset Boulevard, Lake Merced Boulevard, Winston Drive, and 19th Avenue, and passenger loading delays associated with increased ridership would result in significant impacts to the operation of the 29 Sunset bus line in the PM peak hour.

Mitigation Measure M-TR-25A: Implement mitigation measure M-TR-23, which addresses transit improvements (i.e. transit-only lanes) along 19th Avenue from Holloway Avenue to Winston Drive

Mitigation Measure M-TR-25B: Maintain the proposed headways of the 29 Sunset

Mitigation Measure M-TR-25C: Purchase additional transit vehicles as necessary to mitigate the Project impacts to headways on the 29 Sunset.

As noted above, Mitigation Measure M-TR-23, called for in Mitigation Measure M-TR-25A, was found to be infeasible; this finding also applies to M-TR-25A. In addition, implementation of M-TR-25A alone is not expected to eliminate the need for an additional transit vehicle in the PM peak hour. Therefore, the impact remains significant and unavoidable even if Mitigation Measure M-TR-25A were feasible.

Implementation of measure M-TR-25B requires further study by the SFMTA to determine its feasibility, which is not known at this time. Implementation of measure M-TR-25C alone, without M-TR-25A or M-TR-25B, may not be sufficient to reduce impacts to less-than-significant levels. In summary, implementation of measures that together would reduce the impact to a less-than-significant level are infeasible or uncertain at this time. Therefore, impacts on the 29 Sunset bus line remain significant and unavoidable.

Impact TR-26: Implementation of the Proposed Project would contribute traffic to existing traffic volumes at intersections along the Lake Merced Boulevard corridor, which would increase travel times and affect operations of a SamTrans bus line along this facility.

SamTrans Route 122 would experience substantial delays at key intersections along Lake Merced Boulevard, including at Brotherhood Way, Higuera Avenue, and Font Boulevard. This would be a significant impact in the AM and PM peak hours.

Mitigation Measure M-TR-26: Maintain proposed headways on SamTrans Route 122 by implementing mitigation measures M-TR-22A (land modifications at intersections along Lake Merced Boulevard) and M-TR-22B (implementation of transit priority treatment on Lake Merced Boulevard).

See findings above regarding mitigation measures M-TR-22A and M-TR-22B.

Impact TR-28: Implementation of the sub-variant would contribute traffic to existing traffic volumes at intersections along key transit corridors, which would cause congestion and increase travel times and impact operations of transit lines. With implementation of the sub-variant, the

Proposed Project would have the same significant impacts as identified for the Proposed Project in Impacts TR-21 to TR-26.

With implementation of the sub-variant, the impacts on transit travel times would be nearly identical to the Proposed Project and remain significant and unavoidable.

See findings above regarding Impacts TR-21 to TR-26 and related mitigation measures.

Impact TR-36: Implementation of the Proposed Project would contribute to significant cumulative traffic impacts at 14 study intersections.

Of the 34 study intersections, 20 intersections would operate at unacceptable LOS E or F in at least one peak hour under 2030 cumulative conditions. Of those intersections, the Proposed Project would contribute considerably to critical congested movements at the following 14 intersections and the Project's contribution to cumulative impacts would be significant:

- Junipero Serra Boulevard/Sloat Boulevard/St. Francis Boulevard/Portola Drive
- Junipero Serra Boulevard/John Daly Boulevard/I-280 Northbound On-Ramp/I-280 Southbound Off-Ramp/SR 1 Northbound On-Ramp
- 19th Avenue/Sloat Boulevard
- 19th Avenue/Winston Drive
- 19th Avenue/Holloway Avenue
- 19th Avenue/Crespi Drive
- Brotherhood Way/Chumasero Drive
- Sunset Boulevard/Lake Merced Boulevard
- Lake Merced Boulevard/Winston Drive
- Lake Merced Boulevard/Font Boulevard
- Lake Merced Boulevard/Brotherhood Way
- Lake Merced Boulevard/John Muir Drive
- John Daly Boulevard/Lake Merced Boulevard
- Lake Merced Boulevard/Gonzalez Drive

Mitigation measures for the Proposed Project's contribution to significant cumulative impacts at these intersections are infeasible for the reasons set forth here:

- Junipero Serra Boulevard/Sloat Boulevard/St. Francis Boulevard/Portola Drive
- Junipero Serra Boulevard/John Daly Boulevard/I-280 Northbound On-Ramp/I-280 Southbound Off-Ramp/SR 1 Northbound On-Ramp

Mitigation measures to reduce significant cumulative impacts and the Proposed Project's contribution to the cumulative impacts at these locations are infeasible for the same reasons identified in the finding for Impact TR-3, above. Therefore, the Project's contribution to the cumulative impacts at these intersections is significant and unavoidable.

- 19th Avenue/Sloat Boulevard.
- 19th Avenue/Winston Drive

Mitigation measures to reduce the Proposed Project's contribution to significant cumulative impacts at these locations are infeasible for the same reasons identified in the finding for Impact TR-2, above. Therefore, the Proposed Project's contribution to the cumulative impacts at these intersections is significant and unavoidable.

- 19th Avenue/Holloway Avenue

Mitigation Measure M-TR-36A: Retime signal at 19th Avenue/Holloway Avenue to allocate more green time to the east-west movements.

Implementation of this measure would achieve acceptable operations at the intersection of 19th Avenue / Holloway Avenue. However, 19th Avenue is a coordinated corridor with closely spaced intersections where the traffic signal timing is interconnected. Traffic progression relies on the interconnectivity between each signal. Retiming the signal at this intersection would require evaluation of the entire corridor, and is the responsibility of the SFMTA. The efficacy of this measure is uncertain at this time, and will require SFMTA's evaluation of the entire corridor. Therefore, the ability of this measure to mitigate the impact is uncertain at this time, and the impact remains significant and unavoidable.

- Brotherhood Way/Chumasero Drive

M-TR-36B: Construct a dedicated westbound right-turn lane and convert the shared westbound through/right-turn lane to a dedicated westbound through lane at the Brotherhood Way/Chumasero Drive intersection.

Although implementation of this mitigation measure would reduce the Proposed Project's significant cumulative impact to a less-than-significant level, it may not be feasible. If the existing pedestrian overcrossing across Brotherhood Way at this intersection were to remain, widening the roadway to implement this measure may not be feasible due to conflicts with structural support columns for the overcrossing. Therefore, the ability of this measure to mitigate the impact is uncertain at this time, and the impact remains significant and unavoidable.

- Sunset Boulevard/Lake Merced Boulevard

Mitigation Measure M-TR-2B: Install a traffic signal at Sunset Boulevard/Lake Merced Boulevard

Implementation of this measure is infeasible for the same reasons as identified in the finding related to Impact TR-2, Mitigation Measure M-TR-2B, above. Therefore, the Proposed Project's contribution to the significant impact at this intersection remains significant and unavoidable.

- Lake Merced Boulevard/Winston Drive

Mitigation Measure M-TR-2C: Construct a dedicated northbound right-turn lane from Lake Merced Boulevard to eastbound Winston Drive

The effectiveness of this measure is uncertain for the same reasons as identified in the finding related to Impact TR-2, Mitigation Measure M-TR-2C, above. In addition, implementation would improve operations but would remain at an unacceptable LOS E in the PM peak hour. Therefore, the Proposed Project's contribution to cumulative impacts at this intersection remains significant and unavoidable.

- Lake Merced Boulevard/Font Boulevard

Mitigation Measure M-TR-2D: Provide a third northbound through lane and a second southbound left-turn lane at the Lake Merced Boulevard/Font Boulevard intersection

Implementation of this measure would improve operations at this intersection, but not such that operations would improve to an acceptable LOS D or better under 2030 cumulative conditions. Additional capacity would be necessary, including providing a dual right-turn lane in the westbound direction. However, a dual right-turn lane against a pedestrian signal is considered a safety hazard and would be inconsistent with the City's goals of promoting walking and bicycling. Therefore, in addition to the finding of infeasibility for Mitigation Measure M-TR-2D presented above, other potential mitigation measures to reduce the impact to a less-than-significant level would be infeasible for pedestrian safety reasons, and the impact remains significant and unavoidable.

- Lake Merced Boulevard/Brotherhood Way

Mitigation Measure M-TR-2E: Reconfigure the westbound right-turn and southbound left-turn as the primary movements at the intersection of Lake Merced Boulevard and Brotherhood Way

Implementation of this measure would improve operations at this intersection, but it would continue to operate at LOS F during both the AM and PM peak hours. A second northbound left-turn lane would be needed in addition to this mitigation measure to reduce the Proposed Project's contribution to significant cumulative impacts to a less-than-significant level and provide an acceptable LOS. However, provision of dual northbound left-turn lanes would present a pedestrian safety conflict with the crosswalk on the northern leg of the intersection. Implementation of such a measure would be inconsistent with the City's goals of promoting walking and bicycling. Therefore, because Mitigation Measure M-TR-2E alone would not reduce the impact to less-than-significant levels, and additional mitigation measures to reduce the impacts at this intersection are infeasible for pedestrian safety reasons, the impact remains significant and unavoidable.

- Lake Merced Boulevard/John Muir Drive

Mitigation Measure M-TR-36C: Install a traffic signal at Lake Merced Boulevard/John Muir Drive

Implementation of this measure would improve intersection operations to acceptable levels, reducing significant cumulative impacts to a less-than-significant level. Project Sponsor shall contribute a fair share toward funding this mitigation measure; however, full funding, for this measure is uncertain at this time. Therefore, the feasibility of this mitigation measure to fully mitigate the impact is uncertain, and the impact is considered significant and unavoidable.

- John Daly Boulevard/Lake Merced Boulevard

Mitigation Measure M-TR-36D: Convert the dedicated southbound through lane into a dedicated left-turn lane at John Daly Boulevard/Lake Merced Boulevard

Implementation of this measure would improve intersection operations to acceptable levels, reducing significant cumulative impacts to a less-than-significant level. Project Sponsor shall contribute a fair share toward funding this mitigation measure. Full funding is uncertain, and implementation of this measure is under the jurisdiction of the City of Daly City. Therefore, the feasibility of this mitigation measure is uncertain and thus currently considered infeasible because it is outside the jurisdiction of the City and County of San Francisco. The impact remains significant and unavoidable.

- Lake Merced Boulevard/Gonzalez Drive

Mitigation Measure M-TR-36E: Install and auxiliary lane from Brotherhood Way through the Lake Merced Boulevard/Gonzalez Drive intersection to provide three northbound through lanes

Implementation of this measure would improve intersection operations to acceptable levels, reducing significant cumulative impacts in the PM peak hour. The SFMTA has determined that further study is required to determine feasibility of this measure, and thus the ability of this measure to fully mitigate the impact is uncertain at this time. The Proposed Project's contribution to cumulatively significant impacts remains significant and unavoidable.

- 19th Avenue/Holloway Avenue

Mitigation Measure M-TR-36A: Retime signal at 19th Avenue/Holloway Avenue to allocate more green time to the east-west movements

The efficacy of this mitigation measure is uncertain for the same reasons as identified in the discuss of M-TR-36A, above. Therefore the impact remains significant and unavoidable.

Impact TR-39: Implementation of the sub-variant in conjunction with the Proposed Project would result in the same significant cumulative traffic impacts at study intersections as identified in Impacts TR-35 and TR-36 for cumulative conditions with the Proposed Project.

The sub-variant would involve constructing a right-turn ingress along 19th Avenue between Crespi Drive and Junipero Serra Boulevard at Cambon Drive. The anticipated impact of this sub-variant in conjunction with the Proposed Project is minor. Mitigation measures identified for Impacts TR-35 and TR-36 would be the same for Impact TR-39 and the findings made above are applicable to this impact and related mitigation measures.

Impact TR-41: Implementation of the Proposed Project would contribute to significant cumulative traffic impacts at four freeway segments.

The four freeway segments that would be significantly affected by project-generated traffic in 2030 cumulative conditions are:

- Southbound SR 1 (Junipero Serra Boulevard): Weaving Segment Between Direct On-Ramp from Brotherhood Way and Direct Off-ramp to John Daly Boulevard

- Northbound SR 1 (Junipero Serra Boulevard): Basic segment between Off-Ramp to Northbound I-280 and On-Ramp from John Daly Boulevard
- Northbound SR 1 (Junipero Serra Boulevard): Weaving Segment between On-Ramp from John Daly Boulevard and Off-Ramp to Alemany Boulevard

These three freeway segments are located in Daly City and would require creating additional lanes on the freeway. Because they are in Daly City and the freeway is under the jurisdiction of Caltrans, any mitigation measures that would improve service levels to acceptable levels are uncertain and currently considered infeasible as outside the jurisdiction of the City and County of San Francisco. Therefore, the Proposed Project's contribution to significant cumulative impacts would be significant and unavoidable.

- Northbound SR 1 (Junipero Serra Boulevard): Weaving Segment Between Loop On-Ramp from Brotherhood Way and Loop Off-ramp to Brotherhood Way

The Proposed Project would increase volumes on this segment of SR 1 by over 40 percent in the PM peak hour. This is a cumulatively considerable contribution and is a significant impact.

Mitigation Measure M-TR-9: Eliminate the weaving segment between the loop on-ramp from Brotherhood Way and the loop off-ramp to Brotherhood Way by reconfiguring the interchange

Although this mitigation measure would reduce the Proposed Project's contribution to significant cumulative impacts to less-than-significant levels, it is infeasible for the same reasons provided in the discussion of Impact TR-9, above, and the impact remains significant and unavoidable.

Impact TR-43: Implementation of the sub-variant would contribute to significant cumulative traffic impacts at four freeway segments expected to experience significant cumulative traffic impacts under future conditions with the Proposed Project, as identified in Impact TR-41.

The sub-variant would not affect travel demand or roadway configurations at Study Area freeway facilities. Therefore, the findings presented for Impact TR-41 are applicable to Impact TR-43.

Impact TR-44: The Proposed Project would contribute transit ridership to Study Area screenlines expected to exceed available capacity under 2030 cumulative conditions.

For the northeast screenline, the Proposed Project would contribute considerably to ridership demand that would exceed the capacity utilization threshold of 85 percent in both the AM peak hour (inbound, toward downtown) and the PM peak hour (outbound, toward Parkmerced). (The northeast screenline examines Muni capacity utilization for the M Ocean View at the perimeter of the Study Area.) Mitigation that would reduce this contribution to a significant cumulative impact is infeasible for the same reasons as discussed in Impact TR-12, above. Therefore, the contribution to cumulatively significant impacts on this screenline is significant and unavoidable.

For the south and north screenlines, the Proposed Project would contribute to capacity utilization greater than 85 percent in the PM peak hour; the Proposed Project would also contribute to capacity utilization greater than 85 percent in the AM peak hour on the 28 19th Avenue bus line at the south screenline. (The south screenline examines Muni capacity utilization for the 28 19th Avenue and the 28L 19th Avenue

Limited. The north screenline examines Muni capacity utilization for the 18 46th Avenue, the 28 19th Avenue, the 28L 19th Avenue Limited and the 29 Sunset). This would be a significant cumulative impact.

Mitigation Measure M-TR-44: Provide additional capacity on the south and north screenlines by adding additional buses to the 28 19th Avenue and 28L 19th Avenue Limited lines.

Implementation of this mitigation measure would reduce cumulative impacts on the south and north screenlines to less-than-significant levels. Although San Francisco has a transit impact fee funding mechanism, it does not apply to residential projects. Therefore, while the project sponsor would be responsible for a fair share contribution toward the measure, full funding is not available to implement the measure, and the measure is infeasible. In addition, further feasibility and capacity studies by SFMTA would be required prior to implementation. Therefore, the mitigation measure is outside the jurisdiction of the Planning Commission. The impacts remain significant and unavoidable.

Impact TR-46: Implementation of the sub-variant would result in significant impacts on the same Muni Study Area Screenlines as identified in Impact TR-44 for the Proposed Project.

The Project sub-variant would not affect cumulative travel demand or transit capacity at Study Area screenlines, compared to the Proposed Project. Therefore, mitigation for this impact is infeasible for the same reasons as provided in Impact TR-44 and the impact remains significant and unavoidable.

Impact NO-3: Project-related traffic would increase noise levels above existing ambient conditions.

The Parkmerced Project would contribute to significant weekday traffic noise level increases along Gonzalez Drive, on the new roadway segment connecting Lake Merced Boulevard to the interior of the Project Site, in existing residences that remain unchanged and occupied when the new road is placed into service. The impact would occur until these residences were demolished and replaced with new, high-density residential buildings in a later phase of development

No feasible mitigation is available that would reduce traffic noise level increases along the affected portion of Gonzalez Drive. Relocating all tenants in existing buildings that remain along this new portion of Gonzalez Drive would reduce the impact to less-than-significant levels; however, relocation opportunities for these existing residents are not assured at this time. Therefore, while temporary, this impact is significant and unavoidable.

Impact NO-4: Increases in traffic from the project in combination with other development would result in cumulative noise increases.

Based on baseline and future traffic projections developed as part of the transportation analysis for the Proposed Project, the Proposed Project would contribute to significant cumulative roadside noise levels along Gonzalez Drive along the new roadway segment connecting Lake Merced Boulevard to the interior of the Project Site in existing residential units that remain occupied when the new roadway is in use. The significant cumulative noise impact would continue until these residences were demolished and replaced with new, high-density residential buildings in a later phase of development.

No feasible mitigation is available that would reduce cumulative traffic noise level increases along the affected portion of Gonzalez Drive. Relocating all tenants in existing buildings that remain along this new portion of Gonzalez Drive would reduce the impact to less-than-significant levels; however, relocation opportunities for these existing residents are not assured at this time. Therefore, this impact is significant and unavoidable.

Impact NO-5: Project-related light rail noise and vibration levels would increase above existing ambient conditions.

Light rail noise and vibration would have the potential to result in a significant increase in ambient noise and vibration conditions at the nearest sensitive receptor locations.

Mitigation Measure M-NO-5: Light Rail Noise and Vibration Reduction Plan

Implementation of Mitigation Measure M-NO-5 would ensure that the proposed realignment of the light rail line and its operations would be designed in a manner that would reduce the potentially significant noise and vibration impacts to a less-than-significant level. However implementation requires discretionary approval actions by the SFMTA, is outside the jurisdiction of the Planning Commission, and is therefore considered uncertain. Therefore, this mitigation measure is currently considered infeasible and thus impact remains significant and unavoidable. The Planning Commission urges the SFMTA to implement this measure.

Impact NO-7: Operation of stationary noise sources (e.g., district energy system, wind, turbines, fire station and police and fire substation(s), etc.) would increase existing noise levels, potentially exceeding noise level standards.

Operation of these noise sources would cause potentially significant impacts to the adjacent land uses including residences and other noise sensitive uses within the Project Site and near the Project Site boundaries.

Mitigation Measure M-NO-7: Stationary Operational Noise Sources

Implementation of Mitigation Measure M-NO-7 would achieve compliance with the noise level limits of the San Francisco Noise Ordinance and achieve acceptable levels at the property lines of nearby residences or other noise sensitive uses, as determined by the San Francisco Land Use Compatibility Guidelines for Community Noise standards. However, shielding the wind turbines and other stationary noise sources from noise sensitive land uses may diminish the utility or efficiency of the systems. In addition, specific information about the design of the stationary noise sources is not available and the feasibility and effectiveness of the noise attenuation that could be featured with the final designs are not known at this time. Therefore, this impact remains significant and unavoidable.

Impact AQ-3: Construction of the Proposed Project could expose persons to substantial levels of toxic air contaminants, which may lead to adverse health effects.

The Proposed Project could increase cancer risk from exposure to emissions of DPM and other TACs associated with off-road construction equipment and on-road haul trucks used during construction of the Proposed Project. Although most residents would have limited exposure either because construction would be occurring at substantial distances from their units or because construction activities would occur for about five years or less in any one location, there is potential for some residents to remain and relocate in such a way that their exposure could result in significant health risks.

Mitigation Measure M-AQ-3: Construction Exhaust Emissions

Implementation of construction emission control measures would reduce DPM exhaust emissions by implementing feasible controls and requiring up-to-date equipment, but the potential remains for receptors closest to the construction to be exposed. Therefore this impact remains significant and unavoidable.

Impact AQ-4: The Proposed Project's operations could affect regional air quality.

The Proposed Project would result in an increase in criteria pollutant emissions that would be considered significant under BAAQMD significance thresholds.

No feasible mitigation measures are available beyond the extensive transportation demand management (TDM) program and other features of the proposed Sustainability Plan minimizing energy use that would reduce emissions below the BAAQMD significance thresholds. Therefore, this impact is significant and unavoidable.

Impact AQ-9: The Proposed Project could result in cumulative air quality impacts.

The Proposed Project would exceed BAAQMD significance thresholds for criteria pollutants, resulting in significant contributions to air quality impacts in the region.

No feasible mitigation is available that would reduce cumulative air quality impacts, as discussed above under Impact AQ-4 regarding the Proposed Projects effects on regional air quality. Therefore, this impact is significant and unavoidable.

Impact AQ-11: The Proposed Project could result in construction-related impacts to regional air quality under the 2010 guidelines.

The 2010 BAAQMD CEQA Guidelines specifies that average daily construction emissions greater than 54 pounds per day of ROG, NO_x, and PM_{2.5}, or 82 pounds per day PM₁₀, would be a significant increase. Because of the considerable levels of construction activities, the construction emissions under the 2010 BAAQMD CEQA Guidelines would be significant and unavoidable and no additional mitigation measures are available.

Mitigation Measure M-AQ-3: Construction Exhaust Emissions

Given current technologies, Mitigation Measure M-AQ-3 would achieve a feasible level of NO_x and ROG reductions, but this measure is unlikely to achieve a sufficient reduction in emissions to bring construction activities to a level below the daily thresholds for ROG, NO_x, PM₁₀, and PM_{2.5}. Construction

emissions of PM₁₀ and PM_{2.5} would be significant according to the 2010 Guidelines, after incorporating dust control strategies (see Impact AQ-1) and feasible strategies to reduce emissions in construction equipment exhaust (Mitigation Measure M-AQ-3). Therefore, the impacts of the Proposed Project with respect to the 2010 BAAQMD CEQA Guidelines would be significant and unavoidable, even with implementation of mitigation.

Impact AQ-12: The Proposed Project could result in construction-related impacts of toxic air contaminants and adverse health effects under the 2010 guidelines.

The Proposed Project could increase cancer risk from exposure to emissions of DPM and other TACs associated with off-road construction equipment and on-road haul trucks used during construction of the Proposed Project, as these emissions would occur within 1,000 feet of existing residential units and educational facilities within and adjacent to the Project Site. The 2010 BAAQMD CEQA Guidelines thresholds for TACs are similar to the current recommendations, with the addition of PM_{2.5} as a pollutant of health risk concern.

Emissions of PM_{2.5} from construction activities would occur at regionally significant levels. Additionally, health risks due to PM_{2.5} emissions would be considered significant under 2010 BAAQMD CEQA Guidelines for construction activities causing concentrations of PM_{2.5} over an annualized threshold of 0.3 micrograms per cubic meter (µg/m³). Existing residential units and educational facilities within 1,000 feet of construction activities would be most likely to experience this impact.

According to the 2010 BAAQMD CEQA Guidelines' "Draft Construction Health Risk Screening Table", the minimum offset distance (buffer distance) to ensure that a sensitive receptor would have a less than significant impact would be 300 meters (984 feet). Existing and planned residential units and educational facilities within this distance would experience a significant impact due to construction-related TAC and PM_{2.5}.

Mitigation Measure M-AQ-3: Construction Exhaust Emissions

Although implementation of the construction emission control measures (including Mitigation Measure M-AQ-3) would reduce TAC, including DPM, exhaust emissions by implementing feasible controls and requiring up-to-date equipment, adverse TAC and PM_{2.5} health effects during construction would remain. Due to the high-density surroundings, individuals would occasionally be essentially adjacent to construction activity. It would be practically impossible to phase construction or restrict public access in such a manner to eliminate the potential risks to individuals occupying and visiting areas within 1,000 feet of the proposed construction activities. Due to uncertainty in quantifying the construction-related incremental cancer risk and non-cancer health impacts, the impact is considered significant and unavoidable.

Impact AQ-13: The Proposed Project could result in operation-related impacts to regional air quality under the 2010 guidelines.

The Proposed Project would result in an increase in criteria pollutant emissions that would be considered significant according to the 2010 BAAQMD significance thresholds of ROG, NOx, or PM_{2.5} greater than

54 pounds per day or PM₁₀ greater than 82 pounds per day. This impact would occur with the project incorporating feasible emission reduction measures within its extensive TDM program and Sustainability Plan. As such, this impact would be significant and unavoidable and no further mitigation is available.

Impact AQ-15: The Proposed Project could result in operation-related impacts to sensitive receptors and substantial pollutant concentrations of toxic air contaminants under 2010 guidelines.

Operation of the Proposed Project operation would cause increases in traffic emitting DPM, other TACs, and PM_{2.5} and would increase the density of residential uses in an area exposed to these emissions. The 2010 BAAQMD Thresholds include screening tables identifying potential cancer risk and non-cancer health hazards experienced by sensitive receptors along Highway 1 (Junipero Serra Boulevard and 19th Avenue). According to the new BAAQMD screening tables, sensitive receptors are exposed to potentially significant concentrations of TAC and PM_{2.5} (exceeding 0.3 µg/m³) within 200 feet east or west of Highway 1. The new BAAQMD screening tables also indicate that the estimated incremental lifetime

cancer risk (70-year lifespan) due to traffic on Highway 1 is greater than 10 cases per million people for

locations within 192 feet east or west of the roadway. Health risks from all roadways are dominated by the effects of DPM, a TAC, and PM_{2.5}.

The Proposed Project would include new residential uses within 1,000 feet of existing stationary sources of TACs and within 200 feet of Highway 1, which could expose new sensitive receptors to concentrations of DPM, other TACs, and PM_{2.5} considered significant under the 2010 guidelines.

Mitigation Measure M-AQ-15: Mechanical Ventilation Systems for New Residential Uses

Mitigation Measure M-AQ-15 requires that new residential uses within 200 feet from the edge of the Project Site boundary along Junipero Serra Boulevard, including ramps on Brotherhood Way, 19th Avenue, or Brotherhood Way incorporate mechanical ventilation systems. Although this would reduce the impact of exposing new receptors to elevated concentrations near roadways, it would not avoid the impact of placing new receptors near Highway 1 and other existing sources of TACs typical of urban environments. Because of uncertain effectiveness and feasibility of implementing this measure, the impact under the 2010 BAAQMD CEQA Guidelines would remain significant and unavoidable.

Impact AQ-18: The Proposed Project could result in cumulative construction impacts under the 2010 guidelines.

Impact AQ-2 identifies the emission increases attributable to construction of the Proposed Project. The Proposed Project would exceed the BAAQMD's adopted significance thresholds for construction-related ROG, NOx, PM₁₀, and PM_{2.5}. Consequently, under the 2010 BAAQMD CEQA Guidelines, the project construction would result in a significant cumulative impact with regard to these emissions. This impact is significant and unavoidable.

Impact AQ-19: The Proposed Project could result in cumulative criteria pollutant impacts under 2010 guidelines.

According to the 2010 BAAQMD CEQA Guidelines, the Proposed Project operational emissions would be cumulatively considerable, resulting in significant adverse air quality impacts to the region's existing air quality conditions. Additional analysis to assess cumulative impacts is deemed unnecessary by BAAQMD, and the Proposed Project would result in a significant cumulative impact with regard to ROG, NO_x, PM₁₀, and PM_{2.5} emissions. This impact is significant and unavoidable.

Impact AQ-20: The Proposed Project could result in cumulative DPM, PM_{2.5}, and TAC impacts under the 2010 guidelines.

Impact AQ-6 shows that, according to the 2010 BAAQMD CEQA Guidelines, the operational impacts due to exposure of receptors to DPM and TACs would be significant and unavoidable because the Proposed Project would expose planned receptors to substantial concentrations of DPM or other TACs. With no additional foreseeable sources of DPM or TACs identified for the cumulative conditions, the cumulative impact would be similar to that described for the Proposed Project. Roadside PM_{2.5} exposure levels found by the analysis performed by the DPH would not exceed the 2010 BAAQMD significance threshold for a cumulatively considerable contribution of PM_{2.5}. No additional PM_{2.5} impacts are identified for the cumulative conditions. Cumulative projects in the area are not anticipated to contribute considerable emissions in addition to the project. However, due to health risks caused by existing sources of TACs including nearby major roadways (Highway 1), the project-related DPM, PM_{2.5}, and TAC exposures would result in a significant and unavoidable cumulative impact. This impact is significant and unavoidable.

Impact WS-1: The phased construction of the Proposed Project could result in a temporary increase in the number of hours that the 26-mph wind hazard criterion is exceeded or an increase in the area that is subjected to winds greater than 26 mph.

Although the Proposed Project, in its entirety, would not result in significant wind impacts and would in fact improve wind conditions on the Project Site, some potentially significant interim wind impacts may occur prior to the completion of construction.

Mitigation Measure M-WI-1A: Wind Impact Analysis for Proposed Buildings Over 100 feet in Height.

Mitigation Measure M-WI-1B: Wind Tunnel Testing for Proposed Buildings Over 50 feet in Height.

Implementation of Mitigation Measures M-WS-1a and M-WS-1b would reduce some, but possibly not all, potentially significant wind impacts to less-than-significant levels during the interior period prior to project build-out. No other mitigation measures have been identified that would feasibly reduce the potentially significant impact to less-than-significant levels during the construction period. Therefore this impact remains potentially significant and unavoidable.

Impact WS-3: The proposed Special Use District could result in increases in the number of hours that the 26-mph wind hazard criterion is exceeded or increases in the area that is subjected to winds greater than 26 mph.

Maximizing building heights and/or building footprints in certain locations on the Project Site would have the potential to change the wind impacts that were predicted by the wind tunnel.

Mitigation Measure M-WI-1A: Wind Impact Analysis for Proposed Buildings Over 100 feet in Height.

Mitigation Measure M-WI-1B: Wind Tunnel Testing for Proposed Buildings Over 50 feet in Height.

Implementation of Mitigation Measures M-WS-1a and M-WS-1b, would reduce some, but possibly not all, potentially significant hazardous wind impacts to less-than-significant levels. No other feasible measures have been identified that would reduce potential hazardous wind conditions to less-than-significant levels. Therefore this impact remains potentially significant and unavoidable.

Impact BI-8: Operation of the 51 proposed wind turbines on the western periphery of the Project Site could have a substantial adverse effect on special-status species, interfere substantially with bird or bat movement and migration corridors, and interfere substantially with raptor nest sites.

The wind turbine site meets two of the four criteria for a high or uncertain potential for wildlife impacts (for both birds and bats). Bi-weekly pre-permitting surveys of a turbine site for at least two years before project approval may be necessary in such cases to determine the level of impacts because of considerable seasonal and annual variation in bird populations.

Mitigation Measure M-BI-8a: Pre-permitting Surveys for Birds and Bats.

Mitigation Measure M-BI-8b: Operations Monitoring Program.

Mitigation Measure M-BI-8c: Implementation of Management Strategies.

Mitigation Measure M-BI-8d: Design Elements to Minimize Bird and/or Bat Strikes.

Mitigation Measure M-BI-8e: Incidental Take Permit.

Implementation of Mitigation Measures M-BI-8a through M-BI-8e may reduce the significant impacts. However, without data from pre-permitting studies, it is not feasible to design a mitigation program that can be demonstrated to reduce impacts to less-than-significant levels. Incidental Take Permits are issued by the California Department of Fish and Game and are outside the jurisdiction of the Planning Commission. Therefore, the impact remains significant and unavoidable.

Impacts Associated with the No Muni Realignment Alternative

The No Muni Realignment Alternative would remove the significant impact at the intersection of 19th Avenue and Crespi Drive, because the northbound left-turn lane would not be added. However, the alternative would result in a new significant impact at the intersection of 19th Avenue and Junipero Serra Boulevard during the weekend midday peak hour and a new cumulative impact at this intersection during the weekday PM peak hour. These impacts would be significant and unavoidable. Thus, the total number of intersections impacted would remain the same with this alternative. The alternative would reduce significant impacts on Muni in that it would have significant impacts due to travel time delays on two fewer transit routes than the Proposed Project. The SFSU light rail station would remain in the 19th Avenue median and would experience substantial overcrowding compared to the proposed new station in the Proposed Project; thus this alternative would result in a significant and unavoidable impact on pedestrians and transit patrons at this location.

Although significant noise and vibration impacts from operation of the Muni M Ocean View line adjacent to new residential and commercial uses would be reduced under the No Muni Alternative, other noise impacts identified under the Proposed Project would essentially be the same. All other impacts identified under the Proposed Project for aesthetics, historic architectural resources, transportation, air quality, wind, and biological resources would remain under this alternative, and all mitigation measures apply to this Alternative.

V. MITIGATION MEASURES REJECTED AS INFEASIBLE

This Section describes the reasons for rejecting certain mitigation measures as infeasible pursuant to CEQA Guidelines Section 150919a)(3). Although CEQA requires that all feasible mitigation measures be imposed to address the significant impacts of a proposed project, mitigation measures may be rejected if they are found to be infeasible for specific economic, legal, social, technological, or other considerations. The following mitigation measures described in the Final EIR are rejected for the reasons set forth below and as supported by substantial evidence in the record.

Mitigation Measure M-TR-2B: Install a traffic signal at Sunset Boulevard/Lake Merced Boulevard

Implementation of this mitigation measure would reduce certain significant impacts at the intersection of Sunset Boulevard/Lake Merced Boulevard to less-than-significant levels; however, the SFMTA has evaluated the feasibility of this measure and has found that it is infeasible. Specifically, the SFMTA's analysis shows that a signal at this location would increase delay for every "major" movement (Northbound and Southbound Sunset Boulevard) through the intersection, including transit, in order to reduce delays on a "minor" movement (Lake Merced Boulevard to Sunset Boulevard). Thus, creating delays on a major thoroughfare to reduce delays on a less utilized movement is not feasible for social and other policy considerations, including transit-priority. Accordingly, this mitigation measure is rejected as infeasible.

Mitigation Measure M-TR-23: Maintain the proposed headways of the 17 Parkmerced, by implementing transit-only lanes along the length of 19th Avenue between Holloway Avenue and Winston Drive if feasible.

Implementation of measure M-TR-23 would require substantial study and public outreach and would result in secondary traffic impacts associated with removal of a traffic lane. SFMTA has determined that the benefits of implementing this measure (and uncertainty of those benefits) are outweighed by the considerable trade-off for auto traffic in this location. Additionally, SFMTA has determined that implementation of transit-only lanes along this portion of 19th Avenue between Holloway Avenue and Winston Drive is too short or discontinuous to add value or to effectively enforce. These specific social and policy concerns render Mitigation Measure M-TR-23 infeasible and, accordingly, this mitigation measure is rejected.

M-TR-24: Implement the Project Variant (i.e., conversion of the fourth southbound lane to high-occupancy vehicle, toll, and transit-only use).

Implementation of the Project Variant would require substantial additional study and public outreach, and would result in secondary traffic impacts associated with the removal of a mixed-flow traffic lane on 19th Avenue. As for M-TR-23, discussed above, SFMTA has determined that the benefits of implementing this measure (and uncertainty of those benefits) are outweighed by the considerable trade-off for auto traffic in this location. Additionally, SFMTA has determined that implementation of transit-only lanes along this segment of 19th Avenue is too short or discontinuous to add value or to effectively enforce. These specific social and policy concerns render Mitigation Measure M-TR-23 infeasible and, accordingly, this mitigation measure is rejected.

Mitigation Measure M-TR-25A: Implement mitigation measure M-TR-23, which addresses transit improvements (i.e. transit-only lanes) along 19th Avenue from Holloway Avenue to Winston Drive.

Because Mitigation Measure M-TR-25A implements M-TR-23, it is rejected as infeasible for the same reasons set forth for M-TR-23, above.

VI. EVALUATION OF PROJECT ALTERNATIVES

This Section describes the reasons for approving the Proposed Project and the reasons for rejecting the alternatives. CEQA mandates that an EIR evaluate a reasonable range of alternatives to the Proposed Project or the project location that substantially reduce or avoid potentially significant impacts of the Proposed Project. CEQA requires that every EIR also evaluate a "No Project" alternative. Alternatives provide the decision maker with a basis of comparison to the Proposed Project in terms of their significant impacts and their ability to meet project objectives. This comparative analysis is used to consider reasonably, potentially feasible options for minimizing environmental consequences of the Proposed Project.

A. Reasons for Approving Proposed Project

The Parkmerced Project will provide the following benefits:

- Add up to approximately 5,679 housing units to the City's housing stock.
- Provide a range of types of housing units, including market-rate and affordable units.
- One for one replacement of the 1,538 rent-controlled dwelling units currently existing on the Project Site. Although none of the Existing Units have washer or dryers, each Replacement Unit will have a washer and a dryer and a dish washer installed by Developer prior to occupancy.
- Relocation by Developer of Existing Tenants from their Existing Units to the Replacement Units, with, under the terms of the proposed Project Development Agreement, an initial rent and pass through charges equal to the rent and pass through charges charged to the Existing Tenant for their Existing Unit at the time of relocation to the Replacement Unit.
- Construction of two new transit stations, relocation of an existing transit station, and a new alignment for the MUNI Metro M-Oceanview, integrated into the SFMTA transit system, that will leave 19th Avenue at Holloway Avenue and proceed through the neighborhood core in Parkmerced as further described in the Transportation Plan, and the provision of a low emissions shuttle bus from Parkmerced to the Daly City BART station and to the Stonestown retail center;
- Reconfiguration of the street grid within the Project Site to conform with San Francisco's Better Streets design guidelines, including the realignment of existing streets and the creation of new publicly-owned streets and publicly-accessible streets that accommodate bicycles, pedestrians and motor vehicles;
- Improvement and reconfiguration of streets and intersections on the periphery of the Project Site to improve access and safety for all modes of transportation;
- Creation and implementation of a Transportation Demand Management ("TDM") program, including but not limited to transit pass subsidies for residents and employees in the Project Site, to facilitate and encourage the use of transportation modes other than the private automobile, to minimize the amount of automobile traffic originating from Parkmerced and to improve traffic flow on adjacent roadways such as 19th Avenue and Brotherhood Way, as further described in the Transportation Plan
- Reconfiguration of the existing open space at Parkmerced to provide more usable open spaces and related public benefits such as a new park, athletic fields, an organic farm, walking and bicycling paths, and community gardens;
- Construction of a series of bioswales, ponds, and other natural filtration systems to capture and filter stormwater runoff from buildings and streets in accordance with the Infrastructure Plan and the Sustainability Plan. The filtered stormwater will either percolate into the groundwater that feeds the Upper Westside groundwater basin and Lake Merced or be released directly into Lake Merced. This feature of the Proposed Project will reduce the amount of stormwater flows directed to the Oceanside Water Pollution Control Plant and reduce combined sewage overflows to the ocean.

- Exclusive zoning of a parcel for the construction of an elementary school.
- Addition of neighborhood-serving retail and office uses within walking distance of residential units where little or no retail exists.
- Provision of infrastructure improvements that will increase sustainability, including use of energy-efficient lighting and HVAC equipment, planting drought-tolerant landscaping, and providing urban infill in an underused area.
- Provision of opportunities to reduce water demand by using recycled water for landscape irrigation.

B. Alternatives Rejected and Reasons for Rejection

The Planning Commission rejects the Alternatives set forth in the Final EIR and listed below because the Commission finds that there is substantial evidence, including evidence of economic, legal, social, technological, and other considerations described in this Section in addition to those described in Section VI below under CEQA Guidelines Section 15091(a)(44), that make these alternatives infeasible. In making these determinations, the Commission is aware that CEQA defines “feasibility” to mean “capable of being accomplished in a successful manner within a reasonable period of time, taking into account economic, environmental, social, legal, and technological factors.” The Commission is also aware that under CEQA case law the concept of “feasibility” encompasses (i) the question of whether a particular alternative promotes the underlying goals and objectives of a project; and (ii) the question of whether an alternative is “desirable” from a policy standpoint to the extent that desirability is based on a reasonable balancing of the relevant economic, environmental, social, legal, and technological factors.

1. No Project Alternative

Under the No Project Alternative, the site would remain in its existing condition, no existing buildings or landscaping would be demolished and no new buildings would be constructed. No on- or off-site infrastructure improvements would be constructed. The physical impacts identified in the Final EIR for the Proposed Project would not occur.

The No Project Alternative would not provide additional density in an underutilized area of the City, would not add up to 5,679 additional residential units to the City’s housing stock, would not help reduce the shortage of affordable housing in the City, would not help the City meet its regional housing needs allocation, would not improve transit service and facilities in the southwest quadrant of the City, would not reduce wet-weather flows in the City’s combined wastewater collection and treatment system, would not provide employment opportunities either during construction or in new retail and office space in the neighborhood core, and would not provide opportunities for renewable energy generation.

Further, this alternative would not improve the City’s revenues by adding new residential and commercial space to the City’s inventories.

For these reasons, the Commission finds that, on balance, the Proposed Project is preferable to the No Project Alternative and that the No Project alternative is rejected as infeasible.

2. Buildout Under Current Zoning Regulations Alternative

Under this alternative, the existing 3,221 residential units would be demolished and 10,500 new residential units would be constructed (7,279 net new units). No retail or commercial uses would be provided. As with the Proposed Project, the Buildout Under Current Zoning Regulations Alternative includes construction of (or provides financing for construction of) a series of traffic and transportation improvements designed to minimize the amount of automobile traffic originating from Parkmerced, and to improve traffic flow on adjacent roadways such as 19th Avenue and Brotherhood Way. This alternative would not include a separated stormwater collection and treatment system, unlike the Proposed Project. This alternative would include about 6 fewer acres of open space than in the Proposed Project; however, the open space in this alternative would be located between buildings and would not be as contiguous as that in the Proposed Project. No athletic fields or organic farm would be built. No wind turbines would be constructed on the Project Site.

There would be significant traffic impacts at the same locations as those identified for the Proposed Project under this alternative, although they would be somewhat exacerbated because more vehicle trips would be generated. There would be additional significant impacts at the intersections of Lake Merced Boulevard/Higuera Avenue and Lake Merced Boulevard/Gonzalez Drive. The impacts at the latter intersection would remain significant and unavoidable because mitigation would involve a double westbound left-turn lane and an additional northbound through lane, resulting in pedestrian safety issues. Under 2030 cumulative conditions, this alternative would contribute to significant cumulative impacts at four additional intersections compared to the Proposed Project's impacts.

Stormwater runoff from the site under the Buildout under Current Zoning Regulations Alternative would flow into the City's combined sewer system. Therefore, this alternative would not reduce the average annual number of combined sewer overflows, although it would not result in a significant increase in overflows and therefore would not result in a new significant impact on water quality.

Impacts on birds and bats from installation and operation of wind turbines identified as significant and unavoidable for the Proposed Project would not occur with this alternative, because no wind turbines are included in the alternative.

Other impacts of the Buildout under Current Zoning Regulations Alternative would be nearly the same as or similar to those identified for the Proposed Project, although in most cases the impacts would be slightly greater.

This alternative would provide more housing units than the Proposed Project and, thus, would further add to the City's housing stock and assist in meeting the City's share of the regional housing need. The alternative would reduce a significant impact on birds and bats by removing one of the renewable energy features included in the Proposed Project.

The Commission rejects the Buildout under Current Zoning Regulations Alternative because it would not reduce any of the other significant and unavoidable impacts of the Proposed Project; would not

reconfigure the Project Site's streets in accordance with the Better Streets Plan, would not provide new and more usable open spaces such as a park; would not provide a more fine-grained system of streets and pathways and therefore correct the deficiencies of the current site plan; would not provide neighborhood-serving retail and commercial uses in close proximity to residential uses, and therefore would not provide the same opportunities to reduce automobile use; it would increase the severity of traffic impacts on local intersections; it would not reduce stormwater flows in the City's combined sewer collection and treatment system; and it would not provide open space in such usable configurations as that in the Proposed Project and therefore would not provide high-quality open space to serve the residents within walking distance.

For these reasons, the Commission finds that, on balance, the Proposed Project is preferable to the Buildout under Current Zoning Regulations Alternative, and that alternative is rejected as infeasible.

3. Retention of the Historic District Central Core Alternative

Under the Retention of the Historic District Central Core Alternative, 2,567 existing units located around the inner core of the site and in the 11 existing tower buildings would remain, and approximately 3,000 new units would be constructed primarily around the western and southern portions of the site, for a total of 5,567 units on the site. About 84,900 gross square feet (gsf) of new retail, 55,900 gsf of new office space, and a new 64,000-gsf community center would be constructed in the eastern and southern areas of the site. Under the Historic District Central Core Alternative some, but not all of the traffic and infrastructure improvements planned for the Proposed Project would be constructed. The Muni light rail line would not be rerouted through the site due to site constraints; it would remain in 19th Avenue as at present, and the San Francisco State University station would remain in the 19th Avenue median. There would be 6 more open space acres than with the Proposed Project; the existing Commons and meadow areas would remain, and the private recreational facilities included in the Proposed Project would be constructed in this alternative. Wind turbines and solar photovoltaic cells would not be installed to offset a portion of the development's energy demand. A separate stormwater collection and treatment system would not be installed; stormwater would continue to be collected and treated in the City's combined sewer/stormwater system.

This alternative would result in the addition of about 2,346 new units to the City's housing stock, about 3,300 fewer than in the Proposed Project. This alternative would include about 205,000 sq. ft. of retail, commercial, and community uses, about 100,000 sq. ft. less than in the Proposed Project.

Retention of the historic district under this alternative would retain essential features and characteristics of the Parkmerced historical resource, and therefore there would be no project-level or cumulative historic architectural resources impacts under this alternative. With fewer residential units and less retail/commercial space, this alternative would result in significant traffic impacts at fewer intersections, although impacts at many of the study intersections would remain significant and unavoidable. The alternative would reduce significant impacts on the transit facilities in the northeast screenline to less-than-significant levels. Traffic generated by this alternative would cause impacts on transit travel times, as with the Proposed Project, but on three transit lines rather than six. Impacts on birds and bats from

installation and operation of wind turbines identified as significant and unavoidable for the Proposed Project would not occur with this alternative, because no wind turbines are included in the alternative.

The Commission rejects the Retention of the Historic District Central Core Alternative because it would add fewer residential units to the City's housing stock and therefore contribute less to the City and regional housing needs allocation; it would add fewer residential units in a urban infill location; it would provide less residential density and therefore would be less consistent with the City's goal to create a sustainable and self-sufficient "better" neighborhood that supports neighborhood serving retail, community facilities and transit infrastructure and service; although it would reduce, it would not eliminate significant transportation impacts; it would require that the majority of new housing be situated on a portion of the project site that is farthest from the Muni M Ocean View light rail line and therefore would be less likely to result in a reduction of automobile dependency; it would not reduce wet-weather flows in the City's combined wastewater collection and treatment system; it would provide fewer employment opportunities both during construction and in new retail and office space; it would not provide the reconfiguration of the street system in accordance with the Better Streets Plan; would not provide a more fine-grained system of streets and pathways and therefore correct the deficiencies of the existing automobile-oriented streets and site plan; would not reconfigure the open space at the Project Site to provide more usable open spaces such as a park; and would not re-route the M Ocean View light rail line into the Project Site, because doing so would negatively impact the historic resource, and therefore would be less consistent with the City's Transit First policy. For these reasons, the Commission finds that, on balance, the Proposed Project is preferable to the Historic District Central Core Alternative, and this alternative is rejected as infeasible.

4. Partial Historic District Alternative

Under the Partial Historic District Alternative, development would be similar to the Proposed Project except that a portion of the northwest corner of the Project Site would remain unchanged. Under this alternative, all 11 towers and two blocks of garden apartments would remain, comprising a total of containing 1,849 residential units. Under this alternative, the remainder of the buildings on the site would be demolished and redesigned to accommodate 6,689 new units (5,317 net new units) and a total of 8,538 units on site. The alternative would result in about 360 fewer residential units than the Proposed Project. Like the Proposed Project, a new neighborhood core containing 224,300 gsf of new neighborhood-serving retail and 80,000 gsf of new office space would be constructed within walking distance of the residences at Parkmerced. A new 37,800-gsf leasing office, a new 64,000-gsf community center, and a new 25,000-gsf school and day care facility, as well as about 70 acres of new open space uses, including athletic fields, walking and biking paths, and an approximately 2-acre organic farm, would also be built on the Project Site.

The development around the periphery of the Project Site would require amendments to the Planning Code and General Plan and approval of a Special Use District, similar to the Proposed Project but covering a smaller area.

Under the Partial Historic District Alternative, traffic and transit improvements would be similar to those planned under the Proposed Project. These improvements include rerouting the Metro M Ocean View light rail line from its current alignment along 19th Avenue, and providing modifications along 19th Avenue to accommodate the new route.

Similar to the Proposed Project, implementation of a sustainability plan would provide for a variety of new infrastructure improvements intended to reduce the alternative's per-unit use of electricity, natural gas, water, and the City's wastewater conveyance and treatment systems. A combination of renewable energy sources, including wind turbines and photovoltaic cells, would be used to meet a portion of this alternative's energy demand. In addition, stormwater runoff from buildings and streets would be captured and filtered through a series of bioswales, ponds, and other natural filtration systems. As with the Proposed Project, the filtered stormwater would then either percolate into the groundwater that feeds the Westside groundwater basin and Lake Merced or be released directly into Lake Merced.

The Commission rejects the Partial Historic District Alternative because retention of only a portion of the historic district resource would not be sufficient to convey its historic and architectural significance and would not justify its eligibility for inclusion in the CRHR. Thus, although this alternative would somewhat reduce impacts to the Parkmerced historic district historic resource, the impact would remain significant and unavoidable. Although a portion of the Parkmerced visual/scenic resource would be retained as a representative sample of the visual character that once existed on the Project Site, the portion retained would not be sufficient to convey the distinctive visual qualities of the site, and the alternative would not reduce significant visual quality impacts. Additionally, impacts on transportation, noise, air quality, wind, and biological resources would be similar to those of the Proposed Project and would not be substantially reduced with implementation of this alternative. Additionally, this alternative would not include the adoption of a land use program for Parkmerced that, among other things, maximizes walking, bicycling and use of public transportation, and minimizes the impacts and use of private automobiles by implementing a land use program with increased residential density and a commercial neighborhood core located within comfortable walking distance of transit service and residences. This alternative would also not provide sufficient housing to help alleviate the effects of suburban sprawl and protect the green belt. For these reasons, the Commission finds that, on balance, the Proposed Project is preferable to the Partial Historic District Alternative, and this alternative is rejected as infeasible.

5. Full Project Buildout With Transit Options Alternative

Under the Full Project Buildout with Transit Options Alternative, the 152-acre site would be replanned and redesigned exactly as it would for the Proposed Project, except for the configuration of the Muni light rail line. The number and location of new and retained residential units would be the same as under the Proposed Project, as would the retail, office, commercial, school and community space facilities, and open space configuration.

Under this alternative, the M Ocean View line would leave 19th Avenue at Holloway Avenue, turn south at Crespi Drive, and continue south through the neighborhood core, as it would with the Proposed Project.

However, unlike the Proposed Project, it would not re-enter 19th Avenue south of Felix Avenue. Instead, it would terminate at a new layover station constructed at the intersection of front Boulevard and Chumasero Drive. The J Church line would be extended from its current terminus at Balboa Park, continue west along the existing M Ocean View alignment, and terminate at a newly-constructed Muni stop on 19th Avenue just south of Holloway Avenue.

Other traffic and infrastructure improvements would be similar to the Proposed Project, except that the northbound left-turn lane at 19th Avenue/Crespi Drive would not be added. Like the Proposed Project, implementation of a sustainability plan would provide for a variety of new infrastructure improvements intended to reduce the per-unit use of electricity, natural gas, water, and the City's wastewater conveyance and treatment systems. A combination of renewable energy sources, including wind turbines and photovoltaic cells, would be used to meet a portion of this alternative's energy demand. In addition, stormwater runoff from buildings and streets would be captured and filtered through a series of bioswales, ponds, and other natural filtration systems. As with the Proposed Project, the filtered stormwater would then either percolate into the groundwater that feeds the Westside groundwater basin and Lake Merced or be released directly into Lake Merced.

A design variant studied under the Full Project Buildout with Transit Options Alternative involves dedicating the fourth southbound through lane on 19th Avenue to transit and high-occupancy vehicle use only (a HOT lane), rather than mixed-flow. There would be no change to this alternative's land use configuration or utilities under the variant.

The Full Buildout With Transit Options would not substantially reduce significant environmental impacts compared to the Proposed Project. A new significant impact would result at the intersection of 19th Avenue and Junipero Serra Boulevard during the weekend midday peak hour and a new cumulative impact would be added at this location during the weekday PM peak hour. (The new significant cumulative impact would not occur with the variant.) Thus, the total number of intersections impacted would be greater than the Proposed Project. This alternative would reduce significant impacts on travel time to less-than-significant levels on two transit lines that would be significantly impacted by the Proposed Project, but would continue to cause significant unavoidable impacts on travel times on the other four transit lines affected by the Proposed Project.

All other significant impacts identified under the Proposed Project for aesthetics, historic architectural resources, noise, air quality, wind, and biological resources would remain under this alternative.

Implementation of this alternative to change the routing of two Muni light rail lines is within the jurisdiction of the San Francisco Municipal Transportation Agency and outside the jurisdiction of the Planning Commission. In addition, the alternative does not substantially reduce the significant impacts of the Proposed Project. For these reasons, the Commission finds that, on balance, the Proposed Project is preferable to the Full Project Buildout With Transit Options Alternative, and this alternative is rejected as infeasible.

6. No Muni Realignment Alternative

As described in Section I above, the Project proposes to reroute the existing Muni Metro M Ocean View line from its current alignment along 19th Avenue, which would require the approval of Caltrans and the CPUC. In the event that such approval is not granted, the approval granted by this Commission would permit the Project to proceed after identifying an alternate transportation improvement of equivalent value to the proposed rerouting of the existing Muni Metro M Ocean View line. In the event that Caltrans and CPUC approval is not granted, the San Francisco Planning Commission approves adoption of the No Muni Realignment Alternative. In the event the Caltrans and CPUC approvals are granted, the Commission presently rejects this Alternative because the Project as proposed is preferable to this Alternative because overall, the alternative would not provide as direct a connection the M Ocean View light rail line for Parkmerced residents and visitors as would the Proposed Project, and would de-emphasize the overall transit-oriented feel of the Project Site. In addition, the alternative continues the overcrowded conditions at the SFSU Muni station. Therefore, the Proposed Project is preferable to the No Muni Realignment Alternative.

E. Alternatives Considered and Rejected in the EIR

1. Infill Development within the Historic District

An infill development within the historic district would retain the majority of the existing buildings and landscape features at Parkmerced, and include new construction of a series of 3- to 14-story infill buildings on the sites of the existing carports between garden apartment buildings, and on sites adjacent to the existing towers. In total, the new infill buildings would consist of 20 three-story buildings; 2 four-story buildings; 1 eight-story building; 2 eleven-story buildings; and 6 fourteen-story towers. Under this scenario, all of the existing 3,221 residential units would remain, and about 1,400 new units would be constructed (a total of 4,621 residential units on site); or about 4,280 fewer units than are included in the Proposed Project. There would be no transit or infrastructure improvements under this scenario, nor would there be any combination of renewable energy sources, such as wind turbines and photovoltaic cells, to offset any portion of energy demand. As under existing conditions, stormwater runoff from buildings and streets would flow into the combined sewer and stormwater lines that lead into the Oceanside Water Pollution Control Plant.

This potential EIR alternative was considered but not selected for detailed analysis in the EIR because it would not achieve most of the Project Sponsor's objectives including those related to maximizing the opportunity to create high-density housing near a commercial core, transportation and infrastructure improvements, and sustainability. Additionally, although this potential EIR alternative would reduce impacts on the Parkmerced historic district resource by retaining most of its existing physical features, it would not retain this resource's essential integrity as it would require demolition of the carports within the garden apartment courtyards and construction of new residential structures within the courtyards. As such, this potential alternative would result in a significant and unavoidable adverse impact on the Parkmerced historic district resource.

The Commission concurs with these findings in the EIR, and rejects this alternative as infeasible because it would not reduce significant impacts on the historic resource at Parkmerced, which would remain significant and unavoidable under this alternative, and would provide substantially fewer residential units. The alternative is also infeasible because it would not provide a neighborhood core of residential and commercial uses with immediate access to transit and therefore would be less likely to encourage use of travel modes other than single-occupant automobile. It would also not reduce the overcrowded conditions at the existing SFSU Muni station in the 19th Avenue median. Therefore the Proposed Project is preferable.

2. West Side Partial Historic District

Preservation of a partial historic district on the west side of Parkmerced would retain about half of the garden courtyard apartment block surrounding Juan Bautista Circle, as well as the blocks surrounding the Meadow and along a portion of Arballo Drive. In addition, all eleven of the tower buildings, the Administration Building, and some of the major landscape features, including the landscaping along Font Boulevard, would be retained. In total, 2,365 existing units would be retained. In the remaining portion of the 152-acre site, about 4,100 new residential units would be constructed (a total of 6,465 units on site), about 2,435 fewer than the Proposed Project. This scenario would include about 120,000 gsf of retail space, 47,500 gsf of office space, a new 64,000-gsf community center, and a 37,800-gsf leasing office, for a total of about 205,300 gsf, about 105,000 gsf less than the Proposed Project. The new 25,000-gsf school and new open space uses including athletic playing fields would be the same as or similar to the Proposed Project.

Under this scenario, transit and transportation improvements would be similar to those in the Proposed Project, including rerouting of the Metro M Ocean View line from its current alignment along 19th Avenue into the Project Site.

Unlike the Proposed Project, there would be no renewable energy sources, such as wind turbines and photovoltaic cells, to offset any portion of energy demand. As under existing conditions, stormwater runoff from buildings and streets would flow into the combined sewer and stormwater lines that lead to the Oceanside Water Pollution Control Plant.

This potential EIR alternative was considered but not selected for detailed analysis in the EIR because it would not achieve the Project Sponsor's objectives, particularly those related to maximizing the opportunity to create high-density housing near a commercial center, sustainability, and financial feasibility. In addition, this potential EIR alternative would not avoid a significant adverse impact on the significance of the Parkmerced's historic district resource. Although a portion of the existing Parkmerced historic district resource would be retained as a representative sample of the historic and architectural significance of the original Parkmerced historic district resource, the retained portion would not be sufficient to convey its historic and architectural significance to justify its eligibility for inclusion in the CRHR, and thus this impact would remain significant and unavoidable.

The Commission concurs with the findings in the EIR, and rejects this alternative as infeasible because it would not avoid significant impacts on the historic resource, and would provide substantially fewer residential units than the Proposed Project.

VII. STATEMENT OF OVERRIDING CONSIDERATIONS

Pursuant to CEQA section 21081 and CEQA Guideline 15093, the Commission hereby finds, after consideration of the Final EIR and the evidence in the record, that each of the specific overriding economic, legal, social, technological and other benefits of the Project as set forth below independently and collectively outweighs the significant and unavoidable impacts and is an overriding consideration warranting approval of the Project. Any one of the reasons for approval cited below is sufficient to justify approval of the Project. Thus, even if a court were to conclude that not every reason is supported by substantial evidence, the Commission will stand by its determination that each individual reason is sufficient. The substantial evidence supporting the various benefits can be found in the preceding findings, which are incorporated by reference into this Section, and in the documents found in the Record of Proceedings, as defined in Section I.

On the basis of the above findings and the substantial evidence in the whole record of this proceeding, the Commission specially finds that there are significant benefits of the Project in spite of the unavoidable significant impacts, and therefore makes this Statement of Overriding Considerations. The Commission further finds that, as part of the process of obtaining Project approval, all significant effects on the environment from implementation of the Project have been eliminated or substantially lessened where feasible. The Commission has determined that any remaining significant effects on the environment found to be unavoidable are acceptable due to the following specific overriding economic, technical, legal, social and other considerations.

The Project will have the following benefits:

- Addition of approximately 5,679 residential units to the City's housing stock, including affordable housing, and helping the City to meet its regional housing needs allocation;
- Addition of approximately 5,679 residential units to the City's housing stock within an urban infill location at close proximity to transit, which will assist in alleviating the effects of suburban sprawl and development of the greenbelt.
- Development of a innovative land use program that provides an innovative model of environmentally sustainable design practices, to, among other things maximize walking, bicycling and use of public transportation, and minimize the impacts and use of private automobiles by implementing a land use program with increased residential density and a commercial neighborhood core located within comfortable walking distance of transit service and residences.

- One-for-one replacement of 1,538 rent-controlled dwelling units currently existing on the Project Site with, under the terms of the Proposed Development Agreement, new rent-controlled units, each of approximately equal or greater size and with the same or greater number of bedrooms and bathrooms as the Existing Unit being replaced. Although none of the Existing Units have washer or dryers, each Replacement Unit will have a washer and a dryer and a dish washer installed by Developer prior to occupancy;
- Under the terms of the proposed Development Agreement, the City is providing certain benefits to the project that, along with Developer's waiver of all rights under the Costa-Hawkins Rental Housing Act and any similar or successor law, are designed to ensure that (i) each Replacement Unit will be subject to rent control and other provisions and provisions protecting tenants under the San Francisco Rent Ordinance and (ii) each Inclusionary Unit will be subject to the City's Inclusionary Unit requirements as set forth in Planning Code section 315;
- Under the terms of the proposed Development Agreement, relocation by Developer of Existing Tenants from their Existing Units to the Replacement Units, with an initial rent and equal to the rent charged to the Existing Tenant for their Existing Unit at the time of relocation to the Replacement Unit, with the right to remain in the Replacement Unit for an unlimited term subject to the eviction rules, procedures and protections set forth in the San Francisco Rent Ordinance, and no pass throughs added to rent of the Replacement Unit for the capital costs of the Project;
- Construction of two new transit stations, relocation of an existing transit station, and a new alignment for the MUNI Metro M-Oceanview, integrated into the SFMTA transit system, that will leave 19th Avenue at Holloway Avenue and proceed through the neighborhood core in Parkmerced as further described in the Transportation Plan, and the provision of a low emissions shuttle bus from Parkmerced to the Daly City BART station and to the Stonestown retail center;
- Reconfiguration of the street grid within the Project Site to conform with San Francisco's Better Streets design guidelines, including the realignment of existing streets and the creation of new publicly-owned streets and publicly-accessible streets that accommodate bicycles, pedestrians and motor vehicles;
- Improvement and reconfiguration of streets and intersections on the periphery of the Project Site to improve access and safety for all modes of transportation;
- Creation and implementation of a Transportation Demand Management ("TDM") program, including but not limited to transit pass subsidies for residents and employees in the Project Site, to facilitate and encourage the use of transportation modes other than the private automobile, to minimize the amount of automobile traffic originating from Parkmerced and to improve traffic flow on adjacent roadways such as 19th Avenue and Brotherhood Way, as further described in the Transportation Plan;
- Reconfiguration of the existing open space at Parkmerced to provide more usable open spaces and related public benefits such as a new park, athletic fields, an organic farm, walking and bicycling paths, and community gardens;
- Construction of a series of bioswales, ponds, and other natural filtration systems to capture and filter stormwater runoff from buildings and streets in accordance with the Infrastructure Plan and

the Sustainability Plan. The filtered stormwater will either percolate into the groundwater that feeds the Upper Westside groundwater basin and Lake Merced or be released directly into Lake Merced. This feature of the Proposed Project will reduce the amount of stormwater flows directed to the Oceanside Water Pollution Control Plant and reduce combined sewage overflows to the ocean.

- Zoning of a parcel for the construction of an elementary school.
- Provision of renewable energy sources on site—installation of photovoltaic cells on up to 50 percent of roof areas of new buildings and up to 51 vertical axis wind turbines; and
- Provision of employment opportunities during construction and in newly-constructed retail and commercial space in the neighborhood core during this period of high unemployment in the City and the region.

In the event that any Non-City agency required to approve the realignment of the Muni M Oceanview line as proposed by the Project denies such approval, Pursuant to CEQA section 21081 and CEQA Guideline 15093, the Commission hereby finds, after consideration of the Final EIR and the evidence in the record, that each of the specific overriding economic, legal, social, technological and other benefits of No Muni Realignment Alternative as set forth below independently and collectively outweighs the significant and unavoidable impacts and is an overriding consideration warranting approval of the No Muni Realignment Alternative. Any one of the reasons for approval cited below is sufficient to justify approval of the No Muni Realignment Alternative. Thus, even if a court were to conclude that not every reason is supported by substantial evidence, the Commission will stand by its determination that each individual reason is sufficient. The substantial evidence supporting the various benefits can be found in the preceding findings, which are incorporated by reference into this Section, and in the documents found in the Record of Proceedings, as defined in Section I.

On the basis of the above findings and the substantial evidence in the whole record of this proceeding, the Commission specially finds that there are significant benefits of the Project in spite of the unavoidable significant impacts, and therefore makes this Statement of Overriding Considerations. The Commission further finds that, as part of the process of obtaining project approval, all significant effects on the environment from implementation of the No Muni Realignment Alternative have been eliminated or substantially lessened where feasible. The Commission has determined that any remaining significant effects on the environment found to be unavoidable are acceptable due to the following specific overriding economic, technical, legal, social and other considerations.

The No Muni Realignment Alternative will have the following benefits:

- Addition of approximately 5,679 residential units to the City's housing stock, including affordable housing, and helping the City to meet its regional housing needs allocation;
- Addition of approximately 5,679 residential units to the City's housing stock within an urban infill location at close proximity to transit, which will assist in alleviating the affects of suburban sprawl and development of the greenbelt.

- Development of a innovative land use program that provides an innovative model of environmentally sustainable design practices, to, among other things maximize walking, bicycling and use of public transportation, and minimize the impacts and use of private automobiles by implementing a land use program with increased residential density and a commercial neighborhood core located within comfortable walking distance of transit service and residences.
- One-for-one replacement of 1,538 rent-controlled dwelling units currently existing on the Project Site with, under the terms of the Proposed Development Agreement, new rent-controlled units, each of approximately equal or greater size and with the same or greater number of bedrooms and bathrooms as the Existing Unit being replaced. Although none of the Existing Units have washer or dryers, each Replacement Unit will have a washer and a dryer and a dish washer installed by Developer prior to occupancy;
- Under the terms of the proposed Development Agreement, the City is providing certain benefits to the project that, along with Developer's waiver of all rights under the Costa-Hawkins Rental Housing Act and any similar or successor law, are designed to ensure that (i) each Replacement Unit will be subject to rent control and other provisions and provisions protecting tenants under the San Francisco Rent Ordinance and (ii) each Inclusionary Unit will be subject to the City's Inclusionary Unit requirements as set forth in Planning Code section 315;
- Under the terms of the proposed Development Agreement, relocation by Developer of Existing Tenants from their Existing Units to the Replacement Units, with an initial rent and equal to the rent charged to the Existing Tenant for their Existing Unit at the time of relocation to the Replacement Unit, with the right to remain in the Replacement Unit for an unlimited term subject to the eviction rules, procedures and protections set forth in the San Francisco Rent Ordinance, and no pass throughs added to rent of the Replacement Unit for the capital costs of the Project;
- The provision of a low emissions shuttle bus from Parkmerced to the Daly City BART station and to the Stonestown retail center;
- Reconfiguration of the street grid within the Project Site to conform with San Francisco's Better Streets design guidelines, including the realignment of existing streets and the creation of new publicly-owned streets and publicly-accessible streets that accommodate bicycles, pedestrians and motor vehicles;
- Improvement and reconfiguration of streets and intersections on the periphery of the Project Site to improve access and safety for all modes of transportation;
- Creation and implementation of a Transportation Demand Management ("TDM") program, including but not limited to transit pass subsidies for residents and employees in the Project Site, to facilitate and encourage the use of transportation modes other than the private automobile, to minimize the amount of automobile traffic originating from Parkmerced and to improve traffic flow on adjacent roadways such as 19th Avenue and Brotherhood Way, as further described in the Transportation Plan;

- Reconfiguration of the existing open space at Parkmerced to provide more usable open spaces and related public benefits such as a new park, athletic fields, an organic farm, walking and bicycling paths, and community gardens;
- Construction of a series of bioswales, ponds, and other natural filtration systems to capture and filter stormwater runoff from buildings and streets in accordance with the Infrastructure Plan and the Sustainability Plan. The filtered stormwater will either percolate into the groundwater that feeds the Upper Westside groundwater basin and Lake Merced or be released directly into Lake Merced. This feature of the Proposed Project will reduce the amount of stormwater flows directed to the Oceanside Water Pollution Control Plant and reduce combined sewage overflows to the ocean.
- Zoning of a parcel for the construction of an elementary school.
- Provision of renewable energy sources on site—installation of photovoltaic cells on up to 50 percent of roof areas of new buildings and up to 51 vertical axis wind turbines; and
- Provision of employment opportunities during construction and in newly-constructed retail and commercial space in the neighborhood core during this period of high unemployment in the City and the region.

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
MITIGATION MEASURES FOR THE PARKMERCED PROJECT				
<i>Cultural Resources and Archeological Paleontological Resources Mitigation Measures</i>				
<p>Mitigation Measure M-CR-1: Documentation and Interpretation</p> <p><u>Documentation</u></p> <p>The Project Sponsor shall retain a professional who meets the Secretary of the Interior's Professional Qualifications Standards for Architectural History to prepare written and photographic documentation of the Parkmerced complex within the Project Site.</p> <p>The documentation for the property shall be prepared based on the National Park Service's (NPS) Historic American Building Survey (HABS) / Historic American Engineering Record (HAER) Historical Report Guidelines, and will include a selection of measured drawings based upon NPS Historic American Landscape Survey (HALS) Guidelines. This type of documentation is based on a combination of both HABS/HAER standards (Levels I, II and III) and NPS's policy for photographic documentation as outlined in the National Register of Historic Places and National Historic Landmarks Survey Photo Policy Expansion.</p> <p>The measured drawings for this documentation shall follow HALS Level I standards. To determine the number of the measured drawings, the professional shall consult with the San Francisco Planning Department's Preservation Coordinator.</p> <p>The written historical data for this documentation shall follow HABS / HAER Level I standards. The written data shall be accompanied by a sketch plan of the property. Efforts should also be made to locate original construction drawings or plans of the property during the period of significance. If located, these drawings should be photographed, reproduced, and included in the dataset. If construction drawings or plans cannot be located, as-built drawings shall be produced.</p> <p>Either HABS/HAER standard large format or digital photography shall be used. If digital photography is used, the ink and paper combinations for printing photographs must be in compliance with NR-NHL Photo Policy Expansion and have a permanency rating of approximately 115 years. Digital photographs will be taken as uncompressed, TIF file format. The size of each image will be 1600x1200 pixels at 330 ppi (pixels per inch) or larger, color format, and printed in black and white. The file name for each electronic image shall correspond with the index of photographs and photograph label.</p> <p>Photograph views for the dataset shall include (a) contextual views; (b) views of each side of each building and interior views, where possible; (c) oblique views of buildings; and (d) detail views of character-defining features, including features on the interiors of some buildings. All views shall be referenced on a photographic key. This</p>	<p>Project sponsor to retain qualified professional consultant</p>	<p>Prior to construction submittal of HABS/HAER/HALS guidelines documentation for approval by Planning Department.</p> <p>Prior to construction, transmit documentation to the SF Library, and NWIC.</p>	<p>Consultant to submit report to Planning Department</p>	

178

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>consultant's work shall be conducted in accordance with this measure and the requirements of the ARDTP (Aroheo-Tec, Archeological Research Design and Treatment Plan, Parkmerced Project, March 2010) at the direction of the Environmental Review Officer (ERO). In instances of inconsistency between the requirements of the project ARDTP and the requirements of this mitigation measure, the requirements of this archaeological mitigation measure shall prevail. All plans and reports prepared by the consultant as specified herein shall be submitted first and directly to the ERO for review and comment, and shall be considered draft reports subject to revision until final approval by the ERO. Archaeological monitoring and/or data recovery programs required by this measure could suspend construction of the project for up to a maximum of four weeks. At the direction of the ERO, the suspension of construction can be extended beyond four weeks only if such a suspension is the only feasible means to reduce to a less-than-significant level potential effects on a significant archaeological resource as defined in CEQA Guidelines Section 15064.5 (a)(c).</p> <p><u>Archaeological Testing Program</u></p> <p>The archaeological consultant shall prepare and submit to the ERO for review and approval an archaeological testing plan (ATP). The archaeological testing program shall be conducted in accordance with the approved ATP. The ATP shall identify the property types of the expected archaeological resource(s) that potentially could be adversely affected by the proposed project, the testing method to be used, and the locations recommended for testing. The purpose of the archaeological testing program will be to determine to the extent possible the presence or absence of archaeological resources and to identify and to evaluate whether any archaeological resource encountered on the site constitutes an historical resource under CEQA.</p> <p>At the completion of the archaeological testing program, the archaeological consultant shall submit a written report of the findings to the ERO. If based on the archaeological testing program the archaeological consultant finds that significant archaeological resources may be present, the ERO in consultation with the archaeological consultant shall determine if additional measures are warranted. Additional measures that may be undertaken include additional archaeological testing, archaeological monitoring, and/or an archaeological data recovery program. If the ERO determines that a significant archaeological resource is present and that the resource could be adversely affected by the proposed project, at the discretion of the project sponsor either:</p> <p>A) The proposed project shall be re-designed so as to avoid any adverse effect on the significant archaeological resource; or</p> <p>B) A data recovery program shall be implemented, unless the ERO determines that the archaeological resource is of greater interpretive than research significance</p>	<p>Project sponsor to retain appropriately qualified consultant</p>	<p>Prior to and during construction</p>	<p>If applicable, upon discovery of human remains and/or associated or unassociated funerary objects, the consultant shall notify the Coroner of the City and County of San Francisco, and in the event of the Coroner's determination that the human remains, notification of the California State Native American Heritage Commission who shall appoint a Most Likely Descendant (MLD) who shall make reasonable efforts to develop an agreement for the treatment of human remains and/or associated or unassociated funerary objects.</p> <p>Consultant to prepare draft and final Archeological Resources Report reports. The ERO to review and approve the Final Archeological Resources Report</p>	

180

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>and that interpretive use of the resource is feasible.</p> <p><u>Archaeological Monitoring Program (AMP)</u></p> <p>If the ERO in consultation with the archaeological consultant determines that an archaeological monitoring program shall be implemented the archaeological monitoring program shall minimally include the following provisions:</p> <ul style="list-style-type: none"> • The archaeological consultant, project sponsor, and ERO shall meet and consult on the scope of the AMP reasonably prior to any project-related soils-disturbing activities commencing. The ERO in consultation with the archaeological consultant shall determine what project activities shall be archaeologically monitored. In most cases, any soils-disturbing activities, such as demolition, foundation removal, excavation, grading, utilities installation, foundation work, driving of piles (foundation, shoring, etc.), site remediation, etc., shall require archaeological monitoring because of the risk these activities pose to potential archaeological resources and to their depositional context; • The archaeological consultant shall advise all project contractors to be on the alert for evidence of the presence of the expected resource(s), of how to identify the evidence of the expected resource(s), and of the appropriate protocol in the event of apparent discovery of an archaeological resource; • The archaeological monitor(s) shall be present on the project site according to a schedule agreed upon by the archaeological consultant and the ERO until the ERO has, in consultation with the project archaeological consultant, determined that project construction activities could have no effects on significant archaeological deposits; • The archaeological monitor shall record and be authorized to collect soil samples and artifactual/ecofactual material as warranted for analysis; • If an intact archaeological deposit is encountered, all soils-disturbing activities in the vicinity of the deposit shall cease. The archaeological monitor shall be empowered to temporarily redirect demolition/excavation/pile driving/construction activities and equipment until the deposit is evaluated. If in the case of pile-driving activity (foundation, shoring, etc.), the archaeological monitor has cause to believe that the pile-driving activity may affect an archaeological resource, the pile-driving activity shall be terminated until an appropriate evaluation of the resource has been made in consultation with the ERO. The archaeological consultant shall immediately notify the ERO of the encountered archaeological deposit. The archaeological consultant shall make a reasonable effort to assess the identity, integrity, and significance of the 	<p>Project sponsor to retain appropriately qualified consultant</p>	<p>Prior to and during construction</p>		

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>encountered archaeological deposit, and present the findings of this assessment to the ERO.</p> <p>Whether or not significant archaeological resources are encountered, the archaeological consultant shall submit a written report of the findings of the monitoring program to the ERO.</p> <p><u>Archaeological Data Recovery Program</u></p> <p>The archaeological data recovery program shall be conducted in accord with an archaeological data recovery plan (ADRP). The archaeological consultant, project sponsor, and ERO shall meet and consult on the scope of the ADRP prior to preparation of a draft ADRP. The archaeological consultant shall submit a draft ADRP to the ERO. The ADRP shall identify how the proposed data recovery program will preserve the significant information the archaeological resource is expected to contain. That is, the ADRP will identify what scientific/historical research questions are applicable to the expected resource, what data classes the resource is expected to possess, and how the expected data classes would address the applicable research questions. Data recovery, in general, should be limited to the portions of the historical property that could be adversely affected by the proposed project. Destructive data recovery methods shall not be applied to portions of the archaeological resources if non-destructive methods are practical.</p> <p>The scope of the ADRP shall include the following elements:</p> <ul style="list-style-type: none"> • Field Methods and Procedures. Descriptions of proposed field strategies, procedures, and operations. • Cataloguing and Laboratory Analysis. Description of selected cataloguing system and artifact analysis procedures. • Discard and De-accession Policy. Description of and rationale for field and post-field discard and de-accession policies. • Interpretive Program. Consideration of an on-site/off-site public interpretive program during the course of the archaeological data recovery program. • Security Measures. Recommended security measures to protect the archaeological resource from vandalism, looting, and non-intentionally damaging activities. • Final Report. Description of proposed report format and distribution of results. • Curation. Description of the procedures and recommendations for the 	<p>Project sponsor to retain appropriately qualified consultant</p>	<p>Prior to and during construction</p>		

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>curation of any recovered data having potential research value, identification of appropriate curation facilities, and a summary of the accession policies of the curation facilities.</p> <p><u>Human Remains and Associated or Unassociated Funerary Objects</u></p> <p>The treatment of human remains and of associated or unassociated funerary objects discovered during any soils-disturbing activity shall comply with applicable State and Federal laws. This shall include immediate notification of the Coroner of the City and County of San Francisco and in the event of the Coroner's determination that the human remains are Native American remains, notification of the California State Native American Heritage Commission (NAHC) who shall appoint a Most Likely Descendant (MLD) (Pub. Res. Code Sec. 5097.98). The archaeological consultant, project sponsor, and MLD shall make all reasonable efforts to develop an agreement for the treatment of, with appropriate dignity, human remains and associated or unassociated funerary objects (CEQA Guidelines Sec. 15064.5(d)). The agreement should take into consideration the appropriate excavation, removal, recordation, analysis, custodianship, curation, and final disposition of the human remains and associated or unassociated funerary objects.</p> <p><u>Final Archaeological Resources Report</u></p> <p>The archaeological consultant shall submit a Draft Final Archaeological Resources Report (FARR) to the ERO that evaluates the historical significance of any discovered archaeological resource and describes the archaeological and historical research methods employed in the archaeological testing/monitoring/data recovery program(s) undertaken. Information that may put at risk any archaeological resource shall be provided in a separate removable insert within the final report.</p> <p>Once approved by the ERO, copies of the FARR shall be distributed as follows: California Archaeological Site Survey Northwest Information Center (NWIC) shall receive one (1) copy and the ERO shall receive a copy of the transmittal of the FARR to the NWIC. The Major Environmental Analysis division of the Planning Department shall receive two copies (bound and unbound) and one unlocked, searchable PDF copy on a CD or DVD of the FARR along with copies of any formal site recordation forms (CA DPR 523 series) and/or documentation for nomination to the National Register of Historic Places/California Register of Historical Resources. In instances of high public interest in or the high interpretive value of the resource, the ERO may require a different final report content, format, and distribution than that presented above.</p>				
<p>Mitigation Measure M-CR-3b: Archaeological Treatment Plan for Subsequent Project Phases</p> <p>Based on a reasonable presumption that archaeological resources may be present within</p>	<p>Project sponsor to retain appropriate consultant</p>	<p>The project archaeologist to consult with ERO prior to preparation of TP. The</p>	<p>Project archaeologist to provide draft and final reports. ERO to review</p>	

183

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>the Project Site, the following measures shall be undertaken to avoid any potentially significant adverse effect from subsequent project phases the Proposed Project on buried archaeological resources. The Project Sponsor shall retain the services of a qualified archaeological consultant having expertise in California prehistoric and urban historical archaeology. The archaeological consultant shall prepare an archaeological treatment plan (TP). The archaeological consultant's work shall be conducted in accordance with this measure at the direction of the Environmental Review Officer (ERO). All plans and reports prepared by the consultant as specified herein shall be submitted first and directly to the ERO for review and comment, and shall be considered draft reports subject to revision until final approval by the ERO.</p> <p>Archaeological Treatment Plan. The archaeological consultant shall meet and consult with the ERO on the scope of the TP prior to preparation of the TP. The TP shall be submitted to the ERO for review and approval prior to the Project ground-breaking activities for subsequent project phases. Archaeological field investigations for subsequent project phases shall be conducted in accordance with the approved TP. The TP shall identify project-specific vertical / horizontal areas of archaeological sensitivity and appropriate archaeological identification and evaluation strategies, and archaeological mitigatory protocols applicable to specific project activities / improvements (for example, excavation building foundation installation, grading, etc.) with the potential to affect archaeological properties. Mitigation strategies requiring archaeological testing plans (ATP) and archaeological monitoring plans (AMP) shall conform to the requirements for preparation and implementation including preparation of archaeological investigation and data recovery results reporting of an ATP and AMP in Mitigation Measure M-CR-3a.</p>		<p>TP for each phase to be completed prior to ground-breaking for that phase. ATP and AMPs, where necessary, shall be prepared pursuant to schedule in M-CR-3a.</p>	<p>and approve</p>	
<p>M-CR-5: Paleontological Resources Monitoring and Mitigation Program</p> <p>The Project Sponsor shall retain the services of a qualified paleontological consultant having expertise in California paleontology to design and implement a Paleontological Resources Monitoring and Mitigation Program (PRMMP). The PRMMP shall include a description of when and where construction monitoring would be required; emergency discovery procedures; sampling and data recovery procedures; procedure for the preparation, identification, analysis, and curation of fossil specimens and data recovered; preconstruction coordination procedures; and procedures for reporting the results of the monitoring program.</p> <p>The PRMMP shall be consistent with the Society for Vertebrate Paleontology (SVP) Standard Guidelines for the mitigation of construction-related adverse impacts to paleontological resources and the requirements of the designated repository for any fossils collected. During construction, earth-moving activities shall be monitored by a qualified paleontological consultant having expertise in California paleontology in the</p>	<p>Project sponsor to retain appropriately qualified consultant to prepare PRMMP, carry out monitoring, and reporting</p>	<p>Prior to and during construction.</p> <p>The project paleontological consultant to consult with the ERO as indicated; completed when ERO accepts final report</p>	<p>ERO to approve final PRMMP.</p> <p>Consultant shall provide brief monthly reports to ERO during monitoring or as identified in the PRMMP, and notify the ERO immediately if work should stop for data recovery during monitoring.</p>	

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>areas where these activities have the potential to disturb previously undisturbed native sediment or sedimentary rocks. Monitoring need not be conducted in areas where the ground has been previously disturbed, in areas of artificial fill, in areas underlain by nonsedimentary rocks, or in areas where exposed sediment would be buried, but otherwise undisturbed.</p> <p>The consultant's work shall be conducted in accordance with this measure and at the direction of the City's Environmental Review officer (ERO). Plans and reports prepared by the consultant shall be submitted first and directly to the ERO for review and comment, and shall be considered draft reports subject to revision until final approval by the ERO. Paleontological monitoring and/or data recovery programs required by this measure could suspend construction of the Proposed Project for up to a maximum of four weeks. At the direction of the ERO, the suspension of construction can be extended beyond four weeks only if such a suspension is the only feasible means to reduce potential effects on a significant paleontological resource as previously defined to a less-than-significant level.</p>			<p>The ERO to review and approve the final documentation as established in the PRMMP</p>	
Transportation and Circulation				
<p>M-TR-1: Parkmerced Construction Traffic Management Program.</p> <p>The Project Sponsor shall develop and implement a Construction Traffic Management Program to minimize impacts of the Project and its contribution to cumulative impacts related to construction activities and construction traffic. The program shall provide necessary information to various contractors and agencies as to how to maximize the opportunities for complementing construction management measures and to minimize the possibility of conflicting impacts on the roadway system, while safely accommodating the traveling public in the area. The program shall supplement and expand, rather than modify or supersede any manual, regulations, or provisions set forth by SFMTA, DPW or other City departments and agencies.</p> <p>Preparation of the Construction Management Program shall be the responsibility of the Project Sponsor, and shall be reviewed and approved by SFMTA and DPW prior to initiation of construction. The program shall:</p> <ul style="list-style-type: none"> • Identify construction traffic management practices in San Francisco, as well as other jurisdictions that could provide useful guidance for a project of this size and characteristic. • Describe procedures required by different departments and/or agencies in the City for implementation of a construction management plan, such as reviewing agencies, approval process, and estimated timelines. • Identify construction traffic management strategies and other elements for the 	<p>Project sponsor and sponsor's construction contractor(s)</p>	<p>Prior to construction in each development phase.</p>	<p>Planning Department, SFMTA, and DPW</p>	

185

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>Project, and present a cohesive program of operational and demand management strategies designed to maintain acceptable traffic operations during periods of construction activities in the Project area. These could include construction strategies, demand management strategies, alternate route strategies, and public information strategies.</p> <ul style="list-style-type: none"> • Coordinate with other projects in construction in the immediate vicinity, so that they can take an integrated approach to construction-related traffic impacts. • Present guidelines for selection of construction traffic management strategies. 				
<p>M-TR-2A: Do not construct the proposed northbound left-turn lane from 19th Avenue onto Crespi Drive. The northbound left-turn lane from 19th Avenue to Crespi Drive would require southbound traffic on 19th Avenue to stop to allow northbound left-turning traffic.</p>	<p>Project sponsor and sponsor's construction contractor(s)</p>	<p>No left hand turn lane would be constructed.</p>	<p>Sponsor to provide revised plans to Planning Department as part of Development Agreement; Planning Department to review and acknowledge change in proposed street configurations.</p>	
<p>M-TR-2C: Construct a dedicated northbound right-turn lane from Lake Merced Boulevard to eastbound Winston Drive. This improvement would provide a dedicated lane for the relatively large number of vehicles expected to execute the northbound right-turn movement. Implementation of the roadway improvement would require roadway widening to the east, which necessitates relocation of the sidewalk, a utility box, a signal mast, and several other elements.</p> <p>Funding, implementation, and construction of this measure shall be the responsibility of the Project Sponsor. The feasibility of this measure is uncertain due to the adjacent unsignalized intersection, approximately 75 feet south of Winston Drive, which would conflict with the northbound right-turn lane.</p> <p>[SFMTA to determine if this is feasible, and if SFMTA determines that it is not, this mitigation measure shall not be implemented.]</p>	<p>Project sponsor and sponsor's construction contractor(s) in consultation with SFMTA</p>	<p>The following effective PM peak hour auto trip generation rates for each major land use proposed (accounting for the mix of uses and the level of transit service proposed) and the total number of PM peak hour trips generated by the Proposed Project that would trigger the need for this mitigation measure are shown below:</p> <p>Effective PM Peak Hour Trip Generation Rates (vehicle trips per unit of</p>	<p>SFMTA</p>	

186

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
		<p>development):</p> <p>Residential: 0.35 trips / dwelling unit</p> <p>Retail: 3.24 trips / 1,000 square feet</p> <p>Commercial: 3.76 trips / 1,000 square feet</p> <p>Recreational: 0.84 trips / 1,000 square feet</p> <p>Schools: 1.60 trips / 1,000 square feet</p> <p>A feasibility study must be completed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 930 trips based on the trip generation rates as described above.</p> <p>If the mitigation measure is deemed feasible, the mitigation measure must be constructed prior to the</p>		

187

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
		issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 930, based on the trip generation rates as described above.		
<p>M-TR-2D: Provide a third northbound through lane and a second southbound left-turn lane at the Lake Merced Boulevard/Font Boulevard intersection. This mitigation measure would require restriping the northbound right-turn lane at the Lake Merced Boulevard/State Drive intersection as a through lane and removing the on-street parking on the north side of the intersection to recreate the dedicated right-turn lane (assuming that it is required for acceptable operations at this intersection).</p> <p>Additionally, providing a second southbound left-turn lane at this intersection would require removal of on-street parking on the south side of Font Boulevard to create a second receiving lane, as well as the removal of some spaces on the west side of Lake Merced Boulevard and shifting the through travel lanes to the west to make room for the second southbound left-turn lane.</p> <p>Implementation would require significant roadway restriping and signal optimization and coordination at multiple intersections, as well as the removal of approximately 25 parking spaces. Funding, implementation, and construction of this measure shall be the responsibility of the Project Sponsor.</p> <p>[SFMTA to determine if this is feasible, and if SFMTA determines that it is not, this mitigation measure shall not be implemented.]</p>	Project sponsor and sponsor's construction contractor(s) in consultation with SFMTA	<p>A feasibility study must be completed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 930, based on the trip generation rates described in M-TR-2C.</p> <p>If the mitigation measure is deemed feasible, the mitigation measure must be constructed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 930, based on the trip generation rates described in M-TR-2C.</p>	SFMTA	
<p>M-TR-2E: Reconfigure the westbound right-turn and southbound left-turn as the primary movements of the intersection of Lake Merced Boulevard/Brotherhood Way. This would</p>	Project sponsor and sponsor's	A feasibility study must be completed prior to the	SFMTA	

188

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>convert the northbound approach of Lake Merced Boulevard into the "minor" approach to the intersection. Although the configuration may be able to fit within the existing right-of-way at the intersection, further study is needed to determine the feasibility of this measure. A conceptual intersection configuration is presented in the Project's Transportation Study. Funding, implementation, and construction of this measure shall be the responsibility of the Project Sponsor.</p>	<p>construction contractor(s) in consultation with SFMTA</p>	<p>issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 1,128, based on the trip generation rates described in M-TR-2C.</p> <p>If the mitigation measure is deemed feasible, the mitigation measure must be constructed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 1,128, based on the trip generation rates described in M-TR-2C.</p>		
<p>M-TR-9: Eliminate the weaving segment between the loop on-ramp from Brotherhood Way and the loop off-ramp to Brotherhood Way by reconfiguring the interchange. Specifically, evaluate the feasibility of closing the loop on-ramp from eastbound Brotherhood Way to northbound SR 1 and instead constructing an eastbound left-turn lane from Brotherhood Way on the east side of the structure. The direct on-ramp from westbound Brotherhood Way to northbound SR 1 should be configured with one access point to serve traffic from westbound Brotherhood Way and those making a left-turn from eastbound Brotherhood Way.</p> <p>The eastbound left turn-lane can and shall be constructed to approximately 150 feet in length. Ultimately, this measure may require a design exception from Caltrans.</p> <p>Funding, implementation, and construction of this measure shall be the responsibility of the Project Sponsor.</p>	<p>Project sponsor and sponsor's construction contractor(s) in consultation with SFMTA and Caltrans</p>	<p>A feasibility study must be completed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 755, based on the trip generation rates described in M-TR-2C.</p> <p>If the mitigation measure is deemed feasible, the</p>	<p>SFMTA</p>	

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
		mitigation measure must be constructed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 755, based on the trip generation rates described in M-TR-2C.		
<p>M-TR-12: Contribute fair share toward developing and implementing revised transit service plan that increases capacity on the M Ocean View. Fund a fair-share contribution towards evaluating and implementing a revised operating plan to increase frequencies on the M Ocean View from 10 minute headways (as proposed by the project) to 7.5 minute headways north of Parkmerced. This would increase capacity such that the northeast screenline would operate within SFMTA's capacity utilization threshold in each peak hour. Under this plan, similar to the proposed service plan, every other train would continue east through the Ingleside neighborhood.</p> <p>The Proposed Project's fair-share contribution toward implementing a comprehensive revised operating plan should be proportional to the magnitude of the Proposed Project's impact in relation to additional capacity identified in a revised operating plan.</p>	Project sponsor and SFMTA	<p>A feasibility study must be completed prior to the completion and operation of the proposed Muni realignment and associated service plan updates. The study shall determine whether additional capacity can be provided on the M Ocean View, and if so, what the Proposed Project's fair share contribution to the service plan updates shall be.</p> <p>If the mitigation measure is deemed feasible, a fair share contribution must be made prior to the re-alignment of the M Ocean View through the Parkmerced site.</p>	SFMTA	
<p>M-TR-21A: Purchase an additional light rail vehicle for the M Ocean View. Purchase and insert another light-rail vehicle into the system in order to maintain headways. This will allow Muni to maintain proposed headways on the M Ocean View with a slightly longer route. The procurement of new light rail vehicles shall be completed by</p>	Project sponsor and SFMTA	Either M-TR-21A or M-TR-21B (but not both) shall be implemented upon rerouting the M	SFMTA	

190

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>SFMTA, and shall be completed prior to operating the rerouted system. However, new transit vehicles required to serve the Proposed Project shall not be the financial responsibility of SFMTA.</p>		<p>Ocean View through the Parkmerced site.</p> <p>If both measures are deemed feasible and effective at reducing impacts to less than significant levels, M-TR-21B shall be implemented and M-TR-21A shall not be required.</p>		
<p>M-TR-21B: Install Transit Signal Priority (TSP) treatments to improve transit travel times on the M Ocean View such that M-TR-21A (an additional vehicle) is not required. A study shall be conducted to determine whether TSP treatments could improve transit travel times along the M Ocean View corridor. If feasible, implement Transit Signal Priority (TSP) measures along the M Ocean View corridor between the Project Site and the West Portal Station. To reduce the Proposed Project's impact to the M Ocean View line, the TSP measures would need to improve the travel time by approximately 50 seconds in the AM peak period and 30 seconds in the PM peak period. Achieving these reductions would reduce the Project's impact to travel time to less than half the headway of the current M Ocean View. SFMTA and Caltrans shall design the measure prior to operating the rerouted system; however, funding, implementation, and construction of this measure shall be the responsibility of the Project Sponsor.</p> <p>[SFMTA and Caltrans to determine if this is feasible, and if SFMTA or Caltrans determines that it is not, this mitigation measure shall not be implemented.]</p>	<p>Project sponsor and sponsor's construction contractor(s) in consultation with SFMTA and Caltrans</p>	<p>Either M-TR-21A or M-TR-21B (but not both) shall be implemented upon rerouting the M Ocean View through the Parkmerced site.</p> <p>If both measures are deemed feasible and effective at reducing impacts to less than significant levels, M-TR-21B shall be implemented and M-TR-21A shall not be required.</p>	<p>SFMTA and Caltrans</p>	
<p>M-TR-22A: Construct intersection mitigations to reduce congestion caused by vehicular delay. To address Project impacts to the 18 46th Avenue, the Project Sponsor in cooperation with SFMTA shall implement the improvements described in mitigation measures M-TR-2C (construct a dedicated northbound right-turn lane at the Lake Merced Boulevard/Winston Drive intersection), M-TR-2D (reconfigure the northbound approach to consist of a third through lane and provide a second southbound left-turn lane at the Lake Merced Boulevard/Font Boulevard intersection), and M-TR-2E (Reconfigure the westbound right-turn and southbound left-turn as the primary movements of the Lake Merced Boulevard/Brotherhood Way intersection). This involves lane modifications at several intersections along Lake Merced Boulevard to increase vehicular capacity, thus reducing approach delay at those intersections.</p> <p>[SFMTA to determine if this is feasible, and if SFMTA determines that it is not, this mitigation measure shall not be implemented.]</p>	<p>Project sponsor and sponsor's construction contractor(s) in consultation with SFMTA</p>	<p>See below with regard to M-TR-22C</p>	<p>SFMTA</p>	

191

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>M-TR-22B: Maintain the proposed headways of the 18 46th Avenue. The Project Sponsor in cooperation with SFMTA shall conduct a study to evaluate the effectiveness and feasibility of the following improvements which could reduce Project impacts on transit operations along the Lake Merced Boulevard corridor, generally between Brotherhood Way and Winston Drive. The study shall create a monitoring program to determine the implementation extent and schedule (as identified below) to maintain the proposed headways of transit lines impacted by the Project.</p> <ul style="list-style-type: none"> • A transit-only queue-jump lane should be considered on Lake Merced Boulevard at Font Boulevard. This treatment could be constructed within the existing curb-to-curb right of way for the northbound direction. • Southbound queue-jumps are viable at State Drive and Font Boulevard with removal of on-street parking. However, these treatments may conflict with mitigation measure M-TR-2C collectively summarized in M-TR-22A), which have been designed to reduce the Project's traffic impacts. <p>These improvements would collectively benefit not only the 18 46th Avenue prior to the TEP improvements, but also SamTrans Route 122, and the proposed "shopper shuttle."</p> <p>Funding, implementation, and construction of this measure shall be the responsibility of the Project Sponsor. The Project Sponsor shall fully fund the costs of implementing the transit priority improvements (either the improvements identified above, or alternative improvements of equal or greater effectiveness and comparable cost) as determined by the study and the monitoring program. Other options to be evaluated in the study could include comprehensive replacement of stop-controlled intersections with interconnected traffic signals equipped with transit priority elements.</p> <p>[SFMTA to determine if this is feasible, and if SFMTA determines that it is not, this mitigation measure shall not be implemented.]</p>	<p>Project sponsor and sponsor's construction contractor(s) in consultation with SFMTA</p>	<p>See below with regard to M-TR-22C</p>	<p>SFMTA</p>	
<p>M-TR-22C: Purchase additional transit vehicles as necessary to mitigate the Project impacts to headways on the 18 46th Avenue. Should mitigation measures M-TR-22A or M-TR-22B not be feasible or effective, the Project Sponsor shall work with SFMTA to purchase additional transit vehicles and contribute to operating costs and facility improvements as necessary to mitigate the Project impacts to headways for the transit line. The Project Sponsor shall be responsible for the procurement and financing of the new transit vehicles.</p>	<p>Project sponsor and sponsor's construction contractor(s) in consultation with SFMTA</p>	<p>A feasibility study of M-TR-22A and M-TR-22B must be completed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 465, based on the trip generation rates described</p>	<p>SFMTA</p>	

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
		<p align="center">in M-TR-2C.</p> <p>To the extent they are deemed either physically feasible or effective at reducing the severity of Impact TR-22, mitigation measures M-TR-22A and M-TR-22B must be constructed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 465, based on the trip generation rates described in M-TR-2C.</p> <p>The schedule for implementing M-TR-22C shall be determined by the feasibility study for M-TR-22A and M-TR-22B.</p>		
<p>M-TR-25B: Maintain the proposed headways of the 29 Sunset. The Project Sponsor in cooperation with SFMTA shall conduct a study to evaluate the effectiveness and feasibility of installing transit priority elements along Lake Merced Boulevard, between Winston Drive and Sunset Boulevard. This may include, but is not limited to, queue-jump lanes and transit-only lanes. Funding, implementation, and construction of this measure shall be the responsibility of the Project Sponsor. The Project Sponsor shall fully fund the costs of implementing the transit priority improvements (either the improvements identified above, or alternative improvements of equal or greater effectiveness and comparable cost) as determined by the study and the monitoring program</p>	<p align="center">SFMTA, with funding from Project Sponsor</p>	<p align="center">See discussion of M-TR-25C</p>	<p align="center">SFMTA</p>	

193

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
[SFMTA to determine if this is feasible, and if SFMTA determines that it is not, this mitigation measure shall not be implemented.]				
<p>M-TR-25C: Purchase additional transit vehicles as necessary to mitigate the Project impacts to headways on the 29 Sunset. Should mitigation measures M-TR-25A or M-TR-25B not be feasible or effective, the Project Sponsor shall work with SFMTA to purchase additional transit vehicles and contribute to operating costs and facility improvements as necessary to mitigate the Project impacts to headways for the transit line. The procurement of new transit vehicles shall be completed by SFMTA. However, new transit vehicles required to serve the Proposed Project shall not be the financial responsibility of SFMTA.</p>	<p align="center">SFMTA, with funding from Project Sponsor</p>	<p>A feasibility study of M-TR-25A and M-TR-25B must be completed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 1,551, based on the trip generation rates described in M-TR-2C.</p> <p>To the extent they are deemed either physically feasible or effective at reducing the severity of Impact TR-25, mitigation measures M-TR-25A and M-TR-25B must be constructed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 1,551, based on the trip generation rates described in M-TR-2C.</p> <p>The schedule and/or need for implementing M-TR-25C shall be determined by the feasibility study for</p>	<p align="center">SFMTA</p>	

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>M-TR-26: Maintain proposed headways on SamTrans Route 122. To address Project impacts to SamTrans Route 122, implement mitigation measures M-TR-22A (lane modifications at several intersections along Lake Merced Boulevard) and M-TR-22B (implementation of transit priority and queue-jump treatments on Lake Merced Boulevard). Since SamTrans Route 122 shares a route with the 18 46th Avenue, improvements designed to reduce travel time impacts to the 18 46th Avenue would also benefit SamTrans Route 122.</p> <p>As described in the discussion of mitigation measures M-TR-22A and M-TR-22B, feasibility of these measures is uncertain.</p>	<p>Project sponsor and sponsor's construction contractor(s) in consultation with SFMTA</p>	<p>M-TR-25A and M-TR-25B.</p> <p>A feasibility study must be completed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 1,880, based on the trip generation rates described in M-TR-2BC.</p> <p>If the mitigation measure is deemed feasible, the mitigation measure must be constructed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 1,880, based on the trip generation rates described in M-TR-2C.</p>	<p>SFMTA</p>	
<p>M-TR-36A: Retime signal at 19th Avenue/Holloway Avenue to allocate more green time to the east-west movements. 19th Avenue is a coordinated corridor with closely spaced intersections. Traffic progression relies on the interconnectivity between each signal. Retiming this particular intersection would require evaluation of the corridor. SFMTA would be responsible for evaluating and implementing a new signal timing plan.</p> <p>[SFMTA and Caltrans to determine if this is feasible, and if SFMTA or Caltrans determines that it is not, this mitigation measure shall not be implemented.]</p>	<p>SFMTA to carry out feasibility study.</p> <p>If feasible, SFMTA to monitor traffic conditions at this intersection to determine when modifications are needed.</p>	<p>A feasibility study must be completed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 1,725, based on the trip</p>	<p>SFMTA</p>	

195

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
	SFMTA to retime signal if determined feasible and necessary.	generation rates described in M-TR-2C. If the mitigation measure is deemed feasible, the mitigation measure must be constructed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 1,725, based on the trip generation rates described in M-TR-2C.		
<p>M-TR-36B: Construct a dedicated westbound right-turn lane and convert the shared westbound through/right-turn lane to a dedicated westbound through lane at the Brotherhood Way/Chumasero Drive intersection.</p> <p>Construction of this mitigation measure would require roadway widening into the Project Site. However, if the existing pedestrian overcrossing across Brotherhood Way at this intersection remains, widening the roadway to implement this measure may not be feasible due to conflicts with structural support columns for the overcrossing. Funding, implementation, and construction of this measure shall be the responsibility of the Project Sponsor.</p> <p>[SFMTA to determine if this is feasible, and if SFMTA determines that it is not, this mitigation measure shall not be implemented.]</p>	<p>SFMTA to carry out feasibility study.</p> <p>Project sponsor and sponsor's construction contractor(s) to carry out design and implementation in consultation with SFMTA</p>	<p>Upon construction of proposed improvements to the Brotherhood Way/Chumasero Drive intersection, as specified in the Development Agreement.</p>	<p>Sponsor to provide revised plans to Planning Department as part of Development Agreement; Planning Department to review and acknowledge change in proposed intersection configurations.</p>	
<p>M-TR-36C: Install a traffic signal at Lake Merced Boulevard/John Muir Drive. The Project Sponsor should contribute a fair-share toward funding this mitigation measure. Funding, implementation, and construction of this measure shall be the responsibility of the Project Sponsor.</p> <p>[SFMTA to determine if this is feasible, and if SFMTA determines that it is not, this mitigation measure shall not be implemented.]</p>	<p>SFMTA to carry out feasibility study.</p> <p>If determined feasible, project sponsor to provide fair-share funding and SFMTA to</p>	<p>A feasibility study must be completed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at</p>	<p>SFMTA</p>	

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
	design and construct.	<p>Parkmerced exceed 2,326, based on the trip generation rates described in M-TR-2C.</p> <p>If the mitigation measure is deemed feasible, the mitigation measure must be constructed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 2,326, based on the trip generation rates described in M-TR-2C.</p>		
<p>M-TR-36D: Convert the dedicated southbound through lane into a dedicated left-turn lane at John Daly Boulevard/Lake Merced Boulevard. This would result in the southbound approach consisting of a shared through-right-turn lane and triple left-turn lanes. To achieve adequate lane utilization, John Daly Boulevard would have to be configured to have three eastbound through travel lanes east of the intersection. This would require the removal of some pedestrian elements and converting the existing right-turn lane into the Westlake Shopping Center into a shared through/right-turn lane. Funding, implementation, and construction of this measure shall be the responsibility of the Project Sponsor.</p> <p>[Project Sponsor to coordinate with City of Daly City to determine if this is feasible, and if Daly City determines that it is not, this mitigation measure shall not be implemented.</p>	Project Sponsor to coordinate with the City of Daly City	<p>A feasibility study must be completed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 2,946, based on the trip generation rates described in M-TR-2C.</p> <p>If the mitigation measure is deemed feasible, the mitigation measure must be constructed prior to the issuance of the certificate of occupancy for any building that, after</p>	Project Sponsor to report to SFMTA and ERO on results of coordination with City of Daly City	

197

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
		completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 2,946, based on the trip generation rates described in M-TR-2C.		
<p>M-TR-36E: Install an auxiliary lane from Brotherhood Way through the Lake Merced Boulevard/Gonzalez Drive intersection to provide three northbound through lanes. Funding, implementation, and construction of this measure shall be the responsibility of the Project Sponsor.</p> <p>[SFMTA to determine if this is feasible, and if SFMTA determines that it is not, this mitigation measure shall not be implemented.]</p>	<p>SFMTA to conduct feasibility study.</p> <p>Project sponsor and sponsor's construction contractor(s) to design and construct in consultation with SFMTA</p>	<p>A feasibility study must be completed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 2,946, based on the trip generation rates described in M-TR-2C.</p> <p>If the mitigation measure is deemed feasible, the mitigation measure must be constructed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 2,946, based on the trip generation rates described in M-TR-2C.</p>	<p align="center">SFMTA</p>	
<p>M-TR-36F: Install an auxiliary lane from Brotherhood Way through the Lake Merced Boulevard/Gonzalez Drive intersection to provide three northbound through lanes.</p>	<p>SFMTA to conduct feasibility study.</p>	<p>A feasibility study must be completed prior to the</p>	<p align="center">SFMTA</p>	

198

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>Funding, implementation, and construction of this measure shall be the responsibility of the Project Sponsor. [SFMTA to determine if this is feasible, and if SFMTA determines that it is not, this mitigation measure shall not be implemented.]</p>	<p>Project sponsor and sponsor's construction contractor(s) to design and construct in consultation with SFMTA</p>	<p>issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 2,946, based on the trip generation rates described in M-TR-2C.</p> <p>If the mitigation measure is deemed feasible, the mitigation measure must be constructed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 2,946, based on the trip generation rates described in M-TR-2C.</p>		
<p>M-TR-44: Provide additional capacity on the south and north screenlines by adding additional buses to the 28 19th Avenue and 28L 19th Avenue Limited lines. Providing additional service on the bus line would require further feasibility and capacity studies with coordination from SFMTA. The Project sponsor would be responsible to fund a "fair share" contribution towards the implementation of this mitigation measure.</p>	<p>SFMTA to conduct feasibility and capacity study.</p> <p>Project sponsor to make fair-share contribution.</p> <p>If feasible, SFMTA to purchase and operate vehicles.</p>	<p>A feasibility study must be completed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 2,667, based on the trip generation rates described in M-TR-2C.</p> <p>If the mitigation measure</p>	<p>SFMTA</p>	

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
		is deemed feasible, the mitigation measure must be constructed prior to the issuance of the certificate of occupancy for any building that, after completion, would make the total number of net new PM peak hour trips at Parkmerced exceed 2,667 based on the trip generation rates described in M-TR-2C.		
<i>Noise</i>				
<p>M-NO-1a: Reduce Noise Levels During Construction</p> <p>The following practices shall be incorporated into the construction contract agreement documents to be implemented by the construction contractor:</p> <ul style="list-style-type: none"> • Provide enclosures and mufflers for stationary equipment, shroud or shield impact tools, and install barriers around particularly noisy activities at the construction sites so that the line of sight between the construction activities and nearby sensitive receptor locations is blocked to the maximum feasible extent; • Use construction equipment with lower noise emission ratings whenever possible, particularly for air compressors; • Provide sound-control devices on equipment no less effective than those provided by the manufacturer; • Locate stationary equipment, material stockpiles, and vehicle staging areas as far as practicable from sensitive receptor locations; • Prohibit unnecessary idling of internal combustion engines; • Require applicable construction-related vehicles and equipment to use designated truck routes to access the project sites; • Implement noise attenuation measures to the extent feasible, which may include, but are not limited to, noise barriers or noise blankets. The 	Project Sponsor and construction contractor(s)	During Construction of each phase	Planning Department	

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>placement of such attenuation measures shall be reviewed and approved by the Director of Public Works prior to issuance of development permits for construction activities.</p> <p>Designate a Noise Disturbance Coordinator who shall be responsible for responding to complaints about noise during construction. The telephone number of the Noise Disturbance Coordinator shall be conspicuously posted at the construction site and shall be provided to the City. Copies of the construction schedule shall also be posted at nearby noise-sensitive areas</p>				
<p>M-NO-1b: Pile Driving Noise-Reducing Techniques and Muffling Devices</p> <p>The Project Sponsor shall require its construction contractor to use noise-reducing pile driving techniques if nearby buildings are subject to pile driving noise and vibration. These techniques shall include pre-drilling pile holes (if feasible, based on soils; see Mitigation Measure M-NO-2, pp. V.F.20-V.F.21) to the maximum feasible depth, installing intake and exhaust mufflers on pile driving equipment, vibrating piles into place when feasible, and installing shrouds around the pile driving hammer where feasible.</p> <p>Construction contractors shall be required to use construction equipment with state-of-the-art noise shielding and muffling devices. In addition, at least 48 hours prior to pile driving activities, the Project Sponsor shall notify building owners and occupants within 500 feet of the project site of the dates, hours, and expected duration of such activities.</p>	Project Sponsor	During Construction of each phase if pile driving is required. At least 48 hours prior to pile driving activities, the Project Sponsor shall notify building owners and occupants within 500 feet of the project site of the dates, hours, and expected duration of such activities.	Planning Department	
<p>M-NO-2: Pre-Construction Assessment to Minimize Vibration Levels Associated with Impact Activities</p> <p>The Project Sponsor shall hire a qualified geotechnical engineer to conduct a pre-construction assessment of existing subsurface conditions and the structural integrity of nearby buildings subject to pile driving noise and vibration prior to receiving a building permit. If recommended by the geotechnical engineer, for structures or facilities within 50 feet of pile driving activities, the Project Sponsor shall require ground-borne vibration monitoring of nearby structures. Such methods and technologies shall be based on the specific conditions at the construction site such as, but not limited to, the following:</p> <ul style="list-style-type: none"> • Pre-construction surveying of potentially affected structures; • Underpinning of foundations of potentially affected structures, as necessary; <p>The construction plan shall include a monitoring program to detect ground settlement or lateral movement of structures in the vicinity of impact activities. Monitoring results shall be submitted to the Department of Building Inspection. In the event of unacceptable ground movement, as determined by the Department of Building</p>	Project Sponsor and qualified geotechnical engineers	Prior to commencement of construction of each phase.	Geotechnical engineer to provide reports to Department of Building Inspection for review and approval	

201

EXHIBIT 1: MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT (Includes Text for Adopted Mitigation and Improvement Measures)				
MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
Inspection, all impact work shall cease and corrective measures shall be implemented. The impact program and ground stabilization measures shall be reevaluated and approved by the Department of Building Inspection.				

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>M-NO-5: Light Rail Noise and Vibration Reduction Plan</p> <p>The proposed realignment of the Muni M Ocean View light rail and its operations shall be designed with input from a qualified acoustical consultant so that light rail operation noise levels are attenuated at and in the vicinity of the final alignment so that the San Francisco Land Use Compatibility Guidelines for Community Noise standards are not exceeded. The Light Rail Noise and Vibration Reduction Plan shall be prepared by a qualified acoustical consultant and submitted to the City for review and approval prior to construction of the proposed realignment. The plan shall identify noise attenuation measures that would ensure compliance with the City's community noise guidelines, including, but not limited to, requiring light rail operators to reduce vehicle speeds when approaching and departing and operating within the Project Site. The following noise and vibration attenuation measures shall be included as part of the plan:</p> <ul style="list-style-type: none"> • Rail Bed Design: The light rail trackwork shall be designed to prevent the production of excessive vibration levels at the nearest sensitive structures. The design should include the installation of high-resilience direct fixation fasteners for embedded track, ballast mat for ballast and tie track, or other measures as determined by a qualified light rail vibration consultant. • Rail Grinding and Replacement: As rails wear, both noise levels from light rail by-passes and vibration levels can increase. By grinding down or replacing worn rail, noise and vibration levels will remain at the initial operating levels. Rail grinding or replacement is normally performed every 3 to 5 years. • Wheel Truing and Replacement: Wheel truing is a method of grinding down flat spots (commonly called "wheel flats") on the light rail's wheels. Flat spots occur primarily because of hard braking. When flat spots occur they can cause increases in both the noise and vibration levels produced by the light rail vehicles. • Vehicle Maintenance: Vehicle maintenance includes performing scheduled and general maintenance on items such as air conditioning units, bearings, wheel skirts, and other mechanical units on the light rail vehicles. Keeping the mechanical system on the light rail vehicles in top condition will also help to control noise and vibration levels. • Operator Training: Operators will be trained to maintain light rail travel speeds at those speeds given in the operation plan and to avoid "hard braking" whenever possible. As stated, hard braking can cause 	<p>Project Sponsor with qualified professional consultant.</p> <p>Project sponsor and sponsor's construction contractor(s) in consultation with SFMTA.</p>	<p>Light Rail Noise and Vibration Reduction Plan shall be prepared by a qualified acoustical consultant and submitted to SFMTA for review and approval prior to construction of the proposed realignment.</p> <p>During final engineering design, vibration propagation testing shall be conducted at the final light rail alignment near Gonzalez Drive and Diaz Avenue.</p>	<p>SFMTA.</p> <p>SFMTA to monitor rail grinding and replacement every other 3 to 5 years.</p> <p>SFMTA shall perform ongoing vehicle maintenance.</p> <p>SFMTA shall perform ongoing operator training.</p>	

203

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>wheel flats and may also damage track. Furthermore, by training operators to identify potential wheel flats and other mechanical problems with the trains, proper maintenance can be performed in a timely manner.</p> <p>During final engineering design, vibration propagation testing shall be conducted at the final light rail alignment near Gonzalez Drive and Diaz Avenue to confirm the predicted impact and finalize the mitigation measures. Where vibration impacts are confirmed, they shall be reduced to meet the FTA criteria.</p>				
<p>M-NO-6: Residential Use Plan Review by Qualified Acoustical Consultant</p> <p>To ensure that interior noise levels induced by the light rail station, and by automobile, bus, and light rail traffic at noise sensitive uses do not result in excessive awakenings, or exceed an interior noise level standard of 45 dBA (L_{dn}), a qualified acoustical consultant shall review plans for all new residential uses, the new Pre K-5 school, and new day care facility, and provide recommendations to provide acoustical insulation or other equivalent measures to ensure that interior noise levels would not exceed acceptable limits and a cumulative noise level of 45 dBA (L_{dn}). These studies shall be presented to the Department of Building Inspection at the time that permits for individual buildings are submitted for review.</p>	<p>Project Sponsor to retain qualified acoustical consultant</p>	<p>Prior to issuance of each individual building permit.</p>	<p>Consultant to submit reports to Department of Building Inspection</p> <p>Building designers to follow the recommendations of the acoustical consultant.</p> <p>DBI to review plans to ensure recommendations are included in plans.</p>	
<p>M-NO-7: Stationary Operational Noise Sources.</p> <p>All utility and industrial stationary noise sources (e.g., district energy system, wind turbines, etc.) shall be located away from noise sensitive receptors, be enclosed within structures with adequate setback and screening, be installed adjacent to noise reducing shields, or constructed with some other adequate noise attenuating features, to achieve compliance with the noise level limits of the San Francisco Noise Ordinance and to achieve acceptable levels at the property lines of nearby residences or other sensitive uses, as determined by the San Francisco Land Use Compatibility Guidelines for Community Noise standards. Once the stationary noise sources have been installed, the Project Sponsor shall retain a qualified acoustics specialist to monitor noise levels to ensure compliance with local noise standards. Initial noise monitoring shall occur within three months after the installation of the stationary noise source, and a report of the results shall be made available to on-site tenants. Subsequent noise monitoring shall be conducted by the Project Sponsor, within three months of on-site tenants reporting persistent intrusive noise. If project stationary noise sources exceed the applicable noise standards, a qualified acoustical consultant shall be retained by the Sponsor to install additional noise attenuation measures or acoustic insulation in order to meet the applicable noise standards.</p>	<p>Project Sponsor to retain qualified acoustical consultant</p>	<p>Within three months of installation of stationary noise sources.</p> <p>Subsequent noise monitoring within three months of on-site tenants reporting persistent intrusive noise.</p>	<p>Planning Department</p>	

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>M-NO-8: Residential Building Plan Review by Qualified Acoustical Consultant To ensure that noise produced during garbage collection is reduced to the maximum practicable extent, a qualified acoustical consultant shall review plans for all new residential buildings and associated garbage collection facilities, and provide recommendations to provide enclosures, acoustical shielding, or other equivalent measures. These studies shall be presented to the Department of Building Inspection at the time that permits for individual buildings are submitted for review.</p>	<p>Project Sponsor to retain qualified acoustical consultant</p>	<p>Prior to issuance of a building permit for each individual building.</p>	<p>Department of Building Inspection</p>	
Air Quality				
<p>M-AQ-3: Construction Exhaust Emissions. The applicant shall implement feasible combustion emission reduction strategies, during construction activities, including the following measures:</p> <ul style="list-style-type: none"> • The project applicant shall keep all off-road equipment well-tuned and regularly serviced to minimize exhaust emissions, and shall establish a regular and frequent check-up and service/maintenance program for equipment. • Off-road diesel equipment operators shall be required to shut down their engines rather than idle for more than five minutes, unless such idling is necessary for proper operation of the equipment. • Clear signage shall be provided for construction workers at all access points. <p>The applicant shall require construction contracts to specify implementation of the following combustion emission reduction strategies, during construction activities:</p> <ul style="list-style-type: none"> • The project should use equipment with engines compliant with USEPA Tier 3 engine standards or better for all off-road equipment, or utilize Retrofit Emission Control Devices which consist of diesel oxidation catalysts, diesel particulate filters or similar retrofit equipment control technology verified by the California Air Resources Board (CARB) (http://www.arb.ca.gov/diesel/verdev/verdev.htm), where feasible. • The project shall use equipment with engines compliant with USEPA Tier 4 engine standards or better for 50 percent of the fleet by 2015, increasing to 100 percent by 2020. <p>The project shall use 2007 or newer model year haul trucks, where feasible.</p>	<p>Project Sponsor and Sponsor's construction contractor(s).</p>	<p>Submit planned emission reduction strategies and copies of applicable construction specification related to off-road equipment for each construction phase prior to issuance of the site permit for that phase.</p> <p>Construction contractor shall submit quarterly reports regarding implementation of emission reduction strategies and use of Tier 3 or Tier 4 or equivalent equipment during construction.</p>	<p>Planning Department and Department of Building Inspection</p>	
<p>M-AQ-15: Mechanical Ventilation Systems for New Residential Uses. New residential uses within 200 feet from the edge of the Project Site boundary along Junipero Serra Boulevard, including ramps on Brotherhood Way, 19th Avenue, or Brotherhood Way shall</p>	<p>Project Sponsor and Sponsor's construction</p>	<p>Prior to issuance of a building permit for each individual building.</p>	<p>Planning Department and</p>	

205

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>incorporate mechanical ventilation systems. If the project anticipates operable windows or other sources of infiltration of ambient air, the residences shall be provided with a central HVAC (heating, ventilation and air conditioning) system that includes high efficiency filters for particulates (MERV-13 or higher). The system should operate to maintain positive pressure within the building interior to prevent entrainment of outdoor air indoors. Alternatively, if the development limits infiltration through non-operable windows and other techniques, the residences shall be provided with a ventilation and filtration system that meets the following specifications: (1) ASHRAE MERV-13 supply air filters; (2) ≥ 1 air exchanges per hour of fresh outside filtered air; (3) ≥ 4 air exchanges / hour recirculation; and (4) ≤ 0.25 air exchanges per hour in unfiltered infiltration.</p>	contractor(s).		Department of Building Inspection	
<i>Wind and Shadow</i>				
<p>M-WS-1a: Wind Impact Analysis for Proposed Buildings Over 100 feet in Height. A wind impact analysis shall be required for any proposed building over 100 feet in height. Wind tunnel testing shall be required for each building unless, upon review by a qualified wind consultant, it is determined that the exposure, massing, and/or orientation of the building are such that adverse wind impacts would not occur. The analysis shall assess wind conditions for the building in conjunction with the anticipated pattern of development on surrounding blocks. All feasible means (such as relocating or reorienting certain buildings, sculpting buildings to include podiums and roof terraces, or installing landscaping) to eliminate hazardous winds, if predicted, shall be implemented. A significant wind impact would be a substantial increase in the number of hours that the 26 mph wind hazard criterion is exceeded or a substantial increase in the area subjected to winds greater than 26 mph.</p>	Project Sponsor to retain qualified professional consultant	Prior to building permit issuance for any proposed building over 100 feet in height.	Planning Department	
<p>M-WS-1b: Wind Tunnel Testing for Proposed Buildings Over 50 feet in Height. Wind tunnel testing shall be required for any proposed building over 50 feet in height that is within 200 feet of any of the existing 13-story buildings on the Project Site. The analysis shall assess wind conditions for the building in conjunction with the anticipated pattern of development one surrounding blocks. All feasible means (such as relocating or reorienting certain buildings, sculpting buildings to include podiums and roof terraces, or installing landscaping) to eliminate hazardous winds, if predicted, shall be implemented. A significant wind impact would be a substantial increase in the number of hours that the 26 mph wind hazard criterion is exceeded or a substantial increase in the area subjected to winds greater than 26 mph.</p>	Project Sponsor to retain qualified professional consultant	Prior to building permit issuance for any proposed building over 50 feet in height that is within 200 feet of any of the existing 13-story buildings on the Project Site.	Planning Department and Department of Building Inspection	
<i>Biological Resources</i>				
<p>M-BI-1a: Pre-construction Survey for Gumplant. A pre-construction survey shall be conducted to locate and fence the boundaries of any gumplant populations with a</p>	Project Sponsor to retain qualified	Prior to construction for each phase, a	Planning Department	

206

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
25-foot buffer zone. To determine if any previously unknown special-status plant or animal species would be affected, a preconstruction survey shall be conducted within the construction area in the spring (May and June) by a qualified biologist authorized by CDFG to conduct such activities.	professional consultant	preconstruction survey shall be conducted within the construction area in the spring (May and June) by a qualified biologist authorized by CDFG.		
M-BI-1b: Avoidance of Gumplant During Construction. The configuration of the construction area shall be modified to avoid any special-status species encountered during the pre-construction survey. No construction activities shall occur within the buffer area. The Project Sponsor shall ensure that the construction area is fenced to the minimum size necessary to avoid impacts from the outfall to the willow basin.	Project Sponsor to retain qualified professional consultant	Prior to construction for each phase	Planning Department	
M-BI-1c: Restoration and Expansion of Gumplant Population. If it is not possible to avoid the gumplant population during construction, the Project Sponsor shall implement a restoration and mitigation plan in consultation with the San Francisco Planning Department (City) and CDFG. Impacts to the San Francisco gumplant will be mitigated by restoring the affected area and expanding the size of the population by increasing the area and number of individual gumplant plants. The size and density of the affected gumplant population shall be measured prior to construction. This mitigation plan shall describe methods for planting, monitoring, and maintaining the affected area. Performance standards to determine success of the mitigation shall be attained that show that the cover and density of the population affected has been replaced. An annual report shall be submitted to the City and CDFG that documents maintenance and monitoring methods and results. Such monitoring and maintenance shall continue for at least 5 years beyond the implementation of the mitigation plan.	Project Sponsor to retain qualified professional consultant	If gumplant population cannot be avoided, prior to construction for each phase, mitigation plan shall be submitted. An annual report shall be submitted to the City and CDFG that documents maintenance and monitoring methods and results. Monitoring and maintenance shall continue for at least 5 years beyond the implementation of the mitigation plan.	Planning Department and CDFG	
M-BI-2a: Preconstruction Survey for Common Yellowthroat Nesting Activities and Buffer Area. If outfall repair or construction activities occur along the Lake Merced shoreline during the breeding season of the common yellowthroat (March-August), a qualified ornithologist authorized by CDFG to conduct such activities shall conduct a preconstruction survey of the work area to determine if any birds are nesting in or in the vicinity of the outfall. The preconstruction survey shall be conducted within 15 days prior to the start of work from March through May (since there is higher	Project Sponsor to retain qualified professional consultant	If outfall repair or construction activities occur during the breeding season (March-August), a qualified ornithologist authorized by CDFG shall conduct a preconstruction	CDFG and Planning Department	

207

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>potential for birds to initiate nesting during this period), and within 30 days prior to the start of work from June through August. If active nests are found in the work area, a buffer of 50 feet shall be established between the work area and the nest(s). No work will be allowed within the buffer until the young have successfully fledged. The size of the nest buffer can be reduced as a result of consultation with the CDFG. Such a reduction shall be dependent on a relatively low frequency and intensity of disturbance and the tolerance of the nesting birds to human disturbance.</p>		<p>survey. The preconstruction survey shall be conducted within 15 days prior to the start of work from March through May, and within 30 days prior to the start of work from June through August.</p>		
<p>M-BI-2b: <u>Monitoring for Western Pond Turtles During Construction.</u> Stormwater outfall construction activities at the Lake Merced outfall site(s) shall be monitored by a biologist to ensure that no western pond turtles are present and subjected to harm. If turtles are present, the biologist shall capture and relocate them or ensure that they are moved to an area outside of the construction zone and away from harm. Identification, capture and relocation of turtles shall be done by a qualified biologist authorized by CDFG to conduct such activities.</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>During construction for each phase</p>	<p>CDFG and Planning Department</p>	
<p>M-BI-2c: <u>SWPPP Design Details for Site Drainage and Water Quality Control in Outfall Construction Area.</u> The SWPPP is required and shall include design details and construction specifications for all site drainage control and other water quality control strategies. It shall also detail the implementation schedule, methods and locations of erosion and water quality control features. The California Stormwater Quality Association Construction Handbook provides guidance for selecting and implementing Best Management Practices (BMPs) that would eliminate or reduce the discharge of pollutants from construction sites to waters of the state. Three levels of BMPs are considered for each potential pollutant: source control, management control, and treatment control. BMPS which could be implemented as part of the SWPPP include: hydroseeding, straw mulch, temporary stream bank stabilization, silt fences, sediment traps, temporary stream crossings, stockpile management, and spill prevention and control.</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>Prior to and during construction for each phase</p>	<p>SFPUC</p>	
<p>M-BI-3a: <u>Restrict Vegetation Removal Activities in Wetland and Riparian Areas During Outfall Construction.</u> Vegetation removal activities in wetland and riparian habitats in the willow basin and along the shoreline of Lake Merced shall be restricted to as small an area as possible. Construction areas shall be no longer than 40 feet and shall be shorter where possible. In addition, construction shall avoid large willow and wax myrtle trees.</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>Prior to and during construction for each phase</p>	<p>Planning Department</p>	
<p>M-BI-3b: <u>Vegetation Restoration in Outfall Construction Area.</u> The vegetation of any affected riparian or wetland area shall be restored to the same or to a more</p>	<p>Project Sponsor to retain qualified</p>	<p>A mitigation plan shall be developed prior to the</p>	<p>Planning Department</p>	

208

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>biologically valuable condition. This shall entail planting of vegetation, if it is not expected to return on its own, and removal of non-native species. A mitigation plan that describes site preparation, planting, performance standards, maintenance (including weed control), and monitoring methods shall be developed for impacts to marsh and riparian vegetation. The performance standards shall include a mitigation ratio of 1:1, standards for cover, plant composition of the restored area, and erosion, at the end of 5 years. Remedial activities shall be outlined in the plan to address any of the restoration areas that are not attaining performance standards at the end of 5 years. The mitigation area shall be monitored and maintained for at least 5 years. Monitoring and maintenance activities shall be summarized in an annual report to be prepared for each of the 5 years the area is monitored. This mitigation plan shall be reviewed and approved by the City prior to the approval of the final map for the project.</p>	<p>professional consultant</p>	<p>approval of the final map for Project. The mitigation area shall be monitored and maintained for at least 5 years. Monitoring and maintenance activities shall be summarized in an annual report to be prepared for each of the 5 years the area is monitored.</p>		
<p>M-BI-4: Breeding Bird Pre-construction Surveys and Buffer Areas. Vegetation removal activities for the Proposed Project and stormwater treatment option areas and building demolitions shall be conducted during the non-breeding season (i.e., September through February) to avoid impact to nesting birds or preconstruction surveys shall be conducted for work scheduled during the breeding season (March through August). Preconstruction surveys shall be conducted by a qualified ornithologist, authorized by CDFG to conduct such activities, to determine if any birds are nesting in or in the vicinity of vegetation or buildings to be removed. The preconstruction survey shall be conducted within 15 days prior to the start of work from March through May (since there is higher potential for birds to initiate nesting during this period), and within 30 days prior to the start of work from June through August. If active songbird nests are found in the work area, a buffer of 50 feet between the nest and work area shall be established. If active raptor nests are found in the work area, a buffer of 200 feet shall be established between the nest and the work area. No work will be allowed with the buffer(s) until the young have successfully fledged. In some instances, the size of the nest buffer can be reduced and its size shall therefore be determined by the biologist in consultation with the CDFG, and shall be based to a large extent on the nesting species, its sensitivity to disturbance, and the type and frequency of disturbance.</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>Vegetation removal activities shall be conducted during the non-breeding season (i.e., September through February), OR preconstruction surveys shall be conducted for work scheduled during the breeding season (March through August). The preconstruction survey shall be conducted within 15 days prior to the start of work from March through May, and within 30 days prior to the start of work from June through August. If active raptor nests are found in the work area, no work will be allowed with the buffer(s) until the young have successfully</p>	<p>CDFG and Planning Department</p>	

209

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>M-BI-7a: <u>Pre-maintenance Surveys for Active Bird Nests and Buffer Areas.</u> If maintenance of the stormwater treatment system occurs during the nesting season (March-August), a qualified ornithologist, authorized by CDFG to conduct such activities, shall conduct a survey of the work area to determine if any birds are nesting in the work area or in the vicinity. The survey shall be conducted within 15 days prior to the start of maintenance work from March through May (since there is higher potential for birds to initiate nesting during this period), and within 30 days prior to the start of work from June through August. If active songbird nests are found in the work area, a buffer of 50 feet between the nest and the work area shall be established. If active raptor nests are found in the work area, a buffer of 200 feet shall be established between the nest and the work area. No work will be allowed within the buffer until the young have successfully fledged. In some instances, the size of the buffer can be reduced and its size shall therefore be determined by the biologist in consultation with the CDFG, and shall be based to a large extent on the nesting species, its sensitivity to disturbance, and the type and frequency of disturbance.</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>fledged.</p> <p>If maintenance of the stormwater treatment system occurs during the nesting season (March-August), a qualified ornithologist shall conduct a survey of the work area.</p> <p>The survey shall be conducted within 15 days prior to the start of maintenance work from March through May, and within 30 days prior to the start of work from June through August.</p>	<p>CDFG and Planning Department</p>	
<p>M-BI-7b: <u>Monitoring During Maintenance Activities.</u> The on-site stormwater features shall be monitored by a qualified biologist, authorized by CDFG to conduct such activities, during maintenance activities to ensure that no western pond turtles or other special-status amphibians or reptiles are present and subject to harm. If turtles or other special-status reptiles and amphibians are present, the biologist shall capture and relocate them, or ensure that they are moved to an area outside of the construction zone and away from harm.</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>Ongoing monitoring after completion of each phase</p>	<p>CDFG and Planning Department (Reporting Only)</p>	
<p>M-BI-8a: <u>Pre-permitting Surveys for Birds and Bats.</u> To obtain baseline information on existing bird use of the proposed wind turbine alignment along Lake Merced Boulevard, the Project Sponsor shall retain a qualified wildlife biologist, authorized by CDFG to conduct such activities, to conduct bi-weekly bird use counts (BUCs) of the area for two years using methods described in Anderson and CEC/CDFG. Three point count stations spaced approximately 500 feet apart in the existing median between Lake Merced Boulevard and Vidal Drive would likely be sufficient to detect all birds using and/or flying through the area, although the final study design shall be subject to review and approval by the CDFG. Methods other than BUCs may be used if improved methods for documenting bird use at proposed wind turbine sites are developed in the interim period between the certification of this EIR and the initiation of the wind turbine program.</p> <p>Obtaining baseline information on existing bat use of the wind turbine alignment is complicated by the fact that bats are much more difficult to detect than birds and</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>Prior to permit issuance for wind turbines, bi-weekly bird use counts (BUCs) shall be conducted for two years.</p> <p>Prior to permit issuance for wind turbines, a qualified bat expert shall conduct a one-day habitat assessment of the proposed wind turbine alignment.</p>	<p>CDFG and Planning Department (Reporting Only)</p>	

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>available monitoring methods (i.e., acoustic monitoring of echolocation calls) may not be feasible in a dense urban environment. As such, the Project Sponsor shall retain a qualified bat expert to conduct a one-day habitat assessment of the proposed wind turbine alignment. Based on the results of the assessment, the bat expert shall provide recommendations on the appropriate level of monitoring required to establish baseline patterns of seasonal bat activity along the proposed wind turbine alignment. If the bat expert believes that focused bat surveys are not necessary or that the proposed wind turbines do not pose a significant risk to local bat populations, he/she shall explain his/her opinions following standard scientific report format.</p> <p>Similarly, the Project Sponsor shall retain a biologist experienced with nocturnal bird survey methods (e.g., radar, acoustic monitoring, visual surveys using night vision equipment) to conduct an assessment of the proposed wind turbine alignment and assess the feasibility of conducting nocturnal surveys for migrating birds. Given substantial uncertainty and variation over the optimal protocols for detecting nocturnal migrating birds and the viability of such protocols to predict collision risk, it is important to identify species of primary concern and develop site-specific questions that any nocturnal studies should address prior to implementing a nocturnal monitoring program. The biologist retained to conduct the nocturnal bird survey feasibility assessment shall provide such information in their report.</p> <p>Data gathered during the pre-permitting surveys shall be used to develop baseline estimates of bird and bat fatality rates (expressed as fatalities/megawatt/year) from the proposed wind turbines. Given the lack of scientific studies on wind turbine-wildlife interactions in urban areas and vertical-axis wind turbine (VAWT) impacts on wildlife, it will be difficult if not impossible to apply known fatality rates from other studies to the project site (although such information may become available by the time the wind turbine program is implemented). As such, baseline fatality estimates shall be developed with input from scientists experienced with statistical analysis of wind turbine-wildlife interactions.</p>		<p>Prior to permit issuance for wind turbines, a biologist experienced with nocturnal bird survey methods (e.g., radar, acoustic monitoring, visual surveys using night vision equipment) shall conduct an assessment of the proposed wind turbine alignment.</p>		
<p>M-BI-8b: Operations Monitoring Program. The Project Sponsor shall implement a scientifically defensible operations monitoring program to estimate bird and bat fatality rates from the new wind turbines. Operations monitoring typically consists of counts of bird and bat carcasses in the vicinity of turbines and ongoing bird use data collection (i.e., continued BUCs) using the most current methods prescribed by the California Energy Commission and CDFG. Given the lack of published information on impacts to birds and bats from urban wind turbines and the site's proximity to a major wildlife habitat feature (i.e., Lake Merced), and the Pacific flyway a minimum of two years of post-construction monitoring shall be conducted. The operations monitoring program shall be developed with input from the CDFG, USFWS, and scientists experienced in</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>A post-construction monitoring program shall be established for a minimum of two years after installation of wind turbines.</p>	<p>CDFG and USFWS and Planning Department (Reporting Only)</p>	

211

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
the analysis of wind turbine-wildlife interactions.				
<p>M-BI-8c: <u>Implementation of Management Strategies (Wind Turbines)</u>. If results of operations monitoring indicate that bird and/or bat fatality rates exceed those predicted during the pre-permitting phase, the City shall require implementation of some or all of the following management strategies or compensation measures:</p> <ol style="list-style-type: none"> 1. Seasonal shutdown (e.g., spring or fall migratory period, depending on results of surveys) of a particular turbine or turbines that may be found to be contributing a disproportionate amount to bird and/or bat fatalities. 2. Contribution of funds towards the management, restoration, enhancement, and/or protection of the local habitats used by species affected by wind turbines (e.g., lands managed by San Francisco Recreation and Park Natural Areas Program or the National Park Service Golden Gate National Recreation Area). <p>Contribution of funds towards research programs aimed at wind turbine-wildlife interactions, nocturnal bird study methods, and/or collision risk.</p>	Project Sponsor to retain qualified professional consultant	Upon conclusion of monitoring program, implementation of management strategies or compensation measures.	Planning Department	
<p>M-BI-8d: <u>Design Elements to Minimize Bird and/or Bat Strikes</u>. The following measures shall be incorporated into wind turbine design to minimize the likelihood of bird strikes:</p> <ol style="list-style-type: none"> 1. FAA-mandated obstruction lighting at the turbine tops shall consist of red or white strobe-type lights rather than steady-burning lights, as several studies have demonstrated reduced mortality of night-migrating birds at facilities using strobe-type lights. 2. No guy wires shall be used to support the wind turbines, as they are a known hazard to birds. 3. To prevent bird collisions with overhead power lines, turbines shall be powered via underground electrical connections. 4. Bare soil or manicured grass around turbine bases may provide habitat for small mammals, resulting in increased prey availability for raptors and putting them at increased risk of collision. To discourage small mammals from burrowing under or near turbine bases, gravel or artificial turf shall be placed at least 5 feet around each turbine foundation. <p>Additional design elements proven to minimize bird and/or bat strikes shall be implemented as information on such measures becomes available in the scientific literature and/or agency guidance documents.</p>	Project Sponsor to retain qualified professional consultant	Prior to wind turbine permit issuance, design measures shall be incorporated.	Planning Department	
M-BI-8e: <u>Incidental Take Permit</u>. As mentioned above, the proposed wind turbines	Project Sponsor to	Prior to wind turbine	CDFG	

212

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>may result in mortality of bank swallows, which is state-listed as threatened under the California Endangered Species Act (CESA) or other species of concern. Given the current uncertainty over the extent and magnitude of potential take of bank swallows or other species of concern, the Project Sponsor shall apply to the CDFG for an incidental take permit pursuant to Section 2081 of CESA and implement all CDFG conditions of that permit, which may include the some or all of the mitigation measures described above. The permit application will comply with the applicable requirements of Section 738.2 of CESA, as it may be amended.</p>	<p>retain qualified professional consultant</p>	<p>permit issuance from the San Francisco Department of Building Inspection, a take permit application from CDFG shall be issued.</p>	<p>and Planning Department (reporting only)</p>	
<p>M-BI-9: Bird-Safe Design Practices. The Project Sponsor shall ensure that the new residential towers should follow bird-safe design practices as much as possible to minimize the potential for increased bird-window collisions. Building facades should create "visual noise" via cladding or other design features that make it easier for birds to identify buildings as such and not mistake windows for open sky or trees. Windows should not be comprised of clear or reflective glass, which is coated with a reflective film to control solar heat gain. Instead, windows should incorporate different glass types such as UV-A or fritted glass. Windows should also incorporate UV-absorbing and UV-reflecting stripe and grid patterns in locations with the highest potential for bird-window collisions (e.g., lower levels near trees).</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>Prior to building permit issuance for each phase, bird-safe design practices shall be included.</p>	<p>Planning Department</p>	
<p>M-BI-10: Study of Willow Basin to Control Water Level and Duration of Inundation. A hydrological study shall be conducted on the willow basin to determine whether the additional input of storm runoff will affect the duration and depth of ponding. If the level of water will rise to within 3 feet of the base of any wax myrtle and remain at that level for more than 4 days, then the outlet of the willow basin shall be modified to prevent such rise of water level and duration. If the water level already exhibits these characteristics, then no change shall be made to ensure that the existing depth and duration of ponding in the willow basin remains as is.</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>Submit a hydrological study prior to permit issuance for each phase. If the level of water will rise to within 3 feet of the base of any wax myrtle and remain at that level for more than 4 days, then the outlet of the willow basin shall be modified to prevent such rise of water level and duration. If the water level already exhibits these characteristics, then no change shall be made in the willow basin .</p>	<p>Planning Department</p>	
<i>Hydrology and Water Quality</i>				
<p>M-HY-1: Best Management Practices for SWPPP. A pollution prevention plan shall</p>	<p>Project Sponsor and</p>	<p>Submit copy of NOI and</p>	<p>SFPUC</p>	

213

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>be developed for all construction activities on the Project Site. The applicant shall apply for coverage under the NPDES General Construction Activity Permit from the State Water Quality Control Board by filing a Notice of Intent (NOI), and, as part of the permit and monitoring process, prepare and implement a Stormwater Pollution Prevention Plan (SWPPP). The SWPPP shall include design details and construction specifications for all site drainage control and other water quality control strategies, including Best Management Practices (BMPs) and other measures for stormwater pollution reduction. These include, but are not limited to, the following:</p> <ul style="list-style-type: none"> • Soil stabilization controls, such as hydroseeding and/or placement of straw mulch; • Watering for dust control; • Perimeter silt fences; • Sediment traps/basins; • Minimizing the length of open trenches and stockpile volumes; • Slip prevention and control, such as minimizing grading during the rainy season; and <p>Controlled entry and egress from the excavation area to minimize off-site tracking of sediment, and vehicle and equipment wash-down facilities.</p>	<p>construction contractor(s)</p>	<p>SWPPP prior to permit issuance for each phase.</p> <p>Provide copies of any monitoring documents required in the SWPPP to Planning Department as well as to the requiring agency.</p>		
Hazards and Hazardous Materials				
<p>M-HZ-2A: Hazardous Materials - Testing for and Handling of Contaminated Soil</p> <p>The Proposed Project would be carried out in four major Phases over a 20-year construction period. Within the geographic boundaries to be redeveloped within each Phase, the Project Sponsor shall, if appropriate, identify large, planned areas of redevelopment. For the purpose of this mitigation measure, each such area is referred to as a "Sub-Phase." The steps below shall be taken for each Sub-Phase. If the Project Sponsor does not identify such areas within a Phase, then each step shall be taken for the geographic boundaries of the entire Phase at once.</p> <p><u>Step 1: Soil Testing</u></p> <p>Soil testing would be done incrementally over the 20-year construction period, including pre-testing of each Sub-Phase, prior to excavation and/or soil disturbance. Prior to obtaining building permits for a particular Sub-Phase, the Project Sponsor shall hire a consultant to collect soil samples (borings) from selected locations in the work area in which soil would be disturbed and/or excavated. (This initial soil sampling and reporting shall be done prior to excavation, but additional soil testing from on-site soil stockpiles</p>	<p>Project Sponsor to retain qualified professional consultant for Steps 1, 2 and 4.</p> <p>Construction contractor to carry out and report on activities required in Step 3.</p>	<p>Soil report and SMP shall be approved by the San Francisco Department of Public Health prior to permit issuance for each phase, with a copy to the Planning Department.</p> <p>Construction contractor to provide annual reports to Department of Public Health (or quarterly reports if required by SMP), with copies to the Planning Department, of activities carried out</p>	<p>Department of Public Health</p>	

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>may also be required, if there are indications [e.g., odors, visible staining] of contamination in the excavated soil.)</p> <p>The soil samples shall be tested for these Compounds of Concern: total lead, petroleum hydrocarbons, volatile organic compounds (VOCs), and four heavy metals: chromium, nickel, copper, and zinc. The consultant shall analyze the soil borings as discrete, not composite samples. The consultant shall prepare a report on the soil testing for the Compounds of Concern that includes the laboratory results of the soil testing and a map that shows the locations from which the consultant collected the soil samples.</p> <p>The Project Sponsor shall submit the report on the soil testing for the Compounds of Concern for the Sub-Phase and a fee of \$501 in the form of a check payable to the San Francisco Department of Public Health (DPH), to the Hazardous Waste Program, Department of Public Health, 1390 Market Street, Suite 210, San Francisco, California 94102. The fee of \$501 shall cover three hours of soil testing report review and administrative handling. If additional review is necessary, DPH shall bill the Project Sponsor for each additional hour of review over the first three hours, at a rate of \$167 per hour. These fees shall be charged pursuant to Section 31.47(c) of the San Francisco Administrative Code. DHP shall review the soil testing program to determine whether soils on the Project Site are contaminated with any of the Compounds of Concern at or above potentially hazardous levels.</p> <p><u>Step 2: Preparation of Site Mitigation Plans</u></p> <p>Incrementally over the 20-year construction period, for each Sub-Phase, prior to beginning demolition, excavation, and construction work for that area, the Project Sponsor shall prepare a Site Mitigation Plan (SMP). The SMP for the Sub-Phase shall include a discussion of the level of contamination of soils by Compounds of Concern, if any, based on the soils testing in Step 1. The SMP shall set forth mitigation measures for managing contaminated soils on the site, if any, including but not limited to: 1) the alternatives for managing contaminated soils on the site (e.g., encapsulation, partial or complete removal, treatment, recycling for reuse, or a combination); 2) the preferred alternative for managing contaminated soils on the site and a brief justification; and 3) the specific practices to be used to handle, haul, and dispose of contaminated soils on the site. The SMP for each Sub-Phase shall be submitted to the Department of Public Health (DPH) for review and approval. A copy of the SMP shall be submitted to the Planning Department to become part of the case file. Additionally, the DPH may require confirmatory samples for the project site.</p> <p><u>Step 3: Handling, Hauling, and Disposal Contaminated Soils</u></p> <p>(a) Specific work practices: The construction contractor shall be alert for the presence of contaminated soils during excavation and other construction activities on the site (detected</p>		<p>pursuant to Step 3 for each construction phase</p> <p>Consultant to submit closure report to DPH for approval pursuant to Step 4 for each phase; a copy of the approved report shall be provided to the Planning Department</p>		

215

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>through soil odor, color, and texture and results of on-site soil testing), and shall be prepared to handle, profile (i.e., characterize), and dispose of such soils appropriately (i.e., as dictated by local, State, and federal regulations, including OSHA work practices) when such soils are encountered on the site.</p> <p>(b) Dust suppression: Soils exposed during excavation for site preparation and project construction activities shall be kept moist throughout the time they are exposed, both during and after work hours.</p> <p>(c) Surface water runoff control: Where soils are stockpiled, visqueen shall be used to create an impermeable liner, both beneath and on top of the soils, with a berm to contain any potential surface water runoff from the soil stockpiles during inclement weather.</p> <p>(d) Soils replacement: If necessary, clean fill or other suitable material(s) shall be used to bring portions of the Project Site, where lead-contaminated soils have been excavated and removed, up to construction grade.</p> <p>(e) Hauling and disposal: If soils are contaminated such that they must be hauled off-site for treatment and/or disposal, contaminated soils shall be hauled off the Project Site by waste hauling trucks appropriately certified with the State of California and adequately covered to prevent dispersion of the soils during transit, and shall be disposed of at the permitted hazardous waste disposal facility registered with the State of California.</p> <p><u>Step 4: Preparation of Closure/Certification Report for Each Sub-Phase</u></p> <p>After excavation and foundation construction activities are completed for a particular Sub-Phase, the Project Sponsor shall prepare and submit a closure/certification report to DPH for review and approval for that area. The closure/certification report shall include the mitigation measures (if any were necessary) in the SMP for handling and removing contaminated soils, if any, from the Project Site, and if applicable, whether the construction contractor modified any of these mitigation measures, and how and why the construction contractor modified those mitigation measures.</p>				
<p>M-HZ-2B: Hazards (Decontamination of Vehicles)</p> <p>If, for any Sub-Phase, the San Francisco Department of Public Health (DPH) determines that the soils in that area are contaminated with contaminants at or above potentially hazardous levels, all trucks and excavation and soil handling equipment working in that area shall be decontaminated following use and prior to removal from the site. Gross contamination shall be first removed through brushing, wiping, or dry brooming. The vehicle or equipment shall then be washed clean (including tires). Prior to removal from the work site, all vehicles and equipment shall be inspected to ensure that contamination has been removed.</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>During construction for each phase, if determined by the San Francisco DPH.</p>	<p>Department of Public Health</p>	
<p>IMPROVEMENT MEASURES FOR THE PARKMERCED PROJECT</p>				

**EXHIBIT 1:
 MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT
 (Includes Text for Adopted Mitigation and Improvement Measures)**

MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
<p>Improvement Measure I-TR-7: Provide a southbound right turn deceleration lane at the new access from 19th Avenue at Cambon Drive to avoid interference with HOT lane operations. As an improvement measure, to avoid conflict with the through traffic, a right-turn deceleration lane should be constructed on the west side of the fourth southbound lane, allowing vehicular access from 19th Avenue to Cambon Drive, minimizing disruption to flow in the HOT lane. This would require the removal of on-street parking in the vicinity of the ingress.</p>	<p>Project Sponsor with coordination of SFMTA and Caltrans</p>	<p>Simultaneous with implementation of HOT lane.</p>	<p>Planning Department</p>	
<p>Improvement Measure I-TR-29: Install colored bike lanes to direct cyclists through the Brotherhood Way/Junipero Serra Boulevard interchange and raise auto awareness of bicycles. This improvement measure may not achieve the same level of comfort for a cyclist that exists under current conditions, but it would improve conditions with implementation of the auxiliary lanes.</p> <p>Implementation of this improvement measure would require approval by Caltrans, which operates the facility.</p>	<p>Project Sponsor with coordination of SFMTA and Caltrans</p>	<p>Simultaneous with construction of other project-proposed improvements at Junipero Serra Boulevard / Brotherhood Way interchange</p>		
<p>Improvement Measure I-WS-A: Design Feature Consideration for Proposed Buildings. Building massing can affect wind flow. Podiums or terraced roofs create horizontal "shelves" that can deflect downward wind flow away from streets and sidewalks. These types of design features should be considered for the proposed buildings at the intersection of Chumasero Drive and Brotherhood Way and the intersection of Junipero Serra Boulevard and Brotherhood Way. Like podiums and terraced roofs, canopies can deflect downward wind flow from streets and sidewalks.</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>Prior to building permit issuance for proposed buildings at the intersection of Chumasero Drive and Brotherhood Way and at the intersection of Junipero Serra Boulevard and Brotherhood Way.</p>	<p>Department of Building Inspection</p>	
<p>Improvement Measure I-WS-B: Incorporation of Landscaping to Reduce Wind Speeds. Landscaping can be effective at reducing wind speeds. Porous materials (latticework, screens, vegetation, etc.) offer more effective wind shelter than solid surfaces. Landscaping should be installed in appropriate locations throughout the Project Site to reduce wind speeds. Wind-sheltering elements should be located west of the area being protected and should be of sufficient height.</p>	<p>Project Sponsor to retain qualified professional consultant</p>	<p>Prior to building permit issuance for each phase</p>	<p>Planning Department</p>	
<p>Improvement Measure I-GE.a: Use of Soldier-Pile-and-Lagging Shoring System. The Project Sponsor has agreed to follow the conclusions and recommendations of the 2008 Geologic, Geotechnical and Seismic Findings report to use a soldier-pile-and-lagging shoring system to shore up soils during excavation for building foundations and basements.</p>	<p>Project Sponsor</p>	<p>Prior to building permit issuance for each phase</p>	<p>Department of Building Inspection</p>	
<p>Improvement Measure I-GE.b: Soil Corrosivity Tests. The Project Sponsor has agreed to follow the conclusions and recommendations of the 2008 Geologic,</p>	<p>Project Sponsor</p>	<p>Prior to building permit issuance for each phase</p>	<p>Department of Building Inspection</p>	

217

EXHIBIT 1: MITIGATION MONITORING AND REPORTING PROGRAM FOR THE PARKMERCED PROJECT (Includes Text for Adopted Mitigation and Improvement Measures)				
MEASURES ADOPTED AS CONDITIONS OF APPROVAL	Responsibility for Implementation	Schedule	Monitoring/Report Responsibility	Status/Date Completed
Geotechnical and Seismic Findings report to test the soils for corrosivity and take appropriate measures to protect new construction in contact with the soil from corrosion.				



SAN FRANCISCO PLANNING DEPARTMENT

Planning Commission Motion No. 18269 Environmental Impact Report Certification

HEARING DATE: FEBRUARY 10, 2011

Hearing Date: February 10, 2011
Case No.: 2008.0021E
Project Address: 3711 19th Avenue
Zoning: RM-4, RM-1 and RH-1(D)
40-X and 1Height and Bulk District
Block/Lot: 7303-001, 7303-A-001, 7308-001, 7309-001, 7309-A-001, 7310-001, 7311-001, 7315-001, 7316-001, 7317-001, 7318-001, 7319-001, 7320-003, 7321-001, 7322-001, 7323-001, 7325-001, 7326-001, 7330-001, 7331-004, 7332-004, 7333-001, 7333-003, 7333-A-001, 7333-B-001, 7333-C-001, 7333-D-001, 7333-E-001, 7334-001, 7335-001, 7336-001, 7337-001, 7338-001, 7339-001, 7340-001, 7341-001, 7342-001, 7343-001, 7344-001, 7345-001, 7345-A-001, 7345-B-001, 7345-C-001, 7356-001, 7357-001, 7358-001, 7359-001, 7360-001, 7361-001, 7362-001, 7363-001, 7364-001, 7365-001, 7366-001, 7367-001, 7368-001, 7369-001, and 7370-001
Project Sponsor: Seth Mallen, Parkmerced Investors, LLC
3711 19th Avenue
San Francisco, CA 94132
Staff Contact: Rick Cooper – (415) 575-9027
rick.cooper@sfgov.org

1650 Mission St.
Suite 400
San Francisco,
CA 94103-2479

Reception:
415.558.6378

Fax:
415.558.6409

Planning
Information:
415.558.6377

ADOPTING FINDINGS RELATED TO THE CERTIFICATION OF A FINAL ENVIRONMENTAL IMPACT REPORT FOR THE PROPOSED PARKMERCED PROJECT

MOVED, that the San Francisco Planning Commission ("Commission") hereby CERTIFIES the Final Environmental Impact Report identified as Case No. 2008.0021E, Parkmerced Project, 3711 19th Avenue ("Project"), based upon the following findings:

1. The City and County of San Francisco, acting through the Planning Department ("Department") fulfilled all procedural requirements of the California Environmental Quality Act (Cal. Pub. Res. Code Section 21000 *et seq.*, "CEQA"), the State CEQA Guidelines (Cal. Code of Regulations Title 14, Section 15000 *et seq.*, "CEQA Guidelines") and Chapter 31 of the San Francisco Administrative Code ("Chapter 31").

- A. The Department determined that an Environmental Impact Report ("EIR") was required and provided public notice of that determination by publication in a newspaper of general circulation on May 20, 2009
 - B. On May 12, 2010, the Department published the Draft Environmental Impact Report ("DEIR") and provided public notice in a newspaper of general circulation of the availability of the DEIR for public review and comment and of the date and time of the Planning Commission public hearing on the DEIR; this notice was mailed to the Department's list of persons requesting such notice.
 - C. Notices of availability of the DEIR and of the date and time of the public hearing were posted near the project site by Department staff on May 12, 2010.
 - D. On May 12, 2010, copies of the DEIR were mailed or otherwise delivered to a list of persons requesting it, to those noted on the distribution list in the DEIR, to adjacent property owners, and to government agencies, the latter both directly and through the State Clearinghouse.
 - E. Notice of Completion was filed with the State Secretary of Resources via the State Clearinghouse on May 12, 2010.
2. The Commission held a duly noticed public hearing on the DEIR on June 17, 2010, and received public comment. The period for acceptance of written comments ended on July 12, 2010.
 3. The Department prepared responses to comments on environmental issues received at the public hearing and in writing during the 61-day public review period for the DEIR, prepared revisions to the text of the DEIR in response to comments received and based on additional information that became available during the public review period, and corrected errors in the DEIR. This material was presented in a Comments and Responses document, published on October 28, 2010, distributed to the Commission and all parties who commented on the DEIR, and made available to the public at the Department at 1650 Mission Street.
 4. The Department has prepared a Final Environmental Impact Report (FEIR), consisting of the DEIR, any consultations and comments received during the review process, any additional information that became available, and the Comments and Responses document, all as required by law.
 5. Project Environmental Impact Report files have been made available for review by the Commission and the public. These files are available for public review at the Department at 1650 Mission Street, and are part of the record before the Commission.
 6. On February 10, 2011 the Commission reviewed and considered the FEIR and finds that the contents of the FEIR and the procedures through which the FEIR was prepared, publicized, and reviewed comply with the provisions of CEQA, the CEQA Guidelines, and Chapter 31.

7. The Planning Commission finds that the FEIR reflects the independent judgment and analysis of the City and County of San Francisco, is adequate, accurate and objective, and that the Comments and Responses document contains no significant revisions to the DEIR, and hereby CERTIFIES THE COMPLETION of the FEIR in compliance with CEQA and the CEQA Guidelines.

8. The Commission, in certifying the completion of the FEIR, finds that the project described in it:

A. Will result in the following significant and unavoidable project-specific environmental impacts:

1) Elimination of a visual/scenic resource of the built environment through the demolition of the existing garden apartment buildings and the removal of the existing landscaping;

2) Impairment of the significance of the Parkmerced historic district, an historical resource, through the demolition of the existing garden apartment buildings and removal of existing landscape features on the Project Site;

3) Construction-related transportation impacts in the project vicinity due to construction vehicle traffic and road construction associated with the realignment of the existing light rail tracks;

4) Traffic impacts at 8 intersections, including:

- Junipero Serra Boulevard/Sloat Boulevard/St. Francisco Boulevard/Portola Drive – Significant contribution to LOS F conditions during the weekday PM peak hour and weekend midday peak hour;
- Junipero Serra Boulevard/John Daly Boulevard/I-280 Northbound On-Ramp/I-280 Southbound Off-Ramp/SR 1 Northbound On-Ramp – Significant contribution to LOS F conditions during the weekday PM peak hour;
- 19th Avenue/Sloat Boulevard – LOS E to LOS F in the AM peak hour;
- 19th Avenue/Winston Drive – LOS D to LOS E in the weekend midday peak hour and significant contribution to LOS F conditions during the PM peak hour;
- Sunset Boulevard/Lake Merced Boulevard – LOS C to LOS E in the PM peak hour;
- Lake Merced Boulevard/Winston Drive – LOS C to LOS E in the AM peak hour and LOS D to LOS F in the PM peak hour;
- Lake Merced Boulevard/Font Boulevard – LOS D to LOS F in the AM peak hour and LOS C to LOS F in the PM peak hour; and
- Lake Merced Boulevard/Brotherhood Way – LOS D to LOS E in the AM peak hour, LOS C to LOS F in the PM peak hour, and LOS C to LOS E in the weekend midday peak hour;

- 5) Traffic impacts on the following freeway segments:
 - Southbound State Route 1 (Junipero Serra Boulevard) weaving segment between the on-ramp from Brotherhood Way and the off-ramp to John Daly Boulevard – Significant contribution to LOS E conditions during the AM peak hour, and LOS E to LOS F during the PM peak hour; and
 - Northbound State Route 1 (Junipero Serra Boulevard) weaving segment between the Brotherhood Way on-ramp and Brotherhood Way off-ramp, due to uncertainty of proposed mitigation to remove the loop onramp and replace it with a left-turn onramp, which is subject to Caltrans' jurisdiction.
- 6) Potential transit impacts due to the exceedance of the available transit capacity of Muni transit routes serving the Project Study Area, due to uncertainty of proposed mitigation to provide additional transit vehicles, which is subject to SFMTA's jurisdiction;
- 7) Potential transit impacts to the M Ocean View light rail due to route realignment and subsequent increased travel time, due to uncertainty of proposed mitigation to provide additional light rail vehicles or install transit signal priority, which are both subject to the SFMTA's jurisdiction;
- 8) Potential transit impacts due to increased vehicular traffic resulting in increased travel times for operations of the Muni 17-Parkmerced, 18-48th Avenue, 28-19th Avenue, 28L-19th Avenue Limited and 29-Sunset bus lines, as well as SamTrans bus service along the Lake Merced Boulevard corridor, due to uncertainty of proposed mitigation to provide additional transit vehicles or install transit preferential treatments, which are both subject to SFMTA's jurisdiction;
- 9) Transit impacts due to increased travel times and effects to operations of the Muni 17-Parkmerced, 28-19th Avenue and 28L-19th Avenue Limited and 29-Sunset bus lines, as well as SamTrans bus service along the Lake Merced Boulevard corridor;
- 10) Noise impacts due to increased traffic;
- 11) Light rail noise and vibration impacts;
- 12) Noise impacts due to operation of stationary noise sources potentially exceeding noise level standards;
- 13) Construction-related toxic air contaminates impact;
- 14) Operational regional air quality impacts;
- 15) Temporary wind impacts during phased construction;

16) Potential wind impacts due to the proposed Special Use District, which could result in exceedances of the wind hazard criterion or increases in the area subject to winds greater than 26 mph;

17): Operational biological impacts to special-status species, including interference with bird or bat movement and migration corridors and raptor nest sites due to operation of the 51 wind turbines on the western periphery of the Project Site;

B. Will contribute considerably to the following cumulative environmental impacts:

1) A cumulative impact to the Parkmerced historic district, an historical resource, through the demolition of the existing garden apartment buildings and removal of existing landscape features.

2) Cumulative traffic impacts at 13 intersections, including:


- Junipero Serra Boulevard/Sloat Boulevard/St. Francis Boulevard/Portola Drive;
- Junipero Serra Boulevard/John Daly Boulevard/I-280 Northbound On-Ramp/I-280 Southbound Off-Ramp/SR 1 Northbound On-Ramp;
- 19th Avenue/Sloat Boulevard;
- 19th Avenue/Winston Drive;
- 19th Avenue/Holloway Avenue;
- Brotherhood Way/Chumasero Drive;
- Sunset Boulevard/Lake Merced Boulevard;
- Lake Merced Boulevard/Winston Drive;
- Lake Merced Boulevard/Font Boulevard;
- Lake Merced Boulevard/Brotherhood Way;
- Lake Merced Boulevard/John Muir Drive;
- John Daly Boulevard/Lake Merced Boulevard; and
- Lake Merced Boulevard/Gonzalez Drive;

3) Cumulative impacts to traffic at four freeway segments on State Route 1 (Junipero Serra Boulevard):

- Southbound between the Brotherhood Way on-ramp and John Daly Boulevard off-ramp;
- Northbound between the off-ramp to Northbound I-280 and the John Daly Boulevard on-ramp;
- Northbound between the John Daly Boulevard on-ramp and the Alemany Boulevard off-ramp; and

- Northbound between the Brotherhood Way loop on- and off-ramps, due to uncertainty of proposed mitigation to remove the loop onramp and replace it with a left-turn onramp, which is subject to Caltrans' jurisdiction;
- 4) Cumulative impact to transit capacity under 2030 cumulative conditions by contributing transit ridership to screenlines expected to exceed available transit capacity;
- 5) Cumulative noise impacts due to increases in traffic from the Project in combination with other development; and
- 6) Cumulative air quality impacts;

I hereby certify that the foregoing Motion was ADOPTED by the Planning Commission at its regular meeting of February 10, 2011.



Linda D. Avery
Commission Secretary

AYES: Commissioners Antonini, Borden, Fong, and Miguel

NAYS: Commissioners Moore, Olague, and Sugaya

ABSENT:

ADOPTED: February 10, 2011



SAN FRANCISCO PLANNING DEPARTMENT

Planning Commission Motion No. 18270

CEQA Findings

HEARING DATE: FEBRUARY 10, 2011

Date: January 27, 2011
Project Name: Parkmerced Mixed-Use Development Program
Case Number: 2008.0021EPMTZW
Initiated by: Seth Mallen, Parkmerced Investors, LLC
 3711 - 19th Avenue
 San Francisco, CA 94132
Staff Contact: Elizabeth Watty, Planner
Elizabeth.Watty@sfgov.org, 415-558-6620
Reviewed By: David Alumbaugh, Acting Director Citywide Planning
David.Alumbaugh@sfgov.org, 415-558-6601.
Recommendation: Adopt CEQA Findings

1650 Mission St.
Suite 400
San Francisco,
CA 94103-2479

Reception:
415.558.6378

Fax:
415.558.6409

Planning
Information:
415.558.6377

ADOPTING PROJECT APPROVAL FINDINGS UNDER THE CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) TO ALLOW THE FULL IMPLEMENTATION OF THE PARKMERCED MIXED-USE DEVELOPMENT PROGRAM ("PROJECT"), BEING ALL OF ASSESSOR'S BLOCKS 7303-001, 7303-A-001, 7308-001, 7309-001, 7309-A-001, 7310-001, 7311-001, 7315-001, 7316-001, 7317-001, 7318-001, 7319-001, 7320-003, 7321-001, 7322-001, 7323-001, 7325-001, 7326-001, 7330-001, 7331-004, 7332-004, 7333-001, 7333-003, 7333-A-001, 7333-B-001, 7333-C-001, 7333-D-001, 7333-E-001, 7334-001, 7335-001, 7336-001, 7337-001, 7338-001, 7339-001, 7340-001, 7341-001, 7342-001, 7343-001, 7344-001, 7345-001, 7345-A-001, 7345-B-001, 7345-C-001, 7356-001, 7357-001, 7358-001, 7359-001, 7360-001, 7361-001, 7362-001, 7363-001, 7364-001, 7365-001, 7366-001, 7367-001, 7368-001, 7369-001, and 7370-001, IN THE RM-1 (RESIDENTIAL MIXED, LOW DENSITY), RM-4 (RESIDENTIAL MIXED, HIGH DENSITY), & RH-1(D) (RESIDENTIAL HOUSE, ONE-FAMILY, DETACHED) DISTRICTS.

PREAMBLE

In determining to approve the Parkmerced Project ("Project") described in Section A, Project Description below, the San Francisco Planning Commission (hereinafter "Commission") makes and adopts the following findings of fact and decisions regarding mitigation measures and alternatives, and adopts the statement of overriding considerations, based on substantial evidence in the whole record of this proceeding and under the California Environmental Quality Act ("CEQA"), California Public Resources Code Sections 21000 et seq., particularly Sections 21081 and 21081.5, the Guidelines for Implementation of CEQA ("CEQA Guidelines"), 14 California Code of Regulations Sections 15000 et seq., particularly Sections 15091 through 15093, and Chapter 31 of the San Francisco Administration Code.

FINDINGS

The San Francisco Planning Commission hereby incorporates by reference as though fully set forth herein the findings for the Project approval of the Parkmerced Mixed-Use Development Program (hereinafter the "Project") attached hereto as Exhibit A pursuant to the California Environmental Quality Act, California Public Resources Code, Sections 21000 et seq. ("CEQA"), the Guidelines for Implementation of CEQA, Title 15 California Code of Regulations Sections 15000 et seq. ("Guidelines"), and Chapter 31 of the San Francisco Administrative Code ("Chapter 31"), entitled Environmental Quality:

A. Project Description

The Parkmerced Mixed-Use Development Program is a long-term (20-30 year) mixed-use development program to comprehensively replan and redevelop the Parkmerced Project Site—the "Project" identified in the Final EIR. The Project would increase residential density, provide a neighborhood core with new commercial and retail services, modify transit facilities, and improve utilities within the development site. A new site for a Pre-K-5 school and/or day care facility, a fitness center, and new open space uses, including athletic playing fields, walking and biking paths, an approximately 2-acre farm, and community gardens, would also be provided. About 1,683 of the existing apartments located in 11 tower buildings would be retained. Over an approximately 20-year period of phased construction, the remaining 1,538 existing apartments would be demolished in phases and fully replaced, and an additional 5,679 net new units would be added to the Project Site, resulting at full build-out in a total of about 8,900 units on the Project Site.

The Project includes construction of (or provides financing for construction of) a series of transportation improvements, which include rerouting the existing Muni Metro M Ocean View line from its current alignment along 19th Avenue. The new alignment, as currently envisioned and analyzed in the Final EIR, would leave 19th Avenue at Holloway Avenue and proceed through the neighborhood core in Parkmerced. The Muni M line trains would then travel alternately along one of two alignments: trains either would re-enter 19th Avenue south of Felix Avenue and terminate at the existing Balboa Park station, or they would terminate at a new station, with full layover and terminal facilities, constructed on the Project Site at the intersection of Font Boulevard and Chumasero Drive.

The Proposed Project also includes a series of infrastructure improvements, including the installation of a combination of renewable energy sources, such as wind turbines and photovoltaic cells, to meet a portion of the Proposed Project's energy demand. In addition, stormwater runoff from buildings and streets would be captured and filtered through a series of bioswales, ponds, and other natural filtration systems. The filtered stormwater would then either percolate into the groundwater that feeds the Upper Westside groundwater basin and Lake Merced or be released directly into Lake Merced.

Amendments to the San Francisco Planning Code and the San Francisco General Plan are also proposed as part of the Proposed Project. The Planning Code amendments would change the Height and Bulk District Zoning Map and would add a Special Use District (SUD) applicable to

the entire Project Site, which would include an overlay of density and uses within the SUD. A Development Agreement is also proposed as part of the Project, as well as adoption of the *Parkmerced Design Standards and Guidelines*, which contain specific development guidelines.

The Final EIR also evaluated a Project sub-variant, which would construct a right-turn ingress along 19th Avenue between Crespi Drive and Junipero Serra Boulevard at Cambon Drive. This new access location would provide ingress for southbound vehicles only and would not provide access out onto 19th Avenue.

B. Planning and Environmental Review Process

The Project Sponsor applied for environmental review on January 8, 2008. The Department determined that an Environmental Impact Report was required and provided public notice of the preparation of such on May 20, 2009, and held a public scoping meeting on June 8, 2009. The Department published a Draft Environmental Impact Report (DEIR) on May 12, 2010. The Commission held a public hearing to solicit testimony on the DEIR on June 17, 2010. The Department received written comments on the DEIR for 61-days, beginning on May 12, 2010. The Department published the Comments and Responses on October 28, 2010. The DEIR, together with the Comments and Responses document, constitute the Final Environmental Impact Report (FEIR) for the Parkmerced Mixed-Use Development Program. The Commission certified the FEIR on February 10, 2011, in Motion No. 18629.

Pursuant to the California Environmental Quality Act, Public Resources Code Section 21000 *et seq.*, (CEQA); Title 14 California Code of Regulations Section 15000 *et seq.* (CEQA Guidelines), and Chapter 31 of the San Francisco Administrative Code, the Planning Commission has reviewed and considered the FEIR, which is available for public review at the Planning Department's offices at 1650 Mission Street.

Pursuant to CEQA Guidelines Section 15162, the Commission finds that the proposed actions before this Commission are within the scope of the project analyzed in the FEIR and (1) that no substantial changes are proposed in the Project and no substantial changes have occurred with respect to the circumstances under which this Project will be undertaken that would require major revisions to the FEIR due to the involvement of any new significant environmental effects or a substantial increase in the severity of previously identified effects and (2) no new information that was not known and could not have been known shows that the project will have any new significant effects not analyzed in the FEIR or a substantial increase in the severity of any effect analyzed or that new mitigation measures should be included that have not. The Commission further finds that an addendum to the FEIR is not required due to any changes in the Project or the Project's circumstances.

The public hearing transcript, a copy of all letters regarding the FEIR received during the public review period, the administrative record, and background documentation for the FEIR are located at the Planning Department, 1650 Mission Street, San Francisco. The Planning Commission Secretary, Linda Avery, is the custodian of records for the Planning Department and the Planning Commission.

Motion No. 18270
Hearing Date: February 10, 2011

CASE NO. 2008.0021EPMTZW
Parkmerced Mixed-Use Development Program

DECISION

That based upon the Record, the submissions by the Applicant, the staff of the Department and other interested parties, the oral testimony presented to this Commission at the public hearings, and all other written materials submitted by all parties, the Commission hereby adopts the CEQA Findings attached hereto as Exhibit A and the Mitigation Monitoring and Reporting Program (MMRP) attached hereto as Exhibit B, which are incorporated herein by reference as though fully set forth.

I hereby certify that the Planning Commission ADOPTED the foregoing Motion on Thursday, February 10, 2011.

Commissioner _____

AYES: Commissioners Antonini, Borden, Fong, and Miguel

NAYS: Commissioners Moore, Olague, and Sugaya

ABSENT:

ADOPTED: February 10, 2011

Somera, Alisa (BOS)

160851 ✓ 160870

om: Board of Supervisors, (BOS)
Sent: Tuesday, September 06, 2016 3:04 PM
Subject: FW: Abandonment of Parkmerced Development, File No. 160870
Attachments: Parkmerced-Letter - Street_PSE Vacation Reserve Easement.pdf

From: Bunone, Morgan [mailto:M9B3@pge.com]
Sent: Tuesday, September 06, 2016 2:55 PM
To: Board of Supervisors, (BOS) <board.of.supervisors@sfgov.org>
Cc: Rivera, Javier (DPW) <Javier.Rivera@sfdpw.org>; Wu, Steven <SKW0@pge.com>
Subject: Abandonment of Parkmerced Development, File No. 160870


Ms. Calvillo,

Attached is a courtesy copy of a letter which will be sent to you in regards to PG&E facilities for the proposed street vacations of the Parkmerced area. An original will be overnighted to you.

Please contact me if you have any questions.

Thank you,

Morgan Bunone | Land Agent
Pacific Gas and Electric Company
245 Market St, 1031F | San Francisco, CA 94105
Office: 415-973-5559



We respect your privacy. Please review our privacy policy for more information.
<http://www.pge.com/en/about/company/privacy/customer/index.page>



*Pacific Gas and
Electric Company™*

September 6, 2016

Angela Calvillo
Clerk of the Board, City Hall
City and County of San Francisco
1 Dr. Carlton Goodlett Place, Room 244
San Francisco, CA 94102

RECEIVED
BOARD OF SUPERVISORS
SAN FRANCISCO
2016 SEP -7 AM 10:31
BY _____
AK

RE: Abandonment of Parkmerced Development Area, File no. 160870

Dear Ms. Calvillo:

This is in response to your letter, dated August 17, 2016, informing PG&E of the proposed Resolution No. 360-16 for the abandonment of portions of the following streets (along with public service easements within those streets) that exist within the Subphases 1A and 1B of the Parkmerced Development Project area, more specifically as follows: Vidal Drive, Galindo Avenue, Chumasero Drive, Acevedo Avenue, Serrano Drive, Gonzalez Drive, Cambon Drive and Font Boulevard.

1) Public Service Easements: Currently, PG&E has existing in-place utility facilities serving the public within the proposed vacation of the public service easement referenced above. Therefore, PG&E objects to the proposed vacation as presented to us.

If the utility facilities need to be relocated to accommodate the proposed vacation, PG&E would do so at your expense. Also, you would be required to provide an equal replacement right for the relocated facilities in the new location.

2) Street Vacations: An investigation indicates that PG&E is presently operating and maintaining utility facilities within the streets of the proposed areas to be abandoned. PG&E objects to the proposed reservation language as presented in Resolution No. 360-16. PG&E does not accept the language for the reservation of rights granted under "temporary immediately revocable licenses" as written in Line 14 of Page 6 of the proposed Resolution No. 360-16. If the abandonment is approved by the City Council/Board of Supervisors, PG&E respectfully requests that the following reservation be inserted in the Resolution of Vacation or Abandonment for the proposed streets to be abandoned:

RESERVING therefrom pursuant to the provisions of Section 8340 of the Streets and Highways Code and for the benefit of Pacific Gas and Electric Company, the permanent easement and the right at any time and from time to time to construct, reconstruct, maintain, operate, replace, remove, repair, renew and enlarge lines of pipes, conduits, cables, wires, poles, electrical conductors, and other equipment, fixtures and appurtenances for the operation of electric, gas, and communication facilities, including

access, and also the rights to trim and cut down trees and brush that may be a hazard to the facilities; said area shall be kept open and free of buildings, structures and wells of any kind."

This reservation will protect our facilities installed pursuant to our franchise agreement with you. Upon approval of the abandonment by the City Council/Board of Supervisors, please send a certified copy of the Resolution of Vacation to:

Pacific Gas and Electric Company
Morgan Bunone
Land & Environmental Management
245 Market St, 1031F
San Francisco, CA 94105

If you have any questions, please contact me at (415) 973-5559.

Sincerely,



Morgan Bunone
Land Agent

Cc: Javier Rivera, Assistant Engineer, SFDPW

BOARD of SUPERVISORS



City Hall
1 Dr. Carlton B. Goodlett Place, Room 244
San Francisco 94102-4689
Tel. No. 554-5184
Fax No. 554-5163
TDD/TTY No. 554-5227

NOTICE OF PUBLIC HEARING

BOARD OF SUPERVISORS OF THE CITY AND COUNTY OF SAN FRANCISCO

NOTICE IS HEREBY GIVEN that the City and County of San Francisco Board of Supervisors will hold a public hearing to consider the following proposal and said public hearing will be held as follows, at which time all interested parties may attend and be heard:

Date: Tuesday, September 6, 2016


Time: 3:00 p.m.

Location: Legislative Chamber, Room 250, located at City Hall
1 Dr. Carlton B. Goodlett Place, San Francisco, CA

Subject: File No. 160880. Hearing to consider an Ordinance (File No. 160851) ordering the conditional vacation of portions of streets (along with public service easements within those streets) that exist within the Subphases 1A and 1B of the Parkmerced Development Project area, an approximately 152 acre site located in the Lake Merced District in the southwest corner of San Francisco and generally bounded by Vidal Drive, Font Boulevard, Pinto Avenue, and Serrano Drive to the north, 19th Avenue and Junipero Serra Boulevard to the east, Brotherhood Way to the south, and Lake Merced Boulevard to the west; reserving various easement rights in favor of the City and third party utilities, subject to conditions specified in this ordinance; delegating authority to the Director of Real Estate to execute certain quit claim deeds; adopting findings under the California Environmental Quality Act; adopting findings that the vacations are consistent with the Parkmerced Development Agreement, the General Plan, and the eight priority policies of Planning Code, Section 101.1; directing the Clerk of the Board of Supervisors to make certain transmittals; and authorizing actions by City officials in furtherance of this Ordinance; scheduled pursuant to a Resolution (File No. 160870) approved by the Board on August 2, 2016.

On August 2, 2016, the Board of Supervisors considered and approved a Resolution of Intention (Resolution No. 360-16), which set the date and time for the subject hearing.

In accordance with Administrative Code, Section 67.7-1, persons who are unable to attend the hearing on this matter may submit written comments to the City prior to the time the hearing begins. These comments will be made as part of the official public record in this matter, and shall be brought to the attention of the members of the Board. Written comments should be addressed to Angela Calvillo, Clerk of the Board, City Hall, 1 Dr. Carlton Goodlett Place, Room 244, San Francisco, CA 94102. Information relating to this matter is available in the Office of the Clerk of the Board. Agenda information relating to this matter will be available for public review on Friday, September 2, 2016.


Angela Calvillo, Clerk of the Board

DATED: August 16, 2016
POSTED/PUBLISHED: August 23 & 30, 2016

CALIFORNIA NEWSPAPER SERVICE BUREAU

DAILY JOURNAL CORPORATION

Mailing Address : 915 E FIRST ST, LOS ANGELES, CA 90012
Telephone (800) 788-7840 / Fax (800) 464-2839
Visit us @ www.LegalAdstore.com

Alisa Somera
CCSF BD OF SUPERVISORS (OFFICIAL NOTICES)
1 DR CARLTON B GOODLETT PL #244
SAN FRANCISCO, CA 94102

COPY OF NOTICE

Notice Type: GPN GOVT PUBLIC NOTICE
Ad Description AS - 09.06.16 Board COW 160880 160851

To the right is a copy of the notice you sent to us for publication in the SAN FRANCISCO EXAMINER. Thank you for using our newspaper. Please read this notice carefully and call us with ny corrections. The Proof of Publication will be filed with the County Clerk, if required, and mailed to you after the last date below. Publication date(s) for this notice is (are):

08/23/2016 , 08/30/2016

The charge(s) for this order is as follows. An invoice will be sent after the last date of publication. If you prepaid this order in full, you will not receive an invoice.

EXM# 2916044

NOTICE OF PUBLIC HEARING BOARD OF SUPERVISORS OF THE CITY AND COUNTY OF SAN FRANCISCO

TUESDAY, SEPTEMBER 6, 2016 - 3:00 PM CITY HALL, LEGISLATIVE CHAMBER, ROOM 250 1 DR. CARLTON B. GOODLETT PLACE, SAN FRANCISCO, CA

NOTICE IS HEREBY GIVEN that the City and County of San Francisco Board of Supervisors will hold a public hearing to consider the following proposal and said public hearing will be held as follows, at which time all interested parties may attend and be heard: File No. 160880. Hearing to consider an Ordinance (File No. 160851) ordering the conditional vacation of portions of streets (along with public service easements within those streets) that exist within the Sub-phases 1A and 1B of the Parkmerced Development Project area, an approximately 152 acre site located in the Lake Merced District in the southwest corner of San Francisco and generally bounded by Vidal Drive, Font Boulevard, Pinto Avenue, and Serrano Drive to the north, 19th Avenue and Junipero Serra Boulevard to the east, Brotherhood Way to the south, and Lake Merced Boulevard to the west; reserving various easement rights in favor of the City and third party utilities, subject to conditions specified in this ordinance; delegating authority to the Director of Real Estate to execute certain quit claim deeds; adopting findings under the California Environmental Quality Act; adopting findings that the vacations are consistent with the Parkmerced Development Agreement, the General Plan, and the eight priority policies of Planning Code, Section 101.1; directing the Clerk of the Board of Supervisors to make certain transmittals; and authorizing actions by City officials in furtherance of this Ordinance; scheduled pursuant to a Resolution (File No. 160870) approved by the Board on August 2, 2016. On August 2, 2016, the Board of Supervisors considered and approved a Resolution of Intention (Resolution No. 380-16), which set the date and time for the subject hearing. In accordance with Administra-

tive Code, Section 67.7-1, persons who are unable to attend the hearing on this matter may submit written comments to the City prior to the time the hearing begins. These comments will be made as part of the official public record in this matter, and shall be brought to the attention of the members of the Board. Written comments should be addressed to Angela Calvillo, Clerk of the Board, City Hall, 1 Dr. Carlton Goodlett Place, Room 244, San Francisco, CA 94102. Information relating to this matter is available in the Office of the Clerk of the Board. Agenda information relating to this matter will be available for public review on Friday, September 2, 2016. - Angela Calvillo, Clerk of the Board



* A 0 0 0 0 0 4 1 9 3 0 7 6 *

BOARD of SUPERVISORS



City Hall
1 Dr. Carlton B. Goodlett Place, Room 244
San Francisco 94102-4689
Tel. No. 554-5184
Fax No. 554-5163
TDD/TTY No. 544-5227

PROOF OF POSTING

Legislative File Nos. 160880 & 160851

Description of Items:

Hearing to consider an Ordinance (File No. 160851) ordering the conditional vacation of portions of streets (along with public service easements within those streets) that exist within the Subphases 1A and 1B of the Parkmerced Development Project area, an approximately 152 acre site located in the Lake Merced District in the southwest corner of San Francisco and generally bounded by Vidal Drive, Font Boulevard, Pinto Avenue, and Serrano Drive to the north, 19th Avenue and Junipero Serra Boulevard to the east, Brotherhood Way to the south, and Lake Merced Boulevard to the west; reserving various easement rights in favor of the City and third party utilities, subject to conditions specified in this ordinance; delegating authority to the Director of Real Estate to execute certain quit claim deeds; adopting findings under the California Environmental Quality Act; adopting findings that the vacations are consistent with the Parkmerced Development Agreement, the General Plan, and the eight priority policies of Planning Code, Section 101.1; directing the Clerk of the Board of Supervisors to make certain transmittals; and authorizing actions by City officials in furtherance of this Ordinance; scheduled pursuant to a Resolution (File No. 160870) approved by the Board on August 2, 2016.

I, Alfred J. Carrero Jr., an employee of the City and County of San Francisco, posted the above described document(s) in at least three (3) public places along the street(s) to be affected at least ten (14) days in advance of the hearing (pursuant to CA Streets and Highways Code, Section 970.5):

Date: 8-22-2016

Time: 10:30A - 3pm

Location: Lake Merced District

Signature: [Handwritten Signature]

Instructions: Upon completion, original must be filed in the above referenced file.

BOARD of SUPERVISORS



City Hall
1 Dr. Carlton B. Goodlett Place, Room 244
San Francisco 94102-4689
Tel. No. 554-5184
Fax No. 554-5163
TDD/TTY No. 544-5227

PROOF OF POSTING

Legislative File Nos. 160880 & 160851

Description of Items:

Hearing to consider an Ordinance (File No. 160851) ordering the conditional vacation of portions of streets (along with public service easements within those streets) that exist within the Subphases 1A and 1B of the Parkmerced Development Project area, an approximately 152 acre site located in the Lake Merced District in the southwest corner of San Francisco and generally bounded by Vidal Drive, Font Boulevard, Pinto Avenue, and Serrano Drive to the north, 19th Avenue and Junipero Serra Boulevard to the east, Brotherhood Way to the south, and Lake Merced Boulevard to the west; reserving various easement rights in favor of the City and third party utilities, subject to conditions specified in this ordinance; delegating authority to the Director of Real Estate to execute certain quit claim deeds; adopting findings under the California Environmental Quality Act; adopting findings that the vacations are consistent with the Parkmerced Development Agreement, the General Plan, and the eight priority policies of Planning Code, Section 101.1; directing the Clerk of the Board of Supervisors to make certain transmittals; and authorizing actions by City officials in furtherance of this Ordinance; scheduled pursuant to a Resolution (File No. 160870) approved by the Board on August 2, 2016.

I, DRAGOMIR RATIC, an employee of the City and County of San Francisco, posted the above described document(s) in at least three (3) public places along the street(s) to be affected at least ten (14) days in advance of the hearing (pursuant to CA Streets and Highways Code, Section 970.5):

Date: 08/22/2016

Time: 10:30 AM - 3:00 PM

Location: Lake Merced District

Signature: Dragomir Ratic

Instructions: Upon completion, original must be filed in the above referenced file.

Print Form

Introduction Form

By a Member of the Board of Supervisors or the Mayor

RECEIVED
BOARD OF SUPERVISORS
SAN FRANCISCO

2016 JUL 26 PM 4:28
Time stamp
or meeting date

BY 

I hereby submit the following item for introduction (select only one):

- 1. For reference to Committee. (An Ordinance, Resolution, Motion, or Charter Amendment)
- 2. Request for next printed agenda Without Reference to Committee.
- 3. Request for hearing on a subject matter at Committee.
- 4. Request for letter beginning "Supervisor inquires"
- 5. City Attorney request.
- 6. Call File No. from Committee.
- 7. Budget Analyst request (attach written motion).
- 8. Substitute Legislation File No.
- 9. Reactivate File No.
- 10. Question(s) submitted for Mayoral Appearance before the BOS on

Please check the appropriate boxes. The proposed legislation should be forwarded to the following:


- Small Business Commission Youth Commission Ethics Commission
- Planning Commission Building Inspection Commission

Note: For the Imperative Agenda (a resolution not on the printed agenda), use a Imperative Form.

Sponsor(s):

Subject:

The text is listed below or attached:

Signature of Sponsoring Supervisor: 

For Clerk's Use Only:

