

File No. 160950

Committee Item No. 7

Board Item No. _____

COMMITTEE/BOARD OF SUPERVISORS

AGENDA PACKET CONTENTS LIST

Committee: Land Use and Transportation

Date October 31, 2016

Board of Supervisors Meeting

Date _____

Cmte Board

| | | |
|-------------------------------------|--------------------------|--|
| <input type="checkbox"/> | <input type="checkbox"/> | Motion |
| <input type="checkbox"/> | <input type="checkbox"/> | Resolution |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | Ordinance |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | Legislative Digest |
| <input type="checkbox"/> | <input type="checkbox"/> | Budget and Legislative Analyst Report |
| <input type="checkbox"/> | <input type="checkbox"/> | Youth Commission Report |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | Introduction Form |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | Department/Agency Cover Letter and/or Report |
| <input type="checkbox"/> | <input type="checkbox"/> | Memorandum of Understanding (MOU) |
| <input type="checkbox"/> | <input type="checkbox"/> | Grant Information Form |
| <input type="checkbox"/> | <input type="checkbox"/> | Grant Budget |
| <input type="checkbox"/> | <input type="checkbox"/> | Subcontract Budget |
| <input type="checkbox"/> | <input type="checkbox"/> | Contract/Agreement |
| <input type="checkbox"/> | <input type="checkbox"/> | Form 126 - Ethics Commission |
| <input type="checkbox"/> | <input type="checkbox"/> | Award Letter |
| <input type="checkbox"/> | <input type="checkbox"/> | Application |
| <input type="checkbox"/> | <input type="checkbox"/> | Form 700 |
| <input type="checkbox"/> | <input type="checkbox"/> | Vacancy Notice |
| <input type="checkbox"/> | <input type="checkbox"/> | Information Sheet |
| <input type="checkbox"/> | <input type="checkbox"/> | Public Correspondence |

OTHER

(Use back side if additional space is needed)

| | | |
|-------------------------------------|--------------------------|--------------------|
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | CEQA Findings |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | Findings |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | Corrections List |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | 2016 State Code |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | 2016 National Code |
| <input type="checkbox"/> | <input type="checkbox"/> | |
| <input type="checkbox"/> | <input type="checkbox"/> | |
| <input type="checkbox"/> | <input type="checkbox"/> | |
| <input type="checkbox"/> | <input type="checkbox"/> | |
| <input type="checkbox"/> | <input type="checkbox"/> | |
| <input type="checkbox"/> | <input type="checkbox"/> | |

Completed by: Alisa Somera Date October 27, 2016

Completed by: _____ Date _____

[Plumbing Code - Repeal of Existing 2013 Code and Enactment of 2016 Edition]

Ordinance repealing the 2013 Plumbing Code in its entirety and enacting a 2016 Plumbing Code consisting of the 2016 California Plumbing Code as amended by San Francisco; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing an operative date of January 1, 2017; and directing the Clerk of the Board of Supervisors to forward the legislation to the California Building Standards Commission as required by State law.

NOTE: **Unchanged Code text and uncodified text** are in plain Arial font.
Additions to Codes are in single-underline italics Times New Roman font.
Deletions to Codes are in ~~strikethrough italics Times New Roman font~~.
Board amendment additions are in double-underlined Arial font.
Board amendment deletions are in ~~strikethrough Arial font~~.
Asterisks (* * * *) indicate the omission of unchanged Code subsections or parts of tables.

Be it ordained by the People of the City and County of San Francisco:

Section 1. Environmental Findings. The Planning Department has determined that the actions contemplated in this ordinance comply with the California Environmental Quality Act (California Public Resources Code Sections 21000 et seq.). Said determination is on file with the Clerk of the Board of Supervisors in File No. 160950 and is incorporated herein by reference. The Board affirms this determination.

Section 2. General Findings.

(a) The State of California adopts a new California Building Standards Code every three years (the "triennial State Code") with supplements published in intervening years. The triennial State Code goes into effect throughout the State of California 180 days after its

1 publication by the California Building Standards Commission or at a later date established by
2 the Commission.

3 (b) The California Building Standards Code is contained in Title 24 of the California
4 Code of Regulations. It consists of 12 Parts based upon model codes that are amended by
5 the State agencies with jurisdiction over the subject matter. The California Plumbing Code is
6 Part 5 of Title 24 of the California Code of Regulations. The 2016 California Plumbing Code
7 will go into effect throughout California on January 1, 2017.

8 (c) Local jurisdictions must enforce the California Building Standards Code but they
9 may also enact more restrictive building standards that are reasonably necessary because of
10 local conditions caused by climate, geology, or topography. Local amendments may be made
11 to a triennial State Code and also throughout the intervening years. However, local
12 amendments previously adopted are not automatically applicable to a new triennial State
13 Code. Rather, they must be re-enacted with the required findings of local conditions,
14 expressly made applicable to the new triennial State Code, and with an operative date no
15 earlier than the effective date of the new State Code.

16 (d) As in past triennial State Code adoption cycles, by this ordinance the Board of
17 Supervisors repeals the 2013 San Francisco Plumbing Code in its entirety, enacts the 2016
18 San Francisco Plumbing Code, and re-enacts the existing local amendments and makes them
19 applicable to the 2016 California Plumbing Code.

20 (e) Pursuant to Charter Section D3.750-5, the Building Inspection Commission
21 considered and approved San Francisco's amendments to the 2016 California Plumbing Code
22 at a duly noticed public hearing that was held on August 17, 2016.

23
24 Section 3. Findings regarding Local Conditions.
25

1 (a) California Health and Safety Code Sections 17958.7 and 18941.5 provide that
2 before making any changes or modifications to the California Plumbing Code and any other
3 applicable provisions published by the California Building Standards Commission, the
4 governing body must make an express finding that each such change or modification is
5 reasonably necessary because of specified local conditions. The local amendments together
6 with the required findings must be filed with the California Building Standards Commission
7 before the local changes or modifications can go into effect.

8 (b) The City and County of San Francisco is unique among California communities
9 with respect to local climatic, geological, topographical, and other conditions. A specific list of
10 findings that support San Francisco's modifications to the 2016 California Plumbing Code,
11 with a section-by-section correlation of each modification with a specific numbered finding, are
12 contained in Exhibit A entitled "Standard Findings for San Francisco Building Standards Code
13 Amendments."

14 (c) Pursuant to California Health and Safety Code Sections 17958.7 and 18941.5,
15 the Board of Supervisors finds and determines that the local conditions described in Exhibit A
16 constitute a general summary of the most significant local conditions giving rise to the need
17 for modification of the 2016 California Plumbing Code provisions published by the California
18 Building Standards Commission. The Board of Supervisors further finds and determines that
19 the proposed modifications are reasonably necessary based upon the local conditions set
20 forth in Exhibit A.

21
22 Section 4. Repeal of the 2013 San Francisco Plumbing Code and Enactment of the
23 2016 San Francisco Plumbing Code.

24 (a) The 2013 San Francisco Plumbing Code is hereby repealed in its entirety. The
25 San Francisco Plumbing Code being repealed was enacted on November 5, 2013, by

1 Ordinance No. 258-13, with an operative date of January 1, 2014. It was amended by
2 Ordinance No. 060-16. These ordinances are available on the website of the Board of
3 Supervisors.

4 (b) The 2016 San Francisco Plumbing Code is hereby enacted. It consists of the
5 2016 California Plumbing Code and San Francisco's existing local amendments, which are re-
6 enacted and expressly made applicable to the 2016 California Plumbing Code. Copies of the
7 2016 California Plumbing Code and the stand-alone San Francisco amendments are declared
8 to be part of Board File No. 160950 and are incorporated into this ordinance by reference as
9 though fully set forth. Additions to the 2016 California Plumbing Code are shown in bold
10 underlined type; deletions are shown with bold strikethrough type.

11
12 Section 5. Continuance of Actions Under Prior Code. Nothing contained in this
13 ordinance shall be construed as abating any action now pending under or by virtue of any
14 ordinance of the City and County of San Francisco hereby repealed, nor shall this ordinance
15 be construed as discontinuing, abating, modifying or altering any penalties accruing, or to
16 accrue, or as waiving any right of the City under any such ordinance.


17
18 Section 6. Severability. If any section, subsection, sentence, clause, or phrase of this
19 ordinance is, for any reason, held to be invalid, such decision shall not affect the validity of the
20 remaining portions of this ordinance. The Board of Supervisors hereby declares that it would
21 have passed this ordinance, and each section, subsection, sentence, clause, or phrase of this
22 Ordinance, irrespective of the fact that any one or more sections, subsections, sentences,
23 clauses, or phrases be declared invalid.

1 Section 7. Effective and Operative Dates. This ordinance shall become effective 30
2 days after enactment. Enactment occurs when the Mayor signs the ordinance, the Mayor
3 returns the ordinance unsigned or does not sign the ordinance within ten days of receiving it,
4 or the Board of Supervisors overrides the Mayor's veto of the ordinance. This ordinance shall
5 take effect and be in full force on and after either January 1, 2017 or its effective date if the
6 effective date is later.

7
8 Section 8. Directions to Clerk. Upon final passage of this ordinance, the Clerk of the
9 Board of Supervisors is hereby directed to transmit this ordinance with the Exhibit A
10 attachment and the San Francisco amendments to the 2016 California Plumbing Code to the
11 California Building Standards Commission pursuant to the applicable provisions of State law.

12
13 APPROVED AS TO FORM:
14 DENNIS J. HERRERA, City Attorney

15 By:


16 JUDITH A. BOYAJIAN
17 Deputy City Attorney
18 n:\land\as2016\1600669\01130927.docx

LEGISLATIVE DIGEST

[Plumbing Code - Repeal of Existing 2013 Code and Enactment of 2016 Edition]

Ordinance repealing the 2013 Plumbing Code in its entirety and enacting a 2016 Plumbing Code consisting of the 2016 California Plumbing Code as amended by San Francisco; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing an operative date of January 1, 2017; and directing the Clerk of the Board of Supervisors to forward the legislation to the California Building Standards Commission as required by State law.

Existing Law

The Plumbing Code regulates the installation and maintenance of plumbing systems and fixtures, water heaters, water supply and distribution, sanitation and ventilation systems, drainage, fuel piping, and medical and gas vacuum systems. The current San Francisco Plumbing Code consists of the 2013 California Plumbing Code (which incorporates the 2012 Uniform Plumbing Code) and San Francisco's local amendments to the 2013 California Plumbing Code ("San Francisco Amendments").

Amendments to Current Law

On January 1, 2017, a 2016 California Plumbing Code will go into effect throughout the State. The San Francisco Amendments to the 2013 California Code must be re-enacted and made applicable to the 2016 California Code. Therefore, as in past State Code adoption cycles, San Francisco will repeal its existing Plumbing Code in its entirety and adopt a new Plumbing Code consisting of the new model code, as amended by the State of California, and as further amended by San Francisco. The San Francisco Amendments to the 2013 California Plumbing Code will be carried forward and made applicable to the 2016 California Plumbing Code with no or only minor technical changes..

The San Francisco Amendments are not integrated into the text of the California Codes but rather are separately printed in a stand-alone document. Therefore, the user must consult both texts in order to determine the complete code requirement. In the San Francisco Amendments, additions to the 2016 California Electrical Code are shown in bold type; deletions are shown with strikethrough.

Background Information

The State of California adopts a new California Building Standards Code every three years (the "triennial State Code") with supplements published in intervening years. The triennial State Code goes into effect throughout the State 180 days after its publication by the California Building Standards Commission or at a later date established by the Commission. In the current triennial State Code adoption cycle, the California Building Standards Code will

go into effect on January 1, 2017. The California Building Standards Code is contained in Title 24 of the California Code of Regulations, and consists of several parts that are based upon model codes with amendments made by the State agencies with jurisdiction over the subject matter. The California Plumbing Code is Part 5 of Title 24 of the California Code of Regulations.

Local jurisdictions must enforce the California Building Standards Code but they may also enact more restrictive building standards that are reasonably necessary because of local conditions caused by climate, geology, or topography. Local amendments may be made to a triennial State Code and also throughout the intervening years. However, local amendments previously adopted are not automatically applicable to a new triennial State Code. Rather, they must be re-enacted with the required findings of local conditions, expressly made applicable to the new triennial State Code, and with an operative date no earlier than the effective date of the new State Code.

n:\egana\as2016\1600669\01131513.doc

BOARD of SUPERVISORS



City Hall
Dr. Carlton B. Goodlett Place, Room 244
San Francisco 94102-4689
Tel. No. 554-5184
Fax No. 554-5163
TDD/TTY No. 554-5227

October 6, 2016

Lisa Gibson
Acting Environmental Review Officer
Planning Department
1650 Mission Street, Ste. 400
San Francisco, CA 94103

Dear Ms. Gibson:

On September 6, 2016, Building Inspection Commission introduced the following proposed legislations:

File No. 160944

Ordinance repealing the 2013 Building Code in its entirety and enacting a 2016 Building Code consisting of the 2016 California Building Code and the 2016 California Residential Code, as amended by San Francisco; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing for an operative date of January 1, 2017; and directing the Clerk of the Board to forward the legislation to the California Building Standards Commission as required by State law.

File No. 160945

Ordinance adding the provisions of the 2016 California Residential Code with local amendments into various chapters of the 2016 San Francisco Building Code, and adding Chapter 36 to the Building Code to serve as a directory of where such provisions may be found; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing for an operative date of January 1, 2017; and directing the Clerk of the Board to forward the legislation to the California Building Standards Commission as required by State law.

File No. 160946

Ordinance repealing the 2013 Electrical Code in its entirety and enacting a 2016 Electrical Code consisting of the 2016 California Electrical Code as amended by San Francisco; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing an operative date of January 1, 2017; and directing the Clerk of the Board of Supervisors to forward the legislation to the California Building Standards Commission as required by State law.

File No. 160947

Ordinance enacting a 2016 San Francisco Existing Building Code consisting of the 2016 California Existing Building Code with San Francisco amendments; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing for an operative date of January 1, 2017; and directing the Clerk of the Board to forward the legislation to the California Building Standards Commission as required by State law.

File No. 160948

Ordinance repealing the 2013 Green Building Code in its entirety and enacting a 2016 Green Building Code consisting of the 2016 California Green Building Standards Code as amended by San Francisco; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing for an operative date of January 1, 2017; and directing the Clerk of the Board of Supervisors to forward the legislation to the California Building Standards Commission as required by State law.

File No. 160949

Ordinance repealing the 2013 Mechanical Code in its entirety and enacting a 2016 Mechanical Code consisting of the 2016 California Mechanical Code as amended by San Francisco; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing an operative date of January 1, 2017; and directing the Clerk of the Board of Supervisors to forward the legislation to the California Building Standards Commission as required by State law.

File No. 160950

Ordinance repealing the 2013 Plumbing Code in its entirety and enacting a 2016 Plumbing Code consisting of the 2016 California Plumbing Code as amended by San Francisco; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing an operative date of January 1, 2017; and directing the Clerk of the Board of Supervisors to forward the legislation to the California Building Standards Commission as required by State law.

This legislation is being transmitted to you for environmental review.

Angela Calvillo, Clerk of the Board

 By: Alisa Somera, Legislative Deputy Director
Land Use and Transportation Committee

Not defined as a project under CEQA Guidelines
Sections 15378 and 15060(c)(2) because they do not
result in a physical change in the environment.

Attachment

c: Joy Navarrete, Environmental Planning
Jeanie Poling, Environmental Planning

Joy
Navarrete

Digitally signed by Joy Navarrete
DN: cn=Joy Navarrete, o=Planning,
ou=Environmental Planning,
email=joy.navarrete@sfgov.org,
c=US
Date: 2016.10.20 15:03:12 -0700

Proposed 2016 San Francisco Building/Existing Building/Electrical/Plumbing/Mechanical/Green Building Code Amendment Correction List

| PROPOSED 2016 SAN FRANCISCO BUILDING CODE AMENDMENTS CORRECTIONS | |
|--|--|
| Section No. | Correction |
| 102A.3.1 | Duplicated text and section number have been deleted. |
| 202 | Story, First in Section 202 has been deleted. |
| 406.3 | Section number of 406.3 and a typo in the text have been corrected |
| 1012.2 | Exception number in Section 1012.2 has been corrected. |
| 1016.2 | Item number has been corrected. |
| 1207 | Section numbers in 1207 has been corrected. |
| | |
| Finding Table Section No. | Correction |
| 102A.4.1 | Section 102A.4.1 has been deleted in the Finding Table. |
| 102A.4.2 | Section 102A.4.2 has been deleted in the Finding Table. |
| 102A.7.1 | Section 102A.7.1 has been deleted in the Finding Table. |
| 102A.7.2 | Section 102A.7.2 has been deleted in the Finding Table. |
| 102A.7.3 | Section 102A.7.3 has been deleted in the Finding Table. |
| 102A.10 | Section 102A.10 has been deleted in the Finding Table. |
| 103A.5 | Section 103A.5 has been added to the Finding Table. |
| 106A.1.14 | Section 106A.1.14 has been added to the Finding Table. |
| 106A.3.1 | Section 106A.3.1 has been added to the Finding Table. |
| 1011.5.5.1 | Section 1011A.5.5.1 has been added to the Finding Table. |
| Chapter 11D | Chapter 11D has been added to the Finding Table. |
| 1207 | Section 1207 has been corrected in the Finding Table. |
| 1312A.1 | A typo in Section 1312A.1 has been corrected. |
| 1510.10 | Section 1510.10 has been corrected. |
| 1705.1.1 | Section 1705.1.1 has been added to the Finding Table. |
| | |
| PROPOSED 2016 SAN FRANCISCO EXISTING BUILDING CODE AMENDMENTS CORRECTIONS | |
| Section No. | Correction |
| 301.2.1 | The reference in this section has been corrected to Section 403. |
| 407.4.1 | Section 407.4.1 has been corrected. |
| | |
| Finding Table Section No. | Correction |
| 326.4.1 | Section 326.4.1 has been added to the Finding Table. |
| 326.4.2 | Section 326.4.2 has been added to the Finding Table. |
| 404D.2.1 | Section 404D.2.1 has been added to the Finding Table. |
| Table 4D-A | Table 4D-A has been added to the Finding Table. |

| | |
|---|--|
| Table 403E | Table 403E has been added to the Finding Table. |
| PROPOSED 2016 SAN FRANCISCO PLUMBING CODE AMENDMENTS CORRECTIONS | |
| Section No. | Correction |
| 1101.2.3 | The reference has been corrected to 1101.2.2 |
| Finding Table Section No. | |
| 603.3 | Section 603.3 has been added in the Finding Table. |
| PROPOSED 2016 SAN FRANCISCO ELECTRICAL CODE AMENDMENTS CORRECTIONS | |
| Section No. | Correction |
| 89.117. (A) | A parenthesis on the left side has been added. |
| 230.43 | Section 230.43 has been corrected by deleting the word “general” in the State language |
| 230.71 | Section 230.71 has been corrected by deleting the old San Francisco amendment. |
| 330.12 | Section 330.12 has been corrected by changing “Revise Item (1)” |
| 411.5 | A comma has been added in the text. |
| 700.16 | Change to “Revise the first paragraph of this section as follows”. |
| 760.46 | Editor’s Note has been deleted. |
| Finding Table Section No. | |
| 210.5(C)(1)(a) | Section 210.5(C)(1)(a) has been corrected in the Finding Table. |
| 215.12(C)(a) | Section 215.12(C)(a) has been corrected in the Finding Table. |
| 330.12 | Section 330.12 has been added in the Finding Table. |
| 355.10(A) | Section 355.10(A) has been corrected in the Finding Table. |
| PROPOSED 2016 SAN FRANCISCO MECHANICAL CODE AMENDMENTS CORRECTIONS | |
| Finding Table Section No. | Correction |
| 101.2 | Section 101.2 has been deleted in the Finding Table. |
| PROPOSED 2016 SAN FRANCISCO GREEN BUILDING CODE AMENDMENTS CORRECTIONS | |
| Section No. | Correction |
| Chapter 4 | The title of Chapter 4 has been corrected. |
| Chapter 5 | The title of Chapter 5 has been corrected. |
| Finding Table Section No. | |
| | |

| | |
|-----------|--|
| 4.201.1 | Section 4.201.1 in the Finding Table has been deleted. |
| 5.101.1 | Section 5.101.1 in the Finding Table has been deleted. |
| 5.201.1.2 | Section 5.201.1.2 has been added to the Finding Table. |

2016 San Francisco Plumbing Code Findings

| Section # | Finding # | Section # | Finding # |
|------------------|-----------|-----------|-----------|
| CHAPTER 1 | | 104.4.3 | 9 |
| 101.1 | 9 | 104.4.3.1 | 9 |
| 103.1 | 9 | 104.4.3.2 | 9 |
| 103.4 | 9 | 104.5 | 9 |
| 103.5 | 9 | 104.5.2 | 9 |
| 103.6 | 9 | 104.5.3 | 9 |
| 103.7 | 9 | 105.2.6 | 9 |
| 104.1 | 9 | 106.3 | 9 |
| 104.1.1 | 9 | 106.5 | 9 |
| 104.1.2 | 9 | 108.0 | 9 |
| 104.2 | 9 | 109.0 | 9 |
| 104.3 | 9 | 110.0 | 9 |
| 104.3.2 | 9 | 110.1 | 9 |
| 104.3.2.1 | 9 | 110.2 | 9 |
| 104.3.2.2 | 9 | 110.3 | 9 |
| 104.3.2.3 | 9 | 110.4 | 9 |
| 104.4 | 9 | | |

| Section # | Finding # | Section # | Finding # |
|------------------|-----------|--|-----------|
| CHAPTER 2 | | CHAPTER 3 | |
| 201.1 | 9 | 313.8 | 1 |
| 204.0 | 9 | 313.8.1 | 1 |
| 208.0 | 9 | 313.8.2 | 1 |
| 216.0 | 9 | | |
| 218.0 | 9 | | |
| 221.0 | 9 | | |
| CHAPTER 4 | | CHAPTER 5 | |
| 405.4 | 7,10 | 504.1 | 4, 9 |
| 415.2.1 | 13 | | |
| CHAPTER 6 | | CHAPTER 7 | |
| 603.1 | 4 | 701.2(2)(a). | 5,10 |
| 603.3 | 9 | 701.2(3) | 1 |
| 603.5.6.4 | 9 | 701.2(7) | 5 |
| 604.1 | 5 | 706.4 | 5,7 |
| 606.2 | 4 | 710.1.1 | 5,7 |
| 606.3 | 4 | | |
| 606.3.1 | 4, 9 | CHAPTER 8 No San Francisco Amendments | |
| 606.5 | 4 | CHAPTER 9 | |
| 606.8 | 5,7 | 901.2 | 5,7 |
| 609.10.2 | 4 | 907.1 | 2,4,14,16 |
| | | | |

160950

| | | | |
|----------|-----|-------|-----------|
| 609.10.3 | 4,9 | 907.3 | 2,4,14,16 |
|----------|-----|-------|-----------|

| Section # | Finding # | Section # | Finding # |
|--|-----------|--|-----------|
| CHAPTER 10 | | | |
| 1008.1 | 4,7 | | |
| 1016.3.1 | 4,7 | | |
| CHAPTER 11 | | CHAPTER 12 | |
| 1101.2.1 | 12,13,15 | 1208.5.1.1 | 16 |
| 1101.2.2 | 12,13,15 | CHAPTER 13 No San Francisco Amendments | |
| 1101.2.3 | 12,13,15 | CHAPTER 14 No San Francisco Amendments | |
| CHAPTER 15 No San Francisco Amendments | | CHAPTER 16 & 16A No San Francisco Amendments | |
| CHAPTER 17 No San Francisco Amendments | | Appendix A, B, D, H, I, J No San Francisco Amendments | |

PROPOSED SAN FRANCISCO PLUMBING CODE AMENDMENTS 2016 Edition

CHAPTER 1 ADMINISTRATION

DIVISION I CALIFORNIA ADMINISTRATION

No San Francisco Plumbing Code Amendments.

DIVISION II ADMINISTRATION

SECTION 101.0 – GENERAL

101.1 Revise this section as follows:

101.1 Title. This document shall be known as the “Uniform 2016 San Francisco Plumbing Code,” may be cited as such, and will be referred to herein as “this code.”

SECTION 103.0 – DUTIES AND POWERS OF THE AUTHORITY HAVING JURISDICTION

103.1 Replace the third paragraph with the followings:

~~The Authority Having Jurisdiction shall be permitted to request the assistance and cooperation of other officials of this jurisdiction so far as required in the discharge of the duties in accordance with this code or other pertinent law or ordinance.~~

The Authority Having Jurisdiction, when necessary, may call upon the Police Department and other City and County of San Francisco agencies for aid or assistance in carrying out or enforcing any of the provisions of this code.

103.4 Revise the first paragraph of this section as follows:

103.4 Right of Entry. Where it is necessary to make an inspection to enforce the provisions of this code or other codes or ordinances, or where the Authority Having Jurisdiction has reasonable cause to believe that there exists in a building or upon a premises a condition or violation of this code or other codes or ordinances that makes the building or premises unsafe, insanitary, dangerous or hazardous, the Authority Having Jurisdiction shall be permitted to enter the building or premises at reasonable times to inspect or to perform the duties imposed upon the Authority Having Jurisdiction by this code or other codes or ordinances, provided that where such building or premises is occupied, the Authority Having Jurisdiction shall present credentials to the occupant and request entry. Where such building or premises is unoccupied, the Authority Having Jurisdiction shall first make a reasonable effort to locate the owner or other person having charge or control of the building or premises and request entry. Where entry is refused, the Authority Having Jurisdiction has recourse to every remedy provided by law to secure entry.

103.5 Add the following section:

103.5 Rules and Regulations. The Authority Having Jurisdiction shall have the power to render interpretations of this code and to adopt and enforce rules and supplemental regulations to clarify the application of its provisions. Such interpretations, rules and regulations shall be in conformance with the intent and purpose of this code. Such rules and regulations, commonly referred to as "Code Rulings" and "Administrative Bulletins" supplemental to this code, shall not take effect until approved by the Building Inspection Commission and signed by the Authority Having Jurisdiction except in unusual circumstances where the Authority Having Jurisdiction has determined that there is an immediate need to protect the public health and safety. When the Authority Having Jurisdiction finds that such circumstances exist, the Authority Having Jurisdiction may order immediate enforcement of a particular rule or regulation. The Authority Having Jurisdiction shall arrange for a subscription service to such rules and regulations, the entire cost of which is to be borne by the subscribers.

103.6 Add the following section:

103.6 Code Revisions. The Authority Having Jurisdiction shall transmit to the Building Inspection Commission, at intervals not exceeding three years, recommendations for changes to this code, based on studies of the following:

1. Requests of the Board of Examiners for variances from this code, and for approvals of alternate materials, alternate designs and methods of construction.
2. Code changes recommended by the Board of Examiners.
3. Code changes recommended by the Code Advisory Committee or other bodies subordinate to the Building Inspection Commission.
4. Results obtained and problems encountered in legal actions taken to correct code violations.
5. Changes or improvements in materials, methods of construction or design, and changes proposed by interested persons.
6. Investigations of fire and structural damage to buildings, and of determination of unsatisfactory building performance.

7. Periodic changes to the California Plumbing Code and other State regulations which may affect this code.

8. Administrative Bulletins and Code Rulings currently in effect.

9. Violations of the code found on inspections or investigations.

103.7 Add the following section:

103.7 Modifications. When there are practical difficulties involved in carrying out the provisions of this code, the Authority Having Jurisdiction may grant modifications for individual cases. The Authority Having Jurisdiction shall first find that a special individual reason makes the strict letter of this code impractical and that the modification is in conformance with the intent and purpose of this code and that such modification does not lessen the standard of this code to safeguard life or limb, health, property, or public welfare. The details of any action granting modifications shall be recorded and entered in the files of the Department of Building Inspection.

SECTION 104.0 – PERMITS

104.1 Add the following as the second paragraph of this section:

Emergency work for the protection of life or limb, health, property and public welfare shall have a permit obtained within one day of commencing such work, excluding Saturdays, Sundays and legal holidays.

104.1.1 Add the following section:

104.1.1 Homeowner's Permit. A permit for plumbing work in, on or about a single-family dwelling may be issued by the Authority Having Jurisdiction, provided said work is done by the owner or a family member who has demonstrated, to the satisfaction of the administrative authority, his or her qualifications to satisfactorily perform the plumbing work in the dwelling which is, or is intended to be, occupied by the owner. If the plumbing work performed under the homeowner's permit does not comply with the requirements of this code and if the corrections are not made as required by the Department of Building Inspection, then the work shall be corrected by a State-licensed plumbing contractor under a separate permit.

Such State-licensed plumbing contractor shall be required to pay only the permit issuance fee as set forth in Section 110A, Table 1A-C – Plumbing/Mechanical Permit Issuance and Inspection Fees - of the Building Code. If additional inspection is required, the appropriate fees as set forth in Section 110A, Table 1A-C - Plumbing/Mechanical Permit Issuance and Inspection Fees and Table 1A-G - Inspection, Surveys and Reports - of the Building Code shall apply.

104.1.2 Add the following section:

104.1.2 Amending Applications. After a permit has been issued and an inspection of the work has been made, the scope of the permit may be altered by filing an amended permit application and paying fees for any additional work as set forth in Table 1A-C - Plumbing/Mechanical Permit Issuance and Inspection Fees and Table 1A-G - Inspections, Survey, and Reports of Section 110A of the Building Code.

104.2 Replace Section 104.2(1) and the first paragraph of Section 104.2(2) as follows:

104.2 Exempt Work. A permit shall not be required for the following:

- (1) Repair of leaks not requiring cutting into or removing piping.
- (2) Unstopping of traps, sewers, vents or waste pipes not requiring cutting into or removal of traps or piping.
- (3) Replacement, repair or maintenance of faucets, valves angle stops, hose bibbs or roof drain not requiring cutting into or removal of piping.
- (4) Replacement of toilets except in structures with alternate water piping.
- (5) Replacement of furnace filters.
- (6) Removal of drainage, water or gas piping from a building when the water supply, gas and drainage lines have been disconnected in an approved manner under a permit.
- (7) Work involved in setting up for display of plumbing fixtures or appliances, when not connected to any supply or drainage lines, in a sales establishment.
- (8) Replacement of water conservation devices not requiring cutting into or removal of piping.
- (9) Work performed in buildings or structures owned and occupied by the State and Federal governments.

104.3 Replace this section as follows:

104.3 Application for Permit. ~~To obtain a permit, the applicant shall first file an application therefore in writing on a form furnished by the Authority Having Jurisdiction for that purpose.~~

...

Permit applicants shall file with the Department of Building Inspection an application on a form furnished for that purpose.

A permit for inspection of the proposed plumbing work set forth in the application will be issued to State-licensed contractors or to homeowners subject to the requirements of Section ~~103.1.3~~ **104.1.1**. A separate permit shall be obtained for each separate building, structure or property.

104.3.2 Replace the following section:

104.3.2 Plan Review fees. ~~Where a plan or other data is required to be submitted in accordance with Section 104.3.1, a plan review fee shall be paid at the time of submitting construction documents for review.~~

...

104.3.2 Inspections Not Covered by Permit Fees.

104.3.2.1 Off Hours of Inspection. Off-hour inspection may be performed outside normal inspection hours by prior arrangement and prepayment of fees as set forth in Section 110A, Table 1A-G - Inspections, Surveys and Reports - of the Building Code.

104.3.2.2 Reinspections. A reinspection fee shall be assessed for each inspection or reinspection made necessary by any of the following conditions:

- (1) When the portion of the work for which the inspection is requested is not complete or code complying.
- (2) When previously identified deficiencies in the work are not properly corrected.
- (3) When the approved construction documents are not available to the inspector.
- (4) When access is not provided on the date and time of the inspection appointment.
- (5) When work deviates from the approved construction documents.

The first reinspection for failure to comply with code requirements shall not be assessed a reinspection fee. All subsequent reinspections for the same or subsequent errors or omissions shall be charged a reinspection fee.

Subsequent to inspector determination of reinspection fee requirements, no required or requested inspections shall be made nor shall the job be given a certificate of final completion and occupancy or final approval until the required reinspection fees are paid. See Section 110A, Table 1A-G - Inspections, Surveys and Reports - of the Building Code for applicable fees.

104.3.2.3 Survey. A plumbing survey may be requested when a plumbing inspector's assistance is desired to establish code compliance of existing or proposed plumbing system requirements. See Section 110A, Table 1A-G - Inspections, Survey and Reports - of the Building Code for applicable fees.

104.4 Add a new second paragraph to this section as follows:

An issued permit entitles the permittee to proceed with the work described therein. The issuance of a permit does not constitute approval of any work done under that permit. Permits shall not be transferable.

104.4.3 Replace this section as follows:

104.4.3 Permit Expiration. A permit issued by the Authority Having Jurisdiction under the provisions of this code shall expire by limitation and become null and void where the work authorized by such permit is not commenced within 180 days from the date of such permit, ... Plumbing permits expire per Section 106A.4.4 of the San Francisco Building Code. Permit fees may be partially refunded if a written cancellation request is made to the Building Official prior to commencement of the

permitted work and within 90 days of the date of permit issuance. See Section 110A, Table 1A-R - Refunds - of the Building Code for refunds.

104.4.3.1 Add the following new section:

104.4.3.1 Commencement of Work on Permit Expired Due to Work Not Started. A new permit shall be obtained to undertake the work described on an expired permit on which no work was performed. If not more than one year has elapsed since the expiration of the original permit, the applicant is eligible for reduced fees. See Section 110A, Table 1A- B – Other Building Permit and Plan Review Fees - of the Building Code for applicable fees.

If a refund has been granted per Section ~~103.3.3~~ **104.4.3**, the applicant shall not be eligible for the reduced fees as set forth in Section 110A, Table 1A-B – Other Building Permit and Plan Review Fees - of the Building Code.

104.4.3.2 Add the following new section:

104.4.3.2 Recommencement of Work on Permit Expired Due to Work Not Completed. The applicant shall obtain a new permit for the work not completed. The permit fee shall be based on work remaining to be done. Fees shall be as set forth in Section 110A, Table 1A-C – Plumbing/Mechanical Permit Issuance and Inspection Fees - of the Building Code.

104.5 Replace this section as follows:

104.5 Permit Fees. ~~Fees shall be assessed in accordance with the provisions of this section and as set forth in the fee schedule, Table 104.5. The fees are to be determined and adopted by this jurisdiction.~~ Before any permit is issued, the applicant shall pay to the Central Permit Bureau the fees as set forth in Section 110A, Table 1A-C – Plumbing/Mechanical Permit Issuance and Inspection Fees - of the Building Code. The replacement of a plumbing fixture or a gas appliance without a change in drainage, piping or venting shall not require the payment of permit issuance fee. A separate permit issuance fee shall be paid for each class of work, i.e., sewers and drainage, gas and water.

Final inspection will not be made unless all outstanding fees related to the permit work have been paid.

104.5.2 Revise this section as follows:

104.5.2 Investigation Fees. An investigation fee, in addition to the permit fee, shall be collected whether or not a permit is then or subsequently issued. See Section 110A, Table 1A-C – Plumbing/Mechanical Permit Issuance and Inspection Fees, and Table 1A-K - Penalties, Hearings, Code Enforcement Assessments- of the Building Code for applicable fees. ~~The investigation fee shall be equal to the amount of the permit fee that is required by this code if a permit were to be issued. The payment of such investigation fee shall not exempt a person from compliance with other provisions of this code, nor from a penalty prescribed by law.~~

The Director may reduce the investigation fee to two times the amount of the permit fee as called for in Section 110A, Table 1A-C - Plumbing/Mechanical Permit Issuance and Inspection Fees - of the Building Code for work that was constructed prior to the current building ownership or for work without permit which was done prior to January 1, 1967, if the owner files with the Director a notarized affidavit together with documents substantiating such dates of work.

Appeals of investigation fees may be filed with the Board of Appeals in the manner provided in Part III of the San Francisco Municipal Code. Such filing shall be subject to the fees and rules of the Board of Appeals. The Board of Appeals, in reviewing the appeal, may reduce the appealed amount to not less than two times the permit fee as set forth in Section 110A, Table 1A-C-Plumbing/Mechanical Permit Issuance and Inspection Fees - of the Building Code.

104.5.3 Replace this section as follows:

104.5.3 Fee Refunds. ~~The Authority Having Jurisdiction shall be permitted to authorize the refunding of a fee as follows:~~

- ~~(1) The amount paid hereunder that was erroneously paid or collected.~~
- ~~(2) Refunding of not more than a percentage, as determined by this jurisdiction where no work has been done under a permit issued in accordance with this code.~~

~~The Authority Having Jurisdiction shall not authorize the refunding of a fee paid except upon written application filed by the original permittees not to exceed 180 days after the date of fee payment.~~

For fee refunds, see Section 107A.6 of the Building Code.

SECTION 105.0 – INSPECTIONS AND TESTING

105.2.6 Revise the fourth paragraph as follows:

To obtain reinspection, the applicant shall file an application therefore in writing upon a form furnished for that purpose and pay the reinspection fee in accordance with ~~Table 104.5-~~ **Section 110A, Table 1A-G - Inspections, Surveys and Reports - of the Building Code.**

SECTION 106.0 – VIOLATIONS AND PENALTIES

106.3 Replace this section as follows:

106.3 Penalties. ~~A person, firm, or corporation violating a provision of this code shall be deemed guilty of a misdemeanor, and upon conviction thereof, shall be punishable by a fine, imprisonment, or both set forth by the governing laws of the jurisdiction. Each separate day or portion thereof, during which a violation of this code occurs or continues, shall be deemed to constitute a separate offense.~~ Any person, the owner or the owner's authorized agent, who violates, disobeys, omits, neglects or refuses to comply with, or resists or opposes the execution of any of the provisions of this code, shall be liable for a civil penalty, not to exceed \$500 for each day such violation is committed or permitted to continue, which penalty shall be assessed and recovered in a civil action brought in the name of the people of the City and County of San Francisco by the City Attorney in any court of competent jurisdiction. Any penalty assessed and recovered in an action brought pursuant to this paragraph shall be paid to the City Treasurer and credited to the Department of Building Inspection's Special Fund.

Any person, the owner or the owner's authorized agent, who violates, disobeys, omits, neglects or refuses to comply with, or who resists or opposes the execution of any of the provisions of this

code, shall be guilty of a misdemeanor, and upon conviction thereof shall be punished by a fine not exceeding \$500 or by imprisonment not exceeding six months, or by both such fine and imprisonment, unless otherwise provided in this code, and shall be deemed guilty of a separate offense for every day such violation, disobedience, omission, neglect or refusal shall continue. Any person who shall do any work in violation of any of the provisions of this code, and any person having charge of such work who shall permit it to be done, shall be liable for the penalty provided.

It shall be unlawful for any person to interfere with the posting of any notice provided for in this code or to tear down or mutilate any such notice posted by the Department of Building Inspection.

106.5 Revise this section as follows:

106.5 Authority to Disconnect Utilities in Emergencies. The Authority Having Jurisdiction shall have the authority to disconnect a plumbing system to a building, structure or equipment regulated by this code in case of emergency where necessary to eliminate an immediate hazard to life or property. For notification procedures, see Section 102A.16 of the Building Code.

SECTION 108.0 – ABATEMENT OF PUBLIC NUISANCE

108.0 Add the following section:

108.0 Abatement of Public Nuisance. In order to abate a nuisance as defined in Section 216.0 of this code, the inspection and abatement procedures as set forth in Section 102A of the Building Code, including, but not limited to, Section 102A.3 through 102A.8, shall apply.

(Amended by Ord. 60-16, File No. 151085, App. 4/27/2016, Eff. 5/27/2016, Oper. 6/1/2016)

SECTION 109.0 – BOARD OF EXAMINERS

109.0 Add the following section:

109.0 Board of Examiners. Application may be made to the Board of Examiners for approval of alternate materials, methods and types of construction and for variances from the provisions of this code. See Building Code, Section 105A.1.

SECTION 110.0 – REPAIRS TO DEFECTIVE BUILDING SEWERS

110.0 Add the following section:

110.0 Repairs to Defective Building Sewers

110.1 General. Any defective building sewer found to be a nuisance or hazardous to the public shall be repaired at the owner's expense by a licensed plumbing contractor in accordance with this code. In the event the owner fails to repair the defective building sewer after written notice has been sent the owner by the Authority Having Jurisdiction, the Authority Having Jurisdiction shall abate the condition in accordance with Section 102A of the Building Code.

110.2 Cost of Repairs by City and County of San Francisco. Whenever the Authority Having Jurisdiction, pursuant to the authority conferred by this code and the Building Code, shall cause a building sewer to be repaired or replaced, the cost thereof shall be paid from the "Plumbing Building Sewer Revolving Fund" and assessed against the property served by said building sewer.

110.3 Plumbing Building Sewer Revolving Fund. A special revolving fund, to be known as the "Plumbing Building Sewer Revolving Fund," is hereby created for the purpose of defraying the costs and expenses which may be incurred by the Department of Building Inspection in carrying out the authority conferred by this code to repair or replace defective building sewers.

The Board of Supervisors shall transfer one half of the funds appropriated to the "Side Sewer Repair" fund of the Department of Building Inspection or shall appropriate, establish or increase the special revolving fund with such funds as it may deem necessary in order to expedite performance of the work of repairing or replacing defective building sewers. The special revolving fund shall be replenished with all funds collected under the proceeding hereinafter provided for, either upon voluntary payments or as a result of the sale of the property after delinquency, or otherwise. Balances remaining in the Plumbing Building Sewer Revolving Fund at the close of any fiscal year shall be carried forward in such fund.

110.4 Assessment for Costs. The Authority Having Jurisdiction shall take action to have the costs of all work done or caused to be done pursuant to this section assessed against the parcel or parcels of land upon which said building is served by the building sewer per Section 102A of the Building Code. Such costs shall include, in addition to all costs related to repairing or replacing the building sewer or demolishing and clearing the site, the City and County of San Francisco's costs in administering the required work. See Section 110A, Table 1A-K - Penalties, Hearings, Code Enforcement Assessments - of the Building Code for the applicable fee.

CHAPTER 2

DEFINITIONS

SECTION 201.0 – GENERAL

201.1 Add the following to the end of the first sentence:

Where words, terms and phrases are not defined, they shall have their ordinary accepted meaning within the context with which they are used.

SECTION 204.0 – B

204.0 Add the following definition:

Boiler - A closed vessel used for heating water or liquid, or for generating steam or vapor by direct application of heat from combustible fuels or electricity.

SECTION 208.0 – F

208.0 Add the following definition:

Foot Vent - See "Relief Vent," Section 220.0.

SECTION 216.0 – N

216.0 *Add the following items after Item (3) under definition of "Nuisance":*

- (4) Open, unsecured, leaking, plugged or otherwise defective sewer, gas or water lines.
- (5) Inadequate plumbing system maintenance, dilapidation, obsolescence, or damage.
- (6) Plumbing or plumbing fixtures, gas appliances or piping installed in violation of this code or without permit.
- (7) Where a change in occupancy classification is made without complying with the applicable provisions of this code and the Building Code.

SECTION 218.0 – P

218.0 *Revise this definition as follows:*

Plumbing System. Includes all potable water, building supply, and distribution pipes; all plumbing fixtures and traps; all drainage and vent pipes; and all building drains and building sewers, including their respective joints and connections, devices, receptors, and appurtenances within the property lines of the premises and shall include potable water piping, potable water treating or using equipment, medical gas and medical vacuum systems, liquid and fuel gas piping, and water heaters and vents for same, and fire sprinkler systems. Plumbing systems shall include all plumbing appliances, plumbing appurtenances and plumbing fixtures.

SECTION 221.0 – S

221.0 *Add the following definition:*

Story - That portion of a building included between the upper surface of any floor and the upper surface of the floor next above. For the purposes of this code, balcony, loft and mezzanine levels that contain plumbing outlets are also to be considered as stories.

CHAPTER 3

GENERAL REGULATIONS

SECTION 313.0 – HANGERS AND SUPPORTS

313.8 *Add the following section:*

313.8 Materials

313.8.1 Plumber's tape hanger iron may be used to secure pipe not greater than 2 inches (50.8 mm) in diameter.

313.8.2 Hanger iron shall be galvanized and not thinner than 22 gauge, 1/32-inch thick (0.8 mm) and 3/4-inch (19.05 mm) wide, securely nailed or screwed to the structure. When the strap-iron is formed around the pipe, it shall be secured with a 1/4-inch (6.35 mm) stove bolt.

CHAPTER 4

PLUMBING FIXTURES AND FIXTURE FITTINGS

SECTION 405 – PROHIBITED FIXTURES

405.0 *Add the following section:*

405.4 **Watercloset-Sink Combinations.** Watercloset-Sink combinations are not allowed in structures with treated alternate water piping.

SECTION 415.0 – DRINKING FOUNTAINS

415.2 *Add the section as follows:*

415.2.1 Drink Tap Stations. For new construction that provides one or more drinking fountains shall provide a Drink Tap Station per San Francisco Environment Code Section 2304.

CHAPTER 5

WATER HEATERS

SECTION 504.0 – WATER HEATER REQUIREMENTS

504.1 *Add a first paragraph to the section:*

504.1 Location. Water Heaters mounted on the exterior of a building and located 7' or more above the floor or grade shall be provided with a permanent platform capable of supporting a tester or maintenance person.

CHAPTER 6

WATER SUPPLY AND DISTRIBUTION

SECTION 603.0 – CROSS-CONNECTION CONTROL

603.1 Add a new third paragraph to this section as follows:

Structures with alternate water piping shall have a Reduced-Pressure Principle Backflow Prevention Assembly installed on the domestic supply as close as practical to the meter.

603.3 Add a new second paragraph to this section as follows:

Refer to SFPUC's Rules & Regs Section "A and/or G Cross connection Control", Table 1 and Table 603.2 of the CPC. The more stringent shall apply.

603.5.6.4 Add the following section:

603.5.6.4 All such installations shall be approved in writing by the San Francisco Water Department prior to installation.

SECTION 604.0 – MATERIALS

604.1 Add the following sentence to the end of the second paragraph:

Connections between copper water piping and ferrous materials shall be made with dielectric or insulated fittings or brass nipples of 6 inches (152.4 mm) minimum length.

SECTION 606.0 – VALVES

606.2 Revise this section as follows:

606.2 Fullway valve. A fullway valve controlling outlets shall be installed on the discharge side of each water meter and on each unmetered water supply as near as possible to the point after where the water supply enters the building and before the first fitting or branch line. Water piping supplying more than one building on one premises shall be equipped with a separate fullway valve to each building, so arranged that the water supply can be turned on or off to any individual or separate building provided; however, that supply piping to a single-family residence and building accessory thereto shall be permitted to be controlled on one valve. Such shutoff valves shall be accessible. A fullway valve shall be installed on the discharge piping from water supply tanks at or near the tank. A fullway valve shall be installed on the cold water supply pipe to each water heater at or near the water heater. In cases where one water heater or boiler supplies hot water to multiple units additional fullway valves will be installed so that the hot water supplies to any apartment / unit / dwelling or condominium can be shut off without interrupting the hot water supply to any other apartment / unit / dwelling or condominium. These valves shall be accessible in the dwelling unit they control or other common area within the building.

606.3 Revise this section as follows:

606.3 Multidwelling Units. In multidwelling units, one or more shutoff valves shall be provided in each dwelling unit so that the hot and cold water supply supplies to a plumbing fixture or group of fixtures in that dwelling unit any apartment / unit / dwelling or condominium can be shut off without stopping interrupting the water supply to fixtures in another dwelling units apartment / unit / dwelling or

condominium. These valves shall be accessible in the dwelling unit they control or other common area within the building.

606.3.1 Add the following section:

606.3.1 Any apartment / unit / dwelling or condominium where a remodel is performed shall meet the requirements of sections 606.2, 606.3 and 606.5.

606.5 Revise this section as follows:

606.5 Control Valve. A control valve shall be installed immediately ahead of each plumbing fixture hot and cold water supply and water supplied appliances and immediately ahead of each slip joint or appliance supply to permit servicing and replacement of individual fixtures.

606.8 Add the following section:

606.8 All buildings four stories or more in height or water supply greater than 40 feet above the water meter shall have an approved backflow assembly installed as near as possible to the water meter and before the first fitting or branch line. The backflow assembly installed shall be in accordance to the degree of hazard within the building, but in no case less than an approved double check assembly. See Table 603.2.

SECTION 609.0 – INSTALLATION, TESTING, UNIONS AND LOCATION

609.10.2 Add the following section:

609.10.2 Air Chambers. Air chambers shall be installed on all hot and cold water outlets supplying quick-acting valves to provide water hammer relief. The size of each air chamber shall be 24 times the diameter of the fixture supply.

609.10.3 Add the following section:

609.10.3 Quick-Acting Valves. The following valves shall be considered quick-acting: flushometers, single-handle faucets, single-handle tub and tub/shower combination control valves, single-handle shower control valves, rapid response electric solenoid valves (such as used on ice-makers, clothes washers, etc.) and any other appliance or fixture that dispenses water in a quick open and close method in its operation.

CHAPTER 7

SANITARY DRAINAGE

PART I – DRAINAGE SYSTEMS

SECTION 701.0 – GENERAL

701.2(2)(a) Revise this section as follows:

701.2(2)(a) ~~(HCD 1 & HCD 2)~~ ABS and PVC installations are limited to not more than two stories of commercial or private areas of residential accommodations.

701.2(3) *Revise this section as follows:*

701.2(3) No vitrified clay pipe or fittings shall be used above-ground or where pressurized by a pump or ejector or **underground within the foundation line of the building**. They shall be kept not less than 12 inches (305 mm) belowground.

701.2(7) *Add the following section:*

701.2(7) Copper tubing shall not be used for urinal drainage or applications which are detrimental to the integrity of copper tubing.

SECTION 706.0 – CHANGES IN DIRECTION OF DRAINAGE FLOW

706.4 *Revise this section as follows:*

706.4 Vertical drainage lines connecting with horizontal drainage lines shall enter through 45 degree (0.79 rad) wye branches, combination wye and one-eighth bend branches, or other approved fittings of equivalent sweep. Branches or offsets of 60 degrees (1.05 rad) shall be permitted to be used where installed in a true vertical position. **In buildings more than three stories in height, any fixture within 10 feet (304 mm) of the connection of the vertical to horizontal change shall enter the horizontal drainage line at least 10 feet (304 mm) downstream from the change or may connect into the next vertical downstream line.**

SECTION 710.0 – DRAINAGE OF FIXTURES LOCATED BELOW THE NEXT UPSTREAM MANHOLE OR BELOW THE MAIN SEWER LEVEL

710.1.1 *Add the following section:*

710.1.1 **Drainage of Fixtures Located Below the Fresh Air Inlet.** Where a fixture is installed with the flood rim level equal to or lower than the elevation of the fresh air inlet serving the house trap, the piping serving the fixture shall be protected by installing an approved type of backwater valve. Where a fixture is installed with the flood rim level higher than the elevation of the fresh air inlet serving the house trap, the fixture shall not discharge through such backwater valve.

CHAPTER 8 INDIRECT WASTES

No San Francisco Plumbing Code Amendments.

CHAPTER 9 VENTS

SECTION 901.0 – GENERAL

901.2. Add second paragraph to this section as follows:

No mechanical device shall be installed in any venting system. Such venting system shall remain unobstructed to an approved termination.

SECTION 907.0 – VENT STACKS AND RELIEF VENTS

907.1 Revise this section as follows:

907.1 Drainage Stack. Each drainage stack that extends ~~10-~~**six (6)** or more stories shall be served by a parallel vent stack, which shall extend undiminished in size from its upper terminal and connect to the drainage stack at or immediately below the lowest fixture drain. ~~Each such vent stack shall also be connected to the drainage stack at each fifth floor, counting down from the uppermost fixture drain, by means of a yoke vent, the size of which shall be not less in diameter than either the drainage or the vent stack, whichever is smaller.~~

907.3 Add the following section:

907.3 Vent Stacks and Relief Vents. Every building in which plumbing is installed shall have at least one main stack which shall run undiminished in size and as directly as possible from each building drain serving said building through to the open air above the roof.

For the purposes of this section, the main stack shall be defined as the largest size stack that is connected to a building drain or sewer.

A vent stack shall be installed with a soil or waste stack whenever relief vents or other branch vents are required in two or more branch intervals. A vent stack shall be installed in accordance with Section 706.1.

The size of the soil stack shall be determined by the total fixture units on that stack as per Table 703.2.

CHAPTER 10

TRAPS AND INTERCEPTORS

SECTION 1008.0 – BUILDING TRAPS

1008.1 Revise this section as follows:

1008.1 General

Building traps shall not be installed except where required by the Authority Having Jurisdiction. Each building trap where installed shall be provided with a cleanout and with a relieving vent or fresh-air intake on the inlet side of the trap, which need not be larger than one-half the diameter of the drain to-

which it connects. ~~Such relieving vent or fresh air intake shall be carried above grade and terminate in a screened outlet located outside the building.~~ Such trap shall have a fresh air inlet of not less than 4 inch (101.6 mm) diameter pipe. The inlet shall be covered by an approved perforated plate not less than 16 square inches (102323.mm²). Perforations shall be not more than 3/8 inch (9.6 mm) diameter and provide an aggregate open area of not less than one-half the cross-sectional area of the sewer trap. The air inlet shall be connected to the building side of the trap and shall lead to the open air, terminating at a point not less than 10 feet (3.05 m) from any window or door.

SECTION 1016.0 – SAND INTERCEPTORS

1016.3.1 Add the following section:

1016.3.1 When drains are provided for planter boxes, such drains shall enter into the sanitary or storm drainage plumbing system by discharging into an approved sump, receiving tank or sand settling tank. No trap shall be installed between the planter box and any approved receptor. Sizes of drains shall conform to Table 703.2.

Catch basins or sumps to drain surface water or collect subsoil drainage shall meet the following requirements:

- (1) The catch basin or sump shall be poured in place, and all sides and bottom shall be watertight.
- (2) A removable metal grill approved for applied design loads shall be placed on top with a screen to prevent mosquito breeding.
- (3) Each catch basin shall be served with its own trap and cleanout, and shall connect to the storm or sanitary system independently.
- (4) If inlet is located below the building sewer or drain, a sump pump minimum of 1-1/2" (38.1 mm) outlet may be used. The bottom of sump shall maintain a 1'- 0" (304.8 mm) distance from the inlet, creating a 1' - 0" (304.8 mm) sand trap.
- (5) If the depth of the sump is over 5' - 0" (1.52 m) a larger catch basin shall be required with a permanent ladder securely bolted to the interior to provide access for maintenance. A minimum clear space of 30" × 30" (762 mm × 762 mm) shall be provided.
- (6) A listed and approved plastic catch basin may be installed in areas of residential buildings that are not subjected to any vehicular traffic and shall be installed on a concrete base to prevent settling, provided all other code requirements of this section and the listing and installation requirements of such catch basin are met.

CHAPTER 11

STORM DRAINAGE

SECTION 1101.0 – GENERAL

1101.2.1 Add the following section:

1101.2.1 Leaders, Connection to Drain. All storm water or casual water from roof areas, balconies, lightwells, courtyards or similar areas which total more than 200 square feet (18.4 square meters) aggregate shall drain or be conveyed directly to the building drain, or building sewer, or to an approved alternate location based on approved geotechnical and engineering designs. Such drainage shall not be directed to flow onto adjacent property or over public way, including sidewalks. The opening of the leader shall meet the same requirements as Section 1103.0 of the California Plumbing Code.

1101.2.2 Add the following section:

1101.2.2 Temporary Provisions. When the stormwater sewer is not yet installed, the building stormwater drainage system may discharge into the sewer on the street side of the main trap as near to the curbline as possible.

1101.2.3 Add the following section:

1101.2.3 Temporary Provisions Drain Trap. When, under the provisions of Section 1101.2.2 the building stormwater drainage system discharges to the sewer, a trap shall be placed in that drain at a point near where it branches into the sewer. The trap shall be supplied with clean water by an approved means such as a hose bibb or trap primer.

CHAPTER 12 FUEL GAS PIPING

SECTION 1208.0 – GAS PIPING SYSTEM DESIGN, MATERIALS, AND COMPONENTS

1208.5.1.1 Add a second paragraph as follows:

Gas piping in exterior locations, except as otherwise regulated by this code, shall be of galvanized iron or steel, with galvanized fittings.

CHAPTER 13 HEALTH CARE FACILITIES AND MEDICAL GAS AND VACUUM SYSTEMS

No San Francisco Plumbing Code Amendments.

CHAPTER 14 FIRESTOP PROTECTION

No San Francisco Plumbing Code Amendments.

CHAPTER 15

ALTERNATE WATER SOURCES FOR NONPOTABLE APPLICATIONS

No San Francisco Plumbing Code Amendments.

CHAPTER 16

NONPOTABLE RAINWATER CATCHMENT SYSTEMS

No San Francisco Plumbing Code Amendments.

CHAPTER 17

REFERENCED STANDARDS

No San Francisco Plumbing Code Amendments.

Appendix A

RECOMMENDED RULES FOR SIZING THE WATER SUPPLY SYSTEM

No San Francisco Plumbing Code Amendments.

Appendix B

EXPLANATORY NOTES ON COMBINATION WASTE AND VENT SYSTEMS

No San Francisco Plumbing Code Amendments.

Appendix D

SIZING STORMWATER DRAINAGE SYSTEMS

No San Francisco Plumbing Code Amendments.

Appendix H

PRIVATE SEWAGE DISPOSAL SYSTEMS

No San Francisco Plumbing Code Amendments.

Appendix I


INSTALLATION STANDARD

No San Francisco Plumbing Code Amendments.

Appendix J

COMBINATION OF INDOOR AND OUTDOOR COMBUSTION AND VENTILATION OPENING DESIGN

No San Francisco Plumbing Code Amendments.



BUILDING INSPECTION COMMISSION (BIC)

Department of Building Inspection
1660 Mission Street, San Francisco, California 94103-2414

Voice (415) 558-6164 - Fax (415) 558-6509

August 26, 2016

Edwin M. Lee
Mayor

COMMISSION

Angus McCarthy
President

Myrna Melgar
Vice-President

Kevin Clinch
Gail Gilman
John Konstin
Frank Lee
Debra Walker

Ms. Angela Calvillo
Clerk of the Board
Board of Supervisors, City Hall
1 Dr. Carlton B. Goodlett Place, Room 244
San Francisco, CA 94102-4694

RE: Code amendments to the 2016 California Building Standards Code, including the Building, Existing Building, Residential, Mechanical, Plumbing, Electrical, and Green Building Codes and recommend approval to the Board of Supervisors.

Sonya Harris
Secretary

Dear Ms. Calvillo:

Tom C. Hui
Director

On August 17, 2016 the Building Inspection Commission held a public hearing on the proposed Code amendments referenced above.

The Commission voted unanimously (7-0) to recommend that the Board of Supervisors approve the amendments.

The Commissioners voted as follows:

| | | | |
|----------------------|-----|-----------------------|-----|
| President McCarthy | Aye | Vice-President Melgar | Aye |
| Commissioner Clinch | Aye | Commissioner Gilman | Aye |
| Commissioner Konstin | Aye | Commissioner Lee | Aye |
| Commissioner Walker | Aye | | |

Enclosed please find the Code Advisory Committee's recommendation to the BIC. Under separate cover, copies of the proposed amendments will follow from the Technical Services Division of the Department of Building Inspection.

Should you have any questions, please do not hesitate to call me at 558-6164.

Sincerely,


Sonya Harris
Commission Secretary

cc: Tom C. Hui, Director
Mayor Edwin M. Lee
Supervisor John Avalos
Supervisor London Breed
Supervisor David Campos
Supervisor Malia Cohen
Supervisor Mark Farrell
Supervisor Jane Kim
Supervisor Eric Mar
Supervisor Aaron Peskin
Supervisor Katy Tang
Supervisor Scott Wiener
Supervisor Norman Yee
Deputy City Attorney John Malamut

EXHIBIT A

STANDARD FINDINGS FOR SAN FRANCISCO BUILDING STANDARDS CODE AMENDMENTS:

1. Certain buildings/occupancies in San Francisco are at increased risk for earthquake-induced failure and consequent fire due to local hazardous microzones, slide areas, and local liquefaction hazards.
(Geology)
2. Certain buildings/occupancies in San Francisco are at increased risk of fire due to high density of buildings on very small lots, with many buildings built up to the property lines. (Topography)
3. Topography of San Francisco has led to development of a high density of buildings on small lots, necessitating special provisions for exiting, fire separation, or fire-resistive construction. (Topography)
4. Many buildings are built on steep hills and narrow streets, requiring special safety consideration. (Topography)
5. Additional fire, structural and other protection is required due to high building density and crowded occupancy. (Topography)
6. San Francisco has narrow, crowded sidewalks due to building and population density and unusual topography. (Topography)
7. All rain water in San Francisco drains to the building drains and sewer; unusual geology, occasional extremely high local rainfall amounts, and the configuration of the City as a peninsula restrict the installation of separate storm water and sewer systems. (Topography, Climate, Geology)
8. Moist, corrosive atmosphere of salt-laden fog in San Francisco necessitates additional requirements. (Climate)
9. Not a building standard; no local findings required.
10. Soil conditions in this region induce adverse reactions with some materials, leading to premature failures and subsequent unsanitary conditions. (Climate)
11. The region is subject to fluctuating rainfall due to changes in climatic conditions.
(Climate)
12. San Francisco is a peninsula surrounded on three sides by water at sea level;

mitigation of climate change impacts, including sea level rise, is critical to the long term protection of the local built environment and local infrastructure.
(Topography)

13. Climate and potential climate change impacts San Francisco's water resources, including reservoirs and distribution facilities. (Climate)
14. Organic material in San Francisco's waste breaks down into methane gas which is a significant contributor to climate change. (Climate)
15. San Francisco is topographically constrained and its built environment occupies most available land, requiring minimization of debris and solid waste.
(Topography)
16. Prevailing winds, coastal mountain ranges, and periodic seasonal high temperatures contribute to photochemical reactions that produce smog and ozone; limiting the emission of smog's chemical precursors - volatile organic chemicals and oxides of nitrogen - is necessary to health and safety. (Climate, Topography)
17. The aquifers underlying San Francisco are small relative to local population, necessitating ongoing water imports and special provisions to ensure efficient use of water in local buildings. (Geology)

**CALIFORNIA
ADOPTED THE FOLLOWING:**

FINAL EXPRESS TERMS
FOR STATE AGENCY APPROVED CHANGES TO THE
2015 UNIFORM MECHANICAL AND PLUMBING CODES (UMC) & (UPC)
FOR
THE 2016 CALIFORNIA MECHANICAL AND PLUMBING CODES (CMC) & (CPC)
CALIFORNIA CODE OF REGULATIONS (CCR), TITLE 24, PARTS 4 & 5 RESPECTIVELY

- THE CALIFORNIA BUILDING STANDARDS COMMISSION (BSC)
- THE DIVISION OF THE STATE ARCHITECT – STRUCTURAL SAFETY (DSA/SS)
- THE DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPEMENT (HCD)
- THE OFFICE OF STATE WIDE HEALTH PLANNING AND DEVELOPMENT (OSHDP)
- THE OFFICE OF THE STATE FIRE MARSHAL (SFM)

Disclaimer: All Final Express Terms for the above mentioned agencies are available and were obtained from the Building Standards Commission at the following link:

<http://www.bsc.ca.gov/Rulemaking/adoptcycle/2015CodeAdoptionCycle/ApprovedStandardsDecember2015.aspx><http://www.bsc.ca.gov/Rulemaking/adoptcycle/2015CodeAdoptionCycle/ApprovedStandardsJanuary2016.aspx>

TABLE OF CONTENTS

| DIVISION | AGENCY PROPOSAL # |
|--|-------------------|
| I) 2015 UNIFORM MECHANICAL CODE STATE AGENCY AMENDMENTS | |
| 1. THE CALIFORNIA BUILDING STANDARDS COMMISSION | (BSC 02/15) |
| 2. THE DIVISION OF THE STATE ARCHITECT – STRUCTURAL SAFETY | (DSA/SS 06/15) |
| 3. THE DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT | (HCD 05/15) |
| 4. THE OFFICE OF STATE WIDE HEALTH PLANNING AND DEVELOPMENT | (OSHDP 06/15) |
| 5. THE OFFICE OF THE STATE FIRE MARSHAL | (SFM 03/15) |
| II) 2015 UNIFORM PLUMBING CODE STATE AGENCY AMENDMENTS | |
| 1. THE CALIFORNIA BUILDING STANDARDS COMMISSION | (BSC 03/15) |
| 2. THE CALIFORNIA BUILDING STANDARDS COMMISSION | (BSC 03/15 ADDEN) |
| 3. THE DIVISION OF THE STATE ARCHITECT – ACCESS COMPLIANCE | (DSA/AC 03/15) |
| 4. THE DIVISION OF THE STATE ARCHITECT – STRUCTURAL SAFETY | (DSA/SS 05/15) |
| 5. THE DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT | (HCD 06/15) |
| 6. THE OFFICE OF STATE WIDE HEALTH PLANNING AND DEVELOPMENT | (OSHDP 05/15) |
| 7. THE OFFICE OF THE STATE FIRE MARSHAL | (SFM 04/15) |

Disclaimer: All Final Express Terms for the above mentioned agencies are available and were obtained from the Building Standards Commission at the following link:

<http://www.bsc.ca.gov/Rulemaking/adoptcycle/2015CodeAdoptionCycle/ApprovedStandardsDecember2015.aspx>
<http://www.bsc.ca.gov/Rulemaking/adoptcycle/2015CodeAdoptionCycle/ApprovedStandardsJanuary2016.aspx>

**FINAL EXPRESS TERMS
FOR
PROPOSED BUILDING STANDARDS
OF THE
CALIFORNIA BUILDING STANDARDS COMMISSION (CBSC)

REGARDING PROPOSED ADOPTION OF THE 2015
UNIFORM PLUMBING CODE (UPC) FOR THE
CALIFORNIA CODE OF REGULATIONS, TITLE 24, PART 5**

(The State agency shall draft the regulations in plain, straightforward language, avoiding technical terms as much as possible and using a coherent and easily readable style. The agency shall draft the regulation in plain English. A notation shall follow the express terms of each regulation listing the specific statutes authorizing the adoption and listing specific statutes being implemented, interpreted, or made specific. (PART 1 – ADMINISTRATIVE CODE)

LEGEND FOR EXPRESS TERMS

1. Existing California amendments or code language being modified are in *italics* when they appear in the model code text: All such language appears in *italics*, modified language is underlined.
2. New California amendments: All such language appears underlined and in italics.
3. Repealed text: All such language appears in ~~strikeout~~.

EXPRESS TERMS

The Building Standards Commission (BSC) proposes to adopt the 2015 edition of the Uniform Plumbing Code (UPC) for codification and effectiveness into the 2016 edition of the California Plumbing Code (CPC) as presented on the following pages, including any necessary amendments. BSC further proposes to:

- Repeal the 2012 edition of the UPC and the 2013 CPC;
- Repeal amendments to the model code that are no longer necessary, repeal or amend building standards that are not addressed by a model code;
- Relocate or codify existing adopted and necessary amendments to the model code into the format of the model code proposed for adoption, the action of which has no regulatory effect; adopt new necessary amendments to the model code proposed for adoption; and/or
- Adopt new building standards that are not addressed by the model code proposed for adoption

PROPOSED REPEALS, ADOPTIONS AND NEW AMENDMENTS

ITEM 1. BSC proposes to bring forward existing California amendments in the *preface* from the 2013 California Plumbing Code for adoption into the 2016 edition of the California Plumbing Code with additional amendments as follows:

PREFACE

This document is the 5th of ~~twelve~~thirteen parts of the official triennial compilation and publication of the

adoptions, amendments and repeal of administrative regulations to *California Code of Regulations, Title 24*, also referred to as the *California Building Standards Code*. Part 5 is known as the *California Plumbing Code* and incorporates, by adoption, the 2012 2015 edition of the *Uniform Plumbing Code* of the International Association of Plumbing and Mechanical Officials with the California amendments.

The *California Building Standards Code* is published in its entirety every ...

...

ACKNOWLEDGEMENTS

The 2013 2016 California Building Standards Code (Code) was developed through the outstanding collaborative efforts of the Department of Housing and Community Development, the Division of the State Architect, the Office of the State Fire Marshal, the Office of Statewide Health Planning and Development, the California Energy Commission, the California Department of Public Health, the California State Lands Commission, the Board of State and Community Corrections, and the California Building Standards Commission (Commission).

This collaborative effort included the assistance of the Commission's Code Advisory Committees and many other volunteers who worked tirelessly to assist the Commission in the production of this Code.

Governor Edmund G. Brown Jr.

Members of the Building Standards Commission

Secretary Anna Caballero Marybel Batjer – Chair
~~James Barthman~~ Steven Winkel – Vice-Chair

| | |
|---|--|
| <i>Stephen Jensen <u>Elley Klausbruckner</u></i> | <i>Rose Conroy <u>Cheryl Roberts</u></i> |
| <i>Randy Twist <u>Larry Booth</u></i> | <i>Sheila Lee <u>David Malcolm Carson</u></i> |
| <i>Richard Sawhill</i> | <i>Richard Sierra</i> |
| <i>Kent Sasaki</i> | <i>Steven Winkel</i> |
| <i><u>Raj Patel</u></i> | <i><u>Erick Mikiten</u></i> |
| <i><u>Pedro Santillan</u></i> | |

Jim McGowan – Executive Director
Michael L. Nearman – Deputy Executive Director

...

Legends of Abbreviations of Adopting State Agencies

| | |
|---------------|--|
| BSC | California Building Standards Commission (see Section 1.2.0) |
| <u>BSC-CG</u> | <u>California Building Standards Commission – Green Code (see Section 1.3.0)</u> |
| SFM ... | |

Notation:

Authority: Health and Safety Code §18934.5, 18949.6

References: Health and Safety Code §18934.5, 18949.6

ITEM 2. BSC proposes to bring forward existing California amendments in Chapter 1, Division I through Chapter 1, Division II from the 2013 California Plumbing Code for adoption into the 2016 edition of the California Plumbing Code with additional amendments as follows:

**CHAPTER 1
CALIFORNIA ADMINISTRATION
DIVISION I**

1.1.0 General

1.1.1 Title. *These regulations shall be known as the California Plumbing Code, may be cited as such and will be referred to herein as "this code." The California Plumbing Code is Part 5 of twelve ~~thirteen~~ parts of the official compilation and publication of the adoptions, amendment, and repeal of building regulations to the California Code of Regulations, Title 24, also referred to as the California Building Standards Code. This part incorporates by adoption the ~~2012~~ 2015 Uniform Plumbing Code of the International Association of Plumbing and Mechanical Officials with necessary California amendments.*

1.1.2 Purpose. *The purpose of this code is to establish the minimum requirements to safeguard the public health, safety and general welfare through structural strength, means of egress facilities, stability, access to persons with disabilities, sanitation, adequate lighting and ventilation, and energy conservation; safety to life and property from fire and other hazards attributed to the built environment; and to provide safety to fire fighters and emergency responders during emergency operations.*

1.1.3 Scope. *The provisions of this code shall apply to the construction, alteration, movement, enlargement, replacement, repair, equipment, use and occupancy, location, maintenance, removal and demolition of every building or structure or any appurtenances connected or attached to such buildings or structures throughout the State of California.*

1.1.3.1 Nonstate-regulated buildings, structures, and applications. *Except as modified by local ordinance pursuant to Section 1.1.8, the following standards in the California Code of Regulations, Title 24, Parts 2, 2.5, 3, 4, 5, 6, 9, 10 and 11 shall apply to all occupancies and applications not regulated by a state agency.*

1.1.3.2 State-Regulated Buildings, Structures, and Applications. *The model code, state amendments to the model code, and/or state amendments where there are no relevant model code provisions, shall apply to the following buildings, structures, and applications regulated by state agencies as specified in Sections 1.2.0 through 1.14.0, except where modified by local ordinance pursuant to Section 1.1.8. When adopted by a state agency, the provisions of this code shall be enforced by the appropriate enforcing agency, but only to the extent of authority granted to such agency by the state legislature.*

Note: *See Preface to distinguish the model-code provisions from the California provisions.*

1. *State-owned buildings, including buildings constructed by the Trustees of the California State University, and to the extent permitted by California laws, buildings designed and constructed by the Regents of the University of California, and regulated by the Building Standards Commission. See Section 1.2.0 for additional scope provisions.*

- ~~2. Section 1.3.0 is reserved for the Local detention facilities regulated by the Corrections Standards Authority Board of State and Community Corrections. See Section 1.3 for additional scope provisions.~~
- ~~3. Section 1.4.0 is reserved for the Department of Consumer Affairs. Barbering, cosmetology or electrolysis establishments, acupuncture offices, pharmacies, veterinary facilities, and structural pest control locations regulated by the Department of Consumer Affairs. See Section 1.4 for additional scope provisions.~~
- ~~4. Section 1.5.0 is reserved Reserved for the California Energy Commission. See Section 1.5 for additional scope provisions.~~
- ~~5. Section 1.6.0 is reserved for the Dairies and places of meat inspection regulated by the Department of Food and Agriculture. See Section 1.6 for additional scope provisions.~~
6. Organized camps, laboratory animal quarters, public swimming pools, radiation protection, commissaries serving mobile food preparation vehicles, and wild animal quarantine facilities regulated by the Department of Public Health. See Section 1.7 for additional scope provisions.
7. Hotels, motels, lodging houses, ~~apartment houses~~ apartments, dwellings, dormitories, condominiums, shelters for homeless persons, congregate residences, employee housing, factory-built housing, and other types of dwellings containing sleeping accommodations with or without common toilets or cooking facilities. See Section 1.8.2.1.1 for additional scope provisions.
8. Accommodations for persons with disabilities in buildings containing newly constructed covered multifamily dwellings, new common use spaces serving existing covered multifamily dwellings, additions to existing buildings where the addition alone meets the definition of "COVERED MULTIFAMILY DWELLINGS," and new common-use spaces areas serving new covered multifamily dwellings which are regulated by the Department of Housing and Community Development. See Section 1.8.2.1.2 for additional scope provisions.
9. Permanent buildings and permanent accessory buildings or structures constructed within mobilehome parks and special occupancy parks regulated by the Department of Housing and Community Development. See Section 1.8.2.1.3 for additional scope provisions.
10. Accommodations for persons with disabilities regulated by the Division of the State Architect. See Section 1.9.1 for additional scope provisions.
11. Public elementary and secondary schools, community college buildings, and state-owned or state-leased essential service buildings regulated by the Division of the State Architect. See Section 1.9.2 for additional scope provisions.
12. Reserved for the State Historical Building Safety Board with the Division of the State Architect. See Section 1.9.3 for additional scope provisions.
13. General acute care hospitals, acute psychiatric hospitals, skilled nursing and/or intermediate care facilities, clinics licensed by the Department of Public Health and correctional treatment centers regulated by the Office of Statewide Health Planning and Development. See Section 1.10 for additional scope provisions.

14. Applications regulated by the Office of State Fire Marshal include but are not limited to the following in accordance with Section 1.11:

1. Buildings or structures used or intended for use as an:

- 1.1. Asylum, jail, prison.
- 1.2. Mental hospital, hospital, home for the elderly, children's nursery, children's home or institution, school or any similar occupancy of any capacity.
- 1.3. Theater, dancehall, skating rink, auditorium, assembly hall, meeting hall, nightclub, fair building, or similar place of assemblage where 50 or more persons may gather together in a building, room or structure for the purpose of amusement, entertainment, instruction, deliberation, worship, drinking or dining, awaiting transportation, or education.
- 1.4. Small family day care homes, large family day-care homes, residential facilities and residential facilities for the elderly, residential care facilities.
- 1.5. State institutions or other state-owned or state-occupied buildings.
- 1.6. High rise structures.
- 1.7. Motion picture production studios.
- 1.8. Organized camps.
- 1.9. Residential structures.

2. Tents, awnings or other fabric enclosures used in connection with any occupancy.
3. Fire alarm devices, equipment and systems in connection with any occupancy.
4. Hazardous materials, flammable and combustible liquids.
5. Public school automatic fire detection, alarm, and sprinkler systems.
6. Wildland-urban interface fire areas.

15. Section 1.12.0 is reserved for Public libraries constructed and renovated using funds from the California Library Construction and Renovation Bond Act of 1988 and regulated by the State Librarian. See Section 1.12 for additional scope provisions.

16. Section 1.13.0 is reserved for the Graywater systems regulated by the Department of Water Resources. See Section 1.13 for additional scope provisions.

17. For applications listed in Section 1.9.1 regulated by the Division of the State Architect – Access Compliance, outdoor environments and uses shall be classified according to accessibility uses described in Chapter 11A, 11B and 44G.

18. Section 1.14.0 is reserved for Marine Oil Terminals regulated by the California State Lands Commission. See Section 1.14 for additional scope provisions.

1.1.4 Appendices. Provisions contained in the appendices of this code shall not apply unless specifically adopted by a state agency or adopted by a local enforcing agency in compliance with Health and Safety Code Section 18901 et. seq. for Building Standards Law, Health and Safety Code Section 17950 for State

Housing Law and Health and Safety Code Section 13869.7 for Fire Protection Districts. See Section 1.1.8 of this code.

1.1.5 Referenced codes. The codes, standards and publications adopted and set forth in this code, including other codes, standards and publications referred to therein are, by title and date of publication, hereby adopted as standard reference documents of this code. When this code does not specifically cover any subject related to building design and construction, recognized architectural or engineering practices shall be employed. The National Fire Codes, standards, and the Fire Protection Handbook of the National Fire Protection Association are permitted to be used as authoritative guides in determining recognized fire prevention engineering practices.

1.1.6 Nonbuilding standards, orders and regulations. Requirements contained in the Uniform Mechanical Code or in any other referenced standard, code or document, which are not building standards as defined in Health and Safety Code Section 18909, shall not be construed as part of the provisions of this code. For nonbuilding standards, orders, and regulations, see other titles of the California Code of Regulations.

1.1.7 Order of precedence and use.

1.1.7.1 Differences. In the event of any differences between these building standards and the standard reference documents, the text of these building standards shall govern.

1.1.7.2 Specific provisions. Where a specific provision varies from a general provision, the specific provision shall apply.

1.1.7.3 Conflicts. When the requirements of this code conflict with the requirements of any other part of the California Building Standards Code, Title 24, the most restrictive requirements shall prevail.

Exception: Detached one-and two-family dwellings, efficiency dwelling units, lodging houses, live/work units, townhouses not more than three stories above grade plane with a separate means of egress, and their accessory structures, shall not be required to comply with the California Residential Code if constructed in accordance with the California Building Code.

1.1.8 City, county, or city and county amendments, additions or deletions.

The provisions of this code do not limit the authority of city, county, or city and county governments to establish more restrictive and reasonably necessary differences to the provisions contained in this code pursuant to complying with Section 1.1.8.1. The effective date of amendments, additions, or deletions to this code by a city, county, or city and county filed pursuant to Section 1.1.8.1 shall be the date filed. However, in no case shall the amendments, additions or deletions to this code be effective any sooner than the effective date of this code.

Local modifications shall comply with Health and Safety Code Section 18941.5 for Building Standards Law, Health and Safety Code Section 17958 for State Housing Law or Health and Safety Code Section 13869.7 for Fire Protection Districts.

1.1.8.1 Findings and filings.

1. The city, county, or city and county shall make express findings for each amendment, addition or deletion based upon climatic, topographical, or geological conditions.

Exception: Hazardous building ordinances and programs mitigating unreinforced

masonry buildings.

2. The city, county, or city and county shall file the amendments, additions, or deletions expressly marked and identified as to the applicable findings. Cities, counties, cities and counties, and fire departments shall file the amendments, additions or deletions, and the findings with the California Building Standards Commission at 2525 Natomas Park Drive, Suite 130, Sacramento, CA 95833.
3. Findings prepared by fire protection districts shall be ratified by the local city, county, or city and county and filed with the California Department of Housing and Community Development, Division of Codes and Standards, P.O. Box 1407, Sacramento, CA 95812-1407 or ~~1800 3rd Street, Room 260, Sacramento, CA 95811~~ 2020 W. El Camino Avenue, Suite 250, Sacramento, CA 95833-1829.

1.1.8.2 Locally adopted energy standards – California Energy Code, Part 6.

In addition to the provisions of Section 89.101.8.1 of this Part, the provisions of this section applies to cities, counties, and city and county amending adopted energy standards affecting buildings and structures subject to the California Energy Code, Part 6.

Applicable provisions of Public Resources Code Section 25402.1 and applicable provisions of Chapter 10 of the California Administrative Code, Part 1 apply to local amendment of energy standards adopted by the California Energy Commission.

1.1.9 Effective date of this code. Only those standards approved by the California Building Standards Commission that are effective at the time an application for building permit is submitted shall apply to the plans and specifications for, and to the construction performed under, that permit. For the effective dates of the provisions contained in this code, see the History Note page of this code.

1.1.10 Availability of codes. At least one complete copy each of Titles 8, 19, 20, 24, and 25 with all revisions shall be maintained in the office of the building official responsible for the administration and enforcement of this code. Each state department concerned and each city, county or city and county shall have an up-to-date copy of the code available for public inspection, See Health and Safety Code Section 18942 ~~(d)~~(e)(1) and (2).

1.1.11 Format. This part fundamentally adopts the International Building Code by reference on a chapter-by-chapter basis. When a specific chapter of the International Building Code is not printed in the code and is marked "Reserved", such chapter of the International Building Code is not adopted as a portion of this code. When a specific chapter of the International Building Code is marked "Not adopted by the State of California" but appears in the code, it may be available for adoption by local ordinance.

Note: Matrix Adoption Tables at the front of each chapter may aid the code user in determining which chapter or sections within a chapter are applicable to buildings under the authority of a specific state agency, but they are not to be considered regulatory.

1.1.12 Validity. If any chapter, section, subsection, sentence, clause or phrase of this code is for any reason held to be unconstitutional, contrary to statute, exceeding the authority of the state as stipulated by statutes or otherwise inoperative, such decision shall not affect the validity of the remaining portion of this code.

SECTION 1.2
BUILDING STANDARDS COMMISSION

1.2.0 Building Standards Commission.

1.2.1 BSC Specific scope of application of the agency responsible for enforcement, the enforcement agency, and the specific authority to adopt and enforce such provisions of this code, unless otherwise stated.

1. State Buildings for all Occupancies.

Application – State buildings (all occupancies), including buildings constructed by the Trustees of the California State University (CSU) and the Regents of the University of California (UC) where no state agency has the authority to adopt building standards applicable to such buildings.

Enforcing Agency – State or local agency specified by the applicable provisions of law.

Authority Cited – Health and Safety Code section 18934.5.

Reference – Health and Safety Code, Division 13, Part 2.5, commencing with section 18901.

2. University of California, California State Universities, and California Community Colleges.

Application – Standards for lighting for parking lots and primary campus walkways at the University of California, California State Universities, and California Community Colleges.

Enforcing Agency – State or local agency specified by the applicable provisions of law.

Authority Cited – Government Code section 14617.

Reference – Government Code section 14617.

3. Existing State-Owned Buildings, including those owned by the University of California and by the California State University– Building seismic retrofit standards including abating falling hazards of structural and nonstructural components and strengthening of building structures. See also Division of the State Architect.

Enforcing Agency – State or local agency specified by the applicable provisions of law.

Authority Cited – Government Code section 16600

Reference – Government Code sections 16600 through 16604

4. Unreinforced Masonry Bearing Wall Buildings.

Application – Minimum seismic strengthening standards for buildings specified in Appendix Chapter 4 of the California Code for Existing Building Conservation Code, except for buildings subject to building standards adopted pursuant to Part 1.5 (commencing with Section 17910)

Enforcing Agency – State or local agency specified by the applicable provisions of law.

Authority Cited – Health and Safety Code section 18934.67

Reference – ~~Health and Safety Code sections 18901 through 18949~~ Health and Safety Code Division 13, Part 2.5 commencing with Sections 18901.

1.2.2 Alternate Materials, Design, and Methods of Construction and Equipment. The provisions of this code are not intended to prevent the installation of any material or to prohibit any design or method of construction not specifically prescribed by this code, provided that any such alternative has been approved. An alternative material, design, or method of construction shall be approved where the building finds that the proposed design is satisfactory and complies with the intent of the provisions of this code, and that the material, method of work offered is, for the purpose intended, at least the equivalent of that prescribed in this code in quantity, strength, effectiveness, fire resistance, durability and safety.

1.2.2.1 State building. For purposes of this code, a "state building" is a structure for which a state agency or state entity has authority to construct, alter, enlarge, replace, repair or demolish.

1.2.2.2 Enforcement. [CSU, UC, Judicial Council and California Department of Corrections Rehabilitation] state agencies or state entities authorized to construct state buildings may appoint a building official who is responsible to the agency for enforcement of the provisions of the California Building Standards Code.

Exception: State buildings regulated by other sections of this code remain the enforcement responsibility of the designated entities.

1.2.2.3 Enforcement, Reserved for DGS.

1.2.3 1.2.2.4 Adopting agency identification. The provisions of this code applicable to buildings identified in this section will be identified in the Matrix Adoption Tables under the acronym BSC.

1.2.3 BSC-CG. Specific scope of application of the agency responsible for enforcement, the enforcement agency, and the specific authority to adopt and enforce such provisions of this code, unless otherwise stated.

Application – All occupancies where no other state agency has the authority to adopt green building standards applicable to those occupancies.

Enforcing agency – State or local agency specified by the applicable provisions of law.

Authority cited – Health and Safety Code Sections 18930.5, 18938 and 18940.5.

Reference – Health and Safety Code, Division 13, Part 2.5, commencing with Section 18901.

1.2.23.1 Research Reports. Supporting data, where necessary to assist in the approval of materials or assemblies not specifically provided for in this code, shall consist of valid research reports from approved sources.

1.2.23.2 Tests. Whenever there is insufficient evidence of compliance with the provisions of this code, or evidence that a material or method does not conform to the requirements of this code, or in order to substantiate claims for alternative materials or methods, the building official shall have the authority to require tests as evidence of compliance to be made at no expense to the jurisdiction. Test methods shall be as specified in this code or by other recognized test standards. In the absence of recognized and accepted test methods, the building official shall approve the testing procedures. Tests shall be performed by an approved agency. Reports of such tests shall be retained by the building official for the period required for retention of public records.

...

1.13.0 Department of Water Resources (DWR).

1.13.1 Application—Construction, installation, or alteration of graywater systems for subsurface irrigation and other safe uses.

Enforcing Agency—Local building department of the Department of Water Resources.

Authority Cited—Water Code Section 14875 through 14877.3.

References—Water Code Section 14875 through 14877.3.

1.13.2 Application - Installation, construction, alteration, or repair of recycled water systems for water closets, urinals, trap primers for floor drains, floor sinks and other allowed uses.

Enforcing Agency – State or local agency specified by the applicable provisions of law.

Authority Cited – Water Code Section 13557.

References – Water Code Section 13553.

1.13.3 1.13.2 Adoption Agency Identification. The provisions of this code applicable to buildings identified in this section will be identified in the Matrix Adoption Tables under the acronym DWR.

...

Notation:

Authority: Health and Safety Code §18934.5, 18949.6

References: Health and Safety Code §18934.5, 18949.6

BSC proposes not to adopt CHAPTER 1 of the 2015 UPC for use in the 2016 CPC as Division II.

ADMINISTRATION

Chapter 1 (2015 UPC) - DIVISION II (2016 CPC)

...

Notation:

Authority: Health and Safety Code §18934.5, 18949.6

References: Health and Safety Code §18934.5, 18949.6

ITEM 3. BSC proposes to adopt Chapter 2 of the 2015 UPC with some model code definitions deleted and existing amendments to be moved forward with modifications for use in the 2016 CPC.

**CHAPTERS 2
DEFINITIONS**

[Check Definitions for alt. water sources to add the word "grey" to match HCD]

...

205.0

-C-

...

Complex System [BSC]. Gray water systems that ...

...

206.0

-D-

....

Disposal Field [BSC]. An intended destination for gray water including but ...

...

207.0

-E-

...

Enforcing Agency [BSC]. "Enforcing Agency" is the designated department or ...

...

209.0

-G-

...

Graywater [BSC]. Pursuant to Health and Safety Code Section 17922.12, "graywater" means untreated wastewater that has not been contaminated by ...

Gray Water. Untreated waste water that has not come into contact with toilet waste, kitchen sink waste, dishwasher waste or similarly contaminated sources. Gray water includes waste water from bathtubs, showers, lavatories, clothes washers, and laundry tubs. Also known as grey water, graywater, and greywater.

Gray Water Diverter Valve. A valve that directs gray water to the sanitary drainage system or to a subsurface irrigation system.

Gray Water System [BSC]. A system designed to collect gray water to be treated on-site for reuse or distribution to an irrigation or disposal field. A gray water system may ...

...

211.0

-I-

...

Irrigation Field [BSC]. An intended destination for graywater in the receiving landscape including ...

...

215.0

-M-

Mulch Basin. A subsurface catchment area for gray water that is filled with mulch and of sufficient depth and volume to prevent ponding, surfacing, or runoff.

Mulch Basin [BSC]. A subsurface type of irrigation or disposal field filled with mulch or ...

...

217.0

-O-

...

~~**On-Site Treated Nonpotable Water.** Nonpotable water, including grey water that has been collected, treated, and intended to be used on-site and is suitable for direct beneficial use.~~

On-Site Treated Nonpotable Water [BSC]. Nonpotable water that has been collected, treated, and intended to be used on-site and is suitable for direct beneficial ...

...

220.0

-R-

...

~~**Rainwater.** Natural precipitation that has not been contaminated by use.~~

Rainwater [BSC]. Precipitation on any public or private parcel that has not entered an offsite storm drain system or channel, a flood control channel, or any other stream ...

~~**Rainwater Catchment System.** A system that utilizes the principal of collecting, storing, and using rainwater from a rooftop or other manmade, aboveground collection surface. Also known as a rainwater harvesting system.~~

Rainwater Catchment System [BSC]. A facility designed to capture, retain, and store rainwater flowing off a building, parking lot, or any other manmade impervious ...

Receiving Landscape [BSC]. Includes features such as ...

~~**Reclaimed Water.** Nonpotable water provided by a water/wastewater utility that, as a result of tertiary treatment of domestic wastewater, meets requirements of the public health Authority Having Jurisdiction for its intended uses.~~

Reclaimed (Recycled) Water [BSC]. Nonpotable water that meets California Department of Public Health statewide uniform criteria for disinfected tertiary recycled ...

...

221.0

-S-

...

Simple System [BSC]. A gray water system serving one-and two-family dwellings, townhouses, or other occupancies with a discharge of 250 gallons (947 L) per day ...

...

222.0

-T-

...

Treated Gray Water [BSC]. Non-potable water meeting the definition of "graywater" collected....

...

Notation:

Authority: Health and Safety Code Sections 18928, 18930.5, 18941.8

Reference: Health and Safety Code Section 18941.8, Water Code Section 14877.1

ITEM 4. BSC proposes to adopt Chapter 3 of the 2015 UMC, without amendments.

**CHAPTER 3
GENERAL REGULATIONS**

...

Notation:

Authority: Health & Safety Code Sections 18928 and 18934.5

Reference(s): Health & Safety Code Sections 18928, 18928.1 and 18934.5

ITEM 5. BSC proposes to adopt Chapter 4 of the 2015 UPC and bring forward exiting amendments from the 2013 CPC with modifications for use in the 2016 CPC.

**CHAPTER 4
PLUMBING FIXTURES AND FIXTURE FITTINGS**

***Note:** In addition the requirements of this chapter, which provide access to, or egress from, buildings or facilities where accessibility is required for applications listed in Section 409 1.9.0, of the California Building Code, regulated by the Division of the State Architect – Access Compliance shall also comply with Chapter 11A for public housing and Chapter 11B for public accommodation under authority cited by Gov. Code §4450 through 4461, 12955.1 and H&SC §18949.1, 19952 through 19959.*

...

402.0 Installation.

...

***Note:** [BSC] On and after January 1, 2014, certain commercial real property, as defined in Civil Code Section 1101.3, shall have...*

...

407.0 Lavatories.

407.1 Application. Lavatories shall comply with ASME A112.19.1/CSA B45.2, ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, ASME A112.19.12, CSA B45.5/IAPMO Z124, or CSA B45.11/IAPMO Z401.

407.2 Water Consumption. The maximum water flow rate of faucets shall comply with Section 407.2.1 and Section 407.2.2.

407.2.1 Maximum Flow Rate. The maximum flow rate for public lavatory faucets shall not exceed 0.5 gpm at 60 psi (1.9 L/m at 414 kPa) and 2.2 gpm at 60 psi (8.3 L/m at 414 kPa) for private lavatory faucets in accordance with ASME A112.18.1/CSA B125.1.

407.2.2 (formerly 403.4) Metering Faucets. Metered faucets shall deliver a maximum of 0.25 gallons (1.0 L) per metering cycle in accordance with ASME A112.18.1/CSA B125.1.

407.2.2.1 Metering Faucets. [BSC-CG] Metering Faucets shall not deliver more than 0.20 gallons (0.76 L) per cycle in compliance with Chapter 5, Division 5.3 of the California Green Building Standards Code (CALGreen).

...

408.0 Showers.

408.1 Application. Manufactured shower receptors and shower bases shall comply with ASME A112.19.1/CSA B45.2, ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, or CSA B45.5/IAPMO Z124.

408.2 Water Consumption. Showerheads shall have a maximum flow rate of not more than 2.5 gpm at 80 psi (9.5 L/m at 552 kPa), in accordance with ASME A112.18.1/CSA B125.1.

408.2.1 Single showerhead. [BSC-CG] Showerheads shall have a maximum flow rate of not more than 2.0 gallons per minute at 80 psi. Showerheads shall be certified to the performance criteria of the U.S. EPA WaterSense Specification for Showerheads in compliance with Chapter 5, Division 5.3. of the California Green Building Standards Code (CALGreen).

408.2.2 Multiple showerheads serving one shower. [BSC-CG] When a shower is served by more than one showerhead, the combined flow rate of all showerheads and/or other shower outlets controlled by a single valve shall not exceed 2.0 gallons per minute at 80 psi, or the shower shall be designed to allow only one shower outlet to be in operation at a time in compliance with Chapter 5, Division 5.3. of the California Green Building Standards Code (CALGreen).

Note: A hand-held shower shall be considered a showerhead.

....

411.0 (formerly 403.2) Water Closets.

411.1 Application. Water closets shall comply with ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, or CSA B45.5/IAPMO Z124. Water closet bowls for public use shall be of the elongated type. In nurseries, schools, and other similar places where plumbing fixtures are provided for the use of children less than 6 years of age, water closets shall be of a size and height suitable for children's use.

411.2 Water Consumption. Water closets shall have a maximum consumption not to exceed 1.6 gallons (6 Lpf) of water per flush in accordance with ASME A112.19.2/CSA B45.1.

411.2.1 Dual Flush Water Closets. Dual flush water closets shall comply with ASME A112.19.14. The effective flush volume for dual flush water closets shall be defined as the composite, average flush volume of two reduced flushes and one full flush.

411.2.2 Flushometer Valve Activated Water Closets. Flushometer valve activated water closets shall have a maximum flush volume of 1.6 gallons (6 Lpf) of water per flush in accordance with ASME A112.19.2/CSA B45.1.

411.2.2.1 Flushometer Valve Activated Water Closets. [BSC-CG] Flushometer valve activated water closets shall have a maximum flush volume of 1.28 gallons (4.8 Lpf) of water per flush in accordance with ASME A112.19.2/CSA B45.1.

411.2.3 Water Closets [BSC-CG] *The effective flush volume of all water closets shall not exceed 1.28 gallons per flush. Tank-type water closets shall be certified to the performance criteria of the U.S. EPA WaterSense Specification for Tank-Type Toilets in compliance with Chapter 5, Division 5.3. of the California Green Building Standards Code (CALGreen).*

...

412.0 (formerly 403.3) Urinals.

412.1 Application. Urinals shall comply with ASME A112.19.2/CSA B45.1, ASME A112.19.19, or CSA B45.5/IAPMO Z124. Urinals shall have an average water consumption not to exceed 1 gallon (3.8 Lpf) of water per flush.

412.1.1 Nonwater Urinal...

~~403.3.2~~ 412.1.2 Wall mounted Urinals. [BSC-CG]...

~~403.3.3~~ 412.1.3 Floor mounted urinals. [BSC-CG]...

...

417.0 Faucets and Fixture Fittings.

417.1 Application. Faucets and fixture fittings shall comply with ASME A112.18.1/CSA B125.1. Fixture fittings covered under the scope of NSF 61 shall be in accordance with the requirements of NSF 61.

417.1.1 Wash Fountains. [BSC-CG] *Wash fountains shall have a maximum flow rate of not more than 1.8 gallons per minute/20 [rim space (inches) at 60 psi] in compliance with Chapter 5, Division 5.3 of the California Green Building Standards Code (CALGreen).*

417.1.2 Metering Faucets for Wash Fountains. [BSC-CG] *Metering faucets for wash fountains shall have a maximum flow rate of not more than 0.20 gallons per cycle/20 [rim space (inches) at 60 psi] in compliance with Chapter 5, Division 5.3 of the California Green Building Standards Code (CALGreen).*

...

420.0 Sinks.

420.1 Application. Sinks shall comply with ASME A112.19.1/CSA B45.2, ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, or CSA B45.5/IAPMO Z124. Moveable sink systems shall comply with ASME A112.19.12.

420.2 Water Consumption. Sink faucets shall have a maximum flow rate of not more than 2.2 gpm at 60 psi (8.3 L/m at 414 kPa) in accordance with ASME A112.18.1/CSA B125.1.

Exceptions:

- (1) Clinical sinks
- (2) Laundry trays
- (3) Service sinks

420.2.1 Kitchen faucets [BSC-CG] *Kitchen faucets shall have a maximum flow rate of not more than 1.8 gallons per minute at 60 psi. Kitchen faucets may temporarily increase the flow above the maximum rate, but not to exceed 2.2 gallons per minute at 60 psi, and must default to a maximum flow rate of 1.8 gallons per minute at 60 psi in compliance with Chapter 5, Division 5.3 of the California Green Building Standards Code (CALGreen).*

...

422.0 Minimum Number of Required Fixtures.

422.1 Fixture Count. Plumbing fixtures shall be provided for the type of building occupancy and in the minimum number shown in Table 422.1. The total occupant load and occupancy classification shall be

determined in accordance with *Occupant Load Factor Table A*. Occupancy classification not shown in Table 422.1 shall be considered separately by the Authority Having Jurisdiction.

...

**TABLE 422.1
MINIMUM PLUMBING FACILITIES¹**

Each building shall be provided with sanitary facilities, including provisions for persons with disabilities as prescribed by the Department Having Jurisdiction^{4,7}. Table 422.1 applies to all new buildings, additions to a building, and changes of occupancy or type in an existing building resulting in increased occupant load.

(Entire Table not shown for clarity)

| TYPE OF OCCUPANCY ² | WATER CLOSETS (FIXTURES PER PERSON) ³ | URINALS (FIXTURES PER PERSON) | LAVATORIES (FIXTURES PER PERSON) | BATHTUBS OR SHOWERS (FIXTURES PER PERSON) | DRINKING FOUNTAINS/FACILITIES (FIXTURES PER PERSON) | OTHER |
|--------------------------------|--|-------------------------------|----------------------------------|---|---|-------|
| ... | ... | ... | ... | ... | ... | ... |

Notes:

¹ The figures shown are based upon one (1) fixture being the minimum required for the number of persons indicated or any fraction thereof.

² A restaurant is defined as a business that sells food to be consumed on the premises.

a. The number of occupants for a drive-in restaurant shall be considered as equal to the number of parking stalls.

b. Hand-washing facilities shall be available in the kitchen for employees.

³ The total number of required water closets for females shall be not less than the total number of required water closets and urinals for males. **[BSC]** *This requirement shall not apply when single occupancy toilet facilities are provided for each sex in an A or E occupancy with an occupant load of less than 50. Either*

a. *The required urinal shall be permitted to be omitted or*

b. *If installed, the urinal shall not require a second water closet to be provided for the female.*

⁴ For each urinal added in excess of the minimum required, one water closet shall be permitted to be deducted. The number of water closets shall not be reduced to less than two-thirds of the minimum requirement.

⁵ Group lavatories that are 24 lineal inches (610 mm) of wash sink or 18 inches (457 mm) of a circular basin, where provided with water outlets for such space, shall be considered equivalent to one lavatory.

⁶ Metering of self closing faucets shall be installed on lavatories intended to serve the transient public.

^{4,7} **[BSC]** *In accordance with Sections 1.8.7 and 301.2, the Authority Having Jurisdiction may approve alternative design criteria when determining the minimum number of plumbing fixtures.*

**TABLE A.
OCCUPANT LOAD FACTOR:
[BSC]**

| Occupancy*, ** | Occupant Load Factor (square feet) (CBC 2001, Table A-29A) |
|----------------|---|
|----------------|---|

| | |
|--|-------|
| Group A | |
| 1. Auditoriums, convention halls, dance floors, lodge rooms, stadiums and casinos (where no seating is provided) <i>fixed</i> (use 1/2 "one-half" the number of fixed seating) | 15 |
| 2. Conference rooms, dining rooms, drinking establishments, exhibit rooms, gymnasiums, lounges, stages and similar uses including restaurants classified as Group B occupancies | 30 |
| 3. Worship places; principal assembly area, educational and activity unit (where no fixed seating is provided) (use 1/2 "one-half" the number of fixed seating) | 30 |
| Group B Office or public buildings (area accessible to the public) | 200 |
| Group E Schools for daycare, elementary, secondary | 50 |
| Educational Facilities Other than Group E Colleges, universities, adult center, etc | 50 |
| Group F Workshop, foundries and similar establishments | 2,000 |
| Group H Hazardous materials fabrication and storage | 2,000 |
| Group I Hospital general use area, Health Care facilities | 200 |
| Group M Retail or Wholesale stores | 200 |
| Group R Congregate residence, Group R-1 | 200 |
| Group S Warehouse | 5,000 |

* Any uses not specifically listed shall be based on similar uses listed in this table.

** For building or space with mixed occupancies, use appropriate occupancy group for each area (for example, a school may have an "A" occupancy for the gymnasium, a "B" occupancy for the office, an "E" occupancy for the classrooms, etc.)

Accessory areas may be excluded (for example: hallway, restroom, stair enclosure)

ITEM 6. BSC proposes to adopt Chapter 5 of the 2015 UPC without amendments.

CHAPTER 5 WATER HEATERS

...

Notation:

Authority: Health & Safety Code Sections 18928 and 18934.5

Reference(s): Health & Safety Code Sections 18928, 18928.1 and 18934.5

ITEM 7. BSC proposes to adopt Chapter 6 of the 2015 UPC with amendments as follows, and to carry forward exiting amendments.

**CHAPTER 6
WATER SUPPLY AND DISTRIBUTION**

TABLE 604.1
[Partial Table shown]

MATERIALS FOR BUILDING SUPPLY AND WATER DISTRIBUTION PIPING AND FITTINGS

| MATERIAL | BUILDING SUPPLY PIPE AND FITTINGS | WATER DISTRIBUTION PIPE AND FITTINGS | REFERENCED STANDARDS(S) PIPE | REFERENCED STANDARD(S) FITTINGS |
|-------------------------|---|---|---|---|
| ... | ... | ... | ... | ... |
| PE | X ¹ | -- | ASTM D2239, ASTM D2737, ASTM D3035, AWWA C901, CSA B137.1 | ASTM D2609, ASTM D2683, ASTM D3261, ASTM F1055, CSA B137.1 |
| ... | ... | ... | ... | ... |
| PEX ^{2,3} | X | X | ASTM F876, ASTM F877, CSA B137.5, AWWA C904 ¹ | ASSE 1061, ASTM F877, ASTM F1807, ASTM F1960, ASTM F1961, ASTM F2080, ASTM F2159, ASTM F2735, CSA B137.5 |
| PEX-AL-PEX ⁴ | X | X | ASTM F1281, CSA B137.10, ASTM F2262 | ASTM F1281, ASTM F1974, ASTM F2434, CSA B137.10 |
| PP | X | X | ASTM F2389, CSA B137.11 | ASTM F2389, CSA B137.11 |
| PVC | X ¹ | -- | ASTM D1785, ASTM D2241, AWWA C900 | ASTM D2464, ASTM D2466, ASTM D2467, ASTM F1970 |
| ... | ... | ... | ... | ... |

¹ For building supply or cold-water applications.

² When PEX tubing is placed in soil and is used in potable water systems intended to supply drinking water to fixtures or appliances, the tubing or piping shall be sleeved with a material approved for potable water use in soil or other material that is impermeable to solvents or petroleum products.

³ PEX tubing shall meet or exceed the requirements of ASTM F876-08 or an equivalent or more stringent standard when used in continuously recirculating hot water systems and the PEX tubing is exposed to the hot water 100% of the time.

⁴ **[For BSC]** The use of PEX-AL-PEX in potable water supply systems is not adopted.

604.13. Water Heater Connections. Flexible metallic water heater connectors or reinforced flexible water heater connectors connecting water heating to the piping system shall be in accordance with the applicable standards referenced in Table 1401.1....

[BSC] PEX-AL-PEX is not adopted for use in potable water supply and distribution systems.

605.10 (Formally 605.11) PEX-AL-PEX Plastic Tubing and Joints. PEX-AL-PEX plastic pipe or tubing and fitting joining methods shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.11.1 and section 605.11.1.1.

[BSC] PEX-AL-PEX is not adopted for use in potable water supply and distribution systems.

605.10.1 (Formally 605.11.1) Mechanical Joints. Mechanical joints between PEX-AL-PEX tubing and fittings shall include mechanical and compression type fittings and insert fittings with a crimping ring...

[BSC] PEX-AL-PEX is not adopted for use in potable water supply and distribution systems.

605.10.1.1 (Formally 605.11.1.1) Compression Joints. Compression joints shall include compression insert fittings and shall be joined to PEX-AL-PEX pipe through the compression of a split ring or compression nut around the outer circumferences of the pipe, forcing the pipe material into the annular space formed by the ribs on the fitting.

[BSC] PEX-AL-PEX is not adopted for use in potable water supply and distribution systems.

...

Notation:

Authority: Health & Safety Code Section 18934.5

Reference(s): Health & Safety Code Sections 18928, 18928.1 and 18934.5

ITEM 8. BSC proposes to adopt Chapter 7 SANITARY DRAINAGE, CHAPTER 8 INDIRECT WASTES, CHAPTER 9 VENTS, CHAPTER 10 TRAPS AND INTERCEPTORS, of the 2015 UPC without amendments.

...

Notation:

Authority: Health & Safety Code Sections 18928 and 18934.5

Reference(s): Health & Safety Code Sections 18928, 18928.1 and 18934.5

ITEM 9. BSC proposes to adopt Chapter 11 of the 2015 UPC without amendment, repeal amendment in Section 1101.3 of the 2013 CPC.

**CHAPTER 11
STORM DRAINAGE**

1101.4 (Formally 1101.3) Material Uses. Pipe, tube, and fittings conveying . . .

. . .

Notation:

Authority: Health & Safety Code Sections 18928 and 18934.5

Reference(s): Health & Safety Code Sections 18928, 18928.1 and 18934.5

ITEM 10. BSC proposes to adopt Chapter 12 of the 2015 UPC without amendments.

**CHAPTER 12
FUEL PIPING**

. . .

Notation:

Authority: Health & Safety Code Sections 18928 and 18934.5

Reference(s): Health & Safety Code Sections 18928, 18928.1 and 18934.5

ITEM 11. BSC proposes not to adopt Chapter 13 of the 2015 UPC.

**CHAPTER 13
HEALTH CARE FACILITIES AND MEDICAL GAS AND VACUUM SYSTEMS**

Notation:

Authority: Health & Safety Code Sections 18928 and 18934.5

Reference(s): Health & Safety Code Sections 18928, 18928.1 and 18934.5

ITEM 12. BSC proposes to adopt Chapter 14 of the 2015 UPC with the following amendments.

**CHAPTER 14
FIRESTOP PROTECTION**

Notation:

Authority: Health & Safety Code Sections 18928 and 18934.5

Reference(s): Health & Safety Code Sections 18928, 18928.1 and 18934.5

ITEM 13. BSC proposes to adopt Chapter 15 of the 2015 UPC with amendments as follows, and to carry forward exiting amendments.

**CHAPTER 15 (Formally Chapter 16)
ALTERNATE WATER SOURCES FOR NONPOTABLE APPLICATIONS**

Intent

The provisions of this chapter are intended to:

1. *Conserve water by facilitating greater reuse of laundry, shower, lavatory and similar sources of discharge for irrigation and/or indoor use.*
2. *Reduce the number of non-compliant graywater systems by making legal compliance easily achievable.*
3. *Provide guidance for avoiding potentially unhealthful conditions.*
4. *Provide an alternative way to relieve stress on a private sewage disposal system by diverting the graywater.*

1501.0 General.

1501.1 (Formally 1601.1) Applicability. ... [BSC] The provisions of this chapter shall apply to the construction, alteration, discharge, use and repair of alternate water source systems for nonpotable applications.

1501.1.1 (Formally 1601.1.1) Allowable Use of Alternate Water. Where approved or required by the Authority Having Jurisdiction, alternate water sources [reclaimed (recycled) water]...

1501.2 (Formally 1601.2 System Design) System Design. ~~Alternate water source systems complying with this chapter shall be designed by a person who demonstrates competency to design the alternate in accordance with this chapter by a registered design professional or who demonstrates competency to design the alternate water source system as required by the Enforcing Agency. The Enforcing Agency may also plans and specifications to be prepared by a licensed design professional for Complex Systems, Components, piping, and fittings used in any alternate water source system shall be listed.~~ Alternate water source systems shall be designed in accordance with this chapter by a registered design professional or who demonstrates competency to design the alternate water source system as required by the Authority Having Jurisdiction. Components, piping, and fittings used in any alternate water source system shall be listed.

1501.3 (Formally 1601.3) Permit. It shall be unlawful for a person to construct, install, alter, or cause to be constructed, installed, or altered an alternate water source system in a building or on a premise without first obtaining a permit to do such work. *Prior to commencing the issuance of permits for indoor gray water systems pursuant to state requirements relating to gray water, a city, county, or other local agency shall seek consultation with the local public health department to ensure that local public health concerns are addressed in local standards or ordinances, or in issuing permits. See California Water Code Section 14877.3.*

Exception: [BSC] A construction permit shall be ...

1501.4 (Formally 1601.4) Component Identification. System components shall be properly ...

1501.5 (Formally 1601.5) Maintenance and Inspection. Alternate water source systems and components shall be inspected and maintained in accordance with *the manufacturer's recommendations*

and/or as required by the Enforcing Agency. **[BSC]** Where no manufacturers recommendations exist, additional recommendations are listed in Table 1601.5 1501.5.

1501.5.1 Frequency. Alternate water source systems and components shall be inspected and maintained in accordance with Section 1501.5.1 unless more frequent inspection and maintenance is required by the manufacturer.

1501.5.2 Maintenance Log. A maintenance log for gray water and on-site treated nonpotable water systems is required to have a permit in accordance with Section 1501.3 and shall be maintained by the property owner or designated appointee shall ensure that a record of testing, inspection and maintenance in accordance with Table 1501.5 is maintained in the log. The log will indicate the frequency of inspection and maintenance for each system.

1501.5.3 1501.5.1 (Formally 1601.5.1) Maintenance Responsibility. The required maintenance and inspection of alternate water source systems shall be the responsibility of ...

1501.6 (Formally 1601.6) Operation and Maintenance Manual. An operation and maintenance manual for gray water, rainwater, and on-site treated water systems required to have a permit in accordance with Section 1501.3 shall be supplied to the building owner by the system designer or installer. The operating and maintenance manual shall include the following:

- (1) ~~Detailed diagram~~ *Diagram(s)* of the entire system and the location of system components.
- (2) Instructions on operating and maintaining the system.
- (3) ~~Details~~ *Instructions* on maintaining the required water quality as determined by the Authority Having Jurisdiction for on-site treated nonpotable water systems.
- (4) Details on *startup, shutdown, and* deactivating the system for maintenance, repair, or other purposes.
- (5) Applicable testing, inspection, and maintenance frequencies in accordance with ~~Table~~ *Section 1501.5*.
- (6) A method of contacting the *installer and/or* manufacturer(s).
- (7) *Directions to the owner or occupant that the manual shall remain with the building throughout the life cycle of the structure.*

1501.7 (Formally 1601.7) Minimum Water Quality Requirements.

The minimum water quality for alternate water source systems shall meet the applicable water quality requirements for the intended application as determined by the Authority Having Jurisdiction. In the absence of water quality requirements, the EPA/625/R-04/108 contains recommended water reuse guidelines to assist regulatory agencies develop, revise, or expand alternate water source water quality standards. **[BSC]** for on-site nonpotable treated gray water systems, the requirements of NSF/ANSI 350 shall apply.

Exception:

Water treatment is not required for gray water used for subsurface/subsoil irrigation or a disposal field.

**TABLE 1501.5 (Formally 1601.5) [BSC]
RECOMMENDED MINIMUM ALTERNATE WATER SOURCE TESTING, INSPECTION, AND
MAINTENANCE FREQUENCY**

| DESCRIPTION | MINIMUM FREQUENCY |
|-------------|-------------------|
|-------------|-------------------|

| | |
|--|---|
| Inspect and clean filters and screens, and replace (where necessary). | <i>In accordance with manufacturer's instructions, and/or the Authority Having Jurisdiction, or Every 3 months.</i> |
| Inspect and verify that disinfection, filters and water quality treatment devices and systems are operational and maintaining minimum water quality requirements as determined by the Authority Having Jurisdiction. | <i>In accordance with manufacturer's instructions, and the Authority Having Jurisdiction.</i> |
| Inspect pumps and verify operation. | <i>In accordance with manufacturer's instructions, and/or the Authority Having Jurisdiction, or After initial installation and every 12 months thereafter.</i> |
| Inspect valves and verify operation. | <i>In accordance with manufacturer's instructions, and/or the Authority Having Jurisdiction, or After initial installation and every 12 months thereafter.</i> |
| Inspect pressure tanks and verify operation. | <i>In accordance with manufacturer's instructions, and/or the Authority Having Jurisdiction, or After initial installation and every 12 months thereafter.</i> |
| Clear debris from and inspect storage tanks, locking devices, and verify operation. | <i>In accordance with manufacturer's instructions, and/or the Authority Having Jurisdiction, or After initial installation and every 12 months thereafter.</i> |
| Inspect caution labels and marking. | <i>In accordance with manufacturer's instructions, and/or the Authority Having Jurisdiction, or After initial installation and every 12 months thereafter.</i> |
| Inspect and maintain mulch basins for gray water irrigation systems. | <i>As needed to maintain mulch depth and prevent ponding and runoff.</i> |
| Cross-connection inspection and test* | <i>In accordance with manufacturer's instructions, and/or the Authority Having Jurisdiction, or After initial installation and every 12 months thereafter.</i> |
| *The cross-connection test shall be performed in the presence of the Authority Having Jurisdiction in accordance with the requirements of this chapter, <i>unless site conditions do not require it. Alternate testing requirements shall be permitted by the Authority Having Jurisdiction.</i> | |

1501.8 (Formally 1601.8) Material Compatibility. Alternate water source systems shall be ...

1501.9 (Formally 1601.9) System Controls. Controls for pumps, valves, and ...

1501.10 (Formally 1604.11.1) Commercial, Industrial, and Institutional Restroom Signs. A sign shall be installed in restrooms in commercial, industrial, and institutional occupancies using reclaimed (recycled) water and on-site treated water, for water closets, urinals, or both. Each sign shall contain ~~1/2~~ of an inch (12.7 mm) letters of a highly visible color on a contrasting background. The location of the sign(s) shall be such that the sign(s) are visible to users. The location of the sign(s) shall be approved by the Authority Having Jurisdiction and shall contain the following text:

TO CONSERVE WATER, THIS BUILDING USES * _____ * ON-SITE TREATED NONPOTABLE GRAY WATER TO FLUSH TOILETS AND URINALS.

1501.10.1 (Formally 1604.11.2) Equipment Room Signs. Each room containing reclaimed (recycled) water and on-site treated water equipment shall have a sign posted in a location that is visible to anyone working on or near nonpotable water equipment with the following wording in 1 inch (25.4 mm) letters:

CAUTION: NONPOTABLE * _____ *, DO NOT DRINK. DO NOT CONNECT TO DRINKING WATER SYSTEM. NOTICE: CONTACT BUILDING MANAGEMENT BEFORE PERFORMING ANY WORK ON THIS WATER SYSTEM.

* _____ * Shall indicate RECLAIMED (RECYCLED) WATER or ON-SITE TREATED WATER, accordingly.

1501.11 (Formally 1604.12) Inspection and Testing. Alternate water source systems shall be inspected and tested in accordance with Section 1501.11.1 and Section 1501.11.2 *and/or as required by the Authority Having Jurisdiction.*

1501.11.1 (Formally 1604.12.1) Supply System Inspection and Test. Alternate ...

1501.11.2 (Formally 1604.12.2) Annual Cross-Connection Inspection and Testing. An initial and subsequent annual inspection and test shall be performed on both the potable and alternate water source systems. The potable and alternate water source system shall be isolated from each other and independently inspected and tested to ensure there is no cross-connection in accordance with Section 1501.11.2.1 through Section 1501.11.2.4.

1501.11.2.1 (Formally 1604.12.2.1) Visual System Inspection. Prior to commencing the cross-connection testing, a dual system inspection shall be ...

1501.11.2.2 (Formally 1604.12.2.2) Cross-Connection Test. The procedure for determining cross-connection shall be followed by the applicant in ...

1501.11.2.3 (Formally 1604.12.2.3) Discovery of Cross-Connection. In the event that a cross-connection is discovered, the following procedure, in ...

1501.11.2.4 Annual Inspection. An annual inspection of the alternate water source system, following the procedures listed in ...

1501.12 Separation Requirements. Underground alternate water source service piping other than gray water shall be separated from the building sewer in accordance...

1501.13 Abandonment. Alternate water source systems that are no longer in ...

1501.13.1 General. An abandoned system or part thereof covered ...

1501.13.2 Underground Tank. An underground water storage tank...

1501.14 (Formally 1604.13) Sizing. Unless otherwise provided for in this chapter, alternate water source piping shall be sized in accordance with Chapter 6 for sizing potable water piping.

1502.0 (Formally 1602.0) Gray Water Systems. [BSC-CG] Gray water systems shall be verified in accordance with the California Green Building Standards Code (CALGreen), Chapter 5, Division 5.3.

1502.1 (Formally 1602.1) General. The provisions of this section shall apply to the construction, alteration, and repair of gray water systems. *A city, county, or city and county or other local government may adopt, after a public hearing and enactment of ...*

- (A) All gray water systems shall be designed with a diverter valve to allow...
- (B) Water used to wash diapers or similarly soiled or ...
- (C) Gray water shall not be used in spray irrigation, allowed to pond ...
- (D) Human contact with gray water or the soil irrigated by gray water ...
- (E) Gray water may be released above the ground surface provided at...
- (F) Gray water shall not contain hazardous chemicals derived from ...
 - (1) **[HCD]** The prohibition in Subsection (F) includes, but is not limited to, home photo labs or similar hobbyist or home occupational activities.
 - (2) **[BSC]** photo labs or similar activities.
- (G) Exemption from construction permit requirements of this code shall ...
- (H) An operation and maintenance manual shall be provided to the ...
- (I) A gray water system shall not be connected to any potable water system ...

1502.1.1 (Formally 1602.1.1) [HCD 1] Clothes Washer System. (Reserved for HCD)

1502.1.2 (Formally 1602.1.2) Simple System. Simple systems exceed a clothes washer system and shall comply with the following:

- (1) The discharge capacity of a gray water system shall be determined by Section ~~1602.8~~ **1502.8**. Simple systems have a discharge capacity of 250 gallons (947 L) per day or less.
- (2) Simple systems shall require a construction permit, unless exempted ...
- (3) The design of simple systems shall meet generally ...

1502.1.3 (Formally 1602.1.3) Complex System. Any gray water system that is not a clothes washer system or simple system shall comply with the following:

- 1. The discharge capacity of a gray water system shall be determined ...
- 2. Complex systems shall require a construction permit, unless exempted from a construction permit by the-Enforcing Agency. The Enforcing Agency ...

1502.2 (Formally 1602.2) System Requirements. Gray water shall be permitted to be diverted away from a sewer or private sewage disposal system, and ...

1502.2.1 (Formally 1602.2.2) Surge Capacity. Gray water systems shall be designed to have the capacity to accommodate peak flow rates and distribute the ...

Exception: It is not the intent of this section to require that all ...

1502.2.2 (Formally 1602.2.3) Diversion. The point of diversion of gray water to the sanitary drainage system shall occur downstream of fixture traps and vent connections...

Exception [HCD 1]: [Reserved for HCD]

1502.2.3 (Formally 1602.2.4) Backwater Valves. Gray water drains subject to backflow ...

1502.3 (Formally 1602.3) Connections to Potable and Reclaimed (Recycled) Water Systems. Gray

water systems shall have no direct unprotected connection to a potable water supply, on-site treated nonpotable water supply, or reclaimed (recycled) water systems. Potable, on-site treated nonpotable, or reclaimed (recycled) water or rainwater is permitted to be used as makeup water for a non-pressurized storage tank provided the connection is protected by an airgap, reduced-pressure principle backflow preventer or other physical device which prevents backflow in accordance with this code.

1502.4 (Formally 1602.4) Location. No gray water system or part thereof shall be located ...

Exception: When there exists a lawfully recorded perpetual and exclusive covenant to an easement appurtenant and right-of-way between adjoining land-owners ...

1502.5 (Formally 1602.5) Plot Plan Submission. No permit for a gray water system shall be...

Exception: (Reserved for HCD)

1502.6 (Formally 1602.6) Prohibited Location. Where there is insufficient lot area or inappropriate soil conditions for adequate absorption to prevent ...

1602.7 Drawings and Specifications. The Authority Having Jurisdiction *may* require the following information to be included with or in the plot plan before a permit is issued for a gray water system, or at a time during the construction thereof:

- (1) Plot plan drawn to scale and completely dimensioned, showing lot lines and structures, ...
- (2) Details of construction necessary to ensure compliance with the requirements of ...
- (3) Details for holding tanks shall include dimensions, structural calculations, bracings, ...
- (4) A log of soil formations and groundwater level as determined by test holes dug...

Exceptions:

- (1) The Authority Having Jurisdiction shall permit the use of Table 1502.10 in ...
- (2) *The Enforcing Agency may waive the requirement for identification of ...*
- (3) *The absence of groundwater in a test hole three (3) vertical feet (915 mm) below ...*
- (5) Distance between the plot and surface waters such as lakes, ponds, rivers or streams, ..

**TABLE 1502.4 (Formally 1602.4)
LOCATION OF GRAY WATER SYSTEM**

| MINIMUM HORIZONTAL DISTANCE IN CLEAR REQUIRED FROM | SURGE TANK (feet) | SUBSURFACE AND SUBSOIL IRRIGATION FIELD AND MULCH BED BASIN (feet) | DISPOSAL FIELD |
|--|----------------------|---|------------------|
| Building structures ¹ | 5 ^{2,3,9} | 2 ^{3,8} | 5 |
| Property line adjoining private property | 5 | 5 ⁸ | 5 |
| Water supply wells ⁴ | 50 | 100 | 100 |
| Streams and lakes ⁴ | 50 | 100 ^{5,10} | 100 ⁵ |
| Sewage pits or cesspools | 5 | 5 | 5 |
| Sewage disposal field ¹⁰ | 5 | 4 ⁶ | 4 ⁶ |
| Septic tank | 0 | 5 | 5 |
| On-site domestic water service line | 5 | 0 | 0 |
| Pressurized public water main ⁷ | 10 | 10 | 10 ⁷ |

For SI units: 1 foot = 304.8 mm

Notes:

- ¹ *Building structures do not include porches and steps, whether covered or uncovered, breezeways, roofed carports, roofed porte cocheres, roofed patios, carports, covered walks, covered driveways, and similar structures or appurtenances.*
- ² *The distance shall be permitted to be reduced to 0 feet for aboveground tanks where first approved by the Authority Having Jurisdiction.*
- ³ *Underground tanks shall not be located within a 45 degree angle from the bottom of the foundation, or they shall be designed to address the surcharge imposed by the structure. The distance may be reduced to six (6) inches (153 mm) for aboveground tanks when first approved by the Enforcing Agency.*
- ⁴ *Where special hazards are involved, the distance required shall be increased as directed by the Authority Having Jurisdiction.*
- ⁵ *These minimum clear horizontal distances shall apply between the irrigation or disposal field and the ocean mean higher high tide line.*
- ⁶ *Add 2 feet (610 mm) for each additional foot of depth in excess of 1 foot (305 mm) below the bottom of the drain line.*
- ⁷ *For parallel construction or for crossings, approval by the Authority Having Jurisdiction shall be required.*
- ⁸ *The distance shall be permitted to be reduced to 1 1/2 feet (457 mm) for drip and mulch basin irrigation systems.*
- ⁹ *The distance shall be permitted to be reduced to 0 feet for surge tanks of 75 gallons (284 L) or less.*
- ¹⁰ *The minimum horizontal distance may be reduced to 50 feet (15,240 mm) for irrigation fields utilizing gray water which has been filtered prior to entering the distribution piping.*

Exception: (Reserved for HCD)

1502.8 (Formally 1602.8) Procedure for Estimating Gray Water Discharge. Gray water systems shall be designed to distribute the total amount of estimated gray water on a daily basis. The water discharge for gray water systems shall be determined in accordance with Section 1502.8.1 or Section 1502.8.2.

Exception: It is not the intent of this section to require that all gray water must be handled by an irrigation field or disposal field. It is acceptable for excess gray water to be diverted to the building sewer through a diverter valve or overflow drain as permitted in this chapter.

1502.8.1 (Formally 1602.8.1) Single Family Dwellings and Multi-Family Dwellings. Reserved for HCD.

1502.8.2 (Formally 1602.8.2) Commercial, Industrial, and Institutional Occupancies. The Authority Having Jurisdiction may utilize the gray water discharge for commercial, industrial, and institutional occupancies shall be calculated by utilizing the procedure in Section 1502.8.1 procedures listed below, water use records, or other documentation to estimate gray water discharge.

1502.8.2.1 (Formally 1602.8.2.1) Lavatories. Daily discharge from lavatories may be determined by the following equation:

(Equation 15.1 46-1)

Occupants X lavatory flow rate X 3

Where:

The number of occupants = square footage of the building divided by the occupant load factor from the California Plumbing Code Chapter 4, Table A.

Lavatory fixture flow rate, new construction = that from the California Green Building Standards (CALGreen) Code Table 5.303.2.3

Lavatory fixture flow rate, existing fixtures = actual flow rate for existing fixtures

3 = average number of uses per person per day

1502.8.2.2 (Formally 1602.8.2.2) Showers. Daily gray water discharge from showers may be determined by the following equation:

(Equation 15.2 46-2)

Number of daily uses X shower flow rate X 5 minutes

1502.8.2.3 (Formally 1602.8.2.3) Commercial Clothes Washers. Daily gray water discharge from commercial clothes washers may be determined by the following equation:

(Equation 15.3 46-3)

Cubic feet of capacity X Water Factor X 6

Where:

Water Factor = gallons per cubic foot

6 = average number of uses per day

Note: Cubic feet of capacity and Water Factor are contained in product specifications or are available from the washer manufacturer.

1502.8.3 (Formally 1602.8.3) Daily Discharge. Gray water systems using tanks shall be designed to minimize the amount of time gray water is held in the tank and shall be sized to distribute the total amount of estimated gray water on a daily basis.

Exception: Approved on-site treated nonpotable gray water systems.

1502.9 (Formally 1602.9) Gray Water System Components. Gray water system components shall comply with Section 1502.9.1 through Section 1502.9.7.

1502.9.1 (Formally 1602.9.1) Surge Tanks. Where installed, surge tanks shall be in accordance with the following:

- (1) Surge tanks shall be constructed of solid, durable materials not subject to excessive corrosion or decay and shall be watertight. *Above ground surge tanks shall be protected from direct sunlight or shall be constructed of opaque UV resistant materials including but not limited to heavily tinted plastic, fiberglass, lined metal, concrete and wood.* Surge tanks constructed of steel shall be approved by the Authority Having Jurisdiction, provided such tanks are in accordance with approved applicable standards.
- (2) Each surge tank shall be vented in accordance with this code. The vent ...
- (3) Each surge tank shall have an access ...
- (4) Each surge tank shall have its rated capacity permanently marked ...
- (5) Each surge tank shall have an overflow drain. The overflow ...
- (6) The overflow drainpipes shall not be less in size than the inlet ...
- (7) Surge tank shall be structurally designed to withstand anticipated earth or ...
- (8) Where a surge tank is installed underground, the ...
- (9) Surge tanks shall be installed on dry, level, well-compacted soil ...
- (10) Surge tanks shall be anchored to prevent against overturning where ...
- (11) *(Reserved for HCD).*

1502.9.2 (Formally 1602.9.2) Gray Water Pipe and Fitting Materials. Aboveground and underground building drainage and vent pipe and ...

1502.9.3 Subsoil Irrigation Field Materials. Subsoil irrigation field piping shall be constructed of perforated high-density polyethylene pipe, perforated ABS pipe, perforated PVC pipe, or other approved materials, provided that sufficient openings are available for distribution of the gray water into the trench area. Material, construction, and perforation of the pipe shall be in accordance with the appropriate absorption field drainage piping standards and shall be approved by the Authority Having Jurisdiction.

1502.9.3 (Formally 1602.9.3) Animals and Insects. Gray water tank openings shall be ...

1502.9.4 Subsurface Irrigation Field and Mulch Basin Supply Line Materials. Materials for gray water piping outside the building shall be polyethylene or PVC. Drip feeder lines shall be PVC or polyethylene tubing.

1502.9.4 (Formally 1602.9.4) Freeze Protection. Tanks and piping installed in locations ...

1502.9.5 Valves. Valves shall be accessible.

1502.9.6 Trap. Gray water piping discharging into the surge tank or having a direct connection to the sanitary drain or sewer piping shall be downstream of an approved water seal type trap(s). Where no such trap(s) exists, an approved vented running trap shall be installed upstream of the connection to protect the building from possible waste or sewer gases.

1502.9.7 Backwater Valve. A backwater valve shall be installed on gray water drain connections to the sanitary drain or sewer.

1502.10 (Formally 1602.10) Subsurface Irrigation System Zones. Irrigation or disposal fields shall be permitted to have one or more valved zones. Each zone

1502.10.1 (Formally 1602.10.1) Required Area of Subsurface Irrigation Fields, Subsoil Irrigation Fields and Mulch Basins. The minimum effective irrigation area of subsurface irrigation fields, subsoil

1502.10.2 (Formally 1602.10.2) Determination of Maximum Absorption Capacity. The irrigation field and mulch basin size shall be based on the maximum absorption capacity of...

Exceptions:

- (1) The Enforcing Agency may waive the requirement for identification of groundwater level and/or soil absorption qualities based on knowledge of local conditions.
- (2) Irrigation fields in compliance with Section 1502.11.2 which only utilize drip type emitters, are exempt from percolation tests.

**TABLE 1502.10 (Formally 1602.10)
DESIGN OF SIX TYPICAL SOILS**

| TYPE OF SOIL | MINIMUM SQUARE FEET OF IRRIGATION/LEACHING AREA PER 100 GALLONS OF ESTIMATED GRAY WATER DISCHARGE PER DAY | MAXIMUM ABSORPTION CAPACITY IN GALLONS PER SQUARE FOOT OF IRRIGATION/LEACHING AREA FOR A 24-HOUR PERIOD |
|---|---|---|
| Coarse sand or gravel | 20 | 5.0 |
| Fine sand | 25 | 4.0 |
| Sandy loam | 40 | 2.5 |
| Sandy clay | 60 | 1.7 |
| Clay with considerable sand or gravel | 90 | 1.1 |
| Clay with small amounts of sand or gravel | 120 | 0.8 |

For SI units: 1 square foot = 0.0929 m², 1 gallon per day = 0.000043 L/s

1502.10.3 (Formally 1602.10.3) Groundwater Level. No excavation for an irrigation field, ...

Note: The absence of groundwater in a test hole three (3) vertical feet (915 mm) below ...

1502.11 Subsurface and Subsoil Irrigation Field, and Mulch Basin Design and Construction. Subsurface and subsoil irrigation field, and mulch basin design and construction shall be in accordance with Section 1502.11.1 through Section 1502.11.3. Where a gray water irrigation system design is predicated on soil tests, the subsurface or subsoil irrigation field or mulch basin shall be installed at the same location and depth as the tested area.

1502.11.1 Subsurface Irrigation Field. A subsurface irrigation field shall comply with Section 1502.11.1.1 through Section 1502.11.1.6.

1502.11.1.1 Minimum Depth. Supply piping, including drip feeders, shall be not less than 2 inches (51 mm) below finished grade and covered with mulch or soil.

1502.11.1.2 Filter. Not less than 140 mesh (105 micron) filter with a capacity of 25 gallons per minute (gpm) (1.58 L/s), or equivalent shall be installed. Where a filter backwash is installed, the backwash and flush discharge shall discharge into the building sewer or private sewage disposal system. Filter backwash and flush water shall not be used.

1502.11.1.3 Emitter Size. Emitters shall be installed in accordance with the manufacturer's installation instructions. Emitters shall have a flow path of not less than 1200 microns (μ) (1200 μ m) and shall not have a coefficient of manufacturing variation (Cv) exceeding 7 percent. Irrigation system design shall be such that emitter flow variation shall not exceed 10 percent.

1502.11.1.4 Number of Emitters. The minimum number of emitters and the maximum discharge of each emitter in an irrigation field shall be in accordance with Table 1502.11.

1502.11.1.5 Controls. The system design shall provide user controls, such as valves, switches, timers, and other controllers, to rotate the distribution of gray water between irrigation zones.

1502.11.1.6 Maximum Pressure. Where pressure at the discharge side of the pump exceeds 20 pounds-force per square inch (psi) (138 kPa), a pressure-reducing valve able to maintain downstream pressure not exceeding 20 psi (138 kPa) shall be installed downstream from the pump and before an emission device.

1502.11.2 Mulch Basin. A mulch basin shall comply with Section 1502.11.2.1 through Section 1502.11.2.4.

1502.11.2.1 Single Family and Multi-Family Dwellings. The gray water discharge to a mulch basin is limited to single family and multi-family dwellings.

1502.11.2.2 Size. Mulch basins shall be of sufficient size to accommodate peak flow rates and distribute the total amount of estimated gray water on a daily basis without surfacing, ponding or runoff. Mulch basins shall have a depth of not less than 10 inches (254 mm) below finished grade. The mulch basin size shall be based on the maximum absorption capacity of the soil and determined using Table 1502.10.

1502.11.2.3 Minimum Depth. Gray water supply piping, including drip feeders, shall be not less than 2 inches (51 mm) below finished grade and covered with mulch.

1502.11.2.4 Maintenance. The mulch basin shall be maintained periodically to retain the required depth and area, and to replenish the required mulch cover.

1502.11.3 Subsoil Irrigation Field. Subsoil irrigation fields shall comply with Section 1502.11.3.1 through Section 1502.11.3.3.

1502.11.3.1 Minimum Pipe Size. Subsoil irrigation field distribution piping shall be not less than 3 inches (80 mm) diameter.

1502.11.3.2 Filter Material and Backfill. Filter material, clean stone, gravel, slag, or similar material acceptable to the Authority Having Jurisdiction, varying in size from ¼ of an inch (19.1 mm) to 2½ inches (64 mm) shall be placed in the trench to the depth and grade in accordance with Table 1502.11.3. The perforated section of subsoil irrigation field distribution piping shall be laid on the filter material in an approved manner. The perforated section shall then be covered with filter material to the minimum depth in accordance with Table 1502.11.3. The filter material shall then be covered with porous material to prevent closure of voids with earth backfill. No earth backfill shall be placed over the filter material cover until after inspection and acceptance.

1502.11.3.3 Subsoil Irrigation Field Construction. Subsoil irrigation fields shall be constructed in accordance with Table 1502.11.3. Where necessary on sloping ground to prevent excessive line slopes, irrigation lines shall be stepped. The lines between each horizontal leaching section shall be made with approved watertight joints and installed on natural or unfilled ground.

1502.11 (Formerly 1602.11) Irrigation, Disposal Field and Mulch Basin Construction. [BSC-CG]
Irrigation design shall be verified in accordance with the California Green Building Standards Code (CALGreen), Chapter 5, Division 5.3. Irrigation fields, disposal fields and mulch basins used in gray water systems shall comply with this section. Gray water systems may contain either a irrigation field or a disposal field or a combination of both. This section is not intended to prevent the use of other methods of gray water irrigation or disposal approved by the Enforcing Agency.

1502.11.1 (Formerly 1602.11.1) Mulch Basin. A mulch basin may be used as an irrigation or disposal field. Mulch basins shall be ...

1502.11.2 (Formerly 1602.11.2) Irrigation Field. The provisions of this section are not intended to prevent the use of any ...

- (1) Filters used in gray water irrigation systems shall be as specified by the manufacturer's installation instructions for the design flow rate ...
- (2) Emitters shall be designed to resist root intrusion and shall be of a design recommended by the manufacturer for the ...
- (3) Each irrigation zone shall be designed to include no less than the number of emitters specified in Table 1602.11, or through a ...
- (4) The system design shall provide user controls, such as valves, switches, timers and other controllers, ...
- (5) All drip irrigation supply lines shall be polyethylene tubing or PVC Class 200 pipe or better and Schedule 40 fittings. All joints shall be ...
- (6) Where pressure at the discharge side of the pump exceeds 20 psi (138 kPa), a pressure-reducing valve able to maintain downstream ...
- (7) When an irrigation system utilizes a pump, and discharges water at a point higher than the pump, a backwater valve shall ...

**TABLE 1502.11 (Formally 1602.11)
SUBSURFACE IRRIGATION DESIGN
CRITERIA FOR SIX TYPICAL SOILS**

| TYPE OF SOIL | MAXIMUM EMITTER DISCHARGE | MINIMUM NUMBER OF EMITTERS PER GALLON OF ESTIMATED GRAY WATER DISCHARGE PER DAY* |
|--------------|------------------------------|--|
| | gallon per day | gallon per day |
| Sand | 1.8 | 0.6 |
| Sandy loam | 1.4 | 0.7 |
| Loam | 1.2 | 0.9 |
| Clay loam | 0.9 | 1.1 |
| Silty clay | 0.6 | 1.6 |
| Clay | 0.5 | 2.0 |

For SI units: 1 gallon per day = 0.000043 L/s

* The estimated gray water discharge per day shall be determined in accordance with Section 1602.8 of this code.

1502.11.3 (Formally 1602.11.3) Disposal Field. The provisions of this section are not intended to prevent the use of ...

- (A) Disposal systems shall be not less than three (3) inches (80 mm) in cross sectional dimension and shall be constructed of ...
- (B) Filter material, clean stone, gravel, slag, or similar filter material acceptable to the Enforcing Agency, varying in size from ...

Exception: Manufactured leaching chambers shall be installed in compliance with ...

- (C) Disposal fields shall be constructed in accordance with Table 1502.11.3 1602.11.3.
- (D) When necessary on sloping ground to prevent excessive line slopes, disposal lines shall be stepped or installed on the contour ...

**TABLE 1502.11.3 (Formally 1602.11.3)
SUBSOIL IRRIGATION FIELD CONSTRUCTION**

| DESCRIPTION | MINIMUM | MAXIMUM |
|---|-----------|-------------------------|
| Number of drain lines per valved zone ¹ | 1 | - |
| Length of each perforated line ¹ | - | 100 feet |
| Bottom width of trench ¹ | 12 inches | 18 24 inches |
| Spacing of lines, center to center ¹ | 4 feet | - |
| Depth of earth cover of lines | 10 inches | - |
| Depth of filter material cover of lines | 2 inches | - |
| Depth of filter material beneath lines ¹ | 3 inches | - |
| Grade of perforated lines level | level | 3 inches per 100 feet |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 inch per foot = 83.3 mm/m

¹ Manufactured leaching chambers shall be installed in compliance with the manufacturer's installation instructions.

1502.12 (Formally 1602.12) Gray Water System Color and Marking Information. Pressurized gray water distribution systems shall be identified as containing nonpotable water in accordance with Section 601.3 of this code. *Marking shall be at intervals not to exceed 5 feet (1,524mm). Gray water distribution piping upstream of any connection to an irrigation or disposal field or a distribution valve shall be identified with the words "CAUTION: NONPOTABLE GRAY WATER, DO NOT DRINK."*

1502.13 (Formally 1602.13) Special Provisions.

4502.13.1 1502.13.1 (Formally 1602.13.1) Other Collection and Distribution Systems. Other collection and distribution systems shall be approved as allowed by Section 301.3 of this code.

4502.13.2 1502.13.2 Higher Requirements. Nothing contained in this chapter shall be construed to prevent the Authority Having Jurisdiction from requiring compliance with higher requirements than those contained herein, where such higher requirements are essential to maintain a safe and sanitary condition.

1502.13.3 (Formally 1602.13.2) Future Connections. *Gray water stub-out plumbing may be allowed for future connection prior to the installation of irrigation lines and landscaping. Stub-out shall be permanently marked "CAUTION: NONPOTABLE GRAY WATER, DO NOT DRINK."*

1502.14 (Formally 1602.14) Testing. Building drains and vents for gray water systems shall be tested in accordance with this code. Surge tanks shall be filled with water ...

1502.15 (Formally 1602.15) Maintenance. Gray water systems and components shall be ...

1503.0 (Formally 1603.0) (Reserved)

1504.0 (Formally 1604.0) On-Site Treated Nonpotable Gray Water Systems.

1504.1 (Formally 1604.1) General. The provisions of this section shall apply to the installation, construction, alteration, and repair of on-site treated nonpotable gray water systems intended to supply uses such as water closets, urinals, trap primers for floor drains and floor sinks, above and belowground irrigation, and other uses approved by the Authority Having Jurisdiction.

Other approved nonpotable water sources including swimming pool backwash operations, air conditioner condensate, rainwater, cooling tower blow-down water, foundation drainage, steam system condensate, fluid cooler discharge water, food steamer discharge water, combination oven discharge water, industrial process water, and fire pump test water may be ...

1504.2 (Formally 1604.2) Plumbing Plan Submission. No permit for an on-site treated nonpotable gray water system shall be issued until ...

1504.3 (Formally 1604.3) System Changes. No changes or connections shall be made to either the on-site treated nonpotable gray ...

1504.4 (Formally 1604.4) Connections to Potable or Reclaimed (Recycled) Water Systems. On-site treated nonpotable gray water systems shall have no *unprotected* connection to a potable water supply or reclaimed (recycled) water source system. Potable, or reclaimed (recycled) water is permitted to be used as makeup water for a non-pressurized storage tank provided the makeup water supply is protected by an

air gap, *reduced-pressure principle backflow preventer or other physical device which prevents backflow* in accordance with this code.

1504.5 (Formally 1604.5) Initial Cross-Connection Test. A cross-connection test is required in accordance with Section 1501.11.2. Before ...

1504.6 (Formally 1604.6) On-Site Treated Nonpotable Gray Water System Materials. On-site treated nonpotable *gray water* supply and distribution system ...

1504.7 (Formally 1604.7) On-Site Treated Nonpotable Gray Water Devices and Systems. Devices or equipment used to treat on-site treated nonpotable *gray water* in ...

1504.8 (Formally 1604.8) On-Site Treated Nonpotable Gray Water System Color and Marking Information. On-site treated *nonpotable gray water* systems shall have a colored background and marking ...

1504.9 (Formally 1604.9) Valves. Valves, except fixture supply control valves, shall be equipped with a locking feature.

1504.10 (Formally 1604.10) Design and Installation. The design and installation of on-site treated nonpotable *gray water* systems shall be in accordance with Section 1504.10.1 through Section ~~1604.10.6~~, 1504.10.5.

1504.10.1 (Formally 1604.10.1) Listing Terms and Installation Instructions. On-site treated nonpotable *gray water* systems shall be ...

1504.10.2 (Formally 1604.10.2) Minimum Water Quality. On-site treated nonpotable *gray water* supplied to toilets or urinals or for other uses in which it ...

1504.10.3 (Formally 1604.10.3) Deactivation and Drainage. The on-site treated nonpotable *gray water* system and the potable water system within the building ...

1504.10.4 (Formally 1604.10.4) Near Underground Potable Water Pipe. On-site treated nonpotable *gray water* pipes shall be...

1504.10.5 (Formally 1604.10.5) Required Filters. A filter permitting the passage of particulates no larger than 100 microns (100 μ m) shall be ...

1504.10.6 (Formally 1604.10.6) Disinfection. *Where the intended use of on-site treated non potable gray water requires disinfection and/or other treatment, on-site treated ...*

1504.11 (Formally 1604.11) Signs. Signs in buildings using on-site treated nonpotable *gray* ...

ITEM 14. BSC proposes to adopt Chapter 16 of the 2015 UPC with the following amendments.

**CHAPTER 16 (Formally Chapter 17)
NONPOTABLE RAINWATER CATCHMENT SYSTEMS**

1601.0 (Formally 1701.0) General.

1601.1 (Formally 1701.1) Applicability. The provisions of this chapter shall apply to the installation, construction, alteration, and repair of nonpotable rainwater catchment systems. *In addition, applicable provisions in Chapter 16, Sections 1601.0 through 1601.9 for "Alternate Water Sources For Nonpotable Applications" shall apply to rainwater catchment systems.*

1601.2 System Design. Rainwater catchment systems shall be designed in accordance with this chapter by a person registered or licensed to perform plumbing design work or who demonstrates competency to design the rainwater catchment system as required by the Authority Having Jurisdiction. Components, piping, and fittings used in a rainwater catchment system shall be listed.

Exceptions:

(1) A person registered or licensed to perform plumbing design work is not required to design rainwater catchment systems used for irrigation with a maximum storage capacity of 360 gallons (1363 L).

(2) A person registered or licensed to perform plumbing design work is not required to design rainwater catchment systems for single family dwellings where outlets, piping, and system components are located on the exterior of the building.

1601.3 (Formally 1702.2.1) Permit. ~~It shall be unlawful for a person to construct, install, alter, or cause to be constructed, installed, or altered a nonpotable rainwater catchment system in a building or on a premise without first obtaining a permit to do such work from the Authority Having Jurisdiction.~~

Permit. It shall be unlawful for a person to construct, install, alter, or cause to be constructed, installed, or altered a nonpotable rainwater catchment system in a building or on a premise without first obtaining a permit to do such work from the Authority Having Jurisdiction.

Exceptions:

(1) A permit is not required for exterior rainwater catchment systems used for outdoor drip ~~non-spray~~ irrigation with a maximum storage capacity of 5000 gallons (18 927L) where the tank is supported directly upon grade and the ratio of height to diameter or width does not exceed 2 to 1, and it does not require electrical power or a makeup water supply connection. ~~and subsurface irrigation with a maximum storage capacity of 360 gallons (1363 L).~~

(2) A plumbing permit is ...

1601.4 Component Identification. ~~System components shall be properly identified as to the manufacturer.~~

1601.5 Maintenance and Inspection. Rainwater catchment systems and components shall be inspected and maintained in accordance with Section 1601.5.1 through Section 1601.5.3. the manufacturers recommendations and/or required by the enforcing agency.

1601.5.1 Frequency. Rainwater catchment systems and components shall be inspected and maintained in accordance with Table 1601.5 unless more frequent inspection and maintenance is required by the manufacturer.

1601.5.2 Maintenance Log. A maintenance log for rainwater catchment systems is required to have a permit in accordance with Section 1601.3 and shall be maintained by the property owner and be available for inspection. The property owner or designated appointee shall ensure that a record of testing, inspection, and maintenance in accordance with Table 1601.5 is maintained in the log. The log will indicate the frequency of inspection and maintenance for each system.

1601.5.3 1601.5.1 Maintenance Responsibility. The required maintenance and inspection of rainwater catchment systems shall be the responsibility of the property owner, unless otherwise required by the Authority Having Jurisdiction.

1601.6 Operation and Maintenance Manual. An operation and maintenance manual for rainwater catchment systems required to have a permit in accordance with Section 1601.3, shall be supplied to the building owner by the system designer or installer. The operating and maintenance manual shall include the following:

- (1) Detailed diagram Diagram(s) of the entire system and the location of system components.
- (2) Instructions on operating and maintaining the system.
- (3) Details Instructions on maintaining the required water quality ~~as determined by the Authority Having Jurisdiction for rainwater catchment systems.~~
- (4) Details on startup, shutdown, and deactivating the system for maintenance, repair, or other purposes.
- (5) Applicable testing, inspection, and maintenance frequencies in accordance with Table Section 1601.5.
- (6) A method of contacting the Installer and/or manufacturer(s).
- (7) Directions to the owner of occupant that the manual shall remain with the building throughout the life cycle of the structure.

1601.7 (Formally 1702.9.4) Minimum Water Quality Requirements. The minimum water quality for rainwater catchment systems shall comply with the applicable water quality requirements for the intended application as determined by the Authority Having Jurisdiction. Water quality for nonpotable rainwater catchment systems shall comply with Section 1602.9.4. *In the absence of water quality requirements for harvested rainwater, Table 1702.9.4 1602.9.4 shall apply.*

Exceptions:

- (1) Water treatment is not required for rainwater catchment systems used for aboveground irrigation with a maximum storage capacity of 360 gallons (1363 L).
- (2) Water treatment is not required for rainwater catchment systems used for surface, subsurface or drip irrigation.

1601.8 Material Compatibility. Rainwater catchment systems shall be constructed of materials that are compatible with the type of pipe and fitting materials, water treatment, and water conditions in the system.

1601.9 System Controls. Controls for pumps, valves, and other devices that contain mercury that come in contact with rainwater supply shall not be permitted.

1601.10 Separation Requirements. Underground rainwater catchment service piping shall be separated from the building sewer in accordance with Section 609.2. Treated nonpotable water pipes shall be permitted to be run or laid in the same trench as potable water pipes with a 12 inch (305 mm) minimum vertical and horizontal separation where both pipe materials are approved for use within a building. Where

horizontal piping materials do not meet this requirement the minimum separation shall be increased to 60 inches (1524 mm). The potable water piping shall be installed at an elevation above the treated nonpotable water piping.

1601.11 Abandonment. Rainwater catchment systems that are no longer in use, or fail to be maintained in accordance with Section 1601.5, shall be abandoned. Abandonment shall comply with Section 1601.11.1 and Section 1601.11.2.

1601.11.1 General. An abandoned system or part thereof covered under the scope of this chapter shall be disconnected from remaining systems, drained, plugged, and capped in an approved manner.

1601.11.2 Underground Tank. An underground water storage tank that has been abandoned or otherwise discontinued from use in a system covered under the scope of this chapter shall be completely drained and filled with earth, sand, gravel, concrete, or other approved material or removed in a manner satisfactory to the Authority Having Jurisdiction.

1601.12 Sizing. Unless otherwise provided for in this chapter, rainwater catchment piping shall be sized in accordance with Chapter 6 for sizing potable water piping.

1602.0 (Formally 1702.0) Nonpotable Rainwater Catchment Systems.

1602.1 (Formally 1702.1) General. The installation, construction, alteration, and repair of rainwater catchments systems intended to supply uses such ...

1602.2 (Formally 1702.2) Plumbing Plan Submission. No permit for a rainwater catchment system shall be issued until complete plumbing plans, with

1602.3 (Formally 1702.3) System Changes. No changes or connections shall be made to either the rainwater catchment system or the potable water system ...

1602.4 (Formally 1702.4) Connections to Potable or Reclaimed (Recycled) Water Systems. Rainwater catchment systems shall have no *unprotected* connection to a potable water supply ...

1602.5 (Formally 1702.5) Initial Cross-Connection Test. Where a portion of a rainwater catchment system is installed within a building, a ...

1602.6 (Formally 1702.6) Sizing. Rainwater catchment system distribution piping for indoor applications shall be sized as outlined in this code for sizing ...

1602.7 (Formally 1702.7) Rainwater Catchment System Materials. Rainwater catchment system materials shall comply ...

1602.7.1 (Formally 1702.7.1) Water Supply and Distribution Materials. Rainwater catchment water supply and distribution materials shall comply with the ...

1602.7.2 (Formerly 1702.7.2) Rainwater Catchment System Drainage Materials. Materials used in rainwater catchment drainage systems, including ...

1602.7.3 (Formerly 1702.7.3) Storage Tanks. Rainwater storage tanks shall comply with ...

1602.7.4 Collection Surfaces. ~~The collection surfaces shall be constructed of a hard, impervious material.~~

1602.8 (Formerly 1702.8) Rainwater Catchment System Color and Marking Information. Rainwater catchment systems shall have a colored ...

1602.9 (Formerly 1702.9) Design and Installation. The design and installation of nonpotable rainwater catchment systems shall be in ...

1602.9.1 (Formerly 1702.9.1) Outside Hose Bibbs. Outside hose bibbs shall be allowed on rainwater piping systems. Hose bibbs supplying rainwater shall be ...



Figure 1602.9 (Formerly 1702.9)

1602.9.2 (Formerly 1702.9.2) Deactivation and Drainage for Cross-Connection Test. The rainwater catchment system and the potable water system within the building ...

1602.9.3 (Formerly 1709.9.3 Collection Surfaces) Rainwater Catchment System Surfaces. ~~Rainwater shall be collected from roof surfaces or other manmade, aboveground collection surfaces.~~ Rainwater shall be collected from roof surfaces or other impervious manmade, above-ground collection surfaces. Rainwater collected from surface water runoff, vehicular parking surfaces or manmade surfaces at or below grade shall comply with the water quality requirements for on-site treated nonpotable gray water in Section ~~1604.0~~ 1504.0.

Exception: *Collected rainwater or storm water used exclusively for subsurface landscape irrigation.*

1602.9.3.1 Other Surfaces. ~~Natural precipitation collected from surface water runoff, vehicular parking surfaces, or manmade surfaces at or below grade shall be in accordance with the stormwater requirements for on-site treated nonpotable water systems in Section 1504.0.~~

1602.9.3.2 1602.9.3.1 (Formally 1702.9.3.1) Prohibited Discharges. Overflows and bleed-off pipes from roof-mounted equipment and appliances shall not discharge onto roof surfaces that are intended to collect rainwater.

1602.9.4 Minimum Water Quality. The minimum water quality for harvested rainwater shall meet the applicable water quality requirements for the intended applications as determined by the Authority Having Jurisdiction. In the absence of water quality requirements determined by the Authority Having Jurisdiction, the minimum treatment and water quality shall be in accordance with Table 1602.9.4. ~~In the absence of water quality requirements for harvested rainwater Table 1702.9.4 shall apply.~~

Exception: [BSC] No treatment is required for rainwater used for non-spray irrigation where the maximum storage volume is less than 5000 gallons (18 927L) where the tank is supported directly upon grade and the ratio of height to diameter or width does not exceed 2 to 1.

1602.9.4.1 Disinfection. Where the initial quality of the collected rainwater requires disinfection or other treatment or both, the collected rainwater shall be treated as necessary to ensure the required water quality is delivered at the point of use. Where chlorine is used for disinfection or treatment, water shall be tested for residual chlorine in accordance with ASTM D 1253. The levels of residual chlorine shall not exceed the levels allowed for the intended use in accordance with the requirements of the local enforcing agency.

**TABLE 1702.9.4
MINIMUM TREATMENT AND WATER QUALITY FOR RAINWATER**

| Application | Minimum Treatment | Minimum Water Quality |
|--|--|---|
| Car washing | <ul style="list-style-type: none"> Debris excluder or other approved means in compliance with Section 1702.9.10 100 Micron (100 µm) in compliance with Section 1702.9.11 for drip irrigation | N/A |
| Surface, subsurface and drip irrigation | <ul style="list-style-type: none"> Debris excluder or other approved means in compliance with Section 1702.9.10 100 Micron (100 µm) in compliance with Section 1702.9.11 for drip irrigation | N/A |
| Spray irrigation where the maximum storage volume is less than less than 360 gallons (1363 L) | <ul style="list-style-type: none"> Debris excluder or other approved means in compliance with Section 1702.9.10 | N/A |
| Spray irrigation where the maximum storage volume is equal to or greater than 360 gallons (1363 L) | <ul style="list-style-type: none"> Debris excluder or other approved means in compliance with Section 1702.9.10 | <ul style="list-style-type: none"> Escherichia coli: < 100 CFU/100 mL Turbidity: < 10 NTU |
| Urinal and water closet flushing, clothes washing, and | <ul style="list-style-type: none"> Debris excluder or other approved means in | <ul style="list-style-type: none"> Escherichia coli: < 100 CFU/100 mL |

| | | |
|--|---|---|
| <i>trap priming</i> | <i>compliance with Section 1702.9.10</i> <i>• 100 Micron (100 μm) in compliance with Section 1702.9.11</i> | <i>• Turbidity: < 10 NTU</i> |
| <i>Ornamental fountains and other water features</i> | <i>• Debris excluder or other approved means in compliance with Section 1702.9.10</i> | <i>• Escherichia coli: < 100 CFU/100 mL</i> <i>• Turbidity: < 10 NTU</i> |
| <i>Cooling tower make-up water</i> | <i>• Debris excluder or other approved means in compliance with Section 1702.9.10</i> <i>• 100 Micron (100 μm) in compliance with Section 1702.9.11</i> | <i>• Escherichia coli: < 100 CFU/100 mL</i> <i>• Turbidity: < 10 NTU</i> |

TABLE 1602.9.4
MINIMUM WATER QUALITY

| APPLICATION | MINIMUM TREATMENT | MINIMUM WATER QUALITY |
|---|--|---|
| Car washing | Debris excluder or other approved means in accordance with Section 1602.9.10, and 100 Micron (100 μ m) in accordance with Section 1602.9.11 for drip irrigation. | N/A |
| Subsurface and drip irrigation | Debris excluder or other approved means in compliance with Section 1602.9.10, and 100 Micron (100 μ m) in accordance with Section 1702.9.11 for drip irrigation. | N/A |
| Spray irrigation where the maximum storage volume is less than 360 gallons (1363 L) | Debris excluder or other approved means in accordance with Section 1602.9.10, and disinfection in accordance with Section 1602.9.8. | N/A |
| Spray irrigation where the maximum storage volume is equal to or more than 360 gallons (1363 L) | Debris excluder or other approved means in accordance with Section 1602.9.10. | Escherichia coli: < 100 CFU/100 mL, and Turbidity: < 10 NTU |
| Urinal and water closet flushing, clothes washing, and trap priming | Debris excluder or other approved means in accordance with Section 1602.9.10, and 100 Micron (100 μ m) in accordance with | Escherichia coli: < 100 CFU/100 mL, Turbidity: < 10 NTU |

| | | |
|---|--|---|
| | Section 1602.9.11. | |
| Ornamental fountains and other water features | Debris excluder or other approved means in accordance with Section 1602.9.10. | Escherichia coli: < 100 CFU/100 mL, Turbidity: < 10 NTU |
| Cooling tower make up water | Debris excluder or other approved means in accordance with Section 1602.9.10, and 100 Micron (100 μ m) in accordance with Section 1602.9.11. | Escherichia coli: < 100 CFU/100 mL, Turbidity: < 10 NTU |

For SI units: 1 micron = 1 μ m, 1 gallon = 3.785 L

1602.9.5 (Formally 1702.9.5 Rainwater Storage Tanks. Rainwater storage tanks shall be constructed and installed in accordance with Section 1602.9.5.1 through Section 1602.9.5.8.

1602.9.5.1 (Formally 1702.9.5.1 Construction. Rainwater storage shall be constructed of solid, durable materials not subject to excessive corrosion ...

1602.9.5.2 (Formally 1702.9.5.2) Location. Rainwater storage tanks shall be permitted to be installed above or below grade.

1602.9.5.3 (Formally 1702.9.5.3) Above Grade. Above grade storage tanks shall be of an opaque material, approved for aboveground use ...

1602.9.5.4 (Formally 1702.9.5.4) Below Grade. Rainwater storage tanks installed below grade shall be structurally designed to withstand ... provided with manholes. *Below-grade storage tanks, located outside of the building, shall be provided with either a manhole not less than 24 inches (610 mm) square or a manhole with an inside diameter of not less than 24 inches (610 mm) Service ports in manhole covers shall be not less than 8 inches (203 mm) in diameter. The manhole opening shall be ...*

1602.9.5.5 (Formally 1702.9.5.5) Drainage and Overflow. Rainwater storage tanks shall be provided with a means of draining and cleaning. The overflow drain shall not be equipped with a shutoff valve. The ... valve or other approved method. *Backwater valves shall be installed so that access is provided to the working parts for service and repair.*

1602.9.5.5.1 (Formally 1702.9.5.5(A)) Overflow Outlet Size. The overflow outlet shall be sized to accommodate the flow of the rainwater entering the tank ...

1602.9.5.6 (Formally 1702.9.5.6(A)) Opening and Access Protection. Rainwater tank openings shall be protected to prevent the entrance of insects, birds, or rodents into the tank *and piping systems. Screens installed on vent pipes, inlets, and overflow pipes shall have an aperture of not greater than 1/16 of an inch (1.6mm) and shall be close fitting.*

Rainwater tank access openings exceeding 12 inches (305 mm) in ...

1602.9.5.6(BA) (Formally 1702.9.5.6(B)) Human Access. *A minimum of one access opening shall be provided to allow inspection and cleaning. Rainwater tank manholes and access openings shall be secured by either a lockable device or other approved method to prevent unauthorized access.*

1602.9.5.7 (Formally 1702.9.5.8) Marking. Rainwater tanks shall be permanently marked with the capacity and the language: "NONPOTABLE RAINWATER." ...

1602.9.5.8 Storage Tank Venting. Where venting by means of drainage or overflow piping is not provided, or is considered insufficient, a vent shall ...

1602.9.5.8 (Formally 1702.9.5.7) Venting. *Rainwater tanks shall be provided with a vent sized in accordance with this code, and based on the size ...*

1602.9.6 (Formally 1709.9.6) Pumps. Pumps serving rainwater catchment systems shall be listed. Pumps supplying water to water closets, urinals, and trap ...

1602.9.7 (Formally 1709.9.7) Roof Drains. Primary and secondary roof drains,...

1602.9.8 (Formally 1709.9.8) Water Quality Devices and Equipment. Devices and equipment used to treat rainwater to maintain the minimum water ...

1602.9.9 (Formally 1709.9.9) Freeze Protection. Tanks and piping installed in locations subject to ...

1602.9.10 (Formally 1709.9.10) Debris Removal. The rainwater catchment conveyance system shall be equipped with a debris ...

1602.9.11 (Formally 1709.0.11) Required Filters. A filter permitting the passage of particulates not larger than 100 microns (100 µm) shall be provided for rainwater supplied to ...

1602.9.12 (Formally 1709.9.12) Roof Gutters. Gutters shall maintain a minimum slope and be sized in accordance ...

1602.10 (Formally 1702.10) Signs. Signs in buildings using rainwater water shall be in accordance with Section 1602.10.1 and Section 1602.10.2 *and shall comply with the California Building Code.*

1602.10.1 (Formally 1702.10.1) Commercial, Industrial, Institutional and Residential Restroom Signs. A sign shall be installed in restrooms in commercial, industrial, and institutional occupancies, *and shall also be installed in residential common use area restrooms* using nonpotable rainwater for water closets, urinals, or both. The number ...

1602.10.2 (Formally 1702.10.2) Equipment Room Signs. Each equipment room containing nonpotable rainwater equipment shall have a sign posted ...

1602.11 (Formally 1702.11) Inspection and Testing. Rainwater catchment systems shall be inspected

and tested in ...

1602.11.1 (Formally 1702.11.1) Supply System Inspection and Test. Rainwater catchment systems shall be inspected and tested in ...

1602.11.2 (Formally 1702.11.2) Cross-Connection Inspection and Testing. An initial inspection and test in accordance ...

1602.11.2.1 (Formally 1702.11.2.1) Visual System Inspection. Prior to commencing the cross-connection testing, a dual system ...

(1) Pumps, equipment, equipment room signs, and ...

1602.11.2.2 (Formally 1702.11.2.2) Cross-Connection Test. The procedure for determining cross-connection shall be followed by the ...

(1) The potable water system shall be ...

(2) The potable water system shall remain pressurized ...

(3) Fixtures, potable and rainwater, shall be tested and inspected ...

(4) The drain on the rainwater catchment water system shall be checked...

(5) The potable water system ...

(6) The rainwater catchment water system shall ...

(7) The rainwater catchment water system shall remain pressurized..

(8) Fixtures, potable and rainwater catchment, shall be ...

(9) The drain on the potable water system shall be checked for ...

(10) Where there is no flow detected in the fixtures which...

1602.11.2.3 (Formally 1702.11.2.3) Discovery of Cross-Connection. In the event that a cross-connection is discovered, the following procedure, in the ..

(1) Rainwater catchment water piping to the ...

(2) Potable water piping to the building shall be shut ...

(3) The cross-connection shall be ...

(4) The building shall be retested following procedures...

(5) The potable water system shall be chlorinated with 50 ppm ...

(6) The potable water system shall be flushed after 24 hours, and a ...

1602.11.2.4 Annual Inspection. An annual inspection of the rainwater catchment water system, following the procedures listed in Section 1602.11.2.1 shall be required. Annual cross-connection testing, following the procedures listed in Section 1602.11.2.2 shall be required by the Authority Having Jurisdiction, unless site conditions do not require it. In no event shall the test occur less than once in 4 years. Alternate testing requirements shall be permitted by the Authority Having Jurisdiction.

Notation:

Authority: Health & Safety Code Sections 18928 and 18934.5

Reference(s): Health & Safety Code Sections 18928, 18928.1 and 18934.5

ITEM 15. BSC proposes to adopt Chapter 17 of the 2015 UPC with the following amendments.

**TABLE 1701.1 (Formally 1401.1)
REFERENCED STANDARDS**

1701.0 (Formally 1401.0) General.

1701.1 (Formally 1401.1) Standards. The standards listed in Table 1701.1 are intended for use in the design, testing, and installation of materials, devices, appliances, and equipment regulated by this code.

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|---|---|---------------|------------------------------------|
| ... | | | |
| NSF 169 – <u>2009</u> <u>2012</u> | Special Purpose Food Equipment and Devices | Appliances | 301.42.2, 301.2 |
| <i>NSF/ANSI 350 – 2011-2012 [BSC]</i> | <i>Onsite Residential and Commercial Water Reuse Treatment Systems, as amended*</i> <i>NSF/ANSI 350, amended sections follow:</i> 5.6 Electrical components. Electrical components The California Electrical Code shall be followed for all electrical components, system installation, and system operation. | Miscellaneous | 1604.10.2 <u>1504.7</u> |
| ... | | | |

Notation:

Authority: Health and Safety Code Sections 18928, 18930.5, 18941.8

Reference: Health and Safety Code Section 18941.8, Water Code Section 14877.1

ITEM 16. BSC proposes to adopt Appendix A, B, D, H, I, and J of the 2015 UPC without amendments.

Notation:

Authority: Health & Safety Code Sections 18928 and 18934.5

Reference(s): Health & Safety Code Sections 18928, 18928.1 and 18934.5

**ADDENDUM TO FINAL EXPRESS TERMS
FOR
PROPOSED BUILDING STANDARDS
OF THE
CALIFORNIA BUILDING STANDARDS COMMISSION (BSC)

REGARDING PROPOSED ADOPTION OF THE 2015
UNIFORM PLUMBING CODE (UPC) FOR THE
CALIFORNIA CODE OF REGULATIONS, TITLE 24, PART 5**

(The State agency shall draft the regulations in plain, straightforward language, avoiding technical terms as much as possible and using a coherent and easily readable style. The agency shall draft the regulation in plain English. A notation shall follow the express terms of each regulation listing the specific statutes authorizing the adoption and listing specific statutes being implemented, interpreted, or made specific. (PART 1 – ADMINISTRATIVE CODE))

LEGEND FOR EXPRESS TERMS

1. Existing California amendments or code language being modified are in italics when they appear in the model code text: All such language appears in *italics*, modified language is underlined.
2. New California amendments: All such language appears underlined and in italics.
3. Repealed text: All such language appears in ~~strikeout~~.
4. Notation: Authority and reference citations are provided at the end of each chapter.

FINAL EXPRESS TERMS

ITEM 12. BSC proposes to NOT adopt Chapter 14 of the 2015 UPC with the following amendments.

**CHAPTER 14
FIRESTOP PROTECTION**

Notation:

Authority: Health & Safety Code Sections 18928 and 18934.5

Reference(s): Health & Safety Code Sections 18928, 18928.1 and 18934.5

**FINAL EXPRESS TERMS
FOR
PROPOSED BUILDING STANDARDS
OF THE
DIVISION OF THE STATE ARCHITECT (DSA-AC)**

**REGARDING PROPOSED CHANGES TO
THE CALIFORNIA PLUMBING CODE
CALIFORNIA CODE OF REGULATIONS, TITLE 24, PART 5**

**2016 CALIFORNIA PLUMBING CODE
TRIENNIAL CODE CYCLE**

LEGEND FOR EXPRESS TERMS

1. Existing California amendments or code language being modified are in *italics* when they appear in the model code text: All such language appears in *italics*, modified language is underlined.
2. New California amendments: All such language appears underlined and in italics.
3. Repealed text: All such language appears in ~~strikeout~~.

FINAL EXPRESS TERMS

DSA-AC proposes to carry forward its adoption of existing California amendments from the 2013 CA Plumbing Code into the 2016 CA Plumbing Code, with further amendment as indicated.

**CHAPTER 1
SCOPE AND ADMINISTRATION
DIVISION I
CALIFORNIA ADMINISTRATION**

ITEM 1.00

CHAPTER 1, DIVISION I – MATRIX ADOPTION TABLE

| Adopting Agency | | DSA-AC |
|---|--|----------|
| Adopt entire California Chapter | | |
| Adopt entire California Chapter as amended (amended Sections listed below) | | |
| Adopt only those Sections that are listed below | | X |
| Chapter / Section | | |
| 1.9.0 | | X |
| 1.9.1 | | X |
| <u>1.9.1.1</u> | | <u>X</u> |

ITEM 1.01

**SECTION 1.9
DIVISION OF THE STATE ARCHITECT**

1.9.1 Division of the State Architect – Access Compliance.

Note: For applications listed in Section 1.9.1 of the California Building code, regulated by the Division of the State Architect—Access Compliance, see California Code of Regulations, Title 24, Part 2 (California Building Code), Chapter 1 (Division 1 California Administration) under authority cited by Government Code Section 4450 and in reference cited by Government Code Section 4450 through 4461, 12955.1, and Health and Safety Code Sections 18949.1, 19952 through 19959.

Buildings or facilities where accessibility is required for applications listed in California Code of Regulations, Title 24, Part 2 (California Building Code), Chapter 1, Section 1.9.1 regulated by the Division of the State Architect—Access Compliance shall comply with Title 24, Part 2, Chapter 11A or 11B, as applicable under authority cited by CA Government Code Section 4450 and in reference cited by CA Government Code Sections 4450 through 4461, 12955.1(c), and CA Health and Safety Code Sections 18949.1, 19952 through 19959.

1.9.1.1 Adopting agency identification. The provisions of this code applicable to buildings identified in this Subsection 1.9.1 will be identified in the Matrix Adoption Tables under the acronym DSA-AC.

**CHAPTER 4
PLUMBING FIXTURES AND FIXTURE FITTINGS**

ITEM 4.00

CHAPTER 4 — MATRIX ADOPTION TABLE

| Adopting Agency | DSA-AC |
|---|--------|
| Adopt entire Chapter | |
| Adopt entire Chapter as amended (amended Sections listed below) | |
| Adopt only those Sections that are listed below | X |
| Chapter / Section | |
| Note under chapter title | X |
| <u>422.1.2</u> | X |
| Table 422.1, <u>Note 4</u> | X |

ITEM 4.01

**CHAPTER 4
PLUMBING FIXTURES AND FIXTURE FITTINGS**

~~**Note:** In addition the requirements of this chapter, which provide access to, or egress from, buildings or facilities where accessibility is required for applications listed in Section 109, of the California Building Code, regulated by the Division of the State Architect—Access Compliance shall also comply with Chapter 11A for public housing and Chapter 11B for public accommodations under authority cited by Gov. Code §4450 and in reference cited by Gov. Code §4450 through 4461, 12955.1 and H&SC §18949.1, 19952 through 19959.~~

In addition to the requirements of this chapter, buildings or facilities where accessibility is required for applications listed in California Code of Regulations, Title 24, Part 2 (California Building Code), Chapter 1, Section 1.9.1 regulated by the Division of the State Architect—Access Compliance shall also comply with Title 24, Part 2, Chapter 11A or 11B, as applicable under authority cited by CA Government Code Section 4450 and in reference cited by CA Government Code Sections 4450 through 4461, 12955.1(c), and CA Health and Safety Code Sections 18949.1, 19952 through 19959.

ITEM 4.02

422.0 Minimum Number of Required Fixtures.

422.1 Fixture Count. ...

422.1.2 ~~[DSA-AS]~~ [DSA-AC] *Effective January 1, 1990, in new construction and those existing facilities which occupancy type are listed in Tables 422.1 and 4-4 for public use, which apply for permit to undertake construction, structural alterations, repairs or improvement which exceed 50 percent of the square footage of the entire facility, shall install water closets, urinals, lavatories and drinking fountains as stipulated in Tables 422.1 and 4-4 for public use. Community and/or municipal parks with a bleacher capacity not exceeding 500 seats shall be exempt from the requirements of this section and Tables 422.1 and 4-4. Each bathroom shall comply with Part 2, Chapter 11A and 11B of the California Building Code.*

ITEM 4.03

422.0 Minimum Number of Required Fixtures.

422.1 Fixture Count. ...

**TABLE 422.1
MINIMUM PLUMBING FACILITIES ...**

Notes:

1 ...

2 ...

3 ...

4 [DSA-AC] *In accordance with Sections 1.8.7 and ~~301.2~~ 301.3, the Authority Having Jurisdiction may approve alternative designs criteria when determining the minimum number of plumbing fixtures.*

Notation

Authority: Government Code Section 4450.

References: Government Code Sections 4450 through 4461, and 12955.1(c); Health and Safety Code Sections 18949.1, 19952 through 19959.

**FINAL EXPRESS TERMS
FOR
PROPOSED BUILDING STANDARDS
OF THE
DIVISION OF THE STATE ARCHITECT - STRUCTURAL SAFETY (DSA-SS AND DSA-SS/CC)

REGARDING PROPOSED CHANGES TO
CALIFORNIA PLUMBING CODE
CALIFORNIA CODE OF REGULATIONS, TITLE 24, PART 5**

The California Building Standards Code (California Code of Regulations, Title 24, Part 1, 2, 2.5, 3, 4, 5, 6, 8, 9, 10, 11, and 12) is published in its entirety every three years and is applicable to all buildings for which an application for a building permit is made during the Code's effective period. Each triennial edition of the California Building Standards Code becomes effective 180 days after its publication.

These proposed regulations will make effective the 2015 edition of the Uniform Plumbing Code (UPC) as the 2016 edition California Plumbing Code (CPC), for application by DSA-SS (Division of the State Architect – Structural Safety) to public elementary and secondary schools, community colleges, and state-owned or state-leased essential services buildings.

These proposed regulations will also make effective the 2015 edition of the UPC as the 2016 edition CPC, for application by DSA-SS/CC (Division of the State Architect – Structural Safety/Community Colleges) to community colleges, which a community college district may elect to use in lieu of standards promulgated by DSA-SS (refer to Education Code Section 81053).

Further, these proposed regulations will repeal the 2012 edition UPC articles adopted as the 2013 edition CPC.

LEGEND FOR EXPRESS TERMS

1. Existing California amendments or code language being modified are in *italics* when they appear in the model code text: All such language appears in *italics*, modified language is underlined.
2. New California amendments: All such language appears underlined and in italics.
3. Repealed text: All such language appears in ~~strikeout~~.

EXPRESS TERMS

**CALIFORNIA PLUMBING CODE
CHAPTER 1 - ADMINISTRATION**

Continue Chapter 1, Division I (California Administration) of the 2013 triennial edition of the CPC for publication in the 2016 triennial edition of the CPC, with DSA proposed editorial amendments as shown below:

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|---|--------|-----------|---|
| Adopt only those sections that are listed below | X | X | |
| 1.1.1 Title | X | X | |
| 1.1.2 Purpose | X | X | |
| 1.1.3 Scope | X | X | DSA-SS adopts Item 11 of Article 1.1.3. |

| | | | |
|---|---|---|--|
| 1.1.4 Appendices | X | X | |
| 1.1.5 Referenced Codes | X | X | |
| 1.1.6 Non-Building Standards, Orders and Regulations | X | X | |
| 1.1.7 Order of Precedence and Use | X | X | |
| 1.1.8 City, County, or City and County Amendments, Additions or Deletions | X | X | |
| 1.1.9 Effective Date of this Code | X | X | |
| 1.1.10 Availability of Codes | X | X | |
| 1.1.11 Format | X | X | |
| 1.1.12 Validity | X | X | |
| 1.9.0 Division of the State Architect | | | |
| 1.9.1 (Reserved for the DSA-AC) | | | |
| 1.9.2 DSA-SS | X | | |
| 1.9.2.1 DSA-SS | X | | |
| 1.9.2.2 DSA-SS/CC | | X | |

**CHAPTER 1
ADMINISTRATION
DIVISION I
CALIFORNIA ADMINISTRATION**

1.1.0 General.

1.1.1 Title. *These regulations shall be known as the California Plumbing Code, may be cited as such and will be referred to herein as "this code." The California Plumbing Code is Part 5 of twelve parts of the official compilation and publication of the adoption, amendment, and repeal of plumbing regulations to the California Code of Regulations, Title 24, also referred to as the California Building Standards Code. This part incorporates by adoption the 2012 2015 Uniform Plumbing Code of the International Association of Plumbing and Mechanical Officials with necessary California amendments.*

1.1.2 Purpose. *The purpose of this code is to establish the minimum requirements to safeguard the public health, safety and general welfare through structural strength, means of egress facilities, stability, access to persons with disabilities, sanitation, adequate lighting and ventilation, and energy conservation; safety to life and property from fire and other hazards attributed to the built environment; and to provide safety to fire fighters and emergency responders during emergency operations.*

1.1.3 Scope. *The provisions of this code shall apply to the construction, alteration, movement, enlargement, replacement, repair, equipment, use and occupancy, location, maintenance, removal and demolition of every building or structure or any appurtenances connected or attached to such buildings or structures throughout the State of California.*

1.1.3.1 Non-State-Regulated Buildings, Structures, and Applications. *Except as modified by local ordinance pursuant to Section 1.1.8, the following standards in the California Code of Regulations, Title 24, Parts 2, 2.5, 3, 4, 5, 6, 9, 10 and 11 shall apply to all occupancies and applications not regulated by a state agency.*

1.1.3.2 State-Regulated Buildings, Structures, and Applications. *The model code, state amendments to the model code, and/or state amendments where there are no relevant model code provisions, shall*

apply to the following buildings, structures, and applications regulated by state agencies as referenced in the Matrix Adoption Tables and as specified in Section 1.2.0 through 1.14.0, except where modified by local ordinance pursuant to Section 1.1.8. When adopted by a state agency, the provisions of this code shall be enforced by the appropriate enforcing agency, but only to the extent of authority granted to such agency by the state Legislature.

Note: See Preface to distinguish the model code provisions from the California provisions.

- 1) ...
- 2) ...
- 3) ...
- 4) ...
- 5) ...
- 6) ...
- 7) ...
- 8) ...
- 9) ...
- 10) ...
- 11) Public elementary and secondary schools, community college buildings and state-owned or state-leased essential service buildings regulated by the Division of the State Architect. See Section 1.9.2 for additional scope provisions.
- 12) ...
- 13) ...
- 14) ...
- 15) ...
- 16) ...
- 17) ...
- 18) ...

1.1.4 Appendices. Provisions contained in the appendices of this code shall not apply unless specifically adopted by a state agency or adopted by a local enforcing agency in compliance with Health and Safety Code Section 18901 et. seq. for Building Standards Law, Health and Safety Code Section 17950 for State Housing Law and Health and Safety Code Section 13869.7 for Fire Protection Districts. See Section 1.1.8 of this code.

1.1.5 Referenced Codes. The codes, standards and publications adopted and set forth in this code, including other codes, standards and publications referred to therein are, by title and date of publication, hereby adopted as standard reference documents of this code. When this code does not specifically cover any subject related to building design and construction, recognized architectural or engineering practices shall be employed. The National Fire Codes, standards, and the Fire Protection Handbook of the National Fire Protection Association are permitted to be used as authoritative guides in determining recognized fire prevention engineering practices.

1.1.6 Non-Building Standards, Orders and Regulations. Requirements contained in the Uniform Plumbing Code, or in any other referenced standard, code or document, which are not building standards as defined in Health and Safety Code Section 18909, shall not be construed as part of the provisions of this code. For nonbuilding standards, orders, and regulations, see other titles of the California Code of Regulations.

1.1.7 Order of Precedence and Use.

1.1.7.1 Differences. In the event of any differences between these building standards and the standard reference documents, the text of these building standards shall govern.

1.1.7.2 Specific Provisions. Where a specific provision varies from a general provision, the specific provision shall apply.

1.1.7.3 Conflicts. When the requirements of this code conflict with the requirements of any other part of the California Building Standards Code, Title 24, the most restrictive requirements shall prevail.

1.1.8 City, County, or City and County Amendments, Additions or Deletions.

...

1.1.9 Effective Date of this Code. Only those standards approved by the California Building Standards Commission that are effective at the time an application for building permit is submitted shall apply to the plans and specifications for, and to the construction performed under, that permit. For the effective dates of the provisions contained in this code, see the History Note page of this code.

1.1.10 Availability of Codes. At least one complete copy each of Titles 8, 19, 20, 24, and 25 with all revisions shall be maintained in the office of the building official responsible for the administration and enforcement of this code. Each state department concerned and each city, county or city and county shall have an up-to-date copy of the code available for public inspection, See Health and Safety Code Section 18942 (d) (1) and (2).

1.1.11 Format. This part fundamentally adopts the Uniform Plumbing Code by reference on a chapter-by-chapter basis. When a specific chapter of the Uniform Plumbing Code is not printed in the code and is marked "Reserved", such chapter of the Uniform Plumbing Code is not adopted as a portion of this code. When a specific chapter of the Uniform Plumbing Code is marked "Not Adopted by the State of California" but appears in the code, it may be available for adoption by local ordinance.

Note: Matrix Adoption Tables at the front of each chapter may aid the code user in determining which chapter or sections within a chapter are applicable to buildings under the authority of a specific state agency, but are not to be considered regulatory.

1.1.12 Validity. If any chapter, section, subsection, sentence, clause or phrase of this code is for any reason held to be unconstitutional, contrary to statute, exceeding the authority of the state as stipulated by statutes or otherwise inoperative, such decision shall not affect the validity of the remaining portion of this code

...

1.9.0 Division of the State Architect.

1.9.1 (Reserved for DSA-AC)

1.9.2 Division of the State Architect - Structural Safety.

1.9.2.1 DSA-SS (Division of the State Architect – Structural Safety).

Application - Public elementary and secondary schools, community college buildings, and state-owned or state-leased essential services buildings.

Enforcing Agency – {Division of the State Architect} – Structural Safety (DSA-SS).

The Division of the State Architect has been delegated the responsibility and authority by the Department of General Services to review and approve the design and observe the construction of public elementary and secondary schools, community colleges, and state-owned or state-leased essential services buildings.

Authority Cited - Education Code Section 17310 and 81142, and Health and Safety Code Section 16022.

References - Education Code Sections 17280 through 17317 and 81130 through 81147, and Health and Safety Code Sections 16000 through 16023.

1.9.2.1.1 Adopting Agency Identification.

The provisions of this code applicable to buildings identified in this Subsection 1.9.2 will be identified in the Matrix Adoption Tables under the acronym DSA SS.

1.9.2.2 DSA-SS/CC (Division of the State Architect – Structural Safety/Community Colleges).

Application - Community Colleges.

The Division of the State Architect has been delegated the authority by the Department of General Services to promulgate alternate building standards for application to community colleges, which a community college may elect to use in lieu of standards promulgated by DSA-SS in accordance with Section 1.9.2.1. Refer to Title 24, Part 2, Section 1.9.2.2.

Enforcing Agency - Division of the State Architect – Structural Safety/Community Colleges (DSA-SS/CC)

The Division of the State Architect has been delegated the authority by the Department of General Services to review and approve the design and ~~oversee~~ observe construction of community colleges electing to use the alternative building standards as provided in this section.

Authority Cited - Education Code Section 81053.

References - Education Code Sections 81052, 81053, and 81130 through 81147.

1.9.2.2.1 Adopting Agency Identification.

The provisions of this code applicable to buildings identified in this Subsection 1.9.2.2 will be identified in the Matrix Adoption Tables under the acronym DSA SS/CC.

...

**DIVISION II
ADMINISTRATION**

...

**CALIFORNIA PLUMBING CODE
CHAPTER 2 - DEFINITIONS**

Repeal Chapter 2 (Definitions) of the 2012 edition UPC.

Adopt Chapter 2 (Definitions) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

**CALIFORNIA PLUMBING CODE
CHAPTER 3 - GENERAL REGULATIONS**

Repeal Chapter 3 (General Regulations) of the 2012 edition UPC.

Adopt Chapter 3 (General Regulations) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

**CALIFORNIA PLUMBING CODE
CHAPTER 4 - PLUMBING FIXTURES AND FIXTURE FITTINGS**

Repeal Chapter 4 (Plumbing Fixtures and Fixture Fittings) of the 2012 edition UPC.

Adopt Chapter 4 (Plumbing Fixtures and Fixture Fittings) of the 2015 edition UPC with existing DSA amendments continued and proposed editorial amendments shown below for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|--|--------|-----------|----------|
| Adopt Entire Chapter | | | |
| Adopt Entire Chapter as amended (amended sections listed below) | X | X | |
| <u>407.2.2.1 Metering Faucet Flow Rate</u> | X | X | |
| <u>408.2.1 Single Shower Head Flow Rate</u> | X | X | |
| <u>408.2.2 Multiple Shower Head Flow Rate</u> | X | X | |
| <u>411.2.2.1 Flushometer Valve Flow Rate</u> | X | X | |
| <u>411.2.3 Water Closets</u> | X | X | |
| <u>412.1.2 Urinal Flow Rate (wall mount)</u> | X | X | |
| <u>412.1.3 Urinal Flow Rate (floor mount)</u> | X | X | |
| <u>417.1.1 Wash Fountain Flow Rate</u> | X | X | |
| <u>417.1.2 Metering Faucet Flow Rate</u> | X | X | |
| <u>420.2.1 Kitchen Faucet Flow Rate</u> | X | X | |
| <u>Table A. Occupant Load Factor</u> | X | X | |
| <u>Table 422.1 Minimum Plumbing Facilities (Footnote-4 7)</u> | X | X | |
| <u>Table A. Occupant Load Factor</u> | X | X | |

**CHAPTER 4
PLUMBING FIXTURES AND FIXTURE FITTINGS**

...

407.0 Lavatories.

407.1 Application. Lavatories shall comply with ASME A112.19.1/CSA B45.2, ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, ASME A112.19.12, CSA B45.5/IAPMO Z124, or CSA B45.11/IAPMO Z401.

407.2 Water Consumption. The maximum water flow rate of faucets shall comply with Section 407.2.1 and Section 407.2.2.

407.2.1 Maximum Flow Rate. The maximum flow rate for public lavatory faucets shall not exceed 0.5 gpm at 60 psi (1.9 L/m at 414 kPa) and 2.2 gpm at 60 psi (8.3 L/m at 414 kPa) for private lavatory faucets in accordance with ASME A112.18.1/CSA B125.1.

407.2.2 Metering Faucets. Metered faucets shall deliver a maximum of 0.25 gallons (1.0 L) per metering cycle in accordance with ASME A112.18.1/CSA B125.1.

407.2.2.1 [DSA-SS & DSA-SS/CC] Metering Faucets shall not deliver more than 0.20 gallons (0.76 L) per cycle in compliance with Chapter 5, Division 5.3 of the California Green Building Standards Code (CALGreen).

...

408.0 Showers.

408.1 Application. Manufactured shower receptors and shower bases shall comply with ASME A112.19.1/CSA B45.2, ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, or CSA B45.5/IAPMO Z124.

408.2 Water Consumption. Showerheads shall have a maximum flow rate of not more than 2.5 gpm at 80 psi (9.5 L/m at 552 kPa), in accordance with ASME A112.18.1/CSA B125.1.

408.2.1 Single Showerhead. [DSA-SS & DSA-SS/CC] Showerheads shall have a maximum flow rate of not more than 2.0 gallons per minute at 80 psi. Showerheads shall be certified to the performance criteria of the U.S. EPA WaterSense Specification for Showerheads in compliance with Chapter 5, Division 5.3 of the California Green Building Standards Code (CALGreen).

408.2.2 Multiple Showerheads Serving One Shower. [DSA-SS & DSA-SS/CC] When a shower is served by more than one showerhead, the combined flow rate of all showerheads and/or other shower outlets controlled by a single valve shall not exceed 2.0 gallons per minute at 80 psi, or the shower shall be designed to allow only one shower outlet to be in operation at a time in compliance with Chapter 5, Division 5.3 of the California Green Building Standards Code (CALGreen).

Note: A hand-held shower shall be considered a showerhead.

...

411.0 Water Closets.

411.1 Application. Water closets shall comply with ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, or CSA B45.5/IAPMO Z124. Water closet bowls for public use shall be of the elongated type. In nurseries, schools, and other similar places where plumbing fixtures are provided for the use of children less than 6 years of age, water closets shall be of a size and height suitable for children's use.

411.2 Water Consumption. Water closets shall have a maximum consumption not to exceed 1.6 gallons (6.0 Lpf) of water per flush in accordance with ASME A112.19.2/CSA B45.1.

411.2.1 Dual Flush Water Closets. Dual flush water closets shall comply with ASME A112.19.14. The effective flush volume for dual flush water closets shall be defined as the composite, average flush volume of two reduced flushes and one full flush.

411.2.2 Flushometer Valve Activated Water Closets. Flushometer valve activated water closets shall have a maximum flush volume of 1.6 gallons (6.0 Lpf) of water per flush in accordance with ASME A112.19.2/CSA B45.1

411.2.2.1 Flushometer Valve Activated Water Closets. [DSA-SS & DSA-SS/CC] *Flushometer valve activated water closets shall have a maximum flush volume of 1.28 gallons (4.8 L) of water per flush in accordance with ASME A112.19.2/CSA B45.1.*

411.2.3 Water Closets [DSA-SS & DSA-SS/CC] *The effective flush volume of all water closets shall not exceed 1.28 gallons per flush. Tank-type water closets shall be certified to the performance criteria of the U.S. EPA WaterSense Specification for Tank-Type Toilets in compliance with Chapter 5, Division 5.3 of the California Green Building Standards Code (CALGreen).*

...

412.0 Urinals.

412.1 Application. Urinals shall comply with ASME A112.19.2/CSA B45.1, ASME A112.19.19, or CSA B45.5/IAPMO Z124. Urinals shall have an average water consumption not to exceed 1 gallon (3.8 Lpf) of water per flush.

412.1.1 Nonwater Urinals. ...

403.3.2 412.1.2 Wall Mounted Urinals. [DSA-SS & DSA-SS/CC] ...

403.3.3 412.1.3 Floor Mounted Urinals. [DSA-SS & DSA-SS/CC] ...

...

417.0 Faucets and Fixture Fittings.

417.1 Application. Faucets and fixture fittings shall comply with ASME A112.18.1/CSA B125.1. Fixture fittings covered under the scope of NSF 61 shall be in accordance with the requirements of NSF 61.

417.1.1 Wash Fountains. [DSA-SS & DSA-SS/CC] *Wash fountains shall have a maximum flow rate of not more than 1.8 gallons per minute/20 [rim space (inches) at 60 psi] in compliance with Chapter 5, Division 5.3 of the California Green Building Standards Code (CALGreen).*

417.1.2 Metering Faucets for Wash Fountains. [DSA-SS & DSA-SS/CC] *Metering faucets for wash fountains shall not deliver more than 0.20 gallons per cycle/20 [rim space (inches) at 60 psi] in compliance with Chapter 5, Division 5.3 of the California Green Building Standards Code (CALGreen).*

...

420.0 Sinks.

420.1 Application. Sinks shall comply with ASME A112.19.1/CSA B45.2, ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, or CSA B45.5/IAPMO Z124. Moveable sink systems shall comply with ASME A112.19.12.

420.2 Water Consumption. Sink faucets shall have a maximum flow rate of not more than 2.2 gpm at 60 psi (8.3 L/m at 414 kPa) in accordance with ASME A112.18.1/CSA B125.1.

Exceptions:

- (1) Clinical sinks
- (2) Laundry trays
- (3) Service sinks

420.2.1 Kitchen Faucets. [DSA-SS & DSA-SS/CC] Kitchen faucets shall have a maximum flow rate of not more than 1.8 gallons per minute at 60 psi. Kitchen faucets may temporarily increase the flow above the maximum rate, but not to exceed 2.2 gallons per minute at 60 psi, and must default to a maximum flow rate of 1.8 gallons per minute at 60 psi in compliance with Chapter 5, Division 5.3 of the California Green Building Standards Code (CALGreen).

...

**Table 422.1
MINIMUM PLUMBING FACILITIES¹**

Each building shall be provided with sanitary facilities, including provisions for persons with disabilities as prescribed by the Department Having Jurisdiction.^{4, 7} Table 422.1 applies to new buildings, additions to a building, and changes of occupancy or type in an existing building resulting in increased occupant load.

For requirements for persons with disabilities, Chapter 11A or 11B of the California Building Code shall be used.

The total occupant load shall be determined in accordance with the [DSA-SS & DSA-SS/CC] Occupant Load Factor Table A.

| TYPE OF OCCUPANCY ² | WATER CLOSETS (FIXTURES PER PERSON) ³ | URINALS (FIXTURES PER PERSON) ⁴ | LAVATORIES (FIXTURES PER PERSON) ^{5, 6} | BATHTUBS OR SHOWERS (FIXTURES PER PERSON) | DRINKING FOUNTAINS/FACILITIES (FIXTURES PER PERSON) | OTHER |
|--------------------------------|---|---|---|--|--|-------|
| A-1 | | | | | | |
| A-2 | | | | | | |
| A-3 | | | | | | |
| A-4 | | | | | | |
| A-5 | | | | | | |
| B | | | | | | |
| E | | | | | | |
| F1, F2 | | | | | | |
| I-1 | | | | | | |
| I-2 | | | | | | |
| I-3 | | | | | | |
| I-4 | | | | | | |
| M | | | | | | |
| R-1 | | | | | | |
| R-2 | | | | | | |
| R-3 | | | | | | |
| R-3 | | | | | | |
| R-4 | | | | | | |
| S-1, S-2 | | | | | | |
| | | | | | | |

STATE OF CALIFORNIA
BUILDING STANDARDS COMMISSION

NOTES:

- 1 The figures shown are based upon one fixture being the minimum required for the number of persons indicated or any fraction thereof.
2. A restaurant is defined as a business that sells food to be consumed on the premises.
 - a. The number of occupants for a drive-in restaurant shall be considered as equal to the number of parking stalls.
 - b. Hand-washing facilities shall be available in the kitchen for employees.
3. The total number of required water closets for females shall be not less than the total number of required water closets and urinals for males.
4. For each urinal added in excess of the minimum required, one water closet shall be permitted to be deducted. The number of water closets shall not be reduced to less than two-thirds of the minimum requirements.
5. Group lavatories that are 24 lineal inches (610 mm) of wash sink or 18 inches (457 mm) of a circular basin, where provided with water outlets for such space, shall be considered equivalent to one lavatory.
6. Metering or self-closing faucets shall be installed on lavatories intended to serve the transient public.
47. [DSA/SS, DSA-SS/CC] In accordance with Sections 1.8.7 and 301.2, the Authority Having Jurisdiction may approve alternative design criteria when determining the minimum number of plumbing fixtures.

TABLE A.
OCCUPANT LOAD FACTOR:
[DSA-SS & DSA-SS/CC]

| OCCUPANCY | OCCUPANT LOAD FACTOR (square feet) (CBC 2001, Table A-29A) |
|---|---|
| Group A | |
| 1. Auditoriums, convention halls, dance floors, lodge rooms, stadiums and casinos (where no fixed seating is provided) (use 1/2 "one-half" the number of fixed seating) | 15 |
| 2. Conference rooms, dining rooms, drinking establishments, exhibit rooms, gymnasiums, lounges, stages and similar uses including restaurants classified as Group B occupancies | 30 |
| 3. Worship places; principal assembly area, educational and activity unit (use 1/2 "one-half" the number of fixed seating) (where no fixed seating is provided) | 30 |
| Group B Office or public buildings (area accessible to the public) | 200 |
| Group E Schools for day care, elementary, secondary | 50 |
| Educational Facilities Other than Group E Colleges, universities, adult center, etc. | 50 |
| Group F Workshop, foundries and similar establishments | 2,000 |
| Group H Hazardous materials fabrication and storage | 2,000 |
| Group I Hospital general use area, health care facilities | 200 |
| Group M Retail or wholesale stores | 200 |

STATE OF CALIFORNIA
BUILDING STANDARDS COMMISSION

| | |
|--|-------|
| Group R Congregate residence, Group R-1 | 200 |
| Group S Warehouse | 5,000 |

* Any uses not specifically listed shall be based on similar uses listed in this table.

** For building or space with mixed occupancies, use appropriate occupancy group for each area (for example, a school may have an "A" occupancy for the gymnasium, a "B" occupancy for the office, an "E" occupancy for the classrooms, etc.)

Accessory areas may be excluded (for example: hallway, restroom, stair enclosure)

**CALIFORNIA PLUMBING CODE
CHAPTER 5 - WATER HEATERS**

Repeal Chapter 5 (Water Heaters) of the 2012 edition UPC.

Adopt Chapter 5 (Water Heaters) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

**CALIFORNIA PLUMBING CODE
CHAPTER 6 - WATER SUPPLY AND DISTRIBUTION**

Repeal Chapter 6 (Water Supply and Distribution) of the 2012 edition UPC.

Adopt Chapter 6 (Water Supply and Distribution) of the 2015 edition UPC with existing DSA amendments continued for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|--|--------|-----------|----------|
| Adopt Entire Chapter | | | |
| Adopt Entire Chapter as amended (amended sections listed below) | X | X | |
| Table 604.1 Materials for Building Supply and Water Distribution Piping and Fittings | X | X | |

**TABLE 604.1
MATERIALS FOR BUILDING SUPPLY AND WATER DISTRIBUTION PIPING AND FITTINGS**

| MATERIAL | BUILDING SUPPLY PIPE AND FITTINGS | WATER DISTRIBUTION PIPE AND FITTINGS | REFERENCED STANDARD(S) PIPE | REFERENCED STANDARD(S) FITTINGS |
|-----------------------------|---|---|---|--|
| Copper and Copper Alloys | X | X | ASTM B42, ASTM B43, ASTM B75, ASTM B88, ASTM B135, ASTM B251, ASTM B302, ASTM B447 | ASME B16.15, ASME B16.18, ASME B16.22, ASME B16.26, ASME B16.51 |
| CPVC | X | X | ASTM D2846, ASTM | ASTM D2846, ASTM |

| | | | | |
|-------------------------|----------------|---|---|---|
| | | | F441, ASTM F442, CSA B137.6 | F437, ASTM F438, ASTM F439, ASTM F1970, CSA B137.6 |
| CPVC-AL- CPVC | X | X | ASTM F2855 | ASTM D2846 |
| Ductile-Iron | X | X | AWWA C151 | ASME B16.4, AWWA C110, AWWA C153 |
| Galvanized Steel | X | X | ASTM A53 | — — |
| Malleable Iron | X | X | — | ASME B16.3 |
| PE | X ¹ | — | ASTM D2239, ASTM D2737, ASTM D3035; AWWA C901, CSA B137.1 | ASTM D2609, ASTM D2683, ASTM D3261, ASTM F1055, CSA B137.1 |
| PE-AL-PE | X | X | ASTM F1282, CSA B137.9 | ASTM F1282, ASTM F1974, CSA B137.9 |
| PE-RT | X | X | ASTM F2769 | ASTM F1807, ASTM F2098, ASTM F2159; ASTM F2735, ASTM F2769 |
| PEX ^{2,3} | X | X | ASTM F876, ASTM F877, CSA B137.5, AWWA C904 ¹ | ASSE 1061, ASTM F877, ASTM F1807, ASTM F1960, ASTM F1961, ASTM F2080, ASTM F2159, ASTM F2735, CSA B137.5 |
| PEX-AL-PEX ⁴ | X | X | ASTM F1281, CSA B137.10, ASTM F2262 | ASTM F1281, ASTM F1974, ASTM F2434, CSA B137.10 |
| PP | X | X | ASTM F2389, CSA B137.11 | ASTM F2389, CSA B137.11 |
| PVC | X ¹ | — | ASTM D1785, ASTM D2241, AWWA C900 | ASTM D2464, ASTM D2466, ASTM D2467, ASTM F1970 |
| Stainless Steel | X | X | ASTM A269, ASTM A312 | — |

1. For Building Supply or cold-water applications.
2. When PEX tubing is placed in soil and is used in potable water systems intended to supply drinking water to fixtures or appliances, the tubing or piping shall be sleeved with a material approved for potable water use in soil or other material that is impermeable to solvents or petroleum products.

STATE OF CALIFORNIA
BUILDING STANDARDS COMMISSION

3. *PEX tubing shall meet or exceed the requirements of ASTM F 876-08 or an equivalent or more stringent standard when used in continuously recirculating hot water systems and the PEX tubing is exposed to the hot water 100% of the time.*
4. **[For DSA/SS, DSA-SS/CC]** *The use of PEX-AL-PEX in potable water supply systems is not adopted.*

...

**CALIFORNIA PLUMBING CODE
CHAPTER 7 - SANITARY DRAINAGE**

Repeal Chapter 7 (Sanitary Drainage) of the 2012 edition UPC.

Adopt Chapter 7 (Sanitary Drainage) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

**CALIFORNIA PLUMBING CODE
CHAPTER 8 - INDIRECT WASTES**

Repeal Chapter 8 (Indirect Wastes) of the 2012 edition UPC.

Adopt Chapter 8 (Indirect Wastes) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

**CALIFORNIA PLUMBING CODE
CHAPTER 9 - VENTS**

Repeal Chapter 9 (Vents) of the 2012 edition UPC.

Adopt Chapter 9 (Vents) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

**CALIFORNIA PLUMBING CODE
CHAPTER 10 - TRAPS AND INTERCEPTORS**

Repeal Chapter 10 (Traps and Interceptors) of the 2012 edition UPC.

Adopt Chapter 10 (Traps and Interceptors) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

**CALIFORNIA PLUMBING CODE
CHAPTER 11 - STORM DRAINAGE**

Repeal Chapter 11 (Storm Drainage) of the 2012 edition UPC.

Adopt Chapter 11 (Storm Drainage) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

**CALIFORNIA PLUMBING CODE
CHAPTER 12 - FUEL GAS PIPING**

Repeal Chapter 12 (Fuel Gas Piping) of the 2012 edition UPC.

Adopt Chapter 12 (Fuel Gas Piping) of the 2015 edition UPC with existing DSA amendments continued with editorial revisions proposed as shown below for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|---|--------|-----------|--|
| Adopt Entire Chapter | X | X | |
| Adopt Entire Chapter as amended (amended sections listed below) | | | |
| Adopt only those sections that are listed below | | | |
| Chapter/Section | | | |
| 1210.18 | | | Note: Sec. 1210.18 (Earthquake-Actuated Gas Shutoff Valves) is printed in Chapter 12 for simplicity and the reader's convenience. Amendment is not applicable to the DSA-SS or DSA-SS/CC occupancies (public schools, community colleges and state essential services buildings). |

**CHAPTER 12
FUEL GAS PIPING**

...

1210.18 Earthquake-Actuated Gas Shutoff Valves. *Earthquake-actuated gas shutoff valves designed to automatically shut off the gas at the location of the valve in the event of a seismic disturbance and, certified by the State Architect as conforming to California Code of Regulations, Title 24, Part 12 Referenced Standards Code (CRSC), Standard 12-4216-1, shall be provided for buildings when such installation is required by local ordinance. Earthquake-actuated gas shutoff valves which have not been certified by the State Architect shall be prohibited in buildings open to the public under mandatory installation by local ordinance. Installation of the valves shall be in accordance with local ordinance, and in the absence of such per the manufacturer's installation instructions.*

An earthquake-actuated gas shutoff valve is a valve for installation in a gas piping system and designed to automatically shut off the gas at the location of the valve in the event of a seismic disturbance.

...

**CALIFORNIA PLUMBING CODE
CHAPTER 13 - HEALTH CARE FACILITIES AND MEDICAL GAS AND
VACUUM SYSTEMS**

STATE OF CALIFORNIA
BUILDING STANDARDS COMMISSION

DSA is not proposing the adoption of Chapter 13 (Health Care Facilities and Medical Gas and Vacuum Systems) of the 2015 edition UPC. DSA did not adopt Chapter 13 (Health Care Facilities and Medical Gas and Vacuum Systems) of the 2012 edition UPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | | | |

CALIFORNIA PLUMBING CODE
CHAPTER 14 – FIRESTOP PROTECTION

DSA is not proposing the adoption of Chapter 14 (Firestop Protection) of the 2015 edition UPC. DSA did not adopt Chapter 15 (Firestop Protection) of the 2012 edition UPC. The State Fire Marshal's Office is responsible for the adoption of fire and life safety standards contained in the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | | | |

CALIFORNIA PLUMBING CODE
**CHAPTER 15 – ALTERNATE WATER SOURCES FOR
NONPOTABLE APPLICATIONS**

DSA is not proposing the adoption of Chapter 15 (Alternate Water Sources for Nonpotable Applications) of the 2015 edition UPC. DSA did not adopt Chapter 16 (Alternate Water Sources for Nonpotable Applications) of the 2012 edition UPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | | | |

CALIFORNIA PLUMBING CODE
**CHAPTER 16 – NONPOTABLE RAINWATER
CATCHMENT SYSTEMS**

DSA is not proposing the adoption of Chapter 16 (Nonpotable Rainwater Catchment Systems) of the 2015 edition UPC. DSA did not adopt Chapter 17 (Nonpotable Rainwater Catchment Systems) of the 2012 edition UPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | | | |

CALIFORNIA PLUMBING CODE
CHAPTER 17 – REFERENCED STANDARDS

Adopt Chapter 17 (Referenced Standards) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

**APPENDIX A – RECOMMENDED RULES FOR SIZING
THE WATER SUPPLY SYSTEM**

Repeal Appendix A (Recommended Rules for Sizing the Water Supply System) of the 2012 edition UPC. Adopt Appendix A (Recommended Rules for Sizing the Water Supply System) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

APPENDIX B – EXPLANATORY NOTES ON COMBINATION WASTE AND VENT SYSTEMS

Repeal Appendix B (Explanatory Notes on Combination Waste and Vent Systems) of the 2012 edition UPC.

Adopt Appendix B (Explanatory Notes on Combination Waste and Vent Systems) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

APPENDIX C – ALTERNATE PLUMBING SYSTEMS

DSA is not proposing the adoption of Appendix C (Alternate Plumbing Systems) of the 2015 edition UPC. DSA did not adopt Appendix C (Alternate Plumbing Systems) of the 2012 edition UPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | | | |

APPENDIX D – SIZING STORM WATER DRAINAGE SYSTEMS

Repeal Appendix D (Sizing Storm Water Drainage Systems) of the 2012 edition UPC.

Adopt Appendix D (Sizing Storm Water Drainage Systems) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

APPENDIX E – MANUFACTURED/MOBILE HOME PARKS AND RECREATIONAL VEHICLE PARKS

DSA is not proposing the adoption of Appendix E (Manufactured/Mobile Home Parks and Recreational Vehicle Parks) of the 2015 edition UPC. DSA did not adopt Appendix E (Manufactured/Mobile Home Parks and Recreational Vehicle Parks) of the 2012 edition UPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | | | |

APPENDIX F – FIREFIGHTER BREATHING AIR REPLENISHMENT SYSTEMS

DSA is not proposing the adoption of Appendix F (Firefighter Breathing Air Replenishment Systems) of the 2015 edition UPC. DSA did not adopt Appendix F (Firefighter Breathing Air Replenishment Systems) of the 2012 edition UPC. The State Fire Marshal's Office is responsible for the adoption of fire and life safety standards contained in the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | | | |

APPENDIX G – SIZING OF VENTING SYSTEMS

DSA is not proposing the adoption of Appendix G (Sizing of Venting Systems) of the 2015 edition UPC.
DSA did not adopt Appendix G (Sizing of Venting Systems) of the 2012 edition UPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | | | |

APPENDIX H – PRIVATE SEWAGE DISPOSAL SYSTEMS

Repeal Appendix H (Private Sewage Disposal Systems) of the 2012 edition UPC.
Adopt Appendix H (Private Sewage Disposal Systems) of the 2015 edition UPC without DSA amendment for publication in the 2016 triennial edition of the CPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | X | X | |

APPENDIX I – INSTALLATION STANDARDS

DSA is not proposing the adoption of Appendix I (Installation Standards) of the 2015 UPC. DSA did not adopt Appendix I (Installation Standards) of the 2012 edition UPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | | | |

APPENDIX J – COMBINATION OF INDOOR AND OUTDOOR COMBUSTION AND VENTILATION OPENING DESIGN

DSA is not proposing the adoption of Appendix J (Combination of Indoor and Outdoor Combustion and Ventilation Opening Design) of the 2015 edition UPC. DSA did not adopt Appendix J (Combination of Indoor and Outdoor Combustion and Ventilation Opening Design) of the 2012 edition UPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | | | |

APPENDIX K – POTABLE RAINWATER CATCHMENT SYSTEMS

DSA is not proposing the adoption of Appendix K (Potable Rainwater Catchment Systems) of the 2015 edition UPC. DSA did not adopt Appendix K (Potable Rainwater Catchment Systems) of the 2012 edition UPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | | | |

APPENDIX L – SUSTAINABLE PRACTICES

DSA is not proposing the adoption of Appendix L (Sustainable Practices) of the 2015 edition UPC.
DSA did not adopt Appendix L (Sustainable Practices) of the 2012 edition UPC.

| Adopting Agency | DSA-SS | DSA-SS/CC | Comments |
|----------------------|--------|-----------|----------|
| Adopt Entire Chapter | | | |

(All existing amendments that are not revised above shall continue without any change)

Notation for [DSA-SS]

Authority: Education Code § 17310 and 81142, and H&S Code §16022.

Reference: Education Code §§ 17280 through 17317, and 81130 through 81147, and Health and Safety Code §§16000 through 16023.

Notation for [DSA-SS/CC]

Authority: Education Code § 81053.

Reference: Education Code §§ 81052, 81053, and 81130 through 81147.

FINAL EXPRESS TERMS
FOR
PROPOSED BUILDING STANDARDS
OF THE
DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT
REGARDING THE ADOPTION BY REFERENCE OF THE
2015 EDITION OF THE UNIFORM PLUMBING CODE
WITH PROPOSED AMENDMENTS INTO THE 2016 CALIFORNIA PLUMBING CODE
CALIFORNIA CODE OF REGULATIONS, TITLE 24, PART 5

(HCD 06/15)

The Department of Housing and Community Development (HCD) proposes to adopt the 2015 edition of the Uniform Plumbing Code (UPC) for codification and effectiveness into the 2016 edition of the California Plumbing Code (CPC) as presented on the following pages, including any necessary amendments. HCD further proposes to:

- Repeal the 2012 edition of the Uniform Plumbing Code;
- Repeal the 2013 edition of the California Plumbing Code, which includes amendments to the model code that are no longer necessary;
- Repeal or amend building standards that are not addressed by a model code;
- Relocate or codify existing adopted and necessary amendments to the model code into the format of the model code proposed for adoption, the action of which has no regulatory effect; adopt new necessary amendments to the model code proposed for adoption; and/or
- Adopt new building standards that are not addressed by the model code proposed for adoption.

LEGEND FOR EXPRESS TERMS:

1. **UPC language with new California amendments:** UPC language shown in normal Arial 9 point; California amendments to UPC text shown underlined and in italics with vertical bar in left margin.
 2. **Existing California amendments being modified:** All such existing language shown in *italics*, modified language is underlined or shown in ~~strikeout~~ with vertical bar in left margin.
 3. **Existing California amendments with no modification:** All such existing language shown in *italics*, modified model code language is shown in ~~strikeout~~.
 4. **Text not being modified:** All language not displayed in full is shown as "..." (i.e., ellipsis).
 5. **Repealed text:** All language shown in ~~strikeout~~.
 6. **Notation:** Authority and Reference citations are provided at the end of each action.
-

SUMMARY OF REGULATORY ACTION

HCD PROPOSES TO:

- Adopt standards from the 2015 Uniform Plumbing Code into the 2016 California Plumbing Code **without amendment**.
- Adopt standards from the 2015 Uniform Plumbing Code into the 2016 California Plumbing Code **with new amendments**.
- Bring forward existing California Amendments from the 2013 California Plumbing Code for adoption into the 2016 California Plumbing Code **with modifications**.
- Bring forward existing California Amendments from the 2013 California Plumbing Code for adoption into the 2016 California Plumbing Code **without modifications**, except for editorial corrections.
- Repeal 2013 California Amendments, which are **not** brought forward into the 2016 California Plumbing Code.

1. HCD proposes to bring forward existing California Amendments in Chapter 1, Division 1, from the 2013 California Plumbing Code for adoption into the 2016 California Plumbing Code with modifications as follows:

**CHAPTER 1
ADMINISTRATION
DIVISION I
CALIFORNIA ADMINISTRATION**

1.1.0 General.

1.1.1 Title. These regulations shall be known as the California Plumbing Code, may be cited as such and will be referred to herein as "this code." The California Plumbing Code is Part 5 of twelve parts of the official compilation and publication of the adoption, amendment, and repeal of plumbing regulations to the California Code of Regulations, Title 24, also referred to as the California Building Standards Code. This part incorporates by adoption the 2012 2015 Uniform Plumbing Code of the International Association of Plumbing and Mechanical Officials with necessary California amendments.

1.1.2 Purpose. The purpose of this code is to establish the minimum requirements to safeguard the public health, safety and general welfare through structural strength, means of egress facilities, stability, access to persons with disabilities, sanitation, adequate lighting and ventilation, and energy conservation; safety to life and property from fire and other hazards attributed to the built environment; and to provide safety to fire fighters and emergency responders during emergency operations.

1.1.3 Scope. The provisions of this code shall apply to the construction, alteration, movement, enlargement, replacement, repair, equipment, use and occupancy, location, maintenance, removal and demolition of every building or structure or any appurtenances connected or attached to such buildings or structures throughout the State of California.

1.1.3.1 Non-State-Regulated Buildings, Structures, and Applications. Except as modified by local ordinance pursuant to Section 1.1.8, the following standards in the California Code of Regulations, Title 24, Parts 2, 2.5, 3, 4, 5, 6, 9, 10 and 11 shall apply to all occupancies and applications not regulated by a state agency.

1.1.3.2 State-Regulated Buildings, Structures, and Applications. The model code, state amendments to the model code, and/or state amendments where there are no relevant model code provisions shall apply to the following buildings, structures, and applications regulated by state agencies as specified in Section 1.2.0 through 1.14.0, except where modified by local ordinance pursuant to Section 1.1.8. When adopted by a state agency, the provisions of this code shall be enforced by the appropriate enforcing agency, but only to the extent of authority granted to such agency by the state legislature.

Note: See Preface to distinguish the model code provisions from the California provisions.

1. State-owned buildings, including buildings constructed by the Trustees of the California State University, and to the extent permitted by California laws, buildings designed and constructed by the Regents of the University of California, and regulated by the Building Standards Commission. See Section 1.2.0 for additional scope provisions.
2. Local detention facilities regulated by the Corrections Standards Authority. See Section 1.3.0 for additional scope provisions.
3. Barbering, cosmetology or electrolysis establishments, acupuncture offices, pharmacies, veterinary facilities, and structural pest control locations regulated by the Department of Consumer Affairs. See Section 1.4.0 for additional scope provisions.
4. Reserved for the California Energy Commission. See Section 1.5.0 for additional scope provisions.
5. Dairies and places of meat inspection regulated by the Department of Food and Agriculture. See Section 1.6.0 for additional scope provisions.
6. Organized camps, laboratory animal quarters, public swimming pools, radiation protection, commissaries serving mobile food preparation vehicles, and wild animal quarantine facilities regulated by the Department of Public Health. See Section 1.7.0 for additional scope provisions.
7. Hotels, motels, lodging houses, apartment houses ~~apartments~~, dwellings, dormitories, condominiums, shelters for homeless persons, congregate residences, employee housing, factory-built housing, and other

- types of dwellings containing sleeping accommodations with or without common toilets or cooking facilities. See Section 1.8.2.1.1 for additional scope provisions.
8. Accommodations for persons with disabilities in buildings containing newly constructed covered multifamily dwellings, new common use spaces areas serving existing covered multifamily dwellings, additions to existing buildings where the addition alone meets the definition of "COVERED MULTIFAMILY DWELLINGS," covered multifamily dwellings, and new common-use spaces areas serving new covered multifamily dwellings which are regulated by the Department of Housing and Community Development. See Section 1.8.2.1.2 for additional scope provisions.
 9. Permanent buildings and permanent accessory buildings or structures constructed within mobilehome parks and special occupancy parks regulated by the Department of Housing and Community Development. See Section 1.8.2.1.3 for additional scope provisions.
 10. Accommodations for persons with disabilities regulated by the Division of the State Architect. See Section 1.9.1 for additional scope provisions.
 11. Public elementary and secondary schools, community college buildings and state-owned or state-leased essential service buildings regulated by the Division of the State Architect. See Section 1.9.2 for additional scope provisions.
 12. Reserved for the State Historical Building Safety Board with the Division of the State Architect. See Section 1.9.3 for additional scope provisions.
 13. General acute care hospitals, acute psychiatric hospitals, skilled nursing and/or intermediate care facilities, clinics licensed by the Department of Public Health and correctional treatment centers regulated by the Office of Statewide Health Planning and Development. See Section 1.10 for additional scope provisions.
 14. Applications regulated by the Office of State Fire Marshal include but are not limited to the following in accordance with Section 1.11.0:
 1. Buildings or structures used or intended for use as an:
 - 1.1. Asylum, jail, prison.
 - 1.2. Mental hospital, hospital, home for the elderly, children's nursery, children's home or institution, school or any similar occupancy of any capacity.
 - 1.3. Theater, dancehall, skating rink, auditorium, assembly hall, meeting hall, nightclub, fair building or similar place of assemblage where 50 or more persons may gather together in a building, room or structure for the purpose of amusement, entertainment, instruction, deliberation, worship, drinking or dining, awaiting transportation, or education.
 - 1.4. Small family day care homes, large family day-care homes, residential facilities and residential facilities for the elderly, residential care facilities.
 - 1.5. State institutions or other state-owned or state-occupied buildings.
 - 1.6. High rise structures.
 - 1.7. Motion picture production studios.
 - 1.8. Organized camps.
 - 1.9. Residential structures.
 2. Tents, awnings or other fabric enclosures used in connection with any occupancy.
 3. Fire alarm devices, equipment and systems in connection with any occupancy.
 4. Hazardous materials, flammable and combustible liquids.
 5. Public school automatic fire detection, alarm and sprinkler systems.
 6. Wildland-urban interface fire areas.
 15. Public libraries constructed and renovated using funds from the California Library Construction and Renovation Bond Act of 1988 and regulated by the State Librarian. See Section 1.12.0 for additional scope provisions.
 16. Graywater systems regulated by the Department of Water Resources. See Section 1.13.0 for additional scope provisions.
 17. For applications listed in Section 1.9.1 regulated by the Division of the State Architect – Access Compliance, outdoor environments and uses shall be classified according to accessibility uses described in Chapter 11A, 11B and 11C.
 18. Marine Oil Terminals regulated the State Lands Commission. See Section 1.14.0 for additional scope provisions.

1.1.4 Appendices. Provisions contained in the appendices of this code shall not apply unless specifically adopted by a state agency or adopted by a local enforcing agency in compliance with Health and Safety Code Section 18901 et seq. for Building Standards Law, Health and Safety Code Section 17950 for State Housing Law and Health and Safety Code Section 13869.7 for Fire Protection Districts. See Section 1.1.8 of this code.

1.1.5 Referenced Codes. The codes, standards and publications adopted and set forth in this code, including other codes, standards and publications referred to therein are, by title and date of publication, hereby adopted as standard

reference documents of this code. When this code does not specifically cover any subject related to building design and construction, recognized architectural or engineering practices shall be employed. The National Fire Codes, standards and the Fire Protection Handbook of the National Fire Protection Association are permitted to be used as authoritative guides in determining recognized fire prevention engineering practices.

1.1.6 Non-Building Standards, Orders and Regulations. Requirements contained in the Uniform Plumbing Code, or in any other referenced standard, code or document, which are not building standards as defined in Health and Safety Code Section 18909 shall not be construed as part of the provisions of this code. For non-building standards, orders, and regulations, see other titles of the California Code of Regulations.

1.1.7 Order of Precedence and Use.

1.1.7.1 Differences. In the event of any differences between these building standards and the standard reference documents, the text of these building standards shall govern.

1.1.7.2 Specific Provisions. Where a specific provision varies from a general provision, the specific provision shall apply.

1.1.7.3 Conflicts. When the requirements of this code conflict with the requirements of any other part of the California Building Standards Code, Title 24, the most restrictive requirements shall prevail.

1.1.8 City, County, or City and County Amendments, Additions or Deletions.

The provisions of this code do not limit the authority of city, county, or city and county governments to establish more restrictive and reasonably necessary differences to the provisions contained in this code pursuant to complying with Section 1.1.8.1. The effective date of amendments, additions, or deletions to this code by city, county, or city and county filed pursuant to Section 1.1.8.1 shall be the date filed. However, in no case shall the amendments, additions or deletions to this code be effective any sooner than the effective date of this code.

Local modifications shall comply with Health and Safety Code Section 18941.5 for Building Standards Law, Health and Safety Code Section 17958 for State Housing Law or Health and Safety Code Section 13869.7 for Fire Protection Districts.

1.1.8.1 Findings and Filings.

1. The city, county, or city and county shall make express findings for each amendment, addition or deletion based upon climatic, topographical, or geological conditions.

Exception: Hazardous building ordinances and programs mitigating unreinforced masonry buildings.

2. The city, county, or city and county shall file the amendments, additions, or deletions expressly marked and identified as to the applicable findings. Cities, counties, cities and counties, and fire departments shall file the amendments, additions or deletions, and the findings with the California Building Standards Commission at 2525 Natomas Park Drive, Suite 130, Sacramento, CA 95833.
3. Findings prepared by fire protection districts shall be ratified by the local city, county, or city and county and filed with the California Department of Housing and Community Development, Division of Codes and Standards, P.O. Box 1407, Sacramento, CA 95812-1407 or ~~4800 3rd Street, Room 260, Sacramento, CA 95844~~ 2020 W. El Camino Avenue, Suite 250, Sacramento, CA 95833-1829.

1.1.9 Effective Date of this Code. Only those standards approved by the California Building Standards Commission that are effective at the time an application for building permit is submitted shall apply to the plans and specifications for, and to the construction performed under, that permit. For the effective dates of the provisions contained in this code, see the History Note page of this code.

1.1.10 Availability of Codes. At least one complete copy each of Titles 8, 19, 20, 24, and 25 with all revisions shall be maintained in the office of the building official responsible for the administration and enforcement of this code. Each state department concerned and each city, county, or city and county shall have an up-to-date copy of the code available for public inspection. See Health and Safety Code Section 18942 ~~(d)~~(e) (1) and (2).

1.1.11 Format. This part fundamentally adopts the Uniform Plumbing Code by reference on a chapter-by-chapter basis. When a specific chapter of the Uniform Plumbing Code is not printed in the code and is marked "Reserved", such chapter of the Uniform Plumbing Code is not adopted as a portion of this code. When a specific chapter of the

Uniform Plumbing Code is marked "Not Adopted by the State of California" but appears in the code, it may be available for adoption by local ordinance.

Note: Matrix Adoption Tables at the front of each chapter may aid the code user in determining which chapter or sections within a chapter are applicable to buildings under the authority of a specific state agency, but they are not considered regulatory.

1.1.12 Validity. If any chapter, section, subsection, sentence, clause or phrase of this code is for any reason held to be unconstitutional, contrary to statute, exceeding the authority of the state as stipulated by statutes or otherwise inoperative, such decision shall not affect the validity of the remaining portion of this code.

1.8.0 Department of Housing and Community Development. (HCD)

1.8.1 Purpose. The purpose of this code is to establish minimum requirements necessary to protect the health, safety, and general welfare of the occupants and the public by governing the erection, construction, reconstruction, enlargement, conversion, alteration, repair, moving, removal, demolition, sanitation, ventilation and maintenance or use of plumbing equipment or systems.

1.8.2 Authority and Abbreviations.

1.8.2.1 General. The Department of Housing and Community Development is authorized by law to promulgate and adopt building standards and regulations for several types of building applications. The applications under the authority of the Department of Housing and Community Development are listed in Sections 1.8.2.1.1 through 1.8.2.1.3.

1.8.2.1.1 Housing Construction.

Application - Hotels, motels, lodging houses, ~~apartment houses~~ apartments, dwellings, dormitories, condominiums, shelters for homeless persons, congregate residences, employee housing, factory built housing, and other types of dwellings containing sleeping accommodations with or without common toilet or cooking facilities including accessory buildings, facilities, and uses thereto. Sections of this code which pertain to applications listed in this section are identified using the abbreviation "HCD 1".

Enforcing Agency - Local building department or the Department of Housing and Community Development.

Authority Cited- Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference- Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

1.8.2.1.2 Housing Accessibility.

Application - ~~"COVERED MULTIFAMILY DWELLINGS"~~ Covered multifamily dwellings, as defined in Chapter 44A 2 of the California Code of Regulations, Title 24, Part 2, also known as the California Building Code (CBC) including, but not limited to lodging houses, dormitories, timeshares, condominiums, shelters for homeless persons, congregate residences, ~~apartment houses~~ apartments, dwellings, employee housing, factory-built housing, and other types of dwellings containing sleeping accommodations with or without common toilet or cooking facilities.

Sections of this code identified by the abbreviation "HCD 1-AC" require specific accommodations for ~~"PERSONS WITH DISABILITIES"~~ persons with disabilities, as defined in Chapter 44A 2 of the CBC California Building Code. The application of such provisions shall be in conjunction with other requirements of this code and apply only to newly constructed ~~"COVERED MULTIFAMILY DWELLINGS"~~ covered multifamily dwellings, as defined in Chapter 44A 2 of the CBC California Building Code. "HCD 1-AC" applications include, but are not limited to, the following:

1. All newly-constructed ~~"COVERED MULTIFAMILY DWELLINGS"~~ covered multifamily dwellings, as defined in Chapter 44A 2 of the CBC California Building Code.
2. New ~~"COMMON USE AREAS"~~ common use areas, as defined in Chapter 44A 2 of the CBC California Building Code serving existing covered multifamily dwellings.

3. Additions to existing buildings, where the addition alone meets the definition of "COVERED MULTIFAMILY DWELLINGS" covered multifamily dwellings, as defined in Chapter 44A 2 of the CBC California Building Code.
4. Common use areas serving covered multifamily dwellings.
5. Where any portion of a building's exterior is preserved, but the interior of the building is removed, including all structural portions of floors and ceilings, the building is considered a new building for determining the application of California Building Code, Chapter 11A.

HCD 1-AC building standards generally do not apply to public use areas or public accommodations such as hotels, and motels, and public housing. Public use areas, public accommodations, and housing, which is publicly funded as defined in Chapter 2 of the California Building Code are subject to the Division of the State Architect (DSA-AC) in Chapter 11B, and are referenced in Section 1.9.1.

Newly constructed covered multifamily dwellings, which can also be defined as public housing, shall be subject to the requirements of Chapter 11A and Chapter 11B.

Enforcing Agency—Local building department or the Department of Housing and Community Development.

Authority Cited- Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

1.8.2.1.3 Permanent Buildings in Mobilehome Parks and Special Occupancy Parks.

Application - Permanent buildings, and permanent accessory buildings or structures, constructed within mobilehome parks and special occupancy parks that are under the control and ownership of the park operator. Sections of this code which pertain to applications listed in this section are identified using the abbreviation "HCD 2".

Enforcing Agency- Local building department or other local agency responsible for the enforcement of Health and Safety Code, Division 13, Part 2.1, commencing with Section 18200 for mobilehome parks and Health and Safety Code, Division 13, Part 2.3, commencing with Section 18860 for special occupancy parks; or the Department of Housing and Community Development.

Authority Cited - Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11 and 19990; and Government Code Section 12955.1.

Reference - Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

1.8.3 Local Enforcing Agency.

1.8.3.1 Duties and Powers. The building department of every city, county, or city and county shall enforce all the provisions of law, this code, and the other rules and regulations promulgated by the Department of Housing and Community Development pertaining to the installation, erection, construction, reconstruction, movement, enlargement, conversion, alteration, repair, removal, demolition, or arrangement of apartment houses apartments, condominiums, hotels, motels, lodging houses and dwellings, including accessory buildings, facilities, and uses thereto.

The provisions regulating the erection and construction of dwellings and appurtenant structures shall not apply to existing structures as to which construction is commenced or approved prior to the effective date of these regulations. Requirements relating to use, maintenance and occupancy shall apply to all dwellings and appurtenant structures approved for construction or constructed before or after the effective date of this code.

For additional information regarding the use and occupancy of existing buildings and appurtenant structures, see California Code of Regulations, Title 25, Division 1, Chapter 1, Subchapter 1, commencing with Section 1.

1.8.3.2 Laws, Rules, and Regulations. Other than the building standards contained in this code, and notwithstanding other provisions of law, the statutory authority and location of the laws, rules, and regulations to be enforced by local enforcing agencies are listed by statute in Sections 1.8.3.2.1 through 1.8.3.2.5 below:

1.8.3.2.1 State Housing Law. Refer to the State Housing Law, California Health and Safety Code, Division 13, Part 1.5, commencing with Section 17910 and California Code of Regulations, Title 25, Division 1, Chapter 1, Subchapter 1, commencing with Section 1, for the erection, construction, reconstruction, movement, enlargement, conversion, alteration, repair, removal, demolition, or arrangement of ~~apartment houses~~ apartments, condominiums, hotels, motels, lodging houses and dwellings, including accessory buildings, facilities, and uses thereto.

1.8.3.2.2 Mobilehome Parks Act. Refer to the Mobilehome Parks Act, California Health and Safety Code, Division 13, Part 2.1, commencing with Section 18200 and California Code of Regulations, Title 25, Division 1, Chapter 2, commencing with Section 1000 for mobilehome park administrative and enforcement authority, permits, plans, fees, violations, inspections, and penalties both within and outside mobilehome parks.

Exception: Mobilehome parks where the Department of Housing and Community Development is the enforcing agency.

1.8.3.2.3 Special Occupancy Parks Act. Refer to the Special Occupancy Parks Act, California Health and Safety Code, Division 13, Part 2.3, commencing with Section 18860 and California Code of Regulations, Title 25, Division 1, Chapter 2.2, commencing with Section 2000 for special occupancy park administrative and enforcement authority, permits, fees, violations, inspections, and penalties both within and outside of special occupancy parks.

Exception: Special occupancy parks where the Department of Housing and Community Development is the enforcing agency.

1.8.3.2.4 Employee Housing Act. Refer to the Employee Housing Act, California Health and Safety Code, Division 13, Part 1, commencing with Section 17000 and California Code of Regulations, Title 25, Division 1, Chapter 1, Subchapter 3, commencing with Section 600 for employee housing administrative and enforcement authority, permits, fees, violations, inspections, and penalties.

1.8.3.2.5 Factory-Built Housing Law. Refer to the Factory-Built Housing Law, California Health and Safety Code, Division 13, Part 6 commencing with Section 19960 and California Code of Regulations, Title 25, Division 1, Chapter 3, Subchapter 1, commencing with Section 3000 for factory-built housing administrative and enforcement authority, permits, fees, violations, inspections, and penalties.

1.8.4 Permits, Fees, Applications, and Inspections.

1.8.4.1 Permits. A written construction permit shall be obtained from the enforcing agency prior to the erection, construction, reconstruction, installation, relocation, or alteration of any plumbing system.

Exceptions:

1. Work exempt from permits as specified in Chapter 1, Administration, Division II, Section ~~403.1.1~~ 104.2 items (1)-(2) of this code.
2. Changes, alterations, or repairs of a minor nature not affecting structural features, egress, sanitation, safety, or accessibility as determined by the enforcing agency.

Exemptions from permit requirements shall not be deemed to grant authorization for any work to be done in any manner in violation of other provisions of law or this code.

1.8.4.2 Fees. Subject to other provisions of law, the governing body of any city, county, or city and county may prescribe fees to defray the cost of enforcement of rules and regulations promulgated by the Department of Housing and Community Development. The amount of the fees shall not exceed the amount reasonably necessary to administer or process permits, certificates, forms, or other documents, or to defray the costs of enforcement. For additional information, see State Housing Law, Health and Safety Code, Division 13, Part 1.5, Section 17951 and California Code of Regulations, Title 25, Division 1, Chapter 1, Subchapter 1, Article 3, commencing with Section 6.

1.8.4.3 Plan Review and Time Limitations. Subject to other provisions of law, provisions related to plan checking, prohibition of excessive delays, and contracting with or employment of private parties to perform plan

checking are set forth in the State Housing Law, Health and Safety Code Section 17960.1, and for employee housing, in Health and Safety Code Section 17021.

1.8.4.3.1 Retention of Plans. The building department of every city, county, or city and county shall maintain an official copy, microfilm, or electronic or other type of photographic copy of the plans of every building, during the life of the building, for which the department issued a building permit.

Exceptions:

1. Single or multiple dwellings not more than two stories and basement in height.
2. Garages and other structures appurtenant to buildings listed in Exception 1.
3. Farm or ranch buildings appurtenant to buildings listed in Exception 1.
4. Any one-story building where the span between bearing walls does not exceed 25 feet (7620 mm), except a steel frame or concrete building.

All plans for common interest developments as defined in Section ~~4354~~ 4100 of the California Civil Code shall be retained. For additional information regarding plan retention and reproduction of plans by an enforcing agency, see Health and Safety Code Sections 19850 through 19852.

1.8.4.4 Inspections. Construction or work for which a permit is required shall be subject to inspection by the building official and such construction or work shall remain accessible and exposed for inspection purposes until approved. Approval as a result of an inspection shall not be construed to be an approval of a violation of the provisions of this code or other regulations of the Department of Housing and Community Development.

1.8.5 Right of Entry for Enforcement.

1.8.5.1 General. Subject to other provisions of law, officers and agents of the enforcing agency may enter and inspect public and private properties to secure compliance with the rules and regulations promulgated by the Department of Housing and Community Development. For limitations and additional information regarding enforcement, see the following:

1. For applications subject to State Housing Law as referenced in Section 1.8.3.2.1 of this code, refer to Health and Safety Code, Division 13, Part 1.5, commencing with Section 17910 and California Code of Regulations, Title 25, Division 1, Chapter 1, Subchapter 1, commencing with Section 1.
2. For applications subject to the Mobilehome Parks Act as referenced in Section 1.8.3.2.2 of this code, refer to Health and Safety Code, Division 13, Part 2.1, commencing with Section 18200 and California Code of Regulations, Title 25, Division 1, Chapter 2, commencing with Section 1000.
3. For applications subject to the Special Occupancy Parks Act as referenced in Section 1.8.3.2.3 of this code, refer to Health and Safety Code Division 13, Part 2.3, commencing with Section 18860 and California Code of Regulations, Title 25, Division 1, Chapter 2.2, commencing with Section 2000.
4. For applications subject to the Employee Housing Act as referenced in Section 1.8.3.2.4 of this code, refer to Health and Safety Code, Division 13, Part 1, commencing with Section 17000 and California Code of Regulations, Title 25, Division 1, Chapter 1, Subchapter 3, commencing with Section 600.
5. For applications subject to the Factory-Built Housing Law as referenced in Section 1.8.3.2.5 of this code, refer to Health and Safety Code, Division 13, Part 6, commencing with Section 19960 and California Code of Regulations, Title 25, Division 1, Chapter 3, Subchapter 1, commencing with Section 3000.

1.8.6 Local Modification by Ordinance or Regulation.

1.8.6.1 General. Subject to other provisions of law, a city, county, or city and county may make changes to the provisions adopted by the Department of Housing and Community Development. If any city, county, or city and county does not amend, add, or repeal by local ordinances or regulations the provisions published in this code or other regulations promulgated by the Department of Housing and Community Development, those provisions shall be applicable and shall become effective 180 days after publication by the California Building Standards Commission. Amendments, additions, and deletions to this code adopted by a city, county, or city and county pursuant to California Health and Safety Code Sections 17958.5, 17958.7 and 18941.5, together with all applicable portions of this code, shall also become effective 180 days after publication of the California Building Standards Code by the California Building Standards Commission.

1.8.6.2 Findings, Filings, and Rejections of Local Modifications. Prior to making any modifications or establishing more restrictive building standards, the governing body shall make express findings and filings, as required by California Health and Safety Code Section 17958.7, showing that such modifications are reasonably necessary due to local climatic, geological, or topographical conditions. No modification shall become effective or operative unless the following requirements are met:

1. The express findings shall be made available as a public record.
2. A copy of the modification and express finding, each document marked to cross-reference the other, shall be filed with the California Building Standards Commission for a city, county, or a city and county, and with the Department of Housing and Community Development for fire protection districts.
3. The California Building Standards Commission has not rejected the modification or change.

Nothing in this section shall limit the authority of fire protection districts pursuant to California Health and Safety Code Section 13869.7(a).

1.8.7 Alternate Materials, Designs, Tests, and Methods of Construction.

1.8.7.1 General. The provisions of this code as adopted by the Department of Housing and Community Development are not intended to prevent the use of any alternate material, appliance, installation, device, arrangement, design, or method of construction not specifically prescribed by this code. Consideration and approval of alternates shall comply with Section 1.8.7.2 for local building departments and Section 1.8.7.3 for the Department of Housing and Community Development.

1.8.7.2 Local Building Departments. The building department of any city, county, or city and county may approve alternates for use in the erection, construction, reconstruction, movement, enlargement, conversion, alteration, repair, removal, demolition, or arrangement of an ~~apartment house~~ apartments, condominiums, hotel hotels, motel motels, lodging house houses, or dwelling dwellings or an accessory ~~structure~~ structures, except for the following:

1. Structures located in mobilehome parks as defined in California Health and Safety Code Section 18214.
2. Structures located in special occupancy parks as defined in California Health and Safety Code Section 18862.43.
3. Factory-built housing as defined in California Health and Safety Code Section 19971.

1.8.7.2.1 Approval of Alternates. The consideration and approval of alternates by a local building department shall comply with the following procedures and limitations:

1. The approval shall be granted on a case-by-case basis.
2. Evidence shall be submitted to substantiate claims that the proposed alternate, in performance, safety, and protection of life and health, conforms to, or is at least equivalent to, the standards contained in this code and other rules and regulations promulgated by the Department of Housing and Community Development.
3. The local building department may require tests performed by an approved testing agency at the expense of the owner or owner's agent as proof of compliance.
4. If the proposed alternate is related to accessibility in covered multifamily dwellings or facilities serving "~~COVERED MULTIFAMILY DWELLINGS~~" covered multifamily dwellings, as defined in Chapter 44A 2 of the CBC California Building Code, the proposed alternate must also meet the threshold set for "~~EQUIVALENT FACILITATION~~" equivalent facilitation as defined in Chapter 44A 2 of the CBC California Building Code.

For additional information regarding approval of alternates by a local building department pursuant to the State Housing Law, see California Health and Safety Code Section 17951(e) and California Code of Regulations, Title 25, Division 1, Chapter 1, Subchapter 1.

1.8.7.3 Department of Housing and Community Development. The Department of Housing and Community Development may approve alternates for use in the erection, construction, reconstruction, movement, enlargement, conversion, alteration, repair, removal or demolition of an ~~apartment house~~ apartments, condominiums, hotel hotels, motel motels, lodging house houses, dwelling dwellings, or an accessory structures thereto. The consideration and approval of alternates shall comply with the following:

1. The department may require tests at the expense of the owner or owner's agent to substantiate compliance with the California Building Standards Code.
2. The approved alternate shall, for its intended purpose, be at least equivalent in performance and safety to the materials, designs, tests, or methods of construction prescribed by this code.

1.8.8 Appeals Board.

1.8.8.1 General. Every city, county, or city and county shall establish a process to hear and decide appeals of orders, decisions, and determinations made by the enforcing agency relative to the application and interpretation of this code and other regulations governing construction, use, maintenance and change of occupancy. The governing body of any city, county, or city and county may establish a local appeals board and a housing

appeals board to serve this purpose. Members of the appeals board(s) shall not be employees of the enforcing agency and shall be knowledgeable in the applicable building codes, regulations and ordinances as determined by the governing body of the city, county, or city and county.

Where no such appeals boards or agencies have been established, the governing body of the city, county, or city and county shall serve as the local appeals board or housing appeals board as specified in California Health and Safety Code Sections 17920.5 and 17920.6.

1.8.8.2 Definitions. The following terms shall for the purposes of this section have the meaning shown.

Housing Appeals Board. The board or agency of a city, county, or city and county which is authorized by the governing body of the city, county, or city and county to hear appeals regarding the requirements of the city, county, or city and county relating to the use, maintenance, and change of occupancy of buildings and structures, including requirements governing alteration, additions, repair, demolition, and moving. In any area in which there is no such board or agency, "housing appeals board" means the local appeals board having jurisdiction over the area.

Local Appeals Board. The board or agency of a city, county, or city and county which is authorized by the governing body of the city, county, or city and county to hear appeals regarding the building requirements of the city, county, or city and county. In any area in which there is no such board or agency, "local appeals board" means the governing body of the city, county, or city and county having jurisdiction over the area.

1.8.8.3 Appeals. Except as otherwise provided by law, any person, firm, or corporation adversely affected by a decision, order, or determination by a city, county, or city and county relating to the application of building standards published in the California Building Standards Code, or any other applicable rule or regulation adopted by the Department of Housing and Community Development, or any lawfully enacted ordinance by a city, county, or city and county, may appeal the issue for resolution to the local appeals board or housing appeals board as appropriate.

The local appeals board shall hear appeals relating to new building construction and the housing appeals board shall hear appeals relating to existing buildings.

1.8.9 Unsafe Buildings or Structures.

1.8.9.1 Authority to Enforce. Subject to other provisions of law, the administration, enforcement, actions, proceedings, abatement, violations, and penalties for unsafe buildings and structures are contained in the following statutes and regulations:

1. For applications subject to State Housing Law as referenced in Section 1.8.3.2.1 of this code, refer to Health and Safety Code, Division 13, Part 1.5, commencing with Section 17910 and California Code of Regulations, Title 25, Division 1, Chapter 1, Subchapter 1, commencing with Section 1.
2. For applications subject to the Mobilehome Parks Act as referenced in Section 1.8.3.2.2 of this code, refer to Health and Safety Code, Division 13, Part 2.1, commencing with Section 18200 and California Code of Regulations, Title 25, Division 1, Chapter 2, commencing with Section 1000.
3. For applications subject to the Special Occupancy Parks Act as referenced in Section 1.8.3.2.3 of this code, refer to Health and Safety Code, Division 13, Part 2.3, commencing with Section 18860 and California Code of Regulations, Title 25, Division 1, Chapter 2.2, commencing with Section 2000.
4. For applications subject to the Employee Housing Act as referenced in Section 1.8.3.2.4 of this code, refer to Health and Safety Code, Division 13, Part 1, commencing with Section 17000 and California Code of Regulations, Title 25, Division 1, Chapter 1, Subchapter 3, commencing with Section 600.
5. For applications subject to the Factory-Built Housing Law as referenced in Section 1.8.3.2.5 of this code, refer to Health and Safety Code, Division 13, Part 6, commencing with Section 19960 and California Code of Regulations, Title 25, Division 1, Chapter 3, Subchapter 1, commencing with Section 3000.

1.8.9.2 Actions and Proceedings. Subject to other provisions of law, punishments, penalties, and fines for violations of building standards are contained in the following statutes and regulations:

1. For applications subject to the State Housing Law as referenced in Section 1.8.3.2.1 of this code, refer to Health and Safety Code, Division 13, Part 1.5, commencing with Section 17910 and California Code of Regulations, Title 25, Division 1, Chapter 1, Subchapter 1, commencing with Section 1.
2. For applications subject to the Mobilehome Parks Act as referenced in Section 1.8.3.2.2 of this code, refer to Health and Safety Code, Division 13, Part 2.1, commencing with Section 18200 and California Code of Regulations, Title 25, Division 1, Chapter 2, commencing with Section 1000.

3. For applications subject to the Special Occupancy Parks Act as referenced in Section 1.8.3.2.3. of this code, refer to Health and Safety Code, Division 13, Part 2.3, commencing with Section 18860 and California Code of Regulations, Title 25, Division 1, Chapter 2.2, commencing with Section 2000.
4. For applications subject to the Employee Housing Act as referenced in Section 1.8.3.2.4 of this code, refer to Health and Safety Code, Division 13, Part 1, commencing with Section 17000 and California Code of Regulations, Title 25, Division 1, Chapter 1, Subchapter 3, commencing with Section 600.
5. For applications subject to the Factory-Built Housing Law as referenced in Section 1.8.3.2.5 of this code, refer to Health and Safety Code, Division 13, Part 6, commencing with Section 19960 and California Code of Regulations, Title 25, Division 1, Chapter 3, Subchapter 1, commencing with Section 3000.

1.8.10 Other Building Regulations.

1.8.10.1 Existing Structures. Notwithstanding other provisions of law, the replacement, retention, and extension of original materials and the use of original methods of construction for any existing building or accessory structure, or portions thereof, shall be permitted in accordance with the provisions of this code and the California Existing Building Code, as adopted by the Department of Housing and Community Development. For additional information, see California Health and Safety Code Sections 17912, 17920.3, 17922 and 17958.8.

~~**1.8.10.2 Moved Structures.** Subject to the requirements of California Health and Safety Code Sections 17922.3 and 17958.9, local ordinances or regulations relating to a moved residential or accessory structure shall, after July 1, 1978, permit the retention of existing materials and methods of construction so long as the structure does not become or continue to be a substandard building.~~

1.8.10.2 Moved Structures. Subject to the requirements of California Health and Safety Code Sections 17922, 17922.3 and 17958.9, local ordinances or regulations relating to a moved residential building or accessory structure thereto, shall permit the replacement, retention, and extension of original materials and the use of original methods of construction so long as the structure does not become or continue to be a substandard building.

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

2. HCD proposes to adopt Chapter 1, Division II, Section 104.2 (Items 1 and 2 only), from the 2015 Uniform Plumbing Code into the 2016 California Plumbing Code without amendment:

DIVISION II ADMINISTRATION

104.2 (Formerly 103.1.1) Exempt Work. ... (No change to text)

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

3. HCD proposes to adopt Chapter 2 from the 2015 Uniform Plumbing Code with new amendments and bring forward existing amendments from the 2013 California Plumbing Code into the 2016 California Plumbing Code as follows:

**CHAPTER 2
DEFINITIONS**

203.0

-A-

Alternate Water Source. Nonpotable source of water that includes but is not limited to gray water, on-site treated non-potable gray water, rainwater, and reclaimed (recycled) water.

Approved. Acceptable to the Authority Having Jurisdiction.

Exception: (HCD 1 & HCD 2) "Approved" means meeting the approval of the Enforcing Agency, except as otherwise provided by law, when used in connection with any system, material, type of construction, fixture or appliance as the result of investigations and tests conducted by the agency, or by reason of accepted principles or tests by national authorities, or technical, health, or scientific organizations or agencies.

Notes:

- (1) See Health and Safety Code Section 17920 for "Approved" as applied to residential construction and buildings or structures accessory thereto, as referenced in Sections 1.8.2.
- (2) See Health and Safety Code Section 17921.1 for "Approved" as applied to the use of hotplates in residential construction referenced in Sections 1.8.2.
- (3) See Health and Safety Code Section 19966 for "Approved" as applied to Factory-Built Housing as referenced in Sections 1.8.3.2.5.
- (4) See Health and Safety Code Section 18201 for "Approved" as applied to Mobilehome Parks as referenced in Section 1.8.2.
- (5) See Health and Safety Code Section 18862.1 for "Approved" as applied to Special Occupancy Parks as referenced in Section 1.8.2.

Approved Testing Agency. An organization primarily established for purposes of testing to approved standards and approved by the Authority Having Jurisdiction.

(HCD 1 & HCD 2) "Approved Testing Agency" is any agency which is determined by the enforcing agency, except as otherwise provided by statute, to have adequate personnel and expertise to carry out the testing of systems, materials, and construction fixtures or appliances.

Authority Having Jurisdiction. The organization, office, or individual responsible for enforcing the requirements of a code or standard, or for approving equipment, materials, installations, or procedures. The Authority Having Jurisdiction shall be a federal, state, local, or other regional department or an individual such as a plumbing official, mechanical official, labor department official, health department official, building official, or others having statutory authority. In the absence of a statutory authority, the Authority Having Jurisdiction may be some other responsible party. This definition shall include the Authority Having Jurisdiction's duly authorized representative.

(HCD 1 & HCD 2) "Authority Having Jurisdiction" shall mean "Enforcing Agency" as defined in Section 207.0 of this code.

204.0

-B-

Building. A structure built, erected, and framed of component structural parts designed for the housing, shelter, enclosure, or support of persons, animals, or property of any kind.

Exceptions: (HCD 1 & HCD 2) "BUILDING" shall not include the following:

1. Any mobilehome as defined in Health and Safety Code Section 18008.

2. Any manufactured home as defined in Health and Safety Code Section 18007.
3. Any commercial modular as defined in Health and Safety Code Section 18001.8 or any special purpose commercial modular as defined in Section 18012.5.
4. Any recreational vehicle as defined in Section Health and Safety Code 18010.
5. Any multifamily manufactured home as defined in Health and Safety Code Section 18008.7.

For additional information, see Health and Safety Code Section 18908.

205.0

-C-

Clothes Washer System (HCD 1). A gray water system utilizing only a single domestic clothes washing machine in a one- or two family dwelling.

Complex System (HCD 1). Gray water systems that discharge over 250 gallons (947 L) per day.

Covered Multifamily Dwellings (HCD 1-AC). See Section 1.8.2.1.2.

206.0

-D-

Department (HCD 1, HCD 2 & HCD 1-AC). "Department" means the Department of Housing and Community Development.

Department Having Jurisdiction. The Authority Having Jurisdiction, including any other law enforcement agency affected by any provision of this code, whether such agency is specifically named or not.

(HCD 1 & HCD 2) "Department Having Jurisdiction" shall mean "Enforcing Agency" as defined in Section 207.0 of this code.

Disposal Field (HCD 1). An intended destination for gray water, including but not limited to, a mulch basin or receiving landscape feature, gray water leach field, or other approved method of disposal.

207.0

-E-

Enforcing Agency (HCD 1, HCD 2 & HCD 1-AC). "Enforcing Agency" is the designated department or agency as specified by statute or regulation.

209.0

-G-

Graywater (HCD 1). Pursuant to Health and Safety Code Section 17922.12, "graywater" means untreated wastewater that has not been contaminated by any toilet discharge, has not been affected by infectious, contaminated, or unhealthy bodily wastes, and does not present a threat from contamination by unhealthful processing, manufacturing, or operating wastes. "Graywater" includes, but is not limited to, wastewater from bathtubs, showers, bathroom washbasins, clothes washing machines, and laundry tubs, but does not include wastewater from kitchen sinks or dishwashers.

Note: For the purpose of applying the standards contained in this code, "Graywater" as defined above, has the same meaning as "gray water", "grey water", and "greywater".

Gray Water System (HCD 1). A system designed to collect gray water on-site for reuse or distribution to an irrigation or disposal field. A gray water system may include, on-site treated nonpotable water devices or equipment, tanks, valves, filters, pumps or other appurtenances along with piping and receiving landscape.

211.0

-I-

Irrigation Field (HCD 1). An intended destination for gray water in the receiving landscape, including but not limited to, a drip irrigation system, mulch basin, or other approved method of dispersal for irrigation purposes.

214.0

-L-

Labeled. Equipment or materials bearing a label of a listing agency (accredited conformity assessment body). See Listed (third-party certified).

(HCD 1 & HCD 2) "Labeled" means equipment or materials to which has been attached a label, symbol or other identifying mark of an organization, approved by the Department, that maintains a periodic inspection program of production of labeled products, installations, equipment, or materials and by whose labeling the manufacturer indicates compliance with appropriate standards or performance in a specified manner.

Lavatory (HCD 1 & HCD 2). "Lavatory" shall mean a plumbing fixture used for washing the hands, arms, face and head.

Limited-Density Owner-Built Rural Dwelling (HCD 1). "Limited-density owner-built rural dwelling" shall mean any structure consisting of one or more habitable rooms intended or designed to be occupied by one family with facilities for living or sleeping, with use restricted to rural areas designated by local jurisdiction in compliance with the requirements of Health and Safety Code Section 17958.2.

Listed (HCD 1 & HCD 2). "Listed" means all products that appear in a list published by an approved testing or listing agency. For additional information, see Health and Safety Code Section 17920(h).

Listing Agency. An agency accredited by an independent and authoritative conformity assessment body to operate a material and product listing and labeling (certification) system and that is accepted by the Authority Having Jurisdiction, which is in the business of listing or labeling. The system includes initial and ongoing product testing, a periodic inspection on current production of listed (certified) products, and makes available a published report of such listing in which specific information is included that the material or product is in accordance with applicable standards and found safe for use in a specific manner.

(HCD 1 & HCD 2) "Listing Agency" means an agency approved by the department that is in the business of listing and labeling products, materials, equipment, and installations tested by an approved testing agency, and that maintains a periodic inspection program on current production of listed products, equipment, and installations, and that, at least annually, makes available a published report of these listings. For additional information, see Health and Safety Code Section 17920(i).

Low VOC Cement (HCD 1 & HCD 2). Cement with a volatile organic compound (VOC) content of less than or equal to 490 g/L for CPVC Cement, 510 g/L for PVC Cement, and 325 g/L for ABS Cement, as determined by the South Coast Air Quality Management District's Laboratory Methods of Analysis for Enforcement Samples, Method 316A.

Low VOC One-Step Cement (HCD 1 & HCD 2). Listed solvent cements that do not require the use of primer with a volatile organic compound (VOC) content of less than or equal to 490 g/L for CPVC Cement, 510 g/L for PVC Cement, and 325 g/L for ABS Cement, as determined by the South Coast Air Quality Management District's Laboratory Methods of Analysis for Enforcement Samples, Method 316A.

Low VOC Primer (HCD 1 & HCD 2). Primer with a volatile organic compound (VOC) content of less than or equal to 550 g/L, as determined by the South Coast Air Quality Management District's Laboratory Methods of Analysis for Enforcement Samples, Method 316A.

215.0

-M-

Mulch Basin (HCD 1). A subsurface type of irrigation or disposal field filled with mulch or other approved permeable material of sufficient depth, length, and width to prevent ponding or runoff. A mulch basin may include a basin around a tree, a trough along a row of plants, or other shapes necessary for irrigation or disposal.

216.0

-N-

Nonwater Supplied Urinal (HCD 1). A plumbing fixture which does not require water supply and is designed to receive and convey the uninhibited flow of liquid waste to the gravity drainage system.

Nuisance. Includes, but is not limited to:

- (1) A public nuisance known at common law or in equity jurisprudence.
- (2) Where work regulated by this code is dangerous to human life or is detrimental to health and property.
- (3) Inadequate or unsafe water supply or sewage disposal system.

(HCD 1 & HCD 2) "Nuisance" shall mean any nuisance as defined in Health and Safety Code Section 17920(k).

Notes:

1. For applications subject to the Mobilehome Parks Act as referenced in Section 1.8.3.2.2 of this code, refer to California Code of Regulations, Title 25, Division 1, Chapter 2 for the definition of "Nuisance".
2. For applications subject to the Special Occupancy Parks Act as referenced in Section 1.8.3.2.3 of this code, refer to California Code of Regulations, Title 25, Division 1, Chapter 2.2 for the definition of "Nuisance".

217.0

-O-

On-Site Treated Nonpotable Water (HCD 1). Nonpotable water that has been collected, treated, and intended to be used on-site and is suitable for direct beneficial use. Sources for on-site treated nonpotable water include, but are not limited to, gray water; rainwater; stormwater; reclaimed (recycled) water; cooling tower blow-down water; and foundation drainage.

220.0

-R-

Rainwater (HCD 1). Precipitation on any public or private parcel that has not entered an offsite storm drain system or channel, a flood control channel, or any other stream channel, and has not previously been put to beneficial use.

Rainwater Catchment System (HCD 1). A facility designed to capture, retain, and store rainwater flowing off a building, parking lot, or any other manmade impervious surface for subsequent onsite use. Rainwater catchment system is also known as "Rainwater Harvesting System" or "Rainwater Capture System."

Receiving Landscape (HCD 1). Includes features such as soil, basins, swales, mulch, and plants.

Reclaimed (Recycled) Water (HCD 1). Nonpotable water that meets California Department of Public Health statewide uniform criteria for disinfected tertiary recycled water. Reclaimed (recycled) water is also known as "recycled water" or "reclaimed water".

221.0

-S-

Simple System (HCD 1). A gray water system serving one-and two-family dwellings, townhouses, or other occupancies with a discharge of 250 gallons (947 L) per day or less. Simple systems exceed a clothes washer system.

222.0

-T-

Testing Agency (HCD 1). See "Approved Testing Agency".

Treated Gray Water (HCD 1). Nonpotable water meeting the definition of "gray water" collected and treated on-site suitable for direct beneficial use.

223.0

-U-

UPC (HCD 1). "UPC" is the latest edition of the Uniform Plumbing Code, published by the International Association of Plumbing and Mechanical Officials.

225.0

-W-

Water Closet (HCD 1). "Water Closet" is a plumbing fixture (which may be used for both solids and liquids) in which the waste matter is removed by flushing with water.

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

4. HCD proposes to delete and NOT adopt the following Chapter 2 definitions from the 2015 Uniform Plumbing Code into the 2016 California Plumbing Code as follows:

**CHAPTER 2
DEFINITIONS**

Gray Water. Untreated wastewater that has not come into contact with toilet waste, kitchen sink waste, dishwasher waste or similarly contaminated sources. Gray water includes wastewater from bathtubs, showers, lavatories, clothes washers, and laundry tubs. Also known as grey water, graywater, and greywater.

Mulch Basin. A subsurface catchment area for gray water that is filled with mulch and of other sufficient depth and volume to prevent ponding, surfacing, or runoff.

On-Site Treated Nonpotable Water. Nonpotable water, including gray water that has been collected, treated, and intended to be used on-site and is suitable for direct beneficial use.

Rainwater. Natural precipitation that has not been contaminated by use.

Rainwater Catchment System. A system that utilizes the principal of collecting, storing, and using rainwater from a rooftop or other manmade, aboveground collection surface. Also known as a rainwater harvesting system.

Reclaimed Water. Nonpotable water provided by a water/wastewater utility that, as a result of tertiary treatment of domestic wastewater, meets requirements of the public health Authority Having Jurisdiction for its intended uses.

Single Family Dwelling. A building designed to be used as a home by the owner of such building, which shall be the only dwelling located on a parcel of ground with the usual accessory buildings.

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

5. HCD proposes to adopt Chapter 3, (except Sections 301.3.1, 301.3.1.1 and 301.3.1.2), from the 2015 Uniform Plumbing Code with new amendments and bring forward existing amendments from the 2013 California Plumbing Code into 2016 California Plumbing Code as follows:

**CHAPTER 3
GENERAL REGULATIONS**

301.3 (Formerly 301.2) Alternate Materials and Methods of Construction Equivalency. Nothing in this code is intended to prevent the use of systems, methods, or devices of equivalent or superior quality, strength, fire resistance, effectiveness, durability, and safety over those prescribed by this code. Technical documentation shall be submitted to the Authority Having Jurisdiction to demonstrate equivalency. The Authority Having Jurisdiction shall have the authority to approve or disapprove the system, method, or device for the intended purpose.
(HCD 1) (See Section 1.8.7).

However, the exercise of this discretionary approval by the Authority Having Jurisdiction shall have no effect beyond the jurisdictional boundaries of said Authority Having Jurisdiction. An alternate material or method of construction so approved shall not be considered as in accordance with the requirements, intent, or both of this code for a purpose other than that granted by the Authority Having Jurisdiction where the submitted data does not prove equivalency.

301.4.1 Coastal High Hazard Areas. Plumbing systems in buildings located in coastal high hazard areas shall be in accordance with the requirements of Section 301.4, and plumbing systems, pipes, and fixtures shall not be mounted on or penetrate through walls that are intended to breakaway under flood loads in accordance with the ~~building code~~ California Building Code or California Residential Code.

301.6 (Formerly 301.5) One- and Two-Family Dwellings. (HCD 1) *The provisions contained in this code shall not apply to one and two-family dwelling private sewage disposal systems and minimum plumbing facilities when alternate facilities or installations have been approved by the local health authority, provided that such alternative facilities or installations provide substantially equivalent or greater protection to health and safety.*

303.1 General. It shall be unlawful for a person to cause, suffer, or permit the disposal of sewage, human excrement, or other liquid wastes, in a place or manner, except through and by means of an approved drainage system, installed and maintained in accordance with the provisions of this code.

Exception: (HCD 1) Limited-density owner-built rural dwellings. *A water closet shall not be required when an alternate system is provided and has been approved by the local health official. Where an alternative to the water closet is installed, a system for the disposal or treatment of graywater shall be provided to the dwelling. Graywater systems shall be designed according to water availability, use and discharge. The design, use and maintenance standards of such systems shall be the prerogative of the local health official.*

304.1 General. Plumbing fixtures, drains, appurtenances, and appliances, used to receive or discharge liquid wastes or sewage, shall be connected properly to the drainage system of the building or premises, in accordance with the requirements of this code.

Exception: (HCD 1) Limited-density owner-built rural dwellings. *Where conventional plumbing, in all or in part, is installed within the structure, it shall be installed in accordance with the provisions of this code. Alternative materials and methods shall be permitted provided that the design complies with the intent of the code, and that such alternatives shall perform to protect health and safety for the intended purpose.*

312.2 Installation: Piping in connection with a plumbing system shall be so installed that piping or connections will not be subject to undue strains or stresses, and provisions shall be made for expansion, contraction, and structural settlement. No plumbing piping shall be directly embedded in concrete or masonry. No structural member shall be seriously weakened or impaired by cutting, notching, or otherwise, as defined in the ~~building code~~ California Building Code or California Residential Code.

312.7. Fire-Resistant Construction. Piping penetrations of fire-resistance-rated walls, partitions, floors, floor/ceiling assemblies, roof/ceiling assemblies, or shaft enclosures shall be protected in accordance with the requirements of the ~~building code and Chapter 14, "Firestop Protection"~~ California Building Code or California Residential Code.

312.11 Structural Members. A structural member weakened or impaired by cutting, notching, or otherwise shall be reinforced, repaired, or replaced so as to be left in a safe structural condition in accordance with the requirements of the ~~building code~~ California Building Code or California Residential Code.

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

6. **HCD proposes to adopt Chapter 4, (except Sections 411.2.2, 422.2, 422.4 and 422.5), from the 2015 Uniform Plumbing Code with new amendments and bring forward existing amendments from the 2013 California Plumbing Code into the 2016 California Plumbing Code as follows:**

**CHAPTER 4
PLUMBING FIXTURES AND FIXTURE FITTINGS**

401.3 Water-Conserving Fixtures and Fittings. (Formerly 403.0) (HCD 1) *Note: On or after January 1, 2014, residential buildings undergoing permitted alterations, additions or improvements shall replace noncompliant plumbing fixtures with water-conserving plumbing fixtures. Plumbing fixture replacement is required prior to issuance of a certificate of final completion, certificate of occupancy or final permit approval by the local building department. See Civil Code Section 1101.43, et seq. for the definition of a noncompliant plumbing fixture, types of buildings affected and other subsequent enactment dates.*

403.1 General (Formerly 402.7 Accessible Plumbing Facilities). Where accessible facilities are required in applicable building regulations, the facilities shall be installed in accordance with those regulations. (HCD 1-AC) *For specific requirements regarding accommodations for persons with disabilities, see California Code of Regulations, Title 24, Part 2, Chapter 11A of the California Building Code.*

403.2 General. (Formerly 421.1 Fixtures and Fixture Fittings for Persons with Disabilities.) Plumbing fixtures and fixture fittings for persons with disabilities shall comply with ICC A117.1 and the applicable standards referenced in Chapter 4. (HCD 1-AC) *Specific requirements regarding accommodations for persons with disabilities are contained in California Code of Regulations, Title 24, Part 2, Chapter 11A of the California Building Code. Table 1401.1 does not contain the correct accessibility standards for use in California.*

407.2.1 Maximum Flow Rate. The maximum flow rate for public lavatory faucets shall not exceed 0.5 gpm at 60 psi (1.9 L/m at 414 kPa), and 2.2 gpm at 60 psi (8.3 L/m at 414 kPa) for private lavatory faucets in accordance with ASME A112.18.1/CSA B125.1.

407.2.1.1 (Formerly 403.6) **Kitchen Faucets.** (HCD 1) *The maximum flow rate of kitchen faucets shall not exceed 1.8 gallons (6.81 L) per minute at 60 psi. Kitchen faucets may temporarily increase the flow above the maximum rate, but not to exceed 2.2 gallons (8.32 L) per minute at 60 psi, and must default to a maximum flow rate of 1.8 gallons (6.81 L) per minute at 60 psi.*

Note: Where faucets meeting the maximum flow rate of 1.8 gpm (6.81 L) are unavailable, aerators or other means may be used to achieve reduction.

407.2.1.2 (Formerly 403.7) **Residential Lavatory Faucets** (HCD 1) *On or after July 1, 2016, the maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons (4.54 L) per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not be less than 0.8 gallons (3.03 L) per minute at 20 psi.*

407.2.1.3 (Formerly 403.8) **Lavatory Faucets in Common and Public Use Areas.** (HCD 1 & HCD 2) *The maximum flow rate of lavatory faucets, installed in common and public use areas (outside of dwellings or sleeping units) in residential buildings, shall not exceed 0.5 gallons (1.89 L) per minute at 60 psi.*

408.2 Water Consumption. (HCD 1) *Showerheads shall have a maximum flow rate of not more than 2.5 gpm at 80 psi (0.16 L/s at 552 kPa), in accordance with ASME A112.18.1/CSA B125.1. Showerheads shall have a maximum flow rate of 2.0 gallons (7.57 L) per minute measured at 80 psi and must comply with Division 4.3 of the California Green Building Standards Code (CALGreen).*

408.5 Finished Curb or Threshold. Where a shower receptor has a finished dam, curb, or threshold it shall not be less than 1 inch (25.4 mm) lower than the sides and back of such receptor. In no case shall a dam or threshold be less than 2 inches (51 mm) or exceeding 9 inches (229 mm) in depth where measured from the top of the dam or threshold to the top of the drain. Each such receptor shall be provided with an integral nailing flange to be located where the receptor meets the vertical surface of the finished interior of the shower compartment. The flange shall be

watertight and extend vertically not less than 1 inch (25.4 mm) above the top of the sides of the receptor. The finished floor of the receptor shall slope uniformly from the sides towards the drain not less than 1/4 inch per foot (20.8 mm/m), nor more than 1/2 inch per foot (41.8 mm/m).

Thresholds shall be of sufficient width to accommodate a minimum 22 inch (559 mm) door. Shower doors shall open so as to maintain not less than a 22 inch (559 mm) unobstructed opening for egress. The immediate adjoining space to showers without thresholds shall be considered a wet location and shall comply with the requirements of the building, residential, and electrical codes California Building, California Residential and California Electrical Codes.

Exceptions:

- (1) Showers that are designed to be in accordance with the accessibility standards listed in Table 1701.4 in Chapter 11A of the California Building Code. (HCD 1-AC) Specific requirements regarding accommodations for persons with disabilities are contained in California Code of Regulations, Title 24, Part 2, Chapter 11A of the California Building Code. Table 1401.4 does not contain the correct accessibility standards for use in California.
- (2) A cast iron shower receptor flange shall be not less than 0.3 of an inch (7.62 mm) in height.
- (3) For flanges not used as a means of securing, the sealing flange shall be not less than 0.3 of an inch (7.62 mm) in height.

408.6 Shower Compartments. Shower compartments, regardless of shape, shall have a minimum finished interior of 1024 square inches (0.6606 m²) and shall also be capable of encompassing a 30 inch (762 mm) circle. The minimum required area and dimensions shall be measured at a height equal to the top of the threshold and at a point tangent to its centerline. The area and dimensions shall be maintained to a point of not less than 70 inches (1778 mm) above the shower drain outlet with no protrusions other than the fixture valve or valves, shower head, soap dishes, shelves, and safety grab bars, or rails. Fold-down seats in accessible shower stalls shall be permitted to protrude into the 30 inch (762 mm) circle.

Exceptions:

- (1) Showers that are designed to comply with ICC-A117.4 Chapter 11A of the California Building Code.
- (2) The minimum required area and dimension shall not apply for a shower receptor having overall dimensions of not less than 30 inches (762 mm) in width and 60 inches (1524 mm) in length.
- (3) (HCD 1-AC) Specific requirements regarding accommodations for persons with disabilities are contained in California Code of Regulations, Title 24, Part 2, Chapter 11A of the California Building Code. ICC/ANSI A117.1, Standard for Accessible and Usable Buildings and Facilities, does not contain the correct accessibility standards for use in California.

411.2 (Formerly 403.2.1 Water Closets on or after July 1, 2011) Water Consumption. Water Closets shall have a maximum consumption not to exceed 1.6 (6.0 Lpf) of water per flush in accordance with ASME A112.19.2/CSA B45.1. The effective flush volume of all water closets shall not exceed 1.28 gallons per flush when tested in accordance with ASME A112.19.2/CSA B45.1.

411.2.1.2 (Formerly 403.2.1.1) Performance [HCD 1 & HCD 2] Water closets installed on or after July 2, 2011, shall meet or exceed the minimum performance criteria developed for certification of high-efficiency toilets under the WaterSense program sponsored by the U.S. Environmental Protection Agency (EPA).

412.1 (Formerly 403.3 Urinals) Application. Urinals shall comply with ASME A112.19.2/CSA B45.1, ASME A112.19.19, or CSA B45.5/IAPMO Z124. ~~On or after January 1, 2016, wall~~ Wall mounted urinals shall have an average water consumption not to exceed 0.125 gallons (0.47 L) of water per flush. Urinals Other urinals shall have an average water consumption not to exceed 4-gallon (3.8 Lpf) 0.5 gallons (1.89 L) of water per flush.

412.1.1 (Formerly 403.3.1) Nonwater Urinals. Nonwater urinals shall have a barrier liquid sealant to maintain a trap seal. Nonwater urinals shall permit the uninhibited flow of waste through the urinal to the sanitary drainage system. Nonwater urinals shall be cleaned and maintained in accordance with the manufacturer's instructions after installation. Where nonwater urinals are installed, not less than one water supplied fixture rated at not less than 1 water supply fixture unit (WSFU) shall be installed upstream on the same drain line to facilitate drain line flow and rinsing. Where nonwater urinals are installed they shall have a water distribution line rough-in to the urinal location to allow for the installation of an approved backflow prevention device in the event of a retrofit. *For additional information, see Health and Safety Code Section 17921.4.*

415.0 Drinking Fountains.

415.1 Application. Drinking fountains shall be self-closing and comply with ASME A112.19.1/CSA B45.2, ASME A112.19.2/CSA B45.1, or ASME A112.19.3/CSA B45.4, and NSF 61. Permanently installed electric water coolers shall also comply with UL 399. *(HCD 1) Drinking fountains shall be installed and so regulated that a jet of water*

extending at least 2 inches (51 mm) in height from the water orifice shall be constantly available. The orifice shall not be accessible to the mouth of the drinker nor subject to immersion.

422.1 Fixture Count. Plumbing fixtures shall be provided for the type of building occupancy and in the minimum number shown in Table 422.1. The total occupant load and occupancy classification shall be determined in accordance with the building code California Building Code. Occupancy classification not shown in Table 422.1 shall be considered separately by the Authority Having Jurisdiction.

**TABLE 422.1
MINIMUM PLUMBING FACILITIES¹**

Each building shall be provided with sanitary facilities, including provisions for persons with disabilities as prescribed by the Department Having Jurisdiction⁷. Table 422.1 applies to new buildings, additions to a building, and changes of occupancy or type in an existing building resulting in increased occupant load.

For requirements for persons with disabilities, Chapter 11A of the California Building Code shall be used.

Exceptions:

- (1) **(HCD 1-AC & HCD 2)** For applications listed in Sections 1.8.2.1.2 and 1.8.2.1.3 regulated by the Department of Housing and Community Development, each building shall be provided with sanitary facilities, including provisions for persons with disabilities as prescribed by the Department. Covered multifamily dwellings required to be accessible to persons with disabilities shall comply with California Code of Regulations, Title 24, Part 2, Chapter 11A of the California Building Code. Permanent buildings in mobilehome parks and special occupancy parks required to be accessible by persons with disabilities, shall comply with California Code of Regulations, Title 24, Part 2, Chapter 11B of the California Building Code.
- (2) **(HCD 1)** For limited density owner-built rural dwelling sanitary facilities, the type, design and number of facilities as required and approved by the local health official shall be provided to the dwelling sites. It shall not be required that such facilities be located within the dwelling.

....(No Changes to Table)

Notes:

- 4 7. In accordance with Sections 1.8.7 and ~~304.2~~ 301.3, the Authority Having Jurisdiction may approve alternative designs criteria when determining the minimum number of plumbing fixtures.

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

7. HCD proposes to repeal existing California amendments from Chapter 4 of the 2013 California Plumbing Code, and not bring these amendments forward into the 2016 California Plumbing Code, as follows:

**CHAPTER 4
PLUMBING FIXTURES AND FIXTURE FITTINGS**

~~403.2.1 Water Closets on or after July 1, 2011 [HCD 1 & HCD 2] Water closets, either flush tank, flushometer tank, or flushometer valve operated installed on or after July 1, 2011, shall have an effective flush volume in compliance with the following:~~

- ~~(1) Single Flush Toilets—The effective flush volume shall not exceed 1.28 gallons (4.8 liters) when tested in accordance with ASME A112.19.2, Standard for Vitreous China Plumbing Fixtures and Hydraulic Fixtures Requirements for Water Closets and Urinals~~

~~(2) Dual Flush Toilets—The effective flush volume shall not exceed 1.28 gallons (4.8 liters) when tested in accordance with ASME A112.19.2, Standard for Vitreous China Plumbing Fixtures and Hydraulic Fixtures Requirements for Water Closets and Urinals, and ASME A112.19.14, Standard for Six Liter Water Closets Equipped with a Dual Flushing Device.~~

~~**403.3.1.1 Nonwater Urinal Drainage Connections.** Where nonwater urinals are installed, not less than one water supplied fixture rated at not less than 1 drainage fixture unit (DFU) shall be installed upstream on the same drain line to facilitate drain line flow and rinsing.~~

403.4 Metered Faucets. Self-closing or self-closing metering faucets shall be installed on lavatories intended to serve the transient public, such as those in, but not limited to, service stations, train stations, airports, restaurants, and convention halls. ~~Metered faucets shall deliver a maximum of 0.25 gallons (0.95 L) of water per use.~~

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

8. HCD proposes to adopt Chapter 5 from the 2015 Uniform Plumbing Code and bring forward existing amendments from the 2013 California Plumbing Code into the 2016 California Plumbing Code as follows:

**CHAPTER 5
WATER HEATERS**

507.2 Seismic Provisions. ~~In seismic design categories C, D, E, and F, water~~ Water heaters shall be anchored or strapped to resist horizontal displacement due to earthquake motion. Strapping shall be at points within the upper one-third and lower one-third of its vertical dimensions. At the lower point, a minimum distance of not less than 4 inches (102 mm) shall be maintained from the controls with the strapping.

Note: ~~(HCD 1 & HCD 2) Reference Health and Safety Code Section 19211(a) which addresses new, replacement, and existing water heaters.~~

~~Section 19211(a) Notwithstanding Section 19100, all new and replacement water heaters, and all existing residential water heaters shall be braced, anchored, or strapped to resist falling or horizontal displacement due to earthquake motion. At a minimum, any water heater shall be secured in accordance with the California Plumbing Code, or modifications made thereto by a city, county, or city and county pursuant to Section 17958.5.~~

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

-
9. **HCD proposes to adopt Chapter 6 (except Section 609.10) from the 2015 Uniform Plumbing Code with new amendments and bring forward existing amendments from the 2013 California Plumbing Code into the 2016 California Plumbing Code as follows:**

**CHAPTER 6
WATER SUPPLY AND DISTRIBUTION**

601.2 Hot and Cold Water Required. (Formerly 601.1 General) Except where not deemed necessary for safety or sanitation by the Authority Having Jurisdiction, each plumbing fixture shall be provided with an adequate supply of potable running water piped thereto in an approved manner, so arranged as to flush and keep it in a clean and sanitary condition without danger of backflow or cross-connection. Water closets and urinals shall be flushed by means of an approved flush tank or flushometer valve.

Exceptions:

1. Listed fixtures that do not require water for their operation and are not connected to the water supply.
2. **(HCD 1 & HCD 2)** For limited-density owner-built rural dwellings, potable water shall be available to the dwelling site, although such water need not be pressurized. Where water is not piped from a well, spring, cistern or other source, there shall be a minimum reserve of 50 gallons (189 L) of potable water available. Where water delivery is pressurized, piping shall be installed in accordance with the provisions of this chapter.
3. ~~**(HCD 1 & HCD 2)** Where deemed not necessary for safety or sanitation by the Enforcing Agency.~~
4. **3. (HCD 1 & HCD 2)** Recycled water or treated graywater may be allowed as specified in Chapter 16A Part II, and on-site treated nonpotable gray water as specified in Chapter 15, Section 1504 of this code.

In occupancies where plumbing fixtures are installed for private use, hot water shall be required for bathing, washing, laundry, cooking purposes, dishwashing or maintenance. In occupancies where plumbing fixtures are installed for public use, hot water shall be required for bathing and washing purposes. This requirement shall not supersede the requirements for individual temperature control limitations for public lavatories and public and private bidets, bathtubs, whirlpool bathtubs, and shower control valves.

601.3.2 (Formerly 601.2.2) Color and Information. Each system shall be identified with a colored pipe or band and coded with paints, wraps and materials compatible with the piping.

Except as required in Sections 601.3.3, nonpotable water systems shall have a yellow background with black uppercase lettering, with the words "CAUTION: NONPOTABLE WATER, DO NOT DRINK." Each nonpotable system shall be identified to designate the liquid being conveyed, and the direction of normal flow shall be clearly shown. The minimum size of the letters and length of the color field shall comply with Table 601.3.2. **(HCD 1 & HCD 2)** An international symbol of a glass in a circle with a slash through it shall be provided similar to that shown in Figure 601 for all nonpotable water systems.

The background color and required information shall be indicated every twenty 20 feet (6096 mm) but not less than once per room, and shall be visible from the floor level.



**FIGURE 601
INTERNATIONAL SYMBOL**

603.5.11 Nonpotable Water Piping. In cases where it is impractical to correct individual cross-connections on the domestic waterline, the line supplying such outlets shall be considered a nonpotable water line. No drinking or domestic water outlets shall be connected to the nonpotable waterline. Where possible, portions of the nonpotable waterline shall be exposed, and exposed portions shall be properly identified in a manner satisfactory to the Authority Having Jurisdiction. Each outlet on the nonpotable waterline that is permitted to be used for drinking or domestic purposes shall be posted: "CAUTION: NONPOTABLE WATER, DO NOT DRINK." (HCD 1 & HCD 2) An international symbol of a glass in a circle with a slash through it shall be provided similar to that shown in Figure 601.

TABLE 604.1
MATERIALS FOR BUILDING SUPPLY AND WATER DISTRIBUTION WATER PIPING AND FITTINGS

....(No Changes to Table)

For Building Supply or cold-water applications.

- ¹ When PEX tubing is placed in soil and is used in potable water systems intended to supply drinking water to fixtures or appliances, the tubing or piping shall be sleeved with a material approved for potable water use in soil or other material that is impermeable to solvents or petroleum products.
- ² PEX tubing shall meet or exceed the requirements of ASTM F876-08~~2013a~~ or an equivalent or more stringent standard when used in continuously recirculating hot water systems and the PEX tubing is exposed to the hot water 100% of the time.
- ³ The use of PEX-AL-PEX in potable water supply systems is not adopted.

604.1.1 Local Authority to Approve CPVC Pipe Within Residential Buildings Under Specified Conditions. (HCD 1 & HCD 2) The local responsible building official of any city, county, or city and county, shall authorize by permit the use of CPVC for hot and cold water distribution systems within the interior of residential buildings provided all of the following conditions are satisfied:

- (a) **Permit Conditions.** Any building permit issued pursuant to Section 604.1.1 shall be conditioned on compliance with the mitigation measures set forth in this section.
- (b) **Approved Materials.** Only CPVC plumbing material listed as an approved material and installed in accordance with this code may be used.
- (c) **Installation and Use.** Any installation and use of CPVC plumbing material pursuant to this section shall comply with all applicable requirements of this code and ~~Section 1.2 of Appendix I of this code, Installation Standard for CPVC Solvent Cemented Hot and Cold Water Distribution Systems, IAPMO IS 20-2010~~ the manufacturer's installation instructions.
- (d) **Certification of Compliance.** Prior to issuing a building permit pursuant to Section 604.1.1, the building official shall require as part of the permitting process that the contractor, or the appropriate plumbing subcontractors, provide written certification: (1) that is required in subdivision (e), and (2) that he or she will comply with the flushing procedures and worker safety measures ~~set forth in Section 1.2 of Appendix I of this code, Installation Standard for CPVC Solvent Cemented Hot and Cold Water Distribution Systems, IAPMO (IS 20-2010)~~ of this code and the manufacturer's installation instructions.
- (e) **Worker Safety.** Any contractor applying for a building permit that includes the use of CPVC plumbing materials authorized pursuant to this section shall include in the permit application a signed written certification stating that:
 - (1) They are aware of the health and safety hazards associated with CPVC plumbing installations;
 - (2) They have included in their Injury and Illness Prevention Plan the hazards associated with CPVC plumbing pipe installations; and
 - (3) The worker safety training elements of their Injury and Illness Prevention Plan meet the Department of Industrial Relation's guidelines.
- (f) **Findings of Compliance.** The building official shall not give final permit approval of any CPVC plumbing materials installed pursuant to Section 604.1.1 unless he or she finds that the material has been installed in compliance with the requirements of this code ~~and that the installer has complied with the requirements in Section 1.2.1 of Appendix I of this code, Installation Standards for CPVC Solvent~~

Cemented Hot and Cold Water Distribution Systems, (IAPMO IS 20-2010) and the manufacturer's installation instructions.

- (g) **Penalties.** Any contractor or subcontractor found to have failed to comply with the flushing, requirements of Section 1.2.1 of Appendix I of this code or the ventilation, and glove requirements of Section 1.2.2 of Appendix I of this code, Installation Standards for CPVC Solvent Cemented Hot and Cold Water Distribution Systems, (IAPMO IS 20-2010) of this code and the manufacturer's installation instructions shall be subject to the penalties in Health and Safety Code, Division 13, Part 1.5, Chapter 6 (Section 17995 et seq.). In addition, if during the conduct of any building inspection the building official finds that the ventilation and glove requirements of Section 2.7.1 of Appendix I of this code, "Special Requirements for CPVC Installation within Residential Buildings," this code are being violated, such building officials shall cite the contractor or subcontractor for that violation

***Informative Note: (Do not Publish in Code) The following provisions have been relocated from an existing California amendment in Installation Standard IAPMO IS-20-2010.

4.2 (h) Special Requirements for CPVC Installation within Residential Structures. (HCD 1)

In addition to the other requirements in the California Plumbing Code and this Appendix for the installation of CPVC Solvent Cemented Hot and Cold Water Distributions Systems, all installations of CPVC pipe within residential structures shall meet the following:

- 4.2.1 (i) Flushing Procedures. (HCD 1)** All installations of CPVC pipe within residential structures shall be flushed twice over a period of at least one (1) week. The pipe system shall be first flushed for at least 10 minutes and then filled and allowed to stand for no less than 1 week, after which all the branches of the pipe system must be flushed long enough to fully empty the contained volume. At the time of the fill, each fixture shall have a removable tag applied stating:

"This new plumbing system was first filled on (date) by (name). The California Department of Housing and Community Development requires that the system be flushed after standing at least one week after the fill date specified above. If the system is used earlier than one week after the fill date, the water must be allowed to run for at least two minutes prior to use for human consumption. This tag may not be removed prior to flushing, except by the homeowner."

- 4.2.2 (j) Worker Safety Measures. (HCD 1)** Mechanical ventilation sufficient to maintain exposures below the relevant exposure limits established by state regulation shall be provided in enclosed spaces. This ventilation shall be directed at the breathing zone of the worker installing the pipe. Where mechanical ventilation is not practical, respirators, suitable for organic vapors, shall be used. For the purpose of this subdivision, an enclosed space is defined as:

- (a) (1) A space less than 100 square feet of floor area under a ceiling with a height of 10 feet or less, and which does not have openings (consisting of doors, windows, or unfinished walls) on at least two sides;
- (b) (2) Crawl spaces having a height of less than three feet;
- (c) (3) Enclosed attics that have a roof and ceiling; or
- (d) (4) Trenches having a depth greater than 24 inches.

Installers of CPVC pipe within residential structures shall use non-latex thin gauge (4 millimeters) nitrile gloves, or other gloves providing an equivalent or better degree of protection during the installation of the CPVC plumbing system. Gloves shall be provided to all workers by the contractor, or plumbing subcontractor, and shall be replaced upon contamination by cements.

604.1.2 PEX. All installations of PEX pipe where it is the initial plumbing piping installed in new construction shall be flushed twice over a period of at least one week. The pipe system shall be first flushed for at least 10 minutes and then filled and allowed to stand for no less than 1 week, after which all the branches of the pipe system must be flushed long enough to fully empty the contained volume. This provision shall not apply to the installation of PEX pipe where it replaces an existing pipe system of any material.

- (1) At the time of fill, each fixture shall have a removable tag applied stating:

- (a) "This new plumbing system was first filled and flushed on _____ (date) by _____ (name). The State of California requires that the system be flushed after standing at least one week after the fill date specified above. If this system is used earlier than one week after the fill date, the water must be allowed to run for at least two minutes prior to use for human consumption. This tag may not be

removed prior to the completion of the required second flushing, except by the building owner or occupant."

- (2) Prior to issuing a building permit to install PEX pipe, the building official shall require as part of the permitting process that the contractor, or the appropriate plumbing subcontractors, provide written certification that he or she will comply with the flushing procedures set forth in the code.
- (3) The building official shall not give final permit approval of any PEX plumbing installation unless he or she finds that the material has been installed in compliance with the requirements of the code, including the requirements to flush and tag the systems.
- (4) Any contractor or subcontractor found to have failed to comply with the PEX flushing requirements shall be subject to the penalties in Health and Safety Code, Division 13, Part 1.5, Chapter 6 (Section 17995, et seq.).

604.13 Water Heater Connectors. Flexible metallic (copper and stainless steel), reinforced flexible, braided stainless steel, or polymer braided with EPDM core connectors that connect a water heater to the piping system shall be in accordance with ASME A112.18.6/CSA B125.6. Copper, copper alloy, or stainless steel flexible connectors shall not exceed 24 inches (610 mm). PEX, PEX-AL-PEX, PE-AL-PE, or PE-RT tubing shall not be installed within the first 18 inches (457 mm) of piping connected to a water heater.

(HCD 1 & HCD 2) PEX-AL-PEX is not adopted for use in potable water supply and distribution systems.

605.2.2 (Formerly 605.4.2) Solvent Cement Joints. Solvent cement joints for CPVC pipe and fittings shall be clean from dirt and moisture. Solvent cements in accordance with ASTM F 493, requiring the use of a primer shall be orange in color. The primer shall be colored and be in accordance with ASTM F 656. Listed solvent cement in accordance with ASTM F 493 that does not require the use of primers, yellow or red in color, shall be permitted for pipe and fittings manufactured in accordance with ASTM D 2846, ½ of an inch (15 mm) through 2 inches (50 mm) in diameter or ASTM F 442, ½ of an inch (15 mm) through 3 inches (80 mm) in diameter. Apply primer where required inside the fitting and to the depth of the fitting on pipe. Apply liberal coat of cement to the outside surface of pipe to depth of fitting and inside of fitting. Place pipe inside fitting to forcefully bottom the pipe in the socket and hold together until joint is set.

(HCD 1 & HCD 2) Low VOC One-Step Cement that does not require the use of primer shall be utilized with CPVC pipe and fittings, manufactured in accordance with ASTM D 2846.

605.10 (Formerly 605.11) PEX-AL-PEX Plastic Tubing and Joints. PEX-AL-PEX plastic pipe or tubing and fitting joining methods shall be installed in accordance with the manufacturer's installation instructions and shall comply with 605.10.1 and Section 605.10.1.1

(HCD 1 & HCD 2) PEX-AL-PEX is not adopted for use in potable water supply and distribution systems.

605.12.2 (Formerly 605.13.2) Solvent Cement Joints. Solvent cement joints for PVC pipe and fittings shall be clean from dirt and moisture. Pipe shall be cut square and pipe shall be deburred. Where surfaces to be joined are cleaned and free of dirt, moisture, oil, and other foreign material, apply primer purple in color in accordance with ASTM F 656. Primer shall be applied until the surface of the pipe and fitting is softened. Solvent cements in accordance with ASTM D 2564 shall be applied to all joint surfaces. Joints shall be made while both the inside socket surface and outside surface of pipe are wet with solvent cement. Hold joint in place and undisturbed for 1 minute after assembly.

(HCD 1 & HCD 2) Plastic pipe and fittings joined with solvent cement shall utilize Low VOC primer(s), if a primer is required, and Low VOC solvent cement(s) as defined in Section 214.

605.15 (Formerly 605.16) Dielectric Unions. Dielectric unions where installed at points of connection where there is a dissimilarity of metals shall be in accordance with ASSE 1079. *(HCD 1 & HCD 2) Dielectric unions shall be used at all points of connection where there is a dissimilarity of metals.*

607.1 General. Potable water supply tanks shall be installed in accordance with the manufacturer's installation instructions, and supported in accordance with the building code California Building Code.

609.10 Water Hammer. *(Not adopted by HCD)*

**TABLE 610.3
WATER SUPPLY FIXTURE UNITS (WSFU) AND MINIMUM FIXTURE BRANCH PIPE SIZES ³**

| APPLIANCES, APPURTENANCES OR FIXTURES ² | MINIMUM FIXTURE BRANCH PIPE SIZE ^{1,4} (inches) | PRIVATE | PUBLIC | ASSEMBLY ⁶ |
|---|--|-----------------|--------|-----------------------|
| Mobile Home <i>Mobilehome or Manufactured Home</i> , each (minimum) ⁵ | — | 42.0 <u>6.0</u> | — | — |

For SI units: 1 inch = 25 mm

Notes:

⁹ ~~[HCD-2]~~ For water supply fixture unit values related to lots within mobilehome parks in all parts of the State of California, see California Code of Regulations, Title 25, Division 1, Chapter 2, Article 5, Section 1278. For water supply fixture unit values related to lots within special occupancy parks in all parts of the State of California, see California Code of Regulations, Title 25, Division 1, Chapter 2.2, Article 5, Section 2278.

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

10. HCD proposes to repeal an existing California amendment from Chapter 6 of the 2013 California Plumbing Code as follows:

**CHAPTER 6
WATER SUPPLY AND DISTRIBUTION**

604.11 Lead Content. Water pipe and fittings with a lead content which exceeds 8 percent shall be prohibited in piping systems used to convey potable water.

~~**Note:** On or after January 1, 2010, see Section 116875 of the Health and Safety Code for the lead content of pipes, pipe or plumbing fittings, or fixtures intended to convey or dispense water for human consumption.~~

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

11. HCD proposes to adopt Chapter 7 from the 2015 Uniform Plumbing Code with new amendments and bring forward existing amendments from the 2013 California Plumbing Code into the 2016 California Plumbing Code as follows:

**CHAPTER 7
SANITARY DRAINAGE**

Part I – Drainage Systems.

701.2 (Formerly 701.1) Drainage Piping. Materials for drainage piping shall be in accordance with one of the referenced standards in Table 701.2 except that:

- (1) No galvanized wrought-iron or galvanized steel pipe shall be used underground and shall be kept not less than 6 inches (152 mm) aboveground.
- (2) ABS and PVC DWV piping installations shall be installed in accordance with applicable standards referenced in Table 1701.1, and Chapter 14 "Firestop Protection" this code, and the California Building Code. Except for individual single-family dwelling units, materials exposed within ducts or plenums shall have a flame-spread index of a maximum of 25 and a smoke-developed index of a maximum 50, where tested in accordance with ASTM E84 or UL 723.
 - (a) **(HCD 1 & HCD 2)** *ABS and PVC installations are limited to not more than two stories of areas of residential accommodation.*
- (3) No vitrified clay pipe or fittings shall be used aboveground or where pressurized by a pump or ejector. They shall be kept not less than 12 inches (305 mm) belowground.
- (4) Copper or copper alloy tube for drainage and vent piping shall have a weight of not less than that of copper or copper alloy drainage tube type DWV.
- (5) Stainless steel 304 pipe and fittings shall not be installed underground and shall be kept not less than 6 inches (152 mm) aboveground.
- (6) Cast-iron soil pipe and fittings shall be listed and tested in accordance with standards referenced in Table 1701.1. Such pipe and fittings shall be marked with the country of origin and identification of the original manufacturer in addition to markings required by referenced standards.

**TABLE 702.1
DRAINAGE FIXTURE UNIT VALUES (DFU)**

| PLUMBING APPLIANCES, APPURTENANCES, OR FIXTURES | MINIMUM SIZE TRAP AND TRAP ARM ⁷ (INCHES) | PRIVATE | PUBLIC | ASSEMBLY ⁸ |
|--|--|-----------------|--------|-----------------------|
| Mobile Home <u>Mobilehome or Manufactured Home</u> , trap ⁹ | 3 | 42.0 <u>6.0</u> | — | — |

For SI units: 1 inch = 25 mm

Notes:

⁹ **[HCD 2]** For drainage fixture unit values related to lots within mobilehome parks in all parts of the State of California, see California Code of Regulations, Title 25, Division 1, Chapter 2, Article 5, Section 1268. For drainage fixture unit values related to lots within special occupancy parks in all parts of the State of California, see California Code of Regulations, Title 25, Division 1, Chapter 2.2, Article 5, Section 2268.

705.1.2 Solvent Cement Joints. Solvent cement joints for ABS pipe and fittings shall be clean from dirt and moisture. Pipe shall be cut square and shall be deburred. Where surfaces to be joined are cleaned and free of dirt, moisture, oil, and other foreign material, solvent cement in accordance with ASTM D2235 shall be applied to all joint surfaces. Joints shall be made while both the inside socket surface and outside surface of pipe are wet with solvent cement. Hold joint in place and undisturbed for 1 minute after assembly.

(HCD 1 & HCD 2) Plastic pipe and fittings joined with solvent cement shall utilize Low VOC primer(s), if a primer is required, and Low VOC cement(s) as defined in Section 214.0.

705.5.2 Solvent Cement Joints. Solvent cement joints for PVC pipe and fittings shall be clean from dirt and moisture. Pipe shall be cut square and pipe shall be deburred. Where surfaces to be joined are cleaned and free of dirt, moisture, oil, and other foreign material, apply primer purple in color in accordance with ASTM F656. Primer shall be applied until the surface of the pipe and fitting is softened. Solvent cements in accordance with ASTM D2564 shall be applied to all joint surfaces. Joints shall be made while both the inside socket surface and outside surface of pipe are wet with solvent cement. Hold joint in place and undisturbed for 1 minute after assembly.

(HCD 1 & HCD 2) Plastic pipe and fittings joined with solvent cement shall utilize Low VOC primer(s), if a primer is required, and Low VOC cement(s) as defined in Section 214.0.

705.8.4 (Formerly 705.10.4) Transition Joint. A solvent cement transition joint between ABS and PVC building drain and building sewer shall be made using listed transition solvent cement in accordance with ASTM D3138.
(HCD 1 & HCD 2) Plastic pipe and fittings joined with solvent cement shall utilize Low VOC primer(s), if a primer is required, and Low VOC solvent cement(s) as defined in Section 214.0.

710.3 Sewage Ejector and Pumps. A sewage ejector or sewage pump receiving the discharge of water closets or urinals:

- (1) Shall have a discharge capacity of not less than 20 gpm (1.26 L/s).
- (2) In single dwelling units, the ejector or pump shall be capable of passing a 1 1/2 inch (38 mm) diameter solid ball, and the discharge piping of each ejector or pump shall have a backwater valve and gate valve, and be not less than 2 inches (50 51 mm) in diameter.
- (3) In other than single-dwelling units, the ejector or pump shall be capable of passing a 2 inch (51 mm) diameter solid ball, and the discharge piping of each ejector or pump shall have a backwater valve and gate valve, and be not less than 3 inches (80 mm) in diameter.

710.3.1 (HCD 1 & HCD 2) The minimum size of any pump or any discharge pipe from a sump having a water closet connected thereto shall be not less than (2) inches (50 51 mm).

713.4 Public Sewer Availability. The public sewer shall be permitted to be considered as not being available where such public sewer or a building or an exterior drainage facility connected thereto is located more than 200 feet (60 960 mm) from a proposed building or exterior drainage facility on a lot or premises that abuts and is served by such public sewer.

(HCD 1) For residential occupancies, the public sewer may be considered as not being available by the Authority Having Jurisdiction.

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

12. HCD proposes to adopt Chapter 8 from the 2015 Uniform Plumbing Code into the 2016 California Plumbing Code without amendment:

CHAPTER 8 INDIRECT WASTES

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

13. HCD proposes to adopt Chapter 9 from the 2015 Uniform Plumbing Code with new amendments, and bring forward existing amendments from the 2013 California Plumbing Code into the 2016 California Plumbing Code as follows:

**CHAPTER 9
VENTS**

903.1 Applicable Standards. Vent pipe and fittings shall comply with the applicable standards referenced in Table 701.2, except that:

- (1) No galvanized steel or 304 stainless steel pipe shall be install underground and shall be not less than 6 inches (152 mm) aboveground.
- (2) ABS and PVC DWV piping installations shall be in accordance with the applicable standards referenced in Table 1701.1, and Chapter 14 "Firestop Protection" *this code, and the California Building Code*. Except for individual single-family dwelling units, materials exposed within ducts or plenums shall have a flame-spread index of not more than 25 and a smoke-developed index of not more than 50 where tested in accordance with ASTM E84 or UL 723.

903.1.1 (HCD 1 & HCD 2) *ABS or PVC installations are limited to not more than two stories of areas of residential accommodation.*

903.1.2 (HCD 1) *All malleable iron vents shall be galvanized.*

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

14. HCD proposes to adopt Chapter 10 from the 2015 Uniform Plumbing Code with a new amendment and bring forward existing amendments from the 2013 California Plumbing Code into the 2016 California Plumbing Code as follows:

**CHAPTER 10
TRAPS AND INTERCEPTORS**

1003.1 General Requirements. Each trap, except for traps within an interceptor or similar device shall be self-cleaning. Traps for bathtubs, showers, lavatories, sinks, laundry tubs, floor drains, urinals, drinking fountains, dental units, and similar fixtures shall be of standard design, weight and shall be of ABS, cast-brass, cast-iron, lead, PP, PVC, or other approved material. An exposed and readily accessible drawn-copper alloy tubing trap, not less than 17 B & S Gauge (0.045 inch) (1.143 mm), shall be permitted to be used on fixtures discharging domestic sewage.

Exceptions:

- (2) **(HCD 1 & HCD 2)** *Non-water supplied urinals conforming to ASME A112.19.19-2006, Standard for Vitreous China Nonwater Urinals, or reference standards in Table 4401.4 1701.1 for non-vitreous ceramic or plastic urinal fixtures.*

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690,

18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

15. HCD proposes to adopt Chapter 11 from the 2015 Uniform Plumbing Code with new amendments and bring forward existing amendments from the 2013 California Plumbing Code into the 2016 California Plumbing Code as follows:

**CHAPTER 11
STORM DRAINAGE**

1101.4 (Formerly 1101.3) Material Uses. Pipe, tube, and fittings conveying rainwater shall be of such materials and design as to perform their intended function to the satisfaction of the Authority Having Jurisdiction. Conductors within a vent or shaft shall be of cast-iron, galvanized steel, wrought iron, copper, copper alloy, lead, Schedule 40 ABS DWV, Schedule 40 PVC DWV, stainless steel 304 or 316L (stainless steel 304 pipe and fittings shall not be installed underground and shall be kept not less than 6 inches (152 mm) aboveground), or other approved materials, and changes in direction shall be in accordance with the requirements of Section 706.0. ABS and PVC DWV piping installations shall be installed in accordance with ~~Chapter 14 "Firestop Protection" this code, and the California Building Code.~~ Except for individual single-family dwelling units, materials exposed within ducts or plenums shall have a flame-spread index of a maximum of 25 and a smoke-developed index of a maximum of 50, where tested in accordance with ASTM E84 and UL 723.

(HCD 1) ABS or PVC installations are limited to not more than two stories of areas of residential accommodation.

1101.4.2.1 (Formerly 1102.1.2) (HCD 1) *ABS or PVC installations are limited to not more than two stories of areas of residential accommodation.*

1101.6 (Formerly 1101.5) Subsoil Drains. Subsoil drains shall be provided around the perimeter of buildings having basements, cellars, or crawl spaces or floors below grade. Such subsoil drains shall be permitted to be positioned inside or outside of the footing, shall be of perforated or open-jointed approved drain tile or pipe, not less than 3 inches (80 mm) in diameter, and shall be laid in gravel, slag, crushed rock, approved 3/4 inch (19.1 mm) crushed, recycled glass aggregate, or other approved porous material with not less than 4 inches (102 mm) surrounding the pipe. Filter media shall be provided for exterior subsoil piping.

Exception: (HCD 1 & HCD 2) *Subsoil drains are mandatory only when required by the Authority Having Jurisdiction due to geological conditions.*

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

16. HCD proposes to adopt Chapter 12 from the 2015 Uniform Plumbing Code into the 2016 California Plumbing Code without amendment.

**CHAPTER 12
FUEL GAS PIPING**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

17. HCD proposes to NOT adopt Chapter 13 from the 2015 Uniform Plumbing Code.

**CHAPTER 13
HEALTH CARE FACILITIES AND MEDICAL GAS AND MEDICAL VACUUM SYSTEMS**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

18. HCD proposes to NOT adopt Chapter 14 from the 2015 Uniform Plumbing Code.

**CHAPTER 14
FIRESTOP PROTECTION**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

19. HCD proposes to adopt Chapter 15 from the 2015 Uniform Plumbing Code with new amendments and bring forward existing amendments from the 2013 California Plumbing Code into the 2016 California Plumbing Code as follows:

**CHAPTER 15
ALTERNATE WATER SOURCES FOR NONPOTABLE APPLICATIONS**

Intent

The provisions of this chapter are intended to:

1. Conserve water by facilitating greater reuse of laundry, shower, lavatory and similar sources of discharge for irrigation and/or indoor use.
2. Reduce the number of non-compliant gray water systems by making legal compliance easily achievable.
3. Provide guidance for avoiding potentially unhealthful conditions.
4. Provide an alternative way to relieve stress on a private sewage disposal system by diverting the gray water.

1501.1 (Formerly 1601.1) Applicability. (HCD 1) *Except as otherwise provided for in this chapter, the provisions of this code shall be applicable to alternate water source system installation. The provisions of this chapter shall apply to the construction, alteration, discharge, use and repair of alternate water source systems for nonpotable applications.*

1501.1.1 (Formerly 1601.1.1) Allowable Use of Alternate Water. Where approved or required by the Authority Having Jurisdiction, alternate water sources [reclaimed (recycled) water, gray water and on-site treated nonpotable gray water] shall be permitted to be used in lieu of potable water for the applications identified in this chapter.

1501.2 System Design. ~~Alternate water source systems shall be designed in accordance with this chapter by a registered design professional or who demonstrates competency to design the alternate water source system as required by the Authority Having Jurisdiction. Components, piping, and fittings used in an alternate water source system shall be listed.~~

Exceptions:

- (1) ~~A registered design professional is not required to design gray water systems having a maximum discharge capacity of 250 gallons per day (gal/d) (0.011 L/s) for single family and multi family dwellings.~~
- (2) ~~A registered design professional is not required to design an on-site treated nonpotable water system for single family dwellings having a maximum discharge capacity of 250 gal/d (0.011 L/s).~~

1501.2 System Design. (Formerly 1601.2 System Design.) (HCD 1) *Alternate water source systems complying with this chapter shall be designed by a person who demonstrates competency to design the alternate water source system as required by the Enforcing Agency. The Enforcing Agency may also require plans and specifications to be prepared by a licensed design professional for Complex Systems. Components, piping, and fittings used in any alternate water source system shall be listed.*

1501.3 (Formerly 1601.3) Permit. It shall be unlawful for a person to construct, install, alter, or cause to be constructed, installed, or altered an alternate water source system in a building or on a premise without first obtaining a permit to do such work from the Authority Having Jurisdiction. *Prior to commencing the issuance of permits for indoor gray water systems pursuant to state requirements relating to gray water, a city, county, city and county or other local agency shall seek consultation with the local public health department to ensure that local public health concerns are addressed in local standards or ordinances, or in issuing permits. See California Water Code Section 14877.3.*

Exception: (HCD 1) *A construction permit shall not be required for a clothes washer system meeting the requirements of Section 4602.4.4 1502.1.1.*

1501.5 (Formerly 1601.5) Maintenance and Inspection. Alternate water source systems and components shall be inspected and maintained in accordance with Section 1501.5.1 through Section 1501.5.3 *the manufacturer's recommendations and/or as required by the Enforcing Agency.*

1501.5.1 Frequency. ~~Alternate water source systems and components shall be inspected and maintained in accordance with Table 1501.5 unless more frequent inspection and maintenance is required by the manufacturer.~~

1501.5.2 Maintenance Log. ~~A maintenance log for gray water, rainwater, and on-site treated nonpotable water systems is required to have a permit in accordance with Section 1501.3 and shall be maintained by the property owner and be available for inspection. The property owner or designated appointee shall ensure that a record of testing, inspection and maintenance in accordance with Table 1501.5 is maintained in the log. The log will indicate the frequency of inspection and maintenance for each system.~~

1501.5.3 1501.5.1 (Formerly 1601.5.1) Maintenance Responsibility. The required maintenance and inspection of alternate water source systems shall be the responsibility of the property owner, unless otherwise required by the Authority Having Jurisdiction.

1501.6 (Formerly 1601.6) Operation and Maintenance Manual. An operation and maintenance manual for gray water and on-site treated water systems required to have a permit in accordance with Section 1501.3 shall be supplied to the building owner by the system designer or installer. The operating and maintenance manual shall include the following:

- (1) ~~Detailed diagram~~ *Diagram(s)* of the entire system and the location of system components.
- (2) Instructions on operating and maintaining the system.
- (3) ~~Details-Instructions~~ on maintaining the required water quality as determined by the Authority Having Jurisdiction for on-site treated nonpotable water systems.
- (4) Details on *startup, shutdown, and deactivating* the system for maintenance, repair, or other purposes.
- (5) Applicable testing, inspection, and maintenance frequencies in accordance with ~~Table~~ *Section 1501.5*.
- (6) A method of contacting the *installer and/or manufacturer(s)*.
- (7) *Directions to the owner or occupant that the manual shall remain with the building throughout the life cycle of the structure.*

1501.7 (Formerly 1601.7.2) Minimum Water Quality Requirements. (HCD 1) The minimum water quality for alternate water source systems shall meet the applicable water quality requirements for the intended application as determined by the Authority Having Jurisdiction. In the absence of water quality requirements, ~~the EPA/625/R-04/108 contains recommended water reuse guidelines to assist regulatory agencies develop, revise, or expand alternate water source water quality standards for on-site treated nonpotable gray water systems, the requirements of NSF 350 the following water quality requirements shall apply:~~

- 1) ~~For owner occupied single family dwellings NSF/ANSI 350.~~
- 2) ~~For R-1 and R-2 occupancies, the California Department of Public Health statewide uniform criteria for disinfected tertiary recycled water as provided in California Code of Regulations, Title 22, Section 60301.230.~~

Exception:

Water treatment is not required for gray water used *in a disposal field* or for subsurface or subsoil irrigation.

1501.10 (Formerly 1604.11.1) Commercial, Industrial, and Institutional, and Residential Restroom Signs. A sign shall be installed in restrooms in commercial, industrial, and institutional occupancies, *and shall also be installed in residential common use area restrooms* using reclaimed (recycled) water and on-site treated nonpotable gray water for water closets, urinals, or both. Each sign shall contain ~~1/2 of an inch (12.7 mm) letters of a highly visible color on a contrasting background. The location of the sign(s) shall be such that the sign(s) are visible to users. The location of the sign(s) shall be approved by the Authority Having Jurisdiction and shall contain the following text:~~

TO CONSERVE WATER, THIS BUILDING USES ON-SITE TREATED NONPOTABLE GRAY WATER TO FLUSH TOILETS AND URINALS.

**TABLE 1501.5
MINIMUM ALTERNATE WATER SOURCE TESTING, INSPECTION, AND MAINTENANCE FREQUENCY**

| DESCRIPTION | MINIMUM FREQUENCY |
|--|--|
| Inspect and clean filters and screens, and replace (where necessary). | Every 3 months |
| Inspect and verify that disinfection, filters and water quality treatment devices and systems are operational and maintaining minimum water quality requirements as determined by the Authority Having Jurisdiction. | In accordance with manufacturer's instructions, and the Authority Having Jurisdiction. |
| Inspect pumps and verify operation. | After initial installation and every 12 months thereafter |
| Inspect valves and verify operation. | After initial installation and every 12 months thereafter |
| Inspect pressure tanks and verify operation. | After initial installation and every 12 months thereafter |
| Clear debris from and inspect storage tanks, locking devices, and verify operation. | After initial installation and every 12 months thereafter |
| Inspect caution labels and marking. | After initial installation and every 12 months thereafter. |
| Inspect and maintain mulch basins for gray water irrigation systems. | As needed to maintain mulch depth and prevent ponding and runoff. |
| Cross-connection inspection and test* | After initial installation and every 12 months thereafter. |

*The cross-connection test shall be performed in the presence of the Authority Having Jurisdiction in accordance with the requirements of this chapter.

1501.10.1 (Formerly 1604.11.2) Equipment Room Signs. Each room containing reclaimed (recycled) and on-site treated gray water equipment shall have a sign posted in a location that is visible to anyone working on or near nonpotable gray water equipment with the following wording in 1 inch (25.4 mm) letters:

CAUTION: NONPOTABLE * _____ *, DO NOT DRINK. DO NOT CONNECT TO DRINKING WATER SYSTEM. NOTICE: CONTACT BUILDING MANAGEMENT BEFORE PERFORMING ANY WORK ON THIS WATER SYSTEM.

* _____ * Shall indicate RECLAIMED (RECYCLED) WATER or ON-SITE TREATED GRAY WATER, accordingly.

1501.11.2 (Formerly 1604.12.2) Annual Cross-Connection Inspection and Testing. An initial and subsequent annual inspection and test shall be performed on both the potable and gray alternate water source systems. The potable and gray alternate water source system shall be isolated from each other and independently inspected and tested to ensure there is no cross-connection in accordance with Section 1501.11.2.1 through Section 1501.11.2.4.

1502.0 Gray Water Systems.

1502.1 (Formerly 1602.1) General. The provisions of this section shall apply to the construction, alteration, and repair of gray water systems. *A city, county, or city and county or other local government may adopt, after a public hearing and enactment of an ordinance or resolution, building standards that are more restrictive than the gray water building standards adopted in this code. For additional information, see Health and Safety Code Section 18941.7.*

- (A) All gray water systems shall be designed with a diverter valve to allow the user to direct the flow to the building sewer and either the irrigation field or disposal field, whichever is used. The means of changing the direction of the gray water shall be clearly labeled and readily accessible to the user.
- (B) Water used to wash diapers or similarly soiled or infectious garments or other prohibited contents shall be diverted by the user to the building sewer.
- (C) Gray water shall not be used in spray irrigation, allowed to pond or runoff and shall not be discharged directly into or reach any storm sewer system or any surface body of water.
- (D) Human contact with gray water or the soil irrigated by gray water shall be minimized and avoided, except as required to maintain the gray water system. The discharge point of any gray water subsoil irrigation or subsurface irrigation field shall be covered by at least (2) inches (51 mm) of mulch, rock, or soil, or a solid shield to minimize the possibility of human contact.

- (E) Gray water may be released above the ground surface provided at least two (2) inches (51 mm) of mulch, rock, or soil, or a solid shield covers the release point. Other methods which provide equivalent separation are also acceptable.
- (F) Gray water shall not contain hazardous chemicals derived from activities such as cleaning car parts, washing greasy or oily rags, or disposing of waste solutions.
 - (1) (HCD 1) The prohibition in Subsection (F) includes, but is not limited to, home photo labs or other similar hobbyist or home occupational activities.
- (G) Exemption from construction permit requirements of this code shall not be deemed to grant authorization for any gray water system to be installed in a manner that violates other provisions of this code or any other laws or ordinances of the Enforcing Agency.
- (H) An operation and maintenance manual shall be provided to the owner. Directions shall indicate that the manual is to remain with the building throughout the life of the system and upon change of ownership or occupancy.
- (I) A gray water system shall not be connected to any potable water system without an air gap, reduced-pressure principle backflow preventer, or other physical device which prevents backflow and shall not cause ponding or runoff of gray water.

1502.1.1 (Formerly 1602.1.1) (HCD 1) Clothes Washer System. A clothes washer system in compliance with all of the following is exempt from the construction permit specified in Section 1.8.4.1 and may be installed or altered without a construction permit:

1. If required, notification has been provided to the enforcing agency regarding the proposed location and installation of a gray water irrigation or disposal system.
2. The design shall allow the user to direct the flow to the irrigation or disposal field or the building sewer. The direction control of the gray water shall be clearly labeled and readily accessible to the user.
3. The installation, change, alteration, or repair of the system does not include a potable water connection or a pump and does not affect other building, plumbing, electrical, or mechanical components including structural features, egress, fire-life safety, sanitation, potable water supply piping, or accessibility.

Note: The pump in a clothes washer shall not be considered part of the gray water system.
4. The gray water shall be contained on the site where it is generated.
5. Gray water shall be directed to and contained within an irrigation or disposal field.
6. Ponding or runoff is prohibited and shall be considered a nuisance.
7. Gray water may be released above the ground surface provided at least two (2) inches (51 mm) of mulch, rock, or soil, or a solid shield covers the release point. Other methods which provide equivalent separation are also acceptable.
8. Gray water systems shall be designed to minimize contact with humans and domestic pets.
9. Water used to wash diapers or similarly soiled or infectious garments shall not be used and shall be diverted to the building sewer.
10. Gray water shall not contain hazardous chemicals derived from activities such as cleaning car parts, washing greasy or oily rags, or disposing of waste solutions from home photo labs or similar hobbyist or home occupational activities.
11. Exemption from construction permit requirements of this code shall not be deemed to grant authorization for any gray water system to be installed in a manner that violates other provisions of this code or any other laws or ordinances of the enforcing agency.
12. An operation and maintenance manual shall be provided to the owner. Directions shall indicate that the manual is to remain with the building throughout the life of the system and upon change of ownership or occupancy.
13. Gray water discharge from a clothes washer system through a standpipe shall be properly trapped in accordance with Section 1005.0.

1502.1.2 (Formerly 1602.1.2) Simple System. Simple systems exceed a clothes washer system and shall comply with the following:

1. The discharge capacity of a gray water system shall be determined by Section ~~4602.8~~ **1502.8**. Simple systems have a discharge capacity of 250 gallons (947 L) per day or less.
2. Simple systems shall require a construction permit unless exempted from a construction permit by the Enforcing Agency. The Enforcing Agency shall consult with the water purveyor for any public water system (as defined in Health and Safety Code Section 116275) providing drinking water to the dwelling before allowing an exemption from a construction permit.
3. The design of simple systems shall meet generally accepted gray water system design criteria.

1502.1.3 (Formerly 1602.1.3) Complex System. Any gray water system that is not a clothes washer system or simple system shall comply with the following:

1. The discharge capacity of a gray water system shall be determined by Section ~~4602.8~~ **1502.8**. Complex systems have a discharge capacity over 250 gallons (947 L) per day.
2. Complex systems shall require a construction permit unless exempted from a construction permit by the Enforcing Agency. The Enforcing Agency shall consult with the water purveyor for any public water system (as defined in Health and Safety Code Section 116275) providing drinking water to the dwelling before allowing an exemption from a construction permit.

1502.2 (Formerly 1602.2.1 Discharge) System Requirements. Gray water shall be permitted to be diverted away from a sewer or private sewage disposal system, and discharge to a subsurface irrigation or subsoil irrigation system, or disposal field. The gray water shall be permitted to discharge to a mulch basin for single-family and multi-family dwellings residential occupancies. Gray water shall not be used to irrigate root crops or food crops intended for human consumption that come in contact with soil.

1502.2.1 (Formerly 1602.2.2) Surge Capacity. Gray water systems shall be designed to have the capacity to accommodate peak flow rates and distribute the total amount of estimated gray water on a daily basis to a subsurface irrigation field, subsoil irrigation field, disposal field, or mulch basin without surfacing, ponding, or runoff. A surge tank is required for systems that are unable to accommodate peak flow rates and distribute the total amount of gray water by gravity drainage. The water discharge for gray water systems shall be determined in accordance with Section ~~1502.8.1~~ or Section ~~1502.8.2~~.

Exception: It is not the intent of this section to require that all gray water must be handled by an irrigation field or disposal field. It is acceptable for excess gray water to be diverted to the building sewer through a diverter valve or overflow drain as permitted in this chapter.

1502.2.2 (Formerly 1602.2.3) Diversion. The gray water system shall connect to the sanitary drainage system downstream of fixture traps and vent connections through an approved gray water diverter valve. The gray water diverter valve shall be installed in a readily accessible location and clearly indicate the direction of flow.

*Exception: (HCD 1) A clothes washer system in compliance with ~~4602.1.1~~ **1502.1.1**.*

1502.2.3 (Formerly 1602.2.4) Backwater Valves. Gray water drains subject to backflow shall be provided with a backwater valve at the point of connection to the building sewer system, so located as to be accessible for inspection and maintenance.

1502.3 (Formerly 1602.3) Connections to Potable and Reclaimed (Recycled) Water Systems. Gray water systems shall have no direct unprotected connection to a potable water supply, on-site treated nonpotable water supply, or reclaimed (recycled) water systems. Potable, on-site treated nonpotable, or reclaimed (recycled) water, or rainwater is permitted to be used as makeup water for a non-pressurized storage tank provided the connection is protected by an airgap, reduced-pressure principle backflow preventer, or other physical device which prevents backflow in accordance with this code.

1502.4 (Formerly 1602.4) Location. No gray water system or part thereof shall be located on a lot other than the lot that is the site of the building or structure that discharges the gray water, nor shall a gray water system or part thereof be located at a point having less than the minimum distances indicated in Table 1502.4.

Exception: When there exists a lawfully recorded perpetual and exclusive covenant to an easement appurtenant and right-of-way between adjoining land-owners of two or more contiguous lots to discharge gray water from one lot to an adjoining lot.

**TABLE 1502.4 (Formerly 1602.4)
LOCATION OF GRAY WATER SYSTEM⁷**

| MINIMUM HORIZONTAL DISTANCE IN CLEAR REQUIRED FROM | SURGE TANK (feet) | SUBSURFACE AND SUBSOIL IRRIGATION FIELD AND MULCH BED BASIN (feet) | DISPOSAL FIELD |
|--|--------------------|--|------------------|
| Building structures ¹ | 5 ^{2,3,9} | 2 ^{3,8} | 5 |
| Property line adjoining private property | 5 | 5 ⁸ | 5 |
| Water supply wells ⁴ | 50 | 100 | 100 |
| Streams and lakes ⁴ | 50 | 50 100 ^{5,10} | 100 ⁵ |
| Sewage pits or cesspools | 5 | 5 | 5 |
| Sewage disposal field ¹⁰ | 5 | 4 ⁶ | 4 ⁶ |
| Septic tank | 0 | 5 | 5 |
| On-site domestic water service line | 5 | 5 0 | 0 |
| Pressurized public water main ⁷ | 10 | 10 | 10 ⁷ |

For SI units: 1 foot = 304.8 mm

Notes:

- ¹ Including *Building structures* do not include porches and steps, whether covered or uncovered, breezeways, roofed carports, *roofed porte cocheres*, roofed patios, carports, covered walks, covered driveways, and similar structures or appurtenances.
- ² The distance shall be permitted to be reduced to 0 feet for aboveground tanks where first approved by the Authority Having Jurisdiction.
- ³ ~~Reference to a 45 degree (0.79 rad) angle from foundation. Underground tanks shall not be located within a 45 degree angle from the bottom of the foundation, or they shall be designed to address the surcharge imposed by the structure. The distance may be reduced to six (6) inches (153 mm) for aboveground tanks when first approved by the Enforcing Agency.~~
- ⁴ Where special hazards are involved, the distance required shall be increased as directed by the Authority Having Jurisdiction.
- ⁵ These minimum clear horizontal distances shall apply between the irrigation or disposal field and the ocean mean higher high tide line.
- ⁶ Add 2 feet (610 mm) for each additional foot of depth in excess of 1 foot (305 mm) below the bottom of the drain line.
- ⁷ For parallel construction or for crossings, approval by the Authority Having Jurisdiction shall be required.
- ⁸ The distance shall be permitted to be reduced to 1 1/2 feet (457 mm) for drip and mulch basin irrigation systems.
- ⁹ The distance shall be permitted to be reduced to 0 feet for surge tanks of 75 gallons (284 L) or less.
- ¹⁰ ~~Where irrigation or disposal fields are installed in sloping ground, the minimum horizontal distance between a part of the distribution system and the ground surface shall be 15 feet (4572 mm).~~
- ¹⁰ The minimum horizontal distance may be reduced to 50 feet (15,240 mm) for irrigation or disposal fields utilizing gray water which has been filtered prior to entering the distribution piping.

1502.5 (Formerly 1602.5) Plot Plan Submission. No permit for a gray water system shall be issued until a plot plan with data satisfactory to the Authority Having Jurisdiction has been submitted and approved.

Exception (HCD 1): A construction permit shall not be required for a clothes washer system in compliance with Section ~~4602.1.4~~ 1502.1.1.

1502.6 (Formerly 1602.6) Prohibited Location. ~~Where there is insufficient lot area or inappropriate soil conditions for adequate absorption to prevent the ponding, surfacing, or runoff of the gray water, as determined by the Authority Having Jurisdiction, no gray water system shall be permitted. A gray water system is not permitted on a property in a geologically sensitive area as determined by the Authority Having Jurisdiction.~~

1502.7 (Formerly 1602.7) Drawings and Specifications. The Authority Having Jurisdiction shall *may* require the following information to be included with or in the plot plan before a permit is issued for a gray water system, or at a time during the construction thereof:

- (1) Plot plan drawn to scale and completely dimensioned, showing lot lines and structures, direction and approximate slope of surface, location of present or proposed retaining walls, drainage channels, water supply lines, wells, paved areas and structures on the plot, number of bedrooms and plumbing fixtures in each structure, location of private sewage disposal system and expansion area or building sewer connecting to the public sewer, and location of the proposed gray water system.

- (2) Details of construction necessary to ensure compliance with the requirements of this chapter, together with a full description of the complete installation, including installation methods, construction, and materials in accordance with the Authority Having Jurisdiction.
- (3) Details for holding tanks shall include dimensions, structural calculations, bracings, and such other pertinent data as required.
- (4) A log of soil formations and groundwater level as determined by test holes dug in proximity to the proposed irrigation and/or disposal area, together with a statement of water absorption characteristics of the soil at the proposed site as determined by approved percolation tests.

Exceptions:

- (1) The Authority Having Jurisdiction shall permit the use of Table 1502.10 in lieu of percolation tests.
- (2) *The Enforcing Agency may waive the requirement for identification of groundwater level and/or soil absorption qualities based on knowledge of local conditions.*
- (3) *The absence of groundwater in a test hole three (3) vertical feet (915 mm) below the deepest irrigation or disposal point shall be sufficient to satisfy this section unless seasonal high groundwater levels have been documented to rise to within this area.*
- (5) Distance between the plot and surface waters such as lakes, ponds, rivers or streams, and the slope between the plot and the surface water, where in close proximity.

1502.8 (Formerly 1602.8) Procedure for Estimating Gray Water Discharge. Gray water systems shall be designed to distribute the total amount of estimated gray water on a daily basis. The water discharge for gray water systems shall be determined in accordance with Section 1502.8.1 or Section 1502.8.2.

Exception: *It is not the intent of this section to require that all gray water must be handled by an irrigation field or disposal field. It is acceptable for excess gray water to be diverted to the building sewer through a diverter valve or overflow drain as permitted in this chapter.*

1502.8.1 (Formerly 1602.8.1) Single Family Dwellings and Multi-Family Dwellings, Residential

Occupancies. The gray water discharge for single family and multi-family dwellings residential occupancies shall be calculated by water use records, calculations of local daily per person interior water use, or the following procedure:

- (1) The number of occupants of each dwelling unit shall be calculated as follows:

| | |
|-------------------------|-------------|
| First Bedroom | 2 occupants |
| Each additional bedroom | 1 occupant |

- (2) The estimated gray water flows of each occupant shall be calculated as follows:

| | |
|----------------------------------|------------------------------------|
| Showers, bathtubs and lavatories | 25 gallons (95 L) per day/occupant |
| Laundry | 15 gallons (57 L) per day/occupant |

- (3) The total number of occupants shall be multiplied by the applicable estimated gray water discharge as provided above and the type of fixtures connected to the gray water system.

1502.8.3 (Formerly 1602.8.3) Daily Discharge. Gray water systems using tanks shall be designed to minimize the amount of time gray water is held in the tank and shall be sized to distribute the total amount of estimated gray water on a daily basis.

Exception: *Approved on-site treated nonpotable gray water systems.*

1502.9 (Formerly 1602.9) Gray Water System Components. Gray water system components shall comply with Section 1502.9.1 through Section 1502.9.7.

(HCD 1) *Gray water system components shall comply with this chapter.*

1502.9.1 (Formerly 1602.9.1) Surge Tanks. Where installed, surge tanks shall be in accordance with the following:

- (1) Surge tanks shall be constructed of solid, durable materials not subject to excessive corrosion or decay and shall be watertight. Above ground surge tanks shall be protected from direct sunlight or shall be constructed of UV resistant materials including but not limited to heavily tinted or opaque plastic, fiberglass,

lined metal, concrete and wood. Surge tanks constructed of steel shall be approved by the Authority Having Jurisdiction, provided such tanks are in accordance with approved applicable standards.

- (2) Each surge tank shall be vented in accordance with this code. The vent size shall be determined based on the total gray water fixture units as outlined in this code.
- (3) Each surge tank shall have an access opening with lockable gasketed covers or approved equivalent to allow for inspection and cleaning.
- (4) Each surge tank shall have its rated capacity permanently marked on the unit. In addition, a sign stating ~~GRAY WATER, DANGER UNSAFE WATER~~ *GRAY WATER SYSTEM, CAUTION – UNSAFE WATER* shall be permanently marked on the holding tank.
- (5) Each surge tank shall have an overflow drain. The overflow drains shall have permanent connections to the building drain or building sewer, upstream of septic tanks. The overflow drain shall not be equipped with a shutoff valve.
- (6) The overflow drainpipes shall not be less in size than the inlet pipe. Unions or equally effective fittings shall be provided for piping connected to the surge tank.
- (7) Surge tank shall be structurally designed to withstand anticipated earth or other loads. Surge tank covers shall be capable of supporting an earth load of not less than 300 pounds per square foot (lb/ft²) (1465 kg/m²) where the tank is designed for underground installation.
- (8) Where a surge tank is installed underground, the overflow system shall be designed so that the tank overflow will gravity drain to the existing sewer line or septic tank. The tank shall be protected against sewer line backflow by a backwater valve installed in accordance with this code.
- (9) Surge tanks shall be installed on dry, level, well-compacted soil where underground or on a level 3 inch (76 mm) thick concrete slab or *other approved method* where aboveground.
- (10) Surge tanks shall be anchored to prevent against overturning where installed aboveground. Underground tanks shall be ballasted, anchored, or otherwise secured, to prevent the tank from floating out of the ground where empty. The combined weight of the tank and hold down system shall meet or exceed the buoyancy forces of the tank.
- (11) *(HCD 1) An overflow drain and backwater valve is not required on a clothes washer system.*

1502.9.2.1 (Formerly 1602.9.3) *Animals and Insects.* Gray water tank openings shall be protected to prevent the entrance of insects, birds, or rodents into the tank and piping systems. Screens installed on vent pipes, inlets, and overflow pipes shall have an aperture of not greater than 1/16 of an inch (1.6 mm) and shall be close fitting.

1502.9.2.2 (Formerly 1602.9.4) *Freeze Protection.* Tanks and piping installed in locations subject to freezing shall be provided with an approved means of freeze protection.

1502.9.3 ~~Subsoil Irrigation Field Materials.~~ Subsoil irrigation field and disposal field piping shall be constructed of perforated high-density polyethylene pipe, perforated ABS pipe, perforated PVC pipe, or other approved materials, provided that sufficient openings are available for distribution of the gray water into the trench area. Material, construction, and perforation of the pipe shall be in accordance with the appropriate absorption field drainage piping standards and shall be approved by the Authority Having Jurisdiction.

1502.9.4 ~~Subsurface Irrigation Field and Mulch Basin Supply Line Materials.~~ Materials for gray water piping outside the building shall be polyethylene or PVC. Drip feeder lines shall be PVC or polyethylene tubing.

1502.9.5 ~~Valves.~~ Valves shall be accessible.

1502.9.6 ~~Trap.~~ Gray water piping discharging into the surge tank or having a direct connection to the sanitary drain or sewer piping shall be downstream of an approved water seal type trap(s). Where no such trap(s) exists, an approved vented running trap shall be installed upstream of the connection to protect the building from possible waste or sewer gases.

1502.9.7 ~~Backwater Valve.~~ A backwater valve shall be installed on gray water drain connections to the sanitary drain or sewer.

**TABLE 1502.10 (Formerly 1602.10)
DESIGN OF SIX TYPICAL SOILS**

| TYPE OF SOIL | MINIMUM SQUARE FEET OF IRRIGATION/LEACHING AREA PER 100 GALLONS OF ESTIMATED GRAY WATER DISCHARGE PER DAY | MAXIMUM ABSORPTION CAPACITY IN GALLONS PER SQUARE FOOT OF IRRIGATION/LEACHING AREA FOR A 24-HOUR PERIOD |
|---|---|---|
| Coarse sand or gravel | 20 | 5.0 |
| Fine sand | 25 | 4.0 |
| Sandy loam | 40 | 2.5 |
| Sandy clay | 60 | 1.7 |
| Clay with considerable sand or gravel | 90 | 1.1 |
| Clay with small amounts of sand or gravel | 120 | 0.8 |

For SI units: 1 square foot = 0.0929 m², 1 gallon per day = 0.000043 L/s

1502.10.2 (Formerly 1602.10.2) Determination of Maximum Absorption Capacity. The irrigation field and mulch basin size shall be based on the maximum absorption capacity of the soil and determined using Table 1502.10. For soils not listed in Table 1502.10, the maximum absorption capacity for the proposed site shall be determined by percolation tests or other method acceptable to the Authority Having Jurisdiction. A gray water system shall not be permitted, where the percolation test shows the absorption capacity of the soil is unable to accommodate the maximum discharge of the proposed gray water irrigation system.

Exceptions:

- (1) *The Enforcing Agency may waive the requirement for identification of groundwater level and/or soil absorption qualities based on knowledge of local conditions.*
- (2) *Irrigation fields in compliance with Section 1502.11.2 which only utilize drip type emitters are exempt from percolation tests.*

1502.10.3 (Formerly 1602.10.3) Groundwater Level. No excavation for an irrigation field, disposal field, or mulch basin shall extend within 3 feet (914 mm) vertical of the highest known seasonal groundwater level nor to a depth where gray water contaminates the groundwater or surface water. The applicant shall supply evidence of groundwater depth to the satisfaction of the Authority Having Jurisdiction.

Note: *The absence of groundwater in a test hole three (3) vertical feet (915 mm) below the deepest irrigation or disposal point shall be sufficient to satisfy this section unless seasonal high groundwater levels have been documented to rise to within this area.*

1502.11 Subsurface and Subsoil Irrigation Field, and Mulch Basin Design and Construction.

Subsurface and subsoil irrigation field, and mulch basin design and construction shall be in accordance with Section 1502.11.1 through Section 1502.11.3. Where a gray water irrigation system design is predicated on soil tests, the subsurface or subsoil irrigation field or mulch basin shall be installed at the same location and depth as the tested area.

1502.11.1 Subsurface Irrigation Field. A subsurface irrigation field shall comply with Section 1502.11.1.1 through Section 1502.11.1.6.

1502.11.1.1 Minimum Depth. Supply piping, including drip feeders, shall be not less than 2 inches (51 mm) below finished grade and covered with mulch or soil.

1502.11.1.2 Filter. Not less than 140 mesh (105 micron) filter with a capacity of 25 gallons per minute (gpm) (1.58 L/s), or equivalent shall be installed. Where a filter backwash is installed, the backwash and flush discharge shall discharge into the building sewer or private sewage disposal. Filter backwash and flush water shall not be used.

1502.11.1.3 Emitter Size. Emitters shall be installed in accordance with the manufacturer's installation instructions. Emitters shall have a flow path of not less than 1200 microns (μ) (1200 μ m) and shall not have a coefficient of manufacturing variation (Cv) exceeding 7 percent. Irrigation system design shall be such that emitter flow variation shall not exceed 10 percent.

1502.11.1.4 Number of Emitters. The minimum number of emitters and the maximum discharge of each emitter in an irrigation field shall be in accordance with Table 1502.11.

1502.11.1.5 Controls. The system design shall provide user controls, such as valves, switches, timers, and other controllers, to rotate the distribution of gray water between irrigation zones.

1502.11.1.6 Maximum Pressure. Where pressure at the discharge side of the pump exceeds 20 pounds-force per square inch (psi) (138 kPa), a pressure-reducing valve able to maintain downstream pressure not exceeding 20 psi (138 kPa) shall be installed downstream from the pump and before an emission device.

1502.11.2 Mulch Basin. A mulch basin shall comply with Section 1502.11.2.1 through Section 1502.11.2.4.

1502.11.2.1 Single Family and Multi-Family Dwellings. The gray water discharge to a mulch basin is limited to single family and multi-family dwellings.

1502.11.2.2 Size. Mulch basins shall be of sufficient size to accommodate peak flow rates and distribute the total amount of estimated gray water on a daily basis without surfacing, ponding or runoff. Mulch basins shall have a depth of not less than 10 inches (254 mm) below finished grade. The mulch basin size shall be based on the maximum absorption capacity of the soil and determined using Table 1602.10.

1502.11.2.3 Minimum Depth. Gray water supply piping, including drip feeders, shall be not less than 2 inches (51 mm) below finished grade and covered with mulch.

1502.11.2.4 Maintenance. The mulch basin shall be maintained periodically to retain the required depth and area, and to replenish the required mulch cover.

1502.11.3 Subsoil Irrigation Field. Subsoil irrigation fields shall comply with Section 1502.11.3.1 through Section 1502.11.3.3.

1502.11.3.1 Minimum Pipe Size. Subsoil irrigation field distribution piping shall be not less than 3 inches (80 mm) diameter.

1502.11.3.2 Filter Material and Backfill. Filter material, clean stone, gravel, slag, or similar material acceptable to the Authority Having Jurisdiction, varying in size from 3/4 of an inch (19.1 mm) to 2 1/2 inches (64 mm) shall be placed in the trench to the depth and grade in accordance with Table 1502.11.3. The perforated section of subsoil irrigation field distribution piping shall be laid on the filter material in an approved manner. The perforated section shall then be covered with filter material to the minimum depth in accordance with Table 1502.11.3. The filter material shall then be covered with porous material to prevent closure of voids with earth backfill. No earth backfill shall be placed over the filter material cover until after inspection and acceptance.

1502.11.3.3 Subsoil Irrigation Field Construction. Subsoil irrigation fields shall be constructed in accordance with Table 1502.11.3. Where necessary on sloping ground to prevent excessive line slopes, irrigation lines shall be stepped. The lines between each horizontal leaching section shall be made with approved watertight joints and installed on natural or unfilled ground.

1502.11 (Formerly 1602.11) Irrigation, Disposal Field and Mulch Basin Construction.

Irrigation fields, disposal fields and mulch basins used in gray water systems shall comply with this section. Gray water systems may contain either an irrigation field or a disposal field or a combination of both. This section is not intended to prevent the use of other methods of gray water irrigation or disposal approved by the Enforcing Agency.

1502.11.1 (Formerly 1602.11.1) Mulch Basin. A mulch basin may be used as an irrigation or disposal field. Mulch basins shall be sized in accordance with Table 1602.10 1502.10 and of sufficient depth, length and width to prevent ponding or runoff during the gray water surge of a clothes washer, bathtub or shower. Mulch must be replenished as required due to decomposition of organic matter. Mulch basins will require periodic maintenance, reshaping or removal of dirt to maintain surge capacity and to accommodate plant growth and prevent ponding or runoff.

1502.11.2 (Formerly 1602.11.2) Irrigation Field. The provisions of this section are not intended to prevent the use of any appropriate material, appliance, installation, device, design or method of construction. If an alternate

design is not available, the following provisions may be used as guidance in the design of a gray water irrigation field:

- (1) Filters used in gray water irrigation systems shall be as specified by the manufacturer's installation instructions for the design flow rate and intended use. The filter backwash and flush discharge shall be contained and disposed of into the building sewer system, septic tank or, with approval of the Enforcing Agency, a separate mini-leachfield sized to accept all the backwash and flush discharge water. Filter backwash water and flush water shall not be used for any purpose. Sanitary procedures shall be followed when handling filter backwash and flush discharge or gray water.
- (2) Emitters shall be designed to resist root intrusion and shall be of a design recommended by the manufacturer for the intended gray water flow and use. For emitter ratings, refer to Irrigation Equipment Performance Report, Drip Emitters and Micro-Sprinklers, Center for Irrigation Technology, California State University, 5730 N. Chestnut Avenue, Fresno, California 93740-0018
- (3) Each irrigation zone shall be designed to include no less than the number of emitters specified in Table 1602.11 1502.11 or through a procedure designated by the Enforcing Agency. Minimum spacing between emitters in any direction shall be sufficient to prevent surfacing or runoff.
- (4) The system design shall provide user controls, such as valves, switches, timers and other controllers, as appropriate, to rotate the distribution of gray water between irrigation zones.
- (5) All drip irrigation supply lines shall be polyethylene tubing or PVC Class 200 pipe or better and Schedule 40 fittings. All joints shall be pressure tested at 40 psi (276 kPa), and shown to be drip tight for five minutes, before burial. All supply piping shall be covered to a minimum depth of two (2) inches (51 mm) of mulch or soil. Drip feeder lines can be poly or flexible PVC tubing and shall be covered to a minimum depth of two (2) inches (51 mm) of mulch or soil.
- (6) Where pressure at the discharge side of the pump exceeds 20 psi (138 kPa), a pressure-reducing valve able to maintain downstream pressure no greater than the maximum operating pressure of the installed tubing, emitters, or other components shall be installed downstream from the pump and before any emission device.
- (7) When an irrigation system utilizes a pump, and discharges water at a point higher than the pump, a backwater valve shall be installed downstream of the pump to prevent back siphonage of water and soil.

**TABLE 1502.11 (Formerly 1602.11)
SUBSURFACE IRRIGATION DESIGN
CRITERIA FOR SIX TYPICAL SOILS**

| TYPE OF SOIL | MAXIMUM EMITTER DISCHARGE (gallons per day) | MINIMUM NUMBER OF EMITTERS PER GALLON OF ESTIMATED GRAY WATER DISCHARGE PER DAY* (gallons per day) |
|--------------|--|--|
| Sand | 1.8 | 0.6 |
| Sandy loam | 1.4 | 0.7 |
| Loam | 1.2 | 0.9 |
| Clay loam | 0.9 | 1.1 |
| Silty clay | 0.6 | 1.6 |
| Clay | 0.5 | 2.0 |

For SI units: 1 gallon per day = 0.000043 L/s

*The estimated gray water discharge per day shall be determined in accordance with Section 1502.8 of this code.

1502.11.3 (Formerly 1602.11.3) Disposal Field. The provisions of this section are not intended to prevent the use of any appropriate material, appliance, installation, device, design or method of construction. If an alternate design is not available the following provisions may be used as guidance in the design of a gray water disposal field:

- (A) Disposal systems shall be not less than three (3) inches (80 mm) in cross sectional dimension and shall be constructed of perforated high-density polyethylene pipe, perforated ABS pipe, perforated PVC pipe, leaching chambers or other approved materials, provided that sufficient openings are available for distribution of the gray water into the trench area. Material, construction, and perforation shall be in

compliance with the appropriate absorption fields drainage standards and shall be approved by the Enforcing Agency.

- (B) Filter material, clean stone, gravel, slag, or similar filter material acceptable to the Enforcing Agency, varying in size from three-quarter (3/4) inch (19.1 mm) to two and one-half (2-1/2) inches (64 mm) shall be placed in the trench to the depth and grade required by this section. The perforated section shall be laid on the filter material in an approved manner. The perforated section shall then be covered with filter material to the minimum depth required by this section. The filter material shall then be covered with untreated building paper, straw, or similar porous material to prevent closure of voids with earth backfill. No earth backfill shall be placed over the filter material cover until after inspection and acceptance.

Exception: Manufactured leaching chambers shall be installed in compliance with the manufacturer's installation instructions.

- (C) Disposal fields shall be constructed in accordance with Table ~~1602.11.3~~ 1502.11.3
- (D) When necessary on sloping ground to prevent excessive line slopes, disposal lines shall be stepped or installed on the contour lines of the slope. The lines between each horizontal leaching section shall be made with approved water-tight joints and installed on natural or unfilled ground.

**TABLE 1502.11.3 (Formerly 1602.11.3)
SUBSOIL IRRIGATION FIELD CONSTRUCTION**

| DESCRIPTION | MINIMUM | MAXIMUM |
|---|-----------|-----------------------|
| Number of drain lines per valved zone ¹ | 1 | - |
| Length of each perforated line ¹ | - | 100 feet |
| Bottom width of trench ¹ | 12 inches | 24 inches |
| Spacing of lines, center to center ¹ | 4 feet | - |
| Depth of earth cover of lines | 10 inches | - |
| Depth of filter material cover of lines | 2 inches | - |
| Depth of filter material beneath lines ¹ | 3 inches | - |
| Grade of perforated lines level | level | 3 inches per 100 feet |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 inch per foot = 83.3 mm/m

¹ Manufactured leaching chambers shall be installed in compliance with the manufacturer's installation instructions.

1502.12 (Formerly 1602.12) Gray Water System Color and Marking Information. Pressurized gray water distribution systems shall be identified as containing nonpotable water in accordance with Section 601.3 of this code. Marking shall be at intervals not to exceed 5 feet (1524 mm). Gray water distribution piping upstream of any connection to an irrigation or disposal field or a distribution valve shall be identified with the words "CAUTION: NONPOTABLE GRAY WATER, DO NOT DRINK".

1502.13 (Formerly 1602.13.1). Other Collection and Distribution Systems. Other collection and distribution systems shall be approved by the local Authority Having Jurisdiction, as allowed by Section 301.3 of this code.

1502.13.1 Higher Requirements. Nothing contained in this chapter shall be construed to prevent the Authority Having Jurisdiction from requiring compliance with higher requirements than those contained herein, where such higher requirements are essential to maintain a safe and sanitary condition.

1502.13.1 (Formerly 1602.13.2) Future Connections. Gray water stub-out plumbing may be allowed for future connection prior to the installation of irrigation lines and landscaping. Stub-out shall be permanently marked "CAUTION: NONPOTABLE GRAY WATER, DO NOT DRINK".

1502.15 (Formerly 1602.15) Maintenance. Gray water systems and components shall be maintained in accordance with Table Section 1501.5.

1503.0 Reclaimed (Recycled) Water Systems Reserved.

1503.1 General. The provisions of this section shall apply to the installation, construction, alteration, and repair of reclaimed (recycled) water systems intended to supply uses such as water closets, urinals, trap primers for floor drains and floor sinks, aboveground and subsurface irrigation, industrial or commercial cooling or air conditioning and other uses approved by the Authority Having Jurisdiction.

1503.2 Permit. It shall be unlawful for a person to construct, install, alter, or cause to be constructed, installed, or altered a reclaimed (recycled) water system within a building or on a premises without first obtaining a permit to do such work from the Authority Having Jurisdiction.

1503.2.1 Plumbing Plan Submission. No permit for a reclaimed (recycled) water system shall be issued until complete plumbing plans, with data satisfactory to the Authority Having Jurisdiction, have been submitted and approved.

1503.3 System Changes. No changes or connections shall be made to either the reclaimed (recycled) water system or the potable water system within a site containing a reclaimed (recycled) water system without approval by the Authority Having Jurisdiction.

1503.4 Connections to Potable or Reclaimed (Recycled) Water Systems. Reclaimed (recycled) water systems shall have no connection to a potable water supply or alternate water source system. Potable water is permitted to be used as makeup water for a reclaimed (recycled) water storage tank provided the water supply inlet is protected by an airgap or reduced-pressure-principle backflow preventer in accordance with this code.

1503.5 Initial Cross-Connection Test. A cross-connection test is required in accordance with Section 1501.11.2. Before the building is occupied or the system is activated, the installer shall perform the initial cross-connection test in the presence of the Authority Having Jurisdiction and other authorities having jurisdiction. The test shall be ruled successful by the Authority Having Jurisdiction before final approval is granted.

1503.6 Reclaimed (Recycled) Water System Materials. Reclaimed (recycled) water supply and distribution system materials shall comply with the requirements of this code for potable water supply and distribution systems, unless otherwise provided for in this section.

1503.7 Reclaimed (Recycled) Water System Color and Marking Information. Reclaimed (recycled) water systems shall have a colored background and marking information in accordance with Section 601.3 of this code.

1503.8 Valves. Valves, except fixture supply control valves, shall be equipped with a locking feature.

1503.9 Hose Bibbs. Hose bibbs shall not be allowed on reclaimed (recycled) water piping systems located in areas accessible to the public. Access to reclaimed (recycled) water at points in the system accessible to the public shall be through a quick disconnect device that differs from those installed on the potable water system. Hose bibbs supplying reclaimed (recycled) water shall be marked with the words: "CAUTION: NONPOTABLE RECLAIMED WATER, DO NOT DRINK," and the symbol in Figure 1503.9



FIGURE 1503.9

1503.10 Required Appurtenances. The reclaimed (recycled) water system and the potable water system within the building shall be provided with the required appurtenances (e.g., valves, air/vacuum relief valves, etc.) to allow for deactivation or drainage as required for a cross-connection test in accordance with Section 1501.11.2.

1503.11 Same Trench as Potable Water Pipes. Reclaimed (recycled) water pipes shall be permitted to be run or laid in the same trench as potable water pipes with a 42 inches (305 mm) minimum vertical and horizontal separation where both pipe materials are approved for use within a building. Where piping materials do not meet this requirement the minimum horizontal separation shall be increased to 60 inches (1524 mm). The potable water piping shall be installed at an elevation above the reclaimed (recycled) water piping. Reclaimed (Recycled) water pipes laid in the same trench or crossing building sewer or drainage piping shall be installed in accordance with this code for potable water piping.

1503.12 Signs. Rooms and water closet tanks in buildings using reclaimed (recycled) water shall be in accordance with Section 1501.10 and Section 1501.10.1.

1503.13 Inspection and Testing. Reclaimed (recycled) water systems shall be inspected and testing in accordance with Section 1501.11.

1504.0 (Formerly 1604.0) On-Site Treated Nonpotable Gray Water Systems.

1504.1 (Formerly 1604.1) General. The provisions of this section shall apply to the installation, construction, alteration, and repair of on-site treated nonpotable gray water systems intended to supply uses such as water closets, urinals, trap primers for floor drains and floor sinks, above and belowground irrigation, and other uses approved by the Authority Having Jurisdiction.

Other approved nonpotable water sources, including swimming pool backwash operations, air conditioner condensate, rainwater, cooling tower blow-down water, foundation drainage, steam system condensate, fluid cooler discharge water, food steamer discharge water, combination oven discharge water, industrial process water, and fire pump test water may be permitted to be collected for re-use by gray water systems, as approved for the intended application.

1504.2 (Formerly 1604.2) Plumbing Plan Submission. No permit for an on-site treated nonpotable gray water system shall be issued until complete plumbing plans, with data satisfactory to the Authority Having Jurisdiction, have been submitted and approved.

1504.3 (Formerly 1604.3) System Changes. No changes or connections shall be made to either the on-site treated nonpotable gray water system or the potable water system within a site containing an on-site treated nonpotable gray water system without approval by the Authority Having Jurisdiction.

1504.4 (Formerly 1604.4) Connections to Potable or Reclaimed (Recycled) Water Systems. On-site treated nonpotable gray water systems shall have no *unprotected* connection to a potable water supply or reclaimed (recycled) water source system. Potable or reclaimed (recycled) water is permitted to be used as makeup water for a non-pressurized storage tank provided the makeup water supply is protected by an air gap, *reduced-pressure principle backflow preventer, or other physical device which prevents backflow* in accordance with this code.

1504.6 (Formerly 1604.6) On-Site Treated Nonpotable Gray Water System Materials. On-site treated nonpotable gray water supply and distribution system materials shall comply with the requirements of this code for potable water supply and distribution systems, unless otherwise provided for in this section.

1504.7 (Formerly 1604.7) On-Site Treated Nonpotable Gray Water Devices and Systems. Devices or equipment used to treat on-site treated nonpotable gray water in order to maintain the minimum water quality requirements determined by the Authority Having Jurisdiction shall be listed or labeled (third-party certified) by a listing agency (accredited conformity assessment body) and approved for the intended application. Devices or equipment used to treat on-site treated nonpotable gray water for use in water closet and urinal flushing, surface irrigation, and similar applications shall be listed or labeled to NSF 350 or approved by the Authority Having Jurisdiction.

1504.8 (Formerly 1604.8) On-Site Treated Nonpotable Gray Water System Color and Marking Information. On-site treated *nonpotable* gray water systems shall have a colored background and marking information in accordance with Section 601.3 of this code.

1504.10 (Formerly 1604.10) Design and Installation. The design and installation of on-site treated nonpotable gray water systems shall be in accordance with Section 1504.10.1 through Section 1504.10.5 1504.10.6.

1504.10.1 (Formerly 1604.10.1) Listing Terms and Installation Instructions. On-site treated nonpotable gray water systems shall be installed in accordance with the terms of its listing and the manufacturer's installation instructions.

1504.10.2 (Formerly 1604.10.2) Minimum Water Quality. On-site treated nonpotable gray water supplied to toilets or urinals or for other uses in which it is sprayed or exposed shall be disinfected. Acceptable disinfection methods shall include chlorination, ultraviolet sterilization, ozone, or other methods as approved by the Authority Having Jurisdiction. The minimum water quality for on-site treated nonpotable gray water systems shall meet the applicable water quality requirements for the intended applications as determined by the public health Authority Having Jurisdiction. *In the absence of local water quality requirements for on-site treated nonpotable gray water, Section 4604.7 1501.7 shall apply.*

1504.10.3 (Formerly 1604.10.3) Deactivation and Drainage. The on-site treated nonpotable gray water system and the potable water system within the building shall be provided with the required appurtenances (e.g., valves, air/vacuum relief valves, etc.) to allow for deactivation or drainage as required for a cross-connection test in accordance with Section 1501.11.2.

1504.10.4 (Formerly 1604.10.4) Near Underground Potable Water Pipe. On-site treated nonpotable gray water pipes shall be permitted to be run or laid in the same trench as potable water pipes with a 12 inch (305 mm) minimum vertical and horizontal separation where both pipe materials are approved for use within a building. Where piping materials do not meet this requirement the minimum separation shall be increased to 60 inches (1524 mm). The potable water piping shall be installed at an elevation above the on-site treated nonpotable gray water piping.

1504.10.5 (Formerly 1604.10.5) Required Filters. A filter permitting the passage of particulates no larger than 100 microns (100 µm) shall be provided for on-site treated nonpotable gray water supplied to water closets, urinals, trap primers, and drip irrigation system.

1504.10.6 (Formerly 1604.10.6) Disinfection. *Where the intended use of on-site treated nonpotable gray water requires disinfection and/or other treatment, on-site treated nonpotable gray water shall be disinfected as needed to ensure the required water quality is obtained at the point of use. Where chlorine is used for disinfection or treatment, water shall be tested for residual chlorine in accordance with ASTM D 1253.*

1504.11 (Formerly 1604.11) Signs. Signs in buildings using on-site treated nonpotable gray water shall comply with Section 1501.10 and Section 1501.10.1, and applicable requirements of the California Building Code.

1504.12 (Formerly 1604.12) Inspection and Testing. On-site treated nonpotable gray water systems shall be inspected and tested in accordance with Section 1501.11 and/or as required by the Authority Having Jurisdiction.

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

20. HCD proposes to adopt Chapter 16 from the 2015 Uniform Plumbing Code with new amendments and bring forward existing amendments from the 2013 California Plumbing Code into the 2016 California Plumbing Code as follows:

CHAPTER 16 (Formerly 17) NONPOTABLE RAINWATER CATCHMENT SYSTEMS

1601.0 General.

1601.1 Applicability. (HCD 1) The provisions of this chapter shall apply to the installation, construction, alteration, and repair of nonpotable rainwater catchment systems. *In addition, applicable provisions in Chapter 15, Sections ~~through 1601.0~~ 1501.7 through 1601.9 for "Alternate Water Sources for Nonpotable Applications" shall apply to rainwater catchment systems.*

1601.2 System Design. Rainwater catchment systems shall be designed in accordance with this chapter ~~by a person registered or licensed to perform plumbing design work or who demonstrates competency to design the rainwater catchment system as required by the Authority Having Jurisdiction~~ by a person who demonstrates competency to design the alternate water source system as required by the Enforcing Agency. The Enforcing Agency may also require plans and specifications to be prepared by a licensed design professional. Components, piping, and fittings used in any alternate water source system shall be listed.

Exceptions:

- (1) A person registered or licensed to perform plumbing design work is not required to design rainwater catchment systems used for irrigation with a maximum storage capacity of 360 gallons (1363 L).
- (2) A person registered or licensed to perform plumbing design work is not required to design rainwater catchment systems for single family dwellings where outlets, piping, and system components are located on the exterior of the building.

1601.3 (Formerly 1702.2.1) Permit. It shall be unlawful for a person to construct, install, alter, or cause to be constructed, installed, or altered a rainwater catchment system in a building or on a premise without first obtaining a permit to do such work from the Authority Having Jurisdiction.

Exceptions:

- ~~(1) A permit is not required for exterior rainwater catchment systems used for outdoor drip and subsurface irrigation with a maximum storage capacity of 360 gallons (1363 L).~~
- ~~(2) A plumbing permit is not required for rainwater catchment systems for single family dwellings where outlets, piping, and system components are located on the exterior of the building. This does not exempt the need for permits where required for electrical connections, tank supports, or enclosures.~~
- (1) A permit is not required for exterior rainwater catchment systems used for outdoor non-spray irrigation with a maximum storage capacity of 5000 gallons (18 927 L) where the tank is supported directly upon grade and the ratio of height to diameter or width does not exceed 2 to 1 and it does not require electrical power or a makeup water supply connection.
- (2) (HCD 1 & HCD 2) A permit is not required for exterior rainwater catchment systems used for spray irrigation with a maximum storage capacity of 360 gallons (1363 L).

1601.5 Maintenance and Inspection. Rainwater catchment systems and components shall be inspected and maintained in accordance with Section 1601.5.1 through Section 1601.5.3 the manufacturer's recommendations and/or as required by the enforcing agency.

1601.5.1 Frequency. Rainwater catchment systems and components shall be inspected and maintained in accordance with Table 1601.5 unless more frequent inspection and maintenance is required by the manufacturer.

1601.5.2 Maintenance Log. A maintenance log for rainwater catchment systems is required to have a permit in accordance with Section 1601.3 and shall be maintained by the property owner and be available for inspection. The property owner or designated appointee shall ensure that a record of testing, inspection and maintenance in accordance with Table 1601.5 is maintained in the log. The log will indicate the frequency of inspection and maintenance for each system.

1601.5.3 1601.5.1 Maintenance Responsibility. The required maintenance and inspection of rainwater catchment systems shall be the responsibility of the property owner, unless otherwise required by the Authority Having Jurisdiction.

TABLE 1601.5
MINIMUM ALTERNATE WATER SOURCE TESTING, INSPECTION, AND MAINTENANCE FREQUENCY

| DESCRIPTION | MINIMUM FREQUENCY |
|--|--|
| Inspect and clean filters and screens, and replace (where necessary). | Every 3 months |
| Inspect and verify that disinfection, filters and water quality treatment devices and systems are operational and maintaining minimum water quality requirements as determined by the Authority Having Jurisdiction. | In accordance with manufacturer's instructions, and the Authority Having Jurisdiction. |
| Inspect and clear debris from rainwater gutters, downspouts, and roof washers. | Every 6 months |
| Inspect and clear debris from roof or other aboveground rainwater collection surfaces. | Every 6 months |
| Remove tree branches and vegetation overhanging roof or other aboveground rainwater collection surfaces. | As needed |
| Inspect pumps and verify operation. | After initial installation and every 12 months thereafter |
| Inspect valves and verify operation. | After initial installation and every 12 months thereafter |
| Inspect pressure tanks and verify operation. | After initial installation and every 12 months thereafter |
| Clear debris from and inspect storage tanks, locking devices, and verify operation. | After initial installation and every 12 months thereafter |
| Inspect caution labels and marking. | After initial installation and every 12 months thereafter. |
| Cross-connection inspection and test* | After initial installation and every 12 months thereafter. |
| Test water quality of rainwater catchment systems required by Section 1602.9.4 to maintain water quality | Every 12 months. After system renovation or repair. |

*The cross-connection test shall be performed in the presence of the Authority Having Jurisdiction in accordance with the requirements of this chapter.

1601.6 Operation and Maintenance Manual. An operation and maintenance manual for rainwater catchment systems required to have a permit in accordance with Section 1601.3, shall be supplied to the building owner by the system designer or installer. The operating and maintenance manual shall include the following:

- (1) Detailed diagram Diagram(s) of the entire system and the location of system components.
- (2) Instructions on operating and maintaining the system.
- (3) Details Instructions on maintaining the required water quality as determined by the Authority Having Jurisdiction for rainwater catchment systems.
- (4) Details on startup, shutdown, and deactivating the system for maintenance, repair, or other purposes.
- (5) Applicable testing, inspection, and maintenance frequencies in accordance with Table Section 1601.5.
- (6) A method of contacting the installer and/or manufacturer(s).
- (7) Directions to the owner or occupant that the manual shall remain with the building throughout the life cycle of the structure.

1601.7 (Formerly 1702.9.4) Minimum Water Quality Requirements. The minimum water quality for rainwater catchment systems shall comply with the applicable water quality requirements for the intended application as determined by Authority Having Jurisdiction. Water quality for nonpotable rainwater catchment systems, shall comply with Section 1602.9.4. *In the absence of water quality requirements for harvested rainwater, Table 1702.9.4 1602.9.4 shall apply.*

Exceptions:

- (1) Water treatment is not required for rainwater catchment systems used for aboveground irrigation with a maximum storage capacity of 360 (1363 L).
- (2) Water treatment is not required for rainwater catchment systems used for surface, subsurface or drip irrigation.

1602.0 Nonpotable Rainwater Catchment Systems.

1602.4 (Formerly 1702.4) Connections to Potable or Reclaimed (Recycled) Water Systems. Rainwater catchment systems shall have no ~~direct~~ *unprotected* connection to a potable water supply or alternate water source system. Potable or reclaimed (recycled) water is permitted to be used as makeup water for a rainwater catchment system provided the potable or reclaimed (recycled) water supply connection is protected by an airgap or reduced-pressure principle backflow preventer in accordance with this code.

1602.9.3.1 Other Surfaces. Natural precipitation collected from surface water runoff, vehicular parking surfaces, or manmade surfaces at or below grade shall be in accordance with the ~~with the stormwater~~ *water quality* requirements for on-site treated nonpotable *gray* water systems in section 1504.0.

Exception: Collected rainwater or storm water used exclusively for subsurface landscape irrigation.

1602.9.4.1 (Formerly 1702.9.4.1) Disinfection. *Where the initial quality of the collected rainwater requires disinfection or other treatment or both, the collected rainwater shall be treated as necessary to ensure the required water quality is delivered at the point of use. Where chlorine is used for disinfection or treatment, water shall be tested for residual chlorine in accordance with ASTM D 1253. The levels of residual chlorine shall not exceed the levels allowed for the intended use in accordance with the requirements of the local Enforcing Agency.*

**TABLE 1602.9.4 (Formerly 1702.9.4)
MINIMUM WATER QUALITY**

| Application | Minimum Treatment | Minimum Water Quality |
|--|---|---|
| Car washing | Debris excluder or other approved means in compliance with Section 1602.9.10 100 Micron (100 μ m) in compliance with Section 1602.9.11 for drip irrigation | N/A |
| Surface, subsurface and drip irrigation | Debris excluder or other approved means in compliance with Section 1602.9.10 100 Micron (100 μ m) in compliance with Section 1602.9.11 for drip irrigation | N/A |
| Spray irrigation where the maximum storage volume is less than 360 gallons (1363 L) | Debris excluder or other approved means in compliance with Section 1602.9.10, and disinfection in accordance with Section 1602.9.8 | N/A |
| Spray irrigation where the maximum storage volume is equal to or greater than 360 gallons (1363 L) | Debris excluder or other approved means in compliance with Section 1602.9.10 | Escherichia coli: < 100 CFU/100 ml Turbidity: < 10 NTU |
| Urinal and water closet flushing, clothes washing, and trap priming | Debris excluder or other approved means in compliance with Section 1602.9.10 100 Micron (100 μ m) in compliance with Section 1602.9.11 | Escherichia coli: < 100 CFU/100 ml Turbidity: < 10 NTU |
| Ornamental fountains and other water features | Debris excluder or other approved means in compliance with Section 1602.9.10 | Escherichia coli: < 100 CFU/100 ml Turbidity: < 10 NTU |
| Cooling tower make up water | Debris excluder or other approved means in compliance with Section 1602.9.10 100 Micron (100 μ m) in compliance with Section 1602.9.11 | Escherichia coli: < 100 CFU/100 ml Turbidity: < 10 NTU |

1602.9.5.3 (Formerly 1702.9.5.3) Above Grade. Above grade storage tanks shall be of an opaque material, approved for aboveground use in direct sunlight or shall be shielded from direct sunlight. Tanks shall be installed in an accessible location to allow for inspection and cleaning. The tank shall be installed on a foundation or platform that is constructed to accommodate loads in accordance with the building code California Building Code.

1602.9.5.4 (Formerly 1702.9.5.4) Below Grade. Rainwater storage tanks installed below grade shall be structurally designed to withstand anticipated earth or other loads. Holding tank covers shall be capable of supporting an earth load of not less than 300 pounds per square foot (lb/ft²) (1465 kg/m²) where the tank is designed for underground installation. Below grade rainwater tanks installed underground shall be provided with manholes. *Below grade storage tanks, located outside of the building, shall be provided with either a manhole not less than 24 inches (610 mm) square or a manhole with an inside diameter of not less than 24 inches (610 mm). Service ports in manhole covers shall be not less than 8 inches (203 mm) in diameter. The manhole opening shall be not less than 20 inches (508 mm) in diameter and located not less than a minimum of 4 inches (102 mm) above the surrounding grade. The surrounding grade shall be sloped away from the manhole. Underground tanks shall be ballasted, anchored, or otherwise secured, to prevent the tank from*

floating out of the ground where empty. The combined weight of the tank and hold down system should meet or exceed the buoyancy force of the tank.

1602.9.5.5 (Formerly 1702.9.5.5) Drainage and Overflow. Rainwater storage tanks shall be provided with a means of draining and cleaning. The overflow drain shall not be equipped with a shutoff valve. The overflow outlet shall discharge in accordance with this code for storm drainage systems. Where discharging to the storm drainage system, the overflow drain *and tank drain* shall be protected from backflow of the storm drainage system by a backwater valve or other approved method. *Backwater valves shall be installed so that access is provided to the working parts for service and repair.*

1602.9.5.6 Opening and Access Protection. Rainwater tank openings shall be protected to prevent the entrance of insects, birds, or rodents into the tank *and piping systems*. ~~Rainwater tank access openings exceeding 12 inches (305mm) in diameter shall be secured to prevent tampering and unintended entry by either a lockable device or other approved method.~~

(A) Animals and Insects. (Formerly 1702.9.5.6 (A)) Screens installed on vent pipes, inlets, and overflow pipes shall have an aperture of not greater than 1/16 of an inch (1.6 mm) and shall be close fitting.

(B) Human Access. (Formerly 1702.9.5.6 (B))

A minimum of one access opening shall be provided to allow inspection and cleaning. Rainwater tank manholes and access openings shall be secured by either a lockable device or other approved method to prevent unauthorized access.

1602.9.5.8 Storage Tank Venting (Formerly 1702.9.5.7 Venting). Where venting by means of drainage or overflow piping is not provided, or is considered insufficient, a vent shall be installed on each tank. The vent shall extend from the top of the tank and terminate not less than 6 inches (152 mm) above grade and shall be not less than 1 1/2 inches (40 mm) in diameter *shall be provided with a vent sized in accordance with this code, and based on the size of the tank influent pipe.* The vent terminal shall be directed downward and covered with a 3/32 1/16 of an inch (2.4 mm) (1.6 mm) mesh screen to prevent the entry of vermin and insects. *Tank vent pipes shall not be connected to the sanitary drainage system vent.*

1602.10 (Formerly 1702.10) Signs. Signs in buildings using rainwater water shall be in accordance with Section 1602.10.1 and Section 1602.10.2 *and shall also comply with the applicable requirements of the California Building Code.*

1602.10.1 (Formerly 1702.10.1) Commercial, Industrial, and Institutional, and Residential Restroom Signs. A sign shall be installed in restrooms in commercial, industrial, and institutional occupancies, *and shall also be installed in residential common use area restrooms* using nonpotable rainwater for water closets, urinals, or both. Each sign shall contain 1/2 of an inch (12.7 mm) letters of a highly visible color on a contrasting background. ~~The location of the sign(s) shall be such that the sign(s) shall be visible to users. The number and location of the signs shall be approved by the Authority Having Jurisdiction and shall contain the following text:~~

TO CONSERVE WATER, THIS BUILDING USES RAINWATER TO FLUSH TOILETS AND URINALS.

1602.10.2 (Formerly 1702.10.2) Equipment Room Signs. Each equipment room containing nonpotable rainwater equipment shall have a sign posted with the following wording in 1 inch (25.4 mm) letters:

CAUTION NONPOTABLE RAINWATER, DO NOT DRINK. DO NOT CONNECT TO DRINKING WATER SYSTEM. NOTICE: CONTACT BUILDING MANAGEMENT BEFORE PERFORMING ANY WORK ON THIS WATER SYSTEM.

This sign shall be posted in a location that is visible to anyone working on or near rainwater water equipment.

1602.11.2 (Formerly 1702.11.2) Annual Cross-Connection Inspection and Testing. An initial and subsequent annual inspection and test required in accordance with Section 1602.5 shall be performed on both the potable and rainwater catchment water systems. The potable and rainwater catchment water systems shall be isolated from each other and independently inspected and tested to ensure there is no cross-connection in accordance with Section 1602.11.2.1 through Section 1602.11.2.4.

1602.11.2.3 (Formerly 1702.11.2.3) Discovery of Cross-Connection. In the event that a cross-connection is discovered, the following procedure, in the presence of the Authority Having Jurisdiction, shall be activated immediately:

- (1) Rainwater catchment water piping to the building shall be shut down at the meter supply source(s), and the rainwater water riser shall be drained.
- (2) Potable water piping to the building shall be shut down at the meter.
- (3) The cross-connection shall be uncovered and disconnected.
- (4) The building shall be retested following procedures listed in Section 1602.11.2.1 and Section 1602.11.2.2.
- (5) The potable water system shall be chlorinated with 50 ppm chlorine for 24 hours.
- (6) The potable water system shall be flushed after 24 hours, and a standard bacteriological test shall be performed. Where test results are acceptable, the potable water system shall be permitted to be recharged.

1602.11.2.4 Annual Inspection. An annual inspection of the rainwater catchment water system, following the procedures listed in Section 1602.11.2.1 shall be required. Annual cross-connection testing, following the procedures listed in Section 1602.11.2.2 shall be required by the Authority Having Jurisdiction, unless site conditions do not require it. In no event shall the test occur less than once in 4 years. Alternate testing requirements shall be permitted by the Authority Having Jurisdiction.

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 1295

21. HCD proposes to repeal existing California amendments from Chapter 16 of the 2013 California Plumbing Code and not bring forward these amendments into the 2016 California Plumbing Code as follows:

**CHAPTER 16
ALTERNATE WATER SOURCES FOR NONPOTABLE APPLICATIONS**

1604.12.1 Supply System Inspection and Test. On-site treated nonpotable *gray* water systems shall be inspected and tested in accordance with this code for testing of potable water piping.

1604.12.2 Cross-Connection Inspection and Testing. An initial and test shall be performed on both the potable and on-site treated nonpotable *gray* water systems. The potable and on-site treated nonpotable *gray* water system shall be isolated from each other and independently inspected and tested to ensure there is no cross-connection in accordance with Section 1604.12.2.1 through Section 1604.12.2.3.

1604.12.2.2 Cross-Connection Test. The procedure for determining cross-connection shall be followed by the applicant in the presence of the Authority Having Jurisdiction and other Authorities Having Jurisdiction to determine whether a cross-connection has occurred as follows:

- (1) The potable water system shall be activated and pressurized. The on-site treated nonpotable *gray* water system shall be shut down and completely drained.
- (2) The potable water system shall remain pressurized for a minimum period of time specified by the Authority Having Jurisdiction while the on-site treated nonpotable *gray* water system is empty. The minimum period the on-site treated nonpotable *gray* water system is to remain depressurized shall be determined on a case-by-case basis, taking into account the size and complexity of the potable and on-site treated *gray* water distribution systems, but in no case shall that period be less than 1 hour.
- (3) Fixtures, potable and on-site treated, shall be tested and inspected for flow. Flow from an on-site treated *gray* water system outlet indicates a cross-connection. No flow from a potable water outlet shall indicate that it is connected to the on-site treated *gray* water system.
- (4) The drain on the on-site treated nonpotable *gray* water system shall be checked for flow during the test and at the end of the test.
- (5) The potable water system shall then be completely drained.

- (6) The on-site treated nonpotable ~~gray~~ water system shall then be activated and pressurized.
- (7) The on-site treated nonpotable ~~gray~~ water system shall remain pressurized for a minimum period of time specified by the Authority Having Jurisdiction while the potable water system is empty. The minimum period the potable water system is to remain depressurized shall be determined on a case-by-case basis, but in no case shall that period be less than 1 hour.
- (8) Fixtures, potable and on-site treated nonpotable, shall be tested and inspected for flow. Flow from a potable water system outlet indicates a cross-connection. No flow from an on-site treated ~~gray~~ water outlet will indicate that it is connected to the potable water system.
- (9) The drain on the potable water system shall be checked for flow during the test and at the end of the test.
- (10) Where there is no flow detected in the fixtures which would indicate a cross-connection, the potable water system shall be repressurized.

1604.12.2.3 Discovery of Cross-Connection. In the event that a cross-connection is discovered, the following procedure, in the presence of the Authority Having Jurisdiction, shall be activated immediately:

- (1) On-site treated nonpotable ~~gray~~ water piping to the building shall be shut down at the ~~source~~ and the on-site treated ~~gray~~ water riser shall be drained.
- (2) Potable water piping to the building shall be shut down at the meter.
- (3) The cross-connection shall be uncovered and disconnected.
- (4) The building shall be retested in accordance with procedures listed in Section 1604.12.2.1 and Section 1604.12.2.2.
- (5) The potable water system shall be chlorinated with 50 ppm chlorine for 24 hours.
- (6) The potable water system shall be flushed after 24 hours, and a standard bacteriological test shall be performed. Where test results are acceptable, the potable water system shall be permitted to be recharged.

1604.13 Sizing. On-site treated nonpotable ~~gray~~ water piping shall be sized in accordance with Section 610.0 of this code.

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

22. HCD proposes to repeal existing California amendments from Chapter 17 of the 2013 California Plumbing Code as follows:

CHAPTER 17 RAINWATER CATCHMENT SYSTEMS

~~**1702.2.1 Permit.** It shall be unlawful for a person to construct, install, alter, or cause to be constructed, installed, or altered, a nonpotable rainwater catchment system in a building or on a premise without first obtaining a permit to do such work from the Authority Having Jurisdiction.~~

~~**1702.9.3 Collection Surfaces.** Rainwater shall be collected from roof surfaces, or other manmade, above-ground impervious collection surfaces. Rainwater collected from surface water runoff, vehicular parking surfaces or manmade surfaces at or below grade shall comply with the water quality requirements for on-site treated nonpotable gray water in Section 1604.0.~~

~~**1702.9.4 Minimum Water Quality.** The minimum water quality for harvested rainwater shall meet the applicable water quality requirements for the intended applications as determined by the Authority Having Jurisdiction. No treatment is required for rainwater used for subsurface or non-sprinkled surface irrigation where the maximum storage volume is less than 360 gallons (1363 L). In the absence of water quality requirements for harvested rainwater, Table 1702.9.4 shall apply.~~

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

23. HCD proposes to adopt Chapter 17 from the 2015 Uniform Plumbing Code and bring forward existing amendments from the 2013 California Plumbing Code into the 2016 California Plumbing Code with modification as follows:

**CHAPTER 17 (Formerly 14)
REFERENCED STANDARDS**

**TABLE 1701.1 (Formerly 1401.1)
REFERENCED STANDARDS**

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|----------------------------|---|----------------------|--|
| <u>ASTM D1253-14</u> | <u>Standard Test Method for Residual Chlorine in Water</u> | <u>Miscellaneous</u> | <u>1504.10.6,</u> <u>1602.9.4.1</u> |
| <u>NSF 350 – 2011 2012</u> | <u>Onsite Residential and Commercial Water Reuse Treatment Systems</u> <u>NSF/ANSI 350, amended sections follow:</u> <u>5.6 Electrical components.</u> <u>Electrical components...The California Electrical Code shall be followed for all electrical components, system installation, and system operation.</u> | <u>Miscellaneous</u> | <u>1601.7,</u> <u>1604.10.2</u> <u>1501.7,</u> <u>1504.10.2</u> |
| ... | | | |

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

24. HCD proposes to adopt Appendix A from the 2015 Uniform Plumbing Code into the 2016 California Plumbing Code without amendments:

**APPENDIX A
RECOMMENDED RULES FOR SIZING THE WATER SUPPLY SYSTEM**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

25. HCD proposes to NOT adopt Appendix B from the 2015 Uniform Plumbing Code.

**APPENDIX B
EXPLANATORY NOTES ON COMBINATION WASTE AND VENT SYSTEMS**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

26. HCD proposes to NOT adopt Appendix C from the 2015 Uniform Plumbing Code.

**APPENDIX C
ALTERNATE PLUMBING SYSTEMS**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

27. HCD proposes to adopt Appendix D from the 2015 Uniform Plumbing Code into the 2016 California Plumbing Code without amendment:

**APPENDIX D
SIZING STORM WATER DRAINAGE SYSTEMS**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

28. HCD proposes to NOT adopt Appendix E from the 2015 Uniform Plumbing Code.

**APPENDIX E
MANUFACTURED/MOBILE HOME PARKS AND RECREATIONAL VEHICLE PARKS**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

29. HCD proposes to NOT adopt Appendix F from the 2015 Uniform Plumbing Code.

**APPENDIX F
FIREFIGHTER BREATHING AIR REPLENISHMENT SYSTEMS**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

30. HCD proposes to NOT adopt Appendix G from the 2015 Uniform Plumbing Code.

**APPENDIX G
SIZING OF VENTING SYSTEMS**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

31. HCD proposes to adopt Appendix H from the 2015 Uniform Plumbing Code into the 2016 California Plumbing Code without amendment:

**APPENDIX H
PRIVATE SEWAGE DISPOSAL SYSTEMS**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

32. HCD proposes to adopt Appendix I from the 2015 Uniform Plumbing Code into the 2016 California Plumbing Code without amendment:

**APPENDIX I
INSTALLATION STANDARD FOR PEX TUBING SYSTEMS
FOR HOT – AND COLD-WATER DISTRIBUTION**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

33. HCD proposes to repeal existing California amendments from the 2013 California Plumbing Code and not bring forward into the 2016 California Plumbing Code as follows:

**INSTALLATION STANDARD
FOR ABS BUILDING DRAIN, WASTE AND VENT PIPE AND FITTINGS
IAPMO IS 5-2006**

2.2.6 Piping Installed in Fire Resistive Construction.

All piping penetrations of fire resistance rated walls, partitions, floors, floor/ceiling assemblies, roof/ceiling assemblies, or shaft enclosures shall be protected in accordance with the requirements of the *California Building Code and* IAPMO Installation Standards. (UPC 213.7)

**INSTALLATION STANDARD
FOR CPVC SOLVENT CEMENTED HOT AND COLD WATER DISTRIBUTION SYSTEMS
IAPMO IS 20-2010**

1.2 Special Requirements for CPVC Installation within Residential Structures. ~~[HCD 1] In addition to the other requirements in the California Plumbing Code and this Appendix for the installation of CPVC Solvent Cemented Hot and Cold Water Distributions Systems, all installations of CPVC pipe within residential structures shall meet the following:~~

1.2.1 Flushing Procedures. ~~All installations of CPVC pipe within residential structures shall be flushed twice over a period of at least one (1) week. The pipe system shall be first flushed for at least 10 minutes and then filled and allowed to stand for no less than 1 week, after which all the branches of the pipe system must be flushed long enough to fully empty the contained volume. At the time of the fill, each fixture shall have a removable tag applied stating: "This new plumbing system was first filled on (date) by (name). The California Department of Housing and Community Development requires that the system be flushed after standing at least one week after the fill date specified above. If the system is used earlier than one week after the fill date, the water must be allowed to run for at least two minutes prior to use for human consumption. This tag may not be removed prior to flushing, except by the homeowner."~~

1.2.2 Worker Safety Measures. ~~Mechanical ventilation sufficient to maintain exposures below the relevant exposure limits established by state regulation shall be provided in enclosed spaces. This ventilation shall be directed at the breathing zone of the worker installing the pipe. Where mechanical ventilation is not practical, respirators, suitable for organic vapors, shall be used. For the purpose of this subdivision, an enclosed space is defined as:~~

~~(a) A space less than 100 square feet of floor area under a ceiling with a height of 10 feet or less, and which does not have openings (consisting of doors, windows, or unfinished walls) on at least two sides;~~

~~(b) Crawl spaces having a height of less than three feet;~~

~~(c) Enclosed attics that have a roof and ceiling; or~~

~~(d) Trenches having a depth greater than 24 inches.~~

~~Installers of CPVC pipe within residential structures shall use non-latex thin gauge (4 millimeters) nitrile gloves, or other gloves providing an equivalent or better degree of protection during the installation of the CPVC plumbing system. Gloves shall be provided to all workers by the contractor, or plumbing subcontractor, and shall be replaced upon contamination by cements.~~

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

34. HCD proposes to NOT adopt Appendix J from the 2015 Uniform Plumbing Code.

APPENDIX J COMBINATION OF INDOOR AND OUTDOOR COMBUSTION AND VENTILATION OPENING DESIGN

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

35. HCD proposes to NOT adopt Appendix K from the 2015 Uniform Plumbing Code.

**APPENDIX K
POTABLE RAINWATER CATCHMENT SYSTEMS**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

36. HCD proposes to NOT adopt Appendix L from the 2015 Uniform Plumbing Code.

**APPENDIX L
SUSTAINABLE PRACTICES**

NOTE:

Authority Cited: Health and Safety Code Sections 17040, 17050, 17920.9, 17921, 17921.3, 17921.6, 17921.10, 17922, 17922.6, 17922.12, 17927, 17928, 17959.6, 18300, 18552, 18554, 18620, 18630, 18640, 18670, 18690, 18691, 18865, 18871.3, 18871.4, 18873, 18873.1, 18873.2, 18873.3, 18873.4, 18873.5, 18938.3, 18944.11, and 19990; and Government Code Section 12955.1.

Reference: Health and Safety Code Sections 17000 through 17062.5, 17910 through 17995.5, 18200 through 18700, 18860 through 18874, and 19960 through 19997; and Government Code Sections 12955.1 and 12955.1.1.

**FINAL EXPRESS TERMS
FOR
PROPOSED BUILDING STANDARDS
OF THE
OFFICE OF STATEWIDE HEALTH PLANNING & DEVELOPMENT

REGARDING PROPOSED CHANGES TO
CALIFORNIA PLUMBING CODE
CALIFORNIA CODE OF REGULATIONS, TITLE 24, PART 5**

| | |
|--|--|
| LEGEND FOR FINAL EXPRESS TERMS (combination of 45-day and 15-day changes) | |
| 1. | For 45-day and 15-Day changes, existing California amendments or code language being modified appears in <i>italics</i> , with modified language <u>underlined</u> . |
| 2. | For 45-day and 15-Day changes, repealed text appears in strikeout . |
| 3. | Highlighted text: The highlighted text provides only clarification of proposed language. |

FINAL EXPRESS TERMS

**CHAPTER 1
ADMINISTRATION**

**DIVISION I
CALIFORNIA ADMINISTRATION**

Adopt the 2015 Uniform Plumbing Code (UPC) and carry forward existing amendments of the 2013 California Plumbing Code (CPC) for OSHPD 1, 2, 3, & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

**CHAPTER 1
DIVISION II
ADMINISTRATION**

Adopt the 2015 Uniform Plumbing Code (UPC) and carry forward existing amendments of the 2013 California Plumbing Code (CPC) for OSHPD 1, 2, 3 & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

**CHAPTER 2
DEFINITIONS**

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter and carry forward existing amendments of the 2013 California Plumbing Code (CPC) for OSHPD 1, 2, 3 & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

CHAPTER 3 GENERAL REGULATIONS

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter and carry forward existing amendments of the 2013 California Plumbing Code (CPC) for OSHPD 1, 2, 3 & 4 with the following modifications:

310.0 Prohibited Fittings and Practices. ...

310.10 [OSHPD 1, 3 & 4] *Floor drains and handwashing fixtures shall not be installed in operating and delivery rooms. Floor drains with self-priming traps may be installed in cystoscopic rooms.*

320.0 Rehabilitation of Piping Systems.

320.1 General. Where pressure piping ... ASTM F2831.

321.0 Essential Plumbing Provisions [OSHPD 1, 2, 3 (surgical clinics), & 4] *During periods of power outages essential electrical power shall be provided for the following equipment:*

- (1) Domestic water booster pumps.
- (2) Domestic hot water circulating pumps.
- (3) Sewage ejector pumps.
- (4) Sump pumps and drainage pumps.
- (5) Domestic water heating equipment and their controls.
- (6) Fuel pumps.
- (7) Grease removal devices requiring electrical power.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

CHAPTER 4 PLUMBING FIXTURES AND FIXTURE FITTINGS

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter and carry forward existing amendments of the 2013 California Plumbing Code (CPC) for OSHPD 1, 2, 3 & 4 with the following modifications:

412.0 Urinals.

412.1 Application. Urinals shall comply with ASME A112.19.2/CSA B45.1, ASME A112.19.19, or CSA B45.5/IAMPO Z124. Urinals shall have an average water consumption not to exceed 1 gallon (3.8 Lpf) of water per flush.

412.1.1 Nonwater Urinals. ~~[Not adopted for OSHPD 1, 2, 3, & 4]~~ Nonwater urinals shall have a barrier liquid sealant to maintain a trap seal. Nonwater urinals shall permit the uninhibited flow of waste through the urinal to the sanitary drainage system. Nonwater urinals shall be cleaned and maintained in accordance with the manufacturer's instructions after installation. Where nonwater urinals are installed, not less than one water supplied fixture rated at not less than 1 water supply fixture unit (WSFU) shall be installed upstream on the same drain line to facilitate drain line flow and rinsing. Where nonwater urinals are installed they shall have a water distribution line rough-in to the urinal location to allow for the installation of an approved backflow prevention device in the event of a retrofit.

...

Due to renumbering in the 2015 Uniform Plumbing Code, the existing 2013 California Plumbing Code OSHPD amendment of Section 413.3 is to be carried forward to Section 413.2.

~~413.3~~ **413.2 Flushometer Valves.** Flushometer valves and tanks shall comply with ASSE 1037 or CSA B125.3, and shall be installed in accordance with Section 603.5.1. No manually controlled flushometer valve shall be used to flush more than one urinal, and each such urinal flushometer valve shall be an approved, self-closing type discharging a predetermined quantity of water. Flushometers shall be installed so that they will be accessible for repair. Flushometer valves shall not be used where the water pressure is insufficient to properly operate them. Where the valve is operated, it shall complete the cycle of operation automatically, opening fully, and closing positively under the line water pressure. Each flushometer shall be provided with a means for regulating the flow through it. ~~[OSHPD 1, 2, 3, & 4]~~ *Sensor operated flush valves shall be capable of functioning during loss of normal power.*

...

422.0 Minimum Number of Required Fixtures.

422.1 Fixture Count. ...

422.2 Separate Facilities. Separate toilet facilities shall be provided for each sex.

Exceptions: ~~[Not adopted for OSHPD 1, 2, 3 & 4]~~

- (1) Residential installations.
- (2) In occupancies with a total occupant load of 10 or less, including customers and employees, one toilet facility, designed for use by no more than one person at a time, shall be permitted for use by both sexes.
- (3) In business and mercantile occupancies with a total occupant load of 50 or less including customers and employees, one toilet facility, designed for use by no more than one person at a time, shall be permitted for use by both sexes.

422.2.1 Family or Assisted-Use Toilet Facilities. Where a separate toilet facility is required for each sex, and each toilet facility is required to have only one water closet, two family or assisted-use toilet facilities shall be permitted in place of the required separate toilet facilities.

Due to the renumbering in the 2015 Uniform Plumbing Code, the existing 2013 California Plumbing Code OSHPD amendment of Section 422.2.1 is to be carried forward to Section 422.2.2.

~~422.2.4.2~~ ~~[OSHPD 1, 2, 3 & 4]~~ *Separate toilet facilities shall be provided for the use of patients, staff personnel and visitors.*

Exception for Primary Care Clinics only: *Where a facility contains no more than three examination and/or treatment rooms, the patient toilet shall be permitted to serve waiting areas.*

...

TABLE 4-2
[OSHPD 1, 2, 3 & 4]²⁴ MINIMUM PLUMBING FACILITIES

| SPACE | HANDWASHING FIXTURE | SCRUB SINKS ³ | TOILETS | BATHTUBS OR SHOWERS | SERVICE SINKS ¹ | CLINIC SINKS |
|-------------------------------------|------------------------|-----------------------------|----------|------------------------|-------------------------------|-----------------|
| <i>Renal Dialysis Service Space</i> | <i>1:4</i> | | | | <i>1</i> | |
| ... | | | | | | |
| <i>Repair room¹¹</i> | <i>1</i> | | | | <i>1</i> | |
| <i>Dialysis P-patient toilet</i> | <i>1 2</i> | | <i>1</i> | | | |
| <i>Staff lounge</i> | | | | | | |

Notes:

1 Each department ...

2 Conventional spouts and controls on hot-and cold-water supplies are acceptable. Aerators are not permitted. Non-aerating laminar flow devices are permitted.

3 Scrub sink ...

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

CHAPTER 5 WATER HEATERS

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter for OSHPD 1, 2, 3 & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

CHAPTER 6 WATER SUPPLY AND DISTRIBUTION

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter and carry forward existing amendments of the 2013 California Plumbing Code (CPC) for OSHPD 1, 2, 3 & 4 with the following modifications:

604.0 Materials.

604.1 Pipe, Tube, and Fittings. Pipe, tube, fittings, solvent cements, thread sealants, solders, and flux used in potable water systems intended to supply drinking water shall be in accordance with the requirements of NSF 61. Where fittings and valves are made from copper alloys containing more than 15 percent zinc by weight, and are used in plastic piping systems, they shall be resistant to dezincification and stress corrosion cracking in accordance with NSF 14.

Materials used in the water supply system, except valves and similar devices, shall be of a like material, except where otherwise approved by the Authority Having Jurisdiction.

Materials for building water piping and building supply piping shall comply with the applicable standards referenced in Table 604.1.

Exception: ~~[OSHPD 1, 2, 3 & 4] Use of CPVC is not permitted for applications under authority of the Office of Statewide Health Planning and Development.~~

...

605.3.3.2 605.1.3.2 [Not permitted for OSHPD 1, 2, 3, & 4] Pressed Fittings. Pressed fittings for copper pipe or copper alloy pipe or tubing shall have an elastomeric O-ring that forms the joint. The pipe or tubing shall be fully inserted into the fitting, and the pipe or tubing marked at the shoulder of the fitting. Pipe or tubing shall be cut square, chamfered, and reamed to full inside diameter. The fitting alignment shall be checked against the mark on the pipe or tubing to ensure the pipe or tubing is inserted into the fitting. The joint shall be pressed using the tool recommended by the manufacturer.

...

Due to renumbering in the 2015 Uniform Plumbing Code, the existing 2013 California Plumbing Code OSHPD amendment of Section 605.16 is to be carried forward to Section 605.15.

605.16 605.15 Dielectric Unions. Dielectric unions where install at points of connection where there is a dissimilarity of metals shall be in accordance with ASSE 1079. **[OSHPD 1, 2, 3 & 4] Dielectric unions shall be used at all points of connection where there is a dissimilarity of metals.**

...

614.0 Dialysis Water-Distribution Systems.

614.1 [OSHPD 1, 2, 3, & 4] Dialysis water feedlines shall be PVC (polyvinyl chloride), glass, stainless steel, or PVDF (polyvinylidene fluoride) and sized to provide a minimum velocity of 1.5 feet per second (0.46 m/s). The piping shall be a singleloop system with or without recirculation. Branches to dialysis machines shall be 1/4 inch (6.4 mm) inside dimension and take off from the bottom of the main feedline. Branch lines may be PFA (perfluoroalkoxy).

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

CHAPTER 7 SANITARY DRAINAGE

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter for OSHPD 1, 2, 3, & 4 and carry forward existing amendments of the 2013 California Plumbing Code (CPC) for OSHPD 1 with the following modifications:

701.0 General.

701.1 Applicability. This chapter shall ...

701.4 701.2 Drainage Piping. Materials for drainage piping shall be in accordance with one of the referenced standards in Table 701.2 except that:

- (1) No galvanized wrought-iron ... aboveground.
- (2) ABS and PVC DWV piping installations shall be installed in accordance with applicable standards referenced in Table 1701.1 and Chapter 14 "Firestop Protection." Except for individual single-family dwelling units, materials exposed within ducts or plenums shall have a flame-spread index of not more than 25 and a smoke-developed index of not more than 50, where tested in accordance with ASTM E84 or UL 723.
- ~~(b) [OSHPD 1, 2, 3 & 4] ABS and PVC installations are not allowed.~~
- (3) No vitrified clay ... belowground.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

CHAPTER 8 INDIRECT WASTE

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter for OSHPD 1, 2, 3 & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

CHAPTER 9 VENTS

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter and carry forward existing amendments of the 2013 California Plumbing Code (CPC) for OSHPD 1, 2, 3 & 4 with the following modifications:

903.0 Materials.

903.1 Applicable Standards. Vent pipe and fittings shall comply with the applicable standards referenced in Table 701.2, except that:

- (1) No galvanized steel ... aboveground.
- (2) ABS and PVC DWV piping installations shall be in accordance with the applicable standards referenced in Table 1701.1, and Chapter 14 "Firestop Protection." Except for individual single-family dwelling units, materials exposed within ducts or plenums shall have a flame-spread index of not more than 25 and a smoke-developed index of not more than 50 where tested in accordance with ASTM E84 or UL 723.

~~903.1.3 [OSHPD 1, 2, 3 & 4] ABS and PVC installations are not allowed.~~

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

CHAPTER 10 TRAPS AND INTERCEPTORS

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter and carry forward existing amendments of the 2013 California Plumbing Code (CPC) for OSHPD 1, 2, 3 & 4 with the following modifications.

Due to renumbering of the 2015 Uniform Plumbing Code, the existing 2013 California Plumbing Code OSHPD amendments Sections 1015.6 and 1015.7 are being renumbered and carried forward as follows.

~~1015.5~~ **1015.4 Performance.** FOG disposal systems shall produce an effluent quality no to exceed 5.84 grains per gallon (gr/gal) (100 mg/L) FOG in accordance with ASME A112.14.16.

~~1015.6~~ **1015.5 [OSHPD 1, 2, 3 & 4]** Grease interceptors shall not be installed in food preparation area of kitchens.

~~1015.7~~ **1015.6 [OSHPD 1, 2, 3 & 4]** Grease interceptors shall be installed outside of the kitchen area in location affording ease of maintenance and servicing.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

CHAPTER 11 STORM DRAINAGE

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter and repeal amendments Sections 1101.3.2 and 1102.1.3 for OSHPD 1, 2, 3 & 4 as follows:

~~1101.2~~ 1101.3 Storm Water Drainage to Sanitary Sewer Prohibited. ...

~~1101.3~~ 1101.4 Materials Uses. Pipe, tube, and fittings conveying rainwater shall be of such materials and design as to perform their intended function to the satisfaction of the Authority Having Jurisdiction. Conductors within a vent or shaft shall be of cast-iron, galvanized steel, wrought-iron, copper, copper alloy, lead, Schedule 40 ABS DWV, Schedule 40 PVC DWV, stainless steel 304 or 316L [stainless steel 304 pipe and fittings shall not be installed underground and shall be kept not less than 6 inches (152mm) aboveground], or other approved materials, and changes in direction shall be in accordance with the requirements of Section 706.0. ABS and PVC DWV piping installations shall be installed in accordance with Chapter 14 "Firestop Protection." Except for individual single-family dwelling units, materials exposed within ducts or plenums shall have a flame-spread index of not more than 25 and a smoke-developed index of not more than 50, where tested in accordance with ASTM E84 or UL 723.

~~1101.3.2 [OSHPD 1, 2, 3, & 4] ABS and PVC installations are not allowed.~~

...

~~1102.0~~ 1101.4 Materials Uses.

~~1102.1~~ 1101.4.2 Conductors. Conductors installed aboveground in buildings shall be in accordance with the applicable standards referenced in Table 701.2 for aboveground drain, waste, and vent pipe. Conductors installed aboveground level shall be of seamless copper water tube, Type K, L, or M; Schedule 40 copper pipe or Schedule 40 copper alloy pipe; Type DWV copper drainage tube; service weight cast-iron soil pipe or hubless cast-iron soil pipe; standard weight galvanized steel pipe; stainless steel 304 or 316L [stainless steel 304 pipe and fittings shall not be installed underground and shall be kept not less than 6 inches (152mm) aboveground]; or Schedule 40 ABS or Schedule 40 PVC plastic pipe.

~~1102.1.3 [OSHPD 1, 2, 3, & 4] ABS and PVC installations are not allowed.~~

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

CHAPTER 12 FUEL GAS PIPING

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter for OSHPD 1, 2, 3 & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

CHAPTER 13 HEALTH CARE FACILITIES AND MEDICAL GAS AND MEDICAL VACUUM SYSTEMS

Adopt the 2015 Uniform Plumbing Code (UPC) and carry forward existing amendments of the 2013 California Plumbing Code (CPC) for OSHPD 1, 2, 3 & 4.

Relocating and renumbering existing 2013 California Plumbing Code OSHPD amendment Section 1301.2.1 to Section 1304.1.2.

1304.0 Medical Gas and Medical Vacuum Piping Systems.

1304.1 General. The installation of medical gas and medical vacuum piping systems shall comply with the requirements of this chapter.

~~1301.2.1~~ **1304.1.2 [OSHPD 1, 2, 3 & 4]** *Medical gas systems for health care facilities that are regulated by OSHPD (hospitals, skilled nursing facilities, and intermediate care facilities, licensed clinics, and correctional treatment centers) shall be in accordance with NFPA 99, Standard for Health Care Facilities. See California Building Code Table 1224.4.6.1 for location and number of station outlets for oxygen, vacuum, and medical air.*

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

**CHAPTER 14
FIRESTOP PROTECTION**

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter for OSHPD 1, 2, 3 & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

**CHAPTER 15
ALTERNATE WATER SOURCES FOR NONPOTABLE APPLICATIONS**

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter for OSHPD 1, 2, 3 & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

**CHAPTER 16
NONPOTABLE RAINWATER CATCHMENT SYSTEMS**

Entire Chapter not adopted by OSHPD.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

**CHAPTER 17
REFERENCED STANDARDS**

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter for OSHPD 1, 2, 3 & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

**APPENDIX A
RECOMMENDED RULES FOR SIZING THE WATER SUPPLY SYSTEM**

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter for OSHPD 1, 2, 3 & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

**APPENDIX B
EXPLANATORY NOTES ON COMBINATION WASTE AND VENT SYSTEMS**

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter for OSHPD 1, 2, 3 & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

**APPENDIX D
SIZING STORM WATER DRAINAGE SYSTEMS**

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter for OSHPD 1, 2, 3 & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

**APPENDIX I
INSTALLATION STANDARDS**

Adopt entire 2015 Uniform Plumbing Code (UPC) chapter for OSHPD 1, 2, 3 & 4.

Notation

Authority: Health and Safety Code Sections 1226, 1275, 18928, 129790 and 129850; Government 11152.5

Reference: Health and Safety Code Section 129850

**FINAL EXPRESS TERMS
FOR
PROPOSED BUILDING STANDARDS
OF THE
OFFICE OF THE STATE FIRE MARSHAL
REGARDING PROPOSED CHANGES TO
2016 CALIFORNIA PLUMBING CODE
CALIFORNIA CODE OF REGULATIONS, TITLE 24, PART 5**

LEGEND FOR EXPRESS TERMS

1. Existing California amendments or code language being modified are in italics when they appear in the model code text: All such language appears in *italics*, modified language is underlined.
2. New California amendments: All such language appears underlined and in italics.
3. Repealed text: All such language appears in ~~strikeout~~.

The Office of the State Fire Marshal (SFM) proposes to adopt the 2015 edition of the Uniform Plumbing Code (UPC) into the 2016 edition of the California Plumbing Code (CPC). SFM further proposes to:

- Repeal the adoption by reference of the 2012 Uniform Plumbing Code and incorporate and adopt by reference in its place the 2015 Uniform Plumbing Code for application and effectiveness in the 2016 California Plumbing Code.
 - Repeal certain amendments to the 2012 Uniform Plumbing Code and/or California Building Standards not addressed by the model code that are no longer necessary.
 - Adopt new building standards or necessary amendments to the 2015 Uniform Plumbing Code that address inadequacies of the 2015 Uniform Plumbing Code as they pertain to California laws.
 - Bring forward previously existing California building standards or amendments, which represent no change in their effect from the 2013 California Building Standards Code.
 - Codify non-substantive editorial and formatting amendments from the format based upon the 2012 Uniform Mechanical Code to the format of the 2015 Uniform Plumbing Code.
-

[1. The SFM is proposing to make editorial changes to the Preface..]

**PREFACE
FORMAT OF THE UNIFORM PLUMBING CODE**

Chapter 6 Water Supply and Distribution.

Chapter 6 regulates the design, material and installation of water supply and distribution systems, including residential fire sprinklers. The water supply and distribution system is designed to achieve the correct water pressure and flow rates and avoid cross connections. For fixtures to perform properly, an acceptable supply of potable water is essential to their operation and use. Cross connections and backflow are ranked as the highest priority because of the long history of recognized health risks posed by cross connections, outbreaks, or cases of waterborne disease. Piping materials and components are evaluated for their possible effect on the potable water with which they are in contact. The intent is to control the potential adverse health effects produced by indirect additives, products, and materials that come in contact with potable water. When selecting materials for water supply and distribution systems, consider water pressure, water temperature, compatibility with the water supply, durability, support, and sustainability.

In addition, this chapter regulates the design, location, materials, and installation of multipurpose and stand-alone sprinkler systems that do not include the use of antifreeze. ~~Where systems are installed as a portion of the water distribution system under the requirements of this chapter and are not provided with a fire department connection,~~ Where permitted by Section 612.3.8, backflow protection for the water supply system is not required.

[1. The SFM is proposing to maintain the adoption of those existing California provisions contained Sections 1.1.0 through 1.1.12 with modification.]

**CHAPTER 1
CALIFORNIA ADMINISTRATION
DIVISION I**

1.1.0 General.

1.1.1 Title. *These regulations shall be known as the California Plumbing Code, may be cited as such and will be referred to herein as "this code." The California Plumbing Code is Part 5 of ~~twelve~~thirteen parts of the official compilation and publication of the adoption, amendment, and repeal of building regulations to the California Code of Regulations, Title 24, also referred to as the California Building Standards Code. This part incorporates by adoption the ~~2012~~2015 Uniform Plumbing Code of the International Association of Plumbing and Mechanical Officials with necessary California amendments.*

1.1.2 Purpose. *The purpose of this code is to establish the minimum requirements to safeguard the public health, safety and general welfare through structural strength, means of egress facilities, stability, access to persons with disabilities, sanitation, adequate lighting and ventilation, and energy conservation; safety to life and property from fire and other hazards attributed to the built environment; and to provide safety to fire fighters and emergency responders during emergency operations.*

1.1.3 Scope. *The provisions of this code shall apply to the construction, alteration, movement, enlargement, replacement, repair, equipment, use and occupancy, location, maintenance, removal and demolition of every building or structure or any appurtenances connected or attached to such buildings or structures throughout the State of California.*

1.1.3.1 Nonstate-Regulated Buildings, Structures, and Applications. Except as modified by local ordinance pursuant to Section 1.1.8, the following standards in the California Code of Regulations, Title 24, Parts 2, 2.5, 3, 4, 5, 6, 9, 10 and 11 shall apply to all occupancies and applications not regulated by a state agency.

1.1.3.2 State-Regulated Buildings, Structures, and Applications. The model code, state amendments to the model code, and/or state amendments where there are no relevant model code provisions shall apply to the following buildings, structures, and applications regulated by state agencies as specified in Section 1.2 through 1.14, except where modified by local ordinance pursuant to Section 1.1.8. When adopted by a state agency, the provisions of this code shall be enforced by the appropriate enforcing agency, but only to the extent of authority granted to such agency by the state legislature.

Note: See Preface to distinguish the model code provisions from the California provisions.

1. State-owned buildings, including buildings constructed by the Trustees of the California State University, and to the extent permitted by California laws, buildings designed and constructed by the Regents of the University of California, and regulated by the Building Standards Commission. See Section 1.2 for additional scope provisions.
2. Local detention facilities regulated by the Board of State and Community Corrections Corrections Standards Authority. See Section 1.3 for additional scope provisions.
3. Barbering, cosmetology or electrolysis establishments, acupuncture offices, pharmacies, veterinary facilities, and structural pest control locations regulated by the Department of Consumer Affairs. See Section 1.4 for additional scope provisions.
4. ~~Energy efficiency standards regulated by the~~ Section 1.5 reserved for the California Energy Commission. See ~~Section 1.5 for additional scope provisions.~~
5. Dairies and places of meat inspection regulated by the Department of Food and Agriculture. See Section 1.6 for additional scope provisions.
6. Organized camps, laboratory animal quarters, public swimming pools, radiation protection, commissaries serving mobile food preparation vehicles and wild animal quarantine facilities regulated by the Department of Public Health. See Section 1.7 for additional scope provisions.
7. Hotels, motels, lodging houses, ~~apartment houses~~ apartments, dwellings, dormitories, condominiums, shelters for homeless persons, congregate residences, employee housing, factory-built housing and other types of dwellings containing sleeping accommodations with or without common toilets or cooking facilities. See Section 1.8.2.1.1 for additional scope provisions.
8. Accommodations for persons with disabilities in buildings containing newly constructed covered multifamily dwellings, new common use spaces serving existing covered multifamily dwellings, additions to existing buildings where the addition alone meets the definition of "COVERED MULTIFAMILY DWELLINGS," and new common-use spaces areas serving new covered multifamily dwellings which are regulated by the Department of Housing and Community Development. See Section 1.8.2.1.2 for additional scope provisions.
9. Permanent buildings and permanent accessory buildings or structures constructed within mobilehome parks and special occupancy parks regulated by the Department of Housing and Community Development. See Section 1.8.2.1.3 for additional scope provisions.
10. Reserved for the Division of the State Architect – Access Compliance.
11. Public elementary and secondary schools, community college buildings and state-owned or state leased essential service buildings regulated by the Division of the State Architect. See Section 1.9.2 for additional scope provisions.
12. Reserved for the State Historical Building Safety Board with the Division of the State Architect. See Section 1.9.2 for additional scope provisions.
13. General acute care hospitals, acute psychiatric hospitals, skilled nursing and/or intermediate care facilities, clinics licensed by the Department of Public Health and correctional treatment centers regulated

by the Office of Statewide Health Planning and Development. See Section 1.10 for additional scope provisions.

14. Applications regulated by the Office of State Fire Marshal include but are not limited to the following in accordance with Section 1.11:

1. Buildings or structures used or intended for use as an:

1.1. Asylum, jail, prison.

1.2. Mental hospital, hospital, home for the elderly, children's nursery, children's home or institution, school or any similar occupancy of any capacity.

1.3. Theater, dancehall, skating rink, auditorium, assembly hall, meeting hall, nightclub, fair building or similar place of assemblage where 50 or more persons may gather together in a building, room or structure for the purpose of amusement, entertainment, instruction, deliberation, worship, drinking or dining, awaiting transportation, or education.

1.4. Small family day care homes, large family day-care homes, residential facilities and residential facilities for the elderly, residential care facilities.

1.5. State institutions or other state-owned or state-occupied buildings.

1.6. High rise structures.

1.7. Motion picture production studios.

1.8. Organized camps.

1.9. Residential structures.

2. Tents, awnings or other fabric enclosures used in connection with any occupancy.

3. Fire alarm devices, equipment and systems in connection with any occupancy.

4. Hazardous materials, flammable and combustible liquids.

5. Public school automatic fire detection, alarm and sprinkler systems.

6. Wildland-urban interface fire areas.

15. Public libraries constructed and renovated using funds from the California Library Construction and Renovation Bond Act of 1988 and regulated by the State Librarian. See Section 1.12 for additional scope provisions.

16. Section 1.13 reserved for Graywater systems regulated by the Department of Water Resources. See Section 1.13 for additional scope provisions.

17. For applications listed in Section 1.9.1 regulated by the Division of the State Architect – Access Compliance, outdoor environments and uses shall be classified according to accessibility uses described in Chapter 11A, 11B and 11C.

18. Marine Oil Terminals regulated by the California State Lands Commission. See Section 1.14 for additional scope provisions.

1.1.4 Appendices. Provisions contained in the appendices of this code shall not apply unless specifically adopted by a state agency or adopted by a local enforcing agency in compliance with Health and Safety Code Section 18901 et. seq. for Building Standards Law, Health and Safety Code Section 17950 for State Housing Law and Health and Safety Code Section 13869.7 for Fire Protection Districts. See Section 1.1.8 of this code.

1.1.5 Referenced Codes. The codes, standards and publications adopted and set forth in this code, including other codes, standards and publications referred to therein are, by title and date of publication, hereby adopted as standard reference documents of this code. When this code does not specifically cover any subject related to building design and construction, recognized architectural or engineering practices shall be employed. The National Fire Codes, standards, and the Fire Protection Handbook of the National Fire Protection Association are permitted to be used as authoritative guides in determining recognized fire prevention engineering practices.

1.1.6 Nonbuilding Standards, Orders and Regulations. Requirements contained in the Uniform Plumbing Code or in any other referenced standard, code or document, which are not building standards as defined in Health and Safety Code Section 18909, shall not be construed as part of the provisions of this code. For nonbuilding standards, orders, and regulations, see other titles of the California Code of Regulations.

1.1.7 Order of Precedence and Use.

1.1.7.1 Differences. In the event of any differences between these building standards and the standard reference documents, the text of these building standards shall govern.

1.1.7.2 Specific Provisions. Where a specific provision varies from a general provision, the specific provision shall apply.

1.1.7.3 Conflicts. When the requirements of this code conflict with the requirements of any other part of the California Building Standards Code, Title 24, the most restrictive requirements shall prevail.

Exception: Detached one-and two-family dwellings, efficiency dwelling units, lodging houses, live/work units, townhouses not more than three stories above grade plane with a separate means of egress, and their accessory structures, shall not be required to comply with the California Residential Code if constructed in accordance with the California Building Code.

1.1.8 City, County, or City and County Amendments, Additions or Deletions. The provisions of this code do not limit the authority of city, county, or city and county governments to establish more restrictive and reasonably necessary differences to the provisions contained in this code pursuant to complying with Section 1.1.8.1. The effective date of amendments, additions, or deletions to this code by a city, county, or city and county filed pursuant to Section 1.1.8.1 shall be the date filed. However, in no case shall the amendments, additions, or deletions to this code be effective any sooner than the effective date of this code.

Local modifications shall comply with Health and Safety Code Section 18941.5 for Building Standards Law, Health and Safety Code Section 17958 for State Housing Law or Health and Safety Code Section 13869.7 for Fire Protection Districts.

1.1.8.1 Findings and Filings.

(1) The city, county, or city and county shall make express findings for each amendment, addition, or deletion based upon climatic, topographical, or geological conditions.

Exception: Hazardous building ordinances and programs mitigating unreinforced masonry buildings.

(2) The city, county, or city and county shall file the amendments, additions, or deletions expressly marked and identified as to the applicable findings. Cities, counties, cities and counties, and fire departments shall file the amendments, additions, or deletions, and the findings with the California Building Standards Commission at 2525 Natomas Park Drive, Suite 130, Sacramento, CA 95833.

(3) Findings prepared by fire protection districts shall be ratified by the local city, county, or city and county and filed with the California Department of Housing and Community Development, Division of Codes and Standards, P.O. Box 1407, Sacramento, CA 95812-1407 or ~~1800 3rd Street, Room 260, Sacramento, CA 95811~~ 2020 West El Camino Avenue, Suite 250, Sacramento, CA 95833-1829.

1.1.8.2 Locally adopted energy standards – California Energy Code, Part 6

In addition to the provisions of Section 1.1.8.1 of this Part, the provisions of this section apply to cities, counties, and city and county amending adopted energy standards affecting buildings and structures subject to the California Energy Code, Part 6.

Applicable provisions of Public Resources Code Section 25402.1 and applicable provisions of Chapter 10 of the California Administrative Code, Part 1 apply to local amendment of energy standards adopted by the California Energy Commission.

1.1.9 Effective Date of This Code. Only those standards approved by the California Building Standards Commission that are effective at the time an application for building permit is submitted shall apply to the plans and specifications for, and to the construction performed under, that permit. For the effective dates of the provisions contained in this code, see the History Note page of this code.

1.1.10 Availability of Codes. At least one complete copy each of Titles 8, 19, 20, 24, and 25 with all revisions shall be maintained in the office of the building official responsible for the administration and enforcement of this code. Each state department concerned and each city, county, or city and county shall have an up-to-date copy of the code available for public inspection, See Health and Safety Code Sections 18942(d)(1) and (2).

1.1.11 Format. This part fundamentally adopts the Uniform Plumbing Code by reference on a chapter-by-chapter basis. When a specific chapter of the Uniform Plumbing Code is not printed in the code and is marked "Reserved" such chapter of the Uniform Plumbing Code is not adopted as a portion of this code. When a specific chapter of the Uniform Plumbing Code is marked "Not adopted by the State of California" but appears in the code, it may be available for adoption by local ordinance.

Note: Matrix Adoption Tables at the front of each chapter may aid the code user in determining which chapter or sections within a chapter are applicable to buildings under the authority of a specific state agency, but they are not to be considered regulatory.

1.1.12 Validity. If any chapter, section, subsection, sentence, clause, or phrase of this code is for any reason held to be unconstitutional, contrary to statute, exceeding the authority of the state as stipulated by statutes or otherwise inoperative, such decision shall not affect the validity of the remaining portion of this code.

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[1.1. The SFM is proposing to maintain the adoption of those existing California provisions contained Sections 1.11.0 through 1.11.10 without modification.]

1.11.0 Office of the State Fire Marshal.

1.11.1 SFM– Office of the State Fire Marshal. Specific scope of application of the agency responsible for enforcement, the enforcement agency and the specific authority to adopt and enforce such provisions of this code, unless otherwise stated.

Application:

Institutional, Educational, or any Similar Occupancy. Any building or structure used or intended for use as an asylum, jail, mental hospital, hospital, sanitarium, home for the aged, children's nursery, children's home, school, or any similar occupancy of any capacity.

Authority Cited – Health and Safety Code Section 13143.

Reference – Health and Safety Code Section 13143.

Assembly or Similar Place of Assemblage. Any theater, dancehall, skating rink, auditorium, assembly hall, meeting hall, nightclub, fair building or similar place of assemblage where 50 or more persons may gather together in a building, room or structure for the purpose of amusement, entertainment, instruction, deliberation, worship, drinking or dining, awaiting transportation, or education.

Authority Cited – Health and Safety Code Section 13143.

Reference – Health and Safety Code Section 13143.

Small Family Day Care Homes.

Authority Cited – Health and Safety Code Sections 1597.45, 1597.54, 13143, and 17921.

Reference – Health and Safety Code Section 13143.

Large Family Day Care Homes.

Authority Cited - Health and Safety Code Sections 1597.46, 1597.54, and 17921.

Reference - Health and Safety Code Section 13143.

Residential Facilities and Residential Facilities for the Elderly.

Authority Cited - Health and Safety Code Section 13133.

Reference - Health and Safety Code Section 13143.

Any State Institution, Other State-Owned or State-Occupied Building.

Authority Cited – Health and Safety Code Section 13108.

Reference – Health and Safety Code Section 13143.

High-Rise Structures.

Authority Cited – Health and Safety Code Section 13211.

Reference – Health and Safety Code Section 13143.

Motion Picture Production Studios.

Authority cited – Health and Safety Code Section 13143.1.

Reference – Health and Safety Code Section 13143.

Organized Camps.

Authority Cited – Health and Safety Code Section 18897.3.

Reference – Health and Safety Code Section 13143.

Residential. All hotels, motels, lodging houses, apartment houses, and dwellings, including congregate residences and buildings and structures accessory thereto. Multiple-story structures existing on January 1, 1975, let for human habitation, including and limited to, hotels, motels and apartment houses, less than

75 feet (22 860 mm) above the lowest floor level having building access, wherein rooms used for sleeping are let above the ground floor.

Authority Cited – Health and Safety Code Sections 13143.2 and 17921.

Reference – Health and Safety Code Section 13143.

Residential Care Facilities. Certified family care homes, out-of-home placement facilities, halfway houses, drug and/or alcohol rehabilitation facilities and any building or structure used or intended for use as a home or institution for the housing of any person of any age when such person is referred to or placed within such home or institution for protective social care and supervision services by any governmental agency.

Authority Cited – Health and Safety Code Section 13143.6.

Reference – Health and Safety Code Section 13143.

Tents, Awnings, or other Fabric Enclosures Used in Connection with any Occupancy.

Authority Cited – Health and Safety Code Section 13116.

Reference – Health and Safety Code Section 13143.

Fire Alarm Devices, Equipment, and Systems in Connection with any Occupancy.

Authority Cited – Health and Safety Code Section 13114.

Reference – Health and Safety Code Section 13143.

Hazardous Materials.

Authority Cited – Health and Safety Code Section 13143.9.

Reference – Health and Safety Code Section 13143.

Flammable and Combustible Liquids.

Authority Cited – Health and Safety Code Section 13143.6.

Reference – Health and Safety Code Section 13143.

Public School Automatic Fire Detection, Alarm, and Sprinkler Systems.

Authority Cited – Health and Safety Code Section 13143 and California Education Code Article 7.5, Sections 17074.50, 17074.52, and 17074.54.

References – Government Code Section 11152.5, Health and Safety Code Section 13143 and California Education Code Chapter 12.5, Leroy F. Greene School Facilities Act of 1998, Article 1.

Wildland-Urban Interface Fire Area.

Authority Cited – Health and Safety Code Sections 13143, 13108.5(a), 18949.2(b), (c) and Government Code Section 51189.

References – Health and Safety Code Sections 13143, Government Code Sections 51176, 51177, 51178, and 51179 and Public Resources Code Sections 4201 through 4204.

1.11.2 Duties and Powers of the Enforcing Agency.

1.11.2.1 Enforcement.

1.11.2.1.1 The responsibility for enforcement of building standards adopted by the State Fire Marshal and published in the California Building Standards Code relating to fire and panic safety and other regulations of the State Fire Marshal shall except as provided in Section 1.11.2.1.2 be as follows:

(1) The city, county, or city and county with jurisdiction in the area affected by the standard or regulation shall delegate the enforcement of the building standards relating to fire and panic safety and other regulations of the State Fire Marshal as they relate to Group R-3 occupancies, as described in Section 310.1 of Part 2 of the California Building Standards Code, to either of the following:

1.1. The chief of the fire authority of the city, county, or city and county, or an authorized representative.

1.2. The chief building official of the city, county, or city and county, or an authorized representative.

(2) The chief of any city or county fire department or of any fire protection district, and authorized representatives, shall enforce within the jurisdiction the building standards and other regulations of the State Fire Marshal, except those described in Item 1 or 4.

(3) The State Fire Marshal shall have authority to enforce the building standards and other regulations of the State Fire Marshal in areas outside of corporate cities and districts providing fire protection services.

(4) The State Fire Marshal shall have authority to enforce the building standards and other regulations of the State Fire Marshal in corporate cities and districts providing fire protection services on request of the chief fire official or the governing body.

(5) Any fee charged pursuant to the enforcement authority of this section shall not exceed the estimated reasonable cost of providing the service for which the fee is charged pursuant to Section 66014 of the Government Code.

1.11.2.1.2 Pursuant to Health and Safety Code Section 13108, and except as otherwise provided in this section, building standards adopted by the State Fire Marshal published in the California Building Standards Code relating to fire and panic safety shall be enforced by the State Fire Marshal in all state-owned buildings, state-occupied buildings, and state institutions throughout the state. Upon the written request of the chief fire official of any city, county or fire protection district, the State Fire Marshal may authorize such chief fire official and his or her authorized representatives, in their geographical area of responsibility, to make fire prevention inspections of state-owned or state-occupied buildings, other than state institutions, for the purpose of enforcing the regulations relating to fire and panic safety adopted by the State Fire Marshal pursuant to this section and building standards relating to fire and panic safety published in the California Building Standards Code. Authorization from the State Fire Marshal shall be limited to those fire departments or fire districts which maintain a fire prevention bureau staffed by paid personnel.

Pursuant to Health and Safety Code Section 13108, any requirement or order made by any chief fire official who is authorized by the State Fire Marshal to make fire prevention inspections of state owned or state-occupied buildings, other than state institutions, may be appealed to the State Fire Marshal. The State Fire Marshal shall, upon receiving an appeal and subject to the provisions of Chapter 5 (commencing with Section 18945) of Part 2.5 of Division 13 of the Health and Safety Code, determine if the requirement or order made is reasonably consistent with the fire and panic safety regulations adopted by the State Fire Marshal and building standards relating to fire and panic safety published in the California Building Code.

Any person may request a code interpretation from the State Fire Marshal relative to the intent of any regulation or provision adopted by the State Fire Marshal. When the request relates to a specific project, occupancy or building, the State Fire Marshal shall review the issue with the appropriate local enforcing agency prior to rendering such code interpretation.

1.11.2.1.3 Pursuant to Health and Safety Code Section 13112, any person who violates any order, rule or regulation of the State Fire Marshal is guilty of a misdemeanor punishable by a fine of not less than

\$100.00 or more than \$500.00, or by imprisonment for not less than six months, or by both. A person is guilty of a separate offense each day during which he or she commits, continues or permits a violation of any provision of, or any order, rule or regulation of, the State Fire Marshal as contained in this code. Any inspection authority who, in the exercise of his or her authority as a deputy State Fire Marshal, causes any legal complaints to be filed or any arrest to be made shall notify the State Fire Marshal immediately following such action.

1.11.2.2 Right of Entry. The fire chief of any city, county, or fire protection district, or such person's authorized representative, may enter any state institution or any other state-owned or state-occupied building for the purpose of preparing a fire suppression preplanning program or for the purpose of investigating any fire in a state-occupied building.

The State Fire Marshal, his or her deputies or salaried assistants, the chief of any city or county fire department or fire protection district and his or her authorized representatives may enter any building or premises not used for dwelling purposes at any reasonable hour for the purpose of enforcing this chapter. The owner, lessee, manager or operator of any such building or premises shall permit the State Fire Marshal, his or her deputies or salaried assistants and the chief of any city or county fire department or fire protection district and his or her authorized representatives to enter and inspect them at the time and for the purpose stated in this section.

1.11.2.3 More Restrictive Fire and Panic Safety Building Standards.

1.11.2.3.1 Any fire protection district organized pursuant to Health and Safety Code Part 2.7 (commencing with Section 13800) of Division 12 may adopt building standards relating to fire and panic safety that are more stringent than those building standards adopted by the State Fire Marshal and contained in the California Building Standards Code. For these purposes, the district board shall be deemed a legislative body and the district shall be deemed a local agency. Any changes or modifications that are more stringent than the requirements published in the California Building Standards Code relating to fire and panic safety shall be subject to Section 1.1.8.1.

1.11.2.3.2 Any fire protection district that proposes to adopt an ordinance pursuant to this section shall, not less than 30 days prior to noticing a proposed ordinance for public hearing, provide a copy of that ordinance, together with the adopted findings made pursuant to Section 1.11.2.3.1, to the city, county, or city and county where the ordinance will apply. The city, county, or city and county may provide the district with written comments, which shall become part of the fire protection district's public hearing record.

1.11.2.3.3 The fire protection district shall transmit the adopted ordinance to the city, county, or city and county where the ordinance will apply. The legislative body of the city, county, or city and county may ratify, modify or deny an adopted ordinance and transmit its determination to the district within 15 days of the determination. Any modification or denial of an adopted ordinance shall include a written statement describing the reasons for any modifications or denial. No ordinance adopted by the district shall be effective until ratification by the city, county, or city and county where the ordinance will apply. Upon ratification of an adopted ordinance, the city, county, or city and county shall file a copy of the findings of the district, and any findings of the city, county, or city and county, together with the adopted ordinance expressly marked and identified to which each finding refers, in accordance with Section 1.1.8.1, Item 3.

1.11.2.4 Request for Alternate Means of Protection. Requests for approval to use an alternative material, assembly or materials, equipment, method of construction, method of installation of equipment or means of protection shall be made in writing to the enforcing agency by the owner or the owner's authorized representative and shall be accompanied by a full statement of the conditions. Sufficient evidence or proof shall be submitted to substantiate any claim that may be made regarding its conformance. The enforcing agency may require tests and the submission of a test report from an

approved testing organization as set forth in Title 19, California Code of Regulation, to substantiate the equivalency of the proposed alternative means of protection.

When a request for alternate means of protection involves hazardous materials, the authority having jurisdiction may consider implementation of the findings and recommendations identified in a Risk Management Plan (RMP) developed in accordance with Title 19, Division 2, Chapter 4.5, Article 3.

Approval of a request for use of an alternative material, assembly of materials, equipment, method of construction, method of installation of equipment, or means of protection made pursuant to these provisions shall be limited to the particular case covered by request and shall not be construed as establishing any precedent for any future request.

1.11.2.5 Appeals. When a request for an alternate means of protection has been denied by the enforcing agency, the applicant may file a written appeal to the State Fire Marshal for consideration of the applicant's proposal. In considering such appeal, the State Fire Marshal may seek the advice of the State Board of Fire Services. The State Fire Marshal shall, after considering all of the facts presented, including any recommendations of the State Board of Fire Services, determine if the proposal is for the purposes intended, at least equivalent to that specified in these regulations in quality, strength, effectiveness, fire resistance, durability and safety, and shall transmit such findings and any recommendations to the applicant and to the enforcing agency.

1.11.3 Construction Documents.

1.11.3.1 Public Schools. Plans and specifications for the construction, alteration, or addition to any building owned, leased, or rented by any public school district shall be submitted to the Division of the State Architect.

1.11.3.2 Movable Walls and Partitions. Plans or diagrams shall be submitted to the enforcing agency for approval before the installation of, or rearrangement of, any movable wall or partition in any occupancy. Approval shall be granted only if there is no increase in the fire hazard.

1.11.3.3 New Construction High-Rise Buildings.

(1) Complete plans or specifications, or both, shall be prepared covering all work required to comply with new construction high-rise buildings. Such plans and specifications shall be submitted to the enforcing agency having jurisdiction.

(2) All plans and specifications shall be prepared under the responsible charge of an architect or a civil or structural engineer authorized by law to develop construction plans and specifications, or by both such architect and engineer. Plans and specifications shall be prepared by an engineer duly qualified in that branch of engineering necessary to perform such services. Administration of the work of construction shall be under the charge of the responsible architect or engineer except that where plans and specifications involve alterations or repairs, such work of construction may be administered by an engineer duly qualified to perform such services and holding a valid certificate under Chapter 7 (commencing with Section 65700) of Division 3 of the Business and Professions Code for performance of services in that branch of engineering in which said plans, specifications and estimates and work of construction are applicable.

This section shall not be construed as preventing the design of fire-extinguishing systems by persons holding a C-16 license issued pursuant to Division 3, Chapter 9, Business and Professions Code. In such instances, however, the responsibility charge of this section shall prevail.

1.11.3.4 Existing High-Rise Buildings.

(1) Complete plans or specifications, or both, shall be prepared covering all work required by Section 3412 for existing high-rise buildings. Such plans or specifications shall be submitted to the enforcing agency having jurisdiction.

(2) When new construction is required to conform with the provisions of these regulations, complete plans or specifications, or both, shall be prepared in accordance with the provisions of this subsection. As used in this section, "new construction" is not intended to include repairs, replacements or minor alterations which do not disrupt or appreciably add to or affect the structural aspects of the building.

1.11.3.5 Retention of Plans. Refer to Building Standards Law, Health and Safety Code Sections 19850 and 19851 for permanent retention of plans.

1.11.4 Fees.

1.11.4.1 Other Fees. Pursuant to Health and Safety Code Section 13146.2, a city, county, or district which inspects a hotel, motel, lodging house, or apartment house may charge and collect a fee for the inspection from the owner of the structure in an amount, as determined by the city, county or district, sufficient to pay its costs of that inspection.

1.11.4.2 Large Family Day Care. Pursuant to Health and Safety Code Section 1597.46, Large Family Day Care Homes, the local government shall process any required permit as economically as possible, and fees charged for review shall not exceed the costs of the review and permit process.

1.11.4.3 High-Rise. Pursuant to Health and Safety Code Section 13217, High-rise Structure Inspection: Fees and costs, a local agency which inspects a high-rise structure pursuant to Health and Safety Code Section 13217 may charge and collect a fee for the inspection from the owner of the high-rise structure in an amount, as determined by the local agency, sufficient to pay its costs of that inspection.

1.11.4.4 Fire Clearance Preinspection. Pursuant to Health and Safety Code Section 13235, Fire Clearance Preinspection, fee, upon receipt of a request from a prospective licensee of a community care facility, as defined in Section 1502, of a residential care facility for the elderly, as defined in Section 1569.2, or of a child day care facility, as defined in Section 1596.750, the local fire enforcing agency, as defined in Section 13244, or State Fire Marshal, whichever has primary jurisdiction, shall conduct a preinspection of the facility prior to the final fire clearance approval. At the time of the preinspection, the primary fire enforcing agency shall price consultation and interpretation of the fire safety regulations and shall notify the prospective licensee of the facility in writing of the specific fire safety regulations which shall be enforced in order to obtain fire clearance approval. A fee of not more than \$50.00 may be charged for the preinspection of a facility with a capacity to serve 25 or fewer persons. A fee of not more than \$100.00 may be charged for a preinspection of a facility with a capacity to serve 26 or more persons.

1.11.4.5 Care Facilities. The primary fire enforcing agency shall complete the final fire clearance inspection for a community care facility, residential care facility for the elderly, or child day care facility within 30 days of receipt of the request for the final inspection, or as of the date the prospective facility requests the final preclearance inspection by the State Department of Social Services, whichever is later.

Pursuant to Health and Safety Code Section 13235, a preinspection fee of not more than \$50.00 may be charged for a facility with a capacity to serve 25 or less clients. A fee of not more than \$100.00 may be charged for a preinspection of a facility with a capacity to serve 26 or more clients.

Pursuant to Health and Safety Code Section 13131.5, a reasonable final inspection fee, not to exceed the actual cost of inspection services necessary to complete a final inspection may be charged for occupancies classified as Residential Care Facilities for the Elderly (RCFE).

Pursuant to Health and Safety Code Section 1569.84, neither the State Fire Marshal nor any local public entity shall charge any fee for enforcing fire inspection regulations pursuant to state law or regulation or local ordinance, with respect to Residential Care Facilities for the Elderly (RCFE) which service six or fewer persons.

1.11.4.6 Requests of the Office of the State Fire Marshal. *Whenever a local authority having jurisdiction requests that the State Fire Marshal perform plan review and/or inspection services related to a building permit, the applicable fees for such shall be payable to the Office of the State Fire Marshal.*

1.11.5 Inspections. *Work performed subject to the provisions of this code shall comply with the inspection requirements of Title 24, Part 2, California Building Standards Code, Sections 109.1, 109.3, 109.3.4, 109.3.5, 109.3.6, 109.3.8, 109.3.9, 109.3.10, 109.5, and 109.6 as adopted by the Office of the State Fire Marshal.*

1.11.5.1 Existing Group I-1 or R Occupancies. *Licensed 24-hour care in a Group I-1 or R occupancy in existence and originally classified under previously adopted state codes shall be reinspected under the appropriate previous code, provided there is no change in the use or character which would place the facility in a different occupancy group.*

1.11.6 Certificate of Occupancy. *A Certificate of Occupancy shall be issued as specified in Title 24, Part 2, California Building Code, Section 111.*

Exception: *Group R, Division 3 and Group U occupancies.*

1.11.7 Temporary Structures and Uses. *See Title 24, Part 2, California Building Code, Section 107.*

1.11.8 Service Utilities. *See Title 24, Part 2, California Building Code, Section 112.*

1.11.9 Stop Work Order. *See Title 24, Part 2, California Building Code, Section 115.*

1.11.10 Unsafe Buildings, Structures, and Equipment. *See Title 24, Part 2, California Building Code, Section 116.*

Notation:

Authority: Health and Safety Code Sections 1250, 1569.72, 1569.78, 1568.02, 1502, 1597.44, 1597.45, 1597.46, 1597.54, 1597.65, 13108, 13108.5, 13114, 13143, 13143.2, 13143.6, 13146, 17921, 18949.2, Government Code Section 51189

References: Health and Safety Code Sections 13143, 18949.2, Government Code Sections 51176, 51177, 51178, 51179, Public Resources Code Sections 4201 through 4204

[1.2. The SFM proposes to not adopt UPC Chapter 1. (UPC Chapter 1 Administrative provisions - Sections 101 through 117 relocated to Division II of Chapter 1.)]

DIVISION II

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[2. The SFM proposes to adopt Chapter 2 without amendments.]

CHAPTER 2 DEFINITIONS

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[3. The SFM proposes to adopt Chapter 3 with the following existing amendments and California regulations.]

CHAPTER 3 GENERAL REGULATIONS

310.11 [SFM] *For applications listed in Section 1.11 regulated by the Office of the State Fire Marshal, plastic piping shall not be exposed as a portion of the interior room finish in a building or structure if the piping has a flame-spread rating exceeding 75 when tested in accordance with ASTM E 84- 77a, "Test for Surface Burning Characteristics of Building Materials."*

312.7 Fire-Resistant Construction. Piping penetrations of fire-resistance-rated walls, partitions, floors, floor/ceiling assemblies, roof/ceiling assemblies, or shaft enclosures shall be protected in accordance with the requirements of the *California Building Code* and Chapter 14, "Firestop Protection."

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[4. The SFM proposes to not adopt Chapter 4.]

CHAPTER 4 PLUMBING FIXTURES AND FIXTURE FITTINGS

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[5. The SFM proposes to adopt Chapter 5 with the following existing amendments and California regulations.]

CHAPTER 5 WATER HEATERS

507.2 Seismic Provisions. ~~In seismic design categories C, D, E, and F, water heaters shall be anchored or strapped to resist horizontal displacement due to earthquake motion. Strapping shall be at points within the upper one third and lower one third of its vertical dimensions. At the lower point, a distance of not less than 4 inches (102 mm) shall be maintained from the controls with the strapping. Water heaters shall be anchored or strapped to resist horizontal displacement due to earthquake motion. Strapping shall be at points within the upper one third (1/3) and lower one-third (1/3) of its vertical dimensions. At the lower~~

point, a minimum distance of four (4) inches (102 mm) shall be maintained above the controls with the strapping.

Note: The applicable subsection of Health and Safety Code Section 19211(a) which addresses new, replacement, and existing water heaters is repeated here for clarity and reads as follows:

Section 19211(a) Notwithstanding Section 19100, all new and replacement water heaters, and all existing residential water heaters shall be braced, anchored, or strapped to resist falling or horizontal displacement due to earthquake motion. At a minimum, any water heater shall be secured in accordance with the California Plumbing Code, or modifications made thereto by a city county, or city and county pursuant to Section 17958.5.

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[6. The SFM proposes to adopt Section 603.5.14 and Section 612 of Chapter 6 with the following existing amendments and California regulations.]

CHAPTER 6 WATER SUPPLY AND DISTRIBUTION

603.5.14 Protection from Fire Systems. ~~Except as provided under Section 603.5.14.1 and Section 603.5.14.2, potable water supplies to fire protection systems that are normally under pressure, including but not limited to standpipes and automatic sprinkler systems, except in one or two family or townhouse residential sprinkler systems, piped in materials approved for potable water distribution systems shall be protected from backpressure and back siphonage by one of the following testable devices:~~

- ~~(1) Double check valve backflow prevention assembly (DC)~~
- ~~(2) Double check detector fire protection backflow prevention assembly~~
- ~~(3) Reduced pressure principle backflow prevention assembly (RP)~~
- ~~(4) Reduced pressure detector fire protection backflow prevention assembly~~

~~Potable water supplies to fire protection systems that are not normally under pressure shall be protected from backflow and shall be in accordance with the requirements of the appropriate standards referenced in Table 1701.1.~~

Note: Fire Protection Systems has not been adopted by the State Fire Marshal. This section cannot be adopted or enforced pursuant to California Health and Safety Code 13114.7(a), which is being cited for reference. California Health and Safety Code 13114.7

(a) For the purposes of this section the following are definitions of class I and class II systems:

- (1) American Water Works Association (A.W.W.A) Manual No. M-14 class 1 – Automatic fire sprinkler systems with direct connection from public water mains only; no pumps, tanks, or reservoirs; no physical connection from other water supplies; no antifreeze or additives of any kind; and all sprinkler drains discharging to the atmosphere or other safe outlets.
- (2) American Water Works Association (A.W.W.A) Manual No. M-14 class 2 – Automatic fire sprinkler systems which are the same as class 1, except that booster pumps may be installed in the connections from the street mains.

(b) Automatic fire sprinkler systems described in subdivision (a) shall not required any backflow protection equipment at the service connection other than required by standards for those systems contained in the publication of the National Fire Protection Association entitled "Installation of Sprinkler Systems" (NFPA Pamphlet No. 13, 1980 edition)

~~**603.5.14.1 Fire Department Connection.** Where fire protection systems supplied from a potable water system include a fire department (siamese) connection that is located less than 1700 feet (518.2 m) from a nonpotable water source that is capable of being used by the fire department as a secondary water supply, the potable water supply shall be protected by one of the following:~~

- ~~(1) Reduced pressure principle backflow prevention assembly (RP)~~
- ~~(2) Reduced pressure detector fire protection backflow prevention assembly~~

~~Nonpotable water sources include fire department vehicles carrying water of questionable quality or water that is treated with antifreeze, corrosion inhibitors, or extinguishing agents.~~

~~**603.5.14.2 Chemicals.** Where antifreeze, corrosion inhibitors, or other chemicals are added to a fire protection system supplied from a potable water supply, the potable water system shall be protected by one of the following:~~

- ~~(1) Reduced pressure principle backflow prevention assembly (RP)~~
- ~~(2) Reduced pressure detector fire protection backflow prevention assembly~~

~~**603.5.14.3 Hydraulic Design.** Where a backflow device is installed in the potable water supply to a fire protection system, the hydraulic design of the system shall account for the pressure drop through the backflow device. Where such devices are retrofitted for an existing fire protection system, the hydraulics of the sprinkler system design shall be checked to verify that there will be sufficient water pressure available for satisfactory operation of the fire sprinklers.~~

612.2 Types of Systems. This section shall apply to stand-alone and multipurpose wet-pipe sprinkler systems that do not include the use of antifreeze. A multipurpose fire sprinkler system shall provide potable water to both fire sprinklers and plumbing fixtures. A stand-alone sprinkler system shall be separate and independent from the potable water distribution system. ~~A backflow preventer shall not be required to separate a stand-alone sprinkler system from the water distribution system where the sprinkler system material is in accordance with the requirements of Section 604.0.~~

612.3.1 Required Sprinkler Locations. Sprinklers shall be installed to protect all floor areas of a dwelling unit in one and two family dwellings or townhouses.

Exceptions:

- (1) Attics, crawl spaces, and normally unoccupied concealed spaces that do not contain fuel-fired appliances do not require sprinklers. In attics, crawl spaces, and normally unoccupied concealed spaces that contain fuel-fired equipment, a sprinkler shall be provided to protect the equipment; however, sprinklers shall not be required in the remainder of the space.
- (2) Clothes closets, linen closets, and pantries that do not exceed 24 square feet (2.2 m²) in area, with the smallest dimension not exceeding 3 feet (914 mm) and having wall and ceiling surfaces of gypsum board.
- (3) Bathrooms and toilet rooms that do not exceed 55 square feet (5.1 m²) in area.
- (4) Detached Garages; carports with no habitable space above; open attached exterior porches; unheated entry areas, such as mud rooms, that are adjacent to an exterior door; and similar areas.
- (5) Covered unheated projections of the building at entrances/exits provided it is not the only means of egress from the dwelling unit.
- (6) Ceiling pockets that meet the following requirements:(a) The total volume of an unprotected ceiling pocket does not exceed 100 cubic feet (2.83 m³).

- (b) The entire floor under the unprotected ceiling pocket is protected by the sprinklers at the lower ceiling elevation.
- (c) Each unprotected ceiling pocket is separated from an adjacent unprotected ceiling pocket by not less than a 10 feet (3048 mm) horizontal distance.
- (d) The interior finish of the unprotected ceiling pocket is noncombustible material.
- (e) Skylights not exceeding 32 square feet (2.97 m²).

612.3.4 Freezing Areas. The piping system shall be protected in accordance with the requirements of Chapter 3. Where sprinklers are required in areas that are subject to freezing, dry-sidewall or dry-pendent sprinklers extending from a non-freezing area into a freezing area shall be installed. Where fire sprinkler piping cannot be adequately protected against freezing, the system shall be designed and installed in accordance with NFPA 13D.

612.3.8 Backflow protection. A backflow preventer shall not be required to separate a sprinkler system from the water distribution system, provided that:

- 1. The system complies with NFPA 13D or Section R313, and
- 2. Piping material are suitable for potable water in accordance with the California Plumbing Code, and
- 3. The system does not contain antifreeze or have a fire department connection.

612.5.1 Determining System Design Flow. The sizing of the sprinkler piping system shall be based on the flow rate and pressure of each sprinkler in accordance with Section 612.5.1.1 and the number of sprinklers in accordance with Section 612.5.1.2 **612.5.1.3.**

612.5.1.3 Fire Sprinklers Attached garages, and carports with habitable space above. Attached garages, and carports with habitable space above shall be protected by fire sprinklers in accordance with this Section and Section R313. Protection shall be provided in accordance with one of the following:

- 1. Residential Sprinklers installed in accordance with their listing.
- 2. Extended Coverage sprinklers discharging water not less than their listed flow rate for Light Hazard in accordance with NFPA 13.
- 3. Quick-Response spray sprinklers at light hazard spacing in accordance with NFPA 13 designed to discharge at 0.05 gpm/ft² density (minimum).

The system demand shall be permitted to be limited to the number of sprinklers in the compartment but shall not exceed two sprinklers for hydraulic calculation purposes. Garage doors shall not be considered obstructions and shall be permitted to be ignored for placement and calculation of sprinklers.

612.5.2 Sprinkler Pipe Water Supply. The water supply for a multipurpose or stand alone sprinkler system shall be provided by the public water main, private water main, private well system, or storage tank. The water supply required shall be determined in accordance with Section 612.5.1.2 at a pressure not less than that used in accordance with Section 612.5.3. Where a water supply serves both domestic and fire sprinkler systems, 5 gpm (19 L/min) shall be added to the sprinkler system demand at the point where the systems are connected, to determine the size of common piping and the size of the total water supply requirements where no provision is made to prevent flow into the domestic water system upon operation of a sprinkler.

612.5.2.1 Water Pressure from Individual Sources. Where a dwelling unit water supply is from a tank system, a private well system, a pump, or a combination of these, the available water pressure shall be based on the minimum pressure control setting of the pump.

612.5.2.2 Required Capacity. The water supply shall have the capacity to provide the required flow rate to the sprinklers for a period of time as follows:

(1) Seven minutes for one story dwelling units less than 2000 square feet (185.81 m²) in area. For the purpose of determining the area of the dwelling unit, the area of attached garages and attached open carports, porches, balconies and patios shall not be included.

(2) Ten minutes for multi-level dwelling units and one story dwelling units not less than 2000 square feet (185.81 m²) in area. For the purpose of determining the area of the dwelling unit, the area of attached garages and attached open carports, porches, balconies, and patios shall not be included.

Where a well system, a water supply tank system, a pump, or a combination thereof is used the water supply shall serve both domestic and fire sprinkler systems. A combination of well capacity and tank storage shall be permitted to meet the capacity requirement.

Notation:

Authority: Health and Safety Code Sections 13108, 13114.7, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[7. The SFM proposes to not adopt Chapters 7 through 11 without amendment.]

**CHAPTER 7
SANITARY DRAINAGE**

**CHAPTER 8
INDIRECT WASTES**

**CHAPTER 9
VENTS**

**CHAPTER 10
TRAPS AND INTERCEPTORS**

**CHAPTER 11
STORM DRAINAGE**

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[8. The SFM proposes to adopt Chapter 12 with the following existing amendments and California regulations.]

**CHAPTER 12
FUEL PIPING**

1211.6 Electrical Connections. Electrical connections between wiring and electrically operated control devices in a piping system shall comply with the requirements of ~~NEPA-70~~ *California Electrical Code*.

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[9. The SFM proposes to adopt Chapter 13 without amendments.]

CHAPTER 13
HEALTH CARE FACILITIES AND MEDICAL GAS AND VACUUM SYSTEMS

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[10. The SFM proposes to not adopt Chapters 14 without amendments.]

CHAPTER 14
FIRESTOP PROTECTION

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[11. The SFM proposes to not adopt Chapters 15 and 16.]

CHAPTER 15
ALTERNATE WATER SOURCES FOR NONPOTABLE

CHAPTER 16
NONPOTABLE RAINWATER CATCHMENT SYSTEMS

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[12. The SFM proposes to adopt Chapter 17 without amendments]

CHAPTER 17
MANDATORY REFERENCED STANDARDS - TABLE 1701.1

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[13. The SFM proposes to not adopt Appendices A through L]

APPENDIX A
RECOMMENDED RULES FOR SIZING THE WATER SUPPLY SYSTEM

APPENDIX B
EXPLANATORY NOTES ON COMBINATION WASTE AND VENT SYSTEMS

APPENDIX C
ALTERNATE PLUMBING SYSTEMS

**APPENDIX D
SIZING STORMWATER DRAINAGE SYSTEMS**

**APPENDIX E
MANUFACTURED/MOBILE HOME PARKS AND RECREATIONAL VEHICLE PARKS**

**APPENDIX F
FIREFIGHTER BREATHING AIR REPLENISHMENT SYSTEMS**

**APPENDIX G
SIZING OF VENTING SYSTEMS**

**APPENDIX H
PRIVATE SEWAGE DISPOSAL SYSTEMS**

**APPENDIX I
INSTALLATION STANDARDS**

**Installation Standard
For
ABS BUILDING DRAIN, WASTE AND VENT PIPE AND FITTINGS
IAPMO IS 5-2006**

2.2.6 Piping Installed in Fire Resistive Construction. All piping penetrations of fire resistance rated walls, partitions, floors, floor/ ceiling assemblies, roof/ceiling assemblies, or shaft enclosures shall be protected in accordance with the requirements of the *California Building Code and IAPMO Installation Standards*, and Chapter 14 "Firestop Protection for DWV and Stormwater Applications". [UPC 313.7]

**APPENDIX J
COMBINATION OF INDOOR AND OUTDOOR COMBUSTION AND VENTILATION OPENING DESIGN**

**APPENDIX K
POTABLE RAINWATER CATCHMENT SYSTEMS**

**APPENDIX L
SUSTAINABLE PRACTICES**

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2

[14. The SFM proposes to not adopt Appendices for Useful Tables]

USEFUL TABLES

Notation:

Authority: Health and Safety Code Sections 13108, 13143, 13143.9, 13146, 17921, 18949.2

References: Health and Safety Code Sections 13143, 18949.2



Errata for 2015 Uniform Plumbing Code – 1st Printing

The following is a change that we found after the first printing of the 2015 Uniform Plumbing Code. This change may or may not apply to your code book. However, we do encourage you to check your code book with this list to ensure that all the changes are updated. Thank you.

Appendix C

Table C 304.2 Revise the fixture unit value in the table for 12 inch pipe at $\frac{1}{16}$ slope. Table shows 2900 fixture units to 3900 fixture units in accordance with ASPE Handbook.

**TABLE C 304.2
BUILDING DRAINS AND BUILDING SEWERS¹**

| DIAMETER OF PIPE (Inches) | MAXIMUM NUMBER OF DRAINAGE FIXTURE UNITS FOR SANITARY BUILDING DRAINS AND RUNOUTS FROM STACKS | | | |
|---------------------------------|---|---------------|-----------------|-----------------|
| | SLOPE (inches per foot) | | | |
| | $\frac{1}{16}$ | $\frac{1}{8}$ | $\frac{1}{4}$ | $\frac{1}{2}$ |
| 2 | | | 21 | 26 |
| 2½ | | | 24 | 31 |
| 3 | | 20 | 42 ² | 50 ² |
| 4 | | 180 | 216 | 250 |
| 5 | | 390 | 480 | 575 |
| 6 | | 700 | 840 | 1000 |
| 8 | 1400 | 1600 | 1920 | 2300 |
| 10 | 2500 | 2900 | 3500 | 4200 |
| 12 | 3900 | 4600 | 5600 | 6700 |
| 15 | 7000 | 8300 | 10 000 | 12 000 |

For SI units, 1 inch = 25 mm, 1 inch per foot = 83.3 mm/m

Notes:

¹ On-site sewers that serve more than one building shall be permitted to be sized according to the current standards and specifications of the administrative authority for public sewers.

² A maximum of two water closets or two bathroom groups, except in single-family dwellings, where a maximum of three water closets or three bathroom groups shall be permitted to be installed.

04/01/15

Chapter 17

Section 1701.1 Revise Section 1701.1 to add a solid vertical line in the margin to indicate a technical change has occurred from the 2012 UPC edition.

CHAPTER 17 REFERENCED STANDARDS

1701.0 General.

1701.1 Standards. The standards listed in Table 1701.1 are intended for use in the design, testing, and installation of materials, devices, appliances, and equipment regulated by this code.

These standards are mandatory where required by sections in this code.

Organization abbreviations referred to in Table 1701.1 are defined in a list found at the end of the table.

10/22/15

2015 **UNIFORM PLUMBING CODE**[®]

AN AMERICAN NATIONAL STANDARD
IAPMO/ANSI UPC 1 – 2015



Copyright © 2015

International Association of Plumbing and Mechanical Officials

All Rights Reserved

No part of this work may be reproduced or recorded in any form or by any means,
except as may be expressly permitted in writing by the publisher.

Twenty-Seventh Edition

First Printing, January 2015

ISSN 0733-2335

Published by the International Association of Plumbing and Mechanical Officials

4755 E. Philadelphia Street • Ontario, CA 91761-2816 – USA

Main Phone: (909) 472-4100 • Main Fax: (909) 472-4150

Important Notices and Disclaimers

The 2015 edition of the *Uniform Plumbing Code* is developed through a consensus standards development process approved by the American National Standards Institute. This process brings together volunteers representing varied viewpoints and interests to achieve consensus on plumbing issues. While the International Association of Plumbing and Mechanical Officials (IAPMO) administers the process and establishes rules to promote fairness in the development of consensus, it does not independently test, evaluate, or verify the accuracy of any information or the soundness of any judgments contained in its codes and standards.

IAPMO disclaims liability for any personal injury, property, or other damages of any nature whatsoever, whether special, indirect, consequential, or compensatory, directly or indirectly resulting from the publication, use of, or reliance on this document. IAPMO also makes no guarantee or warranty as to the accuracy or completeness of any information published herein.

In issuing and making this document available, IAPMO is not undertaking to render professional or other services for or on behalf of any person or entity. Nor is IAPMO undertaking to perform any duty owed by any person or entity to someone else. Anyone using this document should rely on his or her independent judgment or, as appropriate, seek the advice of a competent professional in determining the exercise of reasonable care in any given circumstances.

Updating IAPMO Codes

Users of IAPMO codes should be aware that IAPMO codes may be amended from time to time through the issuance of Tentative Interim Amendments or corrected by Errata. IAPMO codes consist of the current edition of the document together with any Tentative Interim Amendment and any Errata in effect.

In order to determine whether an IAPMO code has been amended through the issuance of Tentative Interim Amendments or corrected by Errata, please visit the IAPMO Group codes information pages on IAPMO's website (www.iapmo.org). The codes information pages provide a list of IAPMO codes with up-to-date, specific information including any issued Tentative Interim Amendments and Errata.

To access the codes information pages for a specific code, go to <http://codes.iapmo.org> to select from the list of IAPMO codes. For Tentative Interim Amendments, go to the standard council decisions. For Errata, select the archived revision information.

FOREWORD

Origin and Development

The advantages of a statewide adopted *Uniform Plumbing Code* are recognized throughout the industry. Disorder in the industry because of widely divergent plumbing practices and the use of many different, often conflicting, plumbing codes by local jurisdictions influenced the Western Plumbing Officials Association (now the International Association of Plumbing and Mechanical Officials [IAPMO]) to form a committee. This committee of plumbing inspectors, master and journeyman plumbers, and plumbing engineers, backed by public utility companies and the plumbing industry to create a basic plumbing document for general use. The product of this effort, the first edition of the *Uniform Plumbing Code*[™] (UPC[™]) was adopted by IAPMO in 1945. The widespread use of this code over the past five decades by jurisdictions throughout the United States and internationally is testament to its merit.

Publishing the 2003 *Uniform Plumbing Code*, is a significant milestone because it is the first time in the history of the United States, a plumbing code was developed through a true consensus process. The 2015 edition represents the most current approaches in the plumbing field and is the fifth edition developed under the ANSI consensus process. Contributions to the content of this code consists of diverse interests as consumers, enforcing authorities, installers/maintainers, labor, manufacturers, research/standards/testing laboratories, special experts, and users.

The *Uniform Plumbing Code* provides consumers with safe and sanitary plumbing systems while, at the same time, allowing latitude for innovation and new technologies. The public at large is invited and encouraged to take part in IAPMO's open consensus code development process. This code is updated every three years. The *Uniform Plumbing Code* is dedicated to all those who, in working to achieve "the ultimate plumbing code," have unselfishly devoted their time, effort, and personal funds to create and maintain this, the finest plumbing code in existence today.

The *Uniform Plumbing Code* updates every three years in revision cycles that begin twice each year that takes two years to complete.

Each revision cycle advances according to a published schedule that includes final dates for all major events and contains four basic steps as follows:

1. Public and Committee Proposal Stage;
2. Comment Stage;
3. Association Technical Meeting;
4. Council Appeals and Issuance of Code.

IAPMO develops "full consensus" codes built on a foundation of maximum participation and agreement by a broad range of interests. This philosophy has led to producing technically sound codes that promote health and safety, yet do not stifle design or development.

It is important to stress that; the process remains committed to the principles of consensus code development where consensus Technical Committees and Correlating Committees revise codes. The public and membership is offered multiple opportunities to debate, provide input and raise concerns through Amending Motions at the annual Assembly Consideration Session. Anyone may submit an appeal related to the issuance of a document through the IAPMO Standards Council.

The 2015 *Uniform Plumbing Code* is supported by the American Society of Sanitary Engineering (ASSE), the Mechanical Contractors Association of America (MCAA), the Plumbing-Heating-Cooling Contractors National Association (PHCC-NA), the United Association (UA), and the World Plumbing Council (WPC). The presence of these logos, while reflecting support, does not imply any ownership of the copyright to the UPC, which is held exclusively by IAPMO. Further, the logos of these associations indicate the support of IAPMO's open consensus process being used to develop IAPMO's codes and standards.

The addresses of the organizations are as follows:

ASSE – 18927 Hickory Creek Drive, Suite 220 • Mokena, IL 60448 • (708) 995-3019

MCAA – 1385 Piccard Drive • Rockville, MD 20850 • (301) 869-5800

PHCC-NA – PO Box 6808 • Falls Church, VA 22046 • (800) 533-7694

UA – Three Park Place • Annapolis, MD 21401 • (410) 269-2000

WPC – World Plumbing Council Secretariat, 353 Shepperton Road • East Victoria Park 6101 • Western Australia • +61 (439) 943-098

Adoption

The *Uniform Plumbing Code* is available for adoption and use by jurisdictions in the United States and Internationally. Its use within a governmental jurisdiction is accomplished through adoption by reference in accordance with applicable jurisdictional laws. At adoption, jurisdictions should insert the applicable information in bracketed words in the sample ordinance. The sample legislation for adoption of the *Uniform Plumbing Code* on page xii provides key components, regulations and resolutions.

Revision Markings

Solid vertical lines in the margins indicate a technical change from the requirements of the 2012 edition. An arrow (←) in the margin indicates where an entire section, paragraph, exception or table has been deleted, or an item in a list of items or a table has been deleted.

A double right angle (↻) in the margin indicates that the text or a table has been relocated within the code. The table found on page xiv points out the relocations in the 2015 edition of the *Uniform Plumbing Code*.

A reference in brackets [] following a section or paragraph indicates material that has been extracted from another document. This reprinted material is not the complete and official position of the source document on the referenced subject that is represented by the standard in its entirety.

Text that is extracted pursuant to IAPMO's Extract Guidelines, but outside of the regular revision process is denoted with the use of the source document in the margin. This text is not fully processed by IAPMO in accordance with ANSI's public announcement consensus requirements for an American National Standard (ANS) nor approved by ANSI's Board of Standards Review. The next revision cycle processes such text in accordance with those requirements.

FORMAT OF THE UNIFORM PLUMBING CODE

The format of the *Uniform Plumbing Code* (UPC) arranges each chapter in accordance with a specific subject matter. However, Chapter 3 is dedicated to general requirements that are applicable to every chapter. The subject matters are divided as follows:

| CHAPTERS | SUBJECTS |
|------------|---|
| 1 | Administration |
| 2 | Definitions |
| 3 | General Regulations |
| 4 | Plumbing Fixtures and Fixture Fittings |
| 5 | Water Heaters |
| 6 | Water Supply and Distribution |
| 7 | Sanitary Drainage |
| 8 | Indirect Wastes |
| 9 | Vents |
| 10 | Traps and Interceptors |
| 11 | Storm Drainage |
| 12 | Fuel Gas Piping |
| 13 | Health Care Facilities and Medical Gas and Medical Vacuum Systems |
| 14 | Firestop Protection |
| 15 | Alternate Water Sources for Nonpotable Applications |
| 16 | Nonpotable Rainwater Catchment Systems |
| 17 | Referenced Standards |
| Appendix A | Recommended Rules for Sizing the Water Supply System |
| Appendix B | Explanatory Notes on Combination Waste and Vent Systems |
| Appendix C | Alternate Plumbing Systems |
| Appendix D | Sizing Storm Water Drainage Systems |
| Appendix E | Manufactured/Mobile Home Parks and Recreational Vehicle Parks |
| Appendix F | Firefighter Breathing Air Replenishment Systems |
| Appendix G | Sizing of Venting Systems |
| Appendix H | Private Sewage Disposal Systems |
| Appendix I | Installation Standard |
| Appendix J | Combination of Indoor and Outdoor Combustion and Ventilation Opening Design |
| Appendix K | Potable Rainwater Catchment Systems |
| Appendix L | Sustainable Practices |

FORMAT OF THE UNIFORM PLUMBING CODE

The following is a summary of the scope and intent of the provisions addressed within the chapters and appendices of the *Uniform Plumbing Code*:

Chapter 1 Administration.

Chapter 1 regulates the application, enforcement, and administration of subsequent requirements of the code. As well as establishing the scope of the code, this chapter is concerned with enforcing the requirements contained in the body of the code. A plumbing code, as with any other code, is intended to be adopted as a legally enforceable document to safeguard health, safety, property and public welfare. The code cannot be effective without satisfactory provisions for its administration and enforcement. The Authority Having Jurisdiction is to review the proposed and completed work and to decide whether a plumbing system conforms to the code requirements. As a public servant, the Authority Having Jurisdiction enforces the code in an unbiased, proper manner. The design professional is responsible for the design of a safe plumbing system. The contractor is responsible for installing the system in accordance with the plans.

Chapter 2 Definitions.

To maintain consistency and encourage the use of common terminology, Chapter 2 establishes definitions to provide clarity of terms and promote the use of a common language throughout the code. Understanding definitions within the context of their application enables greater collaboration, efficiency, standardization and interpretation in applying and enforcing terms used throughout the code. Codes are technical documents, and every term can impact the meaning of the code text. Terms not defined have a normally accepted meaning.

Chapter 3 General Regulations.

Chapter 3 regulates the general requirements, not specific to other chapters, for installing plumbing systems. Many regulations are not specific plumbing requirements, but relate to the overall plumbing system. This chapter contains safety requirements for installing plumbing and also contains nonplumbing requirements for identifying pipe, pipe fittings, traps, fixtures, materials and devices used in plumbing systems. Listing or labeling method of approval, based on applicable nationally recognized standards, for the safe and proper installation of plumbing systems is essential to ensure protection of public health, safety, and welfare. The safety requirements provide protection for piping, material, and structures, with provisions for installation practices, removing stress and strain of the pipe, sleeving, and hanger support. The building's structural stability is protected by the regulations for cutting and notching of structural members.

Chapter 4 Plumbing Fixtures and Fixture Fittings.

This chapter regulates the minimum number of plumbing fixtures of a specific type and quality for each building. The fixtures must be properly installed to be usable by the individuals occupying the building. The quality and design of every fixture must conform to the applicable referenced standard. Compliance with this chapter will result in a building or structure having acceptable plumbing fixtures for the sanitary, hygienic, cleaning, washing and food preparation needs of the occupants.

Chapter 5 Water Heaters.

Chapter 5 regulates the design, approval, installation, and safety devices of fuel burning and other types of water heaters with the combustion air requirements for ventilation and dilution of flue gases for appliances installed in buildings. This chapter does not apply to direct vent appliances. In addition, this chapter regulates the design, construction, installation, maintenance of chimneys, vents and their connections to fuel burning appliances. Methods to supply combustion air may be supplied from an indoor air supply, outdoor air supply, a combination of indoor and outdoor air supply, mechanical air supply, or an engineered system. Combustion air provisions are based on the number of openings and the total opening size required based on the total energy input rating of the appliance. Acceptable air supply for combustion and ventilation is necessary for proper operation of fuel burning appliances. A shortage of combustion air can result in incomplete combustion and production of poisonous gases, such as carbon monoxide or appliance overheating. Ventilation air provides cooling for the appliance casing and internal controls. Inadequate ventilation of the space in which an appliance is installed can result in increased surrounding temperatures that stress the appliance itself or other appliances in the vicinity.

Chapter 6 Water Supply and Distribution.

Chapter 6 regulates the design, material and installation of water supply and distribution systems, including residential fire sprinklers. The water supply and distribution system is designed to achieve the correct water pressure and flow rates and

FORMAT OF THE UNIFORM PLUMBING CODE

avoid cross connections. For fixtures to perform properly, an acceptable supply of potable water is essential to their operation and use. Cross connections and backflow are ranked as the highest priority because of the long history of recognized health risks posed by cross connections, outbreaks, or cases of waterborne disease. Piping materials and components are evaluated for their possible effect on the potable water with which they are in contact. The intent is to control the potential adverse health effects produced by indirect additives, products, and materials that come in contact with potable water. When selecting materials for water supply and distribution systems, consider water pressure, water temperature, compatibility with the water supply, durability, support, and sustainability.

In addition, this chapter regulates the design, location, materials, and installation of multipurpose and stand-alone sprinkler systems that do not include the use of antifreeze. Where systems are installed as a portion of the water distribution system under the requirements of this chapter and are not provided with a fire department connection, backflow protection for the water supply system is not required.

Chapter 7 Sanitary Drainage.

This chapter regulates the design and installation of sanitary drainage systems to ensure they will work as intended. Drainage piping should not be oversized nor undersized, and constructed of approved materials to guard against fouling, deposit of solids, clogging, and with cleanouts so arranged that the pipes may be readily cleaned. The purpose of the sanitary drainage system is to remove effluent discharged from plumbing fixtures and other equipment to an approved point of disposal, such as a public sanitary system or private sewage disposal system.

The basics of a sanitary drainage system include public and private sewage disposal; selection of materials; installation of the building drain and sewer; joining methods for pipe and fittings; drainage fixture units for sizing the drainage system; sumps and ejectors; vent sizing and length of vents; and testing.

Chapter 8 Indirect Wastes.

Chapter 8 regulates indirect waste connections that are required for plumbing fixtures and plumbing appliances dealing with food preparation, dishwashing, potable liquids, and similar equipment. An indirect connection prevents sewage from backing up into a fixture or appliance, thus providing protection against potential health hazards. The waste pipe discharges through an air gap or air break into a waste receptor or standpipe. The protection in the form of an air gap is necessary when the contamination is a potential health hazard or cross connection with the potable water system. Where there is no possibility of contaminating the potable water (nonpotable discharge), the indirect waste pipe may connect in the form of an air break. This method is often preferred to prevent splashing. In addition, health care facilities and special wastes must be protected from contamination that may result from the connection to the drainage system. The waste must be treated to prevent any damage to the piping or sewage treatment process. Waste receptors are sized and designed to prevent splashing and allow for peak discharge conditions.

Chapter 9 Vents.

Chapter 9 regulates the material, design, and installation of vents. A vent system is a pipe or pipes installed in a drainage system that provide a flow of air to and from the system to ventilate it, provide a circulation of air to eliminate trap siphonage, and reduce back-pressure and vacuum surge. In addition, vents provide the rapid and silent flow of waste without exposing occupants of the building to any sewer gases. Proper installation of vents is crucial, as a telltale sign that there is a problem in the drain and vent system is related to the elevation of the horizontal portion of the venting. Venting is not limited to sanitary drainage systems. Venting methods are applicable to other drainage systems such as those for chemical waste, graywater waste, and clear water waste. Sizing the venting system is directly tied to the design of the drainage system. For example, the velocities in the drainage system and its peak flow rates affect the diameters in the venting system. Where the vertical distance between a fixture outlet and trap is excessive, velocities in the entire drainage system will be greater than those in the vent sizing table. All venting methods in this chapter are categorized as either dry vents or wet vents. Vent stacks, stack vents, branch vents, island vents, relief vents, and individual vents are dry vents. Wet vents (horizontal or vertical), circuit vents, combination drain and vents are versions of "wet venting" in which the vent is wetted by drainage flow.

Chapter 10 Traps and Interceptors.

Chapter 10 regulates the material, design, and installation of traps, interceptors, and separators. Traps are required on drainage type plumbing fixtures and must be self-scouring without interior partitions. Interceptors, on the other hand, are

designed to control what goes down a drain. Interceptors are used to keep harmful substances from entering the sanitary drainage system, such as grease, sand, oil and other materials. The retained materials need periodic removal to maintain efficiency and function of the separating device. The capacity of an interceptor is based on retention and flow rate. There are many types of interceptors that are used at beauty salons, hospitals, meat, fish or foul packaging, refineries, repair garages, gas stations, car washing facilities, various plants, factories, and processing sites. The designer of the building is responsible for locating interceptors with the expectation for the frequency of maintenance, ease of cleaning and floor space for equipment.

Chapter 11 Storm Drainage.

Chapter 11 regulates the removal of stormwater from roofs, yards, paved areas, and similar areas. The objective of storm drainage systems is to provide a conduit or channel through which runoff will be carried from a point of collection to a point of disposal; this protects the property and the public from the uncontrolled flow of runoff and ensures that drains and inlets are adequately sized to receive the volume of runoff that flows to the drains. For the purpose of system design, it's necessary to specify the duration of a selected storm. All methods used to determine volumes and peak flow use historical data. Drain location must be coordinated with the architectural design of the building. When selecting the type of roof drain to use, the roof construction and its thickness, along with the intended use of the roof, are required. Where the roof perimeter extends above the roof in such a manner that water is entrapped and causes ponding, or if any portion of the roof is designed so water can pond, secondary drainage is required. Where secondary drainage is required, scuppers, or a secondary system of roof drains and pipes, are installed to prevent the accumulation of excessive rainwater.

Chapter 12 Fuel Gas Piping.

Chapter 12 regulates the installation of gas piping in a building, structure or within the property lines of buildings up to 5 psi. Gas piping systems must supply the minimum volume of gas required by each gas appliance to perform their proper operation under working conditions without exceeding the maximum pressure specified by each manufacturer. Because of the hazards associated with fuel gas, it is important to ensure the gas system has been inspected and tested, and that it is safe to turn on the gas supply to the building.

Chapter 13 Health Care Facilities and Medical Gas and Medical Vacuum Systems.

Chapter 13 regulates the installation, inspection, testing, maintenance, performance, and safe practices for medical gas and medical vacuum systems located in health care facilities. This chapter addresses the installation and maintenance of health care fixtures, devices, and equipment. The purpose of medical gas and medical vacuum systems is to provide safe and sufficient flows at required pressures to the medical gas outlet or vacuum inlet terminals. System design and layout should allow convenient access by the medical staff to outlet and inlet terminals, valves, and equipment during patient care or emergencies, as safety is of primary concern.

Chapter 14 Firestop Protection.

Chapter 14 regulates piping penetrations of fire-resistance-rated walls, partitions, floors, floor and ceiling assemblies, roof and ceiling assemblies, or shaft enclosures through firestopping. To firestop is to create a physical barrier that impedes the spread of smoke, gases, and flames from one compartment in the building design to the next. The firestop is seen as a part that is essential to protecting the lives of people who live or work in the structure, increasing the chances of not succumbing to smoke or gases before they are able to evacuate the building. Fireproofing of this type helps to restore the fire-resistant properties of the building materials before the openings were created as part of the construction process.

Chapter 15 Alternate Water Sources for Nonpotable Applications.

Chapter 15 regulates gray water sources, reclaimed (recycled) water sources and on-site treated nonpotable water systems. Water sources include subsurface irrigation, subsoil irrigation, and mulch basin systems. Subsoil water irrigation provides a means to disperse shallow drip irrigation lines and mulch basins that collect and spread water in various applications. The reclaimed water provisions to on-site nonpotable water systems include gray water and other nonpotable water sources that are used for on-site applications. Water reuse is integral to sustainable water management because it allows water to remain in the environment and be preserved for future use while meeting the water requirements of the present. Water reuse reduces energy use by removing added potable water treatment, offsetting water demands, and providing water for energy production.

FORMAT OF THE UNIFORM PLUMBING CODE

Chapter 16 Nonpotable Rainwater Catchment Systems.

Chapter 16 regulates nonpotable rainwater catchment systems that include irrigation; toilet and urinal flushing with proper treatment; provisions where permits are required; maintenance of alternate water sources; and minimum water quality. This chapter provides guidance on how to optimize rainwater use while ensuring there is a decrease of risk to consumers from poor design, installation, and maintenance. Rainwater harvesting is the process of capturing, channeling, and storing water runoff for later use. Most systems are constructed of three principal components: the catchment area, the collection device, and the conveyance system.

Chapter 17 Referenced Standards.

Chapter 17 provides a comprehensive list of referenced standards. Referenced standards set forth specific details of accepted practices, materials specifications, or test methods in many specialized applications. Standards provide an efficient method of conveying complex information and specifications on the performance requirements for materials, products, systems, application, and installation. The manner and purpose for a standard's use and, in turn, code compliance, must be definitive in all references to the standard. If the standard is intended to be a requirement for judging code compliance, the code must state its intent for use. The standard should adequately address a defined need and at the same time specify the minimum performance requirements, technical characteristics and methods of testing, and required test results.

The referenced standards table is organized in a manner that makes it easy to find specific standards in alphabetical order, and by acronym of the publishing agency of the standard. The table lists the title of the standard, the edition, any addenda, and the section or sections of the code that reference the standard. Contact information for each publishing agency is provided at the end of the chapter.

Appendix A Recommended Rules for Sizing the Water Supply System.

Appendix A provides a method of sizing the water supply and distribution system that provides precise calculations to establish the proper pressures and flow to the system's fixtures. The goal of sizing the system is to deliver an acceptable volume of water to the most hydraulically remote fixture during minimum pressure and maximum flow conditions; provide satisfactory water pressure to the most hydraulically remote fixture during minimum pressure and maximum flow conditions; and to prevent excessive water velocity during maximum flow conditions.

Appendix B Explanatory Notes on Combination Waste and Vent Systems.

Appendix B contains general guidelines for the design and installation of combination waste and vent systems. These systems are designed for waste piping and are purposely oversized to serve as both a waste and vent pipe to avoid excessive pneumatic effects at fixture drains.

Appendix C Alternate Plumbing Systems.

The intent of this appendix is to provide clarification of procedures for the design and approval of engineered plumbing systems, alternate materials, and equipment that are not specifically covered in other parts of the code. Alternative methods are allowed to be used where approved by the authority having jurisdiction. Approval of alternatives is based on a demonstration showing that the method or material used is at least equivalent in strength, deflection, and capacity to that provided by the prescriptive methods and materials.

Appendix D Sizing Storm Water Drainage Systems.

Appendix D provides general guidelines for the sizing of stormwater drainage systems. There are two pieces of information that must always be a given. They are the roof size and the rate of rainfall for the area.

Appendix E Manufactured/Mobile Home Parks and Recreational Vehicle Parks.

The provisions of this appendix apply to the plumbing and drainage systems of mobile home and recreational vehicle parks. These provisions also apply to the use, maintenance, and installation for supplying fuel gas, water, electricity, and disposal of sewage from accessory buildings or structures, and building components.

Appendix F Firefighter Breathing Air Replenishment Systems.

Appendix F provides guidance on installing firefighter breathing air replenishment systems. System components include outside fire department connection panel, interior air fill panel or station, interconnected piping distribution system and pressure monitoring switch. Fire departments access the system through an outside connection panel and are able to pump air into the system. The firefighters inside the structure access the system at fill stations that are found throughout the building. The piping distribution system is made from stainless tubing or other approved materials. It delivers compressed air to the building interior air fill stations and interior air fill panels. The tubing also acts as a conduit in the interior of the building between the outside connection panel and the air storage system. If the system becomes over-pressurized, the air monitoring system also acts as a pressure relief. A system isolation valve is placed alongside each interior air fill station and interior air fill panel to isolate the system.

Appendix G Sizing of Venting Systems.

Appendix G provides added information on the sizing of gas vents. This appendix is useful to the end user for the proper sizing of venting systems. A series of examples are given that show how to use the tables and other requirements of Chapter 5.

Appendix H Private Sewage Disposal Systems.

Appendix H provides general guidelines for the materials, design, and installation of new or existing private sewage disposal systems. Where a building cannot be served by a public sewer system, the building site must be provided with a system for treating the waste water generated from the use of plumbing fixtures in the building. The appendix addresses site evaluations, materials, soil absorption systems, holding tanks, cesspools and on-site waste-water treatment systems. Private sewage disposal systems must be designed based on the soil conditions, constructed using approved materials, and installed according to prescribed dimensions.

Appendix I Installation Standard for PEX Tubing Systems for Hot- and Cold-Water Distribution.

The installation standard provides guidelines for SDR 9 crosslinked polyethylene (PEX) tubing and fittings intended for hot- and cold-water distribution systems. Provisions include joining methods, clearances, sizing and flow velocities, handling, storage, exposure to heat and chemicals, and thermal expansion and contraction.

Appendix J Combination of Indoor and Outdoor Combustion and Ventilation Opening Design.

Appendix J provides an example of how to determine the required combination of indoor and outdoor combustion air opening sizes for appliances. The combustion air example also provides a table that contains the required volume of a space per the appliance BTU/h input that is based on the standard method.

Appendix K Potable Rainwater Catchment Systems.

Potable rainwater catchment system is defined as a system that uses the principal of collecting and using rain from a rooftop or other man-made, aboveground collection surface. This appendix applies to new rainwater catchment installations, as well as changes, additions, maintenance, and repairs to existing installations. Rainwater harvesting is the practice of collecting the water produced during rainfall events before it has a chance to run off into a river or stream or soak into the ground and become groundwater.

Appendix L Sustainable Practices.

This appendix provides a comprehensive set of technically sound provisions that encourage sustainable practices and works toward improving the design and construction of plumbing systems that result in a positive long-term environmental impact. Environmental sustainability is important because it involves natural resources that human beings need for economic or manufactured capital. Their sustainability is defined by their reliance on infinitely available resources that are naturally occurring, constant, and free to access.

SAMPLE LEGISLATION FOR ADOPTION OF THE UNIFORM PLUMBING CODE

The Uniform Codes are designed to be adopted by jurisdictions through an ordinance. Jurisdictions wishing to adopt the 2015 *Uniform Plumbing Code* as an enforceable regulation governing plumbing systems by reference should ensure the legal basis under which adoption and implementation are included in the ordinance.

The following sample ordinance is a guide for drafting an ordinance for adoption that addresses key components regulations and resolutions.

ORDINANCE NO.

An ordinance of the [JURISDICTION] adopting the 2015 edition of the *Uniform Plumbing Code*, regulating and controlling the design, construction, quality of materials, erection, installation, alteration, repair, location, relocation, replacement, addition to, use or maintenance of plumbing systems in the [JURISDICTION]; providing for the issuance of permits and collection of fees therefor; repealing Ordinance No. of the [JURISDICTION] and all other ordinances and parts of the ordinances in conflict therewith.

The [GOVERNING BODY] of the [JURISDICTION] does ordain as follows:

Section 1 Codes Adopted by Reference. That certain documents, three (3) copies of which are on file in the office of the [JURISDICTION'S KEEPER OF RECORDS] and the [JURISDICTION], being marked and designated as the 2015 *Uniform Plumbing Code*, including Appendix Chapters [FILL IN THE APPENDIX CHAPTERS BEING ADOPTED], as published by the International Association of Plumbing and Mechanical Officials, be and is hereby adopted as the Code of the [JURISDICTION], in the State of [STATE NAME] regulating and controlling the design, construction, quality of materials, erection, installation, alteration, repair, location, relocation, replacement, addition to, use or maintenance of plumbing systems as herein provided; providing for the issuance of permits and collection of fees therefor; and each and all of the regulations, provisions, penalties, conditions and terms of such 2015 *Uniform Plumbing Code* on file in the office of the [JURISDICTION] are hereby referred to, adopted, and made a part hereof, as if fully set out in this ordinance.

Section 2 Modifications. The following sections are hereby revised:

Section 101.1. Insert: [NAME OF JURISDICTION]

Section 104.5. Insert: [APPROPRIATE FEE SCHEDULE]

Section 3 Conflicting Ordinances Repealed. That Ordinance No. of [JURISDICTION] entitled [TITLE OF THE ORDINANCE OR ORDINANCES IN EFFECT AT THE PRESENT TIME SO THAT THEY WILL BE REPEALED BY MENTION] and all other ordinances or parts of ordinances in conflict herewith are hereby repealed.

Section 4 Severability. That if any section, subsection, sentence, clause or phrase of this ordinance is, for any reason, held to be unconstitutional, such decision shall not affect the validity of the remaining portions of this ordinance. The [GOVERNING BODY] hereby declares that it would have passed this ordinance, and each section, subsection, clause or phrase thereof, irrespective of the fact that any one or more sections, subsections, sentences, clauses and phrases be declared unconstitutional.

Section 5 Legal Notice. That the [JURISDICTION'S KEEPER OF RECORDS] is hereby ordered and directed to cause this ordinance to be published. (An additional provision may be required to direct the number of times the ordinance is to be published and to specify that it is to be in a newspaper in general circulation. Posting may also be required.)

Section 6 Violations and Penalties. [INCORPORATE PENALTIES FOR VIOLATIONS]

Section 7 Effective Date. That this ordinance and the rules, regulations, provisions, requirements, orders and matters established and adopted hereby shall take effect and be in full force and effect [TIME PERIOD] from and after the date of its final passage and adoption.

COMMITTEE ON UNIFORM PLUMBING CODE

These lists represent the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred.

IAPMO Standards Council

Linden Raimer, *Chairman*

Raimer Consulting Services, LLC, [U]

Tim Brink, Mechanical Contractors Association of Eastern PA [I/M]

Rex Crawford, City of Lincoln [E]

Carl Crimmins, MN State Pipe Trades [SE]

James Majerowicz, UA Instructor [L]

Rich Prospal, ASSE [C]

Ron Rice, City of St. Paul [C]

Bob Siemsen, City of Lincoln [E]

Kevin Tindall, Tindall & Ranson Plumbing, Heating & A/C, Inc. [I/M]

Nonvoting

Gabriella M. Davis, Secretary

International Association of Plumbing and Mechanical Officials

Lynne Simnick, Recording Secretary

International Association of Plumbing and Mechanical Officials

IAPMO Uniform Plumbing Code Technical Committee

Tim Collings, *Chairman*

Salt Lake City, Utah [E]

Bob Adler, City of San Jose, California [E]

Sarah Aguilar, Southland Industries [I/M]

Julius Ballanco, American Society of Plumbing Engineers [SE]

DJ Berger, Plumbers and Steamfitters [L]

Sylvanus Bloice, Roots Plumbing Services [I/M]

Jeremy Brown, NSF International [R/S/T]

Dan Buuck, National Association of Home Builders [U]

Paul Cabot, American Gas Association [U]

Phil Campbell, United Association [L]

Maggie Carroll, Underwriters Laboratories [R/S/T]

Ian Chang, Intertek Testing Services [R/S/T]

Richard Church, Plastic Pipe and Fittings Association [M]

Bill Erickson, MCAA [I/M]

Pennie Feehan, Copper Development Association [M]

John Fischer, Self [C]

William LeVan, Cast Iron Soil Pipe Institute [M]

David L. Mann, CA Pipe Trades Council [L]

John Nielsen, State of Idaho - Div. of Building Safety [E]

Thomas Pape, Alliance for Water Efficiency (AWE) [C]

Phil Ribbs, PHR Consultants [SE]

Arnold Rodio, Jr., Pace Setter Plumbing [I/M]

Martin "Mo" Salberg, Plumbers, Steamfitters and Refrigeration Fitters UA Local 393 [L]

Anthony Scarano, Plastics Piping Consultant [SE]

Steve Silber, ASSE [R/S/T]

Larry Soskin, Ace Duraflo [I/M]

Jim Stack, Plumbing-Heating-Cooling Contractors National Association [I/M]

Amir Tabakh, City of Los Angeles - Department of Water and Power [E]

April Trafton, Donald Dickerson Associates [SE]

Alternates

Mark Casey, City of Los Angeles - Department of Building and Safety [E]

Carl Cimino, Pipe Trades Training Center [L]

Michael Cudahy, Plastic Pipe & Fittings Association [M]

Rickey Fabra, Plumbers & Steamfitters [L]

James Galvin, Plumbing Manufacturers International [M]

Cai Owens, National Association of Home Builders [U]

Steven Panelli, City & County of San Francisco, California [E]

James Pavesic, United Association [L]

Leonard Ramociotti, LAR Consulting [SE]

Arnold Rodio, Sr., Pace Setter Plumbing [I/M]

Chris Salazar, NSF International, [R/S/T]

Billy Smith, American Society of Plumbing Engineers [SE]

Don Summers, ASSE [R/S/T]

Che Timmons, Local 342 [L]

James Walls, Cast Iron Soil Pipe Institute [M]

Nonvoting

Denise Beach, NFPA [R/S/T]

Gary Hile, Ex -Officio IAPMO [E]

Enrique Gonzalez, IAPMO Staff Liaison

COMMITTEE MEMBERSHIP CLASSIFICATION ABBREVIATIONS

These classifications apply to Technical Committee members and represent their principal interest in the activity of a committee.

- M** *Manufacturer*: A representative of a maker or marketer of a product, assembly or system, or portion thereof, that is affected by the standard.
- U** *User*: A representative of an entity that is subject to the provisions of the standard or that voluntarily uses the standard.
- I/M** *Installer/Maintainer*: A representative of an entity that is in the business of installing or maintaining a product, assembly or system affected by the standard.
- L** *Labor*: A labor representative or employee concerned with safety in the workplace.
- R/S/T** *Research/Standards/Testing Laboratory*: A representative of an independent research organization; an organization that develops codes, standards or other similar documents; or an independent testing laboratory.
- E** *Enforcing Authority*: A representative or an agency or an organization that promulgates and/or enforces standards.
- C** *Consumer*: A person who is, or represents, the ultimate purchaser of a product, system, or service affected by the standard, but who is not included in the *User* classification.
- SE** *Special Expert*: A person not representing any of the previous classifications, but who has special expertise in the scope of the standard or portion thereof.

SECTION RELOCATION

| 2015 Location | 2012 Location |
|-------------------|----------------------|
| 102.1 | 101.4 |
| 103.3 | 101.5 |
| 102.4 | 101.6, 101.11 |
| 102.4.1, 102.4.2 | 101.6.1, 101.6.2 |
| 102.3 | 101.7, 101.11.4 |
| 102.8 | 101.10 |
| 102.4 | 101.11 |
| 102.5 | 101.11.1 |
| 102.2 | 101.11.2 |
| 102.6 | 101.11.3 |
| 102.3 | 101.11.4 |
| 103.0, 103.1 | 102.0 – 102.2 |
| 103.4 | 102.2.1 |
| 106.4 – 106.6 | 102.2.2 – 102.2.4 |
| 103.2 | 102.2.5 |
| 107.0 – 107.2 | 102.3, 102.3.1 |
| 106.0, 106.1 | 102.4 |
| 106.3 | 102.5 |
| 104.0 – 104.2 | 103.0 – 103.1.1 |
| 103.3.1 | 103.1.2 |
| 104.3, 104.3.1 | 103.2, 103.2.1 |
| 104.4, 104.4.1 | 103.3 |
| 104.4.6 | 103.3.1 |
| 104.4.2 – 104.4.5 | 103.3.2 – 103.3.4 |
| 104.5 | 103.4 |
| Table 104.5 | Table 103.4 |
| 104.3.2, 104.3.3 | 103.4.1, 103.4.2 |
| 104.5.1, 104.5.2 | 103.4.3, 103.4.3.1 |
| 104.5.3 | 103.4.4 – 103.4.4.2 |
| 105.0, 105.1 | 103.5 |
| 105.2.1.1 | 103.5.1 |
| 105.2 | 103.5.2 |
| 105.2.1.2 | 103.5.3 |
| 105.2.1 | 103.5.4, 103.5.5 |
| 105.3 | 103.5.6 – 103.5.6.4 |
| 105.2.3 – 105.2.5 | 103.5.7 – 103.5.7.2 |
| 105.2.2 | 103.5.8 |
| 105.3.1 | 103.5.8.1 |
| 102.7 | 103.5.8.2 |
| 105.2.6 | 103.5.9 |
| 106.2 | 103.5.9.1 |
| 105.3.2, 105.3.3 | 103.5.9.2, 103.5.9.3 |
| 105.4 | 103.6 – 103.6.2 |

| 2015 Location | 2012 Location |
|---------------------|---------------------|
| 101.4, 101.5 | 103.7, 103.8 |
| 301.2 – 301.2.2 | 301.1 – 301.1.2 |
| 301.2.5 – 301.5.6 | 301.1.3 – 301.4.6 |
| 313.3 – 313.5 | 313.1 – 313.3 |
| Table 313.3 | Table 313.1 |
| 313.2 | 313.4 |
| 313.1 | 313.5 |
| 401.2 | 401.1 |
| 403.0, 403.1 | 402.7 |
| 402.7 – 402.11 | 402.8 – 402.12 |
| 411.2 | 403.2 |
| 412.1, 412.1.1 | 403.3, 403.3.1 |
| 407.2.2 | 403.4 |
| 420.3 | 403.5 |
| 405.0 – 405.3 | 406.0 – 406.3 |
| 406.0 – 406.4 | 407.0 – 407.4 |
| 408.7.5 | 408.7.1 |
| 411.3 | 411.2 – 411.2.2 |
| 412.2 | 412.1 |
| 413.1, 413.2 | 413.2, 413.3 |
| 420.4 | 420.3 |
| 403.2 | 421.0, 421.1 |
| 407.3 | 421.2 |
| 507.3 | 507.1.1 |
| 507.3.1 – 507.5 | 507.2.1 – 507.4 |
| 509.6.2.5 | 509.6 |
| 509.6.3.2 | 509.6.1 |
| 509.6.1 | 509.6.1.1 |
| 509.6.2.6 | 509.6.2.5 |
| 509.6.3.3 | 509.6.3.2 |
| Table 509.10.1.3 | Table 509.10.1 |
| Table 509.10.1.4 | Table 509.10.1(1) |
| 601.2 – 601.3.5 | 601.1 – 601.2.4 |
| Table 601.3.2 | Table 601.2.2 |
| 603.5.13 – 603.5.20 | 603.5.14 – 603.5.21 |
| 604.3 – 604.11 | 604.2 – 604.10 |
| 605.1 – 605.2.3 | 605.3 – 605.4.3 |
| 605.4 – 605.16.3 | 605.5 – 605.17.3 |
| 701.2 – 701.3.3 | 701.1 – 701.2.3 |
| Table 701.2 | Table 701.1 |
| 701.5 – 701.7 | 701.3 – 701.5 |
| Table 701.6 | Table 701.4 |
| Table 701.7 | Table 701.5 |
| 705.2 – 705.9.4 | 705.4 – 705.11.4 |

SECTION RELOCATION

| 2015 Location | 2012 Location |
|-----------------------|-------------------------|
| 801.2 – 801.7 | 801.1 – 801.6 |
| 803.3 | 803.1 |
| 807.2, 807.3 | 807.3, 807.4 |
| Table 814.3 | Table 814.1 |
| 814.3 | 814.2 |
| 814.5 | 814.3 |
| 901.2, 901.3 | 901.1, 901.2 |
| 903.2 – 903.2.3 | 903.2.1 – 903.2.4 |
| 912.0 – 912.2 | 911.0 – 911.2 |
| 1001.2 | 1001.1 |
| 1015.2 – 1015.4 | 1015.3 – 1015.5 |
| 1101.2 – 1101.4 | 1101.1 – 1101.3 |
| 1101.5 – 1101.14 | 1101.4 – 1101.13 |
| Table 1101.8 | Table 1101.7 |
| Table 1101.12 | Table 1101.11 |
| 1101.4.2 | 1102.1, 1102.1.1 |
| 1101.4.3 – 1101.4.6 | 1102.2 – 1102.5 |
| Table 1101.4.6 | Table 1102.5 |
| 1101.15 – 1101.15.3 | 1103.0 – 1103.4 |
| 1101.16 | 1104.0, 1104.1 |
| 1101.16.1, 1101.16.2 | 1104.2, 1104.3 |
| 1102.0 | 1105.0 |
| 1102.3 – 1102.3.2 | 1105.4 – 1105.4.2 |
| 1103.0 – 1106.2.3 | 1106.0 – 1109.2.3 |
| Table 1103.3 | Table 1106.3 |
| Table 1105.1(1) | Table 1108.1(2) |
| Table 1105.1(2) | Table 1108.1(8) |
| 1202.0 – 1202.3 | 1201.0 – 1201.3 |
| 1201.0 – 1201.1 | 1202.0 – 1202.1 |
| 1208.3, 1208.3.1 | 1208.3.1, 1208.3.2 |
| 1208.5.2 – 1208.5.2.3 | 1208.5.2.1 – 1208.5.2.4 |
| 1208.7.5 – 1208.7.9 | 1208.7.5.1 – 1208.7.7 |
| 1210.8 – 1210.8.2 | 1210.8.1 – 1210.8.3 |
| 1211.0 – 1211.6.1 | 1210.15 – 1210.17.1 |
| 1212.0, 1212.1 | 1211.0, 1211.1 |
| 1212.2 – 1212.3.2 | 1211.2 – 1211.3.2 |
| 1212.4 | 1211.4, 1211.4.1 |
| 1212.4.1 – 1212.9 | 1211.4.2 – 1211.9 |
| 1212.10 | 1212.0, 1212.1 |
| 1301.5 | 1301.1 |
| 1301.1 | 1301.2 |
| 1304.0 – 1304.2 | 1302.0 – 1302.2 |
| 1306.1 – 1306.2.1 | 1302.3 – 1302.5 |
| 1310.3.1 | 1303.2 |

| 2015 Location | 2012 Location |
|-----------------------------|-----------------------------|
| 1303.2 | 1304.0, 1304.1 |
| 1303.3 | 1305.0, 1305.1 |
| 1303.4, 1303.4.1 | 1306.0 – 1306.2 |
| 1303.4.2 | 1307.0, 1307.1 |
| 1303.5 | 1308.0, 1308.1 |
| 1301.4 | 1309.3 |
| 1301.2, 1301.3 | 1309.5, 1309.6 |
| 1301.6 | 1309.7 |
| 1313.1.1 | 1310.1.2 |
| 1304.4 | 1310.2 |
| 1304.3 | 1310.4 |
| 1306.3 | 1310.5 |
| 1307.0 – 1307.7 | 1310.6 – 1310.6.6 |
| 1304.5 – 1304.5.3 | 1311.1 – 1311.4 |
| 1305.0 – 1305.3 | 1312.0 – 1312.3 |
| Table 1305.1 – Table 1305.3 | Table 1312.1 – Table 1312.3 |
| 1310.2.1 | 1313.1 |
| Table 1310.2.1(1) | Table 1313.1 |
| 1310.2.2 | 1313.2 |
| 1310.2.3 | 1313.3 |
| 1308.0 – 1308.4 | 1315.0 – 1315.4 |
| 1309.2.1 | 1315.5.2 |
| 1309.4 | 1315.6 |
| 1309.6 | 1315.7 |
| 1309.4.3 | 1315.7.1 |
| 1312.1 | 1315.8 |
| 1311.0 – 1311.2 | 1316.0 – 1316.2 |
| 1310.0 | 1317.0 |
| 1310.3 | 1317.1 |
| 1310.4 | 1317.2 |
| 1310.3.3 | 1317.3 |
| 1310.6 – 1310.6.8 | 1317.4 |
| 1310.7, 1310.7.1 | 1317.5 |
| 1310.9, 1310.9.1 | 1317.6 |
| 1310.5 – 1310.5.4 | 1317.7 |
| Table 1310.5.4(1) | Table 1317.7 |
| 1310.5.5 | 1317.8 |
| 1310.8, 1310.8.1 | 1317.9 |
| 1309.0, 1309.1 | 1318.0, 1318.1 |
| 1309.3 | 1318.2 |
| 1309.3.5 – 1309.3.5.2 | 1318.3 |
| 1309.3.6 – 1309.3.6.9 | 1318.4 |
| 1309.3.7 – 1309.3.7.4 | 1318.5 |

SECTION RELOCATION

| 2015 Location | 2012 Location |
|-------------------------|--------------------|
| 1309.3.9, 1309.3.9.1 | 1318.6 |
| 1309.3.8 – 1309.3.8.10 | 1318.7 |
| 1309.3.10 – 1309.3.10.4 | 1318.8 |
| 1312.0 | 1319.0 |
| 1312.1.2 | 1319.1 |
| 1312.7 – 1312.8.1 | 1319.2 – 1319.3.2 |
| 1312.6.4, 1312.6.4.1 | 1319.3.3, 1319.3.4 |
| 1312.2 – 1312.4 | 1319.4 – 1319.6 |
| 1312.6 – 1312.6.2 | 1319.7 – 1319.7.2 |
| 1312.5.1 | 1319.8, 1319.8.1 |
| 1312.5 | 1319.8.2 |
| 1316.0, 1316.1 | 1320.0, 1320.1 |
| 1313.1.2 | 1320.2 |
| 1316.2 – 1316.3 | 1320.2.1 – 1320.3 |
| 1317.0, 1317.1 | 1321.0, 1321.1 |
| 1317.3 | 1321.2 |
| 1310.11 – 1310.11.2 | 1322.0 – 1322.2 |
| 1312.9 | 1322.3 |
| 1317.4 | 1322.4 |
| 1312.9.2 | 1322.5 |
| 1318.0, 1318.1 | 1323.0, 1323.1 |
| 1318.3 | 1323.2 |
| 1314.0 – 1314.1.1 | 1324.0 – 1324.2 |
| 1314.1.3.1 | 1324.3 |
| 1314.1.4 | 1324.4 |
| 1303.6 | 1324.5 |
| 1314.2.1 | 1324.6 |
| 1314.2 | 1324.7 |
| 1315.0 – 1315.3 | 1325.0 – 1325.2.1 |
| 1315.5 | 1325.3 |
| 1315.5.4 | 1325.3.1 |
| 1315.4 | 1325.4 |
| 1319.0, 1319.1 | 1326.0, 1326.1 |
| 1319.2 | 1326.2, 1326.2.1 |
| 1319.6 – 1319.6.4 | 1326.8 |
| 1319.7 – 1319.7.4 | 1326.9 |
| 1319.5 – 1319.5.3 | 1326.10 |
| 1319.8 | 1326.11 |
| 1320.0, 1320.1 | 1327.0, 1327.1 |
| 1319.12 – 1319.12.2 | 1327.1.1 |
| 1320.2 | 1327.2 |
| 1319.3 | 1327.3 |
| 1320.3 | 1327.4 |

| 2015 Location | 2012 Location |
|--|---------------------------------|
| 1701.0, 1701.1 | 1401.0, 1401.1 |
| Table 1701.1 | Table 1401.1 |
| 1401.0 – 1406.4 | 1501.0 – 1506.4 |
| 1501.0 – 1501.9 | 1601.0 – 1601.9 |
| Table 1501.5 | Table 1601.5 |
| 1502.0, 1502.1 | 1602.0, 1602.1 |
| 1502.2 | 1602.2, 1602.2.1 |
| 1502.2.1 – 1503.8 | 1602.2.2 – 1603.8 |
| Table 1502.4 | Table 1602.4 |
| Table 1502.10, Table 1502.11 | Table 1602.10, Table 1602.11 |
| Table 1502.11.3 | Table 1602.11.3 |
| Figure 1503.9 | Figure 1603.9 |
| 1503.9 – 1503.12 | 1603.9.1 – 1603.10 |
| 1503.13 | 1603.11 |
| 1504.0 – 1504.11 | 1604.0 – 1604.11 |
| 1504.12 | 1604.12 |
| 1601.0, 1601.1 | 1701.0, 1701.1 |
| 1602.0 – 1602.11.2.4 | 1702.0 – 1702.11.2.4 |
| Figure 1602.9 | Figure 1702.9 |
| A 102.0 – A 108.1 | A 1.0 – A 7.1 |
| Table A 103.1 | Table A 2.1 |
| Chart A 103.1(1), Chart A 103.1(2) | Chart A 2.1, Chart A 2.1(1) |
| Table A 104.4 | Table A 3.4 |
| Chart A 105.1(1) – Chart A 105.1(4) | Chart A 4.1 – Chart A 4.1(3) |
| B 101.2 – B 101.6.1 | B 1.0 – B 5.1 |
| C 301.0 | C 2.0 |
| C 201.0 | C 2.1 |
| C 301.1, C 301.2 | C 2.2, C 2.3 |
| C 302.0 – C 303.3 | C 3.0 – C 4.3 |
| Table C 303.1(1), Table C 303.1(2) | Table C 4.1, Table C 4.1(1) |
| C 304.0 | C 5.0 |
| C 304.1 – C 501.9 | C 5.2 – C 7.9 |
| Table C 304.2 | Table C 5.3 |
| Table C 304.3 | Table C 5.4 |
| Table C 401.1 | Table C 6.1 |
| 911.0 – 911.5 | C 8.0 – C 8.5 |
| C 601.0 – C 601.3 | C 9.0 – C 9.3 |
| C 601.4 | C 9.4, C 9.4.1 |
| C 601.4.1 – C 601.9 | C 9.4.2 – C 9.9 |
| Table C 601.2 | Table C 9.2 |
| E 101.2 | E 2.0 |

SECTION RELOCATION

| 2015 Location | 2012 Location |
|---|--------------------------------------|
| E 102.0 – E 401.3 | E 3.0 – E 23.3 |
| Table E 203.1(1), Table E 203.1(2) | Table E 6.1, Table E 6.1(1) |
| E 402.0 | E 24.0 |
| E 402.1 – E 404.3 | E 24.1.1 – E 26.3 |
| E 405.0 – E 501.1 | E 28.0 – E 39.1 |
| Table E 407.1 | Table E 30.1 |
| E 601.0 – E 1201.1 | E 41.0 – E 78.1 |
| Table E 903.1 | Table E 68.1 |
| E 401.4 | E 79.0, E 79.1 |
| G 101.2 | G 1.0 |
| Figure G 101.2(1) – Figure G 101.2(14) | Figure G 1.0(a) – Figure G 1.0(n) |
| G 101.3 – G 101.9 | G 1.1 – G 2.4 |
| Figure G 101.3 – Figure G 101.6 | Figure G 1.1 – Figure G 2.2 |
| Table G 101.8 | Table G 2.3 |
| H 101.2 – H 101.11 | H 1.1 – H 1.10 |
| J 101.2 | J 1.1 |
| Table J 101.2 | Table J 1.1 |
| K 104.4.1 | K 103.3 |
| K 104.4.2 – K 104.4.6 | K 104.4.1 – K 104.4.5 |
| L 402.5 – L 402.5.2.2 | L 402.4 – L 402.4.2.2 |
| L 402.6, L 402.6.1 | L 402.5.1, L 402.5.2 |
| L 406.0 – L 407.3 | L 403.0 – L 404.3 |
| L 409.0, L 409.1 | L 405.0, L 405.1 |
| L 504.4.1 | L 503.3 |
| L 504.4.2 – L 504.4.3.1 | L 504.4.1 – L 504.4.2.1 |
| L 504.4.4 – L 504.4.6 | L 504.4.3.1 – L 504.4.5 |
| L 603.1.1 – L 603.3.2 | L 603.2.1 – L 603.4.2 |
| Table L 603.3.2 | Table L 603.4.2 |
| L 603.3.4, L 603.3.4.1 | L 603.4.4, L 603.4.4.1 |
| L 603.3.4.2 | L 603.4.4.4 |
| L 603.3.5, L 603.3.5.1 | L 603.4.5, L 603.4.5.1 |
| L 603.3.5.2 | L 603.4.5.3 |
| L 603.3.6 – L 603.4.2 | L 603.4.6 – L 603.5.2 |
| L 603.4.3 – L 603.5 | L 603.5.3 – L 603.6 |

TABLE OF CONTENTS

| | | | |
|------------------|--|------------------|--|
| CHAPTER 1 | ADMINISTRATION1 | CHAPTER 2 | DEFINITIONS9 |
| 101.0 | General1 | 201.0 | General9 |
| 101.1 | Title1 | 201.1 | Applicability9 |
| 101.2 | Scope1 | 202.0 | Definition of Terms9 |
| 101.3 | Purpose1 | 202.1 | General9 |
| 101.4 | Unconstitutional1 | | |
| 101.5 | Validity1 | CHAPTER 3 | GENERAL REGULATIONS21 |
| 102.0 | Applicability1 | 301.0 | General21 |
| 102.1 | Conflicts Between Codes1 | 301.1 | Applicability21 |
| 102.2 | Existing Installations1 | 301.2 | Minimum Standards21 |
| 102.3 | Maintenance1 | 301.3 | Alternate Materials and Methods of Construction Equivalency21 |
| 102.4 | Additions, Alterations, Renovations, or Repairs1 | 301.4 | Flood Hazard Areas21 |
| 102.5 | Health and Safety1 | 301.5 | Alternative Engineered Design22 |
| 102.6 | Changes in Building Occupancy1 | 302.0 | Iron Pipe Size (IPS) Pipe22 |
| 102.7 | Moved Structures1 | 302.1 | General22 |
| 102.8 | Appendices1 | 303.0 | Disposal of Liquid Waste22 |
| 103.0 | Duties and Powers of the Authority Having Jurisdiction2 | 303.1 | General22 |
| 103.1 | General2 | 304.0 | Connections to Plumbing System Required22 |
| 103.2 | Liability2 | 304.1 | General22 |
| 103.3 | Applications and Permits2 | 305.0 | Damage to Drainage System or Public Sewer22 |
| 103.4 | Right of Entry2 | 305.1 | Unlawful Practices22 |
| 104.0 | Permits2 | 306.0 | Industrial Wastes22 |
| 104.1 | Permits Required2 | 306.1 | Detrimental Wastes22 |
| 104.2 | Exempt Work2 | 306.2 | Safe Discharge22 |
| 104.3 | Application for Permit2 | 307.0 | Location22 |
| 104.4 | Permit Issuance3 | 307.1 | System22 |
| 104.5 | Fees4 | 307.2 | Ownership22 |
| 105.0 | Inspections and Testing4 | 308.0 | Improper Location22 |
| 105.1 | General4 | 308.1 | General22 |
| 105.2 | Required Inspections4 | 309.0 | Workmanship23 |
| 105.3 | Testing of Systems5 | 309.1 | Engineering Practices23 |
| 105.4 | Connection to Service Utilities5 | 309.2 | Concealing Imperfections23 |
| 106.0 | Violations and Penalties5 | 309.3 | Burred Ends23 |
| 106.1 | General5 | 309.4 | Installation Practices23 |
| 106.2 | Notices of Correction or Violation5 | 310.0 | Prohibited Fittings and Practices23 |
| 106.3 | Penalties5 | 310.1 | Fittings23 |
| 106.4 | Stop Orders6 | 310.2 | Drainage and Vent Piping23 |
| 106.5 | Authority to Disconnect Utilities in Emergencies6 | 310.3 | Waste Connection23 |
| 106.6 | Authority to Condemn6 | 310.4 | Use of Vent and Waste Pipes23 |
| 107.0 | Board of Appeals6 | 310.5 | Obstruction of Flow23 |
| 107.1 | General6 | 310.6 | Dissimilar Metals23 |
| 107.2 | Limitations of Authority6 | 310.7 | Direction of Flow23 |
| Table 104.5 | Plumbing Permit Fees7 | | |

| | | |
|-------------|--|-----|
| 310.8 | Screwed Fittings | .23 |
| 311.0 | Independent Systems | .23 |
| 311.1 | General | .23 |
| 312.0 | Protection of Piping, Materials, and Structures | .23 |
| 312.1 | General | .23 |
| 312.2 | Installation | .23 |
| 312.3 | Building Sewer and Drainage Piping | .23 |
| 312.4 | Corrosion, Erosion, and Mechanical Damage | .23 |
| 312.5 | Protectively Coated Pipe | .23 |
| 312.6 | Freezing Protection | .23 |
| 312.7 | Fire-Resistant Construction | .23 |
| 312.8 | Waterproofing of Openings | .23 |
| 312.9 | Steel Nail Plates | .24 |
| 312.10 | Sleeves | .24 |
| 312.11 | Structural Members | .24 |
| 312.12 | Rodentproofing | .24 |
| 312.13 | Exposed ABS Piping | .24 |
| 312.14 | Exposed PVC Piping | .24 |
| 313.0 | Hangers and Supports | .24 |
| 313.1 | General | .24 |
| 313.2 | Material | .24 |
| 313.3 | Suspended Piping | .24 |
| 313.4 | Alignment | .24 |
| 313.5 | Underground Installation | .24 |
| 313.6 | Hanger Rod Sizes | .24 |
| Table 313.6 | Hanger Rod Sizes | .24 |
| 313.7 | Gas Piping | .24 |
| 314.0 | Trenching, Excavation, and Backfill | .24 |
| 314.1 | Trenches | .24 |
| 314.2 | Tunneling and Driving | .24 |
| 314.3 | Open Trenches | .25 |
| 314.4 | Excavations | .25 |
| 315.0 | Joints and Connections | .25 |
| 315.1 | Unions | .25 |
| 315.2 | Prohibited Joints and Connections | .25 |
| 316.0 | Increases and Reducers | .25 |
| 316.1 | General | .25 |
| 317.0 | Food-Handling Establishments | .25 |
| 317.1 | General | .25 |
| 318.0 | Test Gauges | .25 |
| 318.1 | General | .25 |
| 318.2 | Pressure Tests (10 psi or less) | .25 |
| 318.3 | Pressure Tests (greater than 10 psi to 100 psi) | .25 |
| 318.4 | Pressure Tests (exceeding 100 psi) | .25 |

| | | |
|-------------|-----------------------------------|-----|
| 318.5 | Pressure Range | .25 |
| 319.0 | Medical Gas and Vacuum Systems | .25 |
| 319.1 | General | .25 |
| 320.0 | Rehabilitation of Piping Systems | .25 |
| 320.1 | General | .25 |
| Table 313.3 | Hangers and Supports | .26 |

CHAPTER 4

PLUMBING FIXTURES

AND FIXTURE FITTINGS27

| | | |
|--------|---|-----|
| 401.0 | General | .27 |
| 401.1 | Applicability | .27 |
| 401.2 | Quality of Fixtures | .27 |
| 402.0 | Installation | .27 |
| 402.1 | Cleaning | .27 |
| 402.2 | Joints | .27 |
| 402.3 | Securing Fixtures | .27 |
| 402.4 | Wall-Hung Fixtures | .27 |
| 402.5 | Setting | .27 |
| 402.6 | Flanged Fixture Connections | .27 |
| 402.7 | Supply Fittings | .27 |
| 402.8 | Installation | .27 |
| 402.9 | Design and Installation of Plumbing Fixtures | .28 |
| 402.10 | Slip Joint Connections | .28 |
| 402.11 | Future Fixtures | .28 |
| 403.0 | Accessible Plumbing Facilities | .28 |
| 403.1 | General | .28 |
| 403.2 | Fixtures and Fixture Fittings for Persons with Disabilities | .28 |
| 403.3 | Exposed Pipes and Surfaces | .28 |
| 404.0 | Overflows | .28 |
| 404.1 | General | .28 |
| 405.0 | Prohibited Fixtures | .28 |
| 405.1 | Prohibited Water Closets | .28 |
| 405.2 | Prohibited Urinals | .28 |
| 405.3 | Miscellaneous Fixtures | .28 |
| 406.0 | Special Fixtures and Specialties | .28 |
| 406.1 | Water and Waste Connections | .28 |
| 406.2 | Special Use Sinks | .28 |
| 406.3 | Special Use Fixtures | .28 |
| 406.4 | Zinc Alloy Components | .28 |
| 407.0 | Lavatories | .28 |
| 407.1 | Application | .28 |
| 407.2 | Water Consumption | .28 |
| 407.3 | Limitation of Hot Water Temperature for Public Lavatories | .28 |
| 407.4 | Transient Public Lavatories | .29 |
| 407.5 | Waste Outlet | .29 |

| | | | | | |
|--------|---|----|-------------|---|----|
| 407.6 | Overflow | 29 | 415.1 | Application | 32 |
| 408.0 | Showers | 29 | 415.2 | Drinking Fountain Alternatives ... | 32 |
| 408.1 | Application | 29 | 415.3 | Drainage Connection | 32 |
| 408.2 | Water Consumption | 29 | 415.4 | Location | 32 |
| 408.3 | Individual Shower and Tub-Shower Combination Control Valves | 29 | 416.0 | Emergency Eyewash and Shower Equipment | 32 |
| 408.4 | Waste Outlet | 29 | 416.1 | Application | 32 |
| 408.5 | Finished Curb or Threshold | 29 | 416.2 | Water Supply | 32 |
| 408.6 | Shower Compartments | 29 | 416.3 | Installation | 32 |
| 408.7 | Lining for Showers and Receptors | 29 | 416.4 | Location | 32 |
| 408.8 | Public Shower Floors | 30 | 416.5 | Drain | 32 |
| 408.9 | Location of Valves and Heads ... | 30 | 417.0 | Faucets and Fixture Fittings | 32 |
| 408.10 | Water Supply Riser | 30 | 417.1 | Application | 32 |
| 409.0 | Bathtubs and Whirlpool Bathtubs | 30 | 417.2 | Deck Mounted Bath/Shower Valves | 32 |
| 409.1 | Application | 30 | 417.3 | Handheld Showers | 32 |
| 409.2 | Waste Outlet | 30 | 417.4 | Faucets and Fixture Fittings with Hose Connected Outlets | 32 |
| 409.3 | Overflow | 30 | 417.5 | Separate Controls for Hot and Cold Water | 32 |
| 409.4 | Limitation of Hot Water in Bathtubs and Whirlpool Bathtubs | 30 | 418.0 | Floor Drains | 32 |
| 409.5 | Backflow Protection | 30 | 418.1 | Application | 32 |
| 409.6 | Installation and Access | 30 | 418.2 | Strainer | 32 |
| 410.0 | Bidets | 31 | 418.3 | Location of Floor Drains | 33 |
| 410.1 | Application | 31 | 418.4 | Food Storage Areas | 33 |
| 410.2 | Backflow Protection | 31 | 418.5 | Floor Slope | 33 |
| 410.3 | Limitation of Water Temperature in Bidets | 31 | 419.0 | Food Waste Disposers | 33 |
| 411.0 | Water Closets | 31 | 419.1 | Application | 33 |
| 411.1 | Application | 31 | 419.2 | Drainage Connection | 33 |
| 411.2 | Water Consumption | 31 | 419.3 | Water Supply | 33 |
| 411.3 | Water Closet Seats | 31 | 420.0 | Sinks | 33 |
| 412.0 | Urinals | 31 | 420.1 | Application | 33 |
| 412.1 | Application | 31 | 420.2 | Water Consumption | 33 |
| 412.2 | Backflow Protection | 31 | 420.3 | Pre-Rinse Spray Valve | 33 |
| 413.0 | Flushing Devices | 31 | 420.4 | Waste Outlet | 33 |
| 413.1 | Where Required | 31 | 421.0 | Floor Sinks | 33 |
| 413.2 | Flushometer Valves | 31 | 421.1 | Application | 33 |
| 413.3 | Flush Tanks | 31 | 421.2 | Strainers | 33 |
| 413.4 | Water Supply for Flush Tanks ... | 31 | 422.0 | Minimum Number of Required Fixtures | 33 |
| 413.5 | Overflows in Flush Tanks | 32 | 422.1 | Fixture Count | 33 |
| 414.0 | Dishwashing Machines | 32 | 422.2 | Separate Facilities | 33 |
| 414.1 | Application | 32 | 422.3 | Fixture Requirements for Special Occupancies | 34 |
| 414.2 | Backflow Protection | 32 | 422.4 | Toilet Facilities Serving Employees and Customers | 34 |
| 414.3 | Drainage Connection | 32 | 422.5 | Toilet Facilities for Workers | 34 |
| 415.0 | Drinking Fountains | 32 | Table 422.1 | Minimum Plumbing Facilities | 35 |

| | | | | |
|------------------|--|-----------|---------------|--|
| CHAPTER 5 | WATER HEATERS | 39 | | |
| 501.0 | General | 39 | 507.8 | Safety Shutoff Devices for Unlisted LP-Gas Appliances Used Indoors |
| 501.1 | Applicability | 39 | 507.9 | Use of Air or Oxygen Under Pressure |
| 502.0 | Permits | 39 | 507.10 | Protection of Gas Appliances from Fumes or Gases other than Products of Combustion |
| 502.1 | General | 39 | 507.11 | Process Air |
| 503.0 | Inspection | 39 | 507.12 | Flammable Vapors |
| 503.1 | Inspection of Chimneys or Vents | 39 | 507.13 | Installation in Garages |
| 503.2 | Final Water Heater Inspection | 39 | 507.14 | Installation in Commercial Garages |
| 504.0 | Water Heater Requirements | 39 | 507.15 | Installation in Aircraft Hangars |
| 504.1 | Location | 39 | 507.16 | Venting of Flue Gases |
| 504.2 | Vent | 39 | 507.17 | Extra Device or Attachment |
| 504.3 | Clearance | 39 | 507.18 | Adequate Capacity of Piping |
| Table 501.1(1) | First Hour Rating | 39 | 507.19 | Avoiding Strain on Gas Piping |
| 504.4 | Pressure-Limiting Devices | 40 | 507.20 | Gas Appliance Pressure Regulators |
| 504.5 | Temperature-Limiting Devices | 40 | 507.21 | Venting of Gas Appliance Pressure Regulators |
| 504.6 | Temperature, Pressure, and Vacuum Relief Devices | 40 | 507.22 | Bleed Lines for Diaphragm-Type Valves |
| 505.0 | Oil-Burning and Other Water Heaters | 40 | 507.23 | Combination of Appliances and Equipment |
| 505.1 | Water Heaters | 40 | 507.24 | Installation Instructions |
| 505.2 | Safety Devices | 40 | 507.25 | Protection of Outdoor Appliances |
| 505.3 | Oil-Fired Water Heaters | 40 | 507.26 | Accessibility for Service |
| 505.4 | Indirect-Fired Water Heaters | 40 | 508.0 | Equipment and Appliances on Roofs |
| Table 501.1(2) | Water Heaters | 40 | 508.1 | General |
| 506.0 | Air for Combustion and Ventilation | 40 | 508.2 | Installation of Equipment and Appliances on Roofs |
| 506.1 | General | 40 | 508.3 | Access to Equipment and Appliances on Roofs |
| 506.2 | Indoor Combustion Air | 40 | 508.4 | Appliances in Attics and Under-Floor Spaces |
| 506.3 | Indoor Opening Size and Location | 41 | 509.0 | Venting of Appliances |
| 506.4 | Outdoor Combustion Air | 41 | 509.1 | Listing |
| 506.5 | Combination Indoor and Outdoor Combustion Air | 43 | 509.2 | Connection to Venting Systems |
| 506.6 | Engineered Installations | 43 | 509.3 | Design and Construction |
| 506.7 | Mechanical Combustion Air Supply | 43 | 509.4 | Type of Venting System to be Used |
| 506.8 | Louvers, Grilles, and Screens | 43 | 509.5 | Masonry, Metal, and Factory-Built Chimneys |
| 506.9 | Combustion Air Ducts | 43 | Table 509.4 | Type of Venting System to be Used |
| 507.0 | Appliance and Equipment Installation Requirements | 43 | 509.6 | Gas Vents |
| 507.1 | Dielectric Insulator | 43 | Table 509.6.2 | Roof Pitch Height |
| 507.2 | Seismic Provisions | 44 | | |
| 507.3 | Support of Appliances | 44 | | |
| 507.4 | Ground Support | 44 | | |
| 507.5 | Drainage Pan | 44 | | |
| 507.6 | Added or Converted Equipment or Appliances | 44 | | |
| 507.7 | Types of Gases | 44 | | |

| | | |
|------------------|---|----|
| 509.7 | Single-Wall Metal Pipe | 52 |
| 509.8 | Through-the-Wall Vent Termination | 53 |
| Table 509.7.3(1) | Clearance for Connectors | 53 |
| Table 509.7.3(2) | Reduction of Clearances with Specified Forms of Protection | 55 |
| 509.9 | Condensation Drain | 56 |
| 509.10 | Vent Connectors for Category I Appliances | 56 |
| Table 509.10.1.3 | Minimum Thickness for Galvanized Steel Vent Connectors for Low-Heat Appliances | 57 |
| Table 509.10.1.4 | Minimum Thickness for Steel Vent Connectors for Medium-Heat Appliances and Commercial and Industrial Incinerators | 57 |
| 509.11 | Draft Hoods and Draft Controls .. | 58 |
| 509.12 | Manually Operated Dampers | 59 |
| 509.13 | Automatically Operated Vent Dampers | 59 |
| 509.14 | Obstructions | 59 |
| 510.0 | Sizing of Category I Venting Systems | 59 |
| 510.1 | Single Appliance Vent Table 510.1.2(1) through Table 510.1.2(6) | 59 |
| 510.2 | Multiple Appliance Vent Table 510.2(1) through Table 510.2(9) .. | 61 |
| Table 510.2.1 | Vent Connector Maximum Length | 61 |
| Table 510.1.2(1) | Type B Double-Wall Gas Vent | 65 |
| Table 510.1.2(2) | Type B Double-Wall Gas Vent | 68 |
| Table 510.1.2(3) | Masonry Chimney | 70 |
| Table 510.1.2(4) | Masonry Chimney | 72 |
| Table 510.1.2(5) | Single-Wall Metal Pipe or Type B Asbestos-Cement Vent | 74 |
| Table 510.1.2(6) | Exterior Masonry Chimney | 75 |
| Table 510.2(1) | Type B Double-Wall Vent | 76 |
| Table 510.2(2) | Type B Double-Wall Vent | 80 |
| Table 510.2(3) | Masonry Chimney | 82 |
| Table 510.2(4) | Masonry Chimney | 84 |
| Table 510.2(5) | Single-Wall Metal Pipe or Type B Asbestos-Cement Vent | 86 |
| Table 510.2(6) | Exterior Masonry Chimney | 86 |
| Table 510.2(7) | Exterior Masonry Chimney | 87 |
| Table 510.2(8) | Exterior Masonry Chimney | 88 |
| Table 510.2(9) | Exterior Masonry Chimney | 89 |

| | | |
|------------------|--|-----------|
| CHAPTER 6 | WATER SUPPLY AND DISTRIBUTION | 91 |
| 601.0 | General | 91 |
| 601.1 | Applicability | 91 |

| | | |
|---------------|--|-----|
| 601.2 | Hot and Cold Water Required | 91 |
| 601.3 | Identification of a Potable and Nonpotable Water System | 91 |
| Table 601.3.2 | Minimum Length of Color Field and Size of Letters | 91 |
| 602.0 | Unlawful Connections | 91 |
| 602.1 | Prohibited Installation | 91 |
| 602.2 | Cross-Contamination | 92 |
| 602.3 | Backflow Prevention | 92 |
| 602.4 | Approval by Authority | 92 |
| 603.0 | Cross-Connection Control | 92 |
| 603.1 | General | 92 |
| 603.2 | Approval of Devices or Assemblies | 92 |
| 603.3 | Backflow Prevention Devices, Assemblies, and Methods | 92 |
| Table 603.2 | Backflow Prevention Devices, Assemblies, and Methods | 93 |
| Table 603.3.1 | Minimum Air Gaps for Water Distribution | 95 |
| 603.4 | General Requirements | 95 |
| 603.5 | Specific Requirements | 96 |
| 604.0 | Materials | 98 |
| 604.1 | Pipe, Tube, and Fittings | 98 |
| 604.2 | Lead Content | 98 |
| 604.3 | Copper or Copper Alloy Tube | 98 |
| 604.4 | Hard-Drawn Copper or Copper Alloy Tubing | 98 |
| 604.5 | Flexible Connectors | 98 |
| 604.6 | Cast-Iron Fittings | 98 |
| 604.7 | Malleable Iron Fittings | 98 |
| 604.8 | Previously Used Piping and Tubing | 98 |
| 604.9 | Epoxy Coating | 98 |
| 604.10 | Plastic Materials | 98 |
| 604.11 | Solder | 98 |
| Table 604.1 | Materials for Building Supply and Water Distribution Piping and Fittings | 99 |
| 604.12 | Flexible Corrugated Connectors | 99 |
| 604.13 | Water Heater Connectors | 99 |
| 605.0 | Joints and Connections | 99 |
| 605.1 | Copper or Copper Alloy Pipe, Tubing, and Joints | 99 |
| 605.2 | CPVC Plastic Pipe and Joints | 100 |
| 605.3 | CPVC/AL/CPVC Plastic Pipe and Joints | 101 |
| 605.4 | Ductile Iron Pipe and Joints | 101 |
| 605.5 | Galvanized Steel Pipe and Joints | 101 |
| 605.6 | PE Plastic Pipe/Tubing and Joints | 101 |

| | | | | | |
|--------|---|-----|-----------------|--|-----|
| 605.7 | PE-AL-PE Plastic Pipe/Tubing and Joints | 102 | 609.7 | Abutting Lot | 105 |
| 605.8 | PE-RT | 102 | 609.8 | Low-Pressure Cutoff Required on Booster Pumps for Water Distribution Systems | 106 |
| 605.9 | PEX Plastic Tubing and Joints ... | 102 | 609.9 | Disinfection of Potable Water System | 106 |
| 605.10 | PEX-AL-PEX Plastic Tubing and Joints | 102 | 609.10 | Water Hammer | 106 |
| 605.11 | Polypropylene (PP) Piping and Joints | 102 | 609.11 | Pipe Insulation | 106 |
| 605.12 | PVC Plastic Pipe and Joints | 103 | 610.0 | Size of Potable Water Piping ... | 106 |
| 605.13 | Stainless Steel Pipe and Joints .. | 103 | 610.1 | Size | 106 |
| 605.14 | Slip Joints | 103 | 610.2 | Pressure Loss | 106 |
| 605.15 | Dielectric Unions | 103 | 610.3 | Quantity of Water | 106 |
| 605.16 | Joints Between Various Materials | 103 | 610.4 | Sizing Water Supply and Distribution Systems | 106 |
| 606.0 | Valves | 103 | Table 610.3 | Water Supply Fixture Units (WSFU) and Minimum Fixture Branch Pipe Sizes | 107 |
| 606.1 | General | 103 | Table 610.4 | Fixture Unit Table for Determining Water Pipe and Meter Sizes | 108 |
| 606.2 | Fullway Valve | 103 | 610.5 | Sizing per Appendices A and C | 109 |
| 606.3 | Multidwelling Units | 104 | 610.6 | Friction and Pressure Loss | 109 |
| 606.4 | Multiple Openings | 104 | 610.7 | Conditions for Using Table 610.4 | 109 |
| 606.5 | Control Valve | 104 | 610.8 | Size of Meter and Building Supply Pipe Using Table 610.4 .. | 109 |
| 606.6 | Accessible | 104 | 610.9 | Size of Branches | 109 |
| 606.7 | Multiple Fixtures | 104 | 610.10 | Sizing for Flushometer Valves ... | 109 |
| 607.0 | Potable Water Supply Tanks | 104 | Table 610.10 | Flushometer Fixture Units for Water Sizing Using Table 610.3 | 109 |
| 607.1 | General | 104 | 610.11 | Sizing Systems for Flushometer Tanks | 110 |
| 607.2 | Potable Water Tanks | 104 | 610.12 | Sizing for Velocity | 110 |
| 607.3 | Venting | 104 | 610.13 | Exceptions | 110 |
| 607.4 | Overflow | 104 | 611.0 | Drinking Water Treatment Units | 110 |
| 607.5 | Valves | 104 | 611.1 | Application | 110 |
| 608.0 | Water Pressure, Pressure Regulators, Pressure Relief Valves, and Vacuum Relief Valves | 104 | 611.2 | Air Gap Discharge | 110 |
| 608.1 | Inadequate Water Pressure | 104 | 611.3 | Connection Tubing | 110 |
| 608.2 | Excessive Water Pressure | 104 | 611.4 | Sizing of Residential Softeners ... | 110 |
| 608.3 | Expansion Tanks, and Combination Temperature and Pressure-Relief Valves | 104 | 612.0 | Residential Fire Sprinkler Systems | 110 |
| 608.4 | Pressure Relief Valves | 105 | 612.1 | Where Required | 110 |
| 608.5 | Discharge Piping | 105 | Table 611.4 | Sizing of Residential Water Softeners | 111 |
| 608.6 | Water-Heating Devices | 105 | 612.2 | Types of Systems | 111 |
| 608.7 | Vacuum Relief Valves | 105 | 612.3 | Sprinklers | 111 |
| 609.0 | Installation, Testing, Unions, and Location | 105 | Table 612.3.3.1 | Locations Where Intermediate Temperature Sprinklers are Required | 112 |
| 609.1 | Installation | 105 | | | |
| 609.2 | Trenches | 105 | | | |
| 609.3 | Under Concrete Slab | 105 | | | |
| 609.4 | Testing | 105 | | | |
| 609.5 | Unions | 105 | | | |
| 609.6 | Location | 105 | | | |

| | | | | | |
|--------------------|---|------------|-------------|---|-----|
| 612.4 | Sprinkler Piping System | 112 | 703.0 | Size of Drainage Piping | 126 |
| 612.5 | Sprinkler Piping Design | 112 | 703.1 | Minimum Size | 126 |
| Table 612.3.6 | Minimum Separation From Obstruction | 113 | 703.2 | Maximum Number of Fixture Units | 126 |
| Table 612.5.3.2(1) | Water Service Pressure Loss (PL_{ws}) | 115 | 703.3 | Sizing per Appendix C | 126 |
| Table 612.5.3.2(2) | Minimum Water Meter Pressure Loss (PL_m) | 116 | 704.0 | Fixture Connections (Drainage) | 126 |
| 612.6 | Instructions and Signs | 116 | 704.1 | Inlet Fittings | 126 |
| 612.7 | Inspection and Testing | 116 | 704.2 | Single Vertical Drainage Pipe | 126 |
| Table 612.5.3.2(3) | Elevation Loss (PL_e) | 116 | 704.3 | Commercial Sinks | 126 |
| Table 612.5.3.2(4) | Allowable Pipe Length for 3/4 Inch Type M Copper Water Tubing | 117 | 705.0 | Joints and Connections | 126 |
| Table 612.5.3.2(5) | Allowable Pipe Length for 1 Inch Type M Copper Water Tubing | 118 | 705.1 | ABS and ABS Co-Extruded Plastic Pipe and Joints | 126 |
| Table 612.5.3.2(6) | Allowable Pipe Length for 3/4 Inch IPS CPVC Pipe | 119 | 705.2 | Cast-Iron Pipe and Joints | 126 |
| Table 612.5.3.2(7) | Allowable Pipe Length for 1 Inch IPS CPVC Pipe | 120 | Table 703.2 | Maximum Unit Loading and Maximum Length of Drainage and Vent Piping | 127 |
| Table 612.5.3.2(8) | Allowable Pipe Length for 3/4 Inch PEX Tubing | 121 | 705.3 | Copper or Copper Alloy Pipe (DWV) and Joints | 127 |
| Table 612.5.3.2(9) | Allowable Pipe Length for 1 Inch PEX Tubing | 122 | 705.4 | Galvanized Steel Pipe and Joints | 128 |
| CHAPTER 7 | SANITARY DRAINAGE | 123 | 705.5 | PVC and PVC Co-Extruded Plastic Pipe and Joining Methods | 128 |
| PART I | Drainage Systems | 123 | 705.6 | Stainless Steel Pipe and Joints | 128 |
| 701.0 | General | 123 | 705.7 | Vitrified Clay Pipe and Joints | 128 |
| 701.1 | Applicability | 123 | 705.8 | Special Joints | 128 |
| 701.2 | Drainage Piping | 123 | 705.9 | Joints Between Various Materials | 129 |
| 701.3 | Drainage Fittings | 123 | 706.0 | Changes in Direction of Drainage Flow | 129 |
| 701.4 | Continuous Wastes | 123 | 706.1 | Approved Fittings | 129 |
| 701.5 | Lead | 123 | 706.2 | Horizontal to Vertical | 129 |
| 701.6 | Caulking Ferrules | 123 | 706.3 | Horizontal to Horizontal | 129 |
| 701.7 | Soldering Bushings | 123 | 706.4 | Vertical to Horizontal | 129 |
| Table 701.6 | Caulking Ferrules | 123 | 707.0 | Cleanouts | 129 |
| Table 701.7 | Soldering Bushings | 123 | 707.1 | Plug | 129 |
| 702.0 | Fixture Unit Equivalents | 123 | Table 707.1 | Cleanouts | 129 |
| 702.1 | Trap Size | 123 | 707.2 | Approved | 129 |
| Table 701.2 | Materials for Drain, Waste, Vent Pipe and Fittings | 124 | 707.3 | Watertight and Gastight | 129 |
| Table 702.1 | Drainage Fixture Unit Values (DFU) | 125 | 707.4 | Location | 129 |
| 702.2 | Intermittent Flow | 126 | 707.5 | Cleaning | 130 |
| 702.3 | Continuous Flow | 126 | 707.6 | Extension | 130 |
| Table 702.2(1) | Maximum Drainage Fixture Units for a Trap and Trap Arm | 126 | 707.7 | Interceptor | 130 |
| Table 702.2(2) | Discharge Capacity in Gallons Per Minute for Intermittent Flow Only | 126 | 707.8 | Access | 130 |
| | | | 707.9 | Clearance | 130 |
| | | | 707.10 | Fittings | 130 |
| | | | 707.11 | Pressure Drainage Systems | 130 |
| | | | 707.12 | Countersunk Cleanout Plugs | 130 |
| | | | 707.13 | Hubless Blind Plugs | 130 |

| | | | | | |
|----------------|--|------------|------------------|---|------------|
| 707.14 | Trap Arms | 130 | 714.4 | Commercial Food Waste Disposer | 133 |
| 708.0 | Grade of Horizontal Drainage Piping | 130 | 714.5 | Tanks | 133 |
| 708.1 | General | 130 | 715.0 | Building Sewer Materials | 133 |
| 709.0 | Gravity Drainage Required | 130 | 715.1 | Materials | 133 |
| 709.1 | General | 130 | 715.2 | Joining Methods and Materials | 133 |
| 710.0 | Drainage of Fixtures Located Below the Next Upstream Manhole or Below the Main Sewer Level | 130 | 715.3 | Existing Sewers | 133 |
| 710.1 | Backflow Protection | 130 | 716.0 | Markings | 133 |
| 710.2 | Sewage Discharge | 130 | 716.1 | General | 133 |
| 710.3 | Sewage Ejector and Pumps | 130 | 717.0 | Size of Building Sewers | 133 |
| 710.4 | Discharge Line | 131 | 717.1 | General | 133 |
| 710.5 | Size of Building Drains and Sewers | 131 | Table 717.1 | Maximum/Minimum Fixture Unit Loading on Building Sewer Piping | 133 |
| 710.6 | Backwater Valves | 131 | 718.0 | Grade, Support, and Protection of Building Sewers | 133 |
| 710.7 | Drainage and Venting Systems | 131 | 718.1 | Slope | 133 |
| 710.8 | Sump and Receiving Tank Construction | 131 | 718.2 | Support | 133 |
| 710.9 | Alarm | 131 | 718.3 | Protection from Damage | 133 |
| 710.10 | Sump and Receiving Tank Covers and Vents | 131 | 719.0 | Cleanouts. | 134 |
| 710.11 | Air Tanks | 131 | 719.1 | Locations | 134 |
| 710.12 | Grinder Pump Ejector | 131 | 719.2 | No Additional Cleanouts | 134 |
| 710.13 | Macerating Toilet Systems and Pumped Waste Systems | 131 | 719.3 | Building Sewer Cleanouts | 134 |
| 711.0 | Suds Relief | 132 | 719.4 | Cleaning | 134 |
| 711.1 | General | 132 | 719.5 | Access | 134 |
| 712.0 | Testing | 132 | 719.6 | Manholes | 134 |
| 712.1 | Media | 132 | 720.0 | Sewer and Water Pipes | 134 |
| 712.2 | Water Test | 132 | 720.1 | General | 134 |
| 712.3 | Air Test | 132 | 721.0 | Location | 134 |
| PART II | Building Sewers | 132 | 721.1 | Building Sewer | 134 |
| 713.0 | Sewer Required | 132 | 721.2 | Abutting Lot | 134 |
| 713.1 | Where Required | 132 | 722.0 | Abandoned Sewers and Sewage Disposal Facilities | 134 |
| 713.2 | Private Sewage Disposal System | 132 | 722.1 | Building (House) Sewer | 134 |
| 713.3 | Public Sewer | 132 | 722.2 | Cesspools, Septic Tanks, and Seepage Pits | 134 |
| 713.4 | Public Sewer Availability | 132 | 722.3 | Filling | 134 |
| 713.5 | Permit | 132 | 722.4 | Ownership | 134 |
| 713.6 | Lot | 132 | Table 721.1 | Minimum Horizontal Distance Required from Building Sewer | 135 |
| 713.7 | Installation | 132 | 722.5 | Disposal Facilities | 135 |
| 714.0 | Damage to Public Sewer or Private Sewage Disposal System | 133 | 723.0 | Building Sewer Test | 135 |
| 714.1 | Unlawful Practices | 133 | 723.1 | General | 135 |
| 714.2 | Prohibited Water Discharge | 133 | CHAPTER 8 | INDIRECT WASTES | 137 |
| 714.3 | Prohibited Sewer Connection | 133 | 801.0 | General | 137 |
| | | | 801.1 | Applicability | 137 |
| | | | 801.2 | Air Gap or Air Break Required | 137 |

| | | |
|-------------|---|-----|
| 801.3 | Food and Beverage Handling Establishments | 137 |
| 801.4 | Bar and Fountain Sink Traps | 137 |
| 801.5 | Connections from Water Distribution System | 137 |
| 801.6 | Sterilizers | 137 |
| 801.7 | Drip or Drainage Outlets | 137 |
| 802.0 | Approvals | 137 |
| 802.1 | General | 137 |
| 803.0 | Indirect Waste Piping | 137 |
| 803.1 | Materials | 137 |
| 803.2 | Copper and Copper Alloys | 137 |
| 803.3 | Pipe Size and Length | 137 |
| 804.0 | Indirect Waste Receptors | 138 |
| 804.1 | Standpipe Receptors | 138 |
| 805.0 | Pressure Drainage Connections | 138 |
| 805.1 | General | 138 |
| 806.0 | Sterile Equipment | 138 |
| 806.1 | General | 138 |
| 807.0 | Appliances | 138 |
| 807.1 | Non-Classed Apparatus | 138 |
| 807.2 | Undiluted Condensate Waste | 138 |
| 807.3 | Domestic Dishwashing Machine | 138 |
| 808.0 | Cooling Water | 138 |
| 808.1 | General | 138 |
| 809.0 | Drinking Fountains | 138 |
| 809.1 | General | 138 |
| 810.0 | Steam and Hot Water Drainage Condensers and Sumps | 138 |
| 810.1 | High Temperature Discharge | 138 |
| Table 810.1 | Pipe Connections in Blowoff Condensers and Sumps | 139 |
| 810.2 | Sumps, Condensers, and Intercepting Tanks | 139 |
| 810.3 | Cleaning | 139 |
| 810.4 | Strainers | 139 |
| 811.0 | Chemical Wastes | 139 |
| 811.1 | Pretreatment | 139 |
| 811.2 | Waste and Vent Pipes | 139 |
| 811.3 | Joining Materials | 139 |
| 811.4 | Access | 139 |
| 811.5 | Permanent Record | 139 |
| 811.6 | Chemical Vent | 139 |
| 811.7 | Discharge | 139 |
| 811.8 | Diluted Chemicals | 139 |
| 812.0 | Clear Water Wastes | 139 |
| 812.1 | General | 139 |
| 813.0 | Swimming Pools | 139 |

| | | |
|-------------|--|-----|
| 813.1 | General | 139 |
| 814.0 | Condensate Wastes and Control .. | 140 |
| 814.1 | Condensate Disposal | 140 |
| 814.2 | Condensate Control | 140 |
| 814.3 | Condensate Waste Pipe Material and Sizing | 140 |
| Table 814.3 | Minimum Condensate Pipe Size | 140 |
| 814.4 | Appliance Condensate Drains .. | 140 |
| 814.5 | Point of Discharge | 141 |
| 814.6 | Condensate Waste From Air-Conditioning Coils | 141 |
| 814.7 | Plastic Fittings | 141 |

CHAPTER 9

| | |
|--|------------|
| VENTS | 143 |
| General | 143 |
| Applicability | 143 |
| Vents Required | 143 |
| Trap Seal Protection | 143 |
| Vents Not Required | 143 |
| Interceptor | 143 |
| Bars, Soda Fountains, and Counter | 143 |
| Materials | 143 |
| Applicable Standards | 143 |
| Use of Copper or Copper Alloy Tubing | 143 |
| Changes in Direction | 143 |
| Size of Vents | 143 |
| Size | 143 |
| Length | 143 |
| Vent Pipe Grades and Connections | 144 |
| Grade | 144 |
| Horizontal Drainage Pipe | 144 |
| Vent Pipe Rise | 144 |
| Roof Termination | 144 |
| Location of Opening | 144 |
| Common Vertical Pipe | 144 |
| Vent Termination | 144 |
| Roof Termination | 144 |
| Clearance | 144 |
| Use of Roof | 144 |
| Outdoor Installations | 144 |
| Joints | 144 |
| Lead | 144 |
| Frost or Snow Closure | 144 |
| Vent Stacks and Relief Vents | 144 |

| | | | | | |
|---------------------------|--|------------|----------------|--|-----|
| 907.1 | Drainage Stack | 144 | 1005.1 | General | 148 |
| 907.2 | Yoke Vent | 144 | 1006.0 | Floor Drain Traps | 148 |
| 908.0 | Wet Venting | 144 | 1006.1 | General | 148 |
| 908.1 | Vertical Wet Venting | 144 | 1007.0 | Trap Seal Protection | 148 |
| 908.2 | Horizontal Wet Venting for a Bathroom Group | 145 | 1007.1 | General | 148 |
| 909.0 | Special Venting for Island Fixtures | 145 | 1008.0 | Building Traps | 148 |
| 909.1 | General | 145 | 1008.1 | General | 148 |
| 910.0 | Combination Waste and Vent Systems | 145 | 1009.0 | Interceptors (Clarifiers) and Separators | 148 |
| 910.1 | Where Permitted | 145 | 1009.1 | Where Required | 148 |
| 910.2 | Approval | 145 | 1009.2 | Approval | 148 |
| 910.3 | Vents | 145 | 1009.3 | Design | 148 |
| 910.4 | Size | 145 | 1009.4 | Relief Vent | 148 |
| 910.5 | Vertical Waste Pipe | 145 | 1009.5 | Location | 148 |
| 910.6 | Cleanouts | 145 | 1009.6 | Maintenance of Interceptors | 148 |
| 910.7 | Fixtures | 145 | 1009.7 | Discharge | 148 |
| 911.0 | Circuit Venting | 146 | 1010.0 | Slaughterhouses, Packing Establishments, etc | 148 |
| 911.1 | Circuit Vent Permitted | 146 | 1010.1 | General | 148 |
| 911.2 | Vent Size and Connection | 146 | 1011.0 | Minimum Requirements for Auto Wash Racks | 148 |
| 911.3 | Slope and Size of Horizontal Branch | 146 | 1011.1 | General | 148 |
| 911.4 | Relief Vent | 146 | 1012.0 | Commercial and Industrial Laundries | 149 |
| 911.5 | Additional Fixtures | 146 | 1012.1 | General | 149 |
| 912.0 | Engineered Vent System | 146 | 1013.0 | Bottling Establishments | 149 |
| 912.1 | General | 146 | 1013.1 | General | 149 |
| 912.2 | Minimum Requirements | 146 | 1014.0 | Grease Interceptors | 149 |
| CHAPTER 10 | | | 1014.1 | General | 149 |
| TRAPS AND | | | 1014.2 | Hydromechanical Grease Interceptors | 149 |
| INTERCEPTORS | | 147 | 1014.3 | Gravity Grease Interceptors | 149 |
| 1001.0 | General | 147 | Table 1014.2.1 | Hydromechanical Grease Interceptor Sizing Using Gravity Flow Rates | 150 |
| 1001.1 | Applicability | 147 | Table 1014.3.6 | Gravity Grease Interceptor Sizing | 151 |
| 1001.2 | Where Required | 147 | 1015.0 | FOG (Fats, Oils, and Greases) Disposal System | 151 |
| 1002.0 | Traps Protected by Vent Pipes | 147 | 1015.1 | Purpose | 151 |
| 1002.1 | Vent Pipes | 147 | 1015.2 | Components, Materials, and Equipment | 151 |
| 1002.2 | Fixture Traps | 147 | 1015.3 | Sizing and Installation | 151 |
| 1002.3 | Change of Direction | 147 | 1015.4 | Performance | 151 |
| 1002.4 | Vent Pipe Opening | 147 | 1016.0 | Sand Interceptors | 151 |
| 1003.0 | Traps — Described | 147 | 1016.1 | Discharge | 151 |
| 1003.1 | General Requirements | 147 | 1016.2 | Authority Having Jurisdiction | 151 |
| 1003.2 | Slip Joint Fittings | 147 | 1016.3 | Construction and Size | 151 |
| Table 1002.2 | Horizontal Lengths of Trap Arms | 147 | | | |
| 1003.3 | Size | 148 | | | |
| 1004.0 | Traps | 148 | | | |
| 1004.1 | Prohibited | 148 | | | |
| 1004.2 | Movable Parts | 148 | | | |
| 1005.0 | Trap Seals | 148 | | | |

| | | |
|--------|---|-----|
| 1016.4 | Separate Use | 152 |
| 1017.0 | Oil and Flammable Liquid Interceptors | 152 |
| 1017.1 | Interceptors Required | 152 |
| 1017.2 | Design of Interceptors | 152 |

CHAPTER 11 STORM DRAINAGE153

| | | |
|----------------|---|-----|
| 1101.0 | General | 153 |
| 1101.1 | Applicability | 153 |
| 1101.2 | Where Required | 153 |
| 1101.3 | Storm Water Drainage to Sanitary Sewer Prohibited | 153 |
| 1101.4 | Material Uses | 153 |
| Table 1101.4.6 | Materials for Subsoil Drain Pipe and Fittings | 153 |
| 1101.5 | Expansion Joints Required | 153 |
| 1101.6 | Subsoil Drains | 153 |
| 1101.7 | Building Subdrains | 154 |
| 1101.8 | Areaway Drains | 154 |
| 1101.9 | Window Areaway Drains | 154 |
| 1101.10 | Filling Stations and Motor Vehicle Washing Establishments | 154 |
| 1101.11 | Paved Areas | 154 |
| 1101.12 | Roof Drainage | 154 |
| 1101.13 | Cleanouts | 155 |
| 1101.14 | Rainwater Sumps | 155 |
| 1101.15 | Traps on Storm Drains and Leaders | 155 |
| 1101.16 | Leaders, Conductors, and Connections | 155 |
| 1102.0 | Roof Drains | 155 |
| 1102.1 | Applications | 155 |
| 1102.2 | Dome Strainers Required | 155 |
| 1102.3 | Roof Drain Flashings | 155 |
| 1103.0 | Size of Leaders, Conductors, and Storm Drains | 155 |
| 1103.1 | Vertical Conductors and Leaders | 155 |
| 1103.2 | Size of Horizontal Storm Drains and Sewers | 155 |
| 1103.3 | Size of Roof Gutters | 155 |
| 1103.4 | Side Walls Draining onto a Roof | 155 |
| 1104.0 | Values for Continuous Flow | 156 |
| 1104.1 | General | 156 |
| 1105.0 | Controlled-Flow Roof Drainage | 156 |
| 1105.1 | Application | 156 |

| | | |
|-----------------|--|-----|
| Table 1105.1(1) | Controlled-Flow Maximum Roof Water Depth | 156 |
| Table 1105.1(2) | Distance of Scupper Bottoms Above Roof | 156 |
| 1105.2 | Setback Roofs | 156 |
| 1106.0 | Testing | 157 |
| 1106.1 | Testing Required | 157 |
| 1106.2 | Methods of Testing Storm Drainage Systems | 157 |
| Table 1101.8 | Sizing of Horizontal Rainwater Piping | 158 |
| Table 1101.12 | Sizing Roof Drains, Leaders, and Vertical Rainwater Piping | 159 |
| Table 1103.3 | Size of Gutters | 160 |

CHAPTER 12 FUEL GAS PIPING161

| | | |
|--------|---|-----|
| 1201.0 | General | 161 |
| 1201.1 | Applicability | 161 |
| 1202.0 | Coverage of Piping System | 161 |
| 1202.1 | General | 161 |
| 1202.2 | Piping System Requirements | 161 |
| 1202.3 | Applications | 161 |
| 1203.0 | Inspection | 161 |
| 1203.1 | Inspection Notification | 161 |
| 1203.2 | Excavation | 161 |
| 1203.3 | Type of Inspections | 161 |
| 1203.4 | Inspection Waived | 161 |
| 1204.0 | Certificate of Inspection | 162 |
| 1204.1 | Issuance | 162 |
| 1204.2 | Gas Supplier | 162 |
| 1204.3 | Unlawful | 162 |
| 1205.0 | Authority to Render Gas Service | 162 |
| 1205.1 | Authorized Personnel | 162 |
| 1205.2 | Outlets | 162 |
| 1206.0 | Authority to Disconnect | 162 |
| 1206.1 | Disconnection | 162 |
| 1206.2 | Notice | 162 |
| 1206.3 | Capped Outlets | 162 |
| 1207.0 | Temporary Use of Gas | 162 |
| 1207.1 | General | 162 |
| 1208.0 | Gas Piping System Design, Materials, and Components | 162 |
| 1208.1 | Installation of Piping System | 162 |
| 1208.2 | Provision for Location of Point of Delivery | 162 |
| 1208.3 | Interconnections Between Gas Piping Systems | 162 |
| 1208.4 | Sizing of Gas Piping Systems | 162 |

| | | | | | |
|------------------|---|-----|-----------------|---|-----|
| Table 1208.4.1 | Approximate Gas Input for Typical Appliances | 163 | 1212.2 | Suspended Low-Intensity Infrared Tube Heaters | 172 |
| 1208.5 | Acceptable Piping Materials and Joining Methods | 163 | 1212.3 | Use of Gas Hose Connectors ... | 172 |
| Table 1208.5.7.2 | Specifications for Threading Metallic Pipe | 164 | 1212.4 | Connection of Portable and Mobile Industrial Gas Appliances | 172 |
| 1208.6 | Gas Meters | 166 | 1212.5 | Appliance Shutoff Valves and Connections | 172 |
| 1208.7 | Gas Pressure Regulators | 166 | 1212.6 | Quick-Disconnect Devices | 173 |
| 1208.8 | Backpressure Protection | 167 | 1212.7 | Gas Convenience Outlets | 173 |
| 1208.9 | Low-Pressure Protection | 167 | 1212.8 | Sediment Trap | 173 |
| 1208.10 | Shutoff Valves | 167 | 1212.9 | Installation of Piping | 173 |
| 1208.11 | Expansion and Flexibility | 167 | 1212.10 | Liquefied Petroleum Gas Facilities and Piping | 173 |
| 1209.0 | Excess Flow Valve | 167 | 1213.0 | Pressure Testing and Inspection | 173 |
| 1209.1 | General | 167 | 1213.1 | Piping Installations | 173 |
| 1210.0 | Gas Piping Installation | 167 | 1213.2 | Test Preparation | 173 |
| 1210.1 | Piping Underground | 167 | 1213.3 | Test Pressure | 174 |
| 1210.2 | Installation of Piping | 168 | 1213.4 | Detection of Leaks and Defects .. | 174 |
| Table 1210.2.4.1 | Support of Piping | 169 | 1213.5 | Piping System Leak Test | 174 |
| 1210.3 | Concealed Piping in Buildings ... | 169 | 1213.6 | Purging Requirements | 174 |
| 1210.4 | Piping in Vertical Chases | 169 | Table 1213.6.1 | Size and Length of Piping | 174 |
| 1210.5 | Maximum Design Operating Pressure | 170 | 1214.0 | Interconnections Between Gas Piping Systems | 175 |
| 1210.6 | Appliance Overpressure Protection | 170 | 1214.1 | Interconnections Supplying Separate Users | 175 |
| 1210.7 | Gas Pipe Turns | 170 | 1214.2 | Interconnections for Standby Fuels | 175 |
| 1210.8 | Drips and Sediment Traps | 170 | 1215.0 | Required Gas Supply | 175 |
| 1210.9 | Outlets | 170 | 1215.1 | General | 175 |
| 1210.10 | Branch Pipe Connection | 171 | 1215.2 | Volume | 175 |
| 1210.11 | Manual Gas Shutoff Valves | 171 | 1215.3 | Gas Appliances | 176 |
| 1210.12 | Prohibited Devices | 171 | 1215.4 | Size of Piping Outlets | 176 |
| 1210.13 | Systems Containing Gas-Air Mixtures Outside the Flammable Range | 171 | 1216.0 | Required Gas Piping Size | 176 |
| 1210.14 | Systems Containing Flammable Gas-Air Mixtures | 171 | 1216.1 | Pipe Sizing Methods | 176 |
| 1211.0 | Electrical Bonding and Grounding | 171 | 1216.2 | Tables for Sizing Gas Piping Systems | 176 |
| 1211.1 | Pipe and Tubing other than CSST | 171 | 1216.3 | Sizing Equations | 176 |
| 1211.2 | Bonding of CSST Gas Piping | 171 | Table 1216.3 | <i>Cr</i> and <i>Y</i> for Natural Gas and Undiluted Propane at Standard Conditions | 176 |
| 1211.3 | Grounding Conductor or Electrode | 171 | 1216.4 | Sizing of Piping Sections | 176 |
| 1211.4 | Lightning Protection System | 171 | 1216.5 | Engineering Methods | 177 |
| 1211.5 | Electrical Circuits | 171 | 1216.6 | Variable Gas Pressure | 177 |
| 1211.6 | Electrical Connections | 171 | Table 1216.2(1) | Schedule 40 Metallic Pipe | 179 |
| 1212.0 | Appliance Connections to Building Piping | 172 | Table 1216.2(2) | Schedule 40 Metallic Pipe | 180 |
| 1212.1 | Connecting Gas Appliances | 172 | Table 1216.2(3) | Schedule 40 Metallic Pipe | 181 |
| | | | Table 1216.2(4) | Schedule 40 Metallic Pipe | 182 |

| | | |
|------------------|---|-----|
| Table 1216.2(5) | Schedule 40 Metallic Pipe | 183 |
| Table 1216.2(6) | Schedule 40 Metallic Pipe | 184 |
| Table 1216.2(7) | Semi-Rigid Copper Tubing | 185 |
| Table 1216.2(8) | Semi-Rigid Copper Tubing | 186 |
| Table 1216.2(9) | Semi-Rigid Copper Tubing | 187 |
| Table 1216.2(10) | Semi-Rigid Copper Tubing | 188 |
| Table 1216.2(11) | Semi-Rigid Copper Tubing | 189 |
| Table 1216.2(12) | Semi-Rigid Copper Tubing | 190 |
| Table 1216.2(13) | Semi-Rigid Copper Tubing | 191 |
| Table 1216.2(14) | Corrugated Stainless Steel Tubing (CSST) | 192 |
| Table 1216.2(15) | Corrugated Stainless Steel Tubing (CSST) | 193 |
| Table 1216.2(16) | Corrugated Stainless Steel Tubing (CSST) | 194 |
| Table 1216.2(17) | Corrugated Stainless Steel Tubing (CSST) | 195 |
| Table 1216.2(18) | Corrugated Stainless Steel Tubing (CSST) | 196 |
| Table 1216.2(19) | Polyethylene Plastic Pipe | 197 |
| Table 1216.2(20) | Polyethylene Plastic Pipe | 198 |
| Table 1216.2(21) | Polyethylene Plastic Pipe | 199 |
| Table 1216.2(22) | Polyethylene Plastic Tubing | 200 |
| Table 1216.2(23) | Polyethylene Plastic Tubing | 200 |
| Table 1216.2(24) | Schedule 40 Metallic Pipe | 201 |
| Table 1216.2(25) | Schedule 40 Metallic Pipe | 202 |
| Table 1216.2(26) | Schedule 40 Metallic Pipe | 203 |
| Table 1216.2(27) | Schedule 40 Metallic Pipe | 204 |
| Table 1216.2(28) | Semi-Rigid Copper Tubing | 205 |
| Table 1216.2(29) | Semi-Rigid Copper Tubing | 206 |
| Table 1216.2(30) | Semi-Rigid Copper Tubing | 207 |
| Table 1216.2(31) | Corrugated Stainless Steel Tubing (CSST) | 208 |
| Table 1216.2(32) | Corrugated Stainless Steel Tubing (CSST) | 209 |
| Table 1216.2(33) | Corrugated Stainless Steel Tubing (CSST) | 210 |
| Table 1216.2(34) | Polyethylene Plastic Pipe | 211 |
| Table 1216.2(35) | Polyethylene Plastic Pipe | 212 |
| Table 1216.2(36) | Polyethylene Plastic Tubing | 213 |

CHAPTER 13 HEALTH CARE FACILITIES AND MEDICAL GAS AND MEDICAL VACUUM SYSTEMS215

| | | |
|---------------|-----------------------------|------------|
| PART I | General Requirements | 215 |
| 1301.0 | General | 215 |
| 1301.1 | Applicability | 215 |
| 1301.2 | Where Not Applicable | 215 |
| 1301.3 | Conflict of Requirements | 215 |
| 1301.4 | Terms | 215 |

| | | |
|--------------|---|-----|
| 1301.5 | Where Required | 215 |
| 1301.6 | Existing Systems | 215 |
| 1302.0 | Design Requirements | 215 |
| 1302.1 | Building System Categories | 215 |
| 1302.2 | Patient Care Rooms | 215 |
| 1302.3 | Anesthetizing Locations | 215 |
| 1302.4 | Wet Procedure Locations | 215 |
| 1303.0 | Health Care Facilities | 215 |
| 1303.1 | Drinking Fountain Control Valves | 215 |
| 1303.2 | Psychiatric Patient Rooms | 215 |
| 1303.3 | Locations for Ice Storage | 215 |
| 1303.4 | Sterilizers and Bedpan Steamers | 215 |
| 1303.5 | Aspirators | 216 |
| 1303.6 | Drains | 216 |
| 1303.7 | Clinical Sinks | 216 |
| 1303.8 | Water Supply for Hospitals | 216 |
| 1304.0 | Medical Gas and Medical Vacuum Piping Systems | 216 |
| 1304.1 | General | 216 |
| 1304.2 | Manufacturer's Instructions | 216 |
| 1304.3 | Supply Source | 216 |
| 1304.4 | Certification of Systems | 216 |
| 1304.5 | Construction Documents | 216 |
| 1305.0 | System Performance | 216 |
| 1305.1 | Required Operating Pressures | 216 |
| 1305.2 | Minimum Flow Rates | 216 |
| 1305.3 | Minimum Station Outlets and Inlets | 216 |
| Table 1305.1 | Standard Designation Colors and Operating Pressures for Medical Gas and Medical Vacuum Systems | 217 |
| Table 1305.2 | Minimum Flow Rates | 217 |
| 1306.0 | Qualifications of Installers | 217 |
| 1306.1 | General | 217 |
| 1306.2 | Brazing | 217 |
| Table 1305.3 | Minimum Outlets and Inlets Per Station | 218 |
| 1306.3 | Health Care Organization Personnel | 218 |
| 1307.0 | Brazing Procedures | 218 |
| 1307.1 | General | 218 |
| 1307.2 | Examination | 218 |
| 1307.3 | Brazing Procedure Specification | 218 |
| 1307.4 | Documentation | 218 |
| 1307.5 | Procedures | 218 |
| 1307.6 | Conditions of Acceptance | 218 |
| 1307.7 | Qualifications | 218 |

| | | |
|-------------------|---|-----|
| PART II | Medical Gas and Medical Vacuum System Piping | 219 |
| 1308.0 | Pipe Materials | 219 |
| 1308.1 | General | 219 |
| 1308.2 | Cleaning | 219 |
| 1308.3 | Delivery | 219 |
| 1308.4 | Tubes for Medical Gas Systems | 219 |
| 1308.5 | Tubes for Medical Vacuum Systems | 219 |
| 1309.0 | Joints and Connections | 219 |
| 1309.1 | General | 219 |
| 1309.2 | Changes in Direction | 219 |
| 1309.3 | Brazed Joints and Fittings | 219 |
| 1309.4 | Special Fittings | 222 |
| 1309.5 | Welded Joints | 222 |
| 1309.6 | Prohibited Joints | 223 |
| 1310.0 | Installation of Piping | 223 |
| 1310.1 | General | 223 |
| 1310.2 | Required Pipe Sizing | 223 |
| Table 1310.2.1(1) | System Sizing – Flow Requirements for Station Outlets and Inlets | 223 |
| Table 1310.2.2(1) | Maximum Permitted Pressure Loss in Medical Gas and Medical Vacuum Systems | 224 |
| 1310.3 | Pipe Protection | 224 |
| 1310.4 | Location of Piping | 224 |
| 1310.5 | Pipe Support | 224 |
| Table 1310.5.4(1) | Maximum Metallic Pipe Support Spacing | 224 |
| Table 1310.5.4(2) | Maximum Plastic Pipe Support Spacing | 225 |
| 1310.6 | Backfilling and Trenching | 225 |
| 1310.7 | Connectors | 225 |
| 1310.8 | Prohibited System Interconnections | 225 |
| 1310.9 | Changes in System Use | 225 |
| Table 1310.2.1(2) | Pressure Loss for Medical Air | 226 |
| Table 1310.2.1(3) | Pressure Loss for Nitrogen | 226 |
| Table 1310.2.1(4) | Pressure Loss for Nitrous Oxide and Carbon Dioxide | 227 |
| Table 1310.2.1(5) | Pressure Loss for Oxygen | 227 |
| Table 1310.2.1(6) | Pressure Loss for Vacuum | 228 |
| Table 1310.2.1(7) | Pressure Loss for Vacuum (Category 3) | 229 |
| 1310.10 | Breaching or Penetrating Medical Gas Piping | 230 |
| 1310.11 | Labeling and Identification | 230 |

| | | |
|-----------------|--|-----|
| 1311.0 | Cleaning for Medical Gas Piping Systems | 231 |
| 1311.1 | Cleaning | 231 |
| 1311.2 | Contaminated Materials | 231 |
| 1312.0 | Shutoff Valves | 231 |
| 1312.1 | General | 231 |
| 1312.2 | Source Valves | 231 |
| 1312.3 | Main Valves | 231 |
| 1312.4 | Riser Valves | 231 |
| 1312.5 | Service Valves | 231 |
| 1312.6 | Zone Valves | 232 |
| 1312.7 | In-Line Shutoff Valves | 232 |
| 1312.8 | Future Piping | 232 |
| 1312.9 | Identification | 232 |
| PART III | Systems, Equipment, and Components | 233 |
| 1313.0 | Central Supply Systems | 233 |
| 1313.1 | General | 233 |
| 1314.0 | Medical Air Systems | 233 |
| 1314.1 | Medical Air Compressors | 233 |
| 1314.2 | Medical Air Receivers | 234 |
| 1315.0 | Medical Vacuum System | 234 |
| 1315.1 | General | 234 |
| 1315.2 | Medical-Surgical Vacuum Sources | 235 |
| 1315.3 | Vacuum Pumps | 235 |
| 1315.4 | Vacuum Receivers | 235 |
| 1315.5 | Vacuum Source Exhausts | 235 |
| 1316.0 | Pressure-Regulating Equipment | 235 |
| 1316.1 | Where Required | 235 |
| 1316.2 | Pressure-Relief Valves | 235 |
| 1316.3 | Pressure Gauges | 235 |
| 1317.0 | Station Outlets and Inlets | 236 |
| 1317.1 | General | 236 |
| 1317.2 | Required Valves | 236 |
| 1317.3 | Post Installation | 236 |
| 1317.4 | Identification | 236 |
| 1318.0 | Warning Systems | 236 |
| 1318.1 | Category 1 and 2 Systems | 236 |
| 1318.2 | Category 3 Systems | 236 |
| 1318.3 | Components | 237 |
| PART IV | Testing, Inspection and Certification | 237 |
| 1319.0 | Testing and Inspection | 237 |
| 1319.1 | Where Required | 237 |
| 1319.2 | Breached Systems | 237 |
| 1319.3 | Reports | 237 |

| | | |
|---------------|---|-----|
| 1319.4 | Initial Piping Blow Down | 237 |
| 1319.5 | Initial Pressure Tests – Medical Gas and Medical Vacuum Systems | 237 |
| 1319.6 | Cross-Connection Tests – Medical Gas and Medical Vacuum Systems | 237 |
| 1319.7 | Standing Pressure Tests – Medical Gas Piping Systems . . . | 238 |
| 1319.8 | Standing Pressure Tests – Medical Vacuum Piping Systems | 238 |
| 1319.9 | Purge Tests | 238 |
| 1319.10 | Operational Pressure Test | 238 |
| 1319.11 | Medical Gas Concentration Test | 239 |
| Table 1319.11 | Gas Concentrations | 239 |
| 1319.12 | System Verification | 239 |
| 1320.0 | System Certification | 239 |
| 1320.1 | Certification | 239 |
| 1320.2 | Certification Tests | 239 |
| 1320.3 | Report Items | 239 |

CHAPTER 14 FIRESTOP PROTECTION241

| | | |
|--------|--|-----|
| 1401.0 | General | 241 |
| 1401.1 | Applicability | 241 |
| 1402.0 | Construction Documents | 241 |
| 1402.1 | Penetrations | 241 |
| 1403.0 | Installation | 241 |
| 1403.1 | Materials | 241 |
| 1404.0 | Combustible Piping Installations | 241 |
| 1404.1 | General Requirements | 241 |
| 1404.2 | Fire-Resistance Rating | 241 |
| 1404.3 | Firestop Systems | 241 |
| 1404.4 | Connections | 241 |
| 1404.5 | Insulation and Coverings | 241 |
| 1404.6 | Sleeves | 241 |
| 1405.0 | Noncombustible Piping Installations | 241 |
| 1405.1 | General Requirements | 241 |
| 1405.2 | Fire-Resistance Rating | 241 |
| 1405.3 | Firestop Systems | 241 |
| 1405.4 | Connections | 242 |
| 1405.5 | Unshielded Couplings | 242 |
| 1405.6 | Sleeves | 242 |
| 1405.7 | Insulation and Coverings | 242 |
| 1406.0 | Required Inspection | 242 |

| | | |
|--------|-------------------------------|-----|
| 1406.1 | General | 242 |
| 1406.2 | Examination | 242 |
| 1406.3 | Penetrations | 242 |
| 1406.4 | Field Installations | 242 |

CHAPTER 15

**ALTERNATE WATER SOURCES
FOR NONPOTABLE
APPLICATIONS243**

| | | |
|---------------|--|-----|
| 1501.0 | General | 243 |
| 1501.1 | Applicability | 243 |
| 1501.2 | System Design | 243 |
| 1501.3 | Permit | 243 |
| 1501.4 | Component Identification | 243 |
| 1501.5 | Maintenance and Inspection . . . | 243 |
| 1501.6 | Operation and Maintenance Manual | 243 |
| 1501.7 | Minimum Water Quality Requirements | 243 |
| 1501.8 | Material Compatibility | 243 |
| 1501.9 | System Controls | 243 |
| 1501.10 | Commercial, Industrial, and Institutional Restroom Signs | 243 |
| Table 1501.5 | Minimum Alternate Water Source Testing, Inspection, and Maintenance Frequency . . . | 244 |
| 1501.11 | Inspection and Testing | 244 |
| 1501.12 | Separation Requirements | 245 |
| 1501.13 | Abandonment | 245 |
| 1501.14 | Sizing | 245 |
| 1502.0 | Gray Water Systems | 245 |
| 1502.1 | General | 245 |
| 1502.2 | System Requirements | 245 |
| 1502.3 | Connections to Potable and Reclaimed (Recycled) Water Systems | 246 |
| 1502.4 | Location | 246 |
| 1502.5 | Plot Plan Submission | 246 |
| 1502.6 | Prohibited Location | 246 |
| 1502.7 | Drawings and Specifications . . . | 246 |
| Table 1502.4 | Location of Gray Water System . . | 246 |
| 1502.8 | Procedure for Estimating Gray Water Discharge | 247 |
| 1502.9 | Gray Water System Components | 247 |
| 1502.10 | Subsurface Irrigation System Zones | 248 |
| Table 1502.10 | Design of Six Typical Soils | 248 |
| 1502.11 | Subsurface and Subsoil Irrigation Field, and Mulch Basin Design and Construction . . | 248 |

| | | |
|-----------------|---|-----|
| Table 1502.11 | Subsurface Irrigation Design Criteria for Six Typical Soils | 249 |
| Table 1502.11.3 | Subsoil Irrigation Field Construction | 249 |
| 1502.12 | Gray Water System Color and Marking Information | 250 |
| 1502.13 | Other Collection and Distribution Systems | 250 |
| 1502.14 | Testing | 250 |
| 1502.15 | Maintenance | 250 |
| 1503.0 | Reclaimed (Recycled) Water Systems | 250 |
| 1503.1 | General | 250 |
| 1503.2 | Permit | 250 |
| 1503.3 | System Changes | 250 |
| 1503.4 | Connections to Potable or Reclaimed (Recycled) Water Systems | 250 |
| 1503.5 | Initial Cross-Connection Test . . . | 250 |
| 1503.6 | Reclaimed (Recycled) Water System Materials | 250 |
| 1503.7 | Reclaimed (Recycled) Water System Color and Marking Information | 250 |
| 1503.8 | Valves | 250 |
| 1503.9 | Hose Bibbs | 250 |
| 1503.10 | Required Appurtenances | 250 |
| 1503.11 | Same Trench as Potable Water Pipes | 251 |
| 1503.12 | Signs | 251 |
| 1503.13 | Inspection and Testing | 251 |
| 1504.0 | On-Site Treated Nonpotable Water Systems | 251 |
| 1504.1 | General | 251 |
| 1504.2 | Plumbing Plan Submission | 251 |
| 1504.3 | System Changes | 251 |
| 1504.4 | Connections to Potable or Reclaimed (Recycled) Water Systems | 251 |
| 1504.5 | Initial Cross-Connection Test . . . | 251 |
| 1504.6 | On-Site Treated Nonpotable Water System Materials | 251 |
| 1504.7 | On-Site Treated Nonpotable Water Devices and Systems . . . | 251 |
| 1504.8 | On-Site Treated Nonpotable Water System Color and Marking Information | 251 |
| 1504.9 | Valves | 251 |
| 1504.10 | Design and Installation | 251 |
| 1504.11 | Signs | 252 |
| 1504.12 | Inspection and Testing | 252 |

CHAPTER 16

| | | |
|----------------|---|-----|
| 1601.0 | General | 253 |
| 1601.1 | Applicability | 253 |
| 1601.2 | System Design | 253 |
| 1601.3 | Permit | 253 |
| 1601.4 | Component Identification | 253 |
| 1601.5 | Maintenance and Inspection . . . | 253 |
| Table 1601.5 | Minimum Alternate Water Source Testing, Inspection, and Maintenance Frequency . . . | 253 |
| 1601.6 | Operation and Maintenance Manual | 254 |
| 1601.7 | Minimum Water Quality Requirements | 254 |
| 1601.8 | Material Compatibility | 254 |
| 1601.9 | System Controls | 254 |
| 1601.10 | Separation Requirements | 254 |
| 1601.11 | Abandonment | 254 |
| 1601.12 | Sizing | 254 |
| 1602.0 | Nonpotable Rainwater Catchment Systems | 254 |
| 1602.1 | General | 254 |
| 1602.2 | Plumbing Plan Submission | 254 |
| 1602.3 | System Changes | 254 |
| 1602.4 | Connections to Potable or Reclaimed (Recycled) Water Systems | 254 |
| 1602.5 | Initial Cross-Connection Test . . . | 254 |
| 1602.6 | Sizing | 255 |
| 1602.7 | Rainwater Catchment System Materials | 255 |
| 1602.8 | Rainwater Catchment System Color and Marking Information . . | 255 |
| 1602.9 | Design and Installation | 255 |
| Table 1602.9.4 | Minimum Water Quality | 256 |
| 1602.10 | Signs | 257 |
| 1602.11 | Inspection and Testing | 257 |

CHAPTER 17

| | | |
|--------|---------------------|-----|
| 1701.0 | General | 259 |
| 1701.1 | Standards | 259 |

APPENDICES

| | | |
|------------|---|-----|
| Appendix A | Recommended Rules for Sizing the Water Supply System | 285 |
| Appendix B | Explanatory Notes on Combination Waste and Vent Systems | 295 |

NONPOTABLE RAINWATER CATCHMENT SYSTEMS253

TABLE OF CONTENTS283

| | | |
|--------------|---|------------|
| Appendix C | Alternate Plumbing Systems | 297 |
| Appendix D | Sizing Storm Water Drainage Systems | 305 |
| Appendix E | Manufactured/Mobile Home Parks and Recreational Vehicle Parks | 313 |
| Appendix F | Firefighter Breathing Air Replenishment Systems | 323 |
| Appendix G | Sizing of Venting Systems | 327 |
| Appendix H | Private Sewage Disposal Systems | 337 |
| Appendix I | Installation Standard | 347 |
| Appendix J | Combination of Indoor and Outdoor Combustion and Ventilation Opening Design | 355 |
| Appendix K | Potable Rainwater Catchment Systems | 357 |
| Appendix L | Sustainable Practices | 363 |
| INDEX | | 383 |

CHAPTER 1

ADMINISTRATION

101.0 General.

101.1 Title. This document shall be known as the "Uniform Plumbing Code," may be cited as such, and will be referred to herein as "this code."

101.2 Scope. The provisions of this code shall apply to the erection, installation, alteration, repair, relocation, replacement, addition to, use, or maintenance of plumbing systems within this jurisdiction.

101.3 Purpose. This code is an ordinance providing minimum requirements and standards for the protection of the public health, safety, and welfare.

» **101.4 Unconstitutional.** Where a section, subsection, sentence, clause, or phrase of this code is, for a reason, held to be unconstitutional, such decision shall not affect the validity of the remaining portions of this code. The legislative body hereby declares that it would have passed this code, and each section, subsection, sentence, clause, or phrase thereof, irrespective of the fact that one or more sections, subsections, sentences, clauses, and phrases are declared unconstitutional.

» **101.5 Validity.** Where a provision of this code, or the application thereof to a person or circumstance, is held invalid, the remainder of the code, or the application of such provision to other persons or circumstances, shall not be affected thereby.

102.0 Applicability.

» **102.1 Conflicts Between Codes.** Where the requirements within the jurisdiction of this plumbing code conflict with the requirements of the mechanical code, this code shall prevail. In instances where this code, applicable standards, or the manufacturer's installation instructions conflict, the more stringent provisions shall prevail. Where there is a conflict between a general requirement and a specific requirement, the specific requirement shall prevail.

» **102.2 Existing Installations.** Plumbing systems lawfully in existence at the time of the adoption of this code shall be permitted to have their use, maintenance, or repair continued where the use, maintenance, or repair is in accordance with the original design and location and no hazard to life, health, or property has been created by such plumbing system.

» **102.3 Maintenance.** The plumbing and drainage system, both existing and new, of a premises under the Authority Having Jurisdiction shall be maintained in a sanitary and safe operating condition. Devices or safeguards required by this code shall be maintained in accordance with the code edition under which installed.

The owner or the owner's designated agent shall be responsible for maintenance of plumbing systems. To determine compliance with this subsection, the Authority Having Jurisdiction shall be permitted to cause a plumbing system to be reinspected.

102.4 Additions, Alterations, Renovations, or Repairs. Additions, alterations, renovations or repairs shall conform to that required for a new system without requiring the existing plumbing system to be in accordance with the requirements of this code. Additions, alterations, renovations, or repairs shall not cause an existing system to become unsafe, insanitary, or overloaded.

Additions, alterations, renovations, or repairs to existing plumbing installations shall comply with the provisions for new construction, unless such deviations are found to be necessary and are first approved by the Authority Having Jurisdiction.

102.4.1 Building Sewers and Drains. Existing building sewers and building drains shall be permitted to be used in connection with new buildings or new plumbing and drainage work where they are found on examination and test to be in accordance with the requirements governing new work, and the proper Authority Having Jurisdiction shall notify the owner to make changes necessary to be in accordance with this code. No building, or part thereof, shall be erected or placed over a part of a drainage system that is constructed of materials other than those approved elsewhere in this code for use under or within a building.

102.4.2 Openings. Openings into a drainage or vent system, excepting those openings to which plumbing fixtures are properly connected or which constitute vent terminals, shall be permanently plugged or capped in an approved manner, using the appropriate materials in accordance with this code.

102.5 Health and Safety. Where compliance with the provisions of this code fail to eliminate or alleviate a nuisance, or other dangerous or insanitary condition that involves health or safety hazards, the owner or the owner's agent shall install such additional plumbing and drainage facilities or shall make such repairs or alterations as ordered by the Authority Having Jurisdiction.

102.6 Changes in Building Occupancy. Plumbing systems that are a part of a building or structure undergoing a change in use or occupancy, as defined in the building code, shall be in accordance with the requirements of this code that are applicable to the new use or occupancy.

102.7 Moved Structures. Parts of the plumbing system of a building or part thereof that is moved from one foundation to another, or from one location to another, shall be in accordance with the provisions of this code for new installations and completely tested as prescribed elsewhere in this section for new work, except that walls or floors need not be removed during such test where other equivalent means of inspection acceptable to the Authority Having Jurisdiction are provided.

102.8 Appendices. The provisions in the appendices are intended to supplement the requirements of this code and shall not be considered part of this code unless formally adopted as such.

» **103.0 Duties and Powers of the Authority Having Jurisdiction.**

- » **103.1 General.** The Authority Having Jurisdiction shall be the Authority duly appointed to enforce this code. For such purposes, the Authority Having Jurisdiction shall have the powers of a law enforcement officer. The Authority Having Jurisdiction shall have the power to render interpretations of this code and to adopt and enforce rules and regulations supplemental to this code as deemed necessary in order to clarify the application of the provisions of this code. Such interpretations, rules, and regulations shall comply with the intent and purpose of this code.

In accordance with the prescribed procedures and with the approval of the appointing authority, the Authority Having Jurisdiction shall be permitted to appoint such number of technical officers, inspectors, and other employees as shall be authorized from time to time. The Authority Having Jurisdiction shall be permitted to deputize such inspectors or employees as necessary to carry out the functions of the code enforcement agency.

The Authority Having Jurisdiction shall be permitted to request the assistance and cooperation of other officials of this jurisdiction so far as required in the discharge of the duties in accordance with this code or other pertinent law or ordinance.

- » **103.2 Liability.** The Authority Having Jurisdiction charged with the enforcement of this code, acting in good faith and without malice in the discharge of the Authority Having Jurisdiction's duties, shall not thereby be rendered personally liable for damage that accrues to persons or property as a result of an act or by reason of an act or omission in the discharge of duties. A suit brought against the Authority Having Jurisdiction or employee because of such act or omission performed in the enforcement of provisions of this code shall be defended by legal counsel provided by this jurisdiction until final termination of such proceedings.

- » **103.3 Applications and Permits.** The Authority Having Jurisdiction shall be permitted to require the submission of plans, specifications, drawings, and such other information in accordance with the Authority Having Jurisdiction, prior to the commencement of, and at a time during the progress of, work regulated by this code.

The issuance of a permit upon construction documents shall not prevent the Authority Having Jurisdiction from thereafter requiring the correction of errors in said construction documents or from preventing construction operations being carried on thereunder where in violation of this code or of other pertinent ordinance or from revoking a certificate of approval where issued in error.

- » **103.3.1 Licensing.** Provision for licensing shall be determined by the Authority Having Jurisdiction.

- » **103.4 Right of Entry.** Where it is necessary to make an inspection to enforce the provisions of this code, or where the Authority Having Jurisdiction has reasonable cause to believe that there exists in a building or upon a premises a condition or violation of this code that makes the building or premises unsafe, insanitary, dangerous, or hazardous, the Authority

Having Jurisdiction shall be permitted to enter the building or premises at reasonable times to inspect or to perform the duties imposed upon the Authority Having Jurisdiction by this code, provided that where such building or premises is occupied, the Authority Having Jurisdiction shall present credentials to the occupant and request entry. Where such building or premises is unoccupied, the Authority Having Jurisdiction shall first make a reasonable effort to locate the owner or other person having charge or control of the building or premises and request entry. Where entry is refused, the Authority Having Jurisdiction has recourse to every remedy provided by law to secure entry.

Where the Authority Having Jurisdiction shall have first obtained an inspection warrant or other remedy provided by law to secure entry, no owner, occupant, or person having charge, care, or control of a building or premises shall fail or neglect, after a request is made as herein provided, to promptly permit entry herein by the Authority Having Jurisdiction for the purpose of inspection and examination pursuant to this code.

104.0 Permits.

104.1 Permits Required. It shall be unlawful for a person, firm, or corporation to make an installation, alteration, repair, replacement, or remodel a plumbing system regulated by this code except as permitted in Section 104.2, or to cause the same to be done without first obtaining a separate plumbing permit for each separate building or structure.

104.2 Exempt Work. A permit shall not be required for the following:

- (1) The stopping of leaks in drains, soil, waste, or vent pipe, provided, however, that a trap, drain pipe, soil, waste, or vent pipe become defective and it becomes necessary to remove and replace the same with new material, the same shall be considered as new work and a permit shall be procured and inspection made as provided in this code.
- (2) The clearing of stoppages, including the removal and reinstallation of water closets, or the repairing of leaks in pipes, valves, or fixtures, provided such repairs do not involve or require the replacement or rearrangement of valves, pipes, or fixtures.

Exemption from the permit requirements of this code shall not be deemed to grant authorization for work to be done in violation of the provisions of the code or other laws or ordinances of this jurisdiction.

104.3 Application for Permit. To obtain a permit, the applicant shall first file an application therefore in writing on a form furnished by the Authority Having Jurisdiction for that purpose. Such application shall:

- (1) Identify and describe the work to be covered by the permit for which application is made.
- (2) Describe the land upon which the proposed work is to be done by legal description, street address, or similar description that will readily identify and definitely locate the proposed building or work.

- (3) Indicate the use or occupancy for which the proposed work is intended.
- (4) Be accompanied by construction documents in accordance with Section 104.3.1.
- (5) Be signed by the permittee or the permittee's authorized agent. The Authority Having Jurisdiction shall be permitted to require evidence to indicate such authority.
- (6) Give such other data and information in accordance with the Authority Having Jurisdiction.

104.3.1 Construction Documents. Construction documents, engineering calculations, diagrams, and other data shall be submitted in two or more sets with each application for a permit. The construction documents, computations, and specifications shall be prepared by, and the plumbing designed by, a registered design professional. Construction documents shall be drawn to scale with clarity to identify that the intended work to be performed is in accordance with the code.

Exception: The Authority Having Jurisdiction shall be permitted to waive the submission of construction documents, calculations, or other data where the Authority Having Jurisdiction finds that the nature of the work applied for is such that reviewing of construction documents is not necessary to obtain compliance with the code.

104.3.2 Plan Review Fees. Where a plan or other data is required to be submitted in accordance with Section 104.3.1, a plan review fee shall be paid at the time of submitting construction documents for review.

The plan review fees for plumbing work shall be determined and adopted by this jurisdiction.

The plan review fees specified in this subsection are separate fees from the permit fees specified in Section 104.5.

Where plans are incomplete or changed so as to require additional review, a fee shall be charged at the rate shown in Table 104.5.

104.3.3 Time Limitation of Application. Applications for which no permit is issued within 180 days following the date of application shall expire by limitation, plans and other data submitted for review thereafter, shall be returned to the applicant or destroyed by the Authority Having Jurisdiction. The Authority Having Jurisdiction shall be permitted to exceed the time for action by the applicant for a period not to exceed 180 days upon request by the applicant showing that circumstances beyond the control of the applicant have prevented action from being taken. No application shall be extended more than once. In order to renew action on an application after expiration, the applicant shall resubmit plans and pay a new plan review fee.

104.4 Permit Issuance. The application, construction documents, and other data filed by an applicant for a permit shall be reviewed by the Authority Having Jurisdiction. Such plans shall be permitted to be reviewed by other departments of this jurisdiction to verify compliance with applicable laws under their jurisdiction. Where the Authority Having Jurisdiction

finds that the work described in an application for permit and the plans, specifications, and other data filed therewith are in accordance with the requirements of the code and other pertinent laws and ordinances, and that the fees specified in Section 104.5 have been paid, the Authority Having Jurisdiction shall issue a permit therefore to the applicant.

104.4.1 Approved Plans or Construction Documents. Where the Authority Having Jurisdiction issues the permit where plans are required, the Authority Having Jurisdiction shall endorse in writing or stamp the construction documents "APPROVED." Such approved construction documents shall not be changed, modified, or altered without authorization from the Authority Having Jurisdiction, and the work shall be done in accordance with approved plans.

The Authority Having Jurisdiction shall be permitted to issue a permit for the construction of a part of a plumbing system before the entire construction documents for the whole system have been submitted or approved, provided adequate information and detailed statements have been filed in accordance with the pertinent requirements of this code. The holder of such permit shall be permitted to proceed at the holder's risk without assurance that the permit for the entire building, structure, or plumbing system will be granted.

104.4.2 Validity of Permit. The issuance of a permit or approval of construction documents shall not be construed to be a permit for, or an approval of, a violation of the provisions of this code or other ordinance of the jurisdiction. No permit presuming to give authority to violate or cancel the provisions of this code shall be valid.

The issuance of a permit based upon plans, specifications, or other data shall not prevent the Authority Having Jurisdiction from thereafter requiring the correction of errors in said plans, specifications, and other data or from preventing building operations being carried on thereunder where in violation of this code or of other ordinances of this jurisdiction.

104.4.3 Expiration. A permit issued by the Authority Having Jurisdiction under the provisions of this code shall expire by limitation and become null and void where the work authorized by such permit is not commenced within 180 days from the date of such permit, or where the work authorized by such permit is suspended or abandoned at a time after the work is commenced for a period of 180 days. Before such work is recommenced, a new permit shall first be obtained to do so, and the fee therefore shall be one-half the amount required for a new permit for such work, provided no changes have been made or will be made in the original construction documents for such work, and provided further that such suspensions or abandonment has not exceeded 1 year.

104.4.4 Extensions. A permittee holding an unexpired permit shall be permitted to apply for an extension of the time within which work shall be permitted to commence under that permit where the permittee is unable to commence work within the time required by this section. The Authority Having Jurisdiction shall be permitted to

extend the time for action by the permittee for a period not exceeding 180 days upon written request by the permittee showing that circumstances beyond the control of the permittee have prevented action from being taken. No permit shall be extended more than once. In order to renew action on a permit after expiration, the permittee shall pay a new full permit fee.

» **104.4.5 Suspension or Revocation.** The Authority Having Jurisdiction shall be permitted to, in writing, suspend or revoke a permit issued under the provisions of this code where the permit is issued in error or on the basis of incorrect information supplied or in violation of other ordinance or regulation of the jurisdiction.

» **104.4.6 Retention of Plans.** One set of approved construction documents and computations shall be retained by the Authority Having Jurisdiction until final approval of the work covered therein.

One set of approved construction documents, computations, and manufacturer's installation instructions shall be returned to the applicant, and said set shall be kept on the site of the building or work at times during which the work authorized thereby is in progress.

» **104.5 Fees.** Fees shall be assessed in accordance with the provisions of this section and as set forth in the fee schedule, Table 104.5. The fees are to be determined and adopted by this jurisdiction.

» **104.5.1 Work Commencing Before Permit Issuance.** Where work for which a permit is required by this code has been commenced without first obtaining said permit, a special investigation shall be made before a permit is issued for such work.

» **104.5.2 Investigation Fees.** An investigation fee, in addition to the permit fee, shall be collected whether or not a permit is then or subsequently issued. The investigation fee shall be equal to the amount of the permit fee that is required by this code if a permit were to be issued. The payment of such investigation fee shall not exempt a person from compliance with other provisions of this code, nor from a penalty prescribed by law.

» **104.5.3 Fee Refunds.** The Authority Having Jurisdiction shall be permitted to authorize the refunding of a fee as follows:

- (1) The amount paid hereunder that was erroneously paid or collected.
- (2) Refunding of not more than a percentage, as determined by this jurisdiction where no work has been done under a permit issued in accordance with this code.

The Authority Having Jurisdiction shall not authorize the refunding of a fee paid except upon written application filed by the original permittee not to exceed 180 days after the date of fee payment.

» **105.0 Inspections and Testing.**

» **105.1 General.** Plumbing systems for which a permit is required by this code shall be inspected by the Authority Having Jurisdiction.

No plumbing system or portion thereof shall be covered, concealed, or put into use until inspected and approved as prescribed in this code. Neither the Authority Having Jurisdiction nor the jurisdiction shall be liable for expense entailed in the removal or replacement of material required to permit inspection. Plumbing systems regulated by this code shall not be connected to the water, the energy fuel supply, or the sewer system until authorized by the Authority Having Jurisdiction.

» **105.2 Required Inspections.** New plumbing work and such portions of existing systems as affected by new work, or changes, shall be inspected by the Authority Having Jurisdiction to ensure compliance with the requirements of this code and to ensure that the installation and construction of the plumbing system is in accordance with approved plans. The Authority Having Jurisdiction shall make the following inspections and other such inspections as necessary. The permittee or the permittee's authorized agent shall be responsible for the scheduling of such inspections as follows:

- (1) Underground inspection shall be made after trenches or ditches are excavated and bedded, piping installed, and before backfill is put in place.
- (2) Rough-in inspection shall be made prior to the installation of wall or ceiling membranes.
- (3) Final inspection shall be made upon completion of the installation.

» **105.2.1 Uncovering.** Where a drainage or plumbing system, building sewer, private sewage disposal system, or part thereof, which is installed, altered, or repaired, is covered or concealed before being inspected, tested, and approved as prescribed in this code, it shall be uncovered for inspection after notice to uncover the work has been issued to the responsible person by the Authority Having Jurisdiction.

The requirements of this section shall not be considered to prohibit the operation of plumbing installed to replace existing equipment or fixtures serving an occupied portion of the building in the event a request for inspection of such equipment or fixture has been filed with the Authority Having Jurisdiction not more than 72 hours after such replacement work is completed, and before a portion of such plumbing system is concealed by a permanent portion of the building.

» **105.2.1.1 Water Supply System.** No water supply system or portion thereof shall be covered or concealed until it first has been tested, inspected, and approved.

» **105.2.1.2 Covering or Using.** No plumbing or drainage system, building sewer, private sewer disposal system, or part thereof, shall be covered, concealed, or put into use until it has been tested, inspected, and accepted as prescribed in this code.

» **105.2.2 Other Inspections.** In addition to the inspections required by this code, the Authority Having Jurisdiction shall be permitted to require other inspections to ascertain compliance with the provisions of this code and other laws that are enforced by the Authority Having Jurisdiction.

- » **105.2.3 Inspection Requests.** It shall be the duty of the person doing the work authorized by a permit to notify the Authority Having Jurisdiction that such work is ready for inspection. The Authority Having Jurisdiction shall be permitted to require that a request for inspection be filed not less than 1 working day before such inspection is desired. Such request shall be permitted to be made in writing or by telephone, at the option of the Authority Having Jurisdiction.

It shall be the duty of the person requesting inspections in accordance with this code to provide access to and means for inspection of such work.

- » **105.2.4 Advance Notice.** It shall be the duty of the person doing the work authorized by the permit to notify the Authority Having Jurisdiction, orally or in writing, that said work is ready for inspection. Such notification shall be given not less than 24 hours before the work is to be inspected.
- » **105.2.5 Responsibility.** It shall be the duty of the holder of a permit to make sure that the work will stand the test prescribed before giving the notification.

The equipment, material, and labor necessary for inspection or tests shall be furnished by the person to whom the permit is issued or by whom inspection is requested.

- » **105.2.6 Reinspections.** A reinspection fee shall be permitted to be assessed for each inspection or reinspection where such portion of work for which inspection is called is not complete or where required corrections have not been made.

This provision shall not to be interpreted as requiring reinspection fees the first time a job is rejected for failure to be in accordance with the requirements of this code, but as controlling the practice of calling for inspections before the job is ready for inspection or reinspection.

Reinspection fees shall be permitted to be assessed where the approved plans are not readily available to the inspector, for failure to provide access on the date for which the inspection is requested, or for deviating from plans requiring the approval of the Authority Having Jurisdiction.

To obtain reinspection, the applicant shall file an application therefore in writing upon a form furnished for that purpose and pay the reinspection fee in accordance with Table 104.5.

In instances where reinspection fees have been assessed, no additional inspection of the work will be performed until the required fees have been paid.

- » **105.3 Testing of Systems.** Plumbing systems shall be tested and approved in accordance with this code or the Authority Having Jurisdiction. Tests shall be conducted in the presence of the Authority Having Jurisdiction or the Authority Having Jurisdiction's duly appointed representative.

No test or inspection shall be required where a plumbing system, or part thereof, is set up for exhibition purposes and has no connection with a water or drainage system. In cases

where it would be impractical to provide the required water or air tests, or for minor installations and repairs, the Authority Having Jurisdiction shall be permitted to make such inspection as deemed advisable in order to be assured that the work has been performed in accordance with the intent of this code. Joints and connections in the plumbing system shall be gastight and watertight for the pressures required by the test.

» **105.3.1 Defective Systems.** An air test shall be used in testing the sanitary condition of the drainage or plumbing system of building premises where there is reason to believe that it has become defective. In buildings or premises condemned by the Authority Having Jurisdiction because of an insanitary condition of the plumbing system, or part thereof, the alterations in such system shall be in accordance with the requirements of this code.

» **105.3.2 Retesting.** Where the Authority Having Jurisdiction finds that the work will not pass the test, necessary corrections shall be made, and the work shall be resubmitted for test or inspection.

» **105.3.3 Approval.** Where prescribed tests and inspections indicate that the work is in accordance with this code, a certificate of approval shall be issued by the Authority Having Jurisdiction to the permittee on demand.

» **105.4 Connection to Service Utilities.** No person shall make connections from a source of energy or fuel to a plumbing system or equipment regulated by this code and for which a permit is required until approved by the Authority Having Jurisdiction. No person shall make connection from a water-supply line nor shall connect to a sewer system regulated by this code and for which a permit is required until approved by the Authority Having Jurisdiction. The Authority Having Jurisdiction shall be permitted to authorize temporary connection of the plumbing equipment to the source of energy or fuel for the purpose of testing the equipment.

» **106.0 Violations and Penalties.**

» **106.1 General.** It shall be unlawful for a person, firm, or corporation to erect, construct, enlarge, alter, repair, move, improve, remove, convert, demolish, equip, use, or maintain plumbing or permit the same to be done in violation of this code.

» **106.2 Notices of Correction or Violation.** Notices of correction or violation shall be written by the Authority Having Jurisdiction and shall be permitted to be posted at the site of the work or mailed or delivered to the permittee or their authorized representative.

Refusal, failure, or neglect to comply with such notice or order within 10 days of receipt thereof, shall be considered a violation of this code and shall be subject to the penalties set forth by the governing laws of the jurisdiction.

» **106.3 Penalties.** A person, firm, or corporation violating a provision of this code shall be deemed guilty of a misdemeanor, and upon conviction thereof, shall be punishable by a fine, imprisonment, or both set forth by the governing laws of the jurisdiction. Each separate day or portion thereof, during which a violation of this code occurs or continues, shall be deemed to constitute a separate offense.

- » **106.4 Stop Orders.** Where work is being done contrary to the provisions of this code, the Authority Having Jurisdiction shall be permitted to order the work stopped by notice in writing served on persons engaged in the doing or causing such work to be done, and such persons shall forthwith stop work until authorized by the Authority Having Jurisdiction to proceed with the work.
- » **106.5 Authority to Disconnect Utilities in Emergencies.** The Authority Having Jurisdiction shall have the authority to disconnect a plumbing system to a building, structure, or equipment regulated by this code in case of emergency where necessary to eliminate an immediate hazard to life or property.
- » **106.6 Authority to Condemn.** Where the Authority Having Jurisdiction ascertains that a plumbing system or portion thereof, regulated by this code, has become hazardous to life, health, or property, or has become insanitary, the Authority Having Jurisdiction shall order in writing that such plumbing either be removed or placed in a safe or sanitary condition. The order shall fix a reasonable time limit for compliance. No person shall use or maintain defective plumbing after receiving such notice.

Where such plumbing system is to be disconnected, written notice shall be given. In cases of immediate danger to life or property, such disconnection shall be permitted to be made immediately without such notice.

» **107.0 Board of Appeals.**

- | **107.1 General.** In order to hear and decide appeals of orders, decisions, or determinations made by the Authority Having Jurisdiction relative to the application and interpretations of this code, there shall be and is hereby created a Board of Appeals consisting of members who are qualified by experience and training to pass upon matters pertaining to plumbing design, construction, and maintenance and the public health aspects of plumbing systems and who are not employees of the jurisdiction. The Authority Having Jurisdiction shall be an ex-officio member and shall act as secretary to said board but shall have no vote upon a matter before the board. The Board of Appeals shall be appointed by the governing body and shall hold office at its pleasure. The board shall adopt rules of procedure for conducting its business and shall render decisions and findings in writing to the appellant with a duplicate copy to the Authority Having Jurisdiction.
- » **107.2 Limitations of Authority.** The Board of Appeals shall have no authority relative to interpretation of the administrative provisions of this code, nor shall the board be empowered to waive requirements of this code.

TABLE 104.5
PLUMBING PERMIT FEES

Permit Issuance

- | | | |
|---|---|--|
| 1. For issuing each permit | * | |
| 2. For issuing each supplemental permit | * | |

Unit Fee Schedule (in addition to Item 1 and Item 2 above)

- | | | |
|--|---|--|
| 1. For each plumbing fixture on one trap or a set of fixtures on one trap (including water, drainage piping, and backflow protection therefore) | * | |
| 2. For each building sewer and each trailer park sewer | * | |
| 3. Rainwater systems – per drain (inside building) | * | |
| 4. For each cesspool (where permitted) | * | |
| 5. For each private sewage disposal system | * | |
| 6. For each water heater, vent, or both | * | |
| 7. For each gas piping system of one to five outlets | * | |
| 8. For each additional gas piping system outlet, per outlet | * | |
| 9. For each industrial waste pretreatment interceptor, including its trap and vent, except kitchen-type grease interceptors functioning as fixture traps | * | |
| 10. For each installation, alteration, or repair of water piping, water treating equipment, or both | * | |
| 11. For each repair or alteration of drainage or vent piping, each fixture | * | |
| 12. For each lawn sprinkler system on one meter including backflow protection devices therefore | * | |
| 13. For atmospheric-type vacuum breakers not referenced in Item 12: | | |
| One to 5 | * | |
| Over 5, each | * | |
| 14. For each backflow protective device other than atmospheric-type vacuum breakers: | | |
| Two inches (50 mm) in diameter and smaller | * | |
| Over 2 inches (50 mm) in diameter | * | |
| 15. For each gray water system | * | |
| 16. For initial installation and testing for a reclaimed water system | * | |
| 17. For each annual cross-connection testing of a reclaimed water system (excluding initial test) | * | |
| 18. For each medical gas piping system serving one to five inlet(s)/outlet(s) for a specific gas | * | |
| 19. For each additional medical gas inlet(s)/outlet(s) | * | |

Other Inspections and Fees

- | | | |
|--|---|--|
| 1. Inspections outside of normal business hours | * | |
| 2. Reinspection fee | * | |
| 3. Inspections for which no fee is specifically indicated | * | |
| 4. Additional plan review required by changes, additions, or revisions to approved plans (minimum charge – ½ hour) | * | |

For SI units: 1 inch = 25 mm

* Jurisdiction will indicate their fees here.

CHAPTER 2

DEFINITIONS

201.0 General.

201.1 Applicability. For the purpose of this code, the following terms have the meanings indicated in this chapter.

No attempt is made to define ordinary words, which are used in accordance with their established dictionary meanings, except where a word has been used loosely and it is necessary to define its meaning as used in this code to avoid misunderstanding.

202.0 Definition of Terms.

202.1 General. The definitions of terms are arranged alphabetically according to the first word of the term.

203.0

— A —

ABS. Acrylonitrile-butadiene-styrene.

Accepted Engineering Practice. That which conforms to technical or scientific-based principles, tests, or standards that are accepted by the engineering profession.

Accessible. Where applied to a fixture, connection, appliance, or equipment, “accessible” means having access thereto, but which first may require the removal of an access panel, door, or similar obstruction.

Accessible, Readily. Having a direct access without the necessity of removing a panel, door, or similar obstruction.

Air Break. A physical separation which may be a low inlet into the indirect waste receptor from the fixture, appliance, or device indirectly connected.

Air Gap, Drainage. The unobstructed vertical distance through the free atmosphere between the lowest opening from a pipe, plumbing fixture, appliance, or appurtenance conveying waste to the flood-level rim of the receptor.

Air Gap, Water Distribution. The unobstructed vertical distance through the free atmosphere between the lowest opening from a pipe or faucet conveying potable water to the flood-level rim of a tank, vat, or fixture.

Alternate Water Source. Nonpotable source of water that includes but not limited to gray water, on-site treated nonpotable water, rainwater, and reclaimed (recycled) water.

Anchors. See Supports.

Anesthetizing Location. An area of a facility that has been designated to be used for the administration of general anesthesia. [NFPA 99:3.3.9]

Appliance. A device that utilizes an energy source to produce light, heat, power, refrigeration, or air conditioning. This definition also shall include a vented decorative appliance.

Appliance, Low-Heat. A fuel-burning appliance that produces a continuous flue gas temperature, at the point of entrance to the flue, of not more than 1000°F (538°C).

Appliance, Medium-Heat. A fuel-burning appliance that produces a continuous flue gas temperature, at the

point of entrance to the flue, of more than 1000°F (538°C) and less than 2000°F (1093°C).

Appliance Categorized Vent Diameter/Area. The minimum vent area/diameter permissible for Category I appliances to maintain a nonpositive vent static pressure where tested in accordance with nationally recognized standards. [NFPA 54:3.3.7]

Appliance Fuel Connector. An assembly of listed semi-rigid or flexible tubing and fittings to carry fuel between a fuel-piping outlet and a fuel-burning appliance.

Approved. Acceptable to the Authority Having Jurisdiction.

Approved Testing Agency. An organization primarily established for purposes of testing to approved standards and approved by the Authority Having Jurisdiction.

Area Drain. A receptor designed to collect surface or storm water from an open area.

Aspirator. A fitting or device supplied with water or other fluid under positive pressure that passes through an integral orifice or constriction, causing a vacuum.

Authority Having Jurisdiction. The organization, office, or individual responsible for enforcing the requirements of a code or standard, or for approving equipment, materials, installations, or procedures. The Authority Having Jurisdiction shall be a federal, state, local, or other regional department or an individual such as a plumbing official, mechanical official, labor department official, health department official, building official, or others having statutory authority. In the absence of a statutory authority, the Authority Having Jurisdiction may be some other responsible party. This definition shall include the Authority Having Jurisdiction’s duly authorized representative.

204.0

— B —

Backflow. The flow of water or other liquids, mixtures, or substances into the distributing pipes of a potable supply of water from sources other than its intended source. See Backpressure Backflow and Backsiphonage.

Backflow Connection. An arrangement whereby backflow can occur.

Backflow Preventer. A backflow prevention device, an assembly, or other method to prevent backflow into the potable water system.

Backpressure Backflow. Backflow due to an increased pressure above the supply pressure, which may be due to pumps, boilers, gravity, or other sources of pressure.

Backsiphonage. The flowing back of used, contaminated, or polluted water from a plumbing fixture or vessel into a water supply pipe due to a pressure less than atmospheric in such pipe. See Backflow.

Backwater Valve. A device installed in a drainage system to prevent reverse flow.

DEFINITIONS

Bathroom. A room equipped with a shower, bathtub, or combination bath/shower.

Bathroom, Half. A room equipped with only a water closet and lavatory.

Bathroom Group. Any combination of fixtures, not to exceed one water closet, two lavatories, either one bathtub or one combination bath/shower, and one shower, and may include a bidet and an emergency floor drain.

Battery of Fixtures. A group of two or more similar, adjacent fixtures that discharge into a common horizontal waste or soil branch.

Bedpan Steamer. A fixture that is used to sterilize bedpans by way of steam.

Boiler Blowoff. An outlet on a boiler to permit emptying or discharge of sediment.

Bonding Jumper. A reliable conductor to ensure the required electrical conductivity between metal parts required to be electrically connected. [NFPA 70:100(I)]

Bottle Filling Station. A plumbing fixture connected to the potable water distribution system and sanitary drainage system that is designed and intended for filling personal use drinking water bottles or containers not less than 10 inches (254 mm) in height. Such fixtures can be separate from or integral to a drinking fountain and can incorporate a water filter and a cooling system for chilling the drinking water.

Branch. A part of the piping system other than a main, riser, or stack.

Branch, Fixture. See Fixture Branch.

Branch, Horizontal. See Horizontal Branch.

Branch Vent. A vent connecting one or more individual vents with a vent stack or stack vent.

Building. A structure built, erected, and framed of component structural parts designed for the housing, shelter, enclosure, or support of persons, animals, or property of any kind.

Building Drain. That part of the lowest piping of a drainage system that receives the discharge from soil, waste, and other drainage pipes inside the walls of the building and conveys it to the building sewer beginning 2 feet (610 mm) outside the building wall.

Building Drain (Sanitary). A building drain that conveys sewage only.

Building Drain (Storm). A building drain that conveys storm water or other drainage, but no sewage.

Building Sewer. That part of the horizontal piping of a drainage system that extends from the end of the building drain and that receives the discharge of the building drain and conveys it to a public sewer, private sewer, private sewage disposal system, or other point of disposal.

Building Sewer (Combined). A building sewer that conveys both sewage and storm water or other drainage.

Building Sewer (Sanitary). A building sewer that conveys sewage only.

Building Sewer (Storm). A building sewer that conveys storm water or other drainage, but no sewage.

Building Subdrain. That portion of a drainage system that does not drain by gravity into the building sewer.

Building Supply. The pipe carrying potable water from the water meter or other source of water supply to a building or other point of use or distribution on the lot.

205.0

— C —

Category 1. Facility systems in which failure of such equipment or system is likely to cause major injury or death of patients or caregivers. [NFPA 99:4.1.1]

Category 2. Facility systems in which failure of such equipment is likely to cause minor injury to patients or caregivers. [NFPA 99:4.1.2]

Category 3. Facility systems in which failure of such equipment is not likely to cause injury to patients or caregivers, but can cause patient discomfort. [NFPA 99:4.1.3]

Category 3 Medical Vacuum System. A medical vacuum distribution system that can be either a wet system designed to remove liquids, air-gas, or solids from the treated area; or a dry system designed to trap liquids and solids before the service inlet and to accommodate air-gas only through the service inlet. [NFPA 99:3.3.23]

Certified Backflow Assembly Tester. A person who has shown competence to test and maintain backflow assemblies to the satisfaction of the Authority Having Jurisdiction.

Cesspool. A lined excavation in the ground that receives the discharge of a drainage system or part thereof, so designed as to retain the organic matter and solids discharging therein, but permitting the liquids to seep through the bottom and sides.

Chemical Waste. See Special Wastes.

Chimney. One or more passageways, vertical or nearly so, for conveying flue or vent gases to the outdoors. [NFPA 54:3.3.18]

Chimney, Factory-Built. A chimney composed of listed factory-built components assembled in accordance with the manufacturer's installation instructions to form the completed chimney. [NFPA 54:3.3.18.2]

Chimney, Masonry. A field-constructed chimney of solid masonry units, bricks, stones, listed masonry chimney units, or reinforced portland cement concrete, lined with suitable chimney flue liners. [NFPA 54:3.3.18.3]

Chimney, Metal. A chimney constructed of metal with a minimum thickness not less than 0.127 inch (3.23 mm) (No. 10 manufacturer's standard gauge) steel sheet.

Chimney Classifications:

Chimney, High-Heat Appliance-Type. A factory-built, masonry, or metal chimney suitable for removing the products of combustion from fuel-burning high-heat appliances producing combustion gases in excess of 2000°F (1093°C), measured at the appliance flue outlet.

Chimney, Low-Heat Appliance-Type. A factory-built, masonry, or metal chimney suitable for removing the products of combustion from fuel-burning low-heat

appliances producing combustion gases not in excess of 1000°F (538°C) under normal operating conditions, but capable of producing combustion gases of 1400°F (760°C) during intermittent forced firing for periods up to one hour. Temperatures are measured at the appliance flue outlet.

Chimney, Medium-Heat Appliance-Type. A factory-built, masonry, or metal chimney suitable for removing the products of combustion from fuel-burning medium-heat appliances producing combustion gases not in excess of 2000°F (1093°C), measured at the appliance flue outlet.

Chimney, Residential Appliance-Type. A factory-built or masonry chimney suitable for removing products of combustion from residential-type appliances producing combustion gases not in excess of 1000°F (538°C), measured at the appliance flue outlet. Factory-built Type HT chimneys have high-temperature thermal shock resistance.

Clarifier. See Interceptor (Clarifier).

Clear Water Waste. Cooling water and condensate drainage from refrigeration and air-conditioning equipment; cooled condensate from steam heating systems; and cooled boiler blowdown water.

Clinical Sink. A fixture that has the same flushing and cleansing characteristics of a water closet that is used to receive the wastes from a bedpan. Also known as a bedpan washer.

Coastal High Hazard Areas. An area within the flood hazard area that is subject to high velocity wave action, and shown on a Flood Insurance Rate Map or other flood hazard map as Zone V, VO, VE or V1-30.

Code. A standard that is an extensive compilation of provisions covering broad subject matter or that is suitable for adoption into law independently of other codes and standards.

Combination Temperature and Pressure-Relief Valve. A relief valve that actuates when a set temperature, pressure, or both is reached. Also known as a T&P Valve.

Combination Thermostatic/Pressure Balancing Valve. A mixing valve that senses outlet temperature and incoming hot and cold water pressure and compensates for fluctuations in incoming hot and cold water temperatures, pressures, or both to stabilize outlet temperatures.

Combination Waste and Vent System. A specially designed system of waste piping embodying the horizontal wet venting of one or more sinks or floor drains by means of a common waste and vent pipe, adequately sized to provide free movement of air above the flow line of the drain.

Combined Building Sewer. See Building Sewer (Combined).

Combustible Material. As pertaining to materials adjacent to or in contact with heat-producing appliances, vent connectors, gas vents, chimneys, steam and hot water pipes, and warm air ducts, materials made of or surfaced with wood, compressed paper, plant fibers, or other materials that are capable of being ignited and burned. Such material shall be considered combustible even though flame-proofed, fire-retardant treated, or plastered. [NFPA 54:3.3.67.1]

Common. That part of a plumbing system that is so designed and installed as to serve more than one appliance, fixture, building, or system.

Condensate. The liquid phase produced by condensation of a particular gas or vapor.

Conductor. A pipe inside the building that conveys storm water from the roof to a storm drain, combined building sewer, or other approved point of disposal.

Confined Space. A room or space having a volume less than 50 cubic feet per 1000 British thermal units per hour (Btu/h) (4.83 m³/kW) of the aggregate input rating of all fuel-burning appliances installed in that space.

Construction Documents. Plans, specifications, written, graphic, and pictorial documents prepared or assembled for describing the design, location, and physical characteristics of the elements of a project necessary for obtaining a permit.

Contamination. An impairment of the quality of the potable water that creates an actual hazard to the public health through poisoning or through the spread of disease by sewage, industrial fluids, or waste. Also defined as High Hazard.

Continuous Vent. A vertical vent that is a continuation of the drain to which it connects.

Continuous Waste. A drain connecting the compartments of a set of fixtures to a trap or connecting other permitted fixtures to a common trap.

Copper Alloy. A homogenous mixture of two or more metals in which copper is the primary component, such as brass and bronze.

CPVC. Chlorinated Polyvinyl Chloride.

Critical Care Area. See Patient Care Room. [NFPA 99:3.3.31]

Critical Level. The critical level (C-L or C/L) marking on a backflow prevention device or vacuum breaker is a point conforming to approved standards and established by the testing laboratory (usually stamped on the device by the manufacturer) that determines the minimum elevation above the flood-level rim of the fixture or receptor served at which the device may be installed. Where a backflow prevention device does not bear a critical level marking, the bottom of the vacuum breaker, combination valve, or the bottom of such approved device shall constitute the critical level.

Cross-Connection. A connection or arrangement, physical or otherwise, between a potable water supply system and a plumbing fixture or a tank, receptor, equipment, or device, through which it may be possible for nonpotable, used, unclean, polluted, and contaminated water, or other substances to enter into a part of such potable water system under any condition.

206.0

— D —

Debris Excluder. A device installed on the rainwater catchment conveyance system to prevent the accumulation of leaves, needles, or other debris in the system.

Department Having Jurisdiction. The Authority Having Jurisdiction, including any other law enforcement agency

DEFINITIONS

affected by a provision of this code, whether such agency is specifically named or not.

Design Flood Elevation. The elevation of the “design flood,” including wave height, relative to the datum specified on the community’s legally designated flood hazard map. In areas designated as Zone AO, the design flood elevation is the elevation of the highest existing grade of the building’s perimeter plus the depth number (in feet) specified on the flood hazard map. In areas designated as Zone AO where a depth number is not specified on the map, the depth number is taken as being equal to 2 feet (610 mm).

Developed Length. The length along the center line of a pipe and fittings.

Diameter. Unless specifically stated, “diameter” is the nominal diameter as designated commercially.

Direct-Vent Appliances. Appliances that are constructed and installed so that air for combustion is derived directly from the outdoors and flue gases are discharged to the outdoors. [NFPA 54:3.3.6.3]

Domestic Sewage. The liquid and water-borne wastes derived from the ordinary living processes, free from industrial wastes, and of such character as to permit satisfactory disposal, without special treatment, into the public sewer or by means of a private sewage disposal system.

Downspout. The rain leader from the roof to the building storm drain, combined building sewer, or other means of disposal located outside of the building. See Conductor and Leader.

Drain. A pipe that carries waste or waterborne wastes in a building drainage system.

Drainage System. Includes all the piping within public or private premises that conveys sewage, storm water, or other liquid wastes to a legal point of disposal, but does not include the mains of a public sewer system or a public sewage treatment or disposal plant.

Drinking Fountain. A plumbing fixture connected to the potable water distribution system and sanitary drainage system that provides drinking water in a flowing stream so that the user can consume water directly from the fixture without the use of accessories. Drinking fountains should also incorporate a bottle filling station, and can incorporate a water filter and a cooling system for chilling the drinking water.

Dry Vent. A vent that does not receive the discharge of any sewage or waste.

Durham System. A soil or waste system in which all piping is threaded pipe, tubing, or other such rigid construction, using recessed drainage fittings to correspond to the types of piping.

207.0

– E –

Effective Ground-Fault Current Path. An intentionally constructed, low-impedance electrically conductive path designed and intended to carry current under ground-fault

conditions from the point of a ground fault on a wiring system to the electrical supply source and that facilitates the operation of the overcurrent protective device or ground-fault detectors on high-impedance grounded systems. [NFPA 54:3.3.36]

Effective Opening. The minimum cross-sectional area at the point of water supply discharge measured or expressed in terms of: (1) diameter of a circle or (2) where the opening is not circular, the diameter of a circle of equivalent cross-sectional area. (This is applicable to an air gap)

Essentially Nontoxic Transfer Fluid. Essentially nontoxic at practically nontoxic, Toxicity Rating Class 1 (reference “Clinical Toxicology of Commercial Products” by Gosselin, Smith, Hodge, & Braddock).

Exam Room Sink. A sink used in the patient exam room of a medical or dental office with a primary purpose for the washing of hands.

Excess Flow Valve (EFV). A valve designed to activate where the fuel gas passing through it exceeds a prescribed flow rate. [NFPA 54:3.3.104.3]

Existing Work. A plumbing system or any part thereof that has been installed prior to the effective date of this code.

Expansion Joint. A fitting or arrangement of pipe and fittings that permits the contraction and expansion of a piping system.

208.0

– F –

F Rating. The time period that the penetration firestop system limits the spread of fire through the penetration, where tested in accordance with ASTM E814 or UL 1479.

Fixture Branch. A water supply pipe between the fixture supply pipe and the water distribution pipe.

Fixture Drain. The drain from the trap of a fixture to the junction of that drain with any other drain pipe.

Fixture Fitting. A device that controls and guides the flow of water.

Fixture Supply. A water supply pipe connecting the fixture with the fixture branch.

Fixture Unit. A quantity in terms of which the load-producing effects on the plumbing system of different kinds of plumbing fixtures are expressed on some arbitrarily chosen scale.

Flammable Vapor or Fumes. The concentration of flammable constituents in air that exceeds 25 percent of its lower flammability limit (LFL).

Flood Hazard Area. The greater of the following two areas:

- (1) The area within a floodplain subject to a 1 percent or greater chance of flooding in any given year.
- (2) The area designated as a flood hazard area on a community’s flood hazard map, or otherwise legally designated.

Flood Level. See Flooded.

Flood-Level Rim. The top edge of a receptor from which water overflows.

Flooded. A fixture is flooded where the liquid therein rises to the flood-level rim.

Flue Collar. That portion of an appliance designed for the attachment of a draft hood, vent connector, or venting system. [NFPA 54:3.3.46]

Flush Tank. A tank located above or integral with water closets, urinals, or similar fixtures for the purpose of flushing the usable portion of the fixture.

Flush Valve. A valve located at the bottom of a tank for the purpose of flushing water closets and similar fixtures.

Flushometer Tank. A tank integrated within an air accumulator vessel that is designed to discharge a predetermined quantity of water to fixtures for flushing purposes.

Flushometer Valve. A valve that discharges a predetermined quantity of water to fixtures for flushing purposes and is actuated by direct water pressure.

FOG Disposal System. A grease interceptor that reduces nonpetroleum fats, oils, and grease (FOG) in effluent by separation, mass, and volume reduction.

Fuel Gas. Natural, manufactured, liquefied petroleum, or a mixture of these.

Fuel Gas Quick-Disconnect. A hand-operated device that provides a means for connecting and disconnecting an appliance or an appliance connector to a gas supply and that is equipped with an automatic means to shut off the gas supply where the device is disconnected. [NFPA 54:3.3.29.3]

Fuel Gas Vent. A listed factory-made vent pipe and vent fittings for conveying flue gases to the outdoors.

Fuel Gas Venting System. A continuous open passage-way from the flue collar or draft hood of an appliance to the outdoors for the purpose of removing flue or vent gases. [NFPA 54:3.3.99.7]

209.0

— G —

Gang or Group Shower. Two or more showers in a common area.

Gas Piping. An installation of pipe, valves, or fittings that is used to convey fuel gas, installed on a premises or in a building, but shall not include:

- (1) A portion of the service piping.
- (2) An approved piping connection 6 feet (1829 mm) or less in length between an existing gas outlet and a gas appliance in the same room with the outlet.

Gas Piping System. An arrangement of gas piping or regulators after the point of delivery and each arrangement of gas piping serving a building, structure, or premises, whether individually metered or not.

General Care Areas. See Patient Care Room. [NFPA 99:3.3.64]

Governing Body. The person or persons who have the overall legal responsibility for the operation of a health care facility. [NFPA 99:3.3.65]

Grade. The slope or fall of a line of pipe in reference to a horizontal plane. In drainage, it is usually expressed as the fall in a fraction of an inch (mm) or percentage slope per foot (meter) length of pipe.

Gravity Grease Interceptor. A plumbing appurtenance or appliance that is installed in a sanitary drainage system to intercept nonpetroleum fats, oils, and greases (FOG) from a wastewater discharge and is identified by volume, 30 minute retention time, baffle(s), not less than two compartments, a total volume of not less than 300 gallons (1135 L), and gravity separation. [These interceptors comply with the requirements of Chapter 10 or are designed by a registered design professional.] Gravity grease interceptors are generally installed outside.

Gray Water. Untreated wastewater that has not come into contact with toilet waste, kitchen sink waste, dishwasher waste or similarly contaminated sources. Gray water includes wastewater from bathtubs, showers, lavatories, clothes washers, and laundry tubs. Also known as grey water, graywater, and greywater.

Gray Water Diverter Valve. A valve that directs gray water to the sanitary drainage system or to a subsurface irrigation system.

Grease Interceptor. A plumbing appurtenance or appliance that is installed in a sanitary drainage system to intercept nonpetroleum fats, oil, and greases (FOG) from a wastewater discharge.

Grease Removal Device (GRD). A hydromechanical grease interceptor that automatically, mechanically removes non-petroleum fats, oils and grease (FOG) from the interceptor, the control of which are either automatic or manually initiated.

Grounding Electrode. A conducting object through which a direct connection to earth is established. [NFPA 70:100(I)]

210.0

— H —

Hangers. See Supports.

Heat-Fusion Weld Joints. A joint used in some thermoplastic systems to connect pipe to fittings or pipe lengths directly to one another (butt-fusion). This method of joining pipe to fittings includes socket-fusion, electro-fusion, and saddle-fusion. This method of welding involves the application of heat and pressure to the components, allowing them to fuse together forming a bond between the pipe and fitting.

High Hazard. See Contamination.

Horizontal Branch. A drain pipe extending laterally from a soil or waste stack or building drain with or without vertical sections or branches, which receives the discharge from one or more fixture drains and conducts it to the soil or waste stack or to the building drain.

Horizontal Pipe. A pipe or fitting that is installed in a horizontal position or which makes an angle of less than 45 degrees (0.79 rad) with the horizontal.

Hot Water. Water at a temperature exceeding or equal to 120°F (49°C).

House Drain. See Building Drain.

DEFINITIONS

House Sewer. See Building Sewer.

Hydromechanical Grease Interceptor. A plumbing appurtenance or appliance that is installed in a sanitary drainage system to intercept nonpetroleum fats, oil, and grease (FOG) from a wastewater discharge and is identified by flow rate, and separation and retention efficiency. The design incorporates air entrainment, hydromechanical separation, interior baffling, or barriers in combination or separately, and one of the following:

- (1) External flow control, with air intake (vent), directly connected.
- (2) External flow control, without air intake (vent), directly connected.
- (3) Without external flow control, directly connected.
- (4) Without external flow control, indirectly connected.

These interceptors comply with the requirements of Table 1014.2.1. Hydromechanical grease interceptors are generally installed inside.

211.0 – I –

Indirect-Fired Water Heater. A water heater consisting of a storage tank equipped with an internal or external heat exchanger used to transfer heat from an external source to heat potable water. The storage tank either contains heated potable water or water supplied from an external source, such as a boiler.

Indirect Waste Pipe. A pipe that does not connect directly with the drainage system but conveys liquid wastes by discharging into a plumbing fixture, interceptor, or receptacle that is directly connected to the drainage system.

Individual Vent. A pipe installed to vent a fixture trap and that connects with the vent system above the fixture served or terminates in the open air.

Industrial Waste. Liquid or water-borne waste from industrial or commercial processes, except domestic sewage.

Insanitary. A condition that is contrary to sanitary principles or is injurious to health.

Conditions to which “insanitary” shall apply include the following:

- (1) A trap that does not maintain a proper trap seal.
- (2) An opening in a drainage system, except where lawful, that is not provided with an approved liquid-sealed trap.
- (3) A plumbing fixture or other waste discharging receptor or device that is not supplied with water sufficient to flush and maintain the fixture or receptor in a clean condition.
- (4) A defective fixture, trap, pipe, or fitting.
- (5) A trap, except where in this code exempted, directly connected to a drainage system, the seal of which is not protected against siphonage and backpressure by a vent pipe.
- (6) A connection, cross-connection, construction, or condition, temporary or permanent, that would permit or make possible by any means whatsoever for an unapproved foreign matter to enter a water distribution system used for domestic purposes.

- (7) The foregoing enumeration of conditions to which the term “insanitary” shall apply, shall not preclude the application of that term to conditions that are, in fact, insanitary.

Interceptor (Clarifier). A device designed and installed so as to separate and retain deleterious, hazardous, or undesirable matter from normal wastes and permit normal sewage or liquid wastes to discharge into the disposal terminal by gravity.

Invert. The lowest portion of the inside of a horizontal pipe.

212.0 – J –

Joint, Brazed. A joint obtained by joining of metal parts with alloys that melt at temperatures exceeding 840°F (449°C), but less than the melting temperature of the parts to be joined.

Joint, Compression. A multipiece joint with cup-shaped threaded nuts that, when tightened, compress tapered sleeves so that they form a tight joint on the periphery of the tubing they connect.

Joint, Flanged. One made by bolting together a pair of flanged ends.

Joint, Flared. A metal-to-metal compression joint in which a conical spread is made on the end of a tube that is compressed by a flare nut against a mating flare.

Joint, Mechanical. General form for gastight or liquid-tight joints obtained by the joining of parts through a positive holding mechanical construction.

Joint, Soldered. A joint obtained by the joining of metal parts with metallic mixtures or alloys that melt at a temperature up to and including 840°F (449°C).

Joint, Welded. A gastight joint obtained by the joining of metal parts in the plastic molten state.

213.0 – K –

No definitions.

214.0 – L –

Labeled. Equipment or materials bearing a label of a listing agency (accredited conformity assessment body). See Listed (third-party certified).

Lavatories in Sets. Two or three lavatories that are served by one trap.

Leader. An exterior vertical drainage pipe for conveying storm water from roof or gutter drains. See Downspout.

Levels of Sedation.

Deep Sedation. A drug-induced depression of consciousness during which patients cannot be easily aroused but respond purposefully following repeated or painful stimulation. The ability to independently maintain ventilatory function may be impaired. Patients may require assistance in maintaining a patent airway, and spontaneous ventilation may be inadequate. Cardiovascular function is usually maintained. [NFPA 99:3.3.63.1]

General Anesthesia. A drug-induced loss of consciousness during which patients are not arousable, even by painful stimulation. The ability to independently

maintain ventilatory function is often impaired. Patients often require assistance in maintaining a patent airway, and positive pressure ventilation may be required because of depressed spontaneous ventilation or drug-induced depression of neuromuscular function. Cardiovascular function may be impaired. [NFPA 99:3.3.63.2]

Moderate Sedation. A drug-induced depression of consciousness during which patients respond purposefully to verbal commands, either alone or accompanied by light tactile stimulation. No interventions are required to maintain a patent airway, and spontaneous ventilation is adequate. Cardiovascular function is usually maintained. [NFPA 99:3.3.63.4]

Liquefied Petroleum Gas (LP-Gas) Facilities. Liquefied petroleum gas (LP-Gas) facilities include tanks, containers, container valves, regulating equipment, meters, appurtenances, or any combination thereof for the storage and supply of liquefied petroleum gas for a building, structure, or premises.

Liquid Waste. The discharge from a fixture, appliance, or appurtenance in connection with a plumbing system that does not receive fecal matter.

Listed (Third-party certified). Equipment or materials included in a list published by a listing agency (accredited conformity assessment body) that maintains periodic inspection on current production of listed equipment or materials and whose listing states either that the equipment or material complies with approved standards or has been tested and found suitable for use in a specified manner.

Listing Agency. An agency accredited by an independent and authoritative conformity assessment body to operate a material and product listing and labeling (certification) system and that is accepted by the Authority Having Jurisdiction, which is in the business of listing or labeling. The system includes initial and ongoing product testing, a periodic inspection on current production of listed (certified) products, and that makes available a published report of such listing in which specific information is included that the material or product is in accordance with applicable standards and found safe for use in a specific manner.

Lot. A single or individual parcel or area of land legally recorded or validated by other means acceptable to the Authority Having Jurisdiction on which is situated a building or which is the site of any work regulated by this code, together with the yards, courts, and unoccupied spaces legally required for the building or works, and that is owned by or is in the lawful possession of the owner of the building or works.

Low Hazard. See Pollution.

215.0

— M —

Macerating Toilet System. A system comprised of a sump with macerating pump and with connections for a water closet and other plumbing fixtures, which is designed to accept, grind, and pump wastes to an approved point of discharge.

Main. The principal artery of a system of continuous piping to which branches may be connected.

Main Sewer. See Public Sewer.

Main Vent. The principal artery of the venting system to which vent branches may be connected.

May. A permissive term.

Medical Air. Air that is supplied from cylinders, bulk containers, medical air compressors, or has been reconstituted from oxygen USP and oil-free, dry nitrogen NF [NFPA 99:3.3.104]. Medical air has the following characteristics:

- (1) Supplied from cylinders, bulk containers, medical air compressor sources, or be reconstituted from oxygen USP and oil-free dry nitrogen NF.
- (2) Meets the requirements of medical air USP.
- (3) No detectable liquid hydrocarbons.
- (4) Less than 25 parts per million (ppm) gaseous hydrocarbons.
- (5) Equal to or less than 6.85 E-07 pounds per cubic yard (lb/yd³) (4.064 E-07 kg/m³) of permanent particulates sized 1 micron (1 μ m) or larger in the air at normal atmospheric pressure. [NFPA 99:5.1.3.6.1]

Medical Gas. A patient medical gas or medical support gas. [NFPA 99:3.3.107]

Medical Gas Manifold. A device for connecting the outlets of one or more gas cylinders to the central piping system for that specific gas. [NFPA 99:3.3.101]

Medical Gas System. An assembly of equipment and piping for the distribution of nonflammable medical gases such as oxygen, nitrous oxide, compressed air, carbon dioxide, and helium. [NFPA 99:3.3.108]

Medical Support Gas. Nitrogen or instrument air used for a medical support purpose (e.g. to remove excess moisture from instruments before further processing, or to operate medical-surgical tools, air-driven booms, pendants, or similar applications) and, where appropriate to the procedures, used in laboratories and are not respired as part of a treatment. Medical support gas falls under the general requirements for medical gases. [NFPA 99:3.3.109]

Medical-Surgical Vacuum. A method used to provide a source of drainage, aspiration, and suction in order to remove body fluids from patients. [NFPA 99:3.3.110]

Medical-Surgical Vacuum System. An assembly of central vacuum-producing equipment and a network of piping for patient suction in medical, medical-surgical, and waste anesthetic gas disposal (WAGD) applications. [NFPA 99:3.3.111]

Mobile Home Park Sewer. That part of the horizontal piping of a drainage system that begins 2 feet (610 mm) downstream from the last mobile home site and conveys it to a public sewer, private sewer, private sewage disposal system, or other point of disposal.

Mulch. Organic materials, such as wood chips and fines, tree bark chips, and pine needles that are used in a mulch basin to conceal gray water outlets and permit the infiltration of gray water.

Mulch Basin. A subsurface catchment area for gray water that is filled with mulch and of sufficient depth and volume to prevent ponding, surfacing, or runoff.

216.0

– N –

Nitrogen, NF (Oil-Free, Dry). Nitrogen complying, at a minimum, with oil-free, dry nitrogen NF. [NFPA 99:3.3.118.1]

Nuisance. Includes, but is not limited to:

- (1) A public nuisance known at common law or in equity jurisprudence.
- (2) Where work regulated by this code is dangerous to human life or is detrimental to health and property.
- (3) Inadequate or unsafe water supply or sewage disposal system.

217.0

– O –

Offset. A combination of elbows or bends in a line of piping that brings one section of the pipe out of line but into a line parallel with the other section.

Oil Interceptor. See Interceptor (Clarifier).

On-Site Treated Nonpotable Water. Nonpotable water, including gray water that has been collected, treated, and intended to be used on-site and is suitable for direct beneficial use.

218.0

– P –

Patient Care Room. A room of a health care facility where patients are intended to be examined or treated. [NFPA 99:3.3.138]

Basic Care Room. A room in which the failure of equipment or a system is not likely to cause injury to the patients or caregivers but can cause patient discomfort (Category 3). [NFPA 99:3.3.138.1]

Critical Care Room. A room in which failure of equipment or a system is likely to cause major injury or death of patients or caregivers (Category 1). [NFPA 99:3.3.138.2]

General Care Room. A room in which failure of equipment or a system is likely to cause minor injury to patients or caregivers (Category 2). [NFPA 99:3.3.138.3]

Patient Medical Gas. Piped gases such as oxygen, nitrous oxide, helium, carbon dioxide, and medical air that are used in the application of human respiration and the calibration of medical devices used for human respiration. [NFPA 99:3.3.142]

PB. Polybutylene.

PE. Polyethylene.

PE-AL-PE. Polyethylene-aluminum-polyethylene.

PE-RT. Polyethylene of raised temperature.

Penetration Firestop System. A specific assemblage of field-assembled materials, or a factory-made device, which has been tested to a standard test method and, where installed properly on penetrating piping materials, is capable of maintaining the fire-resistance rating of assemblies penetrated.

Person. A natural person, his heirs, executor, administrators, or assigns and shall also include a firm, corporation, municipal or quasi-municipal corporation, or governmental agency. Singular includes plural, male includes female.

PEX. Cross-linked polyethylene.

PEX-AL-PEX. Cross-linked polyethylene-aluminum-cross-linked polyethylene.

Pipe. A cylindrical conduit or conductor conforming to the particular dimensions commonly known as “pipe size.”

Plumbing. The business, trade, or work having to do with the installation, removal, alteration, or repair of plumbing systems or parts thereof.

Plumbing Appliance. A special class of device or equipment that is intended to perform a special plumbing function. Its operation, control, or both may be dependent upon one or more energized components, such as motors, controls, heating elements, or pressure- or temperature-sensing elements. Such device or equipment may operate automatically through one or more of the following actions: a time cycle, a temperature range, a pressure range, a measured volume or weight; or the device or equipment may be manually adjusted or controlled by the user or operator.

Plumbing Appurtenance. A manufactured device, a prefabricated assembly, or an on-the-job assembly of component parts that is an adjunct to the basic piping system and plumbing fixtures. An appurtenance demands no additional water supply, nor does it add a discharge load to a fixture or the drainage system. It performs some useful function in the operation, maintenance, servicing, economy, or safety of the plumbing system.

Plumbing Fixture. An approved-type installed receptacle, device, or appliance that is supplied with water or that receives liquid or liquid-borne wastes and discharges such wastes into the drainage system to which it may be directly or indirectly connected. Industrial or commercial tanks, vats, and similar processing equipment are not plumbing fixtures, but may be connected to or discharged into approved traps or plumbing fixtures where and as otherwise provided for elsewhere in this code.

Plumbing Official. See Authority Having Jurisdiction.

Plumbing System. Includes all potable water, building supply, and distribution pipes; all plumbing fixtures and traps; all drainage and vent pipes; and all building drains and building sewers, including their respective joints and connections, devices, receptors, and appurtenances within the property lines of the premises and shall include potable water piping, potable water treating or using equipment, medical gas and medical vacuum systems, liquid and fuel gas piping, and water heaters and vents for same.

Plumbing Vent. A pipe provided to ventilate a plumbing system, to prevent trap siphonage and backpressure, or to equalize the air pressure within the drainage system.

Plumbing Vent System. A pipe or pipes installed to provide a flow of air to or from a drainage system or to provide a circulation of air within such system to protect trap seals from siphonage and backpressure.

Pollution. An impairment of the quality of the potable water to a degree that does not create a hazard to the public health but which does adversely and unreasonably affect the aesthetic qualities of such potable water for domestic use. Also defined as “Low Hazard.”

Potable Water. Water that is satisfactory for drinking, culinary, and domestic purposes and that meets the requirements of the Health Authority Having Jurisdiction.

PP. Polypropylene.

Pressed Fitting. A mechanical connection for joining copper tubing that uses a crimping tool to affix the o-ring seal to copper or copper alloy fitting to the tubing. The tubing shall be inserted into the fitting, and the crimp shall be made using the tool recommended by the manufacturer.

Pressure. The normal force exerted by a homogeneous liquid or gas, per unit of area, on the wall of the container.

Residual Pressure. The pressure available at the fixture or water outlet after allowance is made for pressure drop due to friction loss, head, meter, and other losses in the system during maximum demand periods.

Static Pressure. The pressure existing without any flow.

Pressure-Balancing Valve. A mixing valve that senses incoming hot and cold water pressures and compensates for fluctuations in either to stabilize outlet temperature.

Pressure-Lock-Type Connection. A mechanical connection that depends on an internal retention device to prevent pipe or tubing separation. Connection is made by inserting the pipe or tubing into the fitting to a prescribed depth.

Private or Private Use. Applies to plumbing fixtures in residences and apartments, to private bathrooms in hotels and hospitals, and to restrooms in commercial establishments where the fixtures are intended for the use of a family or an individual.

Private Sewage Disposal System. A septic tank with the effluent discharging into a subsurface disposal field, into one or more seepage pits, or into a combination of subsurface disposal field and seepage pit or of such other facilities as may be permitted under the procedures set forth elsewhere in this code.

Private Sewer. A building sewer that receives the discharge from more than one building drain and conveys it to a public sewer, private sewage disposal system, or other point of disposal.

Proportioning System for Medical Air USP. A central supply that produces medical air (USP) reconstituted from oxygen USP and nitrogen NF by means of a mixer or blender. [NFPA 99:3.3.104.1]

→ **Public or Public Use.** Applies to plumbing fixtures that are not defined as private or private use.

Public Sewer. A common sewer directly controlled by public authority.

→ **Push Fit Fitting.** A mechanical fitting where the connection is assembled by pushing the tube or pipe into the fitting and is sealed with an o-ring.

PVC. Polyvinyl Chloride.

PVDF. Polyvinylidene Fluoride.

219.0

– Q –

Quick-Disconnect Device. A hand-operated device that provides a means for connecting and disconnecting a hose to a water supply and that is equipped with a means to shut off the water supply where the device is disconnected.

220.0

– R –

Rainwater. Natural precipitation that has not been contaminated by use.

Rainwater Catchment System. A system that utilizes the principal of collecting, storing, and using rainwater from a rooftop or other manmade, aboveground collection surface. Also known as a rainwater harvesting system.

Rainwater Storage Tank. The central component of the rainwater catchment system. Also known as a cistern or rain barrel.

Receptor. An approved plumbing fixture or device of such material, shape, and capacity as to adequately receive the discharge from indirect waste pipes, so constructed and located as to be readily cleaned.

Reclaimed Water. Nonpotable water provided by a water/wastewater utility that, as a result of tertiary treatment of domestic wastewater, meets requirements of the public health Authority Having Jurisdiction for its intended uses.

Registered Design Professional. An individual who is registered or licensed by the laws of the state to perform such design work in the jurisdiction.

Regulating Equipment. Includes valves and controls used in a plumbing system that are required to be accessible or readily accessible.

Relief Vent. A vent, the primary function of which is to provide circulation of air between drainage and vent systems or to act as an auxiliary vent on a specially designed system.

Remote Outlet. Where used for sizing water piping, it is the furthest outlet dimension, measuring from the meter, either the developed length of the cold-water piping or through the water heater to the furthest outlet on the hot-water piping.

Rim. See Flood-Level Rim.

Riser. A water supply pipe that extends vertically one full story or more to convey water to branches or fixtures.

Roof Drain. A drain installed to receive water collecting on the surface of a roof and to discharge it into a leader, downspout, or conductor.

Roof Washer. A device or method for removal of sediment and debris from a collection surface by diverting initial rainfall from entry into the cistern(s). Also known as a first flush device.

Roughing-In. The installation of all parts of the plumbing system that can be completed prior to the installation of fixtures. This includes drainage, water supply, gas piping, vent piping, and the necessary fixture supports.

DEFINITIONS

221.0

— S —

Sand Interceptor. See Interceptor (Clarifier).

Scavenging. Evacuation of exhaled mixtures of oxygen and nitrous oxide. [NFPA 99:3.3.160]

SCFM. Standard cubic feet per minute. [NFPA 99:3.3.161]

SDR. An abbreviation for “standard dimensional ratio,” which is the specific ratio of the average specified outside diameter to the minimum wall thickness for outside controlled diameter plastic pipe.

Seam, Welded. See Joint, Welded.

Seepage Pit. A lined excavation in the ground which receives the discharge of a septic tank so designed as to permit the effluent from the septic tank to seep through its bottom and sides.

Septic Tank. A watertight receptacle that receives the discharge of a drainage system or part thereof, designed and constructed so as to retain solids, digest organic matter through a period of detention, and allow the liquids to discharge into the soil outside of the tank through a system of open joint piping or a seepage pit meeting the requirements of this code.

Service Piping. The piping and equipment between the street gas main and the gas piping system inlet that is installed by, and is under the control and maintenance of, the serving gas supplier.

Sewage. Liquid waste containing animal or vegetable matter in suspension or solution and that may include liquids containing chemicals in solution.

Sewage Ejector. A device for lifting sewage by entraining it on a high-velocity jet stream, air, or water.

Sewage Pump. A permanently installed mechanical device, other than an ejector, for removing sewage or liquid waste from a sump.

Shall. Indicates a mandatory requirement.

Shielded Coupling. An approved elastomeric sealing gasket with an approved outer shield and a tightening mechanism.

Shock Arrestor. See Water Hammer Arrestor.

Should. Indicates a recommendation or that which is advised but not required.

Single-Family Dwelling. A building designed to be used as a home by the owner of such building, which shall be the only dwelling located on a parcel of ground with the usual accessory buildings.

Size and Type of Tubing. See Diameter.

Slip Joint. An adjustable tubing connection, consisting of a compression nut, a friction ring, and a compression washer, designed to fit a threaded adapter fitting or a standard taper pipe thread.

Slope. See Grade.

Soil Pipe. A pipe that conveys the discharge of water closets, urinals, clinical sinks, or fixtures having similar functions of collection and removal of domestic sewage, with or without the discharge from other fixtures, to the building drain or building sewer.

Special Wastes. Wastes that require some special method of handling, such as the use of indirect waste piping and receptors, corrosion-resistant piping, sand, oil or grease interceptors, condensers, or other pretreatment facilities.

Stack. The vertical main of a system of soil, waste, or vent piping extending through one or more stories.

Stack Vent. The extension of a soil or waste stack above the highest horizontal drain connected to the stack.

Standard. A document, the main text of which contains only mandatory provisions using the word “shall” to indicate requirements and which is in a form generally suitable for mandatory reference by another standard or code or for adoption into law. Nonmandatory provisions shall be located in an appendix, footnote, or fine print note and are not to be considered a part of the requirements of a standard.

Station Inlet. An inlet point in a piped medical-surgical vacuum distribution system at which the user makes connections and disconnections. [NFPA 99:3.3.169]

Station Outlet. An outlet point in a piped medical gas distribution system at which the user makes connections and disconnections. [NFPA 99:3.3.170]

Sterilizer. A piece of equipment that disinfects instruments and equipment by way of heat.

Storm Drain. See Building Drain (Storm).

Storm Sewer. A sewer used for conveying rainwater, surface water, condensate, cooling water, or similar liquid wastes.

Subsoil Drain. A drain that collects subsurface or seepage water and conveys it to a place of disposal.

Subsoil Irrigation Field. Gray water irrigation field installed in a trench within the layer of soil below the topsoil. This system is typically used for irrigation of deep rooted plants.

Subsurface Irrigation Field. Gray water irrigation field installed below finished grade within the topsoil.

Sump. An approved tank or pit that receives sewage or liquid waste and which is located below the normal grade of the gravity system and which must be emptied by mechanical means.

Supports. Supports, hangers, and anchors are devices for properly supporting and securing pipe, fixtures, and equipment.

Surge Tank. A reservoir to modify the fluctuation in flow rates to allow for uniform distribution of gray water to the points of irrigation.

222.0

— T —

T Rating. The time period that the penetration firestop system, including the penetrating item, limits the maximum temperature rise of 325°F (181°C) above its initial temperature through the penetration on the nonfire side, where tested in accordance with ASTM E814 or UL 1479.

Tailpiece. The pipe or tubing that connects the outlet of a plumbing fixture to a trap.

Thermostatic (Temperature Control) Valve. A mixing valve that senses outlet temperature and compensates for fluctuations in incoming hot or cold water temperatures.

Transition Gas Riser. A listed or approved section or sections of pipe and fittings used to convey fuel gas and installed in a gas piping system for the purpose of providing a transition from belowground to aboveground.

Trap. A fitting or device so designed and constructed as to provide, where properly vented, a liquid seal that will prevent the back passage of air without materially affecting the flow of sewage or wastewater through it.

Trap Arm. That portion of a fixture drain between a trap and the vent.

Trap Primer. A device and system of piping that maintains a water seal in a remote trap.

Trap Seal. The vertical distance between the crown weir and the top dip of the trap.

Crown Weir (Trap Weir). The lowest point in the cross-section of the horizontal waterway at the exit of the trap.

Top Dip (of trap). The highest point in the internal cross-section of the trap at the lowest part of the bend (inverted siphon). By contrast, the bottom dip is the lowest point in the internal cross-section.

Type B Gas Vent. A factory-made gas vent listed by nationally recognized testing agency for venting listed or approved appliances equipped to burn only gas.

Type BW Gas Vent. A factory-made gas vent listed by a nationally recognized testing agency for venting listed or approved gas-fired vented wall furnaces.

Type L Gas Vent. A venting system consisting of listed vent piping and fittings for use with oil-burning appliances listed for use with Type L or with listed gas appliances.

223.0 – U –

Unsanitary. See Insanitary.

User Outlet. See Station Outlet.

224.0 – V –

Vacuum. A pressure less than that exerted by the atmosphere.

Vacuum Breaker. See Backflow Preventer.

Vacuum Relief Valve. A device that prevents excessive vacuum in a pressure vessel.

Vacuum System-Level 1. A system consisting of central vacuum-producing equipment with pressure and operating controls, shutoff valves, alarm warning systems, gauges, and a network of piping extending to and terminating with suitable station inlets at locations where patient suction could be required.

Valve, Isolation. A valve that isolates one piece of equipment from another.

Valve, Pressure-Relief. A pressure-actuated valve held closed by a spring or other means and designed to automatically relieve pressure in excess of its setting.

Valve, Riser. A valve at the base of a vertical riser that isolates that riser.

Valve, Service. A valve serving horizontal piping extending from a riser to a station outlet or inlet.

Valve, Source. A single valve at the source that controls a number of units that make up the source.

Valve, Zone. A valve that controls the gas or vacuum to a particular area.

Vent. See Plumbing Vent; Dry Vent; Wet Vent.

Vent Connector, Gas. That portion of a gas venting system that connects a listed gas appliance to a gas vent and is installed within the space or area in which the appliance is located.

Vent Offset. An arrangement of two or more fittings and pipe installed for the purpose of locating a vertical section of vent pipe in a different but parallel plane with respect to an adjacent section of a vertical vent pipe. [NFPA 54:3.3.108]

Vent Pipe. See Plumbing Vent.

Vent Stack. The vertical vent pipe installed primarily for the purpose of providing circulation of air to and from any part of the drainage system.

Vent System. See Plumbing Vent System.

Vented Flow Control Device. A device installed upstream from the hydromechanical grease interceptor having an orifice that controls the rate of flow through the interceptor, and an air intake (vent) downstream from the orifice, which allows air to be drawn into the flow stream.

Vertical Pipe. A pipe or fitting that is installed in a vertical position or that makes an angle of not more than 45 degrees (0.79 rad) with the vertical.

225.0 – W –

Wall-Hung Water Closet. A water closet installed in such a way that no part of the water closet touches the floor.

Waste. See Liquid Waste and Industrial Waste.

Waste Anesthetic Gas Disposal (WAGD). The process of capturing and carrying away gases vented from the patient breathing circuit during the normal operation of gas anesthesia or analgesia equipment. [NFPA 99:3.3.183]

Waste Pipe. A pipe that conveys only liquid waste, free of fecal matter.

Water-Conditioning or Treating Device. A device that conditions or treats a water supply so as to change its chemical content or remove suspended solids by filtration.

Water Distribution Pipe. In a building or premises, a pipe that conveys potable water from the building supply pipe to the plumbing fixtures and other water outlets.

Water Hammer Arrestor. A device designed to provide protection against hydraulic shock in the building water supply system.

Water Heater or Hot Water Heating Boiler. An appliance designed primarily to supply hot water for domestic or commercial purposes and equipped with automatic controls limiting water temperature to a maximum of 210°F (99°C).

Water Main (Street Main). A water supply pipe for public or community use.

Water Supply System. The building supply pipe, the water distribution pipes, and the necessary connecting pipes, fittings, control valves, backflow prevention devices, and all

DEFINITIONS

appurtenances carrying or supplying potable water in or adjacent to the building or premises.

Water/Wastewater Utility. A public or private entity which may treat, deliver, or do both functions to reclaimed (recycled) water, potable water, or both to wholesale or retail customers.

Welder, Pipe. A person who specializes in the welding of pipes and holds a valid certificate of competency from a recognized testing laboratory, based on the requirements of the ASME Boiler and Pressure Vessels code, Section IX.

Wet Procedure Locations. The area in a patient care room where a procedure is performed that is normally subject to wet conditions while patients are present, including standing fluids on the floor or drenching of the work area, either of which condition is intimate to the patient or staff. [NFPA 99:3.3.184]

Wet Vent. A vent that also serves as a drain.

Whirlpool Bathtub. A bathtub fixture equipped and fitted with a circulating piping system designed to accept, circulate, and discharge bathtub water upon each use.

226.0 - X -

No definitions.

227.0 -Y-

Yoke Vent. A pipe connecting upward from a soil or waste stack to a vent stack for the purpose of preventing pressure changes in the stacks.

228.0 - Z -

No definitions.

CHAPTER 3

GENERAL REGULATIONS

301.0 General.

301.1 Applicability. This chapter shall govern the general requirements, not specific to other chapters, for the installation of plumbing systems.

» **301.2 Minimum Standards.** Pipe, pipe fittings, traps, fixtures, material, and devices used in a plumbing system shall be listed or labeled (third-party certified) by a listing agency (accredited conformity assessment body) and shall comply with the approved applicable recognized standards referenced in this code, and shall be free from defects. Unless otherwise provided for in this code, materials, fixtures, or devices used or entering into the construction of plumbing systems, or parts thereof, shall be submitted to the Authority Having Jurisdiction for approval.

» **301.2.1 Marking.** Each length of pipe and each pipe fitting, trap, fixture, material, and device used in a plumbing system shall have cast, stamped, or indelibly marked on it the manufacturer's mark or name, which shall readily identify the manufacturer to the end user of the product. Where required by the approved standard that applies, the product shall be marked with the weight and the quality of the product. Materials and devices used or entering into the construction of plumbing and drainage systems, or parts thereof, shall be marked and identified in a manner satisfactory to the Authority Having Jurisdiction. Such marking shall be done by the manufacturer. Field markings shall not be acceptable.

Exception: Markings shall not be required on nipples created from cutting and threading of approved pipe.

» **301.2.2 Standards.** Standards listed or referred to in this chapter or other chapters cover materials that will conform to the requirements of this code, where used in accordance with the limitations imposed in this or other chapters thereof and their listing. Where a standard covers materials of various grades, weights, quality, or configurations, the portion of the listed standard that is applicable shall be used. Design and materials for special conditions or materials not provided for herein shall be permitted to be used by special permission of the Authority Having Jurisdiction after the Authority Having Jurisdiction has been satisfied as to their adequacy. A list of accepted plumbing material standards is referenced in Table 1701.1. An IAPMO Installation Standard is referenced in Appendix I for the convenience of the users of this code. It is not considered as a part of this code unless formally adopted as such by the Authority Having Jurisdiction.

301.2.3 Plastic Pipe, Plastic Pipe Fittings, and Components. Plastic pipe, plastic pipe fittings, and components other than those for gas shall comply with NSF 14.

301.2.4 Cast-Iron Soil Pipe and Fittings. Cast-iron soil pipe and hubless couplings shall be third party certified in accordance with ASTM C1277 and CISPI 310.

301.2.5 Existing Buildings. In existing buildings or premises in which plumbing installations are to be altered, repaired, or renovated, the Authority Having Jurisdiction has discretionary powers to permit deviation from the provisions of this code, provided that such proposal to deviate is first submitted for proper determination in order that health and safety requirements, as they pertain to plumbing, shall be observed.

301.3 Alternate Materials and Methods of Construction Equivalency. Nothing in this code is intended to prevent the use of systems, methods, or devices of equivalent or superior quality, strength, fire resistance, effectiveness, durability, and safety over those prescribed by this code. Technical documentation shall be submitted to the Authority Having Jurisdiction to demonstrate equivalency. The Authority Having Jurisdiction shall have the authority to approve or disapprove the system, method, or device for the intended purpose.

However, the exercise of this discretionary approval by the Authority Having Jurisdiction shall have no effect beyond the jurisdictional boundaries of said Authority Having Jurisdiction. An alternate material or method of construction so approved shall not be considered as in accordance with the requirements, intent, or both of this code for a purpose other than that granted by the Authority Having Jurisdiction where the submitted data does not prove equivalency.

301.3.1 Testing. The Authority Having Jurisdiction shall have the authority to require tests, as proof of equivalency.

301.3.1.1 Tests. Tests shall be made in accordance with approved or applicable standards, by an approved testing agency at the expense of the applicant. In the absence of such standards, the Authority Having Jurisdiction shall have the authority to specify the test procedure.

301.3.1.2 Request by Authority Having Jurisdiction. The Authority Having Jurisdiction shall have the authority to require tests to be made or repeated where there is reason to believe that a material or device no longer is in accordance with the requirements on which its approval was based.

301.4 Flood Hazard Areas. Plumbing systems shall be located above the elevation in accordance with the building code for utilities and attendant equipment or the elevation of the lowest floor, whichever is higher.

Exception: Plumbing systems shall be permitted to be located below the elevation in accordance with the building code for utilities and attendant equipment or the elevation of the lowest floor, whichever is higher, provided that the systems are designed and installed to prevent water from entering or accumulating within their components and the systems are constructed to resist hydrostatic and hydrodynamic loads and stresses, including the effects of buoyancy, during the occurrence of flooding to such elevation.

- » **301.4.1 Coastal High Hazard Areas.** Plumbing systems in buildings located in coastal high hazard areas shall be in accordance with the requirements of Section 301.4, and plumbing systems, pipes, and fixtures shall not be mounted on or penetrate through walls that are intended to breakaway under flood loads in accordance with the building code.
- » **301.5 Alternative Engineered Design.** An alternative engineered design shall comply with the intent of the provisions of this code and shall provide an equivalent level of quality, strength, effectiveness, fire resistance, durability, and safety. Material, equipment, or components shall be designed and installed in accordance with the manufacturer's installation instructions.
- » **301.5.1 Permit Application.** The registered design professional shall indicate on the design documents that the plumbing system, or parts thereof, is an alternative engineered design so that it is noted on the construction permit application. The permit and permanent permit records shall indicate that an alternative engineered design was part of the approved installation.
- » **301.5.2 Technical Data.** The registered design professional shall submit sufficient technical data to substantiate the proposed alternative engineered design and to prove that the performance meets the intent of this code.
- » **301.5.3 Design Documents.** The registered design professional shall provide two complete sets of signed and sealed design documents for the alternative engineered design for submittal to the Authority Having Jurisdiction. The design documents shall include floor plans and a riser diagram of the work. Where appropriate, the design documents shall indicate the direction of flow, pipe sizes, grade of horizontal piping, loading, and location of fixtures and appliances.
- » **301.5.4 Design Approval.** An approval of an alternative engineered design shall be at the discretion of the Authority Having Jurisdiction. The exercise of this discretionary approval by the Authority Having Jurisdiction shall have no effect beyond the jurisdictional boundaries of said Authority Having Jurisdiction. An alternative engineered design so approved shall not be considered as in accordance with the requirements, intent, or both of this code for a purpose other than that granted by the Authority Having Jurisdiction.
- » **301.5.5 Design Review.** The Authority Having Jurisdiction shall have the authority to require testing of the alternative engineered design in accordance with Section 301.3.1, including the authority to require an independent review of the design documents by a registered design professional selected by the Authority Having Jurisdiction and at the expense of the applicant.
- » **301.5.6 Inspection and Testing.** The alternative engineered design shall be tested and inspected in accordance with the submitted testing and inspection plan and the requirements of this code.

302.0 Iron Pipe Size (IPS) Pipe.

302.1 General. Iron, steel, copper, and copper alloy pipe shall be standard-weight iron pipe size (IPS) pipe.

303.0 Disposal of Liquid Waste.

303.1 General. It shall be unlawful for a person to cause, suffer, or permit the disposal of sewage, human excrement, or other liquid wastes, in a place or manner, except through and by means of an approved drainage system, installed and maintained in accordance with the provisions of this code.

304.0 Connections to Plumbing System Required.

304.1 General. Plumbing fixtures, drains, appurtenances, and appliances, used to receive or discharge liquid wastes or sewage, shall be connected properly to the drainage system of the building or premises, in accordance with the requirements of this code.

305.0 Damage to Drainage System or Public Sewer.

305.1 Unlawful Practices. It shall be unlawful for a person to deposit, by any means whatsoever, into a plumbing fixture, floor drain, interceptor, sump, receptor, or device, which is connected to a drainage system, public sewer, private sewer, septic tank, or cesspool, any ashes; cinders; solids; rags; inflammable, poisonous, or explosive liquids or gases; oils; grease; or any other thing whatsoever that is capable of causing damage to the drainage system or public sewer.

306.0 Industrial Wastes.

306.1 Detrimental Wastes. Wastes detrimental to the public sewer system or detrimental to the functioning of the sewage treatment plant shall be treated and disposed of as found necessary and directed by the Authority Having Jurisdiction.

306.2 Safe Discharge. Sewage or other waste from a plumbing system that is capable of being deleterious to surface or subsurface waters shall not be discharged into the ground or into a waterway unless it has first been rendered safe by some acceptable form of treatment in accordance with the Authority Having Jurisdiction.

307.0 Location.

307.1 System. Except as otherwise provided in this code, no plumbing system, drainage system, building sewer, private sewage disposal system, or parts thereof shall be located in a lot other than the lot that is the site of the building, structure, or premises served by such facilities.

307.2 Ownership. No subdivision, sale, or transfer of ownership of existing property shall be made in such manner that the area, clearance, and access requirements of this code are decreased.

308.0 Improper Location.

308.1 General. Piping, fixtures, or equipment shall not be so located as to interfere with the normal use thereof or with the normal operation and use of windows, doors, or other required facilities.

309.0 Workmanship.

309.1 Engineering Practices. Design, construction, and workmanship shall be in accordance with accepted engineering practices and shall be of such character as to secure the results sought to be obtained by this code.

309.2 Concealing Imperfections. It is unlawful to conceal cracks, holes, or other imperfections in materials by welding, brazing, or soldering or by using therein or thereon a paint, wax, tar, solvent cement, or other leak-sealing or repair agent.

309.3 Burred Ends. Burred ends of pipe and tubing shall be reamed to the full bore of the pipe or tube, and chips shall be removed.

309.4 Installation Practices. Plumbing systems shall be installed in a manner that is in accordance with this code, applicable standards, and the manufacturer's installation instructions.

310.0 Prohibited Fittings and Practices.

310.1 Fittings. No double hub fitting, single or double tee branch, single or double tapped tee branch, side inlet quarter bend, running thread, band, or saddle shall be used as a drainage fitting, except that a double hub sanitary tapped tee shall be permitted to be used on a vertical line as a fixture connection.

310.2 Drainage and Vent Piping. No drainage or vent piping shall be drilled and tapped for the purpose of making connections thereto, and no cast-iron soil pipe shall be threaded.

310.3 Waste Connection. No waste connection shall be made to a closet bend or stub of a water closet or similar fixture.

310.4 Use of Vent and Waste Pipes. Except as hereinafter provided in Section 908.0 through Section 911.0, no vent pipe shall be used as a soil or waste pipe, nor shall a soil or waste pipe be used as a vent. Also, single-stack drainage and venting systems with unvented branch lines are prohibited.

310.5 Obstruction of Flow. No fitting, fixture and piping connection, appliance, device, or method of installation that obstructs or retards the flow of water, wastes, sewage, or air in the drainage or venting systems, in an amount exceeding the normal frictional resistance to flow, shall be used unless it is indicated as acceptable in this code or is approved in accordance with Section 301.2 of this code. The enlargement of a 3 inch (76 mm) closet bend or stub to 4 inches (102 mm) shall not be considered an obstruction.

310.6 Dissimilar Metals. Except for necessary valves, where inter-membering or mixing of dissimilar metals occurs, the point of connection shall be confined to exposed or accessible locations.

310.7 Direction of Flow. Valves, pipes, and fittings shall be installed in correct relationship to the direction of flow.

310.8 Screwed Fittings. Screwed fittings shall be ABS, cast-iron, copper, copper alloy, malleable iron, PVC, steel, or other approved materials. Threads shall be tapped out of solid metal or molded in solid ABS or PVC.

311.0 Independent Systems.

311.1 General. The drainage system of each new building and of new work installed in an existing building shall be separate and independent from that of any other building, and, where available, every building shall have an independent connection with a public or private sewer.

Exception: Where one building stands in the rear of another building on an interior lot, and no private sewer is available or can be constructed to the rear building through an adjoining court, yard, or driveway, the building drain from the front building shall be permitted to be extended to the rear building.

312.0 Protection of Piping, Materials, and Structures.

312.1 General. Piping passing under or through walls shall be protected from breakage. Piping passing through or under cinders or other corrosive materials shall be protected from external corrosion in an approved manner. Approved provisions shall be made for expansion of hot water piping. Voids around piping passing through concrete floors on the ground shall be sealed.

312.2 Installation. Piping in connection with a plumbing system shall be so installed that piping or connections will not be subject to undue strains or stresses, and provisions shall be made for expansion, contraction, and structural settlement. No plumbing piping shall be directly embedded in concrete or masonry. No structural member shall be seriously weakened or impaired by cutting, notching, or otherwise, as defined in the building code.

312.3 Building Sewer and Drainage Piping. No building sewer or other drainage piping or part thereof, constructed of materials other than those approved for use under or within a building, shall be installed under or within 2 feet (610 mm) of a building or structure, or less than 1 foot (305 mm) below the surface of the ground.

312.4 Corrosion, Erosion, and Mechanical Damage. Piping subject to corrosion, erosion, or mechanical damage shall be protected in an approved manner.

312.5 Protectively Coated Pipe. Protectively coated pipe or tubing shall be inspected and tested, and a visible void, damage, or imperfection to the pipe coating shall be repaired in an approved manner.

312.6 Freezing Protection. No water, soil, or waste pipe shall be installed or permitted outside of a building, in attics or crawl spaces, or in an exterior wall unless, where necessary, adequate provision is made to protect such pipe from freezing.

312.7 Fire-Resistant Construction. Piping penetrations of fire-resistance-rated walls, partitions, floors, floor/ceiling assemblies, roof/ceiling assemblies, or shaft enclosures shall be protected in accordance with the requirements of the building code and Chapter 14, "Firestop Protection."

312.8 Waterproofing of Openings. Joints at the roof around pipes, ducts, or other appurtenances shall be made

watertight by the use of lead, copper, galvanized iron, or other approved flashings or flashing material. Exterior wall openings shall be made watertight. Counterflashing shall not restrict the required internal cross-sectional area of the vent.

312.9 Steel Nail Plates. Plastic and copper or copper alloy piping penetrating framing members to within 1 inch (25.4 mm) of the exposed framing shall be protected by steel nail plates not less than No. 18 gauge (0.0478 inches) (1.2 mm) in thickness. The steel nail plate shall extend along the framing member not less than 1½ inches (38 mm) beyond the outside diameter of the pipe or tubing.

Exception: See Section 1210.3.3.

312.10 Sleeves. Sleeves shall be provided to protect piping through concrete and masonry walls, and concrete floors.

Exception: Sleeves shall not be required where openings are drilled or bored.

312.10.1 Building Loads. Piping through concrete or masonry walls shall not be subject to a load from building construction.

312.10.2 Exterior Walls. In exterior walls, annular space between sleeves and pipes shall be sealed and made watertight, as approved by the Authority Having Jurisdiction. A penetration through fire-resistive construction shall be in accordance with Section 312.7.

312.10.3 Firewalls. A pipe sleeve through a firewall shall have the space around the pipe completely sealed with an approved fire-resistive material in accordance with other codes.

312.11 Structural Members. A structural member weakened or impaired by cutting, notching, or otherwise shall be reinforced, repaired, or replaced so as to be left in a safe structural condition in accordance with the requirements of the building code.

312.12 Rodentproofing. Strainer plates on drain inlets shall be designed and installed so that no opening exceeds ½ of an inch (12.7 mm) in the least dimension.

312.12.1 Meter Boxes. Meter boxes shall be constructed in such a manner as to restrict rodents or vermin from entering a building by following the service pipes from the box into the building.

312.12.2 Metal Collars. In or on buildings where openings have been made in walls, floors, or ceilings for the passage of pipes, such openings shall be closed and protected by the installation of approved metal collars securely fastened to the adjoining structure.

312.12.3 Tub Waste Openings. Tub waste openings in framed construction to crawl spaces at or below the first floor shall be protected by the installation of approved metal collars or metal screen securely fastened to the adjoining structure with no opening exceeding ½ of an inch (12.7 mm) in the least dimension.

312.13 Exposed ABS Piping. ABS piping shall not be exposed to direct sunlight.

Exception: ABS piping exposed to sunlight that is protected by water based synthetic latex paints.

312.14 Exposed PVC Piping. PVC piping shall not be exposed to direct sunlight.

Exceptions:

- (1) PVC piping exposed to sunlight that is protected by water based synthetic latex paints.
- (2) PVC piping wrapped with not less than 0.04 inch (1.02 mm) thick tape or otherwise protected from UV degradation.

313.0 Hangers and Supports.

313.1 General. Piping, fixtures, appliances, and appurtenances shall be supported in accordance with this code, the manufacturer's installation instructions, and in accordance with the Authority Having Jurisdiction.

313.2 Material. Hangers and anchors shall be of sufficient strength to support the weight of the pipe and its contents. Piping shall be isolated from incompatible materials.

313.3 Suspended Piping. Suspended piping shall be supported at intervals not to exceed those shown in Table 313.3.

313.4 Alignment. Piping shall be supported in such a manner as to maintain its alignment and prevent sagging.

313.5 Underground Installation. Piping in the ground shall be laid on a firm bed for its entire length; where other support is otherwise provided, it shall be approved in accordance with Section 301.2.

313.6 Hanger Rod Sizes. Hanger rod sizes shall be not smaller than those shown in Table 313.6.

TABLE 313.6
HANGER ROD SIZES

| PIPE AND TUBE SIZE (inches) | ROD SIZE (inches) |
|--------------------------------|----------------------|
| ½ – 4 | ¾ |
| 5 – 8 | ½ |
| 10 – 12 | ¾ |

For SI units: 1 inch = 25.4 mm

313.7 Gas Piping. Gas piping shall be supported by metal straps or hooks at intervals not to exceed those shown in Table 1210.2.4.1.

314.0 Trenching, Excavation, and Backfill.

314.1 Trenches. Trenches deeper than the footing of a building or structure, and paralleling the same, shall be located not less than 45 degrees (0.79 rad) from the bottom exterior edge of the footing, or as approved in accordance with Section 301.2.

314.2 Tunneling and Driving. Tunneling and driving shall be permitted to be done in yards, courts, or driveways of a building site. Where sufficient depth is available to permit, tunnels shall be permitted to be used between open-cut trenches. Tunnels shall have a clear height of 2 feet (610 mm) above the pipe and shall be limited in length to one-half the depth of the trench, with a maximum length of 8 feet (2438 mm). Where

pipes are driven, the drive pipe shall be not less than one size larger than the pipe to be laid.

314.3 Open Trenches. Excavations required to be made for the installation of a building drainage system or part thereof, within the walls of a building, shall be open trench work and shall be kept open until the piping has been inspected, tested, and accepted.

314.4 Excavations. Excavations shall be completely backfilled as soon after inspection as practicable. Precaution shall be taken to ensure compactness of backfill around piping without damage to such piping. Trenches shall be backfilled in thin layers to 12 inches (305 mm) above the top of the piping with clean earth, which shall not contain stones, boulders, cinderfill, frozen earth, construction debris, or other materials that will damage or break the piping or cause corrosive action. Mechanical devices such as bulldozers, graders, etc., shall be permitted to then be used to complete backfill to grade. Fill shall be properly compacted. Precautions shall be taken to ensure permanent stability for pipe laid in filled or made ground.

Underground thermoplastic pipe and fittings for sewers and other gravity flow applications shall be installed in accordance with this code and Section 314.4.1.

314.4.1 Installation of Thermoplastic Pipe and Fittings. Trench width for thermoplastic sewer pipe shall be 1.25 times the outside diameter of the piping plus 12 inches (305 mm) or the outside diameter of the piping plus 16 inches (406 mm). Thermoplastic piping shall be bedded in not less than 4 inches (102 mm) of granular fill supporting the piping. The backfill for thermoplastic piping shall be compacted along the sides of the piping in 6 inch (152 mm) layers and continue to not less than 12 inches (305 mm) above the piping. Compaction shall be not less than a 85 percent standard proctor density.

315.0 Joints and Connections.

315.1 Unions. Approved unions shall be permitted to be used in drainage piping where accessibly located in the trap seal or between a fixture and its trap; in the vent system, except underground or in wet vents; at any point in the water supply system; and in gas piping as permitted by Section 1212.5.

315.2 Prohibited Joints and Connections. A fitting or connection that has an enlargement, chamber, or recess with a ledge, shoulder, or reduction of pipe area that offers an obstruction to flow through the drain shall be prohibited.

316.0 Increases and Reducers.

316.1 General. Where different sizes of pipes and fittings are to be connected, the proper size increasers or reducers or reducing fittings shall be used between the two sizes. Copper alloy or cast-iron body cleanouts shall not be used as a reducer or adapter from cast-iron drainage pipe to iron pipe size (IPS) pipe.

317.0 Food-Handling Establishments.

317.1 General. Food or drink shall not be stored, prepared, or displayed beneath soil or drain pipes, unless those areas

are protected against leakage or condensation from such pipes reaching the food or drink as described below. Where building design requires that soil or drain pipes be located over such areas, the installation shall be made with the least possible number of joints and shall be installed so as to connect to the nearest adequately sized vertical stack with the provisions as follows:

- (1) Openings through floors over such areas shall be sealed watertight to the floor construction.
- (2) Floor and shower drains installed above such areas shall be equipped with integral seepage pans.
- (3) Soil or drain pipes shall be of an approved material as listed in Table 1701.1 and Section 701.2. Materials shall comply with established standards. Cleanouts shall be extended through the floor construction above.
- (4) Piping subject to operation at temperatures that will form condensation on the exterior of the pipe shall be thermally insulated.
- (5) Where pipes are installed in ceilings above such areas, the ceiling shall be of the removable type, or shall be provided with access panels in order to form a ready access for inspection of piping.

318.0 Test Gauges.

318.1 General. Tests in accordance with this code, which are performed utilizing dial gauges, shall be limited to gauges having the following pressure graduations or incrementations.

318.2 Pressure Tests (10 psi or less). Required pressure tests of 10 pounds-force per square inch (psi) (69 kPa) or less shall be performed with gauges of 0.10 psi (0.69 kPa) incrementation or less.

318.3 Pressure Tests (greater than 10 psi to 100 psi). Required pressure tests exceeding 10 psi (69 kPa) but less than or equal to 100 psi (689 kPa) shall be performed with gauges of 1 psi (7 kPa) incrementation or less.

318.4 Pressure Tests (exceeding 100 psi). Required pressure tests exceeding 100 psi (689 kPa) shall be performed with gauges incremented for 2 percent or less of the required test pressure.

318.5 Pressure Range. Test gauges shall have a pressure range not exceeding twice the test pressure applied.

319.0 Medical Gas and Vacuum Systems.

319.1 General. Such piping shall be installed, tested, and verified in accordance with the applicable standards referenced in Table 1701.1 and the requirements of Chapter 13. The Authority Having Jurisdiction shall require evidence of the competency of the installers and verifiers.

320.0 Rehabilitation of Piping Systems.

320.1 General. Where pressure piping systems are rehabilitated using an epoxy lining system it shall be in accordance with ASTM F2831.

**TABLE 313.3
HANGERS AND SUPPORTS**

| MATERIALS | TYPES OF JOINTS | HORIZONTAL | VERTICAL |
|-----------------------------|---|---|--|
| Cast | Lead and Oakum | 5 feet, except 10 feet where 10 foot lengths are installed ^{1, 2, 3} | Base and each floor, not to exceed 15 feet |
| | Compression Gasket | Every other joint, unless over 4 feet then support each joint ^{1, 2, 3} | Base and each floor, not to exceed 15 feet |
| Cast-Iron Hubless | Shielded Coupling | Every other joint, unless over 4 feet then support each joint ^{1, 2, 3, 4} | Base and each floor, not to exceed 15 feet |
| Copper & Copper Alloys | Soldered, Brazed, Threaded, or Mechanical | 1½ inches and smaller, 6 feet; 2 inches and larger, 10 feet | Each floor, not to exceed 10 feet ⁵ |
| Steel Pipe for Water or DWV | Threaded or Welded | ¾ inch and smaller, 10 feet; 1 inch and larger, 12 feet | Every other floor, not to exceed 25 feet ⁵ |
| Steel Pipe for Gas | Threaded or Welded | ½ inch, 6 feet; ¾ inch and 1 inch, 8 feet; 1¼ inches and larger, 10 feet | ½ inch, 6 feet; ¾ inch and 1 inch, 8 feet; 1¼ inches every floor level |
| Schedule 40 PVC and ABS DWV | Solvent Cemented | All sizes, 4 feet; allow for expansion every 30 feet ³ | Base and each floor; provide mid-story guides; provide for expansion every 30 feet |
| CPVC | Solvent Cemented | 1 inch and smaller, 3 feet; 1¼ inches and larger, 4 feet | Base and each floor; provide mid-story guides |
| Lead | Wiped or Burned | Continuous Support | Not to exceed 4 feet |
| Steel | Mechanical | In accordance with standards acceptable to the Authority Having Jurisdiction | |
| PEX | Cold Expansion, Insert and Compression | 1 inch and smaller, 32 inches; 1¼ inches and larger, 4 feet | Base and each floor; provide mid-story guides |
| PEX-AL-PEX | Metal Insert and Metal Compression | ½ inch } ¾ inch } All sizes 98 inches 1 inch } | Base and each floor; provide mid-story guides |
| PE-AL-PE | Metal Insert and Metal Compression | ½ inch } ¾ inch } All sizes 98 inches 1 inch } | Base and each floor; provide mid-story guides |
| PE-RT | Insert and Compression | 1 inch and smaller, 32 inches; 1¼ inches and larger, 4 feet | Base and each floor; provide mid-story guides |
| Polypropylene (PP) | Fusion weld (socket, butt, saddle, electrofusion), threaded (metal threads only), or mechanical | 1 inch and smaller, 32 inches; 1¼ inches and larger, 4 feet | Base and each floor; provide mid-story guides |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm

Notes:

- ¹ Support adjacent to joint, not to exceed 18 inches (457 mm).
- ² Brace not to exceed 40 foot (12 192 mm) intervals to prevent horizontal movement.
- ³ Support at each horizontal branch connection.
- ⁴ Hangers shall not be placed on the coupling.
- ⁵ Vertical water lines shall be permitted to be supported in accordance with recognized engineering principles with regard to expansion and contraction, where first approved by the Authority Having Jurisdiction.

CHAPTER 4

PLUMBING FIXTURES AND FIXTURE FITTINGS

401.0 General.

401.1 Applicability. This chapter shall govern the materials and installation of plumbing fixtures, including faucets and fixture fittings, and the minimum number of plumbing fixtures required based on occupancy.

- » **401.2 Quality of Fixtures.** Plumbing fixtures shall be constructed of dense, durable, non-absorbent materials and shall have smooth, impervious surfaces, free from unnecessary concealed fouling surfaces. Except as permitted elsewhere in this code, fixtures shall comply with the quality and design of nationally recognized applicable standards referenced in Table 1701.1.

402.0 Installation.

402.1 Cleaning. Plumbing fixtures shall be installed in a manner to afford easy access for repairs and cleaning. Pipes from fixtures shall be run to the nearest wall.

402.2 Joints. Where a fixture comes in contact with the wall or floor, the joint between the fixture and the wall or floor shall be made watertight.

402.3 Securing Fixtures. Floor-outlet or floor-mounted fixtures shall be rigidly secured to the drainage connection and to the floor, where so designed, by screws or bolts of copper, copper alloy, or other equally corrosion-resistant material.

402.4 Wall-Hung Fixtures. Wall-hung fixtures shall be rigidly supported by metal supporting members so that no strain is transmitted to the connections. Flush tanks and similar appurtenances shall be secured by approved non-corrosive screws or bolts.

402.5 Setting. Fixtures shall be set level and in proper alignment with reference to adjacent walls. No water closet or bidet shall be set closer than 15 inches (381 mm) from its center to a side wall or obstruction nor closer than 30 inches (762 mm) center to center to a similar fixture. The clear space in front of a water closet, lavatory, or bidet shall be not less than 24 inches (610 mm). No urinal shall be set closer than 12 inches (305 mm) from its center to a side wall or partition nor closer than 24 inches (610 mm) center to center.

Exception: The installation of paper dispensers or accessibility grab bars shall not be considered obstructions.

402.6 Flanged Fixture Connections. Fixture connections between drainage pipes and water closets, floor outlet service sinks and urinals shall be made by means of approved copper alloy, hard lead, ABS, PVC, or iron flanges caulked, soldered, solvent cemented; rubber compression gaskets; or screwed to the drainage pipe. The connection shall be bolted with an approved gasket, washer, or setting compound between the fixture and the connection. The bottom of the flange shall be set on an approved firm base.

Wall-mounted water closet fixtures shall be securely bolted to an approved carrier fitting. The connecting pipe between the carrier fitting and the fixture shall be an approved

material and designed to accommodate an adequately sized gasket. Gasket material shall be neoprene, felt, or similar approved types.

402.6.1 Closet Rings (Closet Flanges). Closet rings (closet flanges) for water closets or similar fixtures shall be of an approved type and shall be copper alloy, copper, hard lead, cast-iron, galvanized malleable iron, ABS, PVC, or other approved materials. Each such closet ring (closet flange) shall be approximately 7 inches (178 mm) in diameter and, where installed, shall, together with the soil pipe, present a 1½ inch (38 mm) wide flange or face to receive the fixture gasket or closet seal.

Caulked-on closet rings (closet flanges) shall be not less than ¼ of an inch (6.4 mm) thick and not less than 2 inches (51 mm) in overall depth.

Closet rings (closet flanges) shall be burned or soldered to lead bends or stubs, shall be caulked to cast-iron soil pipe, shall be solvent cemented to ABS and PVC, and shall be screwed or fastened in an approved manner to other materials.

Closet bends or stubs shall be cut off so as to present a smooth surface even with the top of the closet ring before rough inspection is called.

Closet rings (closet flanges) shall be adequately designed and secured to support fixtures connected thereto.

402.6.2 Securing Closet Flanges. Closet screws, bolts, washers, and similar fasteners shall be of copper alloy, copper, or other listed, equally corrosion-resistant materials. Screws and bolts shall be of a size and number to properly support the fixture installed.

402.6.3 Securing Floor-Mounted, Back-Outlet Water Closet Bowls. Floor-mounted, back-outlet water closet bowls shall be set level with an angle of 90 degrees (1.57 rad) between the floor and wall at the centerline of the fixture outlet. The floor and wall shall have a flat mounting surface not less than 5 inches (127 mm) to the right and left of the fixture outlet centerline. The fixture shall be secured to the wall outlet flange or drainage connection and to the floor by corrosion-resistant screws or bolts. The closet flange shall be secured to a firm base.

Where floor-mounted, back-outlet water closets are used, the soil pipe shall be not less than 3 inches (80 mm) in diameter. Offset, eccentric, or reducing floor flanges shall not be used.

402.7 Supply Fittings. The supply lines and fittings for every plumbing fixture shall be so installed as to prevent backflow in accordance with Chapter 6.

402.8 Installation. Fixtures shall be installed in accordance with the manufacturer's installation instructions.

» **402.9 Design and Installation of Plumbing Fixtures.** Plumbing fixtures shall be installed such that fixture fittings shall be in accordance with the backflow prevention requirements of ASME A112.18.1/CSA B125.1. These requirements shall not be compromised by the designated fixture fitting mounting surface.

» **402.10 Slip Joint Connections.** Fixtures having concealed slip joint connections shall be provided with an access panel or utility space not less than 12 inches (305 mm) in its least dimension and so arranged without obstructions as to make such connections accessible for inspection and repair.

» **402.11 Future Fixtures.** Where provisions are made for the future installation of fixtures, those provided for shall be considered in determining the required sizes of drain and water supply piping. Construction for future installations shall be terminated with a plugged fitting or fittings. Where the plugged fitting is at the point where the trap of a fixture is installed, the plumbing system for such fixture shall be complete and be in accordance with the plumbing requirements of this code.

» **403.0 Accessible Plumbing Facilities.**

» **403.1 General.** Where accessible facilities are required in applicable building regulations, the facilities shall be installed in accordance with those regulations.

» **403.2 Fixtures and Fixture Fittings for Persons with Disabilities.** Plumbing fixtures and fixture fittings for persons with disabilities shall comply with ICC A117.1 and the applicable standards referenced in Chapter 4.

» **403.3 Exposed Pipes and Surfaces.** Water supply and drain pipes under accessible lavatories and sinks shall be insulated or otherwise be configured to protect against contact. Protectors, insulators, or both shall comply with ASME A112.18.9.

404.0 Overflows.

» **404.1 General.** Where a fixture is provided with an overflow, the waste shall be so arranged that the standing water in the fixture shall not rise in the overflow where the stopper is closed or remain in the overflow where the fixture is empty. The overflow pipe from a fixture shall be connected on the house or inlet side of the fixture trap, except that overflow on flush tanks shall be permitted to discharge into the water closets or urinals served by them, but it shall be unlawful to connect such overflows with any other part of the drainage system.

» **405.0 Prohibited Fixtures.**

» **405.1 Prohibited Water Closets.** Water closets having an invisible seal or an unventilated space or having walls which are not thoroughly washed at each discharge shall be prohibited. A water closet that might permit siphonage of the contents of the bowl back into the tank shall be prohibited.

» **405.2 Prohibited Urinals.** Trough urinals and urinals with an invisible seal shall be prohibited.

» **405.3 Miscellaneous Fixtures.** Fixed wooden, or tile wash trays or sinks for domestic use shall not be installed in a building designed or used for human habitation. No sheet metal-lined wooden bathtub shall be installed or reconnected. No dry or chemical closet (toilet) shall be installed in a building used for human habitation, unless first approved by the Health Officer.

406.0 Special Fixtures and Specialties.

» **406.1 Water and Waste Connections.** Baptisteries, ornamental and lily ponds, aquaria, ornamental fountain basins, and similar fixtures and specialties requiring water, waste connections, or both shall be submitted for approval to the Authority Having Jurisdiction prior to installation.

» **406.2 Special Use Sinks.** Restaurant kitchen and other special use sinks shall be permitted to be made of approved-type bonderized and galvanized sheet steel of not less than No. 16 U.S. gauge (0.0625 inches) (1.6 mm). Sheet-metal plumbing fixtures shall be adequately designed, constructed, and braced in an approved manner to accomplish their intended purpose.

» **406.3 Special Use Fixtures.** Special use fixtures shall be made of one of the following:

- (1) Soapstone
- (2) Chemical stoneware
- (3) Copper-based alloy
- (4) Nickel-based alloy
- (5) Corrosion-resistant steel
- (6) Other materials suited for the intended use of the fixture

» **406.4 Zinc Alloy Components.** Zinc alloy components shall comply with applicable nationally recognized standards and shall be used in accordance with their listing.

407.0 Lavatories.

» **407.1 Application.** Lavatories shall comply with ASME A112.19.1/CSA B45.2, ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, ASME A112.19.12, CSA B45.5/IAPMO Z124, or CSA B45.11/IAPMO Z401.

» **407.2 Water Consumption.** The maximum water flow rate of faucets shall comply with Section 407.2.1 and Section 407.2.2.

» **407.2.1 Maximum Flow Rate.** The maximum flow rate for public lavatory faucets shall not exceed 0.5 gpm at 60 psi (1.9 L/m at 414 kPa) and 2.2 gpm at 60 psi (8.3 L/m at 414 kPa) for private lavatory faucets in accordance with ASME A112.18.1/CSA B125.1.

» **407.2.2 Metering Faucets.** Metered faucets shall deliver a maximum of 0.25 gallons (1.0 L) per metering cycle in accordance with ASME A112.18.1/CSA B125.1.

» **407.3 Limitation of Hot Water Temperature for Public Lavatories.** Hot water delivered from public-use lavatories shall be limited to a maximum temperature of 120°F (49°C) by a device that is in accordance with ASSE 1070 or CSA B125.3. The water heater thermostat shall not be considered a control for meeting this provision.

407.4 Transient Public Lavatories. Self-closing or metering faucets shall be installed on lavatories intended to serve the transient public, such as those in, but not limited to service stations, train stations, airports, restaurants, and convention halls.

407.5 Waste Outlet. Lavatories shall have a waste outlet and fixture tailpiece not less than 1¼ inches (32 mm) in diameter. Continuous wastes and fixture tailpieces shall be constructed from the materials specified in Section 701.4. Waste outlets shall be provided with an approved stopper or strainer.

407.6 Overflow. Overflows shall be installed in accordance with Section 404.1.

408.0 Showers.

408.1 Application. Manufactured shower receptors and shower bases shall comply with ASME A112.19.1/CSA B45.2, ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, or CSA B45.5/IAPMO Z124.

408.2 Water Consumption. Showerheads shall have a maximum flow rate of not more than 2.5 gpm at 80 psi (9.5 L/m at 552 kPa), in accordance with ASME A112.18.1/CSA B125.1.

408.3 Individual Shower and Tub-Shower Combination Control Valves. Showers and tub-shower combinations shall be provided with individual control valves of the pressure balance, thermostatic, or combination pressure balance/thermostatic mixing valve type that provide scald and thermal shock protection for the rated flow rate of the installed showerhead. These valves shall be installed at the point of use and in accordance with ASSE 1016 or ASME A112.18.1/CSA B125.1. Gang showers, where supplied with a single temperature-controlled water supply pipe, shall be controlled by a mixing valve that is in accordance with ASSE 1069. Handle position stops shall be provided on such valves and shall be adjusted per the manufacturer's instructions to deliver a maximum mixed water setting of 120°F (49°C). Water heater thermostats shall not be considered a suitable control for meeting this provision.

408.4 Waste Outlet. Showers shall have a waste outlet and fixture tailpiece not less than 2 inches (50 mm) in diameter. Fixture tailpieces shall be constructed from the materials specified in Section 701.2 for drainage piping. Strainers serving shower drains shall have a waterway at least equivalent to the area of the tailpiece.

408.5 Finished Curb or Threshold. Where a shower receptor has a finished dam, curb, or threshold it shall be not less than 1 inch (25.4 mm) lower than the sides and back of such receptor. In no case shall a dam or threshold be less than 2 inches (51 mm) or exceeding 9 inches (229 mm) in depth where measured from the top of the dam or threshold to the top of the drain. Each such receptor shall be provided with an integral nailing flange to be located where the receptor meets the vertical surface of the finished interior of the shower compartment. The flange shall be watertight and extend vertically not less than 1 inch (25.4 mm) above the top of the sides of the receptor. The finished floor of the receptor shall slope uni-

formly from the sides towards the drain not less than ¼ inch per foot (20.8 mm/m), nor more than ½ inch per foot (41.8 mm/m).

Thresholds shall be of sufficient width to accommodate a minimum 22 inch (559 mm) door. Shower doors shall open so as to maintain not less than a 22 inch (559 mm) unobstructed opening for egress. The immediate adjoining space to showers without thresholds shall be considered a wet location and shall comply with the requirements of the building, residential, and electrical codes.

Exceptions:

- (1) Showers that are designed to be in accordance with the accessibility standards listed in Table 1701.1.
- (2) A cast-iron shower receptor flange shall be not less than 0.3 of an inch (7.62 mm) in height.
- (3) For flanges not used as a means of securing, the sealing flange shall be not less than 0.3 of an inch (7.62 mm) in height.

408.6 Shower Compartments. Shower compartments, regardless of shape, shall have a minimum finished interior of 1024 square inches (0.6606 m²) and shall also be capable of encompassing a 30 inch (762 mm) circle. The minimum required area and dimensions shall be measured at a height equal to the top of the threshold and at a point tangent to its centerline. The area and dimensions shall be maintained to a point of not less than 70 inches (1778 mm) above the shower drain outlet with no protrusions other than the fixture valve or valves, showerheads, soap dishes, shelves, and safety grab bars, or rails. Fold-down seats in accessible shower stalls shall be permitted to protrude into the 30 inch (762 mm) circle.

Exceptions:

- (1) Showers that are designed to be in accordance with ICC A117.1.
- (2) The minimum required area and dimension shall not apply for a shower receptor having overall dimensions of not less than 30 inches (762 mm) in width and 60 inches (1524 mm) in length.

408.7 Lining for Showers and Receptors. Shower receptors built on-site shall be watertight and shall be constructed from approved-type dense, nonabsorbent, and non-corrosive materials. Each such receptor shall be adequately reinforced, shall be provided with an approved flanged floor drain designed to make a watertight joint in the floor, and shall have smooth, impervious, and durable surfaces.

Showers receptors shall have the subfloor and rough side of walls to a height of not less than 3 inches (76 mm) above the top of the finished dam or threshold shall be first lined with sheet plastic, lead, or copper, or shall be lined with other durable and watertight materials. Showers that are provided with a built in place, permanent seat or seating area that is located within the shower enclosure, shall be first lined with sheet plastic, lead, copper, or shall be lined with other durable and watertight materials that extend not less than 3 inches (76 mm) above horizontal surfaces of the seat or the seating area.

Lining materials shall be pitched ¼ inch per foot (20.8 mm/m) to weep holes in the subdrain of a smooth and solidly formed subbase. Such lining materials shall extend upward on

the rough jambs of the shower opening to a point not less than 3 inches (76 mm) above the horizontal surfaces of the seat or the seating area, the top of the finished dam or threshold and shall extend outward over the top of the permanent seat, permanent seating area, or rough threshold and be turned over and fastened on the outside face of both the permanent seat, permanent seating area, or rough threshold and the jambs.

Nonmetallic shower subpans or linings shall be permitted to be built up on the job site of not less than three layers of standard grade 15 pound (6.8 kg) asphalt-impregnated roofing felt. The bottom layer shall be fitted to the formed subbase and each succeeding layer thoroughly hot-mopped to that below. Corners shall be carefully fitted and shall be made strong and watertight by folding or lapping, and each corner shall be reinforced with suitable webbing hot-mopped in place.

Folds, laps, and reinforcing webbing shall extend not less than 4 inches (102 mm) in all directions from the corner, and webbing shall be of approved type and mesh, producing a tensile strength of not less than 50 pounds per square foot (lb/ft²) (244 kg/m²) in either direction. Nonmetallic shower subpans or linings shall be permitted to consist of multilayers of other approved equivalent materials suitably reinforced and carefully fitted in place on the job site as elsewhere required in this section.

Linings shall be properly recessed and fastened to approved backing so as not to occupy the space required for the wall covering, and shall not be nailed or perforated at a point that is less than 1 inch (25.4 mm) above the finished dam or threshold. An approved-type subdrain shall be installed with a shower subpan or lining. Each such subdrain shall be of the type that sets flush with the subbase and shall be equipped with a clamping ring or other device to make a tight connection between the lining and the drain. The subdrain shall have weep holes into the waste line. The weep holes located in the subdrain clamping ring shall be protected from clogging.

408.7.1 PVC Sheets. Plasticized polyvinyl chloride (PVC) sheets shall comply with ASTM D4551. Sheets shall be joined by solvent cementing in accordance with the manufacturer's installation instructions.

408.7.2 Chlorinated Polyethylene (CPE) Sheets. Nonplasticized chlorinated polyethylene sheets shall comply with ASTM D4068. The liner shall be joined in accordance with the manufacturer's installation instructions.

408.7.3 Sheet Lead. Sheet lead shall weigh not less than 4 lb/ft² (19 kg/m²) and shall be coated with an asphalt paint or other approved coating. The lead sheet shall be insulated from conducting substances, other than the connecting drain, by 15 pound (6.8 kg) asphalt felt or an equivalent. Sheet lead shall be joined by burning.

408.7.4 Sheet Copper. Sheet copper shall comply with ASTM B152 and shall weigh not less than 12 ounces per square foot (oz/ft²) (3.7 kg/m²) or No. 24 B & S Gauge (0.02 inches) (0.51 mm). The copper sheet shall be insulated from conducting substances, other than the

connecting drain, by 15 pound (6.8 kg) asphalt felt or an equivalent. Sheet copper shall be joined by brazing or soldering.

408.7.5 Tests for Shower Receptors. Shower receptors shall be tested for watertightness by filling with water to the level of the rough threshold. The test plug shall be so placed that both upper and under sides of the subpan shall be subjected to the test at the point where it is clamped to the drain.

408.8 Public Shower Floors. Floors of public shower rooms shall have a nonskid surface and shall be drained in such a manner that wastewater from one bather shall not pass over areas occupied by other bathers. Gutters in public or gang shower rooms shall have rounded corners for easy cleaning and shall be sloped not less than 2 percent toward drains. Drains in gutters shall be spaced at a maximum of 8 feet (2438 mm) from sidewalls nor more than 16 feet (4877 mm) apart.

408.9 Location of Valves and Heads. Control valves and showerheads shall be located on the sidewall of shower compartments or otherwise arranged so that the showerhead does not discharge directly at the entrance to the compartment so that the bather can adjust the valves prior to stepping into the shower spray.

408.10 Water Supply Riser. A water supply riser from the shower valve to the showerhead outlet, whether exposed or not, shall be securely attached to the structure.

409.0 Bathtubs and Whirlpool Bathtubs.

409.1 Application. Bathtubs shall comply with ASME A112.19.1/CSA B45.2, ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, or CSA B45.5/IAPMO Z124. Whirlpool bathtubs shall comply with ASME A112.19.7/CSA B45.10. Pressure sealed doors within a bathtub or whirlpool bathtub enclosure shall comply with ASME A112.19.15.

409.2 Waste Outlet. Bathtubs and whirlpool bathtubs shall have a waste outlet and fixture tailpiece not less than 1½ inches (40 mm) in diameter. Fixture tailpieces shall be constructed from the materials specified in Section 701.2 for drainage piping. Waste outlets shall be provided with an approved stopper or strainer.

409.3 Overflow. Overflows shall be installed in accordance with Section 404.1.

409.4 Limitation of Hot Water in Bathtubs and Whirlpool Bathtubs. The maximum hot water temperature discharging from the bathtub and whirlpool bathtub filler shall be limited to 120°F (49°C) by a device that is in accordance with ASSE 1070 or CSA B125.3. The water heater thermostat shall not be considered a control for meeting this provision.

409.5 Backflow Protection. The water supply to a bathtub and whirlpool bathtub filler valve shall be protected by an air gap or in accordance with Section 417.0.

409.6 Installation and Access. Bathtubs and whirlpool bathtubs shall be installed in accordance with the manufacturer's installation instructions. Access openings shall be of size and opening to permit the removal and replacement of the circulation pump.

Whirlpool pump access located in the crawl space shall be located not more than 20 feet (6096 mm) from an access door, trap door, or crawl hole.

The circulation pump shall be located above the crown weir of the trap.

The pump and the circulation piping shall be self-draining to minimize water retention. Suction fittings on whirlpool bathtubs shall be listed in accordance with ASME A112.19.7/CSA B45.10.

409.6.1 Flexible PVC Hoses and Tubing. Flexible PVC hoses and tubing intended to be used on whirlpool bathtub water circulation systems or pneumatic systems shall be in accordance with IAPMO Z1033.

410.0 Bidets.

410.1 Application. Bidets shall comply with ASME A112.19.2/CSA B45.1 or ASME A112.19.3/CSA B45.4.

410.2 Backflow Protection. The water supply to the bidet shall be protected by an air gap or in accordance with Section 603.3.2, Section 603.3.5, or Section 603.3.6.

410.3 Limitation of Water Temperature in Bidets. The maximum hot water temperature discharging from a bidet shall be limited to 110°F (43°C) by a device that is in accordance with ASSE 1070 or CSA B125.3. The water heater thermostat shall not be considered a control for meeting this provision.

411.0 Water Closets.

411.1 Application. Water closets shall comply with ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, or CSA B45.5/IAPMO Z124. Water closet bowls for public use shall be of the elongated type. In nurseries, schools, and other similar places where plumbing fixtures are provided for the use of children less than 6 years of age, water closets shall be of a size and height suitable for children's use.

» **411.2 Water Consumption.** Water closets shall have a maximum consumption not to exceed 1.6 gallons (6.0 Lpf) of water per flush in accordance with ASME A112.19.2/CSA B45.1.

411.2.1 Dual Flush Water Closets. Dual flush water closets shall comply with ASME A112.19.14. The effective flush volume for dual flush water closets shall be defined as the composite, average flush volume of two reduced flushes and one full flush.

411.2.2 Flushometer Valve Activated Water Closets. Flushometer valve activated water closets shall have a maximum flush volume of 1.6 gallons (6.0 Lpf) of water per flush in accordance with ASME A112.19.2/CSA B45.1.

» **411.3 Water Closet Seats.** Water closet seats shall be properly sized for the water closet bowl type, and shall be of smooth, non-absorbent material. Seats, for public use, shall be of the elongated type and either of the open front type or have an automatic seat cover dispenser. Plastic seats shall comply with IAPMO Z124.5.

412.0 Urinals.

412.1 Application. Urinals shall comply with ASME A112.19.2/CSA B45.1, ASME A112.19.19, or CSA B45.5/IAPMO Z124. Urinals shall have an average water consumption not to exceed 1 gallon (3.8 Lpf) of water per flush.

412.1.1 Nonwater Urinals. Nonwater urinals shall have a barrier liquid sealant to maintain a trap seal. Nonwater urinals shall permit the uninhibited flow of waste through the urinal to the sanitary drainage system. Nonwater urinals shall be cleaned and maintained in accordance with the manufacturer's instructions after installation. Where nonwater urinals are installed, not less than one water supplied fixture unit (WSFU) shall be installed upstream on the same drain line to facilitate drain line flow and rinsing. Where nonwater urinals are installed they shall have a water distribution line rough-in to the urinal location to allow for the installation of an approved backflow prevention device in the event of a retrofit.

412.2 Backflow Protection. A water supply to a urinal shall be protected by an approved-type vacuum breaker or other approved backflow prevention device in accordance with Section 603.5.

413.0 Flushing Devices.

413.1 Where Required. Each water closet, urinal, clinical sink, or other plumbing fixture that depends on trap siphonage to discharge its waste contents shall be provided with a flushometer valve, flushometer tank, or flush tank designed and installed so as to supply water in sufficient quantity and rate of flow to flush the contents of the fixture to which it is connected, to cleanse the fixture, and to refill the fixture trap, without excessive water use. Flushing devices shall comply with the antisiphon requirements in accordance with Section 603.5.

413.2 Flushometer Valves. Flushometer valves and tanks shall comply with ASSE 1037 or CSA B125.3, and shall be installed in accordance with Section 603.5.1. No manually controlled flushometer valve shall be used to flush more than one urinal, and each such urinal flushometer valve shall be an approved, self-closing type discharging a predetermined quantity of water. Flushometers shall be installed so that they will be accessible for repair. Flushometer valves shall not be used where the water pressure is insufficient to properly operate them. Where the valve is operated, it shall complete the cycle of operation automatically, opening fully, and closing positively under the line water pressure. Each flushometer shall be provided with a means for regulating the flow through it.

413.3 Flush Tanks. Flush tanks for manual flushing shall be equipped with a flush valve in accordance with ASME A112.19.5/CSA B45.15 or CSA B125.3, and an antisiphon fill valve (ballcock) that is in accordance with ASSE 1002 or CSA B125.3 and installed in accordance with Section 603.5.2.

413.4 Water Supply for Flush Tanks. An adequate quantity of water shall be provided to flush and clean the fixture served. The water supply for flushing tanks and flushometer

tanks equipped for manual flushing shall be controlled by a float valve or other automatic device designed to refill the tank after each discharge and to completely shut off the water flow to the tank where the tank is filled to operational capacity. Provision shall be made to automatically supply water to the fixture so as to refill the trap seal after each flushing.

413.5 Overflows in Flush Tanks. Flush tanks shall be provided with overflows discharging into the water closet or urinal connected thereto. Overflows supplied as original parts with the fixture shall be of sufficient size to prevent tank flooding at the maximum rate at which the tank is supplied with water under normal operating conditions and where installed in accordance with the manufacturer's installation instructions.

414.0 Dishwashing Machines.

414.1 Application. Domestic dishwashing machines shall comply with UL 749. Commercial dishwashing machines shall comply with NSF 3 and UL 921.

414.2 Backflow Protection. The water supply connection to a commercial dishwashing machine shall be protected by an air gap or a backflow prevention device in accordance with Section 603.3.2, Section 603.3.5, Section 603.3.6, or ASSE 1004.

414.3 Drainage Connection. Domestic dishwashing machines shall discharge indirectly through an air gap fitting in accordance with Section 807.3 into a waste receptor, a wye branch fitting on the tailpiece of a kitchen sink, or dishwasher connection of a food waste disposer. Commercial dishwashing machines shall discharge indirectly through an air gap or direct connection in accordance with Section 704.3 with floor drain protection.

415.0 Drinking Fountains.

415.1 Application. Drinking fountains shall be self-closing and comply with ASME A112.19.1/CSA B45.2, ASME A112.19.2/CSA B45.1, or ASME A112.19.3/CSA B45.4, and NSF 61. Permanently installed electric water coolers shall also comply with UL 399.

415.2 Drinking Fountain Alternatives. Where food is consumed indoors, water stations shall be permitted to be substituted for drinking fountains. Bottle filling stations shall be permitted to be substituted for drinking fountains up to 50 percent of the requirements for drinking fountains. Drinking fountains shall not be required for an occupant load of 30 or less.

415.3 Drainage Connection. Drinking fountains shall be permitted to discharge directly into the drainage system or indirectly through an air break in accordance with Section 809.1.

415.4 Location. Drinking fountains shall not be installed in toilet rooms.

416.0 Emergency Eyewash and Shower Equipment.

416.1 Application. Emergency eyewash and shower equipment shall comply with ISEA Z358.1.

416.2 Water Supply. Emergency eyewash and shower equipment shall not be limited in the water supply flow rates. Flow rate, discharge pattern, and temperature of flushing fluids shall be provided in accordance with ISEA Z358.1 based on the hazardous material.

416.3 Installation. Emergency eyewash and shower equipment shall be installed in accordance with the manufacturer's installation instructions.

416.4 Location. Emergency eyewash and shower equipment shall be located on the same level as the hazard and accessible for immediate use. The path of travel shall be free of obstructions and shall be clearly identified with signage.

416.5 Drain. A drain shall not be required for emergency eyewash or shower equipment. Where a drain is provided, the discharge shall be in accordance with Section 811.0.

417.0 Faucets and Fixture Fittings.

417.1 Application. Faucets and fixture fittings shall comply with ASME A112.18.1/CSA B125.1. Fixture fittings covered under the scope of NSF 61 shall be in accordance with the requirements of NSF 61.

417.2 Deck Mounted Bath/Shower Valves. Deck mounted bath/shower transfer valves with integral backflow protection shall comply with ASME A112.18.1/CSA B125.1. This shall include handheld showers and other bathing appliances mounted on the deck of bathtubs or other bathing appliances that incorporate a hose or pull out feature.

417.3 Handheld Showers. Handheld showers shall comply with ASME A112.18.1/CSA B125.1. Handheld showers with integral backflow protection shall comply with ASME A112.18.1/CSA B125.1 or shall have a backflow prevention device that is in accordance with ASME A112.18.3 or ASSE 1014.

417.4 Faucets and Fixture Fittings with Hose Connected Outlets. Faucets and fixture fittings with pull out spout shall comply with ASME A112.18.1/CSA B125.1. Faucets and fixture fittings with pull out spouts with integral backflow protection shall comply with ASME A112.18.1/CSA B125.1 or shall have a backflow preventer device that is in accordance with ASME A112.18.3.

417.5 Separate Controls for Hot and Cold Water. Where two separate handles control the hot and cold water, the left-hand control of the faucet where facing the fixture fitting outlet shall control the hot water. Faucets and diverters shall be connected to the water distribution system so that hot water corresponds to the left side of the fixture fitting.

Single-handle mixing valves installed in showers and tub-shower combinations shall have the flow of hot water correspond to the markings on the fixture fitting.

418.0 Floor Drains.

418.1 Application. Floor drains shall comply with ASME A112.3.1, ASME A112.6.3, or CSA B79.

418.2 Strainer. Floor drains shall be considered plumbing fixtures, and each such drain shall be provided with an approved-type strainer having a waterway equivalent to the

area of the tailpiece. Floor drains shall be of an approved type and shall provide a watertight joint in the floor.

418.3 Location of Floor Drains. Floor drains shall be installed in the following areas:

- (1) Toilet rooms containing two or more water closets or a combination of one water closet and one urinal, except in a dwelling unit.
- (2) Commercial kitchens and in accordance with Section 704.3.
- (3) Laundry rooms in commercial buildings and common laundry facilities in multi-family dwelling buildings.
- (4) Boiler rooms.

418.4 Food Storage Areas. Where drains are provided in storerooms, walk-in freezers, walk-in coolers, refrigerated equipment, or other locations where food is stored, such drains shall have indirect waste piping. Separate waste pipes shall be run from each food storage area, each with an indirect connection to the building sanitary drainage system. Traps shall be provided in accordance with Section 801.3.2 of this code and shall be vented.

Indirect drains shall be permitted to be located in freezers or other spaces where freezing temperatures are maintained, provided that traps, where supplied, shall be located where the seal will not freeze. Otherwise, the floor of the freezer shall be sloped to a floor drain located outside of the storage compartment.

418.5 Floor Slope. Floors shall be sloped to floor drains.

419.0 Food Waste Disposers.

419.1 Application. Food waste disposal units shall comply with UL 430. Residential food waste disposers shall also comply with ASSE 1008.

419.2 Drainage Connection. Approved wye or other directional-type branch fittings shall be installed in continuous wastes connecting or receiving the discharge from a food waste disposer. No dishwasher drain shall be connected to a sink tailpiece, continuous waste, or trap on the discharge side of a food waste disposer.

419.3 Water Supply. A cold water supply shall be provided for food waste disposers. Such connection to the water supply shall be protected by an air gap or backflow prevention device in accordance with Section 603.2.

420.0 Sinks.

420.1 Application. Sinks shall comply with ASME A112.19.1/CSA B45.2, ASME A112.19.2/CSA B45.1, ASME A112.19.3/CSA B45.4, or CSA B45.5/IAPMO Z124. Moveable sink systems shall comply with ASME A112.19.12.

420.2 Water Consumption. Sink faucets shall have a maximum flow rate of not more than 2.2 gpm at 60 psi (8.3 L/m at 414 kPa) in accordance with ASME A112.18.1/CSA B125.1.

Exceptions:

- (1) Clinical sinks
- (2) Laundry trays
- (3) Service sinks

420.3 Pre-Rinse Spray Valve. Commercial food service pre-rinse spray valves shall have a maximum flow rate of 1.6 gallons per minute (gpm) at 60 pounds-force per square inch (psi) (6.0 L/m at 414 kPa) in accordance with ASME A112.18.1/CSA B125.1 and shall be equipped with an integral automatic shutoff.

420.4 Waste Outlet. Kitchen and laundry sinks shall have a waste outlet and fixture tailpiece not less than 1½ inches (40 mm) in diameter. Service sinks shall have a waste outlet and fixture tailpiece not less than 2 inches (50 mm) in diameter. Fixture tailpieces shall be constructed from the materials specified in Section 701.2 for drainage piping. Waste outlets shall be provided with an approved strainer.

421.0 Floor Sinks.

421.1 Application. Floor sinks shall comply with ASME A112.6.7.

421.2 Strainers. The waste outlet of a floor sink shall be provided with an approved strainer or grate that is removable and accessible.

422.0 Minimum Number of Required Fixtures.

422.1 Fixture Count. Plumbing fixtures shall be provided for the type of building occupancy and in the minimum number shown in Table 422.1. The total occupant load and occupancy classification shall be determined in accordance with the building code. Occupancy classification not shown in Table 422.1 shall be considered separately by the Authority Having Jurisdiction.

The minimum number of fixtures shall be calculated at 50 percent male and 50 percent female based on the total occupant load. Where information submitted indicates a difference in distribution of the sexes such information shall be used in order to determine the number of fixtures for each sex. Once the occupancy load and occupancy are determined, Table 422.1 shall be applied to determine the minimum number of plumbing fixtures required. Where applying the fixture ratios in Table 422.1 results in fractional numbers, such numbers shall be rounded to the next whole number. For multiple occupancies, fractional numbers shall be first summed and then rounded to the next whole number.

422.1.1 Family or Assisted-Use Toilet and Bathing Facilities. Where family or assisted-use toilet and bathing rooms are required, in applicable building regulations, the facilities shall be installed in accordance with those regulations.

422.2 Separate Facilities. Separate toilet facilities shall be provided for each sex.

Exceptions:

- (1) Residential installations.
- (2) In occupancies with a total occupant load of 10 or less, including customers and employees, one toilet facility, designed for use by no more than one person at a time, shall be permitted for use by both sexes.

- (3) In business and mercantile occupancies with a total occupant load of 50 or less including customers and employees, one toilet facility, designed for use by no more than one person at a time, shall be permitted for use by both sexes.

422.2.1 Family or Assisted-Use Toilet Facilities.

Where a separate toilet facility is required for each sex, and each toilet facility is required to have only one water closet, two family or assisted-use toilet facilities shall be permitted in place of the required separate toilet facilities.

422.3 Fixture Requirements for Special Occupancies. Additional fixtures shall be permitted to be required where unusual environmental conditions or referenced activities are encountered. In food preparation areas, fixture requirements shall be permitted to be dictated by health codes.

422.4 Toilet Facilities Serving Employees and Customers. Each building or structure shall be provided with toilet facilities for employees and customers. Requirements for customers and employees shall be permitted to be met with a single set of restrooms accessible to both groups.

Required toilet facilities for employees and customers located in shopping malls or centers shall be permitted to be met by providing a centrally located toilet facility accessible to several stores. The maximum travel distance from entry to any store to the toilet facility shall not exceed 300 feet (91 440 mm).

Required toilet facilities for employees and customers in other than shopping malls or centers shall have a maximum travel distance not to exceed 500 feet (152 m).

422.4.1 Access to Toilet Facilities. In multi-story buildings, accessibility to the required toilet facilities shall not exceed one vertical story. Access to the required toilet facilities for customers shall not pass through areas designated as for employee use only such as kitchens, food preparation areas, storage rooms, closets, or similar spaces. Toilet facilities accessible only to private offices shall not be counted to determine compliance with this section.

422.5 Toilet Facilities for Workers. Toilet facilities shall be provided and maintained in a sanitary condition for the use of workers during construction.

TABLE 422.1
MINIMUM PLUMBING FACILITIES¹

Each building shall be provided with sanitary facilities, including provisions for persons with disabilities as prescribed by the Department Having Jurisdiction. Table 422.1 applies to new buildings, additions to a building, and changes of occupancy or type in an existing building resulting in increased occupant load.

| TYPE OF OCCUPANCY ² | WATER CLOSETS (FIXTURES PER PERSON) ³ | | URINALS (FIXTURES PER PERSON) ⁴ | LAVATORIES (FIXTURES PER PERSON) ^{5, 6} | | BATHTUBS OR SHOWERS (FIXTURES PER PERSON) | DRINKING FOUNTAINS/FACILITIES (FIXTURES PER PERSON) | OTHER |
|---|--|--|--|--|--|---|--|--------------------------------|
| A-1 Assembly occupancy (fixed or permanent seating)- theatres, concert halls and auditoriums | Male 1: 1-100 2: 101-200 3: 201-400 | Female 1: 1-25 2: 26-50 3: 51-100 4: 101-200 6: 201-300 8: 301-400 | Male 1: 1-200 2: 201-300 3: 301-400 4: 401-600 | Male 1: 1-200 2: 201-400 3: 401-600 4: 601-750 | Female 1: 1-100 2: 101-200 4: 201-300 5: 301-500 6: 501-750 | — | 1: 1-250 2: 251-500 3: 501-750 | 1 service sink or laundry tray |
| | Over 400, add 1 fixture for each additional 500 males and 1 fixture for each additional 125 females. | | Over 600, add 1 fixture for each additional 300 males. | Over 750, add 1 fixture for each additional 250 males and 1 fixture for each additional 200 females. | | — | Over 750, add 1 fixture for each additional 500 persons. | |
| A-2 Assembly occupancy- restaurants, pubs, lounges, night clubs and banquet halls | Male 1: 1-50 2: 51-150 3: 151-300 4: 301-400 | Female 1: 1-25 2: 26-50 3: 51-100 4: 101-200 6: 201-300 8: 301-400 | Male 1: 1-200 2: 201-300 3: 301-400 4: 401-600 | Male 1: 1-150 2: 151-200 3: 201-400 | Female 1: 1-150 2: 151-200 4: 201-400 | — | 1: 1-250 2: 251-500 3: 501-750 | 1 service sink or laundry tray |
| | Over 400, add 1 fixture for each additional 250 males and 1 fixture for each 125 females. | | Over 600, add 1 fixture for each additional 300 males. | Over 400, add 1 fixture for each additional 250 males and 1 fixture for each additional 200 females. | | — | Over 750, add 1 fixture for each additional 500 persons. | |
| A-3 Assembly occupancy (typical without fixed or permanent seating)- arcades, places of worship, museums, libraries, lecture halls, gymnasiums (without spectator seating), indoor pools (without spectator seating) | Male 1: 1-100 2: 101-200 3: 201-400 | Female 1: 1-25 2: 26-50 3: 51-100 4: 101-200 6: 201-300 8: 301-400 | Male 1: 1-100 2: 101-200 3: 201-400 4: 401-600 | Male 1: 1-200 2: 201-400 3: 401-600 4: 601-750 | Female 1: 1-100 2: 101-200 4: 201-300 5: 301-500 6: 501-750 | — | 1: 1-250 2: 251-500 3: 501-750 | 1 service sink or laundry tray |
| | Over 400, add 1 fixture for each additional 500 males and 1 fixture for each additional 125 females. | | Over 600, add 1 fixture for each additional 300 males. | Over 750, add 1 fixture for each additional 250 males and 1 fixture for each additional 200 females. | | — | Over 750, add 1 fixture for each additional 500 persons. | |
| A-4 Assembly occupancy (indoor activities or sporting events with spectator seating)- swimming pools, skating rinks, arenas and gymnasiums | Male 1: 1-100 2: 101-200 3: 201-400 | Female 1: 1-25 2: 26-50 3: 51-100 4: 101-200 6: 201-300 8: 301-400 | Male 1: 1-100 2: 101-200 3: 201-400 4: 401-600 | Male 1: 1-200 2: 201-400 3: 401-750 | Female 1: 1-100 2: 101-200 4: 201-300 5: 301-500 6: 501-750 | — | 1: 1-250 2: 251-500 3: 501-750 | 1 service sink or laundry tray |
| | Over 400, add 1 fixture for each additional 500 males and 1 fixture for each additional 125 females. | | Over 600, add 1 fixture for each additional 300 males. | Over 750, add 1 fixture for each additional 250 males and 1 fixture for each additional 200 females. | | — | Over 750, add 1 fixture for each additional 500 persons. | |

TABLE 422.1
MINIMUM PLUMBING FACILITIES¹ (continued)

| TYPE OF OCCUPANCY ² | WATER CLOSETS (FIXTURES PER PERSON) ³ | | URINALS (FIXTURES PER PERSON) ⁴ | LAVATORIES (FIXTURES PER PERSON) ^{5, 6} | | BATHTUBS OR SHOWERS (FIXTURES PER PERSON) | DRINKING FOUNTAINS/ FACILITIES (FIXTURES PER PERSON) | OTHER |
|--|--|--|--|--|--|--|--|--------------------------------|
| A-5 Assembly occupancy (outdoor activities or sporting events)- amusement parks, grandstands and stadiums | Male 1: 1-100 2: 101-200 3: 201-400 | Female 1: 1-25 2: 26-50 3: 51-100 4: 101-200 6: 201-300 8: 301-400 | Male 1: 1-100 2: 101-200 3: 201-400 4: 401-600 | Male 1: 1-200 2: 201-400 3: 401-750 | Female 1: 1-100 2: 101-200 4: 201-300 5: 301-500 6: 501-750 | — | 1: 1-250 2: 251-500 3: 501-750 | 1 service sink or laundry tray |
| | Over 400, add 1 fixture for each additional 500 males and 1 fixture for each additional 125 females. | | Over 600, add 1 fixture for each additional 300 males. | Over 750, add 1 fixture for each additional 250 males and 1 fixture for each additional 200 females. | | | Over 750, add 1 fixture for each additional 500 persons. | |
| B Business occupancy (office, professional or service type transactions)- banks, vet clinics, hospitals, car wash, banks, beauty salons, ambulatory health care facilities, laundries and dry cleaning, educational institutions (above high school), or training facilities not located within school, post offices and printing shops | Male 1: 1-50 2: 51-100 3: 101-200 4: 201-400 | Female 1: 1-15 2: 16-30 3: 31-50 4: 51-100 8: 101-200 11: 201-400 | Male 1: 1-100 2: 101-200 3: 201-400 4: 401-600 | Male 1: 1-75 2: 76-150 3: 151-200 4: 201-300 5: 301-400 | Female 1: 1-50 2: 51-100 3: 101-150 4: 151-200 5: 201-300 6: 301-400 | — | 1 per 150 | 1 service sink or laundry tray |
| | Over 400, add 1 fixture for each additional 500 males and 1 fixture for each additional 150 females. | | Over 600, add 1 fixture for each additional 300 males. | Over 400, add 1 fixture for each additional 250 males and 1 fixture for each additional 200 females. | | | | |
| E Educational occupancy-private or public schools | Male 1 per 50 | Female 1 per 30 | Male 1 per 100 | Male 1 per 40 | Female 1 per 40 | — | 1 per 150 | 1 service sink or laundry tray |
| F1, F2 Factory or Industrial occupancy-fabricating or assembly work | Male 1: 1-50 2: 51-75 3: 76-100 | Female 1: 1-50 2: 51-75 3: 76-100 | — | Male 1: 1-50 2: 51-75 3: 76-100 | Female 1: 1-50 2: 51-75 3: 76-100 | 1 shower for each 15 persons exposed to excessive heat or to skin contamination with poisonous, infectious or irritating material. | 1: 1-250 2: 251-500 3: 501-750 | 1 service sink or laundry tray |
| | Over 100, add 1 fixture for each additional 40 persons. | | — | Over 100, add 1 fixture for each additional 40 persons. | | | Over 750, add 1 fixture for each additional 500 persons. | |
| I-1 Institutional occupancy (houses more than 16 persons on a 24-hour basis)- substance abuse centers, assisted living, group homes, or residential facilities | Male 1 per 15 | Female 1 per 15 | — | Male 1 per 15 | Female 1 per 15 | 1 per 8 | 1 per 150 | 1 service sink or laundry tray |

TABLE 422.1
MINIMUM PLUMBING FACILITIES¹ (continued)

| TYPE OF OCCUPANCY ² | | WATER CLOSETS (FIXTURES PER PERSON) ³ | | URINALS (FIXTURES PER PERSON) ⁴ | LAVATORIES (FIXTURES PER PERSON) ^{5, 6} | | BATHTUBS OR SHOWERS (FIXTURES PER PERSON) | DRINKING FOUNTAINS/FACILITIES (FIXTURES PER PERSON) | OTHER |
|--|--|---|--|--|---|--|---|--|--------------------------------|
| I-2 Institutional occupancy-medical, psychiatric, surgical or nursing homes | Hospitals and nursing homes-individual rooms and ward room | 1 per room | | — | 1 per room | | 1 per room | 1 per 150 | 1 service sink or laundry tray |
| | | 1 per 8 patients | | — | 1 per 10 patients | | 1 per 20 patients | | |
| | Hospital Waiting or Visitor Rooms | 1 per room | | — | 1 per room | | — | 1 per room | — |
| | Employee Use | Male 1: 1-15 2: 16-35 3: 36-55 | Female 1: 1-15 3: 16-35 4: 36-55 | — | Male 1 per 40 | Female 1 per 40 | — | — | — |
| Over 55, add 1 fixture for each additional 40 persons. | | | | | | | | | |
| I-3 Institutional occupancy (houses more than 5 people) | Prisons | 1 per cell | | — | 1 per cell | | 1 per 20 | 1 per cell block/floor | — |
| | Correc-tional facilities or juvenile center | 1 per 8 | | — | 1 per 10 | | 1 per 8 | 1 per floor | 1 service sink or laundry tray |
| | Employee Use | Male 1: 1-15 2: 16-35 3: 36-55 | Female 1: 1-15 3: 16-35 4: 36-55 | — | Male 1 per 40 | Female 1 per 40 | — | 1 per 150 | — |
| | | Over 55, add 1 fixture for each additional 40 persons. | | | | | | | |
| I-4 Institutional occupancy (any age that receives care for less than 24 hours) | | Male 1: 1-15 2: 16-35 3: 36-55 | Female 1: 1-15 3: 16-35 4: 36-55 | — | Male 1 per 40 | Female 1 per 40 | — | 1 per 150 | 1 service sink or laundry tray |
| | | Over 55, add 1 fixture for each additional 40 persons. | | | | | | | |
| M Mercantile occupancy (the sale of merchandise and accessible to the public) | | Male 1: 1-100 2: 101-200 3: 201-400 | Female 1: 1-100 2: 101-200 4: 201-300 6: 301-400 | Male 0: 1-200 1: 201-400 | Male 1: 1-200 2: 201-400 | Female 1: 1-200 2: 201-300 3: 301-400 | — | 1: 1-250 2: 251-500 3: 501-750 | 1 service sink or laundry tray |
| | | Over 400, add 1 fixture for each additional 500 males and 1 fixture for each 200 females. | | Over 400, add 1 fixture for each additional 500 males. | Over 400, add 1 fixture for each additional 500 males and 1 fixture for each 400 females. | | — | Over 750, add 1 fixture for each additional 500 persons. | — |
| R-1 Residential occupancy (minimal stay)-hotels, motels, bed and breakfast homes | | 1 per sleeping room | | — | 1 per sleeping room | | 1 per sleeping room | — | 1 service sink or laundry tray |

TABLE 422.1
MINIMUM PLUMBING FACILITIES¹ (continued)

| TYPE OF OCCUPANCY ² | | WATER CLOSETS (FIXTURES PER PERSON) ³ | | URINALS (FIXTURES PER PERSON) ⁴ | LAVATORIES (FIXTURES PER PERSON) ^{5, 6} | | BATHTUBS OR SHOWERS (FIXTURES PER PERSON) | DRINKING FOUNTAINS/ FACILITIES (FIXTURES PER PERSON) | OTHER |
|--|-----------------|--|--|---|--|--|---|--|--|
| R-2 Residential occupancy (long-term or permanent) | Dormitories | Male 1 per 10 | Female 1 per 8 | 1 per 25 | Male 1 per 12 | Female 1 per 12 | 1 per 8 | 1 per 150 | 1 service sink or laundry tray |
| | | Add 1 fixture for each additional 25 males and 1 fixture for each additional 20 females. | | Over 150, add 1 fixture for each additional 50 males. | Add 1 fixture for each additional 20 males and 1 fixture for each additional 15 females. | | | | |
| | Employee Use | Male 1: 1-15 2: 16-35 3: 36-55 | Female 1: 1-15 3: 16-35 4: 36-55 | — | Male 1 per 40 | Female 1 per 40 | — | — | |
| | | Over 55, add 1 fixture for each additional 40 persons | | | | | | | |
| Apartment house/unit | 1 per apartment | | — | 1 per apartment | | 1 per apartment | — | 1 kitchen sink per apartment. 1 laundry tray or 1 automatic clothes washer connection per unit or 1 laundry tray or 1 automatic clothes washer connection for each 12 units | |
| R-3 Residential occupancy (long-term or permanent in nature) for more than 5 but does not exceed 16 occupants) | | Male 1 per 10 | Female 1 per 8 | — | Male 1 per 12 | Female 1 per 12 | 1 per 8 | 1 per 150 | 1 service sink or laundry tray |
| | | Add 1 fixture for each additional 25 males and 1 fixture for each additional 20 females. | | | Add 1 fixture for each additional 20 males and 1 fixture for each additional 15 females. | | | | |
| R-3 Residential occupancy (one and two family dwellings) | | 1 per one and two family dwelling | | — | 1 per one and two family dwelling | | 1 per one and two family dwelling | — | 1 kitchen sink and 1 automatic clothes washer connection per one and two family dwelling |
| R-4 Residential occupancy (residential care or assisted living) | | Male 1 per 10 | Female 1 per 8 | — | Male 1 per 12 | Female 1 per 12 | 1 per 8 | 1 per 150 | 1 service sink or laundry tray |
| | | Add 1 fixture for each additional 25 males and 1 fixture for each additional 20 females. | | | Add 1 fixture for each additional 20 males and 1 fixture for each additional 15 females. | | | | |
| S-1, S-2 Storage occupancy-storage of goods, warehouse, aircraft hanger, food products, appliances | | Male 1: 1-100 2: 101-200 3: 201-400 | Female 1: 1-100 2: 101-200 3: 201-400 | — | Male 1: 1-200 2: 201-400 3: 401-750 | Female 1: 1-200 2: 201-400 3: 401-750 | — | 1: 1-250 2: 251-500 3: 501-750 | 1 service sink or laundry tray |
| | | Over 400, add 1 fixture for each additional 500 males and 1 fixture for each additional 150 females. | | | Over 750, add 1 fixture for each additional 500 persons. | | | Over 750, add 1 fixture for each additional 500 persons. | |

Notes:

¹ The figures shown are based upon one fixture being the minimum required for the number of persons indicated or any fraction thereof.

² A restaurant is defined as a business that sells food to be consumed on the premises.

a. The number of occupants for a drive-in restaurant shall be considered as equal to the number of parking stalls.

b. Hand-washing facilities shall be available in the kitchen for employees.

³ The total number of required water closets for females shall be not less than the total number of required water closets and urinals for males.

⁴ For each urinal added in excess of the minimum required, one water closet shall be permitted to be deducted. The number of water closets shall not be reduced to less than two-thirds of the minimum requirement.

⁵ Group lavatories that are 24 lineal inches (610 mm) of wash sink or 18 inches (457 mm) of a circular basin, where provided with water outlets for such space, shall be considered equivalent to one lavatory.

⁶ Metering or self closing faucets shall be installed on lavatories intended to serve the transient public.

CHAPTER 5

WATER HEATERS

501.0 General.

501.1 Applicability. The regulations of this chapter shall govern the construction, location, and installation of fuel-burning and other types of water heaters heating potable water, together with chimneys, vents, and their connectors. The minimum capacity for storage water heaters shall be in accordance with the first hour rating listed in Table 501.1(1).

No water heater shall be hereinafter installed that does not comply with the manufacturer's installation instructions and the type and model of each size thereof approved by the Authority Having Jurisdiction. A list of accepted water heater appliance standards are referenced in Table 501.1(2). Listed appliances shall be installed in accordance with the manufacturer's installation instructions. Unlisted water heaters shall be permitted in accordance with Section 504.3.2.

502.0 Permits.

502.1 General. It shall be unlawful for a person to install, remove, or replace or cause to be installed, removed, or replaced a water heater without first obtaining a permit from the Authority Having Jurisdiction to do so.

503.0 Inspection.

503.1 Inspection of Chimneys or Vents. This inspection shall be made after chimneys, vents, or parts thereof, authorized by the permit, have been installed and before such vent or part thereof has been covered or concealed.

503.2 Final Water Heater Inspection. This inspection shall be made after work authorized by the permit has been installed. The Authority Having Jurisdiction will make such inspection as deemed necessary to be assured that the work has been installed in accordance with the intent of this code. No appliance or part thereof shall be covered or concealed until the same has been inspected and approved by the Authority Having Jurisdiction.

504.0 Water Heater Requirements.

504.1 Location. Water heater installations in bedrooms and bathrooms shall be in accordance with one of the following [NFPA 54:10.28.1]:

- (1) Fuel-burning water heaters shall be permitted to be installed in a closet located in the bedroom or bathroom provided the closet is equipped with a listed, gasketed door assembly and a listed self-closing device. The self-closing door assembly shall meet the requirements of Section 504.1.1. The door assembly shall be installed with a threshold and bottom door seal and shall meet the requirements of Section 504.1.2. Combustion air for such installations shall be obtained from the outdoors in accordance with Section 506.4. The closet shall be for the exclusive use of the water heater.
- (2) Water heater shall be of the direct vent type. [NFPA 54:10.28.1(2)]

504.1.1 Self-Closing Doors. Self-closing doors shall swing easily and freely, and shall be equipped with a self-closing device to cause the door to close and latch each time it is opened. The closing mechanism shall not have a hold-open feature.

504.1.2 Gasketing. Gasketing on gasketed doors or frames shall be furnished in accordance with the published listings of the door, frame, or gasketing material manufacturer.

Exception: Where acceptable to the Authority Having Jurisdiction, gasketing of non-combustible or limited-combustible material shall be permitted to be applied to the frame, provided closing and latching of the door are not inhibited.

504.2 Vent. Water heaters of other than the direct-vent type shall be located as close as practical to the chimney or gas vent.

504.3 Clearance. The clearance requirements for water heaters shall comply with Section 504.3.1 or Section 504.3.2.

504.3.1 Listed Water Heaters. The clearances shall not be such as to interfere with combustion air, draft hood clearance and relief, and accessibility for servicing. Listed water heaters shall be installed in accordance with their listings and the manufacturer's installation instructions.

504.3.2 Unlisted Water Heaters. Unlisted water heaters shall be installed with a clearance of 12 inches (305 mm) on all sides and rear. Combustible floors under unlisted water heaters shall be protected in an approved manner. [NFPA 54:10.28.2.2]

TABLE 501.1(1)
FIRST HOUR RATING¹

| Number of Bathrooms | 1 to 1.5 | | | 2 to 2.5 | | | | 3 to 3.5 | | | |
|---|----------|----|----|----------|----|----|----|----------|----|----|----|
| Number of Bedrooms | 1 | 2 | 3 | 2 | 3 | 4 | 5 | 3 | 4 | 5 | 6 |
| First Hour Rating, ² Gallons | 42 | 54 | 54 | 54 | 67 | 67 | 80 | 67 | 80 | 80 | 80 |

For SI units: 1 gallon = 3.785 L

Notes:

¹ The first hour rating is found on the "Energy Guide" label.

² Solar water heaters shall be sized to meet the appropriate first hour rating as shown in the table.

504.4 Pressure-Limiting Devices. A water heater installation shall be provided with overpressure protection by means of an approved, listed device installed in accordance with the terms of its listing and the manufacturer's installation instructions.

504.5 Temperature-Limiting Devices. A water heater installation or a hot water storage vessel installation shall be provided with overtemperature protection by means of an approved, listed device installed in accordance with the terms of its listing and the manufacturer's installation instructions.

504.6 Temperature, Pressure, and Vacuum Relief Devices. Temperature, pressure, and vacuum relief devices or combinations thereof, and automatic gas shutoff devices, shall be installed in accordance with the terms of their listings and the manufacturer's installation instructions. A shutoff valve shall not be placed between the relief valve and the water heater or on discharge pipes between such valves and the atmosphere. The hourly British thermal units (Btu) (kW•h) discharge capacity or the rated steam relief capacity of the device shall be not less than the input rating of the water heater.

505.0 Oil-Burning and Other Water Heaters.

505.1 Water Heaters. Water heaters deriving heat from fuels or types of energy other than gas shall be constructed and installed in accordance with the approved standards referenced in Table 501.1(2), Section 505.3, or Section 505.4. Vents or chimneys for such appliances shall be approved types. An adequate supply of air for combustion and for adequate ventilation of heater rooms or compartments shall be provided. Each such appliance shall be installed in a location approved by the Authority Having Jurisdiction and local and state fire-prevention agencies.

505.2 Safety Devices. Storage-type water heaters and hot water boilers deriving heat from fuels or types of energy other than gas, shall be provided with, in addition to the primary temperature controls, an overtemperature safety protection device constructed, listed, and installed in accordance with nationally recognized applicable standards for such devices and a combination temperature and pressure-relief valve.

505.3 Oil-Fired Water Heaters. Oil-fired water heaters shall be installed in accordance with NFPA 31.

505.4 Indirect-Fired Water Heaters. Indirect-fired water heaters shall comply with the applicable sections of the ASME Boiler and Pressure Vessel Code, or to one of the other applicable standards shown in Table 501.1(2). Each water heater shall bear a label in accordance with ASME requirements, or an approved testing agency, certifying and attesting that such an

appliance has been tested, inspected and meets the requirements of the applicable standards or code.

505.4.1 Single-Wall Heat Exchanger. An indirect-fired water heater that incorporates a single-wall heat exchanger shall be in accordance with the following requirements:

- (1) The heat transfer medium shall be either potable water or contain fluids recognized as safe by the Food and Drug Administration (FDA) as food grade.
- (2) Bear a label with the word "Caution," followed by the following statements:
 - (a) The heat-transfer medium shall be potable water or other nontoxic fluid recognized as safe by the FDA.
 - (b) The maximum operating pressure of the heat exchanger shall not exceed the maximum operating pressure of the potable water supply.
- (3) The word "Caution" and the statements in letters shall have an uppercase height of not less than 0.120 of an inch (3.048 mm). The vertical spacing between lines of type shall be not less than 0.046 of an inch (1.168 mm). Lowercase letters shall be compatible with the uppercase letter size specification.

506.0 Air for Combustion and Ventilation.

506.1 General. Air for combustion, ventilation, and dilution of flue gases for appliances installed in buildings shall be obtained by application of one of the methods covered in Section 506.2 through Section 506.7.3. Where the requirements of Section 506.2 are not met, outdoor air shall be introduced in accordance with methods covered in Section 506.4 through Section 506.7.3.

Exception: This provision shall not apply to direct-vent appliances. [NFPA 54:9.3.1.1]

506.1.1 Other Types of Appliances. Appliances of other than natural draft design and other than Category I vented appliances shall be provided with combustion, ventilation, and dilution air in accordance with the appliance manufacturer's instructions. [NFPA 54:9.3.1.2]

506.1.2 Draft Hood and Regulators. Where used, a draft hood or a barometric draft regulator shall be installed in the same room or enclosure as the appliance served so as to prevent a difference in pressure between the hood or regulator and the combustion air supply. [NFPA 54:9.3.1.4]

506.1.3 Makeup Air. Where exhaust fans, clothes dryers, and kitchen ventilation systems interfere with the operation of appliances, makeup air shall be provided. [NFPA 54:9.3.1.5]

506.2 Indoor Combustion Air. The required volume of indoor air shall be determined in accordance with Section 506.2.1 or Section 506.2.2, except that where the air infiltration rate is known to be less than 0.40 ACH (air change per hour), Section 506.2.2 shall be used. The total required volume shall be the sum of the required volume calculated for appliances located within the space. Rooms communicating directly with the space in which the appliances are installed through openings not furnished with doors, and through combustion air

TABLE 501.1(2)
WATER HEATERS

| TYPE | STANDARD |
|---------------------------|--------------|
| Electric, Household | UL 174 |
| Oil Fired Storage Tank | UL 732 |
| Gas, 75 000 Btu/h or less | CSA Z21.10.1 |
| Gas, Above 75 000 Btu/h | CSA Z21.10.3 |
| Electric, Commercial | UL 1453 |
| Solid Fuel | UL 2523 |

For SI units: 1000 British thermal units per hour = 0.293 kW

openings sized and located in accordance with Section 506.3 are considered a part of the required volume. [NFPA 54:9.3.2]

506.2.1 Standard Method. The required volume shall be not less than 50 cubic feet per 1000 British thermal units per hour (Btu/h) (4.83 m³/kW). [NFPA 54:9.3.2.1]

506.2.2 Known Air Infiltration Rate Method. Where the air infiltration rate of a structure is known, the required volume shall be not less than the following [NFPA 54:9.3.2.2]:

- (1) For appliances other than fan-assisted, calculate using Equation 506.2.2(1). [NFPA 54:9.3.2.2(1)]
- (2) For fan-assisted appliances, calculate using Equation 506.2.2(2). [NFPA 54:9.3.2.2(2)]
- (3) For purposes of these calculations, an infiltration rate greater than 0.60 ACH shall not be used in the equations. [NFPA 54:9.3.2.2(3)]

[Equation 506.2.2(1)]

Required volume $_{other} \geq (21 \text{ ft}^3 / \text{ACH}) \times (I_{other} / 1000 \text{ Btu/h})$

[Equation 506.2.2(2)]

Required volume $_{fan} \geq (15 \text{ ft}^3 / \text{ACH}) \times (I_{fan} / 1000 \text{ Btu/h})$

Where:

I_{other} = Appliances other than fan-assisted input in Btu/h
 I_{fan} = Fan-assisted appliance input in Btu/h
 ACH = Air change per hour (percent of volume of space exchanged per hour, expressed as a decimal)

For SI units: 1 cubic foot = 0.0283 m³, 1000 British thermal units per hour = 0.293 kW

506.3 Indoor Opening Size and Location. Openings used to connect indoor spaces shall be sized and located in accordance with the following:

- (1) Each opening shall have a free area of not less than 1 square inch per 1000 Btu/h (0.002 m²/kW) of the total input rating of appliances in the space, but not less than 100 square inches (0.065 m²). One opening shall commence within 12 inches (305 mm) of the top of the enclosure and one opening shall commence within 12 inches (305 mm) of the bottom of the enclosure (see Figure 506.3). The dimension of air openings shall be not less than 3 inches (76 mm).
- (2) The volumes of spaces in different stories shall be considered as communicating spaces where such spaces are connected by one or more openings in doors or floors having a total free area of not less than 2 square inches per 1000 Btu/h (0.004 m²/kW) of total input rating of appliances. [NFPA 54:9.3.2.3]

506.4 Outdoor Combustion Air. Outdoor combustion air shall be provided through opening(s) to the outdoors in accordance with methods in Section 506.4.1 or Section 506.4.2. The dimension of air openings shall be not less than 3 inches (76 mm). [NFPA 54:9.3.3]




FIGURE 506.3
COMBUSTION AIR FROM ADJACENT INDOOR SPACES
THROUGH INDOOR COMBUSTION AIR OPENINGS
[NFPA 54: FIGURE A.9.3.2.3(1)]

506.4.1 Two Permanent Openings Method. Two permanent openings, one commencing within 12 inches (305 mm) of the top of the enclosure and one commencing within 12 inches (305 mm) of the bottom of the enclosure shall be provided. The openings shall communicate directly, or by ducts, with the outdoors or spaces that freely communicate with the outdoors as follows:

- (1) Where directly communicating with the outdoors or where communicating to the outdoors through vertical ducts, each opening shall have a free area of not less than 1 square inch per 4000 Btu/h (0.0005 m²/kW) of total input rating of appliances in the enclosure. [See Figure 506.4(1) and Figure 506.4(2)]
- (2) Where communicating with the outdoors through horizontal ducts, each opening shall have a free area of not less than 1 square inch per 2000 Btu/h (0.001 m²/kW) of total input rating of appliances in the enclosure. [See Figure 506.4(3)] [NFPA 54:9.3.3.1]

506.4.2 One Permanent Opening Method. One permanent opening, commencing within 12 inches (305 mm) of the top of the enclosure, shall be provided. The appliance shall have clearances of not less than 1 inch (25.4 mm) from the sides and back and 6 inches (152 mm) from the front of the appliance. The opening shall directly communicate with the outdoors or shall communicate through a vertical or horizontal duct to the outdoors or spaces that freely communicate with the outdoors (see Figure 506.4.2) and shall have a free area not less than the following:

- (1) One square inch per 3000 Btu/h (0.0007 m²/kW) of the total input rating of appliances located in the enclosure.
- (2) Not less than the sum of the areas of vent connectors in the space. [NFPA 54:9.3.3.2]

WATER HEATERS




FIGURE 506.4(1)
COMBUSTION AIR FROM OUTDOORS
INLET AIR FROM VENTILATED CRAWL SPACE AND
OUTLET AIR TO VENTILATED ATTIC
[NFPA 54: FIGURE A.9.3.3.1(1)(a)]




FIGURE 506.4(3)
COMBUSTION AIR FROM
OUTDOORS THROUGH HORIZONTAL DUCTS
[NFPA 54: FIGURE A.9.3.3.1(2)]




FIGURE 506.4(2)
COMBUSTION AIR FROM OUTDOORS
THROUGH VENTILATED ATTIC
[NFPA 54: FIGURE A.9.3.3.1(1)(b)]




FIGURE 506.4.2
COMBUSTION AIR FROM OUTDOORS THROUGH
SINGLE COMBUSTION AIR OPENING
[NFPA 54: FIGURE A.9.3.3.2]

For SI units: 1 foot = 304.8 mm

506.5 Combination Indoor and Outdoor Combustion

Air. The use of a combination of indoor and outdoor combustion air shall be in accordance with Section 506.5.1 through Section 506.5.3 (see calculation example in Appendix J). [NFPA 54:9.3.4]

506.5.1 Indoor Openings. Where used, openings connecting the interior spaces shall be in accordance with Section 506.3. [NFPA 54:9.3.4(1)]

506.5.2 Outdoor Openings. Outdoor openings shall be located in accordance with Section 506.4. [NFPA 54:9.3.4(2)]

506.5.3 Outdoor Opening(s) Size. The outdoor opening(s) size shall be calculated in accordance with the following:

- (1) The ratio of interior spaces shall be the volume of the communicating spaces divided by the required volume.
- (2) The outdoor size reduction factor shall be one minus the ratio of interior spaces.
- (3) The size of outdoor openings shall be not less than the full size of outdoor openings calculated in accordance with Section 506.4, multiplied by the reduction factor. The dimension of air openings shall be not less than 3 inches (76 mm). [NFPA 54:9.3.4(3)]

506.6 Engineered Installations. Engineered combustion air installations shall provide a supply of combustion, ventilation, and dilution air that is approved by the Authority Having Jurisdiction. [NFPA 54:9.3.5]

506.7 Mechanical Combustion Air Supply. Where combustion air is provided by a mechanical air supply system, the combustion air shall be supplied from outdoors at the minimum rate of 0.35 cubic feet per minute per 1000 Btu/h [0.034 (m³/min)/kW] for appliances located within the space. [NFPA 54:9.3.6]

506.7.1 Exhaust Fans. Where exhaust fans are installed, additional air shall be provided to replace the exhausted air. [NFPA 54:9.3.6.1]

506.7.2 Interlock. Each of the appliances served shall be interlocked to the mechanical air supply system to prevent main burner operation where the mechanical air supply system is not in operation. [NFPA 54:9.3.6.2]

506.7.3 Specified Combustion Air. Where combustion air is provided by the building's mechanical ventilation system, the system shall provide the specified combustion air rate in addition to the required ventilation air. [NFPA 54:9.3.6.3]

506.8 Louvers, Grilles, and Screens. The required size of openings for combustion, ventilation, and dilution air shall be based on the net free area of each opening. Where the free area through a design of louver, grille, or screen is known, it shall be used in calculating the size opening required to provide the free area specified. Where the louver and grille design and free area are not known, it shall be assumed that wood louvers have 25 percent free area and metal louvers and grilles have 75 percent free area. Nonmotorized louvers and grilles shall be fixed in the open position. [NFPA 54:9.3.7.1]

506.8.1 Minimum Screen Mesh Size. Screens shall be not less than ¼ of an inch (6.4 mm) mesh. [NFPA 54:9.3.7.2]

506.8.2 Motorized Louvers. Motorized louvers shall be interlocked with the appliance so they are proven in the full open position prior to main burner ignition and during main burner operation. Means shall be provided to prevent the main burner from igniting where the louver fail to open during burner start-up and to shut down the main burner where the louvers close during burner operation. [NFPA 54:9.3.7.3]

506.9 Combustion Air Ducts. Combustion air ducts shall comply with the following [NFPA 54:9.3.8]:

- (1) Ducts shall be constructed of galvanized steel or a material having equivalent corrosion resistance, strength, and rigidity.
Exception: Within dwelling units, unobstructed stud and joist spaces shall not be prohibited from conveying combustion air, provided that not more than one fireblock is removed. [NFPA 54:9.3.8.1]
- (2) Ducts shall terminate in an unobstructed space, allowing free movement of combustion air to the appliances. [NFPA 54:9.3.8.2]
- (3) Ducts shall serve a single space. [NFPA 54:9.3.8.3]
- (4) Ducts shall not service both upper and lower combustion air openings where both such openings are used. The separation between ducts serving upper and lower combustion air openings shall be maintained to the source of combustion air. [NFPA 54:9.3.8.4]
- (5) Ducts shall not be screened where terminating in an attic space. [NFPA 54:9.3.8.5]
- (6) Combustion air intake openings located on the exterior of the building shall have the lowest side of the combustion air intake openings located not less than 12 inches (305 mm) vertically from the adjoining finished ground level. [NFPA 54:9.3.8.8]
- (7) Horizontal upper combustion air ducts shall not slope downward toward the source of combustion air. [NFPA 54:9.3.8.6]
- (8) The remaining space surrounding a chimney liner, gas vent, special gas vent, or plastic piping installed within a masonry, metal, or factory-built chimney shall not be used to supply combustion air.

Exception: Direct-vent appliances designed for installation in a solid-fuel-burning fireplace where installed in accordance with the manufacturer's installation instructions. [NFPA 54:9.3.8.7]

507.0 Appliance and Equipment Installation Requirements.

507.1 Dielectric Insulator. The Authority Having Jurisdiction shall have the authority to require the use of an approved dielectric insulator on the water piping connections of water heaters and related water heating appliances.

507.2 Seismic Provisions. In seismic design categories C, D, E, and F, water heaters shall be anchored or strapped to resist horizontal displacement due to earthquake motion. Strapping shall be at points within the upper one-third and lower one-third of its vertical dimensions. At the lower point, a distance of not less than 4 inches (102 mm) shall be maintained from the controls with the strapping.

» **507.3 Support of Appliances.** Appliances and equipment shall be furnished either with load-distributing bases or with an approved number of supports to prevent damage to either the building structure or the appliance and the equipment. [NFPA 54:9.1.8.1]

» **507.3.1 Structural Capacity.** At the locations selected for installation of appliances and equipment, the dynamic and static load-carrying capacities of the building structure shall be checked to determine whether they are capable to carry the additional loads. Appliances and equipment shall be supported and shall be connected to the piping so as not to exert undue stress on the connections. [NFPA 54:9.1.8.2]

» **507.4 Ground Support.** A water heater supported from the ground shall rest on level concrete or other approved base extending not less than 3 inches (76 mm) above the adjoining ground level.

» **507.5 Drainage Pan.** Where a water heater is located in an attic, in or on an attic-ceiling assembly, floor-ceiling assembly, or floor-subfloor assembly where damage results from a leaking water heater, a watertight pan of corrosion-resistant materials shall be installed beneath the water heater with not less than $\frac{3}{4}$ of an inch (20 mm) diameter drain to an approved location. Such pan shall be not less than $1\frac{1}{2}$ inches (38 mm) in depth.

→ **507.6 Added or Converted Equipment or Appliances.**

Where additional or replacement equipment or appliances are installed or an appliance is converted to gas from another fuel, the location in which the equipment or appliance is to be operated shall be checked to verify the following:

- (1) Air for combustion and ventilation is provided where required, in accordance with the provisions of Section 506.0. Where existing facilities are not adequate, they shall be upgraded to be in accordance with Section 506.0 specifications. [NFPA 54:9.1.2(1)]
- (2) The installation components and appliances shall be installed with clearances to combustible material so their operation will not create a hazard to persons or property. Minimum clearances between combustible walls and the back and sides of various conventional types of appliances and their vent connectors are specified in Table 509.7.3(1) and Table 509.7.3(2). [NFPA 54:9.2.2] It shall be determined that the installation and operation of the additional or replacement appliances do not render the remaining appliances unsafe for continued operation.
- (3) The venting system is constructed and sized in accordance with the provisions of Section 509.0. Where the existing venting system is not adequate, it shall be upgraded in accordance with Section 509.0. [NFPA 54:9.1.2(3)]

507.7 Types of Gases. The appliance shall be connected to the fuel gas for which it was designed. No attempt shall be

made to convert the appliance from the gas specified on the rating plate for use with a different gas without consulting the installation instructions, the serving gas supplier, or the appliance manufacturer for complete instructions. [NFPA 54:9.1.3]

507.8 Safety Shutoff Devices for Unlisted LP-Gas Appliance Used Indoors. Unlisted appliances for use with undiluted liquefied petroleum gases and installed indoors, except attended laboratory equipment, shall be equipped with safety shutoff devices of the complete shutoff type. [NFPA 54:9.1.4]

507.9 Use of Air or Oxygen Under Pressure. Where air or oxygen under pressure is used in connection with the gas supply, effective means such as a backpressure regulator and relief valve shall be provided to prevent air or oxygen from passing back into the gas piping. Where oxygen is used, installation shall be in accordance with NFPA 51. [NFPA 54:9.1.5]

507.10 Protection of Gas Appliances from Fumes or Gases other than Products of Combustion. Non-direct-vent appliances installed in beauty shops, barber shops, or other facilities where chemicals that generate corrosive or flammable products such as aerosol sprays are routinely used shall be located in a mechanical equipment room separate or partitioned off from other areas with provisions for combustion and dilution air from outdoors. Direct-vent appliances in such facilities shall be installed in accordance with the appliance manufacturer's installation instructions. [NFPA 54:9.1.6.2]

507.11 Process Air. In addition to air needed for combustion in commercial or industrial processes, process air shall be provided as required for cooling of appliances, equipment, or material; for controlling dew point, heating, drying, oxidation, dilution, safety exhaust, odor control, air for compressors; and for comfort and proper working conditions for personnel. [NFPA 54:9.1.7]

507.12 Flammable Vapors. Appliances shall not be installed in areas where the open use, handling, or dispensing of flammable liquids occurs, unless the design, operation, or installation reduces the potential of ignition of the flammable vapors. Appliances installed in accordance with Section 507.13, Section 507.14, or Section 507.15 shall be considered to be in accordance with the intent of this provision. [NFPA 54:9.1.9]

507.13 Installation in Garages. Appliances in garages and in adjacent spaces that open to the garage and are not part of the living space of a dwelling unit shall be installed so that burners and burner-ignition devices are located not less than 18 inches (457 mm) above the floor unless listed as flammable vapor ignition resistant. [NFPA 54:9.1.10.1]

507.13.1 Physical Damage. Appliances installed in garages, warehouses, or other areas subject to mechanical damage shall be guarded against such damage by being installed behind protective barriers or by being elevated or located out of the normal path of vehicles.

507.13.2 Access from the Outside. Where appliances are installed within a garage and are enclosed in a separate enclosed space having access only from outside of the garage, such appliances shall be permitted to be installed at floor level, provided the required combustion

air is taken from the exterior of the garage. [NFPA 54:9.1.10.3]

507.14 Installation in Commercial Garages. Appliances installed in commercial garages shall comply with Section 507.14.1 and Section 507.14.2.

507.14.1 Parking Structures. Appliances installed in enclosed, basement, and underground parking structures shall be installed in accordance with NFPA 88A. [NFPA 54:9.1.11.1]

507.14.2 Repair Garages. Appliances installed in repair garages shall be installed in a detached building or room, separated from repair areas by walls or partitions, floors, or floor-ceiling assemblies that are constructed so as to prohibit the transmission of vapors and having a fire-resistance rating of not less than 1 hour, and that have no openings in the wall separating the repair area within 8 feet (2438 mm) of the floor. Wall penetrations shall be firestopped. Air for combustion purposes shall be obtained from outside the building. The heating room shall not be used for the storage of combustible materials.

Exceptions:

- (1) Overhead heaters where installed not less than 8 feet (2438 mm) above the floor shall be permitted.
- (2) Heating appliances for vehicle repair areas where there is no dispensing or transferring of Class I or Class II flammable or combustible liquids or liquefied petroleum gas shall be installed in accordance with NFPA 30A. [NFPA 54:9.1.11.2]

507.15 Installation in Aircraft Hangars. Heaters in aircraft hangars shall be installed in accordance with NFPA 409. [NFPA 54:9.1.12]

507.16 Venting of Flue Gases. Appliances shall be vented in accordance with the provisions of this chapter. [NFPA 54:9.1.14]

507.17 Extra Device or Attachment. No device or attachment shall be installed on an appliance that is capable of impairing the combustion of gas. [NFPA 54:9.1.15]

507.18 Adequate Capacity of Piping. Where additional appliances are being connected to a gas piping system, the existing piping shall be checked to determine where it has adequate capacity. Where inadequate, the existing system shall be enlarged as necessary, or separate gas piping of adequate capacity shall be run from the point of delivery to the appliance. [NFPA 54:9.1.16]

507.19 Avoiding Strain on Gas Piping. Appliances shall be supported and connected to the piping so as not to exert undue strain on the connections. [NFPA 54:9.1.17]

507.20 Gas Appliance Pressure Regulators. Where the gas supply pressure is higher than that at which the appliance is designed to operate or varies beyond the design pressure limits of the appliance, a gas appliance pressure regulator shall be installed. [NFPA 54:9.1.18]

507.21 Venting of Gas Appliance Pressure Regulators. Venting of gas appliance pressure regulators shall be in accordance with the following requirements:

- (1) Appliance pressure regulators requiring access to the atmosphere for successful operation shall be equipped with vent piping leading outdoors or, where the regulator vent is an integral part of the appliance, into the combustion chamber adjacent to a continuous pilot, unless constructed or equipped with a vent limiting means to limit the escape of gas from the vent opening in the event of diaphragm failure.
 - (2) Vent limiting means shall be employed on listed gas appliance pressure regulators.
 - (3) In the case of vents leading outdoors, means shall be employed to prevent water from entering this piping and also to prevent blockage of vents by insects and foreign matter.
 - (4) Under no circumstances shall a regulator be vented to the appliance flue or exhaust system.
 - (5) In the case of vents entering the combustion chamber, the vent shall be located so the escaping gas will be readily ignited by the pilot and the heat liberated thereby will not adversely affect the normal operation of the safety shutoff system. The terminus of the vent shall be securely held in a fixed position relative to the pilot. For manufactured gas, the need for a flame arrester in the vent piping shall be determined.
 - (6) Vent lines from an appliance pressure regulator and bleed lines from a diaphragm-type valve shall not be connected to a common manifold terminating in a combustion chamber. Vent lines shall not terminate in positive-pressure-type combustion chambers. [NFPA 54:9.1.19]
- 507.22 Bleed Lines for Diaphragm-Type Valves.** Bleed lines shall comply with the following requirements:
- (1) Diaphragm-type valves shall be equipped to convey bleed gas to the outdoors or into the combustion chamber adjacent to a continuous pilot.
 - (2) In the case of bleed lines leading outdoors, means shall be employed to prevent water from entering this piping and also to prevent blockage of vents by insects and foreign matter.
 - (3) Bleed lines shall not terminate in the appliance flue or exhaust system.
 - (4) In the case of bleed lines entering the combustion chamber, the bleed line shall be located so the bleed gas will be readily ignited by the pilot and the heat liberated thereby will not adversely affect the normal operation of the safety shutoff system. The terminus of the bleed line shall be securely held in a fixed position relative to the pilot. For manufactured gas, the need for a flame arrester in the bleed line piping shall be determined.
 - (5) Bleed lines from a diaphragm-type valve and vent lines from an appliance pressure regulator shall not be connected to a common manifold terminating in a combustion chamber. Bleed lines shall not terminate in positive-pressure-type combustion chambers. [NFPA 54:9.1.20]

507.23 Combination of Appliances and Equipment.

A combination of appliances, equipment, attachments, or devices used together in a manner shall be in accordance with the standards that apply to the individual appliance and equipment. [NFPA 54:9.1.21]

507.24 Installation Instructions. The installing agency shall comply with the appliance and equipment manufacturer's installation instructions in completing an installation. The installing agency shall leave the manufacturer's installation, operating, and maintenance instructions in a location on the premises where they will be readily available for reference and guidance for the Authority Having Jurisdiction, service personnel, and the owner or operator. [NFPA 54:9.1.22]

507.25 Protection of Outdoor Appliances. Appliances not listed for outdoor installation but installed outdoors shall be provided with protection to the degree that the environment requires. Appliances listed for outdoor installation shall be permitted to be installed without protection in accordance with the provisions of its listing and the manufacturer's installation instructions.

507.26 Accessibility for Service. Appliances shall be located with respect to building construction and other equipment so as to permit access to the appliance. Sufficient clearance shall be maintained to permit cleaning of heating surfaces; the replacement of filters, blowers, motors, burners, controls, and vent connections; the lubrication of moving parts where necessary; the adjustment and cleaning of burners and pilots; and the proper functioning of explosion vents, where provided. For attic installation, the passageway and servicing area adjacent to the appliance shall be floored. [NFPA 54:9.2.1]

508.0 Equipment and Appliances on Roofs.

508.1 General. Equipment and appliances on roofs shall be designed or enclosed so as to withstand climatic conditions in the area in which they are installed. Where enclosures are provided, each enclosure shall permit easy entry and movement, shall be of reasonable height, and shall have not less than a 30 inch (762 mm) clearance between the entire service access panel(s) of the equipment and appliance and the wall of the enclosure. [NFPA 54:9.4.1.1]

508.1.1 Load Capacity. Roofs on which equipment and appliances are to be installed shall be capable of supporting the additional load or shall be reinforced to support the additional load. [NFPA 54:9.4.1.2]

508.1.2 Fasteners. Access locks, screws, and bolts shall be of corrosion-resistant material. [NFPA 54:9.4.1.3]

508.2 Installation of Equipment and Appliances on Roofs. Equipment and appliances shall be installed in accordance with the manufacturer's installation instructions. [NFPA 54:9.4.2.1]

508.2.1 Clearance. Equipment and appliances shall be installed on a well-drained surface of the roof. Not less than 6 feet (1829 mm) of clearance shall be between a part of the equipment and appliance and the edge of a roof or similar hazard, or rigidly fixed rails, guards, parapets, or other building structures not less than 42 inches (1067 mm) in height shall be provided on the exposed side. [NFPA 54:9.4.2.2]

508.2.2 Electrical Power. Equipment and appliances requiring an external source of electrical power for its operation shall be provided with the following:

- (1) A readily accessible electrical disconnecting means within sight of the equipment and appliance that will completely de-energize the equipment and appliance.
- (2) A 120-VAC grounding-type receptacle outlet on the roof adjacent to the equipment and appliance. The receptacle outlet shall be on the supply side of the disconnect switch. [NFPA 54:9.4.2.3]

508.2.3 Platform or Walkway. Where water stands on the roof at the equipment and appliance or in the passageways to the equipment and appliance, or where the roof is of a design having a water seal, an approved platform, walkway, or both shall be provided above the waterline. Such platforms or walkways shall be located adjacent to the equipment and appliance and control panels so that the equipment and appliance is capable of being safely serviced where water stands on the roof. [NFPA 54:9.4.2.4]

508.3 Access to Equipment and Appliances on Roofs. Equipment and appliances located on roofs or other elevated locations shall be accessible. [NFPA 54:9.4.3.1]

508.3.1 Access. Buildings exceeding 15 feet (4572 mm) in height shall have an inside means of access to the roof, unless other means acceptable to the Authority Having Jurisdiction are used. [NFPA 54:9.4.3.2]

508.3.2 Access Type. The inside means of access shall be a permanent, or fold-away inside stairway or ladder, terminating in an enclosure, scuttle, or trap door. Such scuttles or trap doors shall be not less than 22 inches by 24 inches (559 mm by 610 mm) in size, shall open easily and safely under all conditions, especially snow; and shall be constructed so as to permit access from the roof side unless deliberately locked on the inside.

Not less than 6 feet (1829 mm) of clearance shall be between the access opening and the edge of the roof or similar hazard, or rigidly fixed rails or guards not less than 42 inches (1067 mm) in height shall be provided on the exposed side. Where parapets or other building structures are utilized in lieu of guards or rails, they shall be not less than 42 inches (1067 mm) in height. [NFPA 54:9.4.3.3]

508.3.3 Permanent Lighting. Permanent lighting shall be provided at the roof access. The switch for such lighting shall be located inside the building near the access means leading to the roof. [NFPA 54:9.4.3.4]

508.4 Appliances in Attics and Under-Floor Spaces. An attic or under-floor space in which an appliance is installed shall be accessible through an opening and passageway not less than as large as the largest component of the appliance, and not less than 22 inches by 30 inches (559 mm by 762 mm).

508.4.1 Length of Passageway. Where the height of the passageway is less than 6 feet (1829 mm), the distance from the passageway access to the appliance shall not exceed 20 feet (6096 mm) measured along the centerline of the passageway. [NFPA 54:9.5.1.1]

508.4.2 Width of Passageway. The passageway shall be unobstructed and shall have solid flooring not less than 24 inches (610 mm) wide from the entrance opening to the appliance. [NFPA 54:9.5.1.2]

508.4.3 Work Platform. A level working platform not less than 30 inches by 30 inches (762 mm by 762 mm) shall be provided in front of the service side of the appliance. [NFPA 54:9.5.2]

508.4.4 Lighting and Convenience Outlet. A permanent 120-volt receptacle outlet and a lighting fixture shall be installed near the appliance. The switch controlling the lighting fixture shall be located at the entrance to the passageway. [NFPA 54:9.5.3]

509.0 Venting of Appliances.

509.1 Listing. Type B and Type B-W gas vents shall comply with UL 441 and Type L gas vents shall comply with UL 641.

509.1.1 Installation. Listed vents shall be installed in accordance with this chapter and the manufacturer's installation instructions. [NFPA 54:12.2.1]

509.1.2 Prohibited Discharge. Appliance vents shall not discharge into a space enclosed by screens having openings less than $\frac{1}{4}$ of an inch (6.4 mm) mesh.

509.2 Connection to Venting Systems. Except as permitted in Section 509.2.1 through Section 509.2.5, appliances shall be connected to venting systems. [NFPA 54:12.3.1]

509.2.1 Appliances Not Required to be Vented. The following appliances shall not be required to be vented [NFPA 54:12.3.2]:

- (1) A single listed booster-type (automatic instantaneous) water heater, where designed and used solely for the sanitizing rinse requirements of a dishwashing machine, provided that the appliance is installed with the draft hood in place and unaltered where a draft hood is required, in a commercial kitchen having a mechanical exhaust system; where installed in this manner, the draft hood outlet shall be not less than 36 inches (914 mm) vertically and 6 inches (152 mm) horizontally from a surface other than the appliance. [NFPA 54:12.3.2(5)]
- (2) Other appliances listed for unvented use and not provided with flue collars. [NFPA 54:12.3.2(10)]

Where appliances in Section 509.2.1(1) and Section 509.2.1(2) are installed so the aggregate input rating exceeds 20 British thermal units per hour per cubic foot $[(\text{Btu}/\text{h})/\text{ft}^3]$ (0.21 kW/m³) of room or space in which it is installed, one or more shall be provided with venting systems or other approved means for conveying the vent gases to the outdoors so the aggregate input rating of the remaining unvented appliance does not exceed 20 $[(\text{Btu}/\text{h})/\text{ft}^3]$ (0.21 kW/m³). Where the calculation includes the volume of an adjacent room or space, the room or space in which the appliance is installed shall be directly connected to the adjacent room or space by a doorway, archway, or other opening of comparable size that cannot be closed. [NFPA 54:12.3.2.1, 12.3.2.2]

509.2.2 Ventilating Hoods. Ventilating hoods and exhaust systems shall be permitted to be used to vent appliances installed in commercial applications and to

vent industrial appliances, particularly where the process itself requires fume disposal. [NFPA 54:12.3.3]

509.2.3 Well-Ventilated Spaces. The operation of industrial appliances such that its flue gases are discharged directly into a large and well-ventilated space shall be permitted. [NFPA 54:12.3.4]

509.2.4 Direct-Vent Appliances. Listed direct-vent appliances shall be installed in accordance with the manufacturer's installation instructions and Section 509.8.2. [NFPA 54:12.3.5]

509.2.5 Appliances with Integral Vents. Appliances incorporating integral venting means shall be installed in accordance with the manufacturer's installation instructions, Section 509.8, and Section 509.8.1. [NFPA 54:12.3.6]

509.3 Design and Construction. Venting systems shall be designed and constructed to convey flue, vent, or both gases to the outdoors. [NFPA 54:12.1]

509.3.1 Appliance Draft Requirements. A venting system shall satisfy the draft requirements of the appliance in accordance with the manufacturer's instructions. [NFPA 54:12.4.1]

509.3.2 Appliance Venting Requirements. Appliances required to be vented shall be connected to a venting system designed and installed in accordance with the provisions of Section 509.4 through Section 509.14 of this code. [NFPA 54:12.4.2]

509.3.3 Mechanical Draft Systems. Mechanical draft systems shall be listed and installed in accordance with both the appliance and the mechanical draft system manufacturer's installation instructions. [NFPA 54:12.4.3.1]

509.3.3.1 Venting. Appliances requiring venting shall be permitted to be vented by means of mechanical draft systems of either forced or induced draft design. [NFPA 54:12.4.3.2]

Exception: Incinerators.

509.3.3.2 Leakage. Forced draft systems and portions of induced draft systems under positive pressure during operation shall be designed and installed so as to prevent leakage of flue or vent gases into a building. [NFPA 54:12.4.3.3]

509.3.3.3 Vent Connectors. Vent connectors serving appliances vented by natural draft shall not be connected into mechanical draft systems operating under positive pressure. [NFPA 54:12.4.3.4]

509.3.3.4 Operation. Where a mechanical draft system is employed, provision shall be made to prevent the flow of gas to the main burners where the draft system is not performing so as to satisfy the operating requirements of the appliance for safe performance. [NFPA 54:12.4.3.5]

509.3.3.5 Exit Terminals. The exit terminals of mechanical draft systems shall be not less than 7 feet (2134 mm) above finished ground level where located adjacent to public walkways and shall be located as specified in Section 509.8 and Section 509.8.1 of this code. [NFPA 54:12.4.3.6]

509.3.4 Ventilating Hoods and Exhaust Systems. Ventilating hoods and exhaust systems shall be permitted to be used to vent appliances installed in commercial applications. [NFPA 54:12.4.4.1]

509.3.4.1 Automatically Operated Appliances. Where automatically operated appliances, other than commercial cooking appliances, are vented through a ventilating hood or exhaust system equipped with a damper or with a power means of exhaust, provisions shall be made to allow the flow of gas to the main burners where the damper is open to a position to properly vent the appliance and where the power means of exhaust is in operation. [NFPA 54:12.4.4.2]

509.3.5 Circulating Air Ducts and Furnace Plenums. Venting systems shall not extend into or pass through a fabricated air duct or furnace plenum. [NFPA 54:12.4.5.1]

509.4 Type of Venting System to be Used. The type of venting system to be used shall be in accordance with Table 509.4. [NFPA 54:12.5.1]

509.4.1 Plastic Piping. Plastic piping used for venting appliances listed for use with such venting materials shall be approved. [NFPA 54:12.5.2]

509.4.2 Plastic Vent Joints. Plastic pipe and fittings used to vent appliances shall be installed in accordance with the appliance manufacturer's installation instructions. Where primer is required, it shall be of a contrasting color. [NFPA 54:12.5.3]

509.4.3 Special Gas Vents. Special gas vents shall be listed and installed in accordance with the special gas vent manufacturer's installation instructions. [NFPA 54:12.5.4]

509.5 Masonry, Metal, and Factory-Built Chimneys. Chimneys shall be installed in accordance with Section 509.5.1 through Section 509.5.3.

509.5.1 Factory-Built Chimneys. Factory-built chimneys shall be installed in accordance with the manufacturer's installation instructions. Factory-built chimneys used to vent appliances that operate at positive vent pressure shall be listed for such application. [NFPA 54:12.6.1.1]

509.5.1.1 Decorative Shrouds. Decorative shrouds addressed in Section 509.5.4.3 shall be listed or labeled in accordance with UL 103 for factory-built residential chimneys.

509.5.1.2 Listing Requirements. Factory-built chimneys shall comply with the requirements of UL 103 or UL 959. Factory-built chimneys for use with wood-burning appliances shall comply with the Type HT requirements of UL 103. [NFPA 211:6.1.3.1, 6.1.3.2]

509.5.2 Metal Chimneys. Metal chimneys shall be built and installed in accordance with NFPA 211. [NFPA 54:12.6.1.2]

509.5.3 Masonry Chimneys. Masonry chimneys shall be built and installed in accordance with NFPA 211 and lined with approved clay flue lining, a listed chimney lining system, or other approved material that resists corrosion, erosion, softening, or cracking from vent gases at temperatures not exceeding 1800°F (982°C).

Exception: Masonry chimney flues lined with a chimney lining system specifically listed for use with listed appliances with draft hoods, Category I appliances, and other appliances listed for use with Type B vents shall be permitted. The liner shall be installed in accordance with the liner manufacturer's installation instructions. A permanent identifying label shall be attached at the point where the connection is to be made to the liner. The label shall read: "This chimney liner is for appliances that burn gas only. Do not connect to solid- or liquid-fuel-burning appliances or incinerators." [NFPA 54:12.6.1.3]

509.5.4 Termination. A chimney for a residential-type or low-heat appliance shall extend not less than 3 feet (914 mm) above the highest point where it passes through the roof of a building and not less than 2 feet (610 mm) higher than a portion of a building within a horizontal distance of 10 feet (3048 mm). (See Figure 509.5.4) [NFPA 54:12.6.2.1]

509.5.4.1 Medium-Heat Gas Appliances. A chimney for a medium-heat appliance shall extend not less than 10 feet (3048 mm) above a portion of a building within 25 feet (7620 mm). [NFPA 54:12.6.2.2]

509.5.4.2 Chimney Height. A chimney shall extend not less than 5 feet (1524 mm) above the highest connected appliance draft hood outlet or flue collar. [NFPA 54:12.6.2.3]

509.5.4.3 Decorative Shrouds. Decorative shrouds shall not be installed at the termination of factory-built chimneys except where such shrouds are listed and labeled for use with the specific factory-built chimney system and are installed in accordance with the manufacturer's installation instructions. [NFPA 54:12.6.2.4]

509.5.5 Size of Chimneys. The effective area of a chimney venting system serving listed appliances with draft hoods, Category I appliances, and other appliances listed for use with Type B vents shall be in accordance with one of the following methods [NFPA 54:12.6.3.1]:

- (1) Section 510.0. [NFPA 54:12.6.3.1(1)]
- (2) For sizing an individual chimney venting system for a single appliance with a draft hood, the effective areas of the vent connector and chimney flue shall be not less than the area of the appliance flue collar or draft hood outlet or exceeding seven times the draft hood outlet area. [NFPA 54:12.6.3.1(2)]
- (3) For sizing a chimney venting system connected to two appliances with draft hoods, the effective area of the chimney flue shall be not less than the area of the larger draft hood outlet plus 50 percent of the


area of the smaller draft hood outlet, or exceeding seven times the smallest draft hood outlet area. [NFPA 54:12.6.3.1(3)]

- (4) Other approved engineering methods. [NFPA 54:12.6.3.1(5)]
- (5) Chimney venting systems using mechanical draft shall be sized in accordance with approved engineering methods. [NFPA 54:12.6.3.1(4)]


509.5.6 Inspection of Chimneys. Before replacing an existing appliance or connecting a vent connector to a chimney, the chimney passageway shall be examined to ascertain that it is clear and free of obstructions and shall be cleaned where previously used for venting solid- or liquid-fuel-burning appliances or fireplaces. [NFPA 54:12.6.4.1]

TABLE 509.4
TYPE OF VENTING SYSTEM TO BE USED
[NFPA 54: TABLE 12.5.1]

| APPLIANCES | TYPE OF VENTING SYSTEM |
|--|--|
| Listed Category I appliances | Type B gas vent (Section 509.6) |
| Listed appliances equipped with draft hood | Chimney (Section 509.5) |
| Appliances listed for Type B gas vent | Single-wall metal pipe (Section 509.7) Listed chimney lining system for gas venting (Section 509.5.3) Special gas vent listed for this appliance (Section 509.4.3) |
| Listed vented wall furnaces | Type B-W gas vent (Section 509.6, Section 509.6.2.2) |
| Category II appliances. Category III appliances Category IV appliances | As specified or furnished by manufacturers of listed appliance (Section 509.4.1, Section 509.4.3) |
| Incinerators, outdoors | Single-wall metal pipe (Section 509.7, Section 509.7.2) |
| Incinerators, indoors | Chimney (Section 509.5) |
| Appliances that are capable of being converted to use of solid fuel | |
| Unlisted combination gas- and oil-burning appliances | |
| Combination gas- and solid-fuel-burning appliances | |
| Appliances listed for use with chimneys only | |
| Unlisted appliances | |
| Listed combination gas- and oil-burning appliances | Type L vent (Section 509.6) or chimney (Section 509.5) |
| Decorative appliance in vented fireplace | Chimney (UMC Section 911.2) |
| Direct-vent appliances | See Section 509.2.4 |
| Appliances with integral vent | See Section 509.2.5 |



(a) Termination 10 feet or Less from Ridge, Wall, or Parapet



(b) Termination More Than 10 feet from Ridge, Wall, or Parapet

For SI units: 1 foot = 304.8 mm

FIGURE 509.5.4
TYPICAL TERMINATION LOCATIONS FOR CHIMNEYS
AND SINGLE-WALL METAL PIPES SERVING
RESIDENTIAL-TYPE AND LOW-HEAT APPLIANCE
[NFPA 54: FIGURE A.12.6.2.1]

509.5.6.1 Standard. Chimneys shall be lined in accordance with NFPA 211.

Exception: Existing chimneys shall be permitted to have their use continued where an appliance is replaced by an appliance of similar type, input rating, and efficiency, where the chimney is in accordance with Section 509.5.6, and the sizing of the chimney is in accordance with Section 509.5.5. [NFPA 54:12.6.4.2]

509.5.6.2 Cleanouts. Cleanouts shall be examined to determine that they will remain tightly closed where not in use. [NFPA 54:12.6.4.3]

509.5.6.3 Existing Chimney. Where inspection reveals that an existing chimney is not safe for the intended application, it shall be repaired, rebuilt, lined, relined, or replaced with a vent or chimney in accordance with NFPA 211, and shall be approved for the appliances to be attached. [NFPA 54:12.6.4.4]

509.5.7 Chimney Serving Appliances Burning Other Fuels. An appliance shall not be connected to a chimney flue serving a separate appliance designed to burn solid fuel. [NFPA 54:12.6.5.1]

509.5.7.1 Gas and Liquid Fuel-Burning Appliances. Where one chimney serves gas appliances and liquid fuel-burning appliances, the appliances shall be connected through separate openings or shall be connected through a single opening where joined by a fitting located as close as practical to the chimney. Where two or more openings are provided into one chimney flue, they shall be at different levels. Where the gas appliance is automatically controlled, it shall be equipped with a safety shutoff device. [NFPA 54:12.6.5.2]

509.5.7.2 Gas and Solid Fuel-Burning Appliances. A listed combination gas- and solid-fuel-burning appliance connected to a single chimney flue shall be equipped with a manual reset device to shut off gas to the main burner in the event of sustained backdraft or flue gas spillage. The chimney flue shall be sized to properly vent the appliance. [NFPA 54:12.6.5.3]

509.5.7.3 Combination Gas- and Oil-Burning Appliances. A single chimney flue serving a listed combination gas- and oil-burning appliance shall be sized to properly vent the appliance. [NFPA 54:12.6.5.4]

509.5.8 Support of Chimneys. Portions of chimneys shall be supported for the design and weight of the materials employed. Listed factory-built chimneys shall be supported and spaced in accordance with the manufacturer's instructions. [NFPA 54:12.6.6]

509.5.9 Cleanouts. Where a chimney that formerly carried flue products from liquid- or solid-fuel-burning appliances is used with an appliance using fuel gas, an accessible cleanout shall be provided. The cleanout shall have a tight-fitting cover and be installed so its upper edge is not less than 6 inches (152 mm) below the lower edge of the lowest chimney inlet opening. [NFPA 54:12.6.7]

509.5.10 Space Surrounding Lining or Vent. The remaining space surrounding a chimney liner, gas vent, special gas vent, or plastic piping installed within a masonry chimney shall not be used to vent another appliance.

Exception: The insertion of another liner or vent within the chimney as provided in this code and the liner or vent manufacturer's instructions. [NFPA 54:12.6.8.1]

509.5.10.1 Combustion Air. The remaining space surrounding a chimney liner, gas vent, special gas vent, or plastic piping installed within a masonry, metal, or factory-built chimney flue shall not be used to supply combustion air.

Exception: Direct-vent appliances designed for installation in a solid-fuel-burning fireplace where installed in accordance with the manufacturer's installation instructions. [NFPA 54:12.6.8.2]

509.6 Gas Vents. Gas vents shall be installed in accordance with the manufacturer's installation instructions. [NFPA 54:12.7.1(1)]

509.6.1 Fasteners. Screws, rivets and other fasteners shall not penetrate the inner wall of double wall gas vents except at the transition from the appliance draft hood outlet, flue collar, or single wall metal connector to a double wall vent. [NFPA 54:12.7.1(4)]

509.6.2 Termination Requirements. A gas vent shall terminate in accordance with one of the following:

- (1) Gas vents that are 12 inches (305 mm) or less in size and located not less than 8 feet (2438 mm) from a vertical wall or similar obstruction shall terminate above the roof in accordance with Figure 509.6.2 and Table 509.6.2. Gas vents that are over 12 inches (305 mm) in size or are located less than 8 feet (2438 mm) from a vertical wall or similar obstruction, shall terminate not less than 2 feet (610 mm) above the highest point where they pass through the roof and not less than 2 feet (610 mm) above a portion of a building within 10 feet (3048 mm) horizontally.
- (2) Industrial appliances as provided in Section 509.2.3.
- (3) Direct-vent systems as provided in Section 509.2.4.
- (4) Appliances with integral vents as provided in Section 509.2.5.
- (5) Mechanical draft systems as provided in Section 509.3.3.
- (6) Ventilating hoods and exhaust systems as provided in Section 509.3.4. [NFPA 54:12.7.2(1)]

509.6.2.1 Type B and L Vents. A Type B or a Type L gas vent shall terminate not less than 5 feet (1524 mm) in vertical height above the highest connected appliance draft hood or flue collar. [NFPA 54:12.7.2(2)]

509.6.2.2 Type B-W Vents. A Type B-W gas vent shall terminate not less than 12 feet (3658 mm) in vertical height above the bottom of the wall furnace. [NFPA 54:12.7.2(3)]




FIGURE 509.6.2
GAS VENT TERMINATION LOCATIONS FOR
LISTED CAPS 12 INCHES OR LESS IN SIZE NOT
LESS THAN 8 FEET FROM A VERTICAL WALL
[NFPA 54: FIGURE 12.7.2]

TABLE 509.6.2
ROOF PITCH HEIGHT
[NFPA 54: TABLE 12.7.2]

| ROOF PITCH | H (minimum) (feet) |
|---|--------------------|
| Flat to $\frac{1}{12}$ | 1.0 |
| Over $\frac{1}{12}$ to $\frac{3}{12}$ | 1.25 |
| Over $\frac{3}{12}$ to $\frac{5}{12}$ | 1.5 |
| Over $\frac{5}{12}$ to $\frac{7}{12}$ | 2.0 |
| Over $\frac{7}{12}$ to $\frac{9}{12}$ | 2.5 |
| Over $\frac{9}{12}$ to $\frac{11}{12}$ | 3.25 |
| Over $\frac{11}{12}$ to $\frac{13}{12}$ | 4.0 |
| Over $\frac{13}{12}$ to $\frac{15}{12}$ | 5.0 |
| Over $\frac{15}{12}$ to $\frac{17}{12}$ | 6.0 |
| Over $\frac{17}{12}$ to $\frac{19}{12}$ | 7.0 |
| Over $\frac{19}{12}$ to $\frac{21}{12}$ | 7.5 |
| Over $\frac{21}{12}$ to $\frac{23}{12}$ | 8.0 |

For SI Units: 1 inch = 25.4 mm, 1 foot = 304.8 mm

509.6.2.3 Exterior Wall Termination. A gas vent extending through an exterior wall shall not terminate adjacent to the wall or below eaves or parapets, except as provided in Section 509.2.4 and Section 509.3.3. [NFPA 54:12.7.2(4)]

509.6.2.4 Decorative Shrouds. Decorative shrouds shall not be installed at the termination of gas vents except where such shrouds are listed for use with the specific gas venting system and are installed in accordance with manufacturer's installation instructions. [NFPA 54:12.7.2(5)]

509.6.2.5 Termination Cap. A gas vent shall extend through the roof flashing roof jack, or roof thimble and terminate with a listed cap or listed roof assembly. [NFPA 54:12.7.2(6)]

509.6.2.6 Forced Air Inlet. A gas vent shall terminate not less than 3 feet (914 mm) above a forced air inlet located within 10 feet (3048 mm). [NFPA 54:12.7.2(7)]

509.6.2.7 Insulation Shield. Where a vent passes through an insulated assembly, an approved metal shield shall be installed between the vent and insulation. The shield shall extend not less than 2 inches (51 mm) above the insulation and be secured to the structure in accordance with the manufacturer's installation instructions.

509.6.3 Size of Gas Vents. Venting systems shall be sized and constructed in accordance with Section 510.0 or other approved engineering methods and the gas vent and gas appliance manufacturer's instructions. [NFPA 54:12.7.3]

509.6.3.1 Category I Appliances. The sizing of natural draft venting systems serving one or more listed appliances equipped with a draft hood or appliances listed for use with Type B gas vent, installed in a single story of a building, shall be in accordance with one of the following:

- (1) The provisions of Section 510.0.
- (2) Vents serving fan-assisted combustion system appliances, or combinations of fan-assisted combustion systems and draft hood-equipped appliances, shall be sized in accordance with Section 510.0 or other approved engineering methods.
- (3) For sizing an individual gas vent for a single, draft hood-equipped appliance, the effective area of the vent connector and the gas vent shall be not less than the area of the appliance draft hood outlet or exceeding seven times the draft hood outlet area.
- (4) For sizing a gas vent connected to two appliances with draft hoods, the effective area of the vent shall be not less than the area of the larger draft hood outlet plus 50 percent of the area of the smaller draft hood outlet or exceeding seven times the smaller draft hood outlet area.
- (5) Approved engineering practices. [NFPA 54:12.7.3.1]

509.6.3.2 Vent Offsets. Type B or Type L vents shall extend in a vertical direction with offsets not exceeding 45 degrees (0.79 rad), except that a vent system having not more than one 60 degree (1.05 rad) offset shall be permitted. An angle greater than 45 degrees (0.79 rad) from the vertical is considered horizontal. The total horizontal distance of a vent plus the horizontal vent connector serving draft hood-equipped appliances shall be not greater than 75 percent of the vertical height of the vent. [NFPA 54:12.7.3.2]

509.6.3.3 Sizing. Chimney venting systems using mechanical draft shall be sized in accordance with approved engineering methods. [NFPA 54:12.7.3.4]

509.6.4 Gas Vents Serving Appliances on more than One Floor. A common vent shall be permitted in multistory installations to vent Category I appliances located on more than one floor level, provided the vent-

ing system is designed and installed in accordance with approved engineering methods.

For the purpose of this section, crawl spaces, basements, and attics shall be considered as floor levels. [NFPA 54:12.7.4.1]

509.6.4.1 Occupiable Space. Appliances connected to the common vent shall be located in rooms separated from an occupiable space. Each of these rooms shall have provisions for an adequate supply of combustion, ventilation, and dilution air that is not supplied from an occupiable space. (See Figure 509.6.4.1) [NFPA 54:12.7.4.2]




FIGURE 509.6.4.1
PLAN VIEW OF PRACTICAL SEPARATION
METHOD FOR MULTISTORY GAS VENTING
[NFPA 54: FIGURE A.12.7.4.2]

509.6.4.2 Multistory Venting System. The size of the connectors and common segments of multistory venting systems for appliances listed for use with a Type B double-wall gas vent shall be in accordance with Table 510.2(1), provided the following apply:

- (1) The total height (H) for each segment of a multistory venting system is the vertical distance between the level of the highest draft hood outlet or flue collar on that floor and the centerline of the next highest interconnection tee.
- (2) The size of the connector for a segment is determined from the appliance's gas input rate and connector rise, and shall not be smaller than the draft hood outlet or flue collar size.
- (3) The size of the common vertical vent segment, and of the interconnection tee at the base of that segment, shall be based on the total appliance's gas input rate entering that segment and its total height. [NFPA 54:12.7.4.3]

509.6.5 Support of Gas Vents. Gas vents shall be supported and spaced in accordance with the manufacturer's installation instructions. [NFPA 54:12.7.5]

509.6.6 Marking. In those localities where solid and liquid fuels are used extensively, gas vents shall be permanently identified by a label attached to the wall or ceiling at a point where the vent connector enters the gas vent. The label shall read: "This gas vent is for appliances that burn gas. Do not connect to solid- or liquid-fuel-burning appliances or incinerators." The Authority Having Jurisdiction shall determine whether its area constitutes such a locality. [NFPA 54:12.7.6]

509.7 Single-Wall Metal Pipe. Single-wall metal pipe shall be constructed of galvanized sheet steel not less than 0.0304 of an inch (0.7722 mm) thick or of other approved, noncombustible, corrosion-resistant material. [NFPA 54:12.8.1]

509.7.1 Cold Climate. Uninsulated single-wall metal pipe shall not be used outdoors for venting appliances. For venting appliances in regions where the 99 percent winter design temperature is below 32°F (0°C). [NFPA 54:12.8.2]

509.7.2 Termination. The termination of single-wall metal pipe shall comply with the following requirements:

- (1) Single-wall metal pipe shall terminate not less than 5 feet (1524 mm) in vertical height above the highest connected appliance draft hood outlet or flue collar.
- (2) Single-wall metal pipe shall extend not less than 2 feet (610 mm) above the highest point where it passes through the roof of a building and not less than 2 feet (610 mm) exceeding a portion of a building within a horizontal distance of 10 feet (3048 mm). (See Figure 509.5.4)
- (3) An approved cap or roof assembly shall be attached to the terminus of a single-wall metal pipe. [NFPA 54:12.8.3]

509.7.3 Installation with Appliances Permitted by Table 509.4. Single-wall metal pipe shall not be used as a vent in dwellings and residential occupancies. [NFPA 54:12.8.4.1]

509.7.3.1 Limitations. Single-wall metal pipe shall be used for runs directly from the space in which the appliance is located through the roof or exterior wall to the outer air. A pipe passing through a roof shall extend without interruption through the roof flashing, roof jacket, or roof thimble. [NFPA 54:12.8.4.2]

509.7.3.2 Attic or Concealed Space. Single-wall metal pipe shall not originate in an unoccupied attic or concealed space and shall not pass through an attic, inside wall, concealed space, or floor. [NFPA 54:12.8.4.3]

509.7.3.3 Incinerator. Single-wall metal pipe used for venting an incinerator shall be exposed and readily examinable for its full length and shall have required clearances maintained.

509.7.3.4 Clearances. Minimum clearances from single-wall metal pipe to combustible material shall be in accordance with Table 509.7.3(1). Reduced clearances from single-wall metal pipe to combustible material shall be as specified for vent connectors in Table 509.7.3(2). [NFPA 54:12.8.4.4]

509.7.3.5 Combustible Exterior Wall. A single-wall metal pipe shall not pass through a combustible exterior wall unless guarded at the point of passage by a ventilated metal thimble not smaller than the following:

- (1) For listed appliances with draft hoods and appliances listed for use with Type B gas vents, the thimble shall be not less than 4 inches (102 mm) larger in diameter than the metal pipe. Where there is a run of not less than 6 feet (1829 mm) of metal pipe in the opening between the draft hood outlet and the thimble, the thimble shall be not less than 2 inches (51 mm) larger in diameter than the metal pipe.
- (2) For unlisted appliances having draft hoods, the thimble shall be not less than 6 inches (152 mm) larger in diameter than the metal pipe.
- (3) For residential and low-heat appliances, the thimble shall be not less than 12 inches (305 mm) larger in diameter than the metal pipe.

Exception: In lieu of thimble protection, combustible material in the wall shall be removed from the metal pipe to provide the specified clearance from combustible material. Material used to close up such opening shall be noncombustible. [NFPA 54:12.8.4.6]

509.7.3.6 Roof Thimble. Where a single-wall metal pipe passes through a roof constructed of combustible material, a noncombustible, nonventilating thimble shall be used at the point of passage. The thimble shall extend not less than 18 inches (457 mm) above and 6 inches (152 mm) below the roof with the annular space open at the bottom and closed at the top. The thimble shall be sized in accordance with Section 509.7.3.5. [NFPA 54:12.8.4.5]

509.7.4 Size of Single-Wall Metal Pipe. Single-wall metal piping shall comply with the Section 509.7.4.1 through Section 509.7.4.3. [NFPA 54:12.8.5]

509.7.4.1 Sizing of Venting System. A venting system of a single-wall metal pipe shall be sized in accordance with one of the following methods and the appliance manufacturer's instructions:

- (1) For a draft hood-equipped appliance, in accordance with Section 510.0.
- (2) For a venting system for a single appliance with a draft hood, the areas of the connector and the pipe each shall be not less than the area of the appliance flue collar or draft hood outlet, whichever is smaller. The vent area shall not exceed seven times the draft hood outlet area.
- (3) Other approved engineering methods. [NFPA 54:12.8.5(1)]

509.7.4.2 Non-Round Metal Pipe. Where a single-wall metal pipe is used and has a shape other than round, it shall have an effective area equal to the effective area of the round pipe for which it is substituted, and the internal dimension of the pipe shall be not less than 2 inches (51 mm). [NFPA 54:12.8.5(2)]

509.7.4.3 Venting Capacity. The vent cap or a roof assembly shall have a venting capacity not less than that of the pipe to which it is attached. [NFPA 54:12.8.5(3)]

509.7.5 Support of Single-Wall Metal Pipe. Portions of single-wall metal pipe shall be supported for the design and weight of the material employed. [NFPA 54:12.8.6]

509.7.6 Marking. Single-wall metal pipe shall comply with the marking provisions of Section 509.6.6. [NFPA 54:12.8.7]

509.8 Through-the-Wall Vent Termination. (See Figure 509.8) A mechanical draft venting system shall terminate not less than 3 feet (914 mm) above a forced air inlet located within 10 feet (3048 mm).

Exceptions:

- (1) This provision shall not apply to the combustion air intake of a direct-vent appliance.

TABLE 509.7.3(1)
CLEARANCE FOR CONNECTORS
[NFPA 54: TABLE 12.8.4.4]*

| MINIMUM DISTANCE FROM COMBUSTIBLE MATERIAL (Inches) | | | | |
|--|---------------------------------|-----------------------------|------------------------|--------------------------------|
| APPLIANCE | LISTED TYPE B GAS VENT MATERIAL | LISTED TYPE L VENT MATERIAL | SINGLE-WALL METAL PIPE | FACTORY-BUILT CHIMNEY SECTIONS |
| Listed appliances with draft hoods and appliances listed for use with Type B gas vents | As listed | As listed | 6 | As listed |
| Residential boilers and furnaces with listed gas conversion burner and with draft hood | 6 | 6 | 9 | As listed |
| Residential appliances listed for use with Type L vents | Not permitted | As listed | 9 | As listed |
| Unlisted residential appliances with draft hood | Not permitted | 6 | 9 | As listed |
| Residential and low-heat appliances other than those above | Not permitted | 9 | 18 | As listed |
| Medium-heat appliances | Not permitted | Not permitted | 36 | As listed |

For SI units: 1 inch = 25.4 mm

* These clearances shall apply unless the installation instructions of a listed appliance or connector specify different clearances, in which case the listed clearances shall apply.


- (2) This provision shall not apply to the separation of the integral outdoor air inlet and flue gas discharge of listed outdoor appliances. [NFPA 54:12.9.1]

509.8.1 Mechanical Draft Venting System. A mechanical draft venting system of other than direct-vent type shall terminate not less than 4 feet (1219 mm) below, 4 feet (1219 mm) horizontally from, or 1 foot (305 mm) above a door, operable window, or gravity air inlet into a building. The bottom of the vent terminal shall be located not less than 12 inches (305 mm) above finished ground level. [NFPA 54:12.9.2]

509.8.2 Direct-Vent Appliance. The vent terminal of a direct-vent appliance with an input of 10 000 Btu/h (3 kW) or less shall be located not less than 6 inches (152 mm) from an air opening into a building, and such an appliance with an input exceeding 10 000 Btu/h (3 kW) but not exceeding 50 000 Btu/h (14.7 kW) shall be installed with a 9 inch (229 mm) vent termination clearance, and an appliance with an input exceeding 50 000 Btu/h (14.7 kW) shall have not less than a 12 inch (305 mm) vent termination clearance. The bottom of the vent terminal and the air intake shall be located not less than 12 inches (305 mm) above finished ground level. [NFPA 54:12.9.3]

509.8.3 Nuisance and Hazard. Through-the-wall vents for Category II and Category IV appliances and noncategorized condensing appliances shall not terminate over public walkways or over an area where condensate or vapor is capable of creating a nuisance or hazard detrimental to the operation of regulators, relief valves, or other equipment. Where local experience indicates that condensate is a problem with Category I and Category III appliances, this provision shall also apply.



Drains for condensate shall be installed in accordance with the appliance and the vent manufacturer's installation instructions. [NFPA 54:12.9.4]



Notes:

- ¹ A – Equals the clearance with no protection specified in Table 509.7.3(1) and Table 509.7.3(2) and in the sections applying to various types of appliances.
- ² B – Equals the reduced clearance permitted in accordance with Table 509.7.3(2).
- ³ The protection applied to the construction using combustible material shall extend far enough in each direction to make C equal to A.


FIGURE 509.7.3(1)^{1, 2, 3}
EXTENT OF PROTECTION NECESSARY TO REDUCE CLEARANCES FROM GAS APPLIANCES OR VENT CONNECTORS
[NFPA 54: FIGURE 10.3.2.3(a)]



For SI units: 1 inch = 25.4 mm

Note: Masonry walls shall be attached to combustible walls using wall ties. Spacers shall not be used directly behind appliance or connector.

FIGURE 509.7.3(2)
WALL PROTECTION REDUCTION SYSTEM
[NFPA 54: FIGURE 10.3.2.3(b)]



For SI units: 1 inch = 25.4 mm

FIGURE 509.7.3(3)
MASONRY CLEARANCE REDUCTION SYSTEM
[NFPA 54: FIGURE 10.3.2.3(c)]

TABLE 509.7.3(2)
REDUCTION OF CLEARANCES WITH SPECIFIED FORMS OF PROTECTION^{1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11}
[NFPA 54: TABLE 10.2.3]

| TYPE OF PROTECTION APPLIED TO AND COVERING SURFACES OF COMBUSTIBLE MATERIAL WITHIN THE DISTANCE SPECIFIED AS THE REQUIRED CLEARANCE WITH NO PROTECTION [SEE FIGURE 509.7.3(1) THROUGH FIGURE 509.7.3(3)] | WHERE THE REQUIRED CLEARANCE WITH NO PROTECTION FROM APPLIANCE, VENT CONNECTOR, OR SINGLE-WALL METAL PIPE IS: | | | | | | | | | |
|--|---|-------------------------|----------------|-------------------------|----------------|-------------------------|----------------|-------------------------|----------------|-------------------------|
| | 36 (inches) | | 18 (inches) | | 12 (inches) | | 9 (inches) | | 6 (inches) | |
| | ALLOWABLE CLEARANCES WITH SPECIFIED PROTECTION (inches) | | | | | | | | | |
| | USE COLUMN 1 FOR CLEARANCES ABOVE APPLIANCE OR HORIZONTAL CONNECTOR. USE COLUMN 2 FOR CLEARANCES FROM APPLIANCES, VERTICAL CONNECTOR, AND SINGLE-WALL METAL PIPE. | | | | | | | | | |
| | ABOVE COLUMN 1 | SIDES AND REAR COLUMN 2 | ABOVE COLUMN 1 | SIDES AND REAR COLUMN 2 | ABOVE COLUMN 1 | SIDES AND REAR COLUMN 2 | ABOVE COLUMN 1 | SIDES AND REAR COLUMN 2 | ABOVE COLUMN 1 | SIDES AND REAR COLUMN 2 |
| (1) 3½ inch thick masonry wall without ventilated air space | — | 24 | — | 12 | — | 9 | — | 6 | — | 5 |
| (2) ½ of an inch insulation board over 1 inch glass fiber or mineral wool batts | 24 | 18 | 12 | 9 | 9 | 6 | 6 | 5 | 4 | 3 |
| (3) 0.024 inch sheet metal over 1 inch glass fiber or mineral wool batts reinforced with wire on rear face with ventilated air space | 18 | 12 | 9 | 6 | 6 | 4 | 5 | 3 | 3 | 3 |
| (4) 3½ inch thick masonry wall with ventilated air space | — | 12 | — | 6 | — | 6 | — | 6 | — | 6 |
| (5) 0.024 inch sheet metal with ventilated air space | 18 | 12 | 9 | 6 | 6 | 4 | 5 | 3 | 3 | 2 |
| (6) ½ of an inch thick insulation board with ventilated air space | 18 | 12 | 9 | 6 | 6 | 4 | 5 | 3 | 3 | 3 |
| (7) 0.024 inch sheet metal with ventilated air space over 0.024 inch sheet metal with ventilated air space | 18 | 12 | 9 | 6 | 6 | 4 | 5 | 3 | 3 | 3 |
| (8) 1 inch glass fiber or mineral wool batts sandwiched between two sheets 0.024 inch sheet metal with ventilated air space | 18 | 12 | 9 | 6 | 6 | 4 | 5 | 3 | 3 | 3 |

For SI units: 1 inch = 25.4 mm, °C = (°F-32)/1.8

Notes:

- ¹ Reduction of clearances from combustible materials shall not interfere with combustion air, draft hood clearance and relief, and accessibility of servicing.
- ² Clearances shall be measured from the outer surface of the combustible material to the nearest point on the surface of the appliance, disregarding an intervening protection applied to the combustible material.
- ³ Spacers and ties shall be of noncombustible material. No spacer or tie shall be used directly opposite the appliance or connector.
- ⁴ Where clearance reduction systems use a ventilated air space, adequate provision for air circulation shall be provided as described. [See Figure 509.7.3(2) and Figure 509.7.3(3)]
- ⁵ There shall be not less than 1 inch (25.4 mm) between clearance reduction systems and combustible walls and ceilings for reduction systems using a ventilated air space.
- ⁶ Where a wall protector is mounted on a single flat wall away from corners, it shall have a minimum 1 inch (25.4 mm) air gap. To provide air circulation, the bottom and top edges, or only the side and top edges, or edges shall be left open.
- ⁷ Mineral wool batts (blanket or board) shall have a minimum density of 8 pounds per cubic foot (lb/ft³) (128 kg/m³) and a minimum melting point of 1500°F (816°C).
- ⁸ Insulation material used as part of a clearance reduction system shall have a thermal conductivity of 1 British thermal unit inch per hour square foot degree Fahrenheit [Btu•in/(h•ft²•°F)] [0.1 W/(m•K)] or less.
- ⁹ There shall be not less than 1 inch (25.4 mm) between the appliance and the protector. In no case shall the clearance between the appliance and the combustible surface be reduced below that allowed in this table.
- ¹⁰ Clearances and thicknesses are minimum; larger clearances and thicknesses are acceptable.
- ¹¹ Listed single-wall connectors shall be installed in accordance with the terms of their listing and the manufacturer's installation instructions.

509.8.4 Annular Spaces. Where vents, including those for direct-vent appliances or combustion air intake pipes, penetrate outside walls of buildings, the annular spaces around such penetrations shall be permanently sealed using approved materials to prevent entry of combustion products into the building. [NFPA 54:12.9.5]

509.8.5 Vent Terminals. Vent terminals that terminate through an outside wall of a building and discharge flue gases perpendicular to the adjacent wall shall be located not less than 10 feet (3048 mm) horizontally from an operable opening in an adjacent building.

Exception: This shall not apply to vent terminals that are 2 feet (610 mm) or more above or 25 feet (7620 mm) or more below operable openings. [NFPA 54:12.9.6]

509.9 Condensation Drain. Provision shall be made to collect and dispose of condensate from venting systems serving Category II and Category IV appliances and noncategorized condensing appliances in accordance with Section 509.8.3. [NFPA 54:12.10.1]

509.9.1 Local Experience. Where local experience indicates that condensation is a problem, provision shall be made to drain off and dispose of condensate from venting systems serving Category I and Category III appliances in accordance with Section 509.8.3. [NFPA 54:12.10.2]

509.10 Vent Connectors for Category I Appliances.

A vent connector shall be used to connect an appliance to a gas vent, chimney, or single-wall metal pipe, except where the gas vent, chimney, or single-wall metal pipe is directly connected to the appliance. [NFPA 54:12.11.1]

509.10.1 Materials. A vent connector shall be made of noncombustible, corrosion resistant material capable of

withstanding the vent gas temperature produced by the appliance and of a thickness to withstand physical damage. [NFPA 54:12.11.2.1]

509.10.1.1 Unconditioned Area. Where the vent connector used for an appliance having a draft hood or a Category I appliance is located in or passes through an unconditioned area, attic or crawl space, that portion of the vent connector shall be listed Type B, Type L, or listed vent material having equivalent insulation qualities.

Exception: Single-wall metal pipe located within the exterior walls of the building and located in an unconditioned area other than an attic or a crawl space having a local 99 percent winter design temperature of 5°F (-15°C) or higher. [NFPA 54:12.11.2.2]

509.10.1.2 Residential-Type Appliances. Vent connectors for residential-type appliances shall comply with the following:

- (1) Vent connectors for listed appliances having draft hoods, appliances having draft hoods and equipped with listed conversion burners, and Category I appliances that are not installed in attics, crawl spaces, or other unconditioned areas shall be one of the following:
 - (a) Type B or Type L vent material.
 - (b) Galvanized sheet steel not less than 0.018 of an inch (0.457 mm) thick.
 - (c) Aluminum (1100 or 3003 alloy or equivalent) sheet not less than 0.027 of an inch (0.686 mm) thick.
 - (d) Stainless steel sheet not less than 0.012 of an inch (0.305 mm) thick.




FIGURE 509.8
EXIT TERMINALS OF MECHANICAL DRAFT AND DIRECT-VENT VENTING SYSTEMS
 [NFPA 54: FIGURE A.12.9]

- (e) Smooth interior wall metal pipe having resistance to heat and corrosion equal to or exceeding that of Section 509.10.1.2(1)(b), Section 509.10.1.2(1)(c), or Section 509.10.1.2(1)(d) above.
 - (f) A listed vent connector.
- (2) Vent connectors shall not be covered with insulation.

Exception: Listed insulated vent connectors shall be installed in accordance with the manufacturer's installation instructions. [NFPA 54:12.11.2.3]

509.10.1.3 Non-Residential Low-Heat Appliances. A vent connector for a non-residential low-heat appliance shall be a factory-built chimney section or steel pipe having resistance to heat and corrosion equivalent to the galvanized pipe specified in Table 509.10.1.3. Factory-built chimney sections shall be installed in accordance with the chimney manufacturer's installation instructions. [NFPA 54:12.11.2.4]

509.10.1.4 Medium-Heat Appliances. Vent connectors for medium-heat appliances, and commercial and industrial incinerators, shall be constructed of factory-built, medium-heat chimney sections or steel of a thickness not less than that specified in Table 509.10.1.4 and shall comply with the following:

- (1) A steel vent connector for appliances with a vent gas temperature in excess of 1000°F (538°C) measured at the entrance to the connector shall be lined with medium-duty fire brick or the equivalent.
- (2) The lining shall be not less than 2½ inches (64 mm) thick for a vent connector having a diameter or greatest cross-sectional dimension of 18 inches (457 mm) or less.
- (3) The lining shall be not less than 4½ inches (114 mm) thick laid on the 4½ inch (114 mm) bed for a vent connector having a diameter or cross-sectional dimension exceeding 18 inches (457 mm).
- (4) Factory-built chimney sections, where employed, shall be installed in accordance with the chimney manufacturer's installation instructions. [NFPA 54:12.11.2.6]

509.10.2 Size of Vent Connector. A vent connector for an appliance with a single draft hood or for a Category I fan-assisted combustion system appliance shall be sized and installed in accordance with Section 510.0 or other approved engineering methods. [NFPA 54:12.11.3.1]

509.10.2.1 Manifold. For a single appliance having more than one draft hood outlet or flue collar, the manifold shall be constructed according to the instructions of the appliance manufacturer. Where there are no instructions, the manifold shall be designed and constructed in accordance with approved engineering practices. As an alternate method, the effective area of the manifold shall equal the combined area of the flue collars or draft hood outlets, and the vent connectors shall have not less than 1 foot (305 mm) rise. [NFPA 54:12.11.3.2]

509.10.2.2 Size. Where two or more appliances are connected to a common vent or chimney, each vent connector shall be sized in accordance with Section 510.0 or other approved engineering methods. [NFPA 54:12.11.3.3]

As an alternative method applicable where the appliances are draft hood-equipped, each vent connector shall have an effective area not less than the area of the draft hood outlet of the appliance to which it is connected. [NFPA 54:12.11.3.4]

509.10.2.3 Height. Where two or more appliances are vented through a common vent connector or vent manifold, the common vent connector or vent manifold shall be located at the highest level consistent with available headroom and clearance to combustible material and shall be sized in accordance with Section 510.0 or other approved engineering methods. [NFPA 54:12.11.3.5]

As an alternate method applicable where there are two draft hood-equipped appliances, the effective area of the common vent connector or vent manifold and junction fittings shall be not less than the area of the larger vent connector plus 50 percent of the areas of smaller flue collar outlets. [NFPA 54:12.11.3.6]

509.10.2.4 Size Increase. Where the size of a vent connector is increased to overcome installation limitations and obtain connector capacity equal to the appliance input, the size increase shall be made at the appliance draft hood outlet. [NFPA 54:12.11.3.7]

TABLE 509.10.1.3
MINIMUM THICKNESS FOR GALVANIZED STEEL VENT
CONNECTORS FOR LOW-HEAT APPLIANCES
[NFPA 54: TABLE 12.11.2.4]

| DIAMETER OF CONNECTOR (inches) | MINIMUM THICKNESS (inches) |
|-----------------------------------|-------------------------------|
| Less than 6 | 0.019 |
| 6 to less than 10 | 0.023 |
| 10 to 12 inclusive | 0.029 |
| 14 to 16 inclusive | 0.034 |
| Over 16 | 0.056 |

For SI units: 1 inch = 25.4 mm, 1 square inch = 0.000645 m²

TABLE 509.10.1.4
MINIMUM THICKNESS FOR STEEL VENT CONNECTORS FOR
MEDIUM-HEAT APPLIANCES AND COMMERCIAL AND
INDUSTRIAL INCINERATORS
[NFPA 54: TABLE 12.11.2.5]

| VENT CONNECTOR SIZE | | |
|---------------------|-------------------------|-------------------------------|
| DIAMETER (inches) | AREA (square inches) | MINIMUM THICKNESS (inches) |
| Up to 14 | Up to 154 | 0.053 |
| Over 14 to 16 | 154 to 201 | 0.067 |
| Over 16 to 18 | 201 to 254 | 0.093 |
| Over 18 | Exceeding 254 | 0.123 |

For SI units: 1 inch = 25.4 mm, 1 square inch = 0.000645 m²

509.10.3 Two or More Appliances Connected to a Single Vent. Where two or more openings are provided into one chimney flue or vent, the openings shall be at different levels, or the connectors shall be attached to the vertical portion of the chimney or vent at an angle of 45 degrees (0.79 rad) or less relative to the vertical. [NFPA 54:12.11.4.1]

509.10.3.1 Height of Connector. Where two or more vent connectors enter a common vent, chimney flue, or single-wall metal pipe, the smaller connector shall enter at the highest level consistent with the available headroom or clearance to combustible material. [NFPA 54:12.11.4.2]

509.10.3.2 Pressure. Vent connectors serving Category I appliances shall not be connected to a portion of a mechanical draft system operating under positive static pressure, such as those serving Category III or Category IV appliances. [NFPA 54:12.11.4.3]

509.10.4 Clearance. Minimum clearances from vent connectors to combustible material shall comply with Table 509.7.3(1).

Exception: The clearance between a vent connector and combustible material shall be permitted to be reduced where the combustible material is protected as specified for vent connectors in Table 509.7.3(2). [NFPA 54:12.11.5]

509.10.5 Joints. Joints between sections of connector piping and connections to flue collars or draft hood outlets shall be fastened in accordance with one of the following methods:

- (1) By sheet metal screws.
- (2) Vent connectors of listed vent material shall be assembled and connected to flue collars or draft hood outlets in accordance with the manufacturer's installation instructions.
- (3) Other approved means. [NFPA 54:12.11.6]

509.10.6 Slope. A vent connector shall be installed without dips or sags and shall slope upward toward the vent or chimney not less than ¼ inch per foot (20.8 mm/m).

Exception: Vent connectors attached to a mechanical draft system installed in accordance with the appliance and draft system manufacturer's installation instructions. [NFPA 54:12.11.7]

509.10.7 Length of Vent Connector. The length of vent connectors shall comply with Section 509.10.7.1 or Section 509.10.7.2.

509.10.7.1 Single Wall Connector. The maximum horizontal length of a single-wall connector shall be 75 percent of the height of the chimney or vent except for engineered systems. [NFPA 54:12.11.8.1]

509.10.7.2 Type B Double Wall Connector. The maximum horizontal length of a Type B double-wall connector shall be 100 percent of the height

of the chimney or vent, except for engineered systems. The maximum length of an individual connector for a chimney or vent system serving multiple appliances, from the appliance outlet to the junction with the common vent or another connector, shall be 100 percent of the height of the chimney or vent. [NFPA 54:12.11.8.2]

509.10.8 Support. A vent connector shall be supported for the design and weight of the material employed to maintain clearances and prevent physical damage and separation of joints. [NFPA 54:12.11.9]

509.10.9 Chimney Connection. Where entering a flue in a masonry or metal chimney, the vent connector shall be installed above the extreme bottom to avoid stoppage. Where a thimble or slip joint is used to facilitate removal of the connector, the connector shall be attached to or inserted into the thimble or slip joint to prevent the connector from falling out. Means shall be employed to prevent the connector from entering so far as to restrict the space between its end and the opposite wall of the chimney flue. [NFPA 54:12.11.10]

509.10.10 Inspection. The entire length of a vent connector shall be readily accessible for inspection, cleaning, and replacement. [NFPA 54:12.11.11]

509.10.11 Fireplaces. A vent connector shall not be connected to a chimney flue serving a fireplace unless the fireplace flue opening is permanently sealed. [NFPA 54:12.11.12]

509.10.12 Passage through Ceilings, Floors, or Walls. A vent connector shall not pass through a ceiling, floor, or fire-resistance-rated wall. A single-wall metal pipe connector shall not pass through an interior wall.

Exception: Vent connectors made of listed Type B or Type L vent material and serving listed appliances with draft hoods and other appliances listed for use with Type B gas vents that pass through walls or partitions constructed of combustible material shall be installed with not less than the listed clearance to combustible material.

509.10.12.1 Medium-Heat Appliances. Vent connectors for medium-heat appliances shall not pass through walls or partitions constructed of combustible material. [NFPA 54:12.11.13.2]

509.11 Draft Hoods and Draft Controls. Vented appliances shall be installed with draft hoods.

Exception: Dual oven-type combination ranges; incinerators; direct-vent appliances; fan-assisted combustion system appliances; appliances requiring chimney draft for operation; single firebox boilers equipped with conversion burners with inputs exceeding 400 000 Btu/h (117 kW); appliances equipped with blast, power, or pressure burners that are not listed for use with draft hoods; and appliances designed for forced venting.

509.11.1 Installation. A draft hood supplied with or forming a part of listed vented appliances shall be installed without alteration, exactly as furnished and specified by the appliance manufacturer. [NFPA 54:12.13.2]

Where a draft hood is not supplied by the appliance manufacturer where one is required, a draft hood shall be installed, be of a listed or approved type, and, in the absence of other instructions, be of the same size as the appliance flue collar. Where a draft hood is required with a conversion burner, it shall be of a listed or approved type. [NFPA 54:12.13.2.1]

Where a draft hood of special design is needed or preferable, the installation shall be approved and in accordance with the recommendations of the appliance manufacturer. [NFPA 54:12.13.2.2]

509.11.2 Draft Control Devices. Where a draft control device is part of the appliance or is supplied by the appliance manufacturer, it shall be installed in accordance with the manufacturer's installation instructions. In the absence of manufacturer's installation instructions, the device shall be attached to the flue collar of the appliance or as near to the appliance as practical. [NFPA 54:12.13.3]

509.11.3 Additional Devices. Appliances requiring controlled chimney draft shall be permitted to be equipped with listed double-acting barometric draft regulators installed and adjusted in accordance with the manufacturer's installation instructions. [NFPA 54:12.13.4]

509.11.4 Location. Draft hoods and barometric draft regulators shall be installed in the same room or enclosure as the appliance in such a manner as to prevent a difference in pressure between the hood or regulator and the combustion air supply. [NFPA 54:12.13.5]

509.11.5 Positioning. Draft hoods and draft regulators shall be installed in the position for which they were designed with reference to the horizontal and vertical planes and shall be located so that the relief opening is not obstructed by a part of the appliance or adjacent construction. The appliance and its draft hood shall be located so that the relief opening is accessible for checking vent operation. [NFPA 54:12.13.6]

509.11.6 Clearance. A draft hood shall be located so that its relief opening is not less than 6 inches (152 mm) from a surface except that of the appliance it serves and the venting system to which the draft hood is connected. Where a greater or lesser clearance is indicated on the appliance label, the clearance shall not be less than that specified on the label. Such clearances shall not be reduced. [NFPA 54:12.13.7]

509.12 Manually Operated Dampers. A manually operated damper shall not be placed in an appliance vent connector. Fixed baffles shall not be classified as manually operated dampers. [NFPA 54:12.14]

509.13 Automatically Operated Vent Dampers. An automatically operated vent damper shall be of a listed type. [NFPA 54:12.15]

509.13.1 Listing. Automatically operated vent dampers for oil fired appliances shall comply with UL 17. The automatic damper control shall comply with UL 378.

509.14 Obstructions. Devices that retard the flow of vent gases shall not be installed in a vent connector, chimney, or vent. The following shall not be considered as obstructions:

- (1) Draft regulators and safety controls specifically listed for installation in venting systems and installed in accordance with the manufacturer's installation instructions.
- (2) Approved draft regulators and safety controls designed and installed in accordance with approved engineering methods.
- (3) Listed heat reclaimers and automatically operated vent dampers installed in accordance with the manufacturer's installation instructions.
- (4) Vent dampers serving listed appliances installed in accordance with Section 510.1 or Section 510.2 or other approved engineering methods.
- (5) Approved economizers, heat reclaimers, and recuperators installed in venting systems of appliances not required to be equipped with draft hoods, provided the appliance manufacturer's installation instructions cover the installation of such a device in the venting system and performance in accordance with Section 509.3 and Section 509.3.1 is obtained. [NFPA 54:12.16]

510.0 Sizing of Category I Venting Systems.

510.1 Single Appliance Vent Table 510.1.2(1) through Table 510.1.2(6). Table 510.1.2(1) through Table 510.1.2(6) shall not be used where obstructions are installed in the venting system. The installation of vents serving listed appliances with vent dampers shall be in accordance with the appliance manufacturer's installation instructions or in accordance with the following:

- (1) The maximum capacity of the vent system shall be determined using the NAT Max column.
- (2) The minimum capacity shall be determined as though the appliance were a fan-assisted appliance, using the FAN Min column to determine the minimum capacity of the vent system. Where the corresponding "FAN Min" is "NA", the vent configuration shall not be permitted and an alternative venting configuration shall be utilized. [NFPA 54:13.1.1]

510.1.1 Vent Downsizing. Where the vent size determined from the tables is smaller than the appliance draft hood outlet or flue collar, the use of the smaller size shall be permitted provided that the installation is in accordance with the following requirements:

- (1) The total vent height (H) is not less than 10 feet (3048 mm).
- (2) Vents for appliance draft hood outlets or flue collars 12 inches (305 mm) in diameter or smaller are not reduced more than one table size.
- (3) Vents for appliance draft hood outlets or flue collars exceeding 12 inches (305 mm) in diameter are not reduced more than two table sizes.
- (4) The maximum capacity listed in the tables for a fan-assisted appliance is reduced by 10 percent (0.90 x maximum table capacity).
- (5) The draft hood outlet exceeds 4 inches (102 mm) in diameter. A 3 inch (76 mm) diameter vent shall not be connected to a 4 inch (102 mm) diameter draft hood outlet. This provision shall not apply to fan-assisted appliances. [NFPA 54:13.1.2]

510.1.2 Elbows. Single-appliance venting configurations with zero lateral lengths in Table 510.1.2(1), Table 510.1.2(2), and Table 510.1.2(5) shall not have elbows in the venting system. Single-appliance venting with lateral lengths, include two 90 degree (1.57 rad) elbows. For each additional elbow up to and including 45 degrees (0.79 rad), the maximum capacity listed in the venting tables shall be reduced by 5 percent. For each additional elbow greater than 45 degrees (0.79 rad) up to and including 90 degrees (1.57 rad), the maximum capacity listed in the venting tables shall be reduced by 10 percent. Where multiple offsets occur in a vent, the total lateral length of offsets combined shall not exceed that specified in Table 510.1.2(1) through Table 510.1.2(5). [NFPA 54:13.1.3]

510.1.3 Zero Lateral. Zero lateral (L) shall apply to a straight vertical vent attached to a top outlet draft hood or flue collar. [NFPA 54:13.1.4]

510.1.4 High-Altitude Installations. Sea level input ratings shall be used where determining maximum capacity for high-altitude installation. Actual input (derated for altitude) shall be used for determining minimum capacity for high-altitude installation. [NFPA 54:13.1.5]

510.1.5 Multiple Input Ratings. For appliances with more than one input rate, the minimum vent capacity (FAN Min) determined from the tables shall be less than the lowest appliance input rating, and the maximum vent capacity (FAN Max/NAT Max) determined from the tables shall exceed the highest appliance rating input. [NFPA 54:13.1.6]

510.1.6 Corrugated Chimney Liner Reduction. Listed corrugated metallic chimney liner systems in masonry chimneys shall be sized by using Table 510.1.2(1) or Table 510.1.2(2) for Type B vents with the maximum capacity reduced by 20 percent (0.80 x maximum capacity) and the minimum capacity as shown in Table 510.1.2(1) or Table 510.1.2(2).

Corrugated metallic liner systems installed with bends or offsets shall have their maximum capacity further reduced in accordance with Section 510.1.2. The 20 percent reduction for corrugated metallic chimney liner systems includes an allowance for one long radius 90 degree (1.57 rad) turn at the bottom of the liner. [NFPA 54:13.1.7]

510.1.7 Connection to Chimney Liners. Connections between chimney liners and listed double-wall connectors shall be made with listed adapters designed for such purposes. [NFPA 54:13.1.8]

510.1.8 Vertical Vent Upsizing Using 7 x Rule. Where the vertical vent has a larger diameter than the vent connector, the vertical vent diameter shall be used to determine the minimum vent capacity, and the connector diameter shall be used to determine the maximum vent capacity. The flow area of the vertical vent shall not exceed seven times the flow area of the listed appliance categorized vent area, flue collar area, or draft hood outlet area unless designed in accordance with approved engineering methods. [NFPA 54:13.1.9]

510.1.9 Draft Hood Conversion Accessories. Draft hood conversion accessories for use with masonry chimneys venting listed Category I fan-assisted appliances shall be listed and installed in accordance with the

listed accessory manufacturer's installation instructions. [NFPA 54:13.1.10]

510.1.10 Chimney and Vent Locations. Table 510.1.2(1) through Table 510.1.2(5) shall be used for chimneys and vents not exposed to the outdoors below the roof line. A Type B vent or listed chimney lining system passing through an unused masonry chimney flue shall not be considered to be exposed to the outdoors. Where vents extend outdoors above the roof more than 5 feet (1524 mm) higher than required by Table 509.6.2, and where vents terminate in accordance with Section 509.6.2(1), the outdoor portion of the vent shall be enclosed as required by this section for vents not considered to be exposed to the outdoors or such venting system shall be engineered. A Type B vent passing through an unventilated enclosure or chase insulated to a value of not less than R-8 shall not be considered to be exposed to the outdoors. Table 510.1.2(3) in combination with Table 510.1.2(6) shall be used for clay-tile-lined exterior masonry chimneys, provided the following requirements are met:

- (1) The vent connector is Type B double wall.
- (2) The vent connector length is limited to 18 inches per inch (18 mm/mm) of vent connector diameter.
- (3) The appliance is draft hood-equipped.
- (4) The input rating is less than the maximum capacity given in Table 510.1.2(3).
- (5) For a water heater, the outdoor design temperature shall be not less than 5°F (-15°C).
- (6) For a space-heating appliance, the input rating exceeds the minimum capacity given by Table 510.1.2(6). [NFPA 54:13.1.11]

510.1.11 Corrugated Vent Connector Size. Corrugated vent connectors shall not be smaller than the listed appliance categorized vent diameter, flue collar diameter, or draft hood outlet diameter. [NFPA 54:13.1.12]

510.1.12 Upsizing. Vent connectors shall not be upsized more than two sizes exceeding the listed appliance categorized vent diameter, flue collar diameter, or draft hood outlet diameter. [NFPA 54:13.1.13]

510.1.13 Single Run of Vent. In a single run of vent or vent connector, more than one diameter and type shall be permitted to be used, provided that the sizes and types are permitted by the tables. [NFPA 54:13.1.14]

510.1.14 Interpolation. Interpolation shall be permitted in calculating capacities for vent dimensions that fall between table entries. [NFPA 54:13.1.15]

510.1.15 Extrapolation. Extrapolation beyond the table entries shall not be permitted. [NFPA 54:13.1.16]

510.1.16 Engineering Methods. For vent heights lower than 6 feet (1829 mm) and higher than vent heights shown in the tables, engineering methods shall be used to calculate vent capacities. [NFPA 54:13.1.17]

510.1.17 Height Entries. Where the actual height of a vent falls between entries in the height column of the applicable table in Table 510.1.2(1) through Table 510.1.2(6), one of the following shall be used:

- (1) Interpolation.

- (2) The lower appliance input rating shown in the table entries for FAN Max and NAT Max column values; and the higher appliance input rating for the FAN Min column values. [NFPA 54:13.1.18]

510.2 Multiple Appliance Vent Table 510.2(1) through

Table 510.2(9). Table 510.2(1) through Table 510.2(9) shall not be used where obstructions are installed in the venting system. The installation of vents serving listed appliances with vent dampers shall be in accordance with the appliance manufacturer's installation instructions or in accordance with the following:

- (1) The maximum capacity of the vent connector shall be determined using the NAT Max column.
- (2) The maximum capacity of the vertical vent or chimney shall be determined using the FAN + NAT column where the second appliance is a fan-assisted appliance, or the NAT + NAT column where the second appliance is equipped with a draft hood.
- (3) The minimum capacity shall be determined as if the appliance were a fan-assisted appliance, as follows:
 - (a) The minimum capacity of the vent connector shall be determined using the FAN Min column.
 - (b) The FAN + FAN column shall be used where the second appliance is a fan-assisted appliance, and the FAN + NAT column shall be used where the second appliance is equipped with a draft hood, to determine whether the vertical vent or chimney configuration is not permitted (NA). Where the vent configuration is NA, the vent configuration shall not be permitted and an alternative venting configuration shall be utilized. [NFPA 54:13.2.1]

510.2.1 Vent Connector Maximum Length. The maximum vent connector horizontal length shall be 18 inches per inch (18 mm/mm) of connector diameter as shown in Table 510.2.1, or as permitted by Section 510.2.2. [NFPA 54:13.2.2]

510.2.2 Vent Connector Exceeding Maximum Length. The vent connector shall be routed to the vent utilizing the shortest possible route. Connectors with longer horizontal lengths than those listed in Table 510.2.1 are permitted under the following conditions:

- (1) The maximum capacity (FAN Max or NAT Max) of the vent connector shall be reduced 10 percent for each additional multiple of the length listed in Table 510.2.1. For example, the length listed for a 4 inch (102 mm) connector shall not exceed 6 feet (1829 mm). With a connector length exceeding 6 feet (1829 mm) but not exceeding 12 feet (3658 mm), the maximum capacity shall be reduced by 10 percent ($0.90 \times$ maximum vent connector capacity). With a connector length exceeding 12 feet (3658 mm) but not exceeding 18 feet (5486 mm), the maximum capacity shall be reduced by 20 percent ($0.80 \times$ maximum vent capacity).
- (2) For a connector serving a fan-assisted appliance, the minimum capacity (FAN Min) of the connector shall be determined by referring to the corresponding single appliance table. For Type B double-wall connec-

tors, Table 510.1.2(1) shall be used. For single-wall connectors, Table 510.1.2(2) shall be used. The height (H) and lateral (L) shall be measured according to the procedures for a single appliance vent, as if the other appliances were not present. [NFPA 54:13.2.3]

510.2.3 Vent Connector Manifold. Where the vent connectors are combined prior to entering the vertical portion of the common vent to form a common vent manifold, the size of the common vent manifold and the common vent shall be determined by applying a 10 percent reduction ($0.90 \times$ maximum common vent capacity) to the common vent capacity part of the common vent tables. The length of the common vent manifold (LM) shall not exceed 18 inches per inch (18 mm/mm) of common vent diameter (D). [NFPA 54:13.2.4]

510.2.4 Vent Offset. Where the common vertical vent is offset, the maximum capacity of the common vent shall be reduced in accordance with Section 510.2.5, and the horizontal length of the common vent offset shall not exceed 18 inches per inch (18 mm/mm) of common vent diameter (D). Where multiple offsets occur in a common vent, the total horizontal length of offsets combined shall not exceed 18 inches per inch (18 mm/mm) of the common vent diameter. [NFPA 54:13.2.5]

510.2.5 Elbow Reduction. For each elbow up to and including 45 degrees (0.79 rad) in the common vent, the maximum common vent capacity listed in the venting tables shall be reduced by 5 percent. For each elbow exceeding 45 degrees (0.79 rad) up to and including 90 degrees (1.57 rad), the maximum common vent capacity listed in the venting tables shall be reduced by 10 percent. [NFPA 54:13.2.6]

510.2.6 Common Vent Minimum Size. The cross-sectional area of the common vent shall be equal to or exceeding the cross-sectional area of the largest connector. [NFPA 54:13.2.8]

TABLE 510.2.1
VENT CONNECTOR MAXIMUM LENGTH
[NFPA 54: TABLE 13.2.2]

| CONNECTOR DIAMETER (inches) | MAXIMUM CONNECTOR HORIZONTAL LENGTH (feet) |
|--------------------------------|---|
| 3 | 4½ |
| 4 | 6 |
| 5 | 7½ |
| 6 | 9 |
| 7 | 10½ |
| 8 | 12 |
| 9 | 13½ |
| 10 | 15 |
| 12 | 18 |
| 14 | 21 |
| 16 | 24 |
| 18 | 27 |
| 20 | 30 |
| 22 | 33 |
| 24 | 36 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm

510.2.7 Tee and Wye Fittings. Tee and wye fittings connected to a common gas vent shall be considered as part of the common gas vent and constructed of materials consistent with that of the common gas vent. [NFPA 54:13.2.9]

510.2.8 Size of Fittings. At the point where tee or wye fittings connect to a common gas vent, the opening size of the fitting shall be equal to the size of the common vent. Such fittings shall not be prohibited from having reduced size openings at the point of connection of appliance gas vent connectors. [NFPA 54:13.2.10]

510.2.9 High-Altitude Installations. Sea level input ratings shall be used where determining maximum capacity for high-altitude installation. Actual input (derated for altitude) shall be used for determining minimum capacity for high-altitude installation. [NFPA 54:13.2.11]

510.2.10 Connector Rise. The connector rise (R) for each appliance connector shall be measured from the draft hood outlet or flue collar to the centerline where the vent gas streams come together. [NFPA 54:13.2.12]

510.2.11 Vent Height. For multiple appliances located on one floor, the total height (H) shall be measured from the highest draft hood outlet or flue collar up to the level of the outlet of the common vent. [NFPA 54:13.2.13]

510.2.12 Multistory Installations. For multistory installations, the total height (H) for each segment of the system shall be the vertical distance between the highest draft hood outlet or flue collar entering that segment and the centerline of the next higher interconnection tee. [NFPA 54:13.2.14]

510.2.13 Size of Vents for Multistory Installations. The size of the lowest connector and of the vertical vent leading to the lowest interconnection of a multistory system shall be in accordance with Table 510.1.2(1) or Table 510.1.2(2) for available total height (H) up to the lowest interconnection. [NFPA 54:13.2.15]

510.2.14 Vent Type Multistory Installations. Where used in multistory systems, vertical common vents shall be Type B double-wall and shall be installed with a listed vent cap. [NFPA 54:13.2.16]

510.2.15 Offsets in Multistory Installations. Offsets in multistory common vent systems shall be limited to a single offset in each system, and systems with an offset shall comply with the following:

- (1) The offset angle shall not exceed 45 degrees (0.79 rad) from vertical.
- (2) The horizontal length of the offset shall not exceed 18 inches per inch (18 mm/mm) of common vent diameter of the segment in which the offset is located.
- (3) For the segment of the common vertical vent containing the offset, the common vent capacity listed in the common venting tables shall be reduced by 20 percent (0.80 x maximum common vent capacity).
- (4) A multistory common vent shall not be reduced in size above the offset. [NFPA 54:13.2.17]

510.2.16 Vertical Vent Size Limitation. Where two or more appliances are connected to a vertical vent or chimney, the flow area of the largest section of vertical vent or chimney shall not exceed seven times the smallest listed appliance categorized vent areas, flue collar area, or draft hood outlet area unless designed in accordance with approved engineering methods. [NFPA 54:13.2.18]

510.2.17 Multiple Input Ratings. For appliances with more than one input rate, the minimum vent connector capacity (FAN Min) determined from the tables shall be less than the lowest appliance input rating, and the maximum vent connector capacity (FAN Max or NAT Max) determined from the table shall exceed the highest appliance input rating. [NFPA 54:13.2.19]

510.2.18 Corrugated Metallic Chimney Liner Reduction. Listed corrugated metallic chimney liner systems in masonry chimneys shall be sized by using Table 510.2(1) or Table 510.2(2) for Type B vents, with the maximum capacity reduced by 20 percent (0.80 x maximum capacity) and the minimum capacity as shown in Table 510.2(1) or Table 510.2(2). Corrugated metallic liner systems installed with bends or offsets shall have their maximum capacity further reduced in accordance with Section 510.2.5. The 20 percent reduction for corrugated metallic chimney liner systems includes an allowance for one long radius 90 degree (1.57 rad) turn at the bottom of the liner. [NFPA 54:13.2.20]

510.2.19 Chimneys and Vents. Table 510.2(1) through Table 510.2(5) shall be used for chimneys and vents not exposed to the outdoors below the roof line. A Type B vent or listed chimney lining system passing through an unused masonry chimney flue shall not be considered to be exposed to the outdoors. A Type B vent passing through an unventilated enclosure or chase insulated to a value of not less than R-8 shall not be considered to be exposed to the outdoors. Where vents extend outdoors above the roof more than 5 feet (1524 mm) higher than required by Table 509.6.2, and where vents terminate in accordance with Section 509.6.2(1), the outdoor portion of the vent shall be enclosed as required by this section for vents not considered to be exposed to the outdoors, or such venting system shall be engineered. Table 510.2(6) through Table 510.2(9) shall be used for clay-tile-lined exterior masonry chimneys, provided the following conditions are met:

- (1) The vent connector is Type B double-wall.
- (2) Not less than one appliance is draft hood-equipped.
- (3) The combined appliance input rating is less than the maximum capacity given by Table 510.2(6) (for NAT + NAT) or Table 510.2(8) (for FAN + NAT).
- (4) The input rating of each space-heating appliance exceeds the minimum input rating given by Table 510.2(7) (for NAT + NAT) or Table 510.2(9) (for FAN + NAT).
- (5) The vent connector sizing is in accordance with Table 510.2(3). [NFPA 54:13.2.22]

510.2.20 Vent Connector Sizing. Vent connectors shall not be increased more than two sizes exceeding the listed appliance categorized vent diameter, flue collar diameter, or draft hood outlet diameter. Vent connectors for draft hood-equipped appliances shall not be smaller than the draft hood outlet diameter. Where vent connector sizes determined from the tables for fan-assisted appliances are smaller than the flue collar diameter, the use of the smaller sizes shall be permitted provided that the installation is in accordance with the following conditions:

- (1) Vent connectors for fan-assisted appliance flue collars 12 inches (305 mm) in diameter or smaller are not reduced by more than one table size [e.g., 12 inches to 10 inches (305 mm to 254 mm) is a one size reduction] and those exceeding 12 inches (305 mm) in diameter are not reduced exceeding two table sizes [e.g., 24 inches to 20 inches (610 mm to 508 mm) is a two size reduction].
- (2) The fan-assisted appliance is common vented with a draft hood-equipped appliance.
- (3) The vent connector has a smooth interior wall. [NFPA 54:13.2.24]

510.2.21 Combination of Pipe Types and Sizes.

Combinations of pipe sizes, single-wall metal pipe, and double-wall metal pipe shall be allowed within a connector run or within the common vent, provided the appropriate tables permit the desired sizes and types of pipe, where they were used for the entire length of the subject connector or vent. Where single-wall and Type B double-wall metal pipes are used for vent connectors within the same venting system, the common vent shall be sized in accordance with Table 510.2(2) or Table 510.2(4). [NFPA 54:13.2.25]

510.2.22 Multiple Connector and Vent Sizes.

Where a table permits more than one diameter of pipe to be used for a connector or vent, the permitted sizes shall be permitted to be used. [NFPA 54:13.2.26]

510.2.23 Interpolation. Interpolation shall be permitted in calculating capacities for vent dimensions that fall between table entries. [NFPA 54:13.2.27]

510.2.24 Extrapolation. Extrapolation beyond the table entries shall not be permitted. [NFPA 54:13.2.28]

510.2.25 Engineering Methods. For vent heights lower than 6 feet (1829 mm) and exceeding vent heights shown in the tables, engineering methods shall be used to calculate vent capacities. [NFPA 54:13.2.29]

510.2.26 Height Entries. Where the actual height of a vent falls between entries in the height column of the applicable table in Table 510.2(1) through Table 510.2(9), one of the following shall be used:

- (1) Interpolation.
- (2) The lower appliance input rating shown in the table entries for FAN Max and NAT Max column values; and the higher appliance input rating for the FAN Min column values. [NFPA 54:13.2.30]

WATER HEATERS



99% Winter Design Temperatures for the Contiguous United States

This map is a necessarily generalized guide to temperatures in the contiguous United States. Temperatures shown for areas such as mountainous regions and large urban centers may not be accurate. The data used to develop this map are from the 1993 ASHRAE Handbook — Fundamentals (Chapter 24, Table 1: Climate Conditions for the United States).

For 99% winter design temperatures in Alaska, consult the ASHRAE Handbook — Fundamentals.

99% winter design temperatures for Hawaii are greater than 37°F.

For SI units: $^{\circ}\text{C} = (^{\circ}\text{F} - 32) / 1.8$

FIGURE 510.1.2(6)
RANGE OF WINTER DESIGN TEMPERATURES USED IN ANALYZING EXTERIOR MASONRY CHIMNEYS IN THE UNITED STATES
[NFPA 54: FIGURE F.2.4]

TABLE 510.1.2(1)
TYPE B DOUBLE-WALL GAS VENT [NFPA 54: TABLE 13.1(a)]*

| | | | | | NUMBER OF APPLIANCES: | | | | | | SINGLE | | | | | | | | |
|---|------------------------|-----|-----|-----|----------------------------|-----|-----|-----|-----|-----|----------------------------|-----|-----|-----|-----|-----|---|--|--|
| | | | | | APPLIANCE TYPE: | | | | | | CATEGORY I | | | | | | | | |
| | | | | | APPLIANCE VENT CONNECTION: | | | | | | CONNECTED DIRECTLY TO VENT | | | | | | | | |
| | | | | | VENT DIAMETER – D (Inch) | | | | | | | | | | | | | | |
| | | | | | 3 | | | 4 | | | 5 | | | 6 | | | 7 | | |
| APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | | | | | | | |
| HEIGHT H (feet) | LATERAL L (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | | | |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | | | |
| 6 | 0 | 0 | 78 | 46 | 0 | 152 | 86 | 0 | 251 | 141 | 0 | 375 | 205 | 0 | 524 | 285 | | | |
| | 2 | 13 | 51 | 36 | 18 | 97 | 67 | 27 | 157 | 105 | 32 | 232 | 157 | 44 | 321 | 217 | | | |
| | 4 | 21 | 49 | 34 | 30 | 94 | 64 | 39 | 153 | 103 | 50 | 227 | 153 | 66 | 316 | 211 | | | |
| | 6 | 25 | 46 | 32 | 36 | 91 | 61 | 47 | 149 | 100 | 59 | 223 | 149 | 78 | 310 | 205 | | | |
| 8 | 0 | 0 | 84 | 50 | 0 | 165 | 94 | 0 | 276 | 155 | 0 | 415 | 235 | 0 | 583 | 320 | | | |
| | 2 | 12 | 57 | 40 | 16 | 109 | 75 | 25 | 178 | 120 | 28 | 263 | 180 | 42 | 365 | 247 | | | |
| | 5 | 23 | 53 | 38 | 32 | 103 | 71 | 42 | 171 | 115 | 53 | 255 | 173 | 70 | 356 | 237 | | | |
| | 8 | 28 | 49 | 35 | 39 | 98 | 66 | 51 | 164 | 109 | 64 | 247 | 165 | 84 | 347 | 227 | | | |
| 10 | 0 | 0 | 88 | 53 | 0 | 175 | 100 | 0 | 295 | 166 | 0 | 447 | 255 | 0 | 631 | 345 | | | |
| | 2 | 12 | 61 | 42 | 17 | 118 | 81 | 23 | 194 | 129 | 26 | 289 | 195 | 40 | 402 | 273 | | | |
| | 5 | 23 | 57 | 40 | 32 | 113 | 77 | 41 | 187 | 124 | 52 | 280 | 188 | 68 | 392 | 263 | | | |
| | 10 | 30 | 51 | 36 | 41 | 104 | 70 | 54 | 176 | 115 | 67 | 267 | 175 | 88 | 376 | 245 | | | |
| 15 | 0 | 0 | 94 | 58 | 0 | 191 | 112 | 0 | 327 | 187 | 0 | 502 | 285 | 0 | 716 | 390 | | | |
| | 2 | 11 | 69 | 48 | 15 | 136 | 93 | 20 | 226 | 150 | 22 | 339 | 225 | 38 | 475 | 316 | | | |
| | 5 | 22 | 65 | 45 | 30 | 130 | 87 | 39 | 219 | 142 | 49 | 330 | 217 | 64 | 463 | 300 | | | |
| | 10 | 29 | 59 | 41 | 40 | 121 | 82 | 51 | 206 | 135 | 64 | 315 | 208 | 84 | 445 | 288 | | | |
| | 15 | 35 | 53 | 37 | 48 | 112 | 76 | 61 | 195 | 128 | 76 | 301 | 198 | 98 | 429 | 275 | | | |
| 20 | 0 | 0 | 97 | 61 | 0 | 202 | 119 | 0 | 349 | 202 | 0 | 540 | 307 | 0 | 776 | 430 | | | |
| | 2 | 10 | 75 | 51 | 14 | 149 | 100 | 18 | 250 | 166 | 20 | 377 | 249 | 33 | 531 | 346 | | | |
| | 5 | 21 | 71 | 48 | 29 | 143 | 96 | 38 | 242 | 160 | 47 | 367 | 241 | 62 | 519 | 337 | | | |
| | 10 | 28 | 64 | 44 | 38 | 133 | 89 | 50 | 229 | 150 | 62 | 351 | 228 | 81 | 499 | 321 | | | |
| | 15 | 34 | 58 | 40 | 46 | 124 | 84 | 59 | 217 | 142 | 73 | 337 | 217 | 94 | 481 | 308 | | | |
| | 20 | 48 | 52 | 35 | 55 | 116 | 78 | 69 | 206 | 134 | 84 | 322 | 206 | 107 | 464 | 295 | | | |
| 30 | 0 | 0 | 100 | 64 | 0 | 213 | 128 | 0 | 374 | 220 | 0 | 587 | 336 | 0 | 853 | 475 | | | |
| | 2 | 9 | 81 | 56 | 13 | 166 | 112 | 14 | 283 | 185 | 18 | 432 | 280 | 27 | 613 | 394 | | | |
| | 5 | 21 | 77 | 54 | 28 | 160 | 108 | 36 | 275 | 176 | 45 | 421 | 273 | 58 | 600 | 385 | | | |
| | 10 | 27 | 70 | 50 | 37 | 150 | 102 | 48 | 262 | 171 | 59 | 405 | 261 | 77 | 580 | 371 | | | |
| | 15 | 33 | 64 | NA | 44 | 141 | 96 | 57 | 249 | 163 | 70 | 389 | 249 | 90 | 560 | 357 | | | |
| | 20 | 56 | 58 | NA | 53 | 132 | 90 | 66 | 237 | 154 | 80 | 374 | 237 | 102 | 542 | 343 | | | |
| | 30 | NA | NA | NA | 73 | 113 | NA | 88 | 214 | NA | 104 | 346 | 219 | 131 | 507 | 321 | | | |
| 50 | 0 | 0 | 101 | 67 | 0 | 216 | 134 | 0 | 397 | 232 | 0 | 633 | 363 | 0 | 932 | 518 | | | |
| | 2 | 8 | 86 | 61 | 11 | 183 | 122 | 14 | 320 | 206 | 15 | 497 | 314 | 22 | 715 | 445 | | | |
| | 5 | 20 | 82 | NA | 27 | 177 | 119 | 35 | 312 | 200 | 43 | 487 | 308 | 55 | 702 | 438 | | | |
| | 10 | 26 | 76 | NA | 35 | 168 | 114 | 45 | 299 | 190 | 56 | 471 | 298 | 73 | 681 | 426 | | | |
| | 15 | 59 | 70 | NA | 42 | 158 | NA | 54 | 287 | 180 | 66 | 455 | 288 | 85 | 662 | 413 | | | |
| | 20 | NA | NA | NA | 50 | 149 | NA | 63 | 275 | 169 | 76 | 440 | 278 | 97 | 642 | 401 | | | |
| | 30 | NA | NA | NA | 69 | 131 | NA | 84 | 250 | NA | 99 | 410 | 259 | 123 | 605 | 376 | | | |
| 100 | 0 | NA | NA | NA | 0 | 218 | NA | 0 | 407 | NA | 0 | 665 | 400 | 0 | 997 | 560 | | | |
| | 2 | NA | NA | NA | 10 | 194 | NA | 12 | 354 | NA | 13 | 566 | 375 | 18 | 831 | 510 | | | |
| | 5 | NA | NA | NA | 26 | 189 | NA | 33 | 347 | NA | 40 | 557 | 369 | 52 | 820 | 504 | | | |
| | 10 | NA | NA | NA | 33 | 182 | NA | 43 | 335 | NA | 53 | 542 | 361 | 68 | 801 | 493 | | | |
| | 15 | NA | NA | NA | 40 | 174 | NA | 50 | 321 | NA | 62 | 528 | 353 | 80 | 782 | 482 | | | |
| | 20 | NA | NA | NA | 47 | 166 | NA | 59 | 311 | NA | 71 | 513 | 344 | 90 | 763 | 471 | | | |
| | 30 | NA | NA | NA | NA | NA | NA | 78 | 290 | NA | 92 | 483 | NA | 115 | 726 | 449 | | | |
| | 50 | NA | NA | NA | NA | NA | NA | NA | NA | NA | 147 | 428 | NA | 180 | 651 | 405 | | | |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

WATER HEATERS

TABLE 510.1.2(1)
TYPE B DOUBLE-WALL GAS VENT [NFPA 54: TABLE 13.1(a)] (continued)

| | | | | | NUMBER OF APPLIANCES: SINGLE | | | | | | CATEGORY I | | | | | |
|---|------------------------|-----|------|-----|------------------------------|------|------|-----|------|------|----------------------------|------|------|-----|------|------|
| | | | | | APPLIANCE TYPE: | | | | | | CATEGORY I | | | | | |
| | | | | | APPLIANCE VENT CONNECTION: | | | | | | CONNECTED DIRECTLY TO VENT | | | | | |
| | | | | | VENT DIAMETER – D (inch) | | | | | | | | | | | |
| 8 | | | | | 9 | | | 10 | | | 12 | | | 14 | | |
| APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | | | | |
| HEIGHT H (feet) | LATERAL L (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 0 | 0 | 698 | 370 | 0 | 897 | 470 | 0 | 1121 | 570 | 0 | 1645 | 850 | 0 | 2267 | 1170 |
| | 2 | 53 | 425 | 285 | 63 | 543 | 370 | 75 | 675 | 455 | 103 | 982 | 650 | 138 | 1346 | 890 |
| | 4 | 79 | 419 | 279 | 93 | 536 | 362 | 110 | 668 | 445 | 147 | 975 | 640 | 191 | 1338 | 880 |
| | 6 | 93 | 413 | 273 | 110 | 530 | 354 | 128 | 661 | 435 | 171 | 967 | 630 | 219 | 1330 | 870 |
| 8 | 0 | 0 | 780 | 415 | 0 | 1006 | 537 | 0 | 1261 | 660 | 0 | 1858 | 970 | 0 | 2571 | 1320 |
| | 2 | 50 | 483 | 322 | 60 | 619 | 418 | 71 | 770 | 515 | 98 | 1124 | 745 | 130 | 1543 | 1020 |
| | 5 | 83 | 473 | 313 | 99 | 607 | 407 | 115 | 758 | 503 | 154 | 1110 | 733 | 199 | 1528 | 1010 |
| | 8 | 99 | 463 | 303 | 117 | 596 | 396 | 137 | 746 | 490 | 180 | 1097 | 720 | 231 | 1514 | 1000 |
| 10 | 0 | 0 | 847 | 450 | 0 | 1096 | 585 | 0 | 1377 | 720 | 0 | 2036 | 1060 | 0 | 2825 | 1450 |
| | 2 | 48 | 533 | 355 | 57 | 684 | 457 | 68 | 852 | 560 | 93 | 1244 | 850 | 124 | 1713 | 1130 |
| | 5 | 81 | 522 | 346 | 95 | 671 | 446 | 112 | 839 | 547 | 149 | 1229 | 829 | 192 | 1696 | 1105 |
| | 10 | 104 | 504 | 330 | 122 | 651 | 427 | 142 | 817 | 525 | 187 | 1204 | 795 | 238 | 1669 | 1080 |
| 15 | 0 | 0 | 970 | 525 | 0 | 1263 | 682 | 0 | 1596 | 840 | 0 | 2380 | 1240 | 0 | 3323 | 1720 |
| | 2 | 45 | 633 | 414 | 53 | 815 | 544 | 63 | 1019 | 675 | 86 | 1495 | 985 | 114 | 2062 | 1350 |
| | 5 | 76 | 620 | 403 | 90 | 800 | 529 | 105 | 1003 | 660 | 140 | 1476 | 967 | 182 | 2041 | 1327 |
| | 10 | 99 | 600 | 386 | 116 | 777 | 507 | 135 | 977 | 635 | 177 | 1446 | 936 | 227 | 2009 | 1289 |
| | 15 | 115 | 580 | 373 | 134 | 755 | 491 | 155 | 953 | 610 | 202 | 1418 | 905 | 257 | 1976 | 1250 |
| 20 | 0 | 0 | 1057 | 575 | 0 | 1384 | 752 | 0 | 1756 | 930 | 0 | 2637 | 1350 | 0 | 3701 | 1900 |
| | 2 | 41 | 711 | 470 | 50 | 917 | 612 | 59 | 1150 | 755 | 81 | 1694 | 1100 | 107 | 2343 | 1520 |
| | 5 | 73 | 697 | 460 | 86 | 902 | 599 | 101 | 1133 | 738 | 135 | 1674 | 1079 | 174 | 2320 | 1498 |
| | 10 | 95 | 675 | 443 | 112 | 877 | 576 | 130 | 1105 | 710 | 172 | 1641 | 1045 | 220 | 2282 | 1460 |
| | 15 | 111 | 654 | 427 | 129 | 853 | 557 | 150 | 1078 | 688 | 195 | 1609 | 1018 | 248 | 2245 | 1425 |
| | 20 | 125 | 634 | 410 | 145 | 830 | 537 | 167 | 1052 | 665 | 217 | 1578 | 990 | 273 | 2210 | 1390 |
| 30 | 0 | 0 | 1173 | 650 | 0 | 1548 | 855 | 0 | 1977 | 1060 | 0 | 3004 | 1550 | 0 | 4252 | 2170 |
| | 2 | 33 | 826 | 535 | 42 | 1072 | 700 | 54 | 1351 | 865 | 74 | 2004 | 1310 | 98 | 2786 | 1800 |
| | 5 | 69 | 811 | 524 | 82 | 1055 | 688 | 96 | 1332 | 851 | 127 | 1981 | 1289 | 164 | 2759 | 1775 |
| | 10 | 91 | 788 | 507 | 107 | 1028 | 668 | 125 | 1301 | 829 | 164 | 1944 | 1254 | 209 | 2716 | 1733 |
| | 15 | 105 | 765 | 490 | 124 | 1002 | 648 | 143 | 1272 | 807 | 187 | 1908 | 1220 | 237 | 2674 | 1692 |
| | 20 | 119 | 743 | 473 | 139 | 977 | 628 | 160 | 1243 | 784 | 207 | 1873 | 1185 | 260 | 2633 | 1650 |
| | 30 | 149 | 702 | 444 | 171 | 929 | 594 | 195 | 1189 | 745 | 246 | 1807 | 1130 | 305 | 2555 | 1585 |
| 50 | 0 | 0 | 1297 | 708 | 0 | 1730 | 952 | 0 | 2231 | 1195 | 0 | 3441 | 1825 | 0 | 4934 | 2550 |
| | 2 | 26 | 975 | 615 | 33 | 1276 | 813 | 41 | 1620 | 1010 | 66 | 2431 | 1513 | 86 | 3409 | 2125 |
| | 5 | 65 | 960 | 605 | 77 | 1259 | 798 | 90 | 1600 | 996 | 118 | 2406 | 1495 | 151 | 3380 | 2102 |
| | 10 | 86 | 935 | 589 | 101 | 1230 | 773 | 118 | 1567 | 972 | 154 | 2366 | 1466 | 196 | 3332 | 2064 |
| | 15 | 100 | 911 | 572 | 117 | 1203 | 747 | 136 | 1536 | 948 | 177 | 2327 | 1437 | 222 | 3285 | 2026 |
| | 20 | 113 | 888 | 556 | 131 | 1176 | 722 | 151 | 1505 | 924 | 195 | 2288 | 1408 | 244 | 3239 | 1987 |
| | 30 | 141 | 844 | 522 | 161 | 1125 | 670 | 183 | 1446 | 876 | 232 | 2214 | 1349 | 287 | 3150 | 1910 |
| 100 | 0 | 0 | 1411 | 770 | 0 | 1908 | 1040 | 0 | 2491 | 1310 | 0 | 3925 | 2050 | 0 | 5729 | 2950 |
| | 2 | 21 | 1155 | 700 | 25 | 1536 | 935 | 30 | 1975 | 1170 | 44 | 3027 | 1820 | 72 | 4313 | 2550 |
| | 5 | 60 | 1141 | 692 | 71 | 1519 | 926 | 82 | 1955 | 1159 | 107 | 3002 | 1803 | 136 | 4282 | 2531 |
| | 10 | 80 | 1118 | 679 | 94 | 1492 | 910 | 108 | 1923 | 1142 | 142 | 2961 | 1775 | 180 | 4231 | 2500 |
| | 15 | 93 | 1095 | 666 | 109 | 1465 | 895 | 126 | 1892 | 1124 | 163 | 2920 | 1747 | 206 | 4182 | 2469 |
| | 20 | 105 | 1073 | 653 | 122 | 1438 | 880 | 141 | 1861 | 1107 | 181 | 2880 | 1719 | 226 | 4133 | 2438 |
| | 30 | 131 | 1029 | 627 | 149 | 1387 | 849 | 170 | 1802 | 1071 | 215 | 2803 | 1663 | 265 | 4037 | 2375 |
| | 50 | 197 | 944 | 575 | 217 | 1288 | 787 | 241 | 1688 | 1000 | 292 | 2657 | 1550 | 350 | 3856 | 2250 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

TABLE 510.1.2(1)
TYPE B DOUBLE-WALL GAS VENT [NFPA 54: TABLE 13.1(a)] (continued)

| | | NUMBER OF APPLIANCES: | | | | | | | | | SINGLE | | | | | |
|-----------------------|------------------------|---|------|------|-----|--------|------|-----|--------|------|----------------------------|--------|------|-----|--------|--------|
| | | APPLIANCE TYPE: | | | | | | | | | CATEGORY I | | | | | |
| | | APPLIANCE VENT CONNECTION: | | | | | | | | | CONNECTED DIRECTLY TO VENT | | | | | |
| | | VENT DIAMETER – D (Inch) | | | | | | | | | | | | | | |
| | | 16 | | | 18 | | | 20 | | | 22 | | | 24 | | |
| | | APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | | |
| HEIGHT H (feet) | LATERAL L (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 0 | 0 | 2983 | 1530 | 0 | 3802 | 1960 | 0 | 4721 | 2430 | 0 | 5737 | 2950 | 0 | 6853 | 3520 |
| | 2 | 178 | 1769 | 1170 | 225 | 2250 | 1480 | 296 | 2782 | 1850 | 360 | 3377 | 2220 | 426 | 4030 | 2670 |
| | 4 | 242 | 1761 | 1160 | 300 | 2242 | 1475 | 390 | 2774 | 1835 | 469 | 3370 | 2215 | 555 | 4023 | 2660 |
| | 6 | 276 | 1753 | 1150 | 341 | 2235 | 1470 | 437 | 2767 | 1820 | 523 | 3363 | 2210 | 618 | 4017 | 2650 |
| 8 | 0 | 0 | 3399 | 1740 | 0 | 4333 | 2220 | 0 | 5387 | 2750 | 0 | 6555 | 3360 | 0 | 7838 | 4010 |
| | 2 | 168 | 2030 | 1340 | 212 | 2584 | 1700 | 278 | 3196 | 2110 | 336 | 3882 | 2560 | 401 | 4634 | 3050 |
| | 5 | 251 | 2013 | 1330 | 311 | 2563 | 1685 | 398 | 3180 | 2090 | 476 | 3863 | 2545 | 562 | 4612 | 3040 |
| | 8 | 289 | 2000 | 1320 | 354 | 2552 | 1670 | 450 | 3163 | 2070 | 537 | 3850 | 2530 | 630 | 4602 | 3030 |
| 10 | 0 | 0 | 3742 | 1925 | 0 | 4782 | 2450 | 0 | 5955 | 3050 | 0 | 7254 | 3710 | 0 | 8682 | 4450 |
| | 2 | 161 | 2256 | 1480 | 202 | 2868 | 1890 | 264 | 3556 | 2340 | 319 | 4322 | 2840 | 378 | 5153 | 3390 |
| | 5 | 243 | 2238 | 1461 | 300 | 2849 | 1871 | 382 | 3536 | 2318 | 458 | 4301 | 2818 | 540 | 5132 | 3371 |
| | 10 | 298 | 2209 | 1430 | 364 | 2818 | 1840 | 459 | 3504 | 2280 | 546 | 4268 | 2780 | 641 | 5099 | 3340 |
| 15 | 0 | 0 | 4423 | 2270 | 0 | 5678 | 2900 | 0 | 7099 | 3620 | 0 | 8665 | 4410 | 0 | 10 393 | 5300 |
| | 2 | 147 | 2719 | 1770 | 186 | 3467 | 2260 | 239 | 4304 | 2800 | 290 | 5232 | 3410 | 346 | 6251 | 4080 |
| | 5 | 229 | 2696 | 1748 | 283 | 3442 | 2235 | 355 | 4278 | 2777 | 426 | 5204 | 3385 | 501 | 6222 | 4057 |
| | 10 | 283 | 2659 | 1712 | 346 | 3402 | 2193 | 432 | 4234 | 2739 | 510 | 5159 | 3343 | 599 | 6175 | 4019 |
| | 15 | 318 | 2623 | 1675 | 385 | 3363 | 2150 | 479 | 4192 | 2700 | 564 | 5115 | 3300 | 665 | 6129 | 3980 |
| 20 | 0 | 0 | 4948 | 2520 | 0 | 6376 | 3250 | 0 | 7988 | 4060 | 0 | 9785 | 4980 | 0 | 11 753 | 6000 |
| | 2 | 139 | 3097 | 2000 | 175 | 3955 | 2570 | 220 | 4916 | 3200 | 269 | 5983 | 3910 | 321 | 7154 | 4700 |
| | 5 | 219 | 3071 | 1978 | 270 | 3926 | 2544 | 337 | 4885 | 3174 | 403 | 5950 | 3880 | 475 | 7119 | 4662 |
| | 10 | 273 | 3029 | 1940 | 334 | 3880 | 2500 | 413 | 4835 | 3130 | 489 | 5896 | 3830 | 573 | 7063 | 4600 |
| | 15 | 306 | 2988 | 1910 | 372 | 3835 | 2465 | 459 | 4786 | 3090 | 541 | 5844 | 3795 | 631 | 7007 | 4575 |
| | 20 | 335 | 2948 | 1880 | 404 | 3791 | 2430 | 495 | 4737 | 3050 | 585 | 5792 | 3760 | 689 | 6953 | 4550 |
| 30 | 0 | 0 | 5725 | 2920 | 0 | 7420 | 3770 | 0 | 9341 | 4750 | 0 | 11 483 | 5850 | 0 | 13 848 | 7060 |
| | 2 | 127 | 3696 | 2380 | 159 | 4734 | 3050 | 199 | 5900 | 3810 | 241 | 7194 | 4650 | 285 | 8617 | 5600 |
| | 5 | 206 | 3666 | 2350 | 252 | 4701 | 3020 | 312 | 5863 | 3783 | 373 | 7155 | 4622 | 439 | 8574 | 5552 |
| | 10 | 259 | 3617 | 2300 | 316 | 4647 | 2970 | 386 | 5803 | 3739 | 456 | 7090 | 4574 | 535 | 8505 | 5471 |
| | 15 | 292 | 3570 | 2250 | 354 | 4594 | 2920 | 431 | 5744 | 3695 | 507 | 7026 | 4527 | 590 | 8437 | 5391 |
| | 20 | 319 | 3523 | 2200 | 384 | 4542 | 2870 | 467 | 5686 | 3650 | 548 | 6964 | 4480 | 639 | 8370 | 5310 |
| | 30 | 369 | 3433 | 2130 | 440 | 4442 | 2785 | 540 | 5574 | 3565 | 635 | 6842 | 4375 | 739 | 8239 | 5225 |
| 50 | 0 | 0 | 6711 | 3440 | 0 | 8774 | 4460 | 0 | 11 129 | 5635 | 0 | 13 767 | 6940 | 0 | 16 694 | 8430 |
| | 2 | 113 | 4554 | 2840 | 141 | 5864 | 3670 | 171 | 7339 | 4630 | 209 | 8980 | 5695 | 251 | 10 788 | 6860 |
| | 5 | 191 | 4520 | 2813 | 234 | 5826 | 3639 | 283 | 7295 | 4597 | 336 | 8933 | 5654 | 394 | 10 737 | 6818 |
| | 10 | 243 | 4464 | 2767 | 295 | 5763 | 3585 | 355 | 7224 | 4542 | 419 | 8855 | 5585 | 491 | 10 652 | 6749 |
| | 15 | 274 | 4409 | 2721 | 330 | 5701 | 3534 | 396 | 7155 | 4511 | 465 | 8779 | 5546 | 542 | 10 570 | 6710 |
| | 20 | 300 | 4356 | 2675 | 361 | 5641 | 3481 | 433 | 7086 | 4479 | 506 | 8704 | 5506 | 586 | 10 488 | 6670 |
| | 30 | 347 | 4253 | 2631 | 412 | 5523 | 3431 | 494 | 6953 | 4421 | 577 | 8557 | 5444 | 672 | 10 328 | 6603 |
| 100 | 0 | 0 | 7914 | 4050 | 0 | 10 485 | 5300 | 0 | 13 454 | 6700 | 0 | 16 817 | 8600 | 0 | 20 578 | 10 300 |
| | 2 | 95 | 5834 | 3500 | 120 | 7591 | 4600 | 138 | 9577 | 5800 | 169 | 11 803 | 7200 | 204 | 14 264 | 8800 |
| | 5 | 172 | 5797 | 3475 | 208 | 7548 | 4566 | 245 | 9528 | 5769 | 293 | 11 748 | 7162 | 341 | 14 204 | 8756 |
| | 10 | 223 | 5737 | 3434 | 268 | 7478 | 4509 | 318 | 9447 | 5717 | 374 | 11 658 | 7100 | 436 | 14 105 | 8683 |
| | 15 | 252 | 5678 | 3392 | 304 | 7409 | 4451 | 358 | 9367 | 5665 | 418 | 11 569 | 7037 | 487 | 14 007 | 8610 |
| | 20 | 277 | 5619 | 3351 | 330 | 7341 | 4394 | 387 | 9289 | 5613 | 452 | 11 482 | 6975 | 523 | 13 910 | 8537 |
| | 30 | 319 | 5505 | 3267 | 378 | 7209 | 4279 | 446 | 9136 | 5509 | 514 | 11 310 | 6850 | 592 | 13 720 | 8391 |
| | 50 | 415 | 5289 | 3100 | 486 | 6956 | 4050 | 572 | 8841 | 5300 | 659 | 10 979 | 6600 | 752 | 13 354 | 8100 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

WATER HEATERS

TABLE 510.1.2(2)
TYPE B DOUBLE-WALL GAS VENT [NFPA 54: TABLE 13.1(b)]*

| | | | | | NUMBER OF APPLIANCES: SINGLE | | | | | | | | | | | | | | |
|---|------------------------|-----|-----|-----|--|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|---|--|--|
| | | | | | APPLIANCE TYPE: CATEGORY I | | | | | | | | | | | | | | |
| | | | | | APPLIANCE VENT CONNECTION: SINGLE-WALL METAL CONNECTOR | | | | | | | | | | | | | | |
| | | | | | VENT DIAMETER – D (inch) | | | | | | | | | | | | | | |
| | | | | | 3 | | | 4 | | | 5 | | | 6 | | | 7 | | |
| APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | | | | | | | |
| HEIGHT H (feet) | LATERAL L (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | | | |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | | | |
| 6 | 0 | 38 | 77 | 45 | 59 | 151 | 85 | 85 | 249 | 140 | 126 | 373 | 204 | 165 | 522 | 284 | | | |
| | 2 | 39 | 51 | 36 | 60 | 96 | 66 | 85 | 156 | 104 | 123 | 231 | 156 | 159 | 320 | 213 | | | |
| | 4 | NA | NA | 33 | 74 | 92 | 63 | 102 | 152 | 102 | 146 | 225 | 152 | 187 | 313 | 208 | | | |
| | 6 | NA | NA | 31 | 83 | 89 | 60 | 114 | 147 | 99 | 163 | 220 | 148 | 207 | 307 | 203 | | | |
| 8 | 0 | 37 | 83 | 50 | 58 | 164 | 93 | 83 | 273 | 154 | 123 | 412 | 234 | 161 | 580 | 319 | | | |
| | 2 | 39 | 56 | 39 | 59 | 108 | 75 | 83 | 176 | 119 | 121 | 261 | 179 | 155 | 363 | 246 | | | |
| | 5 | NA | NA | 37 | 77 | 102 | 69 | 107 | 168 | 114 | 151 | 252 | 171 | 193 | 352 | 235 | | | |
| | 8 | NA | NA | 33 | 90 | 95 | 64 | 122 | 161 | 107 | 175 | 243 | 163 | 223 | 342 | 225 | | | |
| 10 | 0 | 37 | 87 | 53 | 57 | 174 | 99 | 82 | 293 | 165 | 120 | 444 | 254 | 158 | 628 | 344 | | | |
| | 2 | 39 | 61 | 41 | 59 | 117 | 80 | 82 | 193 | 128 | 119 | 287 | 194 | 153 | 400 | 272 | | | |
| | 5 | 52 | 56 | 39 | 76 | 111 | 76 | 105 | 185 | 122 | 148 | 277 | 186 | 190 | 388 | 261 | | | |
| | 10 | NA | NA | 34 | 97 | 100 | 68 | 132 | 171 | 112 | 188 | 261 | 171 | 237 | 369 | 241 | | | |
| 15 | 0 | 36 | 93 | 57 | 56 | 190 | 111 | 80 | 325 | 186 | 116 | 499 | 283 | 153 | 713 | 388 | | | |
| | 2 | 38 | 69 | 47 | 57 | 136 | 93 | 80 | 225 | 149 | 115 | 337 | 224 | 148 | 473 | 314 | | | |
| | 5 | 51 | 63 | 44 | 75 | 128 | 86 | 102 | 216 | 140 | 144 | 326 | 217 | 182 | 459 | 298 | | | |
| | 10 | NA | NA | 39 | 95 | 116 | 79 | 128 | 201 | 131 | 182 | 308 | 203 | 228 | 438 | 284 | | | |
| | 15 | NA | NA | NA | NA | NA | 72 | 158 | 186 | 124 | 220 | 290 | 192 | 272 | 418 | 269 | | | |
| 20 | 0 | 35 | 96 | 60 | 54 | 200 | 118 | 78 | 346 | 201 | 114 | 537 | 306 | 149 | 772 | 428 | | | |
| | 2 | 37 | 74 | 50 | 56 | 148 | 99 | 78 | 248 | 165 | 113 | 375 | 248 | 144 | 528 | 344 | | | |
| | 5 | 50 | 68 | 47 | 73 | 140 | 94 | 100 | 239 | 158 | 141 | 363 | 239 | 178 | 514 | 334 | | | |
| | 10 | NA | NA | 41 | 93 | 129 | 86 | 125 | 223 | 146 | 177 | 344 | 224 | 222 | 491 | 316 | | | |
| | 15 | NA | NA | NA | NA | NA | 80 | 155 | 208 | 136 | 216 | 325 | 210 | 264 | 469 | 301 | | | |
| | 20 | NA | NA | NA | NA | NA | NA | 186 | 192 | 126 | 254 | 306 | 196 | 309 | 448 | 285 | | | |
| 30 | 0 | 34 | 99 | 63 | 53 | 211 | 127 | 76 | 372 | 219 | 110 | 584 | 334 | 144 | 849 | 472 | | | |
| | 2 | 37 | 80 | 56 | 55 | 164 | 111 | 76 | 281 | 183 | 109 | 429 | 279 | 139 | 610 | 392 | | | |
| | 5 | 49 | 74 | 52 | 72 | 157 | 106 | 98 | 271 | 173 | 136 | 417 | 271 | 171 | 595 | 382 | | | |
| | 10 | NA | NA | NA | 91 | 144 | 98 | 122 | 255 | 168 | 171 | 397 | 257 | 213 | 570 | 367 | | | |
| | 15 | NA | NA | NA | 115 | 131 | NA | 151 | 239 | 157 | 208 | 377 | 242 | 255 | 547 | 349 | | | |
| | 20 | NA | NA | NA | NA | NA | NA | 181 | 223 | NA | 246 | 357 | 228 | 298 | 524 | 333 | | | |
| | 30 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | 389 | 477 | 305 | | | |
| 50 | 0 | 33 | 99 | 66 | 51 | 213 | 133 | 73 | 394 | 230 | 105 | 629 | 361 | 138 | 928 | 515 | | | |
| | 2 | 36 | 84 | 61 | 53 | 181 | 121 | 73 | 318 | 205 | 104 | 495 | 312 | 133 | 712 | 443 | | | |
| | 5 | 48 | 80 | NA | 70 | 174 | 117 | 94 | 308 | 198 | 131 | 482 | 305 | 164 | 696 | 435 | | | |
| | 10 | NA | NA | NA | 89 | 160 | NA | 118 | 292 | 186 | 162 | 461 | 292 | 203 | 671 | 420 | | | |
| | 15 | NA | NA | NA | 112 | 148 | NA | 145 | 275 | 174 | 199 | 441 | 280 | 244 | 646 | 405 | | | |
| | 20 | NA | NA | NA | NA | NA | NA | 176 | 257 | NA | 236 | 420 | 267 | 285 | 622 | 389 | | | |
| | 30 | NA | NA | NA | NA | NA | NA | NA | NA | NA | 315 | 376 | NA | 373 | 573 | NA | | | |
| 100 | 0 | NA | NA | NA | 49 | 214 | NA | 69 | 403 | NA | 100 | 659 | 395 | 131 | 991 | 555 | | | |
| | 2 | NA | NA | NA | 51 | 192 | NA | 70 | 351 | NA | 98 | 563 | 373 | 125 | 828 | 508 | | | |
| | 5 | NA | NA | NA | 67 | 186 | NA | 90 | 342 | NA | 125 | 551 | 366 | 156 | 813 | 501 | | | |
| | 10 | NA | NA | NA | 85 | 175 | NA | 113 | 324 | NA | 153 | 532 | 354 | 191 | 789 | 486 | | | |
| | 15 | NA | NA | NA | 132 | 162 | NA | 138 | 310 | NA | 188 | 511 | 343 | 230 | 764 | 473 | | | |
| | 20 | NA | NA | NA | NA | NA | NA | 168 | 295 | NA | 224 | 487 | NA | 270 | 739 | 458 | | | |
| | 30 | NA | NA | NA | NA | NA | NA | 231 | 264 | NA | 301 | 448 | NA | 355 | 685 | NA | | | |
| | 50 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | 540 | 584 | NA | | | |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

TABLE 510.1.2(2)

TYPE B DOUBLE-WALL GAS VENT [NFPA 54: TABLE 13.1(b)] (continued)*

| | | NUMBER OF APPLIANCES: SINGLE | | | | | | | | | | | |
|-----------------------|------------------------|--|------|-----|-----|------|------|-----|------|------|------|------|------|
| | | APPLIANCE TYPE: CATEGORY I | | | | | | | | | | | |
| | | APPLIANCE VENT CONNECTION: SINGLE-WALL METAL CONNECTOR | | | | | | | | | | | |
| | | VENT DIAMETER – D (Inch) | | | | | | | | | | | |
| | | 8 | | | 9 | | | 10 | | | 12 | | |
| | | APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | |
| HEIGHT H (feet) | LATERAL L (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 0 | 211 | 695 | 369 | 267 | 894 | 469 | 371 | 1118 | 569 | 537 | 1639 | 849 |
| | 2 | 201 | 423 | 284 | 251 | 541 | 368 | 347 | 673 | 453 | 498 | 979 | 648 |
| | 4 | 237 | 416 | 277 | 295 | 533 | 360 | 409 | 664 | 443 | 584 | 971 | 638 |
| | 6 | 263 | 409 | 271 | 327 | 526 | 352 | 449 | 656 | 433 | 638 | 962 | 627 |
| 8 | 0 | 206 | 777 | 414 | 258 | 1002 | 536 | 360 | 1257 | 658 | 521 | 1852 | 967 |
| | 2 | 197 | 482 | 321 | 246 | 617 | 417 | 339 | 768 | 513 | 486 | 1120 | 743 |
| | 5 | 245 | 470 | 311 | 305 | 604 | 404 | 418 | 754 | 500 | 598 | 1104 | 730 |
| | 8 | 280 | 458 | 300 | 344 | 591 | 392 | 470 | 740 | 486 | 665 | 1089 | 715 |
| 10 | 0 | 202 | 844 | 449 | 253 | 1093 | 584 | 351 | 1373 | 718 | 507 | 2031 | 1057 |
| | 2 | 193 | 531 | 354 | 242 | 681 | 456 | 332 | 849 | 559 | 475 | 1242 | 848 |
| | 5 | 241 | 518 | 344 | 299 | 667 | 443 | 409 | 834 | 544 | 584 | 1224 | 825 |
| | 10 | 296 | 497 | 325 | 363 | 643 | 423 | 492 | 808 | 520 | 688 | 1194 | 788 |
| 15 | 0 | 195 | 966 | 523 | 244 | 1259 | 681 | 336 | 1591 | 838 | 488 | 2374 | 1237 |
| | 2 | 187 | 631 | 413 | 232 | 812 | 543 | 319 | 1015 | 673 | 457 | 1491 | 983 |
| | 5 | 231 | 616 | 400 | 287 | 795 | 526 | 392 | 997 | 657 | 562 | 1469 | 963 |
| | 10 | 284 | 592 | 381 | 349 | 768 | 501 | 470 | 966 | 628 | 664 | 1433 | 928 |
| | 15 | 334 | 568 | 367 | 404 | 742 | 484 | 540 | 937 | 601 | 750 | 1399 | 894 |
| 20 | 0 | 190 | 1053 | 573 | 238 | 1379 | 750 | 326 | 1751 | 927 | 473 | 2631 | 1346 |
| | 2 | 182 | 708 | 468 | 227 | 914 | 611 | 309 | 1146 | 754 | 443 | 1689 | 1098 |
| | 5 | 224 | 692 | 457 | 279 | 896 | 596 | 381 | 1126 | 734 | 547 | 1665 | 1074 |
| | 10 | 277 | 666 | 437 | 339 | 866 | 570 | 457 | 1092 | 702 | 646 | 1626 | 1037 |
| | 15 | 325 | 640 | 419 | 393 | 838 | 549 | 526 | 1060 | 677 | 730 | 1587 | 1005 |
| | 20 | 374 | 616 | 400 | 448 | 810 | 526 | 592 | 1028 | 651 | 808 | 1550 | 973 |
| 30 | 0 | 184 | 1168 | 647 | 229 | 1542 | 852 | 312 | 1971 | 1056 | 454 | 2996 | 1545 |
| | 2 | 175 | 823 | 533 | 219 | 1069 | 698 | 296 | 1346 | 863 | 424 | 1999 | 1308 |
| | 5 | 215 | 806 | 521 | 269 | 1049 | 684 | 366 | 1324 | 846 | 524 | 1971 | 1283 |
| | 10 | 265 | 777 | 501 | 327 | 1017 | 662 | 440 | 1287 | 821 | 620 | 1927 | 1243 |
| | 15 | 312 | 750 | 481 | 379 | 985 | 638 | 507 | 1251 | 794 | 702 | 1884 | 1205 |
| | 20 | 360 | 723 | 461 | 433 | 955 | 615 | 570 | 1216 | 768 | 780 | 1841 | 1166 |
| | 30 | 461 | 670 | 426 | 541 | 895 | 574 | 704 | 1147 | 720 | 937 | 1759 | 1101 |
| 50 | 0 | 176 | 1292 | 704 | 220 | 1724 | 948 | 295 | 2223 | 1189 | 428 | 3432 | 1818 |
| | 2 | 168 | 971 | 613 | 209 | 1273 | 811 | 280 | 1615 | 1007 | 401 | 2426 | 1509 |
| | 5 | 204 | 953 | 602 | 257 | 1252 | 795 | 347 | 1591 | 991 | 496 | 2396 | 1490 |
| | 10 | 253 | 923 | 583 | 313 | 1217 | 765 | 418 | 1551 | 963 | 589 | 2347 | 1455 |
| | 15 | 299 | 894 | 562 | 363 | 1183 | 736 | 481 | 1512 | 934 | 668 | 2299 | 1421 |
| | 20 | 345 | 866 | 543 | 415 | 1150 | 708 | 544 | 1473 | 906 | 741 | 2251 | 1387 |
| | 30 | 442 | 809 | 502 | 521 | 1086 | 649 | 674 | 1399 | 848 | 892 | 2159 | 1318 |
| 100 | 0 | 166 | 1404 | 765 | 207 | 1900 | 1033 | 273 | 2479 | 1300 | 395 | 3912 | 2042 |
| | 2 | 158 | 1152 | 698 | 196 | 1532 | 933 | 259 | 1970 | 1168 | 371 | 3021 | 1817 |
| | 5 | 194 | 1134 | 688 | 240 | 1511 | 921 | 322 | 1945 | 1153 | 460 | 2990 | 1796 |
| | 10 | 238 | 1104 | 672 | 293 | 1477 | 902 | 389 | 1905 | 1133 | 547 | 2938 | 1763 |
| | 15 | 281 | 1075 | 656 | 342 | 1443 | 884 | 447 | 1865 | 1110 | 618 | 2888 | 1730 |
| | 20 | 325 | 1046 | 639 | 391 | 1410 | 864 | 507 | 1825 | 1087 | 690 | 2838 | 1696 |
| | 30 | 418 | 988 | NA | 491 | 1343 | 824 | 631 | 1747 | 1041 | 834 | 2739 | 1627 |
| | 50 | 617 | 866 | NA | 711 | 1205 | NA | 895 | 1591 | NA | 1138 | 2547 | 1489 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

WATER HEATERS

TABLE 510.1.2(3)
MASONRY CHIMNEY [NFPA 54: TABLE 13.1(c)]*

| | | NUMBER OF APPLIANCES: SINGLE | | | | | | | | | | | | | | |
|--|------------------------|--|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| | | APPLIANCE TYPE: CATEGORY I | | | | | | | | | | | | | | |
| | | APPLIANCE VENT CONNECTION: TYPE B DOUBLE-WALL CONNECTOR | | | | | | | | | | | | | | |
| | | TYPE B DOUBLE-WALL CONNECTOR DIAMETER – D (inch) TO BE USED WITH CHIMNEY AREAS WITHIN THE SIZE LIMITS AT BOTTOM | | | | | | | | | | | | | | |
| | | 3 | | | 4 | | | 5 | | | 6 | | | 7 | | |
| | | APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | | |
| HEIGHT H (feet) | LATERAL L (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 2 | NA | NA | 28 | NA | NA | 52 | NA | NA | 86 | NA | NA | 130 | NA | NA | 180 |
| | 5 | NA | NA | 25 | NA | NA | 49 | NA | NA | 82 | NA | NA | 117 | NA | NA | 165 |
| 8 | 2 | NA | NA | 29 | NA | NA | 55 | NA | NA | 93 | NA | NA | 145 | NA | NA | 198 |
| | 5 | NA | NA | 26 | NA | NA | 52 | NA | NA | 88 | NA | NA | 134 | NA | NA | 183 |
| | 8 | NA | NA | 24 | NA | NA | 48 | NA | NA | 83 | NA | NA | 127 | NA | NA | 175 |
| 10 | 2 | NA | NA | 31 | NA | NA | 61 | NA | NA | 103 | NA | NA | 162 | NA | NA | 221 |
| | 5 | NA | NA | 28 | NA | NA | 57 | NA | NA | 96 | NA | NA | 148 | NA | NA | 204 |
| | 10 | NA | NA | 25 | NA | NA | 50 | NA | NA | 87 | NA | NA | 139 | NA | NA | 191 |
| 15 | 2 | NA | NA | 35 | NA | NA | 67 | NA | NA | 114 | NA | NA | 179 | 53 | 475 | 250 |
| | 5 | NA | NA | 35 | NA | NA | 62 | NA | NA | 107 | NA | NA | 164 | NA | NA | 231 |
| | 10 | NA | NA | 28 | NA | NA | 55 | NA | NA | 97 | NA | NA | 153 | NA | NA | 216 |
| | 15 | NA | NA | NA | NA | NA | 48 | NA | NA | 89 | NA | NA | 141 | NA | NA | 201 |
| 20 | 2 | NA | NA | 38 | NA | NA | 74 | NA | NA | 124 | NA | NA | 201 | 51 | 522 | 274 |
| | 5 | NA | NA | 36 | NA | NA | 68 | NA | NA | 116 | NA | NA | 184 | 80 | 503 | 254 |
| | 10 | NA | NA | NA | NA | NA | 60 | NA | NA | 107 | NA | NA | 172 | NA | NA | 237 |
| | 15 | NA | NA | NA | NA | NA | NA | NA | NA | 97 | NA | NA | 159 | NA | NA | 220 |
| | 20 | NA | NA | NA | NA | NA | NA | NA | NA | 83 | NA | NA | 148 | NA | NA | 206 |
| 30 | 2 | NA | NA | 41 | NA | NA | 82 | NA | NA | 137 | NA | NA | 216 | 47 | 581 | 303 |
| | 5 | NA | NA | NA | NA | NA | 76 | NA | NA | 128 | NA | NA | 198 | 75 | 561 | 281 |
| | 10 | NA | NA | NA | NA | NA | 67 | NA | NA | 115 | NA | NA | 184 | NA | NA | 263 |
| | 15 | NA | NA | NA | NA | NA | NA | NA | NA | 107 | NA | NA | 171 | NA | NA | 243 |
| | 20 | NA | NA | NA | NA | NA | NA | NA | NA | 91 | NA | NA | 159 | NA | NA | 227 |
| 50 | 30 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | 188 |
| | 2 | NA | NA | NA | NA | NA | 92 | NA | NA | 161 | NA | NA | 251 | NA | NA | 351 |
| | 5 | NA | NA | NA | NA | NA | NA | NA | NA | 151 | NA | NA | 230 | NA | NA | 323 |
| | 10 | NA | NA | NA | NA | NA | NA | NA | NA | 138 | NA | NA | 215 | NA | NA | 304 |
| | 15 | NA | NA | NA | NA | NA | NA | NA | NA | 127 | NA | NA | 199 | NA | NA | 282 |
| | 20 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | 185 | NA | NA | 264 |
| | 30 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| Minimum internal area of chimney (square inches) | | 12 | | | 19 | | | 28 | | | 38 | | | 50 | | |
| Maximum internal area of chimney (square inches) | | Seven times the listed appliance categorized vent area, flue collar area, or draft hood outlet areas. | | | | | | | | | | | | | | |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

TABLE 510.1.2(3)
MASONRY CHIMNEY [NFPA 54: TABLE 13.1(c)] (continued)*

| | | NUMBER OF APPLIANCES: SINGLE | | | | | | | | | | | |
|--|------------------------|--|-----|-----|-----|------|-----|-----|------|-----|-----|------|------|
| | | APPLIANCE TYPE: CATEGORY I | | | | | | | | | | | |
| | | APPLIANCE VENT CONNECTION: TYPE B DOUBLE-WALL CONNECTOR | | | | | | | | | | | |
| | | TYPE B DOUBLE-WALL CONNECTOR DIAMETER – D (inch) TO BE USED WITH CHIMNEY AREAS WITHIN THE SIZE LIMITS AT BOTTOM | | | | | | | | | | | |
| | | 8 | | | 9 | | | 10 | | | 12 | | |
| | | APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | |
| HEIGHT H (feet) | LATERAL L (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 2 | NA | NA | 247 | NA | NA | 320 | NA | NA | 401 | NA | NA | 581 |
| | 5 | NA | NA | 231 | NA | NA | 298 | NA | NA | 376 | NA | NA | 561 |
| 8 | 2 | NA | NA | 266 | 84 | 590 | 350 | 100 | 728 | 446 | 139 | 1024 | 651 |
| | 5 | NA | NA | 247 | NA | NA | 328 | 149 | 711 | 423 | 201 | 1007 | 640 |
| | 8 | NA | NA | 239 | NA | NA | 318 | 173 | 695 | 410 | 231 | 990 | 623 |
| 10 | 2 | 68 | 519 | 298 | 82 | 655 | 388 | 98 | 810 | 491 | 136 | 1144 | 724 |
| | 5 | NA | NA | 277 | 124 | 638 | 365 | 146 | 791 | 466 | 196 | 1124 | 712 |
| | 10 | NA | NA | 263 | 155 | 610 | 347 | 182 | 762 | 444 | 240 | 1093 | 668 |
| 15 | 2 | 64 | 613 | 336 | 77 | 779 | 441 | 92 | 968 | 562 | 127 | 1376 | 841 |
| | 5 | 99 | 594 | 313 | 118 | 759 | 416 | 139 | 946 | 533 | 186 | 1352 | 828 |
| | 10 | 126 | 565 | 296 | 148 | 727 | 394 | 173 | 912 | 567 | 229 | 1315 | 777 |
| | 15 | NA | NA | 281 | 171 | 698 | 375 | 198 | 880 | 485 | 259 | 1280 | 742 |
| 20 | 2 | 61 | 678 | 375 | 73 | 867 | 491 | 87 | 1083 | 627 | 121 | 1548 | 953 |
| | 5 | 95 | 658 | 350 | 113 | 845 | 463 | 133 | 1059 | 597 | 179 | 1523 | 933 |
| | 10 | 122 | 627 | 332 | 143 | 811 | 440 | 167 | 1022 | 566 | 221 | 1482 | 879 |
| | 15 | NA | NA | 314 | 165 | 780 | 418 | 191 | 987 | 541 | 251 | 1443 | 840 |
| | 20 | NA | NA | 296 | 186 | 750 | 397 | 214 | 955 | 513 | 277 | 1406 | 807 |
| 30 | 2 | 57 | 762 | 421 | 68 | 985 | 558 | 81 | 1240 | 717 | 111 | 1793 | 1112 |
| | 5 | 90 | 741 | 393 | 106 | 962 | 526 | 125 | 1216 | 683 | 169 | 1766 | 1094 |
| | 10 | 115 | 709 | 373 | 135 | 927 | 500 | 158 | 1176 | 648 | 210 | 1721 | 1025 |
| | 15 | NA | NA | 353 | 156 | 893 | 476 | 181 | 1139 | 621 | 239 | 1679 | 981 |
| | 20 | NA | NA | 332 | 176 | 860 | 450 | 203 | 1103 | 592 | 264 | 1638 | 940 |
| | 30 | NA | NA | 288 | NA | NA | 416 | 249 | 1035 | 555 | 318 | 1560 | 877 |
| 50 | 2 | 51 | 840 | 477 | 61 | 1106 | 633 | 72 | 1413 | 812 | 99 | 2080 | 1243 |
| | 5 | 83 | 819 | 445 | 98 | 1083 | 596 | 116 | 1387 | 774 | 155 | 2052 | 1225 |
| | 10 | NA | NA | 424 | 126 | 1047 | 567 | 147 | 1347 | 733 | 195 | 2006 | 1147 |
| | 15 | NA | NA | 400 | 146 | 1010 | 539 | 170 | 1307 | 702 | 222 | 1961 | 1099 |
| | 20 | NA | NA | 376 | 165 | 977 | 511 | 190 | 1269 | 669 | 246 | 1916 | 1050 |
| | 30 | NA | NA | 327 | NA | NA | 468 | 233 | 1196 | 623 | 295 | 1832 | 984 |
| Minimum internal area of chimney (square inches) | | 63 | | | 78 | | | 95 | | | 132 | | |
| Maximum internal area of chimney (square inches) | | Seven times the listed appliance categorized vent area, flue collar area, or draft hood outlet areas. | | | | | | | | | | | |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

WATER HEATERS

TABLE 510.1.2(4)
MASONRY CHIMNEY [NFPA 54: TABLE 13.1(d)]*

| | | NUMBER OF APPLIANCES: SINGLE | | | | | | | | | | | | | | |
|--|-------------------------------|--|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| | | APPLIANCE TYPE: CATEGORY I | | | | | | | | | | | | | | |
| | | APPLIANCE VENT CONNECTION: SINGLE-WALL METAL CONNECTOR | | | | | | | | | | | | | | |
| | | SINGLE-WALL METAL CONNECTOR DIAMETER – <i>D</i> (inch) TO BE USED WITH CHIMNEY AREAS WITHIN THE SIZE LIMITS AT BOTTOM | | | | | | | | | | | | | | |
| | | 3 | | | 4 | | | 5 | | | 6 | | | 7 | | |
| | | APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | | |
| HEIGHT <i>H</i> (feet) | LATERAL <i>L</i> (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 2 | NA | NA | 28 | NA | NA | 52 | NA | NA | 86 | NA | NA | 130 | NA | NA | 180 |
| | 5 | NA | NA | 25 | NA | NA | 48 | NA | NA | 81 | NA | NA | 116 | NA | NA | 164 |
| 8 | 2 | NA | NA | 29 | NA | NA | 55 | NA | NA | 93 | NA | NA | 145 | NA | NA | 197 |
| | 5 | NA | NA | 26 | NA | NA | 51 | NA | NA | 87 | NA | NA | 133 | NA | NA | 182 |
| | 8 | NA | NA | 23 | NA | NA | 47 | NA | NA | 82 | NA | NA | 126 | NA | NA | 174 |
| 10 | 2 | NA | NA | 31 | NA | NA | 61 | NA | NA | 102 | NA | NA | 161 | NA | NA | 220 |
| | 5 | NA | NA | 28 | NA | NA | 56 | NA | NA | 95 | NA | NA | 147 | NA | NA | 203 |
| | 10 | NA | NA | 24 | NA | NA | 49 | NA | NA | 86 | NA | NA | 137 | NA | NA | 189 |
| 15 | 2 | NA | NA | 35 | NA | NA | 67 | NA | NA | 113 | NA | NA | 178 | 166 | 473 | 249 |
| | 5 | NA | NA | 32 | NA | NA | 61 | NA | NA | 106 | NA | NA | 163 | NA | NA | 230 |
| | 10 | NA | NA | 27 | NA | NA | 54 | NA | NA | 96 | NA | NA | 151 | NA | NA | 214 |
| | 15 | NA | NA | NA | NA | NA | 46 | NA | NA | 87 | NA | NA | 138 | NA | NA | 198 |
| 20 | 2 | NA | NA | 38 | NA | NA | 73 | NA | NA | 123 | NA | NA | 200 | 163 | 520 | 273 |
| | 5 | NA | NA | 35 | NA | NA | 67 | NA | NA | 115 | NA | NA | 183 | NA | NA | 252 |
| | 10 | NA | NA | NA | NA | NA | 59 | NA | NA | 105 | NA | NA | 170 | NA | NA | 235 |
| | 15 | NA | NA | NA | NA | NA | NA | NA | NA | 95 | NA | NA | 156 | NA | NA | 217 |
| | 20 | NA | NA | NA | NA | NA | NA | NA | NA | 80 | NA | NA | 144 | NA | NA | 202 |
| 30 | 2 | NA | NA | 41 | NA | NA | 81 | NA | NA | 136 | NA | NA | 215 | 158 | 578 | 302 |
| | 5 | NA | NA | NA | NA | NA | 75 | NA | NA | 127 | NA | NA | 196 | NA | NA | 279 |
| | 10 | NA | NA | NA | NA | NA | 66 | NA | NA | 113 | NA | NA | 182 | NA | NA | 260 |
| | 15 | NA | NA | NA | NA | NA | NA | NA | NA | 105 | NA | NA | 168 | NA | NA | 240 |
| | 20 | NA | NA | NA | NA | NA | NA | NA | NA | 88 | NA | NA | 155 | NA | NA | 223 |
| | 30 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | 182 |
| 50 | 2 | NA | NA | NA | NA | NA | 91 | NA | NA | 160 | NA | NA | 250 | NA | NA | 350 |
| | 5 | NA | NA | NA | NA | NA | NA | NA | NA | 149 | NA | NA | 228 | NA | NA | 321 |
| | 10 | NA | NA | NA | NA | NA | NA | NA | NA | 136 | NA | NA | 212 | NA | NA | 301 |
| | 15 | NA | NA | NA | NA | NA | NA | NA | NA | 124 | NA | NA | 195 | NA | NA | 278 |
| | 20 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | 180 | NA | NA | 258 |
| | 30 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| Minimum internal area of chimney (square inches) | | 12 | | | 19 | | | 28 | | | 38 | | | 50 | | |
| Maximum internal area of chimney (square inches) | | Seven times the listed appliance categorized vent area, flue collar area, or draft hood outlet areas. | | | | | | | | | | | | | | |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

TABLE 510.1.2(4)
MASONRY CHIMNEY [NFPA 54: TABLE 13.1(d)] (continued)*

| | | NUMBER OF APPLIANCES: SINGLE | | | | | | | | | | | |
|---|------------------------|---|-----|-----|-----|------|-----|-----|------|-----|------|------|------|
| | | APPLIANCE TYPE: CATEGORY I | | | | | | | | | | | |
| | | APPLIANCE VENT CONNECTION: SINGLE-WALL METAL CONNECTOR | | | | | | | | | | | |
| | | SINGLE-WALL METAL CONNECTOR DIAMETER – D (inch) TO BE USED WITH CHIMNEY AREAS WITHIN THE SIZE LIMITS AT BOTTOM | | | | | | | | | | | |
| | | 8 | | | 9 | | | 10 | | | 12 | | |
| | | APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | |
| HEIGHT H (feet) | LATERAL L (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 2 | NA | NA | 247 | NA | NA | 319 | NA | NA | 400 | NA | NA | 580 |
| | 5 | NA | NA | 230 | NA | NA | 297 | NA | NA | 375 | NA | NA | 560 |
| 8 | 2 | NA | NA | 265 | NA | NA | 349 | 382 | 725 | 445 | 549 | 1021 | 650 |
| | 5 | NA | NA | 246 | NA | NA | 327 | NA | NA | 422 | 673 | 1003 | 638 |
| | 8 | NA | NA | 237 | NA | NA | 317 | NA | NA | 408 | 747 | 985 | 621 |
| 10 | 2 | 216 | 518 | 297 | 271 | 654 | 387 | 373 | 808 | 490 | 536 | 1142 | 722 |
| | 5 | NA | NA | 276 | 334 | 635 | 364 | 459 | 789 | 465 | 657 | 1121 | 710 |
| | 10 | NA | NA | 261 | NA | NA | 345 | 547 | 758 | 441 | 771 | 1088 | 665 |
| 15 | 2 | 211 | 611 | 335 | 264 | 776 | 440 | 362 | 965 | 560 | 520 | 1373 | 840 |
| | 5 | 261 | 591 | 312 | 325 | 755 | 414 | 444 | 942 | 531 | 637 | 1348 | 825 |
| | 10 | NA | NA | 294 | 392 | 722 | 392 | 531 | 907 | 504 | 749 | 1309 | 774 |
| | 15 | NA | NA | 278 | 452 | 692 | 372 | 606 | 873 | 481 | 841 | 1272 | 738 |
| 20 | 2 | 206 | 675 | 374 | 258 | 864 | 490 | 252 | 1079 | 625 | 508 | 1544 | 950 |
| | 5 | 255 | 655 | 348 | 317 | 842 | 461 | 433 | 1055 | 594 | 623 | 1518 | 930 |
| | 10 | 312 | 622 | 330 | 382 | 806 | 437 | 517 | 1016 | 562 | 733 | 1475 | 875 |
| | 15 | NA | NA | 311 | 442 | 773 | 414 | 591 | 979 | 539 | 823 | 1434 | 835 |
| | 20 | NA | NA | 292 | NA | NA | 392 | 663 | 944 | 510 | 911 | 1394 | 800 |
| 30 | 2 | 200 | 759 | 420 | 249 | 982 | 556 | 340 | 1237 | 715 | 489 | 1789 | 1110 |
| | 5 | 245 | 737 | 391 | 306 | 958 | 524 | 417 | 1210 | 680 | 600 | 1760 | 1090 |
| | 10 | 300 | 703 | 370 | 370 | 920 | 496 | 500 | 1168 | 644 | 708 | 1713 | 1020 |
| | 15 | NA | NA | 349 | 428 | 884 | 471 | 572 | 1128 | 615 | 798 | 1668 | 975 |
| | 20 | NA | NA | 327 | NA | NA | 445 | 643 | 1089 | 585 | 883 | 1624 | 932 |
| | 30 | NA | NA | 281 | NA | NA | 408 | NA | NA | 544 | 1055 | 1539 | 865 |
| 50 | 2 | 191 | 837 | 475 | 238 | 1103 | 631 | 323 | 1408 | 810 | 463 | 2076 | 1240 |
| | 5 | NA | NA | 442 | 293 | 1078 | 593 | 398 | 1381 | 770 | 571 | 2044 | 1220 |
| | 10 | NA | NA | 420 | 355 | 1038 | 562 | 447 | 1337 | 728 | 674 | 1994 | 1140 |
| | 15 | NA | NA | 395 | NA | NA | 533 | 546 | 1294 | 695 | 761 | 1945 | 1090 |
| | 20 | NA | NA | 370 | NA | NA | 504 | 616 | 1251 | 660 | 844 | 1898 | 1040 |
| | 30 | NA | NA | 318 | NA | NA | 458 | NA | NA | 610 | 1009 | 1805 | 970 |
| Minimum internal area of chimney (square inches) | | 63 | | | 78 | | | 95 | | | 132 | | |
| Maximum internal area of chimney (square inches) | | Seven times the listed appliance categorized vent area, flue collar area, or draft hood outlet areas. | | | | | | | | | | | |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

WATER HEATERS

TABLE 510.1.2(5)
SINGLE-WALL METAL PIPE OR TYPE B ASBESTOS-CEMENT VENT [NFPA 54: TABLE 13.1(e)]*

| | | NUMBER OF APPLIANCES: SINGLE | | | | | | | |
|-----------------------|------------------------|--|-----|-----|-----|-----|-----|-----|------|
| | | APPLIANCE TYPE: DRAFT HOOD-EQUIPPED | | | | | | | |
| | | APPLIANCE VENT CONNECTION: CONNECTED DIRECTLY TO PIPE OR VENT | | | | | | | |
| | | DIAMETER – D (inch) | | | | | | | |
| | | TO BE USED WITH CHIMNEY AREAS WITHIN THE SIZE LIMITS AT BOTTOM | | | | | | | |
| | | 3 | 4 | 5 | 6 | 7 | 8 | 10 | 12 |
| HEIGHT H (feet) | LATERAL L (feet) | APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | |
| | | MAXIMUM APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | |
| 6 | 0 | 39 | 70 | 116 | 170 | 232 | 312 | 500 | 750 |
| | 2 | 31 | 55 | 94 | 141 | 194 | 260 | 415 | 620 |
| | 5 | 28 | 51 | 88 | 128 | 177 | 242 | 390 | 600 |
| 8 | 0 | 42 | 76 | 126 | 185 | 252 | 340 | 542 | 815 |
| | 2 | 32 | 61 | 102 | 154 | 210 | 284 | 451 | 680 |
| | 5 | 29 | 56 | 95 | 141 | 194 | 264 | 430 | 648 |
| | 10 | 24 | 49 | 86 | 131 | 180 | 250 | 406 | 625 |
| 10 | 0 | 45 | 84 | 138 | 202 | 279 | 372 | 606 | 912 |
| | 2 | 35 | 67 | 111 | 168 | 233 | 311 | 505 | 760 |
| | 5 | 32 | 61 | 104 | 153 | 215 | 289 | 480 | 724 |
| | 10 | 27 | 54 | 94 | 143 | 200 | 274 | 455 | 700 |
| | 15 | NA | 46 | 84 | 130 | 186 | 258 | 432 | 666 |
| 15 | 0 | 49 | 91 | 151 | 223 | 312 | 420 | 684 | 1040 |
| | 2 | 39 | 72 | 122 | 186 | 260 | 350 | 570 | 865 |
| | 5 | 35 | 67 | 110 | 170 | 240 | 325 | 540 | 825 |
| | 10 | 30 | 58 | 103 | 158 | 223 | 308 | 514 | 795 |
| | 15 | NA | 50 | 93 | 144 | 207 | 291 | 488 | 760 |
| | 20 | NA | NA | 82 | 132 | 195 | 273 | 466 | 726 |
| 20 | 0 | 53 | 101 | 163 | 252 | 342 | 470 | 770 | 1190 |
| | 2 | 42 | 80 | 136 | 210 | 286 | 392 | 641 | 990 |
| | 5 | 38 | 74 | 123 | 192 | 264 | 364 | 610 | 945 |
| | 10 | 32 | 65 | 115 | 178 | 246 | 345 | 571 | 910 |
| | 15 | NA | 55 | 104 | 163 | 228 | 326 | 550 | 870 |
| | 20 | NA | NA | 91 | 149 | 214 | 306 | 525 | 832 |
| | 30 | NA | NA | NA | NA | NA | NA | NA | NA |
| 30 | 0 | 56 | 108 | 183 | 276 | 384 | 529 | 878 | 1370 |
| | 2 | 44 | 84 | 148 | 230 | 320 | 441 | 730 | 1140 |
| | 5 | NA | 78 | 137 | 210 | 296 | 410 | 694 | 1080 |
| | 10 | NA | 68 | 125 | 196 | 274 | 388 | 656 | 1050 |
| | 15 | NA | NA | 113 | 177 | 258 | 366 | 625 | 1000 |
| | 20 | NA | NA | 99 | 163 | 240 | 344 | 596 | 960 |
| | 30 | NA | NA | NA | NA | 192 | 295 | 540 | 890 |
| | 40 | NA | NA | NA | NA | NA | NA | NA | NA |
| 50 | 0 | NA | 120 | 210 | 310 | 443 | 590 | 980 | 1550 |
| | 2 | NA | 95 | 171 | 260 | 370 | 492 | 820 | 1290 |
| | 5 | NA | NA | 159 | 234 | 342 | 474 | 780 | 1230 |
| | 10 | NA | NA | 146 | 221 | 318 | 456 | 730 | 1190 |
| | 15 | NA | NA | NA | 200 | 292 | 407 | 705 | 1130 |
| | 20 | NA | NA | NA | 185 | 276 | 384 | 670 | 1080 |
| | 30 | NA | NA | NA | NA | 222 | 330 | 605 | 1010 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

TABLE 510.1.2(6)

EXTERIOR MASONRY CHIMNEY [NFPA 54: TABLE 13.1(f)]^{1, 2}

| | | | NUMBER OF APPLIANCES: SINGLE | | | | | |
|--|--|----|---|-----|-----|-----|------|-----|
| | | | APPLIANCE TYPE: NAT | | | | | |
| | | | APPLIANCE VENT CONNECTION: TYPE B DOUBLE-WALL CONNECTOR | | | | | |
| MINIMUM ALLOWABLE INPUT RATING OF SPACE-HEATING APPLIANCE IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | INTERNAL AREA OF CHIMNEY (square inches) | | | | | | | |
| | 12 | 19 | 28 | 38 | 50 | 63 | 78 | 113 |
| 6 8 10 15 20 30 50 | Local 99% winter design temperature: 37°F or greater | | | | | | | |
| | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | NA | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | NA | NA | 123 | 190 | 249 | 184 | 0 | 0 |
| | NA | NA | NA | NA | NA | 393 | 334 | 0 |
| 50 | NA | NA | NA | NA | NA | NA | NA | 579 |
| 6 8 10 15 20 30 50 | Local 99% winter design temperature: 27°F to 36°F | | | | | | | |
| | 0 | 0 | 68 | 116 | 156 | 180 | 212 | 266 |
| | 0 | 0 | 82 | 127 | 167 | 187 | 214 | 263 |
| | 0 | 51 | 97 | 141 | 183 | 201 | 225 | 265 |
| | NA | NA | NA | NA | 233 | 253 | 274 | 305 |
| | NA | NA | NA | NA | NA | 307 | 330 | 362 |
| | NA | NA | NA | NA | NA | 419 | 445 | 485 |
| 50 | NA | NA | NA | NA | NA | NA | 763 | |
| 6 8 10 15 20 30 50 | Local 99% winter design temperature: 17°F to 26°F | | | | | | | |
| | NA | NA | NA | NA | NA | 215 | 259 | 349 |
| | NA | NA | NA | NA | 197 | 226 | 264 | 352 |
| | NA | NA | NA | NA | 214 | 245 | 278 | 358 |
| | NA | NA | NA | NA | NA | 296 | 331 | 398 |
| | NA | NA | NA | NA | NA | 352 | 387 | 457 |
| | NA | NA | NA | NA | NA | NA | 507 | 581 |
| 50 | NA | NA | NA | NA | NA | NA | NA | |
| 6 8 10 15 20 30 50 | Local 99% winter design temperature: 5°F to 16°F | | | | | | | |
| | NA | NA | NA | NA | NA | NA | NA | 416 |
| | NA | NA | NA | NA | NA | NA | 312 | 423 |
| | NA | NA | NA | NA | NA | 289 | 331 | 430 |
| | NA | NA | NA | NA | NA | NA | 393 | 485 |
| | NA | NA | NA | NA | NA | NA | 450 | 547 |
| | NA | NA | NA | NA | NA | NA | NA | 682 |
| 50 | NA | NA | NA | NA | NA | NA | 972 | |
| 6 8 10 15 20 30 50 | Local 99% winter design temperature: -10°F to 4°F | | | | | | | |
| | NA | NA | NA | NA | NA | NA | NA | 484 |
| | NA | NA | NA | NA | NA | NA | NA | 494 |
| | NA | NA | NA | NA | NA | NA | NA | 513 |
| | NA | NA | NA | NA | NA | NA | NA | 586 |
| | NA | NA | NA | NA | NA | NA | NA | 650 |
| | NA | NA | NA | NA | NA | NA | NA | 805 |
| 50 | NA | NA | NA | NA | NA | NA | 1003 | |
| Local 99% winter design temperature: -11°F or lower Not recommended for any vent configurations | | | | | | | | |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m², °C = (°F-32)/1.8**Notes:**¹ See Figure 510.1.2(6) for a map showing local 99 percent winter design temperatures in the United States.² NA: Not applicable.

WATER HEATERS

TABLE 510.2(1)
TYPE B DOUBLE-WALL VENT [NFPA 54: TABLE 13.2(a)]*

| | | | | | NUMBER OF APPLIANCES: TWO OR MORE | | | | | | | | | | | |
|--------------------------------------|---|-----|-----|-----|--|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| | | | | | APPLIANCE TYPE: CATEGORY I | | | | | | | | | | | |
| | | | | | APPLIANCE VENT CONNECTION: TYPE B DOUBLE-WALL CONNECTOR | | | | | | | | | | | |
| | | | | | VENT CONNECTOR CAPACITY | | | | | | | | | | | |
| | | | | | TYPE B DOUBLE-WALL VENT AND CONNECTOR DIAMETER – <i>D</i> (inch) | | | | | | | | | | | |
| | | | | | 3 | | 4 | | 5 | | 6 | | 7 | | | |
| | | | | | APPLIANCE INPUT RATING LIMITS IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | CONNECTOR RISE <i>R</i> (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 1 | 22 | 37 | 26 | 35 | 66 | 46 | 46 | 106 | 72 | 58 | 164 | 104 | 77 | 225 | 142 |
| | 2 | 23 | 41 | 31 | 37 | 75 | 55 | 48 | 121 | 86 | 60 | 183 | 124 | 79 | 253 | 168 |
| | 3 | 24 | 44 | 35 | 38 | 81 | 62 | 49 | 132 | 96 | 62 | 199 | 139 | 82 | 275 | 189 |
| 8 | 1 | 22 | 40 | 27 | 35 | 72 | 48 | 49 | 114 | 76 | 64 | 176 | 109 | 84 | 243 | 148 |
| | 2 | 23 | 44 | 32 | 36 | 80 | 57 | 51 | 128 | 90 | 66 | 195 | 129 | 86 | 269 | 175 |
| | 3 | 24 | 47 | 36 | 37 | 87 | 64 | 53 | 139 | 101 | 67 | 210 | 145 | 88 | 290 | 198 |
| 10 | 1 | 22 | 43 | 28 | 34 | 78 | 50 | 49 | 123 | 78 | 65 | 189 | 113 | 89 | 257 | 154 |
| | 2 | 23 | 47 | 33 | 36 | 86 | 59 | 51 | 136 | 93 | 67 | 206 | 134 | 91 | 282 | 182 |
| | 3 | 24 | 50 | 37 | 37 | 92 | 67 | 52 | 146 | 104 | 69 | 220 | 150 | 94 | 303 | 205 |
| 15 | 1 | 21 | 50 | 30 | 33 | 89 | 53 | 47 | 142 | 83 | 64 | 220 | 120 | 88 | 298 | 163 |
| | 2 | 22 | 53 | 35 | 35 | 96 | 63 | 49 | 153 | 99 | 66 | 235 | 142 | 91 | 320 | 193 |
| | 3 | 24 | 55 | 40 | 36 | 102 | 71 | 51 | 163 | 111 | 68 | 248 | 160 | 93 | 339 | 218 |
| 20 | 1 | 21 | 54 | 31 | 33 | 99 | 56 | 46 | 157 | 87 | 62 | 246 | 125 | 86 | 334 | 171 |
| | 2 | 22 | 57 | 37 | 34 | 105 | 66 | 48 | 167 | 104 | 64 | 259 | 149 | 89 | 354 | 202 |
| | 3 | 23 | 60 | 42 | 35 | 110 | 74 | 50 | 176 | 116 | 66 | 271 | 168 | 91 | 371 | 228 |
| 30 | 1 | 20 | 62 | 33 | 31 | 113 | 59 | 45 | 181 | 93 | 60 | 288 | 134 | 83 | 391 | 182 |
| | 2 | 21 | 64 | 39 | 33 | 118 | 70 | 47 | 190 | 110 | 62 | 299 | 158 | 85 | 408 | 215 |
| | 3 | 22 | 66 | 44 | 34 | 123 | 79 | 48 | 198 | 124 | 64 | 309 | 178 | 88 | 423 | 242 |
| 50 | 1 | 19 | 71 | 36 | 30 | 133 | 64 | 43 | 216 | 101 | 57 | 349 | 145 | 78 | 477 | 197 |
| | 2 | 21 | 73 | 43 | 32 | 137 | 76 | 45 | 223 | 119 | 59 | 358 | 172 | 81 | 490 | 234 |
| | 3 | 22 | 75 | 48 | 33 | 141 | 86 | 46 | 229 | 134 | 61 | 366 | 194 | 83 | 502 | 263 |
| 100 | 1 | 18 | 82 | 37 | 28 | 158 | 66 | 40 | 262 | 104 | 53 | 442 | 150 | 73 | 611 | 204 |
| | 2 | 19 | 83 | 44 | 30 | 161 | 79 | 42 | 267 | 123 | 55 | 447 | 178 | 75 | 619 | 242 |
| | 3 | 20 | 84 | 50 | 31 | 163 | 89 | 44 | 272 | 138 | 57 | 452 | 200 | 78 | 627 | 272 |

| | COMMON VENT CAPACITY | | | | | | | | | | | |
|--------------------------------------|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | TYPE B DOUBLE-WALL COMMON VENT DIAMETER – <i>D</i> (inch) | | | | | | | | | | | |
| | 4 | | | 5 | | | 6 | | | 7 | | |
| | COMBINED APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT |
| 6 | 92 | 81 | 65 | 140 | 116 | 103 | 204 | 161 | 147 | 309 | 248 | 200 |
| 8 | 101 | 90 | 73 | 155 | 129 | 114 | 224 | 178 | 163 | 339 | 275 | 223 |
| 10 | 110 | 97 | 79 | 169 | 141 | 124 | 243 | 194 | 178 | 367 | 299 | 242 |
| 15 | 125 | 112 | 91 | 195 | 164 | 144 | 283 | 228 | 206 | 427 | 352 | 280 |
| 20 | 136 | 123 | 102 | 215 | 183 | 160 | 314 | 255 | 229 | 475 | 394 | 310 |
| 30 | 152 | 138 | 118 | 244 | 210 | 185 | 361 | 297 | 266 | 547 | 459 | 360 |
| 50 | 167 | 153 | 134 | 279 | 244 | 214 | 421 | 353 | 310 | 641 | 547 | 423 |
| 100 | 175 | 163 | NA | 311 | 277 | NA | 489 | 421 | NA | 751 | 658 | 479 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

TABLE 510.2(1)
TYPE B DOUBLE-WALL VENT [NFPA 54: TABLE 13.2(a)] (continued)

| | | NUMBER OF APPLIANCES: | | | TWO OR MORE | | | | | |
|-----------------------------------|--------------------------------------|--|-----|-----|------------------------------|------|-----|-----|------|-----|
| | | APPLIANCE TYPE: | | | CATEGORY I | | | | | |
| | | APPLIANCE VENT CONNECTION: | | | TYPE B DOUBLE-WALL CONNECTOR | | | | | |
| | | VENT CONNECTOR CAPACITY | | | | | | | | |
| | | TYPE B DOUBLE-WALL VENT AND CONNECTOR DIAMETER – <i>D</i> (Inch) | | | | | | | | |
| | | 8 | | | 9 | | | 10 | | |
| | | APPLIANCE INPUT RATING LIMITS IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | CONNECTOR RISE <i>R</i> (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 1 | 92 | 296 | 185 | 109 | 376 | 237 | 128 | 466 | 289 |
| | 2 | 95 | 333 | 220 | 112 | 424 | 282 | 131 | 526 | 345 |
| | 3 | 97 | 363 | 248 | 114 | 463 | 317 | 134 | 575 | 386 |
| 8 | 1 | 100 | 320 | 194 | 118 | 408 | 248 | 138 | 507 | 303 |
| | 2 | 103 | 356 | 230 | 121 | 454 | 294 | 141 | 564 | 358 |
| | 3 | 105 | 384 | 258 | 123 | 492 | 330 | 143 | 612 | 402 |
| 10 | 1 | 106 | 341 | 200 | 125 | 436 | 257 | 146 | 542 | 314 |
| | 2 | 109 | 374 | 238 | 128 | 479 | 305 | 149 | 596 | 372 |
| | 3 | 111 | 402 | 268 | 131 | 515 | 342 | 152 | 642 | 417 |
| 15 | 1 | 110 | 389 | 214 | 134 | 493 | 273 | 162 | 609 | 333 |
| | 2 | 112 | 419 | 253 | 137 | 532 | 323 | 165 | 658 | 394 |
| | 3 | 115 | 445 | 286 | 140 | 565 | 365 | 167 | 700 | 444 |
| 20 | 1 | 107 | 436 | 224 | 131 | 552 | 285 | 158 | 681 | 347 |
| | 2 | 110 | 463 | 265 | 134 | 587 | 339 | 161 | 725 | 414 |
| | 3 | 113 | 486 | 300 | 137 | 618 | 383 | 164 | 764 | 466 |
| 30 | 1 | 103 | 512 | 238 | 125 | 649 | 305 | 151 | 802 | 372 |
| | 2 | 105 | 535 | 282 | 129 | 679 | 360 | 155 | 840 | 439 |
| | 3 | 108 | 555 | 317 | 132 | 706 | 405 | 158 | 874 | 494 |
| 50 | 1 | 97 | 627 | 257 | 120 | 797 | 330 | 144 | 984 | 403 |
| | 2 | 100 | 645 | 306 | 123 | 820 | 392 | 148 | 1014 | 478 |
| | 3 | 103 | 661 | 343 | 126 | 842 | 441 | 151 | 1043 | 538 |
| 100 | 1 | 91 | 810 | 266 | 112 | 1038 | 341 | 135 | 1285 | 417 |
| | 2 | 94 | 822 | 316 | 115 | 1054 | 405 | 139 | 1306 | 494 |
| | 3 | 97 | 834 | 355 | 118 | 1069 | 455 | 142 | 1327 | 555 |

| | COMMON VENT CAPACITY | | | | | | | | |
|--------------------------------------|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | TYPE B DOUBLE-WALL COMMON VENT DIAMETER – <i>D</i> (inch) | | | | | | | | |
| | 8 | | | 9 | | | 10 | | |
| | COMBINED APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT |
| 6 | 404 | 314 | 260 | 547 | 434 | 335 | 672 | 520 | 410 |
| 8 | 444 | 348 | 290 | 602 | 480 | 378 | 740 | 577 | 465 |
| 10 | 477 | 377 | 315 | 649 | 522 | 405 | 800 | 627 | 495 |
| 15 | 556 | 444 | 365 | 753 | 612 | 465 | 924 | 733 | 565 |
| 20 | 621 | 499 | 405 | 842 | 688 | 523 | 1035 | 826 | 640 |
| 30 | 720 | 585 | 470 | 979 | 808 | 605 | 1209 | 975 | 740 |
| 50 | 854 | 706 | 550 | 1164 | 977 | 705 | 1451 | 1188 | 860 |
| 100 | 1025 | 873 | 625 | 1408 | 1215 | 800 | 1784 | 1502 | 975 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

WATER HEATERS

TABLE 510.2(1)
TYPE B DOUBLE-WALL VENT [NFPA 54: TABLE 13.2(a)] (continued)*

| | | | | | NUMBER OF APPLIANCES: | | TWO OR MORE | | | | | | |
|-----------------------------------|--------------------------------------|-----|------|------|--|------|------------------------------|-----|------|------|-----|------|------|
| | | | | | APPLIANCE TYPE: | | CATEGORY I | | | | | | |
| | | | | | APPLIANCE VENT CONNECTION: | | TYPE B DOUBLE-WALL CONNECTOR | | | | | | |
| | | | | | VENT CONNECTOR CAPACITY | | | | | | | | |
| | | | | | TYPE B DOUBLE-WALL VENT AND CONNECTOR DIAMETER – <i>D</i> (inch) | | | | | | | | |
| | | | | | 12 | | 14 | | 16 | | 18 | | |
| | | | | | APPLIANCE INPUT RATING LIMITS IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | CONNECTOR RISE <i>R</i> (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 2 | 174 | 764 | 496 | 223 | 1046 | 653 | 281 | 1371 | 853 | 346 | 1772 | 1080 |
| | 4 | 180 | 897 | 616 | 230 | 1231 | 827 | 287 | 1617 | 1081 | 352 | 2069 | 1370 |
| | 6 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| 8 | 2 | 186 | 822 | 516 | 238 | 1126 | 696 | 298 | 1478 | 910 | 365 | 1920 | 1150 |
| | 4 | 192 | 952 | 644 | 244 | 1307 | 884 | 305 | 1719 | 1150 | 372 | 2211 | 1460 |
| | 6 | 198 | 1050 | 772 | 252 | 1445 | 1072 | 313 | 1902 | 1390 | 380 | 2434 | 1770 |
| 10 | 2 | 196 | 870 | 536 | 249 | 1195 | 730 | 311 | 1570 | 955 | 379 | 2049 | 1205 |
| | 4 | 201 | 997 | 664 | 256 | 1371 | 924 | 318 | 1804 | 1205 | 387 | 2332 | 1535 |
| | 6 | 207 | 1095 | 792 | 263 | 1509 | 1118 | 325 | 1989 | 1455 | 395 | 2556 | 1865 |
| 15 | 2 | 214 | 967 | 568 | 272 | 1334 | 790 | 336 | 1760 | 1030 | 408 | 2317 | 1305 |
| | 4 | 221 | 1085 | 712 | 279 | 1499 | 1006 | 344 | 1978 | 1320 | 416 | 2579 | 1665 |
| | 6 | 228 | 1181 | 856 | 286 | 1632 | 1222 | 351 | 2157 | 1610 | 424 | 2796 | 2025 |
| 20 | 2 | 223 | 1051 | 596 | 291 | 1443 | 840 | 357 | 1911 | 1095 | 430 | 2533 | 1385 |
| | 4 | 230 | 1162 | 748 | 298 | 1597 | 1064 | 365 | 2116 | 1395 | 438 | 2778 | 1765 |
| | 6 | 237 | 1253 | 900 | 307 | 1726 | 1288 | 373 | 2287 | 1695 | 450 | 2984 | 2145 |
| 30 | 2 | 216 | 1217 | 632 | 286 | 1664 | 910 | 367 | 2183 | 1190 | 461 | 2891 | 1540 |
| | 4 | 223 | 1316 | 792 | 294 | 1802 | 1160 | 376 | 2366 | 1510 | 474 | 3110 | 1920 |
| | 6 | 231 | 1400 | 952 | 303 | 1920 | 1410 | 384 | 2524 | 1830 | 485 | 3299 | 2340 |
| 50 | 2 | 206 | 1479 | 689 | 273 | 2023 | 1007 | 350 | 2659 | 1315 | 435 | 3548 | 1665 |
| | 4 | 213 | 1561 | 860 | 281 | 2139 | 1291 | 359 | 2814 | 1685 | 447 | 3730 | 2135 |
| | 6 | 221 | 1631 | 1031 | 290 | 2242 | 1575 | 369 | 2951 | 2055 | 461 | 3893 | 2605 |
| 100 | 2 | 192 | 1923 | 712 | 254 | 2644 | 1050 | 326 | 3490 | 1370 | 402 | 4707 | 1740 |
| | 4 | 200 | 1984 | 888 | 263 | 2731 | 1346 | 336 | 3606 | 1760 | 414 | 4842 | 2220 |
| | 6 | 208 | 2035 | 1064 | 272 | 2811 | 1642 | 346 | 3714 | 2150 | 426 | 4968 | 2700 |

| | COMMON VENT CAPACITY | | | | | | | | | | | |
|--------------------------------------|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | TYPE B DOUBLE-WALL COMMON VENT DIAMETER – <i>D</i> (inch) | | | | | | | | | | | |
| | 12 | | | 14 | | | 16 | | | 18 | | |
| | COMBINED APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT |
| 6 | 900 | 696 | 588 | 1284 | 990 | 815 | 1735 | 1336 | 1065 | 2253 | 1732 | 1345 |
| 8 | 994 | 773 | 652 | 1423 | 1103 | 912 | 1927 | 1491 | 1190 | 2507 | 1936 | 1510 |
| 10 | 1076 | 841 | 712 | 1542 | 1200 | 995 | 2093 | 1625 | 1300 | 2727 | 2113 | 1645 |
| 15 | 1247 | 986 | 825 | 1794 | 1410 | 1158 | 2440 | 1910 | 1510 | 3184 | 2484 | 1910 |
| 20 | 1405 | 1116 | 916 | 2006 | 1588 | 1290 | 2722 | 2147 | 1690 | 3561 | 2798 | 2140 |
| 30 | 1658 | 1327 | 1025 | 2373 | 1892 | 1525 | 3220 | 2558 | 1990 | 4197 | 3326 | 2520 |
| 50 | 2024 | 1640 | 1280 | 2911 | 2347 | 1863 | 3964 | 3183 | 2430 | 5184 | 4149 | 3075 |
| 100 | 2569 | 2131 | 1670 | 3732 | 3076 | 2450 | 5125 | 4202 | 3200 | 6749 | 5509 | 4050 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

TABLE 510.2(1)
TYPE B DOUBLE-WALL VENT [NFPA 54: TABLE 13.2(a)] (continued)*

| | | NUMBER OF APPLIANCES: TWO OR MORE | | | | | | | | |
|--|--------------------------------------|--|------|------|-----|------|------|-----|------|------|
| | | APPLIANCE TYPE: CATEGORY I | | | | | | | | |
| | | APPLIANCE VENT CONNECTION: TYPE B DOUBLE-WALL CONNECTOR | | | | | | | | |
| | | VENT CONNECTOR CAPACITY | | | | | | | | |
| | | TYPE B DOUBLE-WALL VENT AND CONNECTOR DIAMETER – <i>D</i> (inch) | | | | | | | | |
| | | 20 | | 22 | | 24 | | | | |
| APPLIANCE INPUT RATING LIMITS IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | CONNECTOR RISE <i>R</i> (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 2 | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| | 4 | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| | 6 | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| 8 | 2 | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| | 4 | 471 | 2737 | 1800 | 560 | 3319 | 2180 | 662 | 3957 | 2590 |
| | 6 | 478 | 3018 | 2180 | 568 | 3665 | 2640 | 669 | 4373 | 3130 |
| 10 | 2 | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| | 4 | 486 | 2887 | 1890 | 581 | 3502 | 2280 | 686 | 4175 | 2710 |
| | 6 | 494 | 3169 | 2290 | 589 | 3849 | 2760 | 694 | 4593 | 3270 |
| 15 | 2 | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| | 4 | 523 | 3197 | 2060 | 624 | 3881 | 2490 | 734 | 4631 | 2960 |
| | 6 | 533 | 3470 | 2510 | 634 | 4216 | 3030 | 743 | 5035 | 3600 |
| 20 | 2 | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| | 4 | 554 | 3447 | 2180 | 661 | 4190 | 2630 | 772 | 5005 | 3130 |
| | 6 | 567 | 3708 | 2650 | 671 | 4511 | 3190 | 785 | 5392 | 3790 |
| 30 | 2 | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| | 4 | 619 | 3840 | 2365 | 728 | 4861 | 2860 | 847 | 5606 | 3410 |
| | 6 | 632 | 4080 | 2875 | 741 | 4976 | 3480 | 860 | 5961 | 4150 |
| 50 | 2 | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| | 4 | 580 | 4601 | 2633 | 709 | 5569 | 3185 | 851 | 6633 | 3790 |
| | 6 | 594 | 4808 | 3208 | 724 | 5826 | 3885 | 867 | 6943 | 4620 |
| 100 | 2 | NA | NA | NA | NA | NA | NA | NA | NA | NA |
| | 4 | 523 | 5982 | 2750 | 639 | 7254 | 3330 | 769 | 8650 | 3950 |
| | 6 | 539 | 6143 | 3350 | 654 | 7453 | 4070 | 786 | 8892 | 4810 |

| | COMMON VENT CAPACITY | | | | | | | | |
|--------------------------------------|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | TYPE B DOUBLE-WALL COMMON VENT DIAMETER – <i>D</i> (inch) | | | | | | | | |
| | 20 | | | 22 | | | 24 | | |
| | COMBINED APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT |
| 6 | 2838 | 2180 | 1660 | 3488 | 2677 | 1970 | 4206 | 3226 | 2390 |
| 8 | 3162 | 2439 | 1860 | 3890 | 2998 | 2200 | 4695 | 3616 | 2680 |
| 10 | 3444 | 2665 | 2030 | 4241 | 3278 | 2400 | 5123 | 3957 | 2920 |
| 15 | 4026 | 3133 | 2360 | 4971 | 3862 | 2790 | 6016 | 4670 | 3400 |
| 20 | 4548 | 3552 | 2640 | 5573 | 4352 | 3120 | 6749 | 5261 | 3800 |
| 30 | 5303 | 4193 | 3110 | 6539 | 5157 | 3680 | 7940 | 6247 | 4480 |
| 50 | 6567 | 5240 | 3800 | 8116 | 6458 | 4500 | 9837 | 7813 | 5475 |
| 100 | 8597 | 6986 | 5000 | 10 681 | 8648 | 5920 | 13 004 | 10 499 | 7200 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

WATER HEATERS

TABLE 510.2(2)
TYPE B DOUBLE-WALL VENT [NFPA 54: TABLE 13.2(b)]*

| | | NUMBER OF APPLIANCES: TWO OR MORE | | | | | | | | | | | | | | |
|----------------------------|-------------------------------|--|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| | | APPLIANCE TYPE: CATEGORY I | | | | | | | | | | | | | | |
| | | APPLIANCE VENT CONNECTION: SINGLE-WALL METAL CONNECTOR | | | | | | | | | | | | | | |
| | | VENT CONNECTOR CAPACITY | | | | | | | | | | | | | | |
| | | SINGLE-WALL METAL VENT CONNECTOR DIAMETER – D (inch) | | | | | | | | | | | | | | |
| | | 3 | | | 4 | | | 5 | | | 6 | | | 7 | | |
| | | APPLIANCE INPUT RATING LIMITS IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | | |
| VENT HEIGHT H (feet) | CONNECTOR RISE R (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 1 | NA | NA | 26 | NA | NA | 46 | NA | NA | 71 | NA | NA | 102 | 207 | 223 | 140 |
| | 2 | NA | NA | 31 | NA | NA | 55 | NA | NA | 85 | 168 | 182 | 123 | 215 | 251 | 167 |
| | 3 | NA | NA | 34 | NA | NA | 62 | 121 | 131 | 95 | 175 | 198 | 138 | 222 | 273 | 188 |
| 8 | 1 | NA | NA | 27 | NA | NA | 48 | NA | NA | 75 | NA | NA | 106 | 226 | 240 | 145 |
| | 2 | NA | NA | 32 | NA | NA | 57 | 125 | 126 | 89 | 184 | 193 | 127 | 234 | 266 | 173 |
| | 3 | NA | NA | 35 | NA | NA | 64 | 130 | 138 | 100 | 191 | 208 | 144 | 241 | 287 | 197 |
| 10 | 1 | NA | NA | 28 | NA | NA | 50 | 119 | 121 | 77 | 182 | 186 | 110 | 240 | 253 | 150 |
| | 2 | NA | NA | 33 | 84 | 85 | 59 | 124 | 134 | 91 | 189 | 203 | 132 | 248 | 278 | 183 |
| | 3 | NA | NA | 36 | 89 | 91 | 67 | 129 | 144 | 102 | 197 | 217 | 148 | 257 | 299 | 203 |
| 15 | 1 | NA | NA | 29 | 79 | 87 | 52 | 116 | 138 | 81 | 177 | 214 | 116 | 238 | 291 | 158 |
| | 2 | NA | NA | 34 | 83 | 94 | 62 | 121 | 150 | 97 | 185 | 230 | 138 | 246 | 314 | 189 |
| | 3 | NA | NA | 39 | 87 | 100 | 70 | 127 | 160 | 109 | 193 | 243 | 157 | 255 | 333 | 215 |
| 20 | 1 | 49 | 56 | 30 | 78 | 97 | 54 | 115 | 152 | 84 | 175 | 238 | 120 | 233 | 325 | 165 |
| | 2 | 52 | 59 | 36 | 82 | 103 | 64 | 120 | 163 | 101 | 182 | 252 | 144 | 243 | 346 | 197 |
| | 3 | 55 | 62 | 40 | 87 | 107 | 72 | 125 | 172 | 113 | 190 | 264 | 164 | 252 | 363 | 223 |
| 30 | 1 | 47 | 60 | 31 | 77 | 110 | 57 | 112 | 175 | 89 | 169 | 278 | 129 | 226 | 380 | 175 |
| | 2 | 51 | 62 | 37 | 81 | 115 | 67 | 117 | 185 | 106 | 177 | 290 | 152 | 236 | 397 | 208 |
| | 3 | 54 | 64 | 42 | 85 | 119 | 76 | 122 | 193 | 120 | 185 | 300 | 172 | 244 | 412 | 235 |
| 50 | 1 | 46 | 69 | 34 | 75 | 128 | 60 | 109 | 207 | 96 | 162 | 336 | 137 | 217 | 460 | 188 |
| | 2 | 49 | 71 | 40 | 79 | 132 | 72 | 114 | 215 | 113 | 170 | 345 | 164 | 226 | 473 | 223 |
| | 3 | 52 | 72 | 45 | 83 | 136 | 82 | 119 | 221 | 123 | 178 | 353 | 186 | 235 | 486 | 252 |
| 100 | 1 | 45 | 79 | 34 | 71 | 150 | 61 | 104 | 249 | 98 | 153 | 424 | 140 | 205 | 585 | 192 |
| | 2 | 48 | 80 | 41 | 75 | 153 | 73 | 110 | 255 | 115 | 160 | 428 | 167 | 212 | 593 | 228 |
| | 3 | 51 | 81 | 46 | 79 | 157 | 85 | 114 | 260 | 129 | 168 | 433 | 190 | 222 | 603 | 256 |

| VENT HEIGHT <i>H</i> (feet) | COMMON VENT CAPACITY | | | | | | | | | | | |
|--------------------------------------|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | TYPE B DOUBLE-WALL COMMON VENT DIAMETER – <i>D</i> (inch) | | | | | | | | | | | |
| | 4 | | | 5 | | | 6 | | | 7 | | |
| | COMBINED APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | |
| | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT |
| 6 | NA | 78 | 64 | NA | 113 | 99 | 200 | 158 | 144 | 304 | 244 | 196 |
| 8 | NA | 87 | 71 | NA | 126 | 111 | 218 | 173 | 159 | 331 | 269 | 218 |
| 10 | NA | 94 | 76 | 163 | 137 | 120 | 237 | 189 | 174 | 357 | 292 | 236 |
| 15 | 121 | 108 | 88 | 189 | 159 | 140 | 275 | 221 | 200 | 416 | 343 | 274 |
| 20 | 131 | 118 | 98 | 208 | 177 | 156 | 305 | 247 | 223 | 463 | 383 | 302 |
| 30 | 145 | 132 | 113 | 236 | 202 | 180 | 350 | 286 | 257 | 533 | 446 | 349 |
| 50 | 159 | 145 | 128 | 268 | 233 | 208 | 406 | 337 | 296 | 622 | 529 | 410 |
| 100 | 166 | 153 | NA | 297 | 263 | NA | 469 | 398 | NA | 726 | 633 | 464 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

TABLE 510.2(2)
TYPE B DOUBLE-WALL VENT [NFPA 54: TABLE 13.2(b)] (continued)

| | | NUMBER OF APPLIANCES: TWO OR MORE | | | | | | | | |
|-----------------------------------|--------------------------------------|---|-----|-----|-----|------|-----|-----|------|-----|
| | | APPLIANCE TYPE: CATEGORY I | | | | | | | | |
| | | APPLIANCE VENT CONNECTION: SINGLE-WALL METAL CONNECTOR | | | | | | | | |
| | | VENT CONNECTOR CAPACITY | | | | | | | | |
| | | SINGLE-WALL METAL VENT CONNECTOR DIAMETER – <i>D</i> (inch) | | | | | | | | |
| | | 8 | | | 9 | | | 10 | | |
| | | APPLIANCE INPUT RATING LIMITS IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | CONNECTOR RISE <i>R</i> (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 1 | 262 | 293 | 183 | 325 | 373 | 234 | 447 | 463 | 286 |
| | 2 | 271 | 331 | 219 | 334 | 422 | 281 | 458 | 524 | 344 |
| | 3 | 279 | 361 | 247 | 344 | 462 | 316 | 468 | 574 | 385 |
| 8 | 1 | 285 | 316 | 191 | 352 | 403 | 244 | 481 | 502 | 299 |
| | 2 | 293 | 353 | 228 | 360 | 450 | 292 | 492 | 560 | 355 |
| | 3 | 302 | 381 | 256 | 370 | 489 | 328 | 501 | 609 | 400 |
| 10 | 1 | 302 | 335 | 196 | 372 | 429 | 252 | 506 | 534 | 308 |
| | 2 | 311 | 369 | 235 | 381 | 473 | 302 | 517 | 589 | 368 |
| | 3 | 320 | 398 | 265 | 391 | 511 | 339 | 528 | 637 | 413 |
| 15 | 1 | 312 | 380 | 208 | 397 | 482 | 266 | 556 | 596 | 324 |
| | 2 | 321 | 411 | 248 | 407 | 522 | 317 | 568 | 646 | 387 |
| | 3 | 331 | 438 | 281 | 418 | 557 | 360 | 579 | 690 | 437 |
| 20 | 1 | 306 | 425 | 217 | 390 | 538 | 276 | 546 | 664 | 336 |
| | 2 | 317 | 453 | 259 | 400 | 574 | 331 | 558 | 709 | 403 |
| | 3 | 326 | 476 | 294 | 412 | 607 | 375 | 570 | 750 | 457 |
| 30 | 1 | 296 | 497 | 230 | 378 | 630 | 294 | 528 | 779 | 358 |
| | 2 | 307 | 521 | 274 | 389 | 662 | 349 | 541 | 819 | 425 |
| | 3 | 316 | 542 | 309 | 400 | 690 | 394 | 555 | 855 | 482 |
| 50 | 1 | 284 | 604 | 245 | 364 | 768 | 314 | 507 | 951 | 384 |
| | 2 | 294 | 623 | 293 | 376 | 793 | 375 | 520 | 983 | 458 |
| | 3 | 304 | 640 | 331 | 387 | 816 | 423 | 535 | 1013 | 518 |
| 100 | 1 | 269 | 774 | 249 | 345 | 993 | 321 | 476 | 1236 | 393 |
| | 2 | 279 | 788 | 299 | 358 | 1011 | 383 | 490 | 1259 | 469 |
| | 3 | 289 | 801 | 339 | 368 | 1027 | 431 | 506 | 1280 | 527 |

| | COMMON VENT CAPACITY | | | | | | | | |
|--------------------------------------|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | TYPE B DOUBLE-WALL COMMON VENT DIAMETER – <i>D</i> (inch) | | | | | | | | |
| | 8 | | | 9 | | | 10 | | |
| | COMBINED APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT |
| 6 | 398 | 310 | 257 | 541 | 429 | 332 | 665 | 515 | 407 |
| 8 | 436 | 342 | 285 | 592 | 473 | 373 | 730 | 569 | 460 |
| 10 | 467 | 369 | 309 | 638 | 512 | 398 | 787 | 617 | 487 |
| 15 | 544 | 434 | 357 | 738 | 599 | 456 | 905 | 718 | 553 |
| 20 | 606 | 487 | 395 | 824 | 673 | 512 | 1013 | 808 | 626 |
| 30 | 703 | 570 | 459 | 958 | 790 | 593 | 1183 | 952 | 723 |
| 50 | 833 | 686 | 535 | 1139 | 954 | 689 | 1418 | 1157 | 838 |
| 100 | 999 | 846 | 606 | 1378 | 1185 | 780 | 1741 | 1459 | 948 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

WATER HEATERS

TABLE 510.2(3)
MASONRY CHIMNEY [NFPA 54: TABLE 13.2(c)]*

| | | | | | NUMBER OF APPLIANCES: TWO OR MORE | | | | | | | | | | | | | | |
|----------------------------|-------------------------------|-----|-----|-----|--|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|---|--|--|
| | | | | | APPLIANCE TYPE: CATEGORY I | | | | | | | | | | | | | | |
| | | | | | APPLIANCE VENT CONNECTION: TYPE B DOUBLE-WALL CONNECTOR | | | | | | | | | | | | | | |
| | | | | | VENT CONNECTOR CAPACITY | | | | | | | | | | | | | | |
| | | | | | TYPE B DOUBLE-WALL VENT CONNECTOR DIAMETER – D (inch) | | | | | | | | | | | | | | |
| | | | | | 3 | | | 4 | | | 5 | | | 6 | | | 7 | | |
| | | | | | APPLIANCE INPUT RATING LIMITS IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | | |
| VENT HEIGHT H (feet) | CONNECTOR RISE R (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | | | |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | | | |
| 6 | 1 | 24 | 33 | 21 | 39 | 62 | 40 | 52 | 106 | 67 | 65 | 194 | 101 | 87 | 274 | 141 | | | |
| | 2 | 26 | 43 | 28 | 41 | 79 | 52 | 53 | 133 | 85 | 67 | 230 | 124 | 89 | 324 | 173 | | | |
| | 3 | 27 | 49 | 34 | 42 | 92 | 61 | 55 | 155 | 97 | 69 | 262 | 143 | 91 | 369 | 203 | | | |
| 8 | 1 | 24 | 39 | 22 | 39 | 72 | 41 | 55 | 117 | 69 | 71 | 213 | 105 | 94 | 304 | 148 | | | |
| | 2 | 26 | 47 | 29 | 40 | 87 | 53 | 57 | 140 | 86 | 73 | 246 | 127 | 97 | 350 | 179 | | | |
| | 3 | 27 | 52 | 34 | 42 | 97 | 62 | 59 | 159 | 98 | 75 | 269 | 145 | 99 | 383 | 206 | | | |
| 10 | 1 | 24 | 42 | 22 | 38 | 80 | 42 | 55 | 130 | 71 | 74 | 232 | 108 | 101 | 324 | 153 | | | |
| | 2 | 26 | 50 | 29 | 40 | 93 | 54 | 57 | 153 | 87 | 76 | 261 | 129 | 103 | 366 | 184 | | | |
| | 3 | 27 | 55 | 35 | 41 | 105 | 63 | 58 | 170 | 100 | 78 | 284 | 148 | 106 | 397 | 209 | | | |
| 15 | 1 | 24 | 48 | 23 | 38 | 93 | 44 | 54 | 154 | 74 | 72 | 277 | 114 | 100 | 384 | 164 | | | |
| | 2 | 25 | 55 | 31 | 39 | 105 | 55 | 56 | 174 | 89 | 74 | 299 | 134 | 103 | 419 | 192 | | | |
| | 3 | 26 | 59 | 35 | 41 | 115 | 64 | 57 | 189 | 102 | 76 | 319 | 153 | 105 | 448 | 215 | | | |
| 20 | 1 | 24 | 52 | 24 | 37 | 102 | 46 | 53 | 172 | 77 | 71 | 313 | 119 | 98 | 437 | 173 | | | |
| | 2 | 25 | 58 | 31 | 39 | 114 | 56 | 55 | 190 | 91 | 73 | 335 | 138 | 101 | 467 | 199 | | | |
| | 3 | 26 | 63 | 35 | 40 | 123 | 65 | 57 | 204 | 104 | 75 | 353 | 157 | 104 | 493 | 222 | | | |
| 30 | 1 | 24 | 54 | 25 | 37 | 111 | 48 | 52 | 192 | 82 | 69 | 357 | 127 | 96 | 504 | 187 | | | |
| | 2 | 25 | 60 | 32 | 38 | 122 | 58 | 54 | 208 | 95 | 72 | 376 | 145 | 99 | 531 | 209 | | | |
| | 3 | 26 | 64 | 36 | 40 | 131 | 66 | 56 | 221 | 107 | 74 | 392 | 163 | 101 | 554 | 233 | | | |
| 50 | 1 | 23 | 51 | 25 | 36 | 116 | 51 | 51 | 209 | 89 | 67 | 405 | 143 | 92 | 582 | 213 | | | |
| | 2 | 24 | 59 | 32 | 37 | 127 | 61 | 53 | 225 | 102 | 70 | 421 | 161 | 95 | 604 | 235 | | | |
| | 3 | 26 | 64 | 36 | 39 | 135 | 69 | 55 | 237 | 115 | 72 | 435 | 180 | 98 | 624 | 260 | | | |
| 100 | 1 | 23 | 46 | 24 | 35 | 108 | 50 | 49 | 208 | 92 | 65 | 428 | 155 | 88 | 640 | 237 | | | |
| | 2 | 24 | 53 | 31 | 37 | 120 | 60 | 51 | 224 | 105 | 67 | 444 | 174 | 92 | 660 | 260 | | | |
| | 3 | 25 | 59 | 35 | 38 | 130 | 68 | 53 | 237 | 118 | 69 | 458 | 193 | 94 | 679 | 285 | | | |

| | COMMON VENT CAPACITY | | | | | | | | | | | | | | |
|----------------------------|---|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | MINIMUM INTERNAL AREA OF MASONRY CHIMNEY FLUE (square inches) | | | | | | | | | | | | | | |
| | 12 | | | 19 | | | 28 | | | 38 | | | 50 | | |
| | COMBINED APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | | |
| VENT HEIGHT H (feet) | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT |
| 6 | NA | 74 | 25 | NA | 119 | 46 | NA | 178 | 71 | NA | 257 | 103 | NA | 351 | 143 |
| 8 | NA | 80 | 28 | NA | 130 | 53 | NA | 193 | 82 | NA | 279 | 119 | NA | 384 | 163 |
| 10 | NA | 84 | 31 | NA | 138 | 56 | NA | 207 | 90 | NA | 299 | 131 | NA | 409 | 177 |
| 15 | NA | NA | 36 | NA | 152 | 67 | NA | 233 | 106 | NA | 334 | 152 | 523 | 467 | 212 |
| 20 | NA | NA | 41 | NA | NA | 75 | NA | 250 | 122 | NA | 368 | 172 | 565 | 508 | 243 |
| 30 | NA | NA | NA | NA | NA | NA | NA | 270 | 137 | NA | 404 | 198 | 615 | 564 | 278 |
| 50 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | 620 | 328 |
| 100 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | 348 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

TABLE 510.2(3)
MASONRY CHIMNEY [NFPA 54: TABLE 13.2(c)] (continued)*

| | | NUMBER OF APPLIANCES: TWO OR MORE | | | | | | | | |
|-----------------------------------|--------------------------------------|--|-----|-----|-----|------|-----|-----|------|-----|
| | | APPLIANCE TYPE: CATEGORY I | | | | | | | | |
| | | APPLIANCE VENT CONNECTION: TYPE B DOUBLE-WALL CONNECTOR | | | | | | | | |
| | | VENT CONNECTOR CAPACITY | | | | | | | | |
| | | TYPE B DOUBLE-WALL VENT CONNECTOR DIAMETER – <i>D</i> (inch) | | | | | | | | |
| | | 8 | | | 9 | | | 10 | | |
| | | APPLIANCE INPUT RATING LIMITS IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | CONNECTOR RISE <i>R</i> (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 1 | 104 | 370 | 201 | 124 | 479 | 253 | 145 | 599 | 319 |
| | 2 | 107 | 436 | 232 | 127 | 562 | 300 | 148 | 694 | 378 |
| | 3 | 109 | 491 | 270 | 129 | 633 | 349 | 151 | 795 | 439 |
| 8 | 1 | 113 | 414 | 210 | 134 | 539 | 267 | 156 | 682 | 335 |
| | 2 | 116 | 473 | 240 | 137 | 615 | 311 | 160 | 776 | 394 |
| | 3 | 119 | 517 | 276 | 139 | 672 | 358 | 163 | 848 | 452 |
| 10 | 1 | 120 | 444 | 216 | 142 | 582 | 277 | 165 | 739 | 348 |
| | 2 | 123 | 498 | 247 | 145 | 652 | 321 | 168 | 825 | 407 |
| | 3 | 126 | 540 | 281 | 147 | 705 | 366 | 171 | 893 | 463 |
| 15 | 1 | 125 | 511 | 229 | 153 | 658 | 297 | 184 | 824 | 375 |
| | 2 | 128 | 558 | 260 | 156 | 718 | 339 | 187 | 900 | 432 |
| | 3 | 131 | 597 | 292 | 159 | 760 | 382 | 190 | 960 | 486 |
| 20 | 1 | 123 | 584 | 239 | 150 | 752 | 312 | 180 | 943 | 397 |
| | 2 | 126 | 625 | 270 | 153 | 805 | 354 | 184 | 1011 | 452 |
| | 3 | 129 | 661 | 301 | 156 | 851 | 396 | 187 | 1067 | 505 |
| 30 | 1 | 119 | 680 | 255 | 145 | 883 | 337 | 175 | 1115 | 432 |
| | 2 | 122 | 715 | 287 | 149 | 928 | 378 | 179 | 1171 | 484 |
| | 3 | 125 | 746 | 317 | 152 | 968 | 418 | 182 | 1220 | 535 |
| 50 | 1 | 115 | 798 | 294 | 140 | 1049 | 392 | 168 | 1334 | 506 |
| | 2 | 118 | 827 | 326 | 143 | 1085 | 433 | 172 | 1379 | 558 |
| | 3 | 121 | 854 | 357 | 147 | 1118 | 474 | 176 | 1421 | 611 |
| 100 | 1 | 109 | 907 | 334 | 134 | 1222 | 454 | 161 | 1589 | 596 |
| | 2 | 113 | 933 | 368 | 138 | 1253 | 497 | 165 | 1626 | 651 |
| | 3 | 116 | 956 | 399 | 141 | 1282 | 540 | 169 | 1661 | 705 |

| | COMMON VENT CAPACITY | | | | | | | | |
|-------------------------------|---|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | MINIMUM INTERNAL AREA OF MASONRY CHIMNEY FLUE (square inches) | | | | | | | | |
| | 63 | | | 78 | | | 113 | | |
| | COMBINED APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT H (feet) | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT |
| 6 | NA | 458 | 188 | NA | 582 | 246 | 1041 | 853 | NA |
| 8 | NA | 501 | 218 | 724 | 636 | 278 | 1144 | 937 | 408 |
| 10 | 606 | 538 | 236 | 776 | 686 | 302 | 1226 | 1010 | 454 |
| 15 | 682 | 611 | 283 | 874 | 781 | 365 | 1374 | 1156 | 546 |
| 20 | 742 | 668 | 325 | 955 | 858 | 419 | 1513 | 1286 | 648 |
| 30 | 816 | 747 | 381 | 1062 | 969 | 496 | 1702 | 1473 | 749 |
| 50 | 879 | 831 | 461 | 1165 | 1089 | 606 | 1905 | 1692 | 922 |
| 100 | NA | NA | 499 | NA | NA | 669 | 2053 | 1921 | 1058 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

WATER HEATERS

TABLE 510.2(4)
MASONRY CHIMNEY [NFPA 54: TABLE 13.2(d)]*

| | | | | | NUMBER OF APPLIANCES: TWO OR MORE | | | | | | | | | | | |
|---|--------------------------------------|-----|-----|-----|--|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| | | | | | APPLIANCE TYPE: CATEGORY I | | | | | | | | | | | |
| | | | | | APPLIANCE VENT CONNECTION: SINGLE-WALL METAL CONNECTOR | | | | | | | | | | | |
| | | | | | VENT CONNECTOR CAPACITY | | | | | | | | | | | |
| SINGLE-WALL METAL VENT CONNECTOR DIAMETER – <i>D</i> (inch) | | | | | | | | | | | | | | | | |
| 3 | | | | | 4 | | | 5 | | | 6 | | | 7 | | |
| APPLIANCE INPUT RATING LIMITS IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | CONNECTOR RISE <i>R</i> (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 1 | NA | NA | 21 | NA | NA | 39 | NA | NA | 66 | 179 | 191 | 100 | 231 | 271 | 140 |
| | 2 | NA | NA | 28 | NA | NA | 52 | NA | NA | 84 | 186 | 227 | 123 | 239 | 321 | 172 |
| | 3 | NA | NA | 34 | NA | NA | 61 | 134 | 153 | 97 | 193 | 258 | 142 | 247 | 365 | 202 |
| 8 | 1 | NA | NA | 21 | NA | NA | 40 | NA | NA | 68 | 195 | 208 | 103 | 250 | 298 | 146 |
| | 2 | NA | NA | 28 | NA | NA | 52 | 137 | 139 | 85 | 202 | 240 | 125 | 258 | 343 | 177 |
| | 3 | NA | NA | 34 | NA | NA | 62 | 143 | 156 | 98 | 210 | 264 | 145 | 266 | 376 | 205 |
| 10 | 1 | NA | NA | 22 | NA | NA | 41 | 130 | 151 | 70 | 202 | 225 | 106 | 267 | 316 | 151 |
| | 2 | NA | NA | 29 | NA | NA | 53 | 136 | 150 | 86 | 210 | 255 | 128 | 276 | 358 | 181 |
| | 3 | NA | NA | 34 | 97 | 102 | 62 | 143 | 166 | 99 | 217 | 277 | 147 | 284 | 389 | 207 |
| 15 | 1 | NA | NA | 23 | NA | NA | 43 | 129 | 151 | 73 | 199 | 271 | 112 | 268 | 376 | 161 |
| | 2 | NA | NA | 30 | 92 | 103 | 54 | 135 | 170 | 88 | 207 | 295 | 132 | 277 | 411 | 189 |
| | 3 | NA | NA | 34 | 96 | 112 | 63 | 141 | 185 | 101 | 215 | 315 | 151 | 286 | 439 | 213 |
| 20 | 1 | NA | NA | 23 | 87 | 99 | 45 | 128 | 167 | 76 | 197 | 303 | 117 | 265 | 425 | 169 |
| | 2 | NA | NA | 30 | 91 | 111 | 55 | 134 | 185 | 90 | 205 | 325 | 136 | 274 | 455 | 195 |
| | 3 | NA | NA | 35 | 96 | 119 | 64 | 140 | 199 | 103 | 213 | 343 | 154 | 282 | 481 | 219 |
| 30 | 1 | NA | NA | 24 | 86 | 108 | 47 | 126 | 187 | 80 | 193 | 347 | 124 | 259 | 492 | 183 |
| | 2 | NA | NA | 31 | 91 | 119 | 57 | 132 | 203 | 93 | 201 | 366 | 142 | 269 | 518 | 205 |
| | 3 | NA | NA | 35 | 95 | 127 | 65 | 138 | 216 | 105 | 209 | 381 | 160 | 277 | 540 | 229 |
| 50 | 1 | NA | NA | 24 | 85 | 113 | 50 | 124 | 204 | 87 | 188 | 392 | 139 | 252 | 567 | 208 |
| | 2 | NA | NA | 31 | 89 | 123 | 60 | 130 | 218 | 100 | 196 | 408 | 158 | 262 | 588 | 230 |
| | 3 | NA | NA | 35 | 94 | 131 | 68 | 136 | 231 | 112 | 205 | 422 | 176 | 271 | 607 | 255 |
| 100 | 1 | NA | NA | 23 | 84 | 104 | 49 | 122 | 200 | 89 | 182 | 410 | 151 | 243 | 617 | 232 |
| | 2 | NA | NA | 30 | 88 | 115 | 59 | 127 | 215 | 102 | 190 | 425 | 169 | 253 | 636 | 254 |
| | 3 | NA | NA | 34 | 93 | 124 | 67 | 133 | 228 | 115 | 199 | 438 | 188 | 262 | 654 | 279 |

| | COMMON VENT CAPACITY | | | | | | | | | | | | | | |
|-----------------------------------|---|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | MINIMUM INTERNAL AREA OF MASONRY CHIMNEY FLUE (square inches) | | | | | | | | | | | | | | |
| | 12 | | | 19 | | | 28 | | | 38 | | | 50 | | |
| | COMBINED APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT |
| 6 | NA | NA | 25 | NA | 118 | 45 | NA | 176 | 71 | NA | 255 | 102 | NA | 348 | 142 |
| 8 | NA | NA | 28 | NA | 128 | 52 | NA | 190 | 81 | NA | 276 | 118 | NA | 380 | 162 |
| 10 | NA | NA | 31 | NA | 136 | 56 | NA | 205 | 89 | NA | 295 | 129 | NA | 405 | 175 |
| 15 | NA | NA | 36 | NA | NA | 66 | NA | 230 | 105 | NA | 335 | 150 | NA | 400 | 210 |
| 20 | NA | NA | NA | NA | NA | 74 | NA | 247 | 120 | NA | 362 | 170 | NA | 503 | 240 |
| 30 | NA | NA | NA | NA | NA | NA | NA | NA | 135 | NA | 398 | 195 | NA | 558 | 275 |
| 50 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | 612 | 325 |
| 100 | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA | NA |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

TABLE 510.2(4)
MASONRY CHIMNEY [NFPA 54: TABLE 13.2(d)] (continued)*

| | | NUMBER OF APPLIANCES: TWO OR MORE | | | | | | | | |
|-----------------------------------|--------------------------------------|---|-----|-----|-----|------|-----|-----|------|-----|
| | | APPLIANCE TYPE: CATEGORY I | | | | | | | | |
| | | APPLIANCE VENT CONNECTION: SINGLE-WALL METAL CONNECTOR | | | | | | | | |
| | | VENT CONNECTOR CAPACITY | | | | | | | | |
| | | SINGLE-WALL METAL VENT CONNECTOR DIAMETER – <i>D</i> (inch) | | | | | | | | |
| | | 8 | | 9 | | 10 | | | | |
| | | APPLIANCE INPUT RATING LIMITS IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | CONNECTOR RISE <i>R</i> (feet) | FAN | | NAT | FAN | | NAT | FAN | | NAT |
| | | Min | Max | Max | Min | Max | Max | Min | Max | Max |
| 6 | 1 | 292 | 366 | 200 | 362 | 474 | 252 | 499 | 594 | 316 |
| | 2 | 301 | 432 | 231 | 373 | 557 | 299 | 509 | 696 | 376 |
| | 3 | 309 | 491 | 269 | 381 | 634 | 348 | 519 | 793 | 437 |
| 8 | 1 | 313 | 407 | 207 | 387 | 530 | 263 | 529 | 672 | 331 |
| | 2 | 323 | 465 | 238 | 397 | 607 | 309 | 540 | 766 | 391 |
| | 3 | 332 | 509 | 274 | 407 | 663 | 356 | 551 | 838 | 450 |
| 10 | 1 | 333 | 434 | 213 | 410 | 571 | 273 | 558 | 727 | 343 |
| | 2 | 343 | 489 | 244 | 420 | 640 | 317 | 569 | 813 | 403 |
| | 3 | 352 | 530 | 279 | 430 | 694 | 363 | 580 | 880 | 459 |
| 15 | 1 | 349 | 502 | 225 | 445 | 646 | 291 | 623 | 808 | 366 |
| | 2 | 359 | 548 | 256 | 456 | 706 | 334 | 634 | 884 | 424 |
| | 3 | 368 | 586 | 289 | 466 | 755 | 378 | 646 | 945 | 479 |
| 20 | 1 | 345 | 569 | 235 | 439 | 734 | 306 | 614 | 921 | 387 |
| | 2 | 355 | 610 | 266 | 450 | 787 | 348 | 627 | 986 | 443 |
| | 3 | 365 | 644 | 298 | 461 | 831 | 391 | 639 | 1042 | 496 |
| 30 | 1 | 338 | 665 | 250 | 430 | 864 | 330 | 600 | 1089 | 421 |
| | 2 | 348 | 699 | 282 | 442 | 908 | 372 | 613 | 1145 | 473 |
| | 3 | 358 | 729 | 312 | 452 | 946 | 412 | 626 | 1193 | 524 |
| 50 | 1 | 328 | 778 | 287 | 417 | 1022 | 383 | 582 | 1302 | 492 |
| | 2 | 339 | 806 | 320 | 429 | 1058 | 425 | 596 | 1346 | 545 |
| | 3 | 349 | 831 | 351 | 440 | 1090 | 466 | 610 | 1386 | 597 |
| 100 | 1 | 315 | 875 | 328 | 402 | 1181 | 444 | 560 | 1537 | 580 |
| | 2 | 326 | 899 | 361 | 415 | 1210 | 488 | 575 | 1570 | 634 |
| | 3 | 337 | 921 | 392 | 427 | 1238 | 529 | 589 | 1604 | 687 |

| | COMMON VENT CAPACITY | | | | | | | | |
|----------------------------|---|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | MINIMUM INTERNAL AREA OF MASONRY CHIMNEY FLUE (square inches) | | | | | | | | |
| | 63 | | | 78 | | | 113 | | |
| | COMBINED APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT H (feet) | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT | FAN +FAN | FAN +NAT | NAT +NAT |
| 6 | NA | 455 | 187 | NA | 579 | 245 | NA | 846 | NA |
| 8 | NA | 497 | 217 | NA | 633 | 277 | 1136 | 928 | 405 |
| 10 | NA | 532 | 234 | 771 | 680 | 300 | 1216 | 1000 | 450 |
| 15 | 677 | 602 | 280 | 866 | 772 | 360 | 1359 | 1139 | 540 |
| 20 | 765 | 661 | 321 | 947 | 849 | 415 | 1495 | 1264 | 640 |
| 30 | 808 | 739 | 377 | 1052 | 957 | 490 | 1682 | 1447 | 740 |
| 50 | NA | 821 | 456 | 1152 | 1076 | 600 | 1879 | 1672 | 910 |
| 100 | NA | NA | 494 | NA | NA | 663 | 2006 | 1885 | 1046 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

WATER HEATERS

TABLE 510.2(5)
SINGLE-WALL METAL PIPE OR TYPE B ASBESTOS-CEMENT VENT [NFPA 54: TABLE 13.2(e)]*

| | | NUMBER OF APPLIANCES: TWO OR MORE | | | | | |
|---|-------------------------------|---|----|-----|-----|-----|-----|
| | | APPLIANCE TYPE: DRAFT HOOD-EQUIPMENT | | | | | |
| | | APPLIANCE VENT CONNECTION: DIRECT TO PIPE OR VENT | | | | | |
| | | VENT CONNECTOR CAPACITY | | | | | |
| | | VENT CONNECTOR DIAMETER – D (inch) | | | | | |
| TOTAL VENT HEIGHT H (feet) | CONNECTOR RISE R (feet) | 3 | 4 | 5 | 6 | 7 | 8 |
| APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | |
| 6-8 | 1 | 21 | 40 | 68 | 102 | 146 | 205 |
| | 2 | 28 | 53 | 86 | 124 | 178 | 235 |
| | 3 | 34 | 61 | 98 | 147 | 204 | 275 |
| 15 | 1 | 23 | 44 | 77 | 117 | 179 | 240 |
| | 2 | 30 | 56 | 92 | 134 | 194 | 265 |
| | 3 | 35 | 64 | 102 | 155 | 216 | 298 |
| 30 and up | 1 | 25 | 49 | 84 | 129 | 190 | 270 |
| | 2 | 31 | 58 | 97 | 145 | 211 | 295 |
| | 3 | 36 | 68 | 107 | 164 | 232 | 321 |

| COMMON VENT CAPACITY | | | | | | | |
|--|----|-----|-----|-----|-----|-----|------|
| COMMON VENT DIAMETER – D (inch) | | | | | | | |
| TOTAL VENT HEIGHT H (feet) | 4 | 5 | 6 | 7 | 8 | 10 | 12 |
| COMBINED APPLIANCE INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | |
| 6 | 48 | 78 | 111 | 155 | 205 | 320 | NA |
| 8 | 55 | 89 | 128 | 175 | 234 | 365 | 505 |
| 10 | 59 | 95 | 136 | 190 | 250 | 395 | 560 |
| 15 | 71 | 115 | 168 | 228 | 305 | 480 | 690 |
| 20 | 80 | 129 | 186 | 260 | 340 | 550 | 790 |
| 30 | NA | 147 | 215 | 300 | 400 | 650 | 940 |
| 50 | NA | NA | NA | 360 | 490 | 810 | 1190 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

TABLE 510.2(6)
EXTERIOR MASONRY CHIMNEY [NFPA 54: TABLE 13.2(f)]*

| | | | | NUMBER OF APPLIANCES: | | TWO OR MORE | | |
|--|--|----|-----|----------------------------|-----|------------------------------|-----|-----|
| | | | | APPLIANCE TYPE: | | NAT + NAT | | |
| | | | | APPLIANCE VENT CONNECTION: | | TYPE B DOUBLE-WALL CONNECTOR | | |
| COMBINED APPLIANCE MAXIMUM INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT H (feet) | INTERNAL AREA OF CHIMNEY (square inches) | | | | | | | |
| | 12 | 19 | 28 | 38 | 50 | 63 | 78 | 113 |
| 6 | 25 | 46 | 71 | 103 | 143 | 188 | 246 | NA |
| 8 | 28 | 53 | 82 | 119 | 163 | 218 | 278 | 408 |
| 10 | 31 | 56 | 90 | 131 | 177 | 236 | 302 | 454 |
| 15 | NA | 67 | 106 | 152 | 212 | 283 | 365 | 546 |
| 20 | NA | NA | NA | NA | NA | 325 | 419 | 648 |
| 30 | NA | NA | NA | NA | NA | NA | 496 | 749 |
| 50 | NA | NA | NA | NA | NA | NA | NA | 922 |
| 100 | NA | NA | NA | NA | NA | NA | NA | NA |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

TABLE 510.2(7)
EXTERIOR MASONRY CHIMNEY [NFPA 54: TABLE 13.2(g)]^{1, 2}

| | | | | NUMBER OF APPLIANCES: | | TWO OR MORE | | |
|--|--|----|----|----------------------------|----|------------------------------|-----|-----|
| | | | | APPLIANCE TYPE: | | NAT + NAT | | |
| | | | | APPLIANCE VENT CONNECTION: | | TYPE B DOUBLE-WALL CONNECTOR | | |
| MINIMUM ALLOWABLE INPUT RATING OF SPACE-HEATING APPLIANCE IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | INTERNAL AREA OF CHIMNEY (square inches) | | | | | | | |
| | 12 | 19 | 28 | 38 | 50 | 63 | 78 | 113 |
| Local 99% winter design temperature: 37°F or greater | | | | | | | | |
| 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | NA |
| 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 10 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15 | NA | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 20 | NA | NA | NA | NA | NA | 184 | 0 | 0 |
| 30 | NA | NA | NA | NA | NA | 393 | 334 | 0 |
| 50 | NA | NA | NA | NA | NA | NA | NA | 579 |
| 100 | NA | NA | NA | NA | NA | NA | NA | NA |
| Local 99% winter design temperature: 27°F to 36°F | | | | | | | | |
| 6 | 0 | 0 | 68 | NA | NA | 180 | 212 | NA |
| 8 | 0 | 0 | 82 | NA | NA | 187 | 214 | 263 |
| 10 | 0 | 51 | NA | NA | NA | 201 | 225 | 265 |
| 15 | NA | NA | NA | NA | NA | 253 | 274 | 305 |
| 20 | NA | NA | NA | NA | NA | 307 | 330 | 362 |
| 30 | NA | NA | NA | NA | NA | NA | 445 | 485 |
| 50 | NA | NA | NA | NA | NA | NA | NA | 763 |
| 100 | NA | NA | NA | NA | NA | NA | NA | NA |
| Local 99% winter design temperature: 17°F to 26°F | | | | | | | | |
| 6 | NA | NA | NA | NA | NA | NA | NA | NA |
| 8 | NA | NA | NA | NA | NA | NA | 264 | 352 |
| 10 | NA | NA | NA | NA | NA | NA | 278 | 358 |
| 15 | NA | NA | NA | NA | NA | NA | 331 | 398 |
| 20 | NA | NA | NA | NA | NA | NA | 387 | 457 |
| 30 | NA | NA | NA | NA | NA | NA | NA | 581 |
| 50 | NA | NA | NA | NA | NA | NA | NA | 862 |
| 100 | NA | NA | NA | NA | NA | NA | NA | NA |
| Local 99% winter design temperature: 5°F to 16°F | | | | | | | | |
| 6 | NA | NA | NA | NA | NA | NA | NA | NA |
| 8 | NA | NA | NA | NA | NA | NA | NA | NA |
| 10 | NA | NA | NA | NA | NA | NA | NA | 430 |
| 15 | NA | NA | NA | NA | NA | NA | NA | 485 |
| 20 | NA | NA | NA | NA | NA | NA | NA | 547 |
| 30 | NA | NA | NA | NA | NA | NA | NA | 682 |
| 50 | NA | NA | NA | NA | NA | NA | NA | NA |
| 100 | NA | NA | NA | NA | NA | NA | NA | NA |
| Local 99% winter design temperature: 4°F or lower Not recommended for any vent configurations | | | | | | | | |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m², °C = (°F-32)/1.8

Notes:

¹ See Figure 510.1.2(6) for a map showing local 99 percent winter design temperatures in the United States.

² NA: Not applicable.

WATER HEATERS

TABLE 510.2(8)
EXTERIOR MASONRY CHIMNEY [NFPA 54: TABLE 13.2(h)]*

| | | | | | | | | |
|--|--|-----|-----|----------------------------|-----|------------------------------|------|------|
| | | | | NUMBER OF APPLIANCES: | | TWO OR MORE | | |
| | | | | APPLIANCE TYPE: | | FAN + NAT | | |
| | | | | APPLIANCE VENT CONNECTION: | | TYPE B DOUBLE-WALL CONNECTOR | | |
| COMBINED APPLIANCE MAXIMUM INPUT RATING IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT <i>H</i> (feet) | INTERNAL AREA OF CHIMNEY (square inches) | | | | | | | |
| | 12 | 19 | 28 | 38 | 50 | 63 | 78 | 113 |
| 6 | 74 | 119 | 178 | 257 | 351 | 458 | 582 | 853 |
| 8 | 80 | 130 | 193 | 279 | 384 | 501 | 636 | 937 |
| 10 | 84 | 138 | 207 | 299 | 409 | 538 | 686 | 1010 |
| 15 | NA | 152 | 233 | 334 | 467 | 611 | 781 | 1156 |
| 20 | NA | NA | 250 | 368 | 508 | 668 | 858 | 1286 |
| 30 | NA | NA | NA | 404 | 564 | 747 | 969 | 1473 |
| 50 | NA | NA | NA | NA | NA | 831 | 1089 | 1692 |
| 100 | NA | NA | NA | NA | NA | NA | NA | 1921 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m²

* NA: Not applicable.

TABLE 510.2(9)
EXTERIOR MASONRY CHIMNEY [NFPA 54: TABLE 13.2(i)]^{1, 2}

| | | | NUMBER OF APPLIANCES: TWO OR MORE | | | | | |
|--|--|-----|---|-----|-----|-----|-----|------|
| | | | APPLIANCE TYPE: FAN + NAT | | | | | |
| | | | APPLIANCE VENT CONNECTION: TYPE B DOUBLE-WALL CONNECTOR | | | | | |
| MINIMUM ALLOWABLE INPUT RATING OF SPACE-HEATING APPLIANCE IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| VENT HEIGHT H (feet) | INTERNAL AREA OF CHIMNEY (square inches) | | | | | | | |
| | 12 | 19 | 28 | 38 | 50 | 63 | 78 | 113 |
| Local 99% winter design temperature: 37°F or greater | | | | | | | | |
| 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 10 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15 | NA | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 20 | NA | NA | 123 | 190 | 249 | 184 | 0 | 0 |
| 30 | NA | NA | NA | 334 | 398 | 393 | 334 | 0 |
| 50 | NA | NA | NA | NA | NA | 714 | 707 | 579 |
| 100 | NA | NA | NA | NA | NA | NA | NA | 1600 |
| Local 99% winter design temperature: 27°F to 36°F | | | | | | | | |
| 6 | 0 | 0 | 68 | 116 | 156 | 180 | 212 | 266 |
| 8 | 0 | 0 | 82 | 127 | 167 | 187 | 214 | 263 |
| 10 | 0 | 51 | 97 | 141 | 183 | 201 | 225 | 265 |
| 15 | NA | 111 | 142 | 183 | 233 | 253 | 274 | 305 |
| 20 | NA | NA | 187 | 230 | 284 | 307 | 330 | 362 |
| 30 | NA | NA | NA | 330 | 319 | 419 | 445 | 485 |
| 50 | NA | NA | NA | NA | NA | 672 | 705 | 763 |
| 100 | NA | NA | NA | NA | NA | NA | NA | 1554 |
| Local 99% winter design temperature: 17°F to 26°F | | | | | | | | |
| 6 | 0 | 55 | 99 | 141 | 182 | 215 | 259 | 349 |
| 8 | 52 | 74 | 111 | 154 | 197 | 226 | 264 | 352 |
| 10 | NA | 90 | 125 | 169 | 214 | 245 | 278 | 358 |
| 15 | NA | NA | 167 | 212 | 263 | 296 | 331 | 398 |
| 20 | NA | NA | 212 | 258 | 316 | 352 | 387 | 457 |
| 30 | NA | NA | NA | 362 | 429 | 470 | 507 | 581 |
| 50 | NA | NA | NA | NA | NA | 723 | 766 | 862 |
| 100 | NA | NA | NA | NA | NA | NA | NA | 1669 |
| Local 99% winter design temperature: 5°F to 16°F | | | | | | | | |
| 6 | NA | 78 | 121 | 166 | 214 | 252 | 301 | 416 |
| 8 | NA | 94 | 135 | 182 | 230 | 269 | 312 | 423 |
| 10 | NA | 111 | 149 | 198 | 250 | 289 | 331 | 430 |
| 15 | NA | NA | 193 | 247 | 305 | 346 | 393 | 485 |
| 20 | NA | NA | NA | 293 | 360 | 408 | 450 | 547 |
| 30 | NA | NA | NA | 377 | 450 | 531 | 580 | 682 |
| 50 | NA | NA | NA | NA | NA | 797 | 853 | 972 |
| 100 | NA | NA | NA | NA | NA | NA | NA | 1833 |
| Local 99% winter design temperature: -10°F to 4°F | | | | | | | | |
| 6 | NA | NA | 145 | 196 | 249 | 296 | 349 | 484 |
| 8 | NA | NA | 159 | 213 | 269 | 320 | 371 | 494 |
| 10 | NA | NA | 175 | 231 | 292 | 339 | 397 | 513 |
| 15 | NA | NA | NA | 283 | 351 | 404 | 457 | 586 |
| 20 | NA | NA | NA | 333 | 408 | 468 | 528 | 650 |
| 30 | NA | NA | NA | NA | NA | 603 | 667 | 805 |
| 50 | NA | NA | NA | NA | NA | NA | 955 | 1003 |
| 100 | NA | NA | NA | NA | NA | NA | NA | NA |
| Local 99% winter design temperature: -11°F or lower Not recommended for any vent configurations | | | | | | | | |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 square inch = 0.000645 m², °C = (°F-32)/1.8

Notes:

¹ See Figure 510.1.2(6) for a map showing local 99 percent winter design temperatures in the United States.

² NA: Not applicable.

CHAPTER 6

WATER SUPPLY AND DISTRIBUTION

601.0 General.

601.1 Applicability. This chapter shall govern the materials, design, and installation of water supply systems, including methods and devices used for backflow prevention.

» **601.2 Hot and Cold Water Required.** Except where not deemed necessary for safety or sanitation by the Authority Having Jurisdiction, each plumbing fixture shall be provided with an adequate supply of potable running water piped thereto in an approved manner, so arranged as to flush and keep it in a clean and sanitary condition without danger of backflow or cross-connection. Water closets and urinals shall be flushed by means of an approved flush tank or flushometer valve.

Exception: Listed fixtures that do not require water for their operation and are not connected to the water supply.

In occupancies where plumbing fixtures are installed for private use, hot water shall be required for bathing, washing, laundry, cooking purposes, dishwashing or maintenance. In occupancies where plumbing fixtures are installed for public use, hot water shall be required for bathing and washing purposes. This requirement shall not supersede the requirements for individual temperature control limitations for public lavatories and public and private bidets, bathtubs, whirlpool bathtubs, and shower control valves.

» **601.3 Identification of a Potable and Nonpotable Water System.** In buildings where potable water and nonpotable water systems are installed, each system shall be clearly identified in accordance with Section 601.3.1 through Section 601.3.5.

» **601.3.1 Potable Water.** Green background with white lettering.

» **601.3.2 Color and Information.** Each system shall be identified with a colored pipe or band and coded with paints, wraps, and materials compatible with the piping.

Except as required in Section 601.3.3, nonpotable water systems shall have a yellow background with black uppercase lettering, with the words "CAUTION: NONPOTABLE WATER, DO NOT DRINK." Each nonpotable system shall be identified to designate the liquid being conveyed, and the direction of normal flow shall be clearly shown. The minimum size of the letters and length of the color field shall comply with Table 601.3.2.

The background color and required information shall be indicated every 20 feet (6096 mm) but not less than once per room, and shall be visible from the floor level.

TABLE 601.3.2
MINIMUM LENGTH OF COLOR FIELD AND SIZE OF LETTERS

| OUTSIDE DIAMETER OF PIPE OR COVERING (inches) | MINIMUM LENGTH OF COLOR FIELD (inches) | MINIMUM SIZE OF LETTERS (inches) |
|---|--|----------------------------------|
| ½ to 1¼ | 8 | ½ |
| 1½ to 2 | 8 | ¾ |
| 2½ to 6 | 12 | 1¼ |
| 8 to 10 | 24 | 2½ |
| Over 10 | 32 | 3½ |

For SI units: 1 inch = 25.4 mm

601.3.3 Alternate Water Sources. Alternate water source systems shall have a purple (Pantone color No. 512, 522C, or equivalent) background with uppercase lettering and shall be field or factory marked as follows:

- (1) Gray water systems shall be marked in accordance with this section with the words "CAUTION: NONPOTABLE GRAY WATER, DO NOT DRINK" in black letters.
- (2) Reclaimed (recycled) water systems shall be marked in accordance with this section with the words: "CAUTION: NONPOTABLE RECLAIMED (RECYCLED) WATER, DO NOT DRINK" in black letters.
- (3) On-site treated water systems shall be marked in accordance with this section with the words: "CAUTION: ON-SITE TREATED NONPOTABLE WATER, DO NOT DRINK" in black letters.
- (4) Rainwater catchment systems shall be marked in accordance with this section with the words: "CAUTION: NONPOTABLE RAINWATER WATER, DO NOT DRINK" in black letters.

601.3.4 Fixtures. Where vacuum breakers or backflow preventers are installed with fixtures listed in Table 1701.1, identification of the discharge side shall be permitted to be omitted.

601.3.5 Outlets. Each outlet on the nonpotable water line that is used for special purposes shall be posted with black uppercase lettering as follows: "CAUTION: NONPOTABLE WATER, DO NOT DRINK."

602.0 Unlawful Connections.

602.1 Prohibited Installation. No installation of potable water supply piping, or part thereof, shall be made in such a manner that it will be possible for used, unclean, polluted, or contaminated water, mixtures, or substances to enter a portion of such piping from a tank, receptor, equipment, or

plumbing fixture by reason of backsiphonage, suction, or other cause, either during normal use and operation thereof, or where such tank, receptor, equipment, or plumbing fixture is flooded or subject to pressure exceeding the operating pressure in the hot or cold water piping.

602.2 Cross-Contamination. No person shall make a connection or allow one to exist between pipes or conduits carrying domestic water supplied by a public or private building supply system, and pipes, conduits, or fixtures containing or carrying water from any other source or containing or carrying water that has been used for a purpose whatsoever, or piping carrying chemicals, liquids, gases, or substances whatsoever, unless there is provided a backflow prevention device approved for the potential hazard and maintained in accordance with this code. Each point of use shall be separately protected where potential cross-contamination of individual units exists.

602.3 Backflow Prevention. No plumbing fixture, device, or construction shall be installed or maintained, or shall be connected to a domestic water supply, where such installation or connection provides a possibility of polluting such water supply or cross-connection between a distributing system of water for drinking and domestic purposes and water that becomes contaminated by such plumbing fixture, device, or construction unless there is provided a backflow prevention device approved for the potential hazard.

602.4 Approval by Authority. No water piping supplied by a private water supply system shall be connected to any other source of supply without the approval of the Authority Having Jurisdiction, Health Department, or other department having jurisdiction.

603.0 Cross-Connection Control.

603.1 General. Cross-connection control shall be provided in accordance with the provisions of this chapter.

No person shall install a water-operated equipment or mechanism, or use a water-treating chemical or substance, where it is found that such equipment, mechanism, chemical, or substance causes pollution or contamination of the domestic water supply. Such equipment or mechanism shall be permitted where equipped with an approved backflow prevention device or assembly.

603.2 Approval of Devices or Assemblies. Before a device or an assembly is installed for the prevention of backflow, it shall have first been approved by the Authority Having Jurisdiction. Devices or assemblies shall be tested in accordance with recognized standards or other standards acceptable to the Authority Having Jurisdiction. Backflow prevention devices and assemblies shall comply with Table 603.2, except for specific applications and provisions as stated in Section 603.5.1 through Section 603.5.20.

Devices or assemblies installed in a potable water supply system for protection against backflow shall be maintained in good working condition by the person or persons having control of such devices or assemblies. Such devices or assemblies shall be tested at the time of installation, repair, or relocation and not less than on an annual schedule

thereafter, or more often where required by the Authority Having Jurisdiction. Where found to be defective or inoperative, the device or assembly shall be repaired or replaced. No device or assembly shall be removed from use or relocated or other device or assembly substituted, without the approval of the Authority Having Jurisdiction.

Testing or maintenance shall be performed by a certified backflow assembly tester or repairer in accordance with ASSE Series 5000 or otherwise approved by the Authority Having Jurisdiction.

603.3 Backflow Prevention Devices, Assemblies, and Methods. Backflow prevention devices, assemblies, and methods shall comply with Section 603.3.1 through Section 603.3.9.

603.3.1 Air Gap. The minimum air gap to afford backflow protection shall be in accordance with Table 603.3.1.

603.3.2 Atmospheric Vacuum Breaker (AVB). An atmospheric vacuum breaker consists of a body, a checking member, and an atmospheric port.

603.3.3 Hose Connection Backflow Preventer. A hose connection backflow preventer consists of two independent check valves with an independent atmospheric vent between and a means of field testing and draining.

603.3.4 Double Check Valve Backflow Prevention Assembly (DC). A double check valve backflow prevention assembly consists of two independently acting internally loaded check valves, four properly located test cocks, and two isolation valves.

603.3.5 Pressure Vacuum Breaker Backflow Prevention Assembly (PVB). A pressure vacuum breaker backflow prevention assembly consists of a loaded air inlet valve, an internally loaded check valve, two properly located test cocks, and two isolation valves. This device shall be permitted to be installed indoors where provisions for spillage are provided.

603.3.6 Spill-Resistant Pressure Vacuum Breaker (SVB). A pressure-type vacuum breaker backflow prevention assembly consists of one check valve force-loaded closed and an air inlet vent valve force-loaded open to atmosphere, positioned downstream of the check valve, and located between and including two tightly closing shutoff valves and test cocks.

603.3.7 Reduced-Pressure Principle Backflow Prevention Assembly (RP). A reduced-pressure principle backflow prevention assembly consists of two independently acting internally loaded check valves, a differential pressure-relief valve, four properly located test cocks, and two isolation valves.

603.3.8 Double Check Detector Fire Protection Backflow Prevention Assembly. A double check valve backflow prevention assembly with a parallel detector assembly consisting of a water meter and a double check valve backflow prevention assembly (DC).

TABLE 603.2
BACKFLOW PREVENTION DEVICES, ASSEMBLIES, AND METHODS

| DEGREE OF HAZARD | | | | | | |
|--|---|---------------------------|-------------------|--------------------------------|-------------------|--|
| DEVICE, ASSEMBLY, OR METHOD ¹ | APPLICABLE STANDARDS | POLLUTION (LOW HAZARD) | | CONTAMINATION (HIGH HAZARD) | | INSTALLATION ^{2,3} |
| | | BACK- SIPHONAGE | BACK- PRESSURE | BACK- SIPHONAGE | BACK- PRESSURE | |
| Air gap | ASME A112.1.2 | X | — | X | — | See Table 603.3.1 in this chapter. |
| Air gap fittings for use with plumbing fixtures, appliances and appurtenances | ASME A112.1.3 | X | — | X | — | Air gap fitting is a device with an internal air gap and typical installation includes plumbing fixtures, appliances and appurtenances. The critical level shall not be installed below the flood level rim. |
| Atmospheric vacuum breaker (consists of a body, checking member and atmospheric port) | ASSE 1001 or CSA B64.1.1 | X | — | X | — | Upright position. No valve downstream. Minimum of 6 inches or listed distance above all downstream piping and flood-level rim of receptor. ^{4,5} |
| Antisiphon fill valve (ball- cocks) for gravity water closet flush tanks and uri- nal tanks | ASSE 1002 or CSA B125.3 | X | — | X | — | Installation on gravity water closet flush tank and urinal tanks with the fill valve installed with the critical level not less than 1 inch above the opening of the overflow pipe. ^{4,5} |
| Vacuum breaker wall hydrants, hose bibbs, freeze resistant, automatic draining type | ASSE 1019 or CSA B64.2.1.1 | X | — | X | — | Installation includes wall hydrants and hose bibbs. Such devices are not for use under continuous pressure conditions (means of shutoff downstream of device is prohibited). ^{4,5} |
| Hose connection vacuum breakers | ASSE 1011 | X | — | X | — | Such devices are not for use under continuous pressure conditions. No valve downstream. ^{4,6} |
| Hose connection backflow preventers | ASSE 1052 | X | — | X | — | Such devices are not for use under continuous pressure conditions. ^{4,6} |
| Dual check backflow pre- venter wall hydrants, freeze resistant | ASSE 1053 | X | — | X | — | Such devices are not for use under continuous pressure conditions. ⁴ |
| Freeze resistant sanitary yard hydrants | ASSE 1057 | X | — | X | — | Such devices are not for use under continuous pressure conditions. ⁴ |
| Backflow preventer for Carbonated Beverage Dis- pensers (two independent check valves with a vent to the atmosphere) | ASSE 1022 | X | — | — | — | Installation includes carbonated beverage machines or dispensers. These devices operate under intermittent or continuous pressure conditions. |
| Spill-Resistant Pressure Vacuum Breaker (single check valve with air inlet vent and means of field testing) | ASSE 1056 | X | — | X | — | Upright position. Minimum of 12 inches or listed distance above all downstream piping and flood-level rim of receptor. ⁵ |
| Double Check Valve Back- flow Prevention Assembly (two independent check valves and means of field testing) | ASSE 1015; AWWA C510; CSA B64.5 or CSA B64.5.1 | X | X | — | — | Horizontal unless otherwise listed. Access and clearance shall be in accordance with the manufacturer's instructions, and not less than a 12 inch clearance at bottom for maintenance. May need platform/ladder for test and repair. Does not discharge water. |

TABLE 603.2
BACKFLOW PREVENTION DEVICES, ASSEMBLIES, AND METHODS (continued)

| DEGREE OF HAZARD | | | | | | |
|--|--|------------------------|---------------|-----------------------------|---------------|--|
| DEVICE, ASSEMBLY, OR METHOD ¹ | APPLICABLE STANDARDS | POLLUTION (LOW HAZARD) | | CONTAMINATION (HIGH HAZARD) | | INSTALLATION ^{2,3} |
| | | BACK-SIPHONAGE | BACK-PRESSURE | BACK-SIPHONAGE | BACK-PRESSURE | |
| Double Check Detector Fire Protection Backflow Prevention Assembly (two independent check valves with a parallel detector assembly consisting of a water meter and a double check valve backflow prevention assembly and means of field testing) | ASSE 1048 | X | X | — | — | Horizontal unless otherwise listed. Access and clearance shall be in accordance with the manufacturer's instructions, and not less than a 12 inch clearance at bottom for maintenance. May need platform/ladder for test and repair. Does not discharge water. Installation includes a fire protection system and is designed to operate under continuous pressure conditions. |
| Pressure Vacuum Breaker Backflow Prevention Assembly (loaded air inlet valve, internally loaded check valve and means of field testing) | ASSE 1020 or CSA B64.1.2 | X | — | X | — | Upright position. May have valves downstream. Minimum of 12 inches above all downstream piping and flood-level rim of receptor. May discharge water. |
| Reduced Pressure Principle Backflow Prevention Assembly (two independently acting loaded check valves, a differential pressure relief valve and means of field testing) | ASSE 1013; AWWA C511; CSA B64.4 or CSA B64.4.1 | X | X | X | X | Horizontal unless otherwise listed. Access and clearance shall be in accordance with the manufacturer's instructions, and not less than a 12 inch clearance at bottom for maintenance. May need platform/ladder for test and repair. May discharge water. |
| Reduced Pressure Detector Fire Protection Backflow Prevention Assembly (two independently acting loaded check valves, a differential pressure relief valve, with a parallel detector assembly consisting of a water meter and a reduced-pressure principle backflow prevention assembly, and means of field testing) | ASSE 1047 | X | X | X | X | Horizontal unless otherwise listed. Access and clearance shall be in accordance with the manufacturer's instructions, and not less than a 12 inch clearance at bottom for maintenance. May need platform/ladder for test and repair. May discharge water. Installation includes a fire protection system and is designed to operate under continuous pressure conditions. |

For SI units: 1 inch = 25.4 mm

Notes:

- ¹ See description of devices and assemblies in this chapter.
- ² Installation in pit or vault requires previous approval by the Authority Having Jurisdiction.
- ³ Refer to general and specific requirement for installation.
- ⁴ Not to be subjected to operating pressure for more than 12 hours in a 24 hour period.
- ⁵ For deck-mounted and equipment-mounted vacuum breaker, see Section 603.5.13.
- ⁶ Shall be installed in accordance with Section 603.5.7.

TABLE 603.3.1
MINIMUM AIR GAPS FOR WATER DISTRIBUTION⁴

| FIXTURES | WHERE NOT AFFECTED BY SIDEWALLS¹ (inches) | WHERE AFFECTED BY SIDEWALLS² (inches) |
|---|---|---|
| Effective openings ³ not greater than ½ of an inch in diameter | 1 | 1½ |
| Effective openings ³ not greater than ¾ of an inch in diameter | 1½ | 2¼ |
| Effective openings ³ not greater than 1 inch in diameter | 2 | 3 |
| Effective openings ³ greater than 1 inch in diameter | Two times the diameter of effective opening | Three times the diameter of effective opening |

For SI units: 1 inch = 25.4 mm

Notes:

- ¹ Sidewalls, ribs, or similar obstructions do not affect air gaps where spaced from the inside edge of the spout opening a distance exceeding three times the diameter of the effective opening for a single wall, or a distance exceeding four times the effective opening for two intersecting walls.
- ² Vertical walls, ribs, or similar obstructions extending from the water surface to or above the horizontal plane of the spout opening other than specified in Footnote 1 above. The effect of three or more such vertical walls or ribs has not been determined. In such cases, the air gap shall be measured from the top of the wall.
- ³ The effective opening shall be the minimum cross-sectional area at the seat of the control valve or the supply pipe or tubing that feeds the device or outlet. Where two or more lines supply one outlet, the effective opening shall be the sum of the cross-sectional areas of the individual supply lines or the area of the single outlet, whichever is smaller.
- ⁴ Air gaps less than 1 inch (25.4 mm) shall be approved as a permanent part of a listed assembly that has been tested under actual backflow conditions with vacuums of 0 to 25 inches of mercury (85 kPa).

603.3.9 Reduced Pressure Detector Fire Protection Backflow Prevention Assembly. A reduced-pressure principle backflow prevention assembly with a parallel detector assembly consisting of a water meter and a reduced-pressure principle backflow prevention assembly (RP).

603.4 General Requirements. Assemblies shall comply with listed standards and be acceptable to the Authority Having Jurisdiction, with jurisdiction over the selection and installation of backflow prevention assemblies.

603.4.1 Backflow Prevention Valve. Where more than one backflow prevention valve is installed on a single premise, and the valves are installed in one location, each separate valve shall be permanently identified by the permittee in a manner satisfactory to the Authority Having Jurisdiction.

603.4.2 Testing. The premise owner or responsible person shall have the backflow prevention assembly tested by a certified backflow assembly tester at the time of installation, repair, or relocation and not less than on an annual schedule thereafter, or more often where required by the Authority Having Jurisdiction. The periodic testing shall be performed in accordance with the procedures referenced in ASSE Series 5000 by a tester qualified in accordance with those standards.

603.4.3 Access and Clearance. Access and clearance shall be provided for the required testing, maintenance, and repair. Access and clearance shall be in accordance with the manufacturer's instructions, and not less than 12 inches (305 mm) between the lowest portion of the assembly and grade, floor, or platform. Installations elevated that exceed 5 feet (1524 mm)

above the floor or grade shall be provided with a permanent platform capable of supporting a tester or maintenance person.

603.4.4 Connections. Direct connections between potable water piping and sewer-connected wastes shall not be permitted to exist under any condition with or without backflow protection. Where potable water is discharged to the drainage system, it shall be by means of an approved air gap of two pipe diameters of the supply inlet, but in no case shall the gap be less than 1 inch (25.4 mm). Connection shall be permitted to be made to the inlet side of a trap provided that an approved vacuum breaker is installed not less than 6 inches (152 mm), or the distance according to the device's listing, above the flood-level rim of such trapped fixture, so that at no time will such device be subjected to backpressure.

603.4.5 Hot Water Backflow Preventers. Backflow preventers for hot water exceeding 110°F (43°C) shall be a type designed to operate at temperatures exceeding 110°F (43°C) without rendering a portion of the assembly inoperative.

603.4.6 Integral Backflow Preventers. Fixtures, appliances, or appurtenances with integral backflow preventers or integral air gaps manufactured as a unit shall be installed in accordance with their listing requirements and the manufacturer's installation instructions.

603.4.7 Freeze Protection. In cold climate areas, backflow assemblies and devices shall be protected from freezing with an outdoor enclosure in accordance with ASSE 1060 or by a method acceptable to the Authority Having Jurisdiction.

603.4.8 Drain Lines. Drain lines serving backflow devices or assemblies shall be sized in accordance with the discharge rates of the manufacturer's flow charts of such devices or assemblies.

603.4.9 Prohibited Locations. Backflow prevention devices with atmospheric vents or ports shall not be installed in pits, underground, or submerged locations. Backflow preventers shall not be located in an area containing fumes that are toxic, poisonous, or corrosive.

603.5 Specific Requirements. Specific requirements for backflow prevention shall comply with Section 603.5.1 through Section 603.5.20.

603.5.1 Atmospheric Vacuum Breaker. Water closet and urinal flushometer valves shall be protected against backflow by an approved backflow prevention assembly, device, or method. Where the valves are equipped with an atmospheric vacuum breaker, the vacuum breaker shall be installed on the discharge side of the flushometer valve with the critical level not less than 6 inches (152 mm), or the distance according to its listing, above the overflow rim of a water closet bowl or the highest part of a urinal.

603.5.2 Ballcock. Water closet and urinal tanks shall be equipped with a ballcock. The ballcock shall be installed with the critical level not less than 1 inch (25.4 mm) above the full opening of the overflow pipe. In cases where the ballcock has no hush tube, the bottom of the water supply inlet shall be installed 1 inch (25.4 mm) above the full opening of the overflow pipe.

603.5.3 Backflow Prevention. Water closet flushometer tanks shall be protected against backflow by an approved backflow prevention assembly, device, or method.

603.5.4 Heat Exchangers. Heat exchangers used for heat transfer, heat recovery, or solar heating shall protect the potable water system from being contaminated by the heat-transfer medium. Single-wall heat exchangers used in indirect-fired water heaters shall meet the requirements of Section 505.4.1. Double-wall heat exchangers shall separate the potable water from the heat-transfer medium by providing a space between the two walls that are vented to the atmosphere.

603.5.5 Water Supply Inlets. Water supply inlets to tanks, vats, sumps, swimming pools, and other receptors shall be protected by one of the following means:

- (1) An approved air gap.
- (2) A listed vacuum breaker installed on the discharge side of the last valve with the critical level not less than 6 inches (152 mm) or in accordance with its listing.
- (3) A backflow preventer suitable for the degree of hazard, installed in accordance with the requirements for that type of device or assembly as set forth in this chapter.

603.5.6 Protection from Lawn Sprinklers and Irrigation Systems. Potable water supplies to systems having no pumps or connections for pumping

equipment, and no chemical injection or provisions for chemical injection, shall be protected from backflow by one of the following devices:

- (1) Atmospheric vacuum breaker (AVB)
- (2) Pressure vacuum breaker backflow prevention assembly (PVB)
- (3) Spill-resistant pressure vacuum breaker (SVB)
- (4) Reduced-pressure principle backflow prevention assembly (RP)

603.5.6.1 Systems with Pumps. Where sprinkler and irrigation systems have pumps, connections for pumping equipment, or auxiliary air tanks, or are otherwise capable of creating backpressure, the potable water supply shall be protected by the following type of device where the backflow device is located upstream from the source of backpressure:

- (1) Reduced-pressure principle backflow prevention assembly (RP)

603.5.6.2 Systems with Backflow Devices. Where systems have a backflow device installed downstream from a potable water supply pump or a potable water supply pump connection, the device shall be one of the following:

- (1) Atmospheric vacuum breaker (AVB)
- (2) Pressure vacuum breaker backflow prevention assembly (PVB)
- (3) Spill-resistant pressure vacuum breaker (SVB)
- (4) Reduced-pressure principle backflow prevention assembly (RP)

603.5.6.3 Systems with Chemical Injectors. Where systems include a chemical injector or provisions for chemical injection, the potable water supply shall be protected by a reduced-pressure principle backflow prevention assembly (RP).

603.5.7 Outlets with Hose Attachments. Potable water outlets with hose attachments, other than water heater drains, boiler drains, and clothes washer connections, shall be protected by a nonremovable hose bibb-type backflow preventer, a nonremovable hose bibb-type vacuum breaker, or by an atmospheric vacuum breaker installed not less than 6 inches (152 mm) above the highest point of usage located on the discharge side of the last valve. In climates where freezing temperatures occur, a listed self-draining frost-proof hose bibb with an integral backflow preventer or vacuum breaker shall be used.

603.5.8 Water-Cooled Equipment. Water-cooled compressors, degreasers, or other water-cooled equipment shall be protected by a backflow preventer installed in accordance with the requirements of this chapter. Water-cooled equipment that produces backpressure shall be equipped with the appropriate protection.

603.5.9 Aspirators. Water inlets to water-supplied aspirators shall be equipped with a vacuum breaker installed in accordance with its listing requirements and this chapter. The discharge shall drain through an air gap. Where the tailpiece of a fixture to receive the discharge of an aspirator is used, the air gap shall be located above the flood-level rim of the fixture.

603.5.10 Steam or Hot Water Boilers. Potable water connections to steam or hot water boilers shall be protected from backflow by a double check valve backflow prevention assembly or reduced pressure principle backflow prevention assembly in accordance with Table 603.2. Where chemicals are introduced into the system a reduced pressure principle backflow prevention assembly shall be provided in accordance with Table 603.2.

603.5.11 Nonpotable Water Piping. In cases where it is impractical to correct individual cross-connections on the domestic waterline, the line supplying such outlets shall be considered a nonpotable water line. No drinking or domestic water outlets shall be connected to the nonpotable waterline. Where possible, portions of the nonpotable waterline shall be exposed, and exposed portions shall be properly identified in a manner satisfactory to the Authority Having Jurisdiction. Each outlet on the nonpotable waterline that is permitted to be used for drinking or domestic purposes shall be posted: "CAUTION: NONPOTABLE WATER, DO NOT DRINK."

603.5.12 Beverage Dispensers. Potable water supply to beverage dispensers, carbonated beverage dispensers, or coffee machines shall be protected by an air gap or a vented backflow preventer in accordance with ASSE 1022. For carbonated beverage dispensers, piping material installed downstream of the backflow preventer shall not be affected by carbon dioxide gas.

603.5.13 Deck-Mounted and Equipment-Mounted Vacuum Breakers. Deck-mounted or equipment-mounted vacuum breakers shall be installed in accordance with their listing and the manufacturer's installation instructions, with the critical level not less than 1 inch (25.4 mm) above the flood-level rim.

603.5.14 Protection from Fire Systems. Except as provided under Section 603.5.14.1 and Section 603.5.14.2, potable water supplies to fire protection systems that are normally under pressure, including but not limited to standpipes and automatic sprinkler systems, except in one- or two-family or townhouse residential sprinkler systems, piped in materials approved for potable water distribution systems shall be protected from backpressure and backsiphonage by one of the following testable devices:

- (1) Double check valve backflow prevention assembly (DC)
- (2) Double check detector fire protection backflow prevention assembly
- (3) Reduced pressure principle backflow prevention assembly (RP)

- (4) Reduced pressure detector fire protection backflow prevention assembly

Potable water supplies to fire protection systems that are not normally under pressure shall be protected from backflow and shall be in accordance with the requirements of the appropriate standards referenced in Table 1701.1.

603.5.14.1 Fire Department Connection. <<

Where fire protection systems supplied from a potable water system include a fire department (siamese) connection that is located less than 1700 feet (518.2 m) from a nonpotable water source that is capable of being used by the fire department as a secondary water supply, the potable water supply shall be protected by one of the following:

- (1) Reduced pressure principle backflow prevention assembly (RP)
- (2) Reduced pressure detector fire protection backflow prevention assembly

Nonpotable water sources include fire department vehicles carrying water of questionable quality or water that is treated with antifreeze, corrosion inhibitors, or extinguishing agents.

603.5.14.2 Chemicals. << Where antifreeze, corrosion inhibitors, or other chemicals are added to a fire protection system supplied from a potable water supply, the potable water system shall be protected by one of the following:

- (1) Reduced pressure principle backflow prevention assembly (RP)
- (2) Reduced pressure detector fire protection backflow prevention assembly

603.5.14.3 Hydraulic Design. << Where a backflow device is installed in the potable water supply to a fire protection system, the hydraulic design of the system shall account for the pressure drop through the backflow device. Where such devices are retrofitted for an existing fire protection system, the hydraulics of the sprinkler system design shall be checked to verify that there will be sufficient water pressure available for satisfactory operation of the fire sprinklers.

603.5.15 Health Care or Laboratory Areas. << Vacuum breakers for washer-hose bedpans shall be located not less than 5 feet (1524 mm) above the floor. Hose connections in health care or laboratory areas shall be not less than 6 feet (1829 mm) above the floor.

603.5.16 Special Equipment. << Portable cleaning equipment, dental vacuum pumps, and chemical dispensers shall be protected from backflow by an air gap, an atmospheric vacuum breaker, a spill-resistant vacuum breaker, or a reduced pressure principle backflow preventer.

603.5.17 Potable Water Outlets and Valves. << Potable water outlets, freeze-proof yard hydrants, combination stop-and-waste valves, or other fixtures that incorporate a stop and waste feature that drains into the ground shall not be installed underground.

» **603.5.18 Pure Water Process Systems.** The water supply to a pure water process system, such as dialysis water systems, semiconductor washing systems, and similar process piping systems, shall be protected from backpressure and backsiphonage by a reduced-pressure principle backflow preventer.

» **603.5.18.1 Dialysis Water Systems.** The individual connections of the dialysis related equipment to the dialysis pure water system shall not require additional backflow protection.

» **603.5.19 Plumbing Fixture Fittings.** Plumbing fixture fittings with integral backflow protection shall comply with ASME A112.18.1/CSA B125.1.

» **603.5.20 Swimming Pools, Spas, and Hot Tubs.** Potable water supply to swimming pools, spas, and hot tubs shall be protected by an air gap or a reduced pressure principle backflow preventer in accordance with the following:

- (1) The unit is equipped with a submerged fill line.
- (2) The potable water supply is directly connected to the unit circulation system.

604.0 Materials.

604.1 Pipe, Tube, and Fittings. Pipe, tube, fittings, solvent cements, thread sealants, solders, and flux used in potable water systems intended to supply drinking water shall be in accordance with the requirements of NSF 61.

Where fittings and valves are made from copper alloys containing more than 15 percent zinc by weight, and are used in plastic piping systems, they shall be resistant to dezincification and stress corrosion cracking in accordance with NSF 14.

Materials used in the water supply system, except valves and similar devices, shall be of a like material, except where otherwise approved by the Authority Having Jurisdiction.

Materials for building water piping and building supply piping shall comply with the applicable standards referenced in Table 604.1.

604.2 Lead Content. The maximum allowable lead content in pipes, pipe fittings, plumbing fittings, and fixtures intended to convey or dispense water for human consumption shall be not more than a weighted average of 0.25 percent with respect to the wetted surfaces of pipes, pipe fittings, plumbing fittings, and fixtures. For solder and flux, the lead content shall be not more than 0.2 percent where used in piping systems that convey or dispense water for human consumption.

Exceptions:

- (1) Pipes, pipe fittings, plumbing fittings, fixtures, or backflow preventers used for nonpotable services such as manufacturing, industrial processing, irrigation, outdoor watering, or any other uses where the water is not used for human consumption.
- (2) Flush valves, fill valves, flushometer valves, tub fillers, shower valves, service saddles, or water distribution

main gate valves that are 2 inches (50 mm) in diameter or larger.

604.2.1 Lead Content of Water Supply Pipe and Fittings. Pipes, pipe fittings, valves, and faucets utilized in the water supply system for non-drinking water applications shall have a maximum of 8 percent lead content.

604.3 Copper or Copper Alloy Tube. Copper or copper alloy tube for water piping shall have a weight of not less than Type L. <<

Exception: Type M copper or copper alloy tubing shall be permitted to be used for water piping where piping is aboveground in, or on, a building or underground outside of structures.

604.4 Hard-Drawn Copper or Copper Alloy Tubing. << Hard-drawn copper or copper alloy tubing for water supply and distribution in addition to the required incised marking, shall be marked in accordance with ASTM B88. The colors shall be: Type K, green; Type L, blue; and Type M, red.

604.5 Flexible Connectors. Flexible water connectors shall be installed in readily accessible locations, and where under continuous pressure shall be in accordance with ASME A112.18.6/CSA B125.6. <<

604.6 Cast-Iron Fittings. Cast-iron fittings up to and including 2 inches (50 mm) in size, where used in connection with potable water piping, shall be galvanized. <<

604.7 Malleable Iron Fittings. Malleable iron water fittings shall be galvanized. <<

604.8 Previously Used Piping and Tubing. Piping and tubing that has previously been used for a purpose other than for potable water systems shall not be used. <<

604.9 Epoxy Coating. Epoxy coating used on existing, underground steel building supply piping shall be in accordance with NSF 61 and AWWA C210. <<

604.10 Plastic Materials. Approved plastic materials shall be permitted to be used in building supply piping, provided that where metal building supply piping is used for electrical grounding purposes, replacement piping therefore shall be of like materials. <<

Exception: Where a grounding system acceptable to the Authority Having Jurisdiction is installed, inspected, and approved, metallic pipe shall be permitted to be replaced with nonmetallic pipe.

604.10.1 Tracer Wire. Plastic materials for building supply piping outside underground shall have a blue insulated copper tracer wire or other approved conductor installed adjacent to the piping. Access shall be provided to the tracer wire or the tracer wire shall terminate aboveground at each end of the nonmetallic piping. The tracer wire size shall be not less than 18 AWG and the insulation type shall be suitable for direct burial.

604.11 Solder. Solder shall comply with the requirements of Section 604.2. <<

TABLE 604.1
MATERIALS FOR BUILDING SUPPLY AND WATER DISTRIBUTION PIPING AND FITTINGS

| MATERIAL | BUILDING SUPPLY PIPE AND FITTINGS | WATER DISTRIBUTION PIPE AND FITTINGS | REFERENCED STANDARD(S) PIPE | REFERENCED STANDARD(S) FITTINGS |
|--------------------------|---|---|--|--|
| Copper and Copper Alloys | X | X | ASTM B42, ASTM B43, ASTM B75, ASTM B88, ASTM B135, ASTM B251, ASTM B302, ASTM B447 | ASME B16.15, ASME B16.18, ASME B16.22, ASME B16.26, ASME B16.51 |
| CPVC | X | X | ASTM D2846, ASTM F441, ASTM F442, CSA B137.6 | ASTM D2846, ASTM F437, ASTM F438, ASTM F439, ASTM F1970, CSA B137.6 |
| CPVC-AL-CPVC | X | X | ASTM F2855 | ASTM D2846 |
| Ductile-Iron | X | X | AWWA C151 | ASME B16.4, AWWA C110, AWWA C153 |
| Galvanized Steel | X | X | ASTM A53 | — |
| Malleable Iron | X | X | — | ASME B16.3 |
| PE | X* | — | ASTM D2239, ASTM D2737, ASTM D3035, AWWA C901, CSA B137.1 | ASTM D2609, ASTM D2683, ASTM D3261, ASTM F1055, CSA B137.1 |
| PE-AL-PE | X | X | ASTM F1282, CSA B137.9 | ASTM F1282, ASTM F1974, CSA B137.9 |
| PE-RT | X | X | ASTM F2769 | ASTM F1807, ASTM F2098, ASTM F2159, ASTM F2735, ASTM F2769 |
| PEX | X | X | ASTM F876, ASTM F877, CSA B137.5, AWWA C904* | ASSE 1061, ASTM F877, ASTM F1807, ASTM F1960, ASTM F1961, ASTM F2080, ASTM F2159, ASTM F2735, CSA B137.5 |
| PEX-AL-PEX | X | X | ASTM F1281, CSA B137.10, ASTM F2262 | ASTM F1281, ASTM F1974, ASTM F2434, CSA B137.10 |
| PP | X | X | ASTM F2389, CSA B137.11 | ASTM F2389, CSA B137.11 |
| PVC | X* | — | ASTM D1785, ASTM D2241, AWWA C900 | ASTM D2464, ASTM D2466, ASTM D2467, ASTM F1970 |
| Stainless Steel | X | X | ASTM A269, ASTM A312 | — |

* For building supply or cold-water applications.

604.12 Flexible Corrugated Connectors. Flexible corrugated connectors of copper, copper alloy, or stainless steel shall be limited to the following connector lengths:

- (1) Fixture Connectors – 30 inches (762 mm)
- (2) Washing Machine Connectors – 72 inches (1829 mm)
- (3) Dishwasher and Ice Maker Connectors – 120 inches (3048 mm)

604.13 Water Heater Connectors. Flexible metallic (copper and stainless steel), reinforced flexible, braided stainless steel, or polymer braided with EPDM core connectors that connect a water heater to the piping system shall be in accordance with ASME A112.18.6/CSA B125.6. Copper, copper alloy, or stainless steel flexible connectors shall not exceed 24 inches (610 mm). PEX, PEX-AL-PEX, PE-AL-PE, or PE-RT tubing shall not be installed within

the first 18 inches (457 mm) of piping connected to a water heater.

605.0 Joints and Connections.

605.1 Copper or Copper Alloy Pipe, Tubing, and Joints. Joining methods for copper or copper alloy pipe, tubing, and fittings shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.1.1 through Section 605.1.5.

605.1.1 Brazed Joints. Brazed joints between copper or copper alloy pipe or tubing and fittings shall be made with brazing alloys having a liquid temperature above 1000°F (538°C). The joint surfaces to be brazed shall be cleaned bright by either manual or mechanical means. Tubing shall be cut square and reamed to full

inside diameter. Brazing flux shall be applied to the joint surfaces where required by manufacturer's recommendation. Brazing filler metal in accordance with AWS A5.8 shall be applied at the point where the pipe or tubing enters the socket of the fitting.

» **605.1.2 Flared Joints.** Flared joints for soft copper or copper alloy water tubing shall be made with fittings that are in accordance with the applicable standards referenced in Table 604.1. Pipe or tubing shall be cut square using an appropriate tubing cutter. The tubing shall be reamed to full inside diameter, resized to round, and expanded with a proper flaring tool.

» **605.1.3 Mechanical Joints.** Mechanical joints shall include, but are not limited to, compression, flanged, grooved, pressed, and push fit fittings.

» **605.1.3.1 Mechanically Formed Tee Fittings.** Mechanically formed tee fittings shall have extracted collars that shall be formed in a continuous operation consisting of drilling a pilot hole and drawing out the pipe or tube surface to form a collar having a height not less than three times the thickness of the branch tube wall. The branch pipe or tube shall be notched to conform to the inner curve of the run pipe or tube and shall have two dimple depth stops to ensure that penetration of the branch pipe or tube into the collar is of a depth for brazing and that the branch pipe or tube does not obstruct the flow in the main line pipe or tube. Dimple depth stops shall be in line with the run of the pipe or tube. The second dimple shall be ¼ of an inch (6.4 mm) above the first and shall serve as a visual point of inspection. Fittings and joints shall be made by brazing. Soldered joints shall not be permitted.

» **605.1.3.2 Pressed Fittings.** Pressed fittings for copper or copper alloy pipe or tubing shall have an elastomeric o-ring that forms the joint. The pipe or tubing shall be fully inserted into the fitting, and the pipe or tubing marked at the shoulder of the fitting. Pipe or tubing shall be cut square, chamfered, and reamed to full inside diameter. The fitting alignment shall be checked against the mark on the pipe or tubing to ensure the pipe or tubing is inserted into the fitting. The joint shall be pressed using the tool recommended by the manufacturer.

» **605.1.3.3 Push Fit Fittings.** Removable and nonremovable push fit fittings for copper or copper alloy tubing or pipe that employ quick assembly push fit connectors shall be in accordance with ASSE 1061. Push fit fittings for copper or copper alloy pipe or tubing shall have an approved elastomeric o-ring that forms the joint. Pipe or tubing shall be cut square, chamfered, and reamed to full inside diameter. The tubing shall be fully inserted into the fitting, and the tubing marked at the shoulder of the fitting. The fitting alignment shall be checked against the mark on the tubing to ensure

the tubing is inserted into the fitting and gripping mechanism has engaged on the pipe.

» **605.1.4 Soldered Joints.** Soldered joints between copper or copper alloy pipe or tubing and fittings shall be made in accordance with ASTM B828 with the following sequence of joint preparation and operation as follows: measuring and cutting, reaming, cleaning, fluxing, assembly and support, heating, applying the solder, cooling and cleaning. Pipe or tubing shall be cut square and reamed to the full inside diameter including the removal of burrs on the outside of the pipe or tubing. Surfaces to be joined shall be cleaned bright by manual or mechanical means. Flux shall be applied to pipe or tubing and fittings and shall be in accordance with ASTM B813, and shall become noncorrosive and nontoxic after soldering. Insert pipe or tubing into the base of the fitting and remove excess flux. Pipe or tubing and fitting shall be supported to ensure a uniform capillary space around the joint. Heat shall be applied using an air or fuel torch with the flame perpendicular to the pipe or tubing using acetylene or an LP gas. Preheating shall depend on the size of the joint. The flame shall be moved to the fitting cup and alternate between the pipe or tubing and fitting. Solder in accordance with ASTM B32 shall be applied to the joint surfaces until capillary action draws the molten solder into the cup. Solder and fluxes with a lead content that exceeds 0.2 percent shall be prohibited in piping systems conveying potable water. Joint surfaces shall not be disturbed until cool and any remaining flux residue shall be cleaned.

» **605.1.5 Threaded Joints.** Threaded joints for copper or copper alloy pipe shall be made with pipe threads in accordance with ASME B1.20.1. Thread sealant tape or compound shall be applied only on male threads, and such material shall be of approved types, insoluble in water, and nontoxic.

» **605.2 CPVC Plastic Pipe and Joints.** CPVC plastic pipe and fitting joining methods shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.2.1 through Section 605.2.3.

» **605.2.1 Mechanical Joints.** Removable and nonremovable push fit fittings that employ a quick assembly push fit connector shall be in accordance with ASSE 1061.

» **605.2.2 Solvent Cement Joints.** Solvent cement joints for CPVC pipe and fittings shall be clean from dirt and moisture. Solvent cements in accordance with ASTM F493, requiring the use of a primer shall be orange in color. The primer shall be colored and be in accordance with ASTM F656. Listed solvent cement in accordance with ASTM F493 that does not require the use of primers, yellow or red in color, shall be permitted for pipe and fittings manufactured in accordance with ASTM D2846, ½ of an inch (15 mm) through 2 inches (50 mm) in diameter or ASTM F442, ½ of an inch (15 mm) through 3 inches (80 mm) in diameter. Apply primer where required inside the fitting and to

the depth of the fitting on pipe. Apply liberal coat of cement to the outside surface of pipe to depth of fitting and inside of fitting. Place pipe inside fitting to forcefully bottom the pipe in the socket and hold together until joint is set.

- » **605.2.3 Threaded Joints.** Threads shall comply with ASME B1.20.1. A minimum of Schedule 80 shall be permitted to be threaded; however, the pressure rating shall be reduced by 50 percent. The use of molded fittings shall not result in a 50 percent reduction in the pressure rating of the pipe provided that the molded fittings shall be fabricated so that the wall thickness of the material is maintained at the threads. Thread sealant compound that is compatible with the pipe and fitting, insoluble in water, and nontoxic shall be applied to male threads. Caution shall be used during assembly to prevent over tightening of the CPVC components once the thread sealant has been applied. Female CPVC threaded fittings shall be used with plastic male threads only.

605.3 CPVC/AL/CPVC Plastic Pipe and Joints. Chlorinated polyvinyl chloride/aluminum/chlorinated polyvinyl chloride (CPVC/AL/CPVC) plastic pipe and fitting joining methods shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.3.1.

605.3.1 Solvent Cement Joints. Solvent cement joints for CPVC/AL/CPVC pipe and fittings shall be clean from dirt and moisture. Solvent cements in accordance with ASTM F493, requiring the use of a primer shall be orange in color. The primer shall be colored and be in accordance with ASTM F656. Listed solvent cement in accordance with ASTM F493 that does not require the use of primers, yellow in color, shall be permitted to join pipe manufactured in accordance with ASTM F2855 and fittings manufactured in accordance with ASTM D2846, ½ of an inch (15 mm) through 2 inches (50 mm) in diameter. Apply primer where required inside the fitting and to the depth of the fitting on pipe. Apply liberal coat of cement to the outside surface of pipe to depth of fitting and inside of fitting. Place pipe inside fitting to forcefully bottom the pipe in the socket and hold together until joint is set.

- » **605.4 Ductile Iron Pipe and Joints.** Ductile iron pipe and fitting joining methods shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.4.1 or Section 605.4.2.

- » **605.4.1 Mechanical Joints.** Mechanical joints for ductile iron pipe and fittings shall consist of a bell that is cast integrally with the pipe or fitting and provided with an exterior flange having bolt holes and a socket with annular recesses for the sealing gasket and the plain end of the pipe or fitting. The elastomeric gasket shall comply with AWWA C111. Lubricant recommended for potable water application by the pipe manufacturer shall be applied to the gasket and plain end of the pipe.

605.4.2 Push-On Joints. Push-on joints for ductile iron pipe and fittings shall consist of a single elastomeric gasket that shall be assembled by positioning the elastomeric gasket in an annular recess in the pipe or fitting socket and forcing the plain end of the pipe or fitting into the socket. The plain end shall compress the elastomeric gasket to form a positive seal and shall be designed so that the elastomeric gasket shall be locked in place against displacement. The elastomeric gasket shall comply with AWWA C111. Lubricant recommended for potable water application by the pipe manufacturer shall be applied to the gasket and plain end of the pipe.

605.5 Galvanized Steel Pipe and Joints. Galvanized steel pipe and fitting joining methods shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.5.1 or Section 605.5.2.

605.5.1 Mechanical Joints. Mechanical joints shall be made with an approved and listed elastomeric gasket.

605.5.2 Threaded Joints. Threaded joints shall be made with pipe threads that are in accordance with ASME B1.20.1. Thread sealant tape or compound shall be applied only on male threads, and such material shall be of approved types, insoluble in water, and nontoxic.

605.6 PE Plastic Pipe/Tubing and Joints. PE plastic pipe or tubing and fitting joining methods shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.6.1 or Section 605.6.2.

605.6.1 Heat-Fusion Joints. Heat-fusion joints between PE pipe or tubing and fittings shall be assembled in accordance with Section 605.6.1.1 through Section 605.6.1.3 using butt, socket, and electro-fusion heat methods.

605.6.1.1 Butt-Fusion Joints. Butt-fusion joints shall be installed in accordance with ASTM F2620 and shall be made by heating the squared ends of two pipes, pipe and fitting, or two fittings by holding ends against a heated element. The heated element shall be removed where the proper melt is obtained and joined ends shall be placed together with applied force.

605.6.1.2 Electro-Fusion Joints. Electro-fusion joints shall be heated internally by a conductor at the interface of the joint. Align and restrain fitting to pipe to prevent movement and apply electric current to the fitting. Turn off the current when the proper time has elapsed to heat the joint. The joint shall fuse together and remain undisturbed until cool.

605.6.1.3 Socket-Fusion Joints. Socket-fusion joints shall be installed in accordance with ASTM F2620 and shall be made by simultaneously heating the outside surface of a pipe end and the inside of a fitting socket. Where the proper melt is obtained, the pipe and fitting shall be

joined by inserting one into the other with applied force. The joint shall fuse together and remain undisturbed until cool.

- » **605.6.2 Mechanical Joints.** Mechanical joints between PE pipe or tubing and fittings shall include insert and mechanical compression fittings that provide a pressure seal resistance to pullout. Joints for insert fittings shall be made by cutting the pipe square, using a cutter designed for plastic piping, and removal of sharp edges. Two stainless steel clamps shall be placed over the end of the pipe. Fittings shall be checked for proper size based on the diameter of the pipe. The end of pipe shall be placed over the barbed insert fitting, making contact with the fitting shoulder. Clamps shall be positioned equal to 180 degrees (3.14 rad) apart and shall be tightened to provide a leak tight joint. Compression type couplings and fittings shall be permitted for use in joining PE piping and tubing. Stiffeners that extend beyond the clamp or nut shall be prohibited. Bends shall be not less than 30 pipe diameters, or the coil radius where bending with the coil. Bends shall not be permitted closer than 10 pipe diameters of a fitting or valve. Mechanical joints shall be designed for their intended use.

- » **605.7 PE-AL-PE Plastic Pipe/Tubing and Joints.** PE-AL-PE plastic pipe or tubing and fitting joining methods shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.7.1 and Section 605.7.1.1.

- » **605.7.1 Mechanical Joints.** Mechanical joints for PE-AL-PE pipe or tubing and fittings shall be either of the metal insert fittings with a split ring and compression nut or metal insert fittings with copper crimp rings. Metal insert fittings shall comply with ASTM F1974. Crimp insert fittings shall be joined to the pipe by placing the copper crimp ring around the outer circumference of the pipe, forcing the pipe material into the space formed by the ribs on the fitting until the pipe contacts the shoulder of the fitting. The crimp ring shall then be positioned on the pipe so the edge of the crimp ring is $\frac{1}{8}$ of an inch (3.2 mm) to $\frac{1}{4}$ of an inch (6.4 mm) from the end of the pipe. The jaws of the crimping tool shall be centered over the crimp ring and tool perpendicular to the barb. The jaws shall be closed around the crimp ring and shall not be crimped more than once.

- » **605.7.1.1 Compression Joints.** Compression joints for PE-AL-PE pipe or tubing and fittings shall be joined through the compression of a split ring, by a compression nut around the circumference of the pipe. The compression nut and split ring shall be placed around the pipe. The ribbed end of the fitting shall be inserted onto the pipe until the pipe contacts the shoulder of the fitting. Position and compress the split ring by tightening the compression nut onto the insert fitting.

- » **605.8 PE-RT.** Polyethylene of raised temperature (PE-RT) tubing shall be marked with the appropriate standard designation(s) listed in Table 604.1 for which the tubing has

been approved. PE-RT tubing shall be installed in accordance with the manufacturer's installation instructions.

- « **605.8.1 Fittings.** Metal insert fittings, metal compression fittings, and plastic fittings shall be manufactured to and marked in accordance with the standards for fittings in Table 604.1.

- « **605.9 PEX Plastic Tubing and Joints.** PEX plastic tubing and fitting joining methods shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.9.1 and Section 605.9.2.

- « **605.9.1 Fittings.** Fittings for PEX tubing shall comply with the applicable standards referenced in Table 604.1. PEX tubing in accordance with ASTM F876 shall be marked with the applicable standard designation for the fittings, specified by the tubing manufacturer for use with the tubing.

- « **605.9.2 Mechanical Joints.** Mechanical joints shall be installed in accordance with the manufacturer's installation instructions.

- « **605.10 PEX-AL-PEX Plastic Tubing and Joints.** PEX-AL-PEX plastic pipe or tubing and fitting joining methods shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.10.1 and Section 605.10.1.1.

- « **605.10.1 Mechanical Joints.** Mechanical joints between PEX-AL-PEX tubing and fittings shall include mechanical and compression type fittings and insert fittings with a crimping ring. Insert fittings utilizing a crimping ring shall be in accordance with ASTM F1974 or ASTM F2434. Crimp joints for crimp insert fittings shall be joined to PEX-AL-PEX pipe by the compression of a crimp ring around the outer circumference of the pipe, forcing the pipe material into annular spaces formed by ribs on the fitting.

- « **605.10.1.1 Compression Joints.** Compression joints shall include compression insert fittings and shall be joined to PEX-AL-PEX pipe through the compression of a split ring or compression nut around the outer circumference of the pipe, forcing the pipe material into the annular space formed by the ribs on the fitting.

- « **605.11 Polypropylene (PP) Piping and Joints.** PP pipe and fittings shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.11.1 through Section 605.11.3.

- « **605.11.1 Heat-Fusion Joints.** Heat-fusion joints for polypropylene (PP) pipe and fitting joints shall be installed with socket-type heat-fused polypropylene fittings, fusion outlets, butt-fusion polypropylene fittings or pipe, or electro-fusion polypropylene fittings. Joint surfaces shall be clean and free from moisture. The joint shall be undisturbed until cool. Joints shall be made in accordance with ASTM F2389 or CSA B137.11.

- « **605.11.2 Mechanical and Compression Sleeve Joints.** Mechanical and compression sleeve joints shall be installed in accordance with the manufacturer's installation instructions.

» **605.11.3 Threaded Joints.** PP pipe shall not be threaded. PP transition fittings for connection to other piping materials shall only be threaded by use of copper alloy or stainless steel inserts molded in the fitting.

» **605.12 PVC Plastic Pipe and Joints.** PVC plastic pipe and fitting joining methods shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.12.1 through Section 605.12.3.

» **605.12.1 Mechanical Joints.** Mechanical joints shall be designed to provide a permanent seal and shall be of the mechanical or push-on joint. The mechanical joint shall include a pipe spigot that has a wall thickness to withstand without deformation or collapse; the compressive force exerted where the fitting is tightened. The push-on joint shall have a minimum wall thickness of the bell at any point between the ring and the pipe barrel. The elastomeric gasket shall comply with ASTM D3139, and be of such size and shape as to provide a compressive force against the spigot and socket after assembly to provide a positive seal.

» **605.12.2 Solvent Cement Joints.** Solvent cement joints for PVC pipe and fittings shall be clean from dirt and moisture. Pipe shall be cut square and pipe shall be deburred. Where surfaces to be joined are cleaned and free of dirt, moisture, oil, and other foreign material, apply primer purple in color in accordance with ASTM F656. Primer shall be applied until the surface of the pipe and fitting is softened. Solvent cements in accordance with ASTM D2564 shall be applied to all joint surfaces. Joints shall be made while both the inside socket surface and outside surface of pipe are wet with solvent cement. Hold joint in place and undisturbed for 1 minute after assembly.

» **605.12.3 Threaded Joints.** Threads shall comply with ASME B1.20.1. A minimum of Schedule 80 shall be permitted to be threaded; however, the pressure rating shall be reduced by 50 percent. The use of molded fittings shall not result in a 50 percent reduction in the pressure rating of the pipe provided that the molded fittings shall be fabricated so that the wall thickness of the material is maintained at the threads. Thread sealant compound that is compatible with the pipe and fitting, insoluble in water, and nontoxic shall be applied to male threads. Caution shall be used during assembly to prevent over tightening of the PVC components once the thread sealant has been applied. Female PVC threaded fittings shall be used with plastic male threads only.

» **605.13 Stainless Steel Pipe and Joints.** Joining methods for stainless steel pipe and fittings shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.13.1 or Section 605.13.2.

» **605.13.1 Mechanical Joints.** Mechanical joints shall be designed for their intended use. Such joints shall include compression, flanged, grooved, pressed, and threaded.

» **605.13.2 Welded Joints.** Welded joints shall be either fusion or resistance welded based on the selec-

tion of the base metal. Chemical composition of the filler metal shall comply with AWS A5.9 based on the alloy content of the piping material.

605.14 Slip Joints. In water piping, slip joints shall be permitted to be used only on the exposed fixture supply. <<

605.15 Dielectric Unions. Dielectric unions where installed at points of connection where there is a dissimilarity of metals shall be in accordance with ASSE 1079. <<

605.16 Joints Between Various Materials. Joints between various materials shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 605.16.1 through Section 605.16.3. <<

605.16.1 Copper or Copper Alloy Pipe or Tubing to Threaded Pipe Joints. Joints from copper or copper alloy pipe or tubing to threaded pipe shall be made by the use of copper alloy adapter, copper alloy nipple [minimum 6 inches (152 mm)], dielectric fitting, or dielectric union in accordance with ASSE 1079. The joint between the copper or copper alloy pipe or tubing and the fitting shall be a soldered, brazed, flared, or pressed joint and the connection between the threaded pipe and the fitting shall be made with a standard pipe size threaded joint. <<

605.16.2 Plastic Pipe to Other Materials. Where connecting plastic pipe to other types of piping, approved types of adapter or transition fittings designed for the specific transition intended shall be used. <<

605.16.3 Stainless Steel to Other Materials. Where connecting stainless steel pipe to other types of piping, mechanical joints of the compression type, dielectric fitting, or dielectric union in accordance with ASSE 1079 and designed for the specific transition intended shall be used. <<

606.0 Valves.

606.1 General. Valves up to and including 2 inches (50 mm) in size shall be copper alloy or other approved material. Sizes exceeding 2 inches (50 mm) shall be permitted to have cast iron or copper alloy bodies. Each gate or ball valve shall be a fullway type with working parts of non-corrosive material. Valves carrying water used in potable water systems intended to supply drinking water shall be in accordance with the requirements of NSF 61 and ASME A112.4.14, ASME B16.34, ASTM F1970, ASTM F2389, AWWA C500, AWWA C504, AWWA C507, CSA B125.3, MSS SP-67, MSS SP-70, MSS SP-71, MSS SP-72, MSS SP-78, MSS SP-80, MSS SP-110, MSS SP-122, or NSF 359.

606.2 Fullway Valve. A fullway valve controlling outlets shall be installed on the discharge side of each water meter and on each unmetered water supply. Water piping supplying more than one building on one premises shall be equipped with a separate fullway valve to each building, so arranged that the water supply can be turned on or off to an individual or separate building provided; however, that supply piping to a single-family residence and building accessory thereto shall be permitted to be controlled on one

valve. Such shutoff valves shall be accessible. A fullway valve shall be installed on the discharge piping from water supply tanks at or near the tank. A fullway valve shall be installed on the cold water supply pipe to each water heater at or near the water heater.

606.3 Multidwelling Units. In multidwelling units, one or more shutoff valves shall be provided in each dwelling unit so that the water supply to a plumbing fixture or group of fixtures in that dwelling unit can be shut off without stopping water supply to fixtures in other dwelling units. These valves shall be accessible in the dwelling unit that they control.

606.4 Multiple Openings. Valves used to control two or more openings shall be fullway gate valves, ball valves, or other approved valves designed and approved for the service intended.

606.5 Control Valve. A control valve shall be installed immediately ahead of each water-supplied appliance and immediately ahead of each slip joint or appliance supply.

Parallel water distribution systems shall provide a control valve either immediately ahead of each fixture being supplied or installed at the manifold, and shall be identified with the fixture being supplied. Where parallel water distribution system manifolds are located in attics, crawl spaces, or other locations not readily accessible, a separate shutoff valve shall be required immediately ahead of each individual fixture or appliance served.

606.6 Accessible. Required shutoff or control valves shall be accessible.

606.7 Multiple Fixtures. A single control valve shall be installed on a water supply line ahead of an automatic metering valve that supplies a battery of fixtures.

607.0 Potable Water Supply Tanks.

607.1 General. Potable water supply tanks shall be installed in accordance with the manufacturer's installation instructions, and supported in accordance with the building code.

607.2 Potable Water Tanks. Potable water supply tanks, interior tank coatings, or tank liners intended to supply drinking water shall be in accordance with NSF 61.

607.3 Venting. Tanks used for potable water shall be tightly covered and vented in accordance with the manufacturer's installation instructions. Such vent shall be screened with a corrosion-resistant material of not less than number 24 mesh.

607.4 Overflow. Tanks shall have not less than a 16 square inch (0.01 m²) overflow that is screened with a corrosion-resistant material of not less than number 24 mesh.

607.5 Valves. Pressurized tanks shall be provided with a listed pressure-relief valve installed in accordance with the manufacturer's installation instructions. The relief valve shall be discharged in accordance with Section 608.5. Where a potable water supply tank is located above the fixtures, appliances, or system components it serves it shall be equipped with a vacuum relief valve that is in accordance with CSA Z21.22.

608.0 Water Pressure, Pressure Regulators, Pressure Relief Valves, and Vacuum Relief Valves.

608.1 Inadequate Water Pressure. Where the water pressure in the main or other source of supply will not provide a residual water pressure of not less than 15 pounds force per square inch (psi) (103 kPa), after allowing for friction and other pressure losses, a tank and a pump or other means that will provide said 15 psi (103 kPa) pressure shall be installed. Where fixtures, fixture fittings, or both are installed that require residual pressure exceeding 15 psi (103 kPa), that minimum residual pressure shall be provided.

608.2 Excessive Water Pressure. Where static water pressure in the water supply piping is exceeding 80 psi (552 kPa), an approved-type pressure regulator preceded by an adequate strainer shall be installed and the static pressure reduced to 80 psi (552 kPa) or less. Pressure regulator(s) equal to or exceeding 1½ inches (40 mm) shall not require a strainer. Such regulator(s) shall control the pressure to water outlets in the building unless otherwise approved by the Authority Having Jurisdiction. Each such regulator and strainer shall be accessibly located aboveground or in a vault equipped with a properly sized and sloped boresighted drain to daylight, shall be protected from freezing, and shall have the strainer readily accessible for cleaning without removing the regulator or strainer body or disconnecting the supply piping. Pipe size determinations shall be based on 80 percent of the reduced pressure where using Table 610.4. An approved expansion tank shall be installed in the cold water distribution piping downstream of each such regulator to prevent excessive pressure from developing due to thermal expansion and to maintain the pressure setting of the regulator. Expansion tanks used in potable water systems intended to supply drinking water shall be in accordance with NSF 61. The expansion tank shall be properly sized and installed in accordance with the manufacturer's installation instructions and listing. Systems designed by registered design professionals shall be permitted to use approved pressure relief valves in lieu of expansion tanks provided such relief valves have a maximum pressure relief setting of 100 psi (689 kPa) or less.

608.3 Expansion Tanks, and Combination Temperature and Pressure-Relief Valves. A water system provided with a check valve, backflow preventer, or other normally closed device that prevents dissipation of building pressure back into the water main, independent of the type of water heater used, shall be provided with an approved, listed, and adequately sized expansion tank or other approved device having a similar function to control thermal expansion. Such expansion tank or other approved device shall be installed on the building side of the check valve, backflow preventer, or other device and shall be sized and installed in accordance with the manufacturer's installation instructions.

A water system containing storage water heating equipment shall be provided with an approved, listed, adequately sized combination temperature and pressure-relief valve, except for listed nonstorage instantaneous heaters having an inside diameter of not more than 3 inches (80 mm). Each such approved combination temperature and pressure-relief valve shall be installed on the water-heating device in an

approved location based on its listing requirements and the manufacturer's installation instructions. Each such combination temperature and pressure-relief valve shall be provided with a drain in accordance with Section 608.5.

608.4 Pressure Relief Valves. Each pressure relief valve shall be an approved automatic type with drain, and each such relief valve shall be set at a pressure of not more than 150 psi (1034 kPa). No shutoff valve shall be installed between the relief valve and the system.

608.5 Discharge Piping. The discharge piping serving a temperature relief valve, pressure relief valve, or combination of both shall have no valves, obstructions, or means of isolation and be provided with the following:

- (1) Equal to the size of the valve outlet and shall discharge full size to the flood level of the area receiving the discharge and pointing down.
- (2) Materials shall be rated at not less than the operating temperature of the system and approved for such use.
- (3) Discharge pipe shall discharge independently by gravity through an air gap into the drainage system or outside of the building with the end of the pipe not exceeding 2 feet (610 mm) and not less than 6 inches (152 mm) above the ground and pointing downwards.
- (4) Discharge in such a manner that does not cause personal injury or structural damage.
- (5) No part of such discharge pipe shall be trapped or subject to freezing.
- (6) The terminal end of the pipe shall not be threaded.
- (7) Discharge from a relief valve into a water heater pan shall be prohibited.

608.6 Water-Heating Devices. A water-heating device connected to a separate storage tank and having valves between said heater and tank shall be provided with an approved water pressure relief valve.

608.7 Vacuum Relief Valves. Where a hot-water storage tank or an indirect water heater is located at an elevation above the fixture outlets in the hot-water system, a vacuum relief valve that is in accordance with CSA Z21.22 shall be installed on the storage tank or heater.

609.0 Installation, Testing, Unions, and Location.

609.1 Installation. Water piping shall be adequately supported in accordance with Table 313.3. Burred ends shall be reamed to the full bore of the pipe or tube. Changes in direction shall be made by the appropriate use of fittings, except that changes in direction in copper or copper alloy tubing shall be permitted to be made with bends, provided that such bends are made with bending equipment that does not deform or create a loss in the cross-sectional area of the tubing. Changes in direction are allowed with flexible pipe and tubing without fittings in accordance with the manufacturer's instructions. Provisions shall be made for expansion in hot-water piping. Piping, equipment, appurtenances, and devices shall be installed in a workmanlike manner in accordance with the provisions and intent of the code. Building supply yard piping shall be not less than 12 inches (305 mm)

below the average local frost depth. The cover shall be not less than 12 inches (305 mm) below finish grade.

609.2 Trenches. Water pipes shall not be run or laid in the same trench as building sewer or drainage piping constructed of clay or materials that are not approved for use within a building unless both of the following conditions are met:

- (1) The bottom of the water pipe, shall be not less than 12 inches (305 mm) above the top of the sewer or drain line.
- (2) The water pipe shall be placed on a solid shelf excavated at one side of the common trench with a clear horizontal distance of not less than 12 inches (305 mm) from the sewer or drain line.

Water pipes crossing sewer or drainage piping constructed of clay or materials that are not approved for use within a building shall be laid not less than 12 inches (305 mm) above the sewer or drain pipe.

609.3 Under Concrete Slab. Water piping installed within a building and in or under a concrete floor slab resting on the ground shall be installed in accordance with the following requirements:

- (1) Ferrous piping shall have a protective coating of an approved type, machine applied and in accordance with recognized standards. Field wrapping shall provide equivalent protection and shall be restricted to those short sections and fittings necessarily stripped for threading. Zinc coating (galvanizing) shall not be deemed adequate protection for piping or fittings. Approved nonferrous piping shall not be required to be wrapped.
- (2) Copper or copper alloy tubing shall be installed without joints where possible. Where joints are permitted, they shall be brazed, and fittings shall be wrought copper.

For the purpose of this section, "within a building" shall mean within the fixed limits of the building foundation.

609.4 Testing. Upon completion of a section or of the entire hot and cold water supply system, it shall be tested and proved tight under a water pressure not less than the working pressure under which it is to be used. The water used for tests shall be obtained from a potable source of supply. Except for plastic piping, a 50 psi (345 kPa) air pressure shall be permitted to be substituted for the water test. In either method of test, the piping shall withstand the test without leaking for a period of not less than 15 minutes.

609.5 Unions. Unions shall be installed in the water supply piping not more than 12 inches (305 mm) of regulating equipment, water heating, conditioning tanks, and similar equipment that requires service by removal or replacement in a manner that will facilitate its ready removal.

609.6 Location. Except as provided in Section 609.7, no building supply shall be located in a lot other than the lot that is the site of the building or structure served by such building supply.

609.7 Abutting Lot. Nothing contained in this code shall be construed to prohibit the use of an abutting lot to:

- (1) Provide access to connect a building supply to an available public water service where proper cause and legal easement not in violation of other requirements have been first established to the satisfaction of the Authority Having Jurisdiction.

- (2) Provide additional space for a building supply where proper cause, transfer of ownership, or change of boundary not in violation of other requirements have been first established to the satisfaction of the Authority Having Jurisdiction. The instrument recording such action shall constitute an agreement with the Authority Having Jurisdiction, which shall clearly state and show that the areas so joined or used shall be maintained as a unit during the time they are so used. Such an agreement shall be recorded in the office of the County Recorder as a part of the conditions of ownership of said properties, and shall be binding on heirs, successors, and assigns to such properties. A copy of the instrument recording such proceedings shall be filed with the Authority Having Jurisdiction.

609.8 Low-Pressure Cutoff Required on Booster Pumps for Water Distribution Systems. Where a booster pump (excluding a fire pump) is connected to a building supply or underground water pipe, a low-pressure cutoff switch on the inlet side of the pump shall be installed not more than 5 feet (1524 mm) of the inlet. The cutoff switch shall be set for not less than 10 psi (69 kPa). A pressure gauge shall be installed between the shutoff valve and the pump.

609.9 Disinfection of Potable Water System. New or repaired potable water systems shall be disinfected prior to use where required by the Authority Having Jurisdiction. The method to be followed shall be that prescribed by the Health Authority or, in case no method is prescribed by it, the following:

- (1) The pipe system shall be flushed with clean, potable water until potable water appears at the points of outlet.
- (2) The system or parts thereof shall be filled with a water-chlorine solution containing not less than 50 parts per million of chlorine, and the system or part thereof shall be valved-off and allowed to stand for 24 hours; or, the system or part thereof shall be filled with a water-chlorine solution containing not less than 200 parts per million of chlorine and allowed to stand for 3 hours.
- (3) Following the allowed standing time, the system shall be flushed with clean, potable water until the chlorine residual in the water coming from the system does not exceed the chlorine residual in the flushing water.
- (4) The procedure shall be repeated where it is shown by bacteriological examination made by an approved agency that contamination persists in the system.

609.10 Water Hammer. Building water supply systems where quick-acting valves are installed shall be provided with water hammer arrester(s) to absorb high pressures resulting from the quick closing of these valves. Water hammer arresters shall be approved mechanical devices in accordance with ASSE 1010 or PDI-WH 201 and shall be installed as close as possible to quick-acting valves.

609.10.1 Mechanical Devices. Where listed mechanical devices are used, the manufacturer's specifications as to location and method of installation shall be followed.

609.11 Pipe Insulation. Insulation of domestic hot water piping shall be in accordance with Section 609.11.1 and Section 609.11.2.

609.11.1 Insulation Requirements. Domestic hot water piping shall be insulated.

609.11.2 Pipe Insulation Wall Thickness. Hot water pipe insulation shall have a minimum wall thickness of not less than the diameter of the pipe for a pipe up to 2 inches (50 mm) in diameter. Insulation wall thickness shall be not less than 2 inches (51 mm) for a pipe of 2 inches (50 mm) or more in diameter.

Exceptions:

- (1) Piping that penetrates framing members shall not be required to have pipe insulation for the distance of the framing penetration.
- (2) Hot water piping between the fixture control valve or supply stop and the fixture or appliance shall not be required to be insulated.

610.0 Size of Potable Water Piping.

610.1 Size. The size of each water meter and each potable water supply pipe from the meter or other source of supply to the fixture supply branches, risers, fixtures, connections, outlets, or other uses shall be based on the total demand and shall be determined according to the methods and procedures outlined in this section. Water piping systems shall be designed to ensure that the maximum velocities allowed by the code and the applicable standard are not exceeded.

610.2 Pressure Loss. Where a water filter, water softener, backflow prevention device, tankless water heater, or similar device is installed in a water supply line, the pressure loss through such devices shall be included in the pressure loss calculations of the system, and the water supply pipe and meter shall be adequately sized to provide for such a pressure loss.

No water filter, water softener, backflow prevention device, or similar device regulated by this code shall be installed in a potable water supply piping where the installation of such device produces an excessive pressure drop in such water supply piping. In the absence of specific pressure drop information, the diameter of the inlet or outlet of such device or its connecting piping shall be not less than the diameter of such water distribution piping to the fixtures served by the device.

Such devices shall be of a type approved by the Authority Having Jurisdiction and shall be tested for flow rating and pressure loss by an approved laboratory or recognized testing agency to standards consistent with the intent of this chapter.

610.3 Quantity of Water. The quantity of water required to be supplied to every plumbing fixture shall be represented by fixture units, as shown in Table 610.3. Equivalent fixture values shown in Table 610.3 include both hot and cold water demand.

610.4 Sizing Water Supply and Distribution Systems. Systems within the range of Table 610.4 shall be permitted to be sized from that table or by the method in accordance with Section 610.5.

Listed parallel water distribution systems shall be installed in accordance with their listing, but at no time shall a portion of the system exceed the maximum velocities allowed by the code.

TABLE 610.3
WATER SUPPLY FIXTURE UNITS (WSFU) AND MINIMUM FIXTURE BRANCH PIPE SIZES³

| APPLIANCES, APPURTENANCES OR FIXTURES ² | MINIMUM FIXTURE BRANCH PIPE SIZE ^{1,4} (inches) | PRIVATE | PUBLIC | ASSEMBLY ⁶ |
|--|---|---------------------------|--------|-----------------------|
| Bathtub or Combination Bath/Shower (fill) | ½ | 4.0 | 4.0 | — |
| ¾ inch Bathtub Fill Valve | ¾ | 10.0 | 10.0 | — |
| Bidet | ½ | 1.0 | — | — |
| Clothes Washer | ½ | 4.0 | 4.0 | — |
| Dental Unit, cuspidor | ½ | — | 1.0 | — |
| Dishwasher, domestic | ½ | 1.5 | 1.5 | — |
| Drinking Fountain or Water Cooler | ½ | 0.5 | 0.5 | 0.75 |
| Hose Bibb | ½ | 2.5 | 2.5 | — |
| Hose Bibb, each additional ⁸ | ½ | 1.0 | 1.0 | — |
| Lavatory | ½ | 1.0 | 1.0 | 1.0 |
| Lawn Sprinkler, each head ⁵ | — | 1.0 | 1.0 | — |
| Mobile Home, each (minimum) | — | 12.0 | — | — |
| Sinks | — | — | — | — |
| Bar | ½ | 1.0 | 2.0 | — |
| Clinical Faucet | ½ | — | 3.0 | — |
| Clinical Flushometer Valve with or without faucet | 1 | — | 8.0 | — |
| Kitchen, domestic with or without dishwasher | ½ | 1.5 | 1.5 | — |
| Laundry | ½ | 1.5 | 1.5 | — |
| Service or Mop Basin | ½ | 1.5 | 3.0 | — |
| Washup, each set of faucets | ½ | — | 2.0 | — |
| Shower, per head | ½ | 2.0 | 2.0 | — |
| Urinal, 1.0 GPF Flushometer Valve | ¾ | See Footnote ⁷ | | — |
| Urinal, greater than 1.0 GPF Flushometer Valve | ¾ | See Footnote ⁷ | | — |
| Urinal, flush tank | ½ | 2.0 | 2.0 | 3.0 |
| Wash Fountain, circular spray | ¾ | — | 4.0 | — |
| Water Closet, 1.6 GPF Gravity Tank | ½ | 2.5 | 2.5 | 3.5 |
| Water Closet, 1.6 GPF Flushometer Tank | ½ | 2.5 | 2.5 | 3.5 |
| Water Closet, 1.6 GPF Flushometer Valve | 1 | See Footnote ⁷ | | — |
| Water Closet, greater than 1.6 GPF Gravity Tank | ½ | 3.0 | 5.5 | 7.0 |
| Water Closet, greater than 1.6 GPF Flushometer Valve | 1 | See Footnote ⁷ | | — |

For SI units: 1 inch = 25 mm

Notes:

¹ Size of the cold branch pipe, or both the hot and cold branch pipes.

² Appliances, appurtenances, or fixtures not referenced in this table shall be permitted to be sized by reference to fixtures having a similar flow rate and frequency of use.

³ The listed fixture unit values represent their load on the cold water building supply. The separate cold water and hot water fixture unit value for fixtures having both hot and cold water connections shall be permitted to be each taken as three-quarter of the listed total value of the fixture.

⁴ The listed minimum supply branch pipe sizes for individual fixtures are the nominal (I.D.) pipe size.

⁵ For fixtures or supply connections likely to impose continuous flow demands, determine the required flow in gallons per minute (gpm) (L/s), and add it separately to the demand in gpm (L/s) for the distribution system or portions thereof.

⁶ Assembly [Public Use (See Table 422.1)].

⁷ Where sizing flushometer systems, see Section 610.10.

⁸ Reduced fixture unit loading for additional hose bibbs is to be used where sizing total building demand and for pipe sizing where more than one hose bibb is supplied by a segment of water distribution pipe. The fixture branch to each hose bibb shall be sized on the basis of 2.5 fixture units.

TABLE 610.4
FIXTURE UNIT TABLE FOR DETERMINING WATER PIPE AND METER SIZES

| METER AND STREET SERVICE (inches) | BUILDING SUPPLY AND BRANCHES (inches) | MAXIMUM ALLOWABLE LENGTH (feet) | | | | | | | | | | | | | | |
|--|---------------------------------------|---------------------------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|
| | | 40 | 60 | 80 | 100 | 150 | 200 | 250 | 300 | 400 | 500 | 600 | 700 | 800 | 900 | 1000 |
| PRESSURE RANGE – 30 to 45 psi ¹ | | | | | | | | | | | | | | | | |
| ¾ | ½ ² | 6 | 5 | 4 | 3 | 2 | 1 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| ¾ | ¾ | 16 | 16 | 14 | 12 | 9 | 6 | 5 | 5 | 4 | 4 | 3 | 2 | 2 | 2 | 1 |
| ¾ | 1 | 29 | 25 | 23 | 21 | 17 | 15 | 13 | 12 | 10 | 8 | 6 | 6 | 6 | 6 | 6 |
| 1 | 1 | 36 | 31 | 27 | 25 | 20 | 17 | 15 | 13 | 12 | 10 | 8 | 6 | 6 | 6 | 6 |
| ¾ | 1¼ | 36 | 33 | 31 | 28 | 24 | 23 | 21 | 19 | 17 | 16 | 13 | 12 | 12 | 11 | 11 |
| 1 | 1¼ | 54 | 47 | 42 | 38 | 32 | 28 | 25 | 23 | 19 | 17 | 14 | 12 | 12 | 11 | 11 |
| 1½ | 1¼ | 78 | 68 | 57 | 48 | 38 | 32 | 28 | 25 | 21 | 18 | 15 | 12 | 12 | 11 | 11 |
| 1 | 1½ | 85 | 84 | 79 | 65 | 56 | 48 | 43 | 38 | 32 | 28 | 26 | 22 | 21 | 20 | 20 |
| 1½ | 1½ | 150 | 124 | 105 | 91 | 70 | 57 | 49 | 45 | 36 | 31 | 26 | 23 | 21 | 20 | 20 |
| 2 | 1½ | 151 | 129 | 129 | 110 | 80 | 64 | 53 | 46 | 38 | 32 | 27 | 23 | 21 | 20 | 20 |
| 1 | 2 | 85 | 85 | 85 | 85 | 85 | 85 | 82 | 80 | 66 | 61 | 57 | 52 | 49 | 46 | 43 |
| 1½ | 2 | 220 | 205 | 190 | 176 | 155 | 138 | 127 | 120 | 104 | 85 | 70 | 61 | 57 | 54 | 51 |
| 2 | 2 | 370 | 327 | 292 | 265 | 217 | 185 | 164 | 147 | 124 | 96 | 70 | 61 | 57 | 54 | 51 |
| 2 | 2½ | 445 | 418 | 390 | 370 | 330 | 300 | 280 | 265 | 240 | 220 | 198 | 175 | 158 | 143 | 133 |
| PRESSURE RANGE – 46 to 60 psi ¹ | | | | | | | | | | | | | | | | |
| ¾ | ½ ² | 7 | 7 | 6 | 5 | 4 | 3 | 2 | 2 | 1 | 1 | 1 | 0 | 0 | 0 | 0 |
| ¾ | ¾ | 20 | 20 | 19 | 17 | 14 | 11 | 9 | 8 | 6 | 5 | 4 | 4 | 3 | 3 | 3 |
| ¾ | 1 | 39 | 39 | 36 | 33 | 28 | 23 | 21 | 19 | 17 | 14 | 12 | 10 | 9 | 8 | 8 |
| 1 | 1 | 39 | 39 | 39 | 36 | 30 | 25 | 23 | 20 | 18 | 15 | 12 | 10 | 9 | 8 | 8 |
| ¾ | 1¼ | 39 | 39 | 39 | 39 | 39 | 39 | 34 | 32 | 27 | 25 | 22 | 19 | 19 | 17 | 16 |
| 1 | 1¼ | 78 | 78 | 76 | 67 | 52 | 44 | 39 | 36 | 30 | 27 | 24 | 20 | 19 | 17 | 16 |
| 1½ | 1¼ | 78 | 78 | 78 | 78 | 66 | 52 | 44 | 39 | 33 | 29 | 24 | 20 | 19 | 17 | 16 |
| 1 | 1½ | 85 | 85 | 85 | 85 | 85 | 85 | 80 | 67 | 55 | 49 | 41 | 37 | 34 | 32 | 30 |
| 1½ | 1½ | 151 | 151 | 151 | 151 | 128 | 105 | 90 | 78 | 62 | 52 | 42 | 38 | 35 | 32 | 30 |
| 2 | 1½ | 151 | 151 | 151 | 151 | 150 | 117 | 98 | 84 | 67 | 55 | 42 | 38 | 35 | 32 | 30 |
| 1 | 2 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 83 | 80 |
| 1½ | 2 | 370 | 370 | 340 | 318 | 272 | 240 | 220 | 198 | 170 | 150 | 135 | 123 | 110 | 102 | 94 |
| 2 | 2 | 370 | 370 | 370 | 370 | 368 | 318 | 280 | 250 | 205 | 165 | 142 | 123 | 110 | 102 | 94 |
| 2 | 2½ | 654 | 640 | 610 | 580 | 535 | 500 | 470 | 440 | 400 | 365 | 335 | 315 | 285 | 267 | 250 |
| PRESSURE RANGE – Over 60 psi ¹ | | | | | | | | | | | | | | | | |
| ¾ | ½ ² | 7 | 7 | 7 | 6 | 5 | 4 | 3 | 3 | 2 | 1 | 1 | 1 | 1 | 1 | 0 |
| ¾ | ¾ | 20 | 20 | 20 | 20 | 17 | 13 | 11 | 10 | 8 | 7 | 6 | 6 | 5 | 4 | 4 |
| ¾ | 1 | 39 | 39 | 39 | 39 | 35 | 30 | 27 | 24 | 21 | 17 | 14 | 13 | 12 | 12 | 11 |
| 1 | 1 | 39 | 39 | 39 | 39 | 38 | 32 | 29 | 26 | 22 | 18 | 14 | 13 | 12 | 12 | 11 |
| ¾ | 1¼ | 39 | 39 | 39 | 39 | 39 | 39 | 39 | 39 | 34 | 28 | 26 | 25 | 23 | 22 | 21 |
| 1 | 1¼ | 78 | 78 | 78 | 78 | 74 | 62 | 53 | 47 | 39 | 31 | 26 | 25 | 23 | 22 | 21 |
| 1½ | 1¼ | 78 | 78 | 78 | 78 | 78 | 74 | 65 | 54 | 43 | 34 | 26 | 25 | 23 | 22 | 21 |
| 1 | 1½ | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 81 | 64 | 51 | 48 | 46 | 43 | 40 |
| 1½ | 1½ | 151 | 151 | 151 | 151 | 151 | 151 | 130 | 113 | 88 | 73 | 51 | 51 | 46 | 43 | 40 |
| 2 | 1½ | 151 | 151 | 151 | 151 | 151 | 151 | 142 | 122 | 98 | 82 | 64 | 51 | 46 | 43 | 40 |
| 1 | 2 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 | 85 |
| 1½ | 2 | 370 | 370 | 370 | 370 | 360 | 335 | 305 | 282 | 244 | 212 | 187 | 172 | 153 | 141 | 129 |
| 2 | 2 | 370 | 370 | 370 | 370 | 370 | 370 | 370 | 340 | 288 | 245 | 204 | 172 | 153 | 141 | 129 |
| 2 | 2½ | 654 | 654 | 654 | 654 | 654 | 650 | 610 | 570 | 510 | 460 | 430 | 404 | 380 | 356 | 329 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 pound-force per square inch = 6.8947 kPa

Notes:

¹ Available static pressure after head loss.

² Building supply, not less than 3/4 of an inch (20 mm) nominal size.

610.5 Sizing per Appendices A and C. Except as provided in Section 610.4, the size of each water piping system shall be determined in accordance with the procedure set forth in Appendix A. For alternate methods of sizing water supply systems, see Appendix C.

610.6 Friction and Pressure Loss. Except where the type of pipe used and the water characteristics are such that no decrease in capacity due to length of service (age of system) is expected, friction-loss data shall be obtained from the "Fairly Rough" or "Rough" charts in Appendix A of this code. Friction or pressure losses in water meter, valve, and fittings shall be obtained from the same sources. Pressure losses through water-treating equipment, backflow prevention devices, or other flow-restricting devices shall be computed in accordance with Section 610.2.

610.7 Conditions for Using Table 610.4. On a proposed water piping installation sized using Table 610.4, the following conditions shall be determined:

- (1) Total number of fixture units as determined from Table 610.3, Equivalent Fixture Units, for the fixtures to be installed.
- (2) Developed length of supply pipe from meter to most remote outlet.
- (3) Difference in elevation between the meter or other source of supply and the highest fixture or outlet.
- (4) Pressure in the street main or other source of supply at the locality where the installation is to be made.
- (5) In localities where there is a fluctuation of pressure in the main throughout the day, the water piping system shall be designed on the basis of the minimum pressure available.

610.8 Size of Meter and Building Supply Pipe Using Table 610.4. The size of the meter and the building supply pipe shall be determined as follows:

- (1) Determine the available pressure at the water meter or other source of supply.
- (2) Add or subtract depending on positive or negative elevation change, $\frac{1}{2}$ psi (3.4 kPa) for each foot (305 mm) of difference in elevation between such source of supply and the highest water supply outlet in the building or on the premises.
- (3) Use the "pressure range" group within which this pressure will fall using Table 610.4.
- (4) Select the "length" column that is equal to or longer than the required length.
- (5) Follow down the column to a fixture unit value equal to or exceeding the total number of fixture units required by the installation.
- (6) Having located the proper fixture unit value for the required length, sizes of meter and building supply pipe as found in the two left-hand columns shall be applied.

No building supply pipe shall be less than $\frac{3}{4}$ of an inch (20 mm) in diameter.

610.9 Size of Branches. Where Table 610.4 is used, the minimum size of each branch shall be determined by the number of fixture units to be served by that branch, the total developed length of the system, and the meter and street service size in accordance with Section 610.8. No branch piping is required to be larger in size than that required by Table 610.4 for the building supply pipe.


610.10 Sizing for Flushometer Valves. Where using Table 610.4 to size water supply systems serving flushometer valves, the number of flushometer fixture units assigned to every section of pipe, whether branch or main, shall be determined by the number and category of flushometer valves served by that section of pipe, in accordance with Table 610.10. Piping supplying a flushometer valve shall be not less in size than the valve inlet.

Where using Table 610.10 to size water piping, care shall be exercised to assign flushometer fixture units based on the number and category of fixtures served.

TABLE 610.10
FLUSHOMETER FIXTURE UNITS FOR WATER
SIZING USING TABLE 610.3

| FIXTURE CATEGORY: WATER CLOSET WITH FLUSHOMETER VALVES | | |
|--|---|--|
| NUMBER OF FLUSHOMETER VALVES | INDIVIDUAL FIXTURE UNITS ASSIGNED IN DECREASING VALUE | FIXTURE UNITS ASSIGNED FOR WATER CLOSETS AND SIMILAR 10-UNIT FIXTURES IN ACCUMULATIVE VALUES |
| 1 | 40 | 40 |
| 2 | 30 | 70 |
| 3 | 20 | 90 |
| 4 | 15 | 105 |
| 5 or more | 10 each | 115 plus 10 for each additional fixture in excess of 5 |
| FIXTURE CATEGORY: URINALS WITH FLUSHOMETER VALVES | | |
| NUMBER OF FLUSHOMETER VALVES | INDIVIDUAL FIXTURE UNITS ASSIGNED IN DECREASING VALUE | FIXTURE UNITS ASSIGNED FOR URINALS AND SIMILAR 5-UNIT FIXTURES IN ACCUMULATIVE VALUES |
| 1 | 20 | 20 |
| 2 | 15 | 35 |
| 3 | 10 | 45 |
| 4 | 8 | 53 |
| 5 or more | 5 each | 58 plus 5 for each additional fixture in excess of 5 |

In the example below, fixture units assigned to each section of pipe are computed. Each capital letter refers to the section of pipe above it, unless otherwise shown.



| | |
|----|---|
| A: | 1 WC = 40 F.U. |
| B: | 2 WC = 70 F.U. |
| C: | 2 WC (70) + 1 UR (20) = 90 F.U. |
| D: | 2 WC (70) + 2 UR (35) = 105 F.U. |
| E: | 2 WC (70) + 2 UR (35) + 1 LAV (1) = 106 F.U. |
| F: | 2 WC (70) + 2 UR (35) + 2 LAV (2) = 107 F.U. |
| G: | 1 LAV = 1 F.U. |
| H: | 2 LAV = 2 F.U. |
| I: | 2 LAV (2) + 1 UR (20) = 22 F.U. |
| J: | 2 LAV (2) + 2 UR (35) = 37 F.U. |
| K: | 2 LAV (2) + 2 UR (35) + 1 WC (40) = 77 F.U. |
| L: | 2 LAV (2) + 2 UR (35) + 2 WC (70) = 107 F.U. |
| M: | 4 WC (105) + 4 UR (53) + 4 LAV (4) = 162 F.U. |
| N: | 1 WC = 40 F.U. |
| O: | 1 WC (40) + 1 UR (20) = 60 F.U. |
| P: | 1 WC (40) + 1 UR (20) + 1 LAV (1) = 61 F.U. |
| Q: | 2 WC (70) + 1 UR (20) + 1 LAV (1) = 91 F.U. |
| R: | 2 WC (70) + 2 UR (35) + 1 LAV (1) = 106 F.U. |
| S: | 2 WC (70) + 2 UR (35) + 2 LAV (2) = 107 F.U. |
| T: | 6 WC (125) + 6 UR (63) + 6 LAV (6) = 194 F.U. |

EXAMPLE 610.10
SIZING METHOD FOR PUBLIC USE FIXTURES
USING TABLE 610.10

610.11 Sizing Systems for Flushometer Tanks. The size of branches and mains serving flushometer tanks shall be consistent with the sizing procedures for flush tank water closets.

610.12 Sizing for Velocity. Water piping systems shall not exceed the maximum velocities listed in this section or Appendix A.

610.12.1 Copper Tube Systems. Maximum velocities in copper and copper alloy tube and fitting systems shall not exceed 8 feet per second (ft/s) (2.4 m/s) in cold water and 5 ft/s (1.5 m/s) in hot water.

610.12.2 Tubing Systems Using Copper Fittings. Maximum velocities through copper fittings in tubing other than copper shall not exceed 8 ft/s (2.4 m/s) in cold water and 5 ft/s (1.5 m/s) in hot water.

610.13 Exceptions. The provisions of this section relative to size of water piping shall not apply to the following:

- (1) Water supply piping systems designed in accordance with recognized engineering procedures acceptable to the Authority Having Jurisdiction.
- (2) Alteration of or minor additions to existing installations, provided the Authority Having Jurisdiction finds that there will be an adequate supply of water to operate fixtures.
- (3) Replacement of existing fixtures or appliances.
- (4) Piping that is part of fixture equipment.
- (5) Unusual conditions where, in the judgment of the Authority Having Jurisdiction, an adequate supply of water is provided to operate fixtures and equipment.
- (6) The size and material of irrigation water piping installed outside of a building or structure and separated from the potable water supply by means of an approved air gap or backflow prevention device is not regulated by this code. The potable water piping system supplying each such irrigation system shall be adequately sized as required elsewhere in this chapter to deliver the full connected demand of both the domestic use and the irrigation systems.

611.0 Drinking Water Treatment Units.

611.1 Application. Drinking water treatment units shall comply with NSF 42 or NSF 53. Water softeners shall comply with NSF 44. Ultraviolet water treatment systems shall comply with NSF 55. Reverse osmosis drinking water treatment systems shall comply with NSF 58. Drinking water distillation systems shall comply with NSF 62.

611.2 Air Gap Discharge. Discharge from drinking water treatment units shall enter the drainage system through an air gap in accordance with Table 603.3.1 or an air gap device in accordance with Table 603.2, NSF 58, or IAPMO PS 65.

611.3 Connection Tubing. The tubing to and from drinking water treatment units shall be of a size and material as recommended by the manufacturer. The tubing shall comply with the requirements of NSF 14, NSF 42, NSF 44, NSF 53, NSF 55, NSF 58, NSF 62 or the appropriate material standards referenced in Table 1701.1.

611.4 Sizing of Residential Softeners. Residential-use water softeners shall be sized in accordance with Table 611.4.

612.0 Residential Fire Sprinkler Systems.

612.1 Where Required. Where residential sprinkler systems are required in one and two family dwellings or townhouses, the systems shall be installed by an ASSE Series 7000 certified installer in accordance with this section or NFPA 13D. This section shall be considered equivalent to NFPA 13D. Partial residential sprinkler systems shall be permitted to be installed in buildings not required to be equipped with a residential sprinkler system.

TABLE 611.4
SIZING OF RESIDENTIAL WATER SOFTENERS⁴

| REQUIRED SIZE OF SOFTENER CONNECTION (inches) | NUMBER OF BATHROOM GROUPS SERVED ¹ |
|---|---|
| $\frac{3}{4}$ | up to 2 ² |
| 1 | up to 4 ³ |

For SI units: 1 inch = 25 mm

Notes:

¹ Installation of a kitchen sink and dishwasher, laundry tray, and automatic clothes washer permitted without additional size increase.

² An additional water closet and lavatory permitted.

³ Over four bathroom groups, the softener size shall be engineered for the specific installation.

⁴ See also Appendix A, Recommended Rules for Sizing the Water Supply System, and Appendix C, Alternate Plumbing Systems, for alternate methods of sizing water supply systems.

612.2 Types of Systems. This section shall apply to stand-alone and multipurpose wet-pipe sprinkler systems that do not include the use of antifreeze. A multipurpose fire sprinkler system shall provide potable water to both fire sprinklers and plumbing fixtures. A stand-alone sprinkler system shall be separate and independent from the potable water distribution system. A backflow preventer shall not be required to separate a stand-alone sprinkler system from the water distribution system where the sprinkler system material is in accordance with the requirements of Section 604.0.

612.3 Sprinklers. Sprinklers shall be installed in accordance with Section 612.3.1 through Section 612.3.7.

612.3.1 Required Sprinkler Locations. Sprinklers shall be installed to protect all floor areas of a dwelling unit in one and two family dwellings or townhouses.

Exceptions:

- (1) Attics, crawl spaces, and normally unoccupied concealed spaces that do not contain fuel-fired appliances do not require sprinklers. In attics, crawl spaces, and normally unoccupied concealed spaces that contain fuel-fired equipment, a sprinkler shall be provided to protect the equipment; however, sprinklers shall not be required in the remainder of the space.
- (2) Clothes closets, linen closets, and pantries that do not exceed 24 square feet (2.2 m²) in area, with the smallest dimension not exceeding 3 feet (914 mm) and having wall and ceiling surfaces of gypsum board.
- (3) Bathrooms and toilet rooms that do not exceed 55 square feet (5.1 m²) in area.
- (4) Garages; carports; exterior porches; unheated entry areas, such as mud rooms, that are adjacent to an exterior door; and similar areas.
- (5) Covered unheated projections of the building at entrances/exits provided it is not the only means of egress from the dwelling unit.
- (6) Ceiling pockets that meet the following requirements:

- (a) The total volume of an unprotected ceiling pocket does not exceed 100 cubic feet (2.83 m³).
- (b) The entire floor under the unprotected ceiling pocket is protected by the sprinklers at the lower ceiling elevation.
- (c) Each unprotected ceiling pocket is separated from an adjacent unprotected ceiling pocket by not less than a 10 feet (3048 mm) horizontal distance.
- (d) The interior finish of the unprotected ceiling pocket is noncombustible material.
- (e) Skylights not exceeding 32 square feet (2.97 m²).

612.3.2 Sprinkler Installation. Sprinklers shall be listed residential sprinklers and shall be installed in accordance with the sprinkler manufacturer's installation instructions.

612.3.3 Temperature Rating and Separation from Heat Sources. Sprinklers shall have a temperature rating of not less than 135°F (57°C) and not more than 170°F (77°C). Sprinklers shall be separated from heat sources in accordance with the sprinkler manufacturer's installation instructions.

Exception: Sprinklers located close to a heat source in accordance with Section 612.3.3.1 shall be intermediate temperature sprinklers.

612.3.3.1 Intermediate Temperature Sprinklers. Sprinklers shall have an intermediate temperature rating of not less than 175°F (79°C) and not more than 225°F (107°C) where installed in the following locations:

- (1) Directly under skylights, where the sprinkler is exposed to direct sunlight.
- (2) In attics and concealed spaces located directly beneath a roof.
- (3) Within the distance to a heat source in accordance with Table 612.3.3.1.

612.3.4 Freezing Areas. The piping system shall be protected in accordance with the requirements of Chapter 3. Where sprinklers are required in areas that are subject to freezing, dry-sidewall or dry-pendent sprinklers extending from a non-freezing area into a freezing area shall be installed.

612.3.5 Coverage Area Limit. The area of coverage of a single sprinkler shall be based on the sprinkler listing and the sprinkler manufacturer's installation instructions. The area of coverage of a single sprinkler shall not exceed 400 square feet (37.16 m²).

612.3.6 Obstructions to Sprinkler Coverage. The water discharge from a sprinkler shall not be blocked by obstructions unless additional sprinklers are installed to protect the obstructed area. Additional sprinklers shall not be required where sprinkler separation from obstructions is in accordance with the requirements of Table 612.3.6, or the minimum distances specified in the sprinkler manufacturer's installation instructions.

TABLE 612.3.3.1
LOCATIONS WHERE INTERMEDIATE TEMPERATURE
SPRINKLERS ARE REQUIRED

| HEAT SOURCE | DISTANCE FROM HEAT SOURCE ¹ | |
|---|--|---------------------------|
| | MINIMUM DISTANCE ² (Inches) | MAXIMUM DISTANCE (Inches) |
| Fireplace, Side of Open or Recessed Fireplace | 12 | 36 |
| Fireplace, Front of Recessed Fireplace | 36 | 60 |
| Coal and Wood Burning Stove | 12 | 42 |
| Kitchen Range Top | 9 | 18 |
| Oven | 9 | 18 |
| Vent Connector or Chimney Connector | 9 | 18 |
| Heating Duct, Not Insulated | 9 | 18 |
| Hot Water Pipe, Not Insulated | 6 | 12 |
| Side of Ceiling or Wall Warm Air Register | 12 | 24 |
| Front of Wall Mounted Warm Air Register | 18 | 36 |
| Water Heater, Furnace, or Boiler | 3 | 6 |
| Luminaire up to 250 Watts | 3 | 6 |
| Luminaire 250 Watts up to 499 Watts | 6 | 12 |

For SI units: 1 inch = 25.4 mm

Notes:

¹ Distances shall be measured in a straight line from the nearest edge of the heat source to the nearest edge of the sprinkler.

² Sprinklers shall not be located at distances less than the minimum table distance unless the sprinkler listing allows a lesser distance.

612.3.6.1 Additional Requirements for Pendent Sprinklers. Pendent sprinklers located within 3 feet (914 mm) of the center of a ceiling fan, surface-mounted ceiling luminaire, or similar object shall be considered to be obstructed and additional sprinklers shall be provided.

612.3.6.2 Additional Requirements for Sidewall Sprinklers. Sidewall sprinklers located within 5 feet (1524 mm) of the center of a ceiling fan, surface-mounted ceiling luminaire, or similar object shall be considered to be obstructed and additional sprinklers shall be provided.

612.3.7 Sprinkler Modifications Prohibited. Sprinklers shall not be painted, caulked, or modified. A sprinkler that has been painted, caulked, modified, or damaged shall be replaced with a new sprinkler.

612.4 Sprinkler Piping System. Sprinkler piping systems shall be installed in accordance with Section 612.4.1 through Section 612.4.5.

612.4.1 General. Sprinkler piping shall be installed in accordance with the requirements for water distribution piping. Sprinkler piping shall comply with the material requirements for cold water distribution piping. For multipurpose piping systems, the sprinkler piping shall connect to and be a part of the cold water distribution piping system.

612.4.2 Nonmetallic Pipe and Tubing. Nonmetallic pipe and tubing, such as CPVC, PEX-AL-PEX, PE-

RT, and PEX, shall be certified for residential sprinkler installations and shall have a pressure rating of not less than 130 psi (896 kPa) at 120°F (49°C).

612.4.2.1 Nonmetallic Pipe Protection. Non-metallic pipe and tubing systems shall be protected from exposure to the occupied space by a layer of not less than $\frac{3}{8}$ of an inch (9.5 mm) thick gypsum wallboard, $\frac{1}{2}$ of an inch (12.7 mm) thick plywood, or other material having a 15 minute fire rating.

Exceptions:

- (1) Pipe protection shall not be required in areas that are not required to be protected with sprinklers in accordance with Section 612.3.1.
- (2) Pipe protection shall not be required where exposed piping is permitted by the pipe third party listing.

612.4.2.2 Sprinkler Installation on Systems Assembled with Solvent Cement. The solvent cementing of fittings shall be completed and threaded adapters for sprinklers shall be verified as being clear of excess cement prior to the installation of sprinklers on systems assembled with solvent cement.

612.4.3 Shutoff Valves Prohibited. Shutoff valves shall not be installed in a location where the valve would isolate piping serving one or more sprinklers. Shutoff valves shall only be permitted for the entire water distribution system.

612.4.4 Single Dwelling Limit. The sprinkler piping beyond the service valve located at the beginning of the water distribution system shall serve only one dwelling unit.

612.4.5 Drain. A $\frac{1}{2}$ inch (15 mm) drain for the sprinkler system shall be provided on the system side of the water distribution shutoff valve.

612.5 Sprinkler Piping Design. Sprinkler piping systems shall be sized in accordance with Section 612.5.1 through Section 612.5.3.2.2.


612.5.1 Determining System Design Flow. The sizing of the sprinkler piping system shall be based on the flow rate and pressure of each sprinkler in accordance with Section 612.5.1.1 and the number of sprinklers in accordance with Section 612.5.1.2.


612.5.1.1 Determining Required Flow Rate for Each Sprinkler. The minimum flow rate and pressure for each residential sprinkler shall be in accordance with the manufacturer's published data for the specific sprinkler model based on the following:


- (1) The area of coverage
- (2) The ceiling configuration
- (3) The temperature rating
- (4) Additional conditions specified by the sprinkler manufacturer

612.5.1.2 System Flow Rate. The flow rate used for sizing the sprinkler piping system shall be based on the following:

TABLE 612.3.6
MINIMUM SEPARATION FROM OBSTRUCTION

| | |
|--|--|
| PENDENT SPRINKLERS |  |
| DISTANCE FROM DEFLECTOR TO PLANE AT BOTTOM OF OBSTRUCTION (A) (inches) | MINIMUM DISTANCE TO OBSTRUCTION (B) (feet) |
| 1 | 1½ |
| 3 | 3 |
| 5 | 4 |
| 7 | 4½ |
| 9 | 6 |
| 11 | 6½ |
| 14 | 7 |

| | |
|--|---|
| SIDEWALL SPRINKLER SIDE OBSTRUCTION |  |
| DISTANCE FROM DEFLECTOR TO PLANE AT BOTTOM OF OBSTRUCTION (A) (inches) | MINIMUM DISTANCE TO OBSTRUCTION (B) (feet) |
| 1 | 1½ |
| 3 | 3 |
| 5 | 4 |
| 7 | 4½ |
| 9 | 6 |
| 11 | 6½ |
| 14 | 7 |

| | |
|--|--|
| SIDEWALL SPRINKLER FORWARD OBSTRUCTION |  |
| DISTANCE FROM DEFLECTOR TO PLANE AT BOTTOM OF OBSTRUCTION (A) (inches) | MINIMUM DISTANCE TO OBSTRUCTION (B) (feet) |
| 1 | 8 |
| 2 | 10 |
| 3 | 11 |
| 4 | 12 |
| 6 | 13 |
| 7 | 14 |
| 9 | 15 |
| 11 | 16 |
| 14 | 17 |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm

- (1) The flow rate for a room having only one sprinkler shall be the flow rate required for the sprinkler in accordance with Section 612.5.1.1.
- (2) The flow rate for a room having two or more sprinklers shall be determined by identifying the sprinkler in the room with the highest required flow rate in accordance with Section 612.5.1.1, and multiplying that flow rate by 2.
- (3) Where the sprinkler manufacturer specifies different criteria for ceiling configurations that are not smooth, flat, and horizontal the required flow rate for that room shall be in accordance with the sprinkler manufacturer's instructions.
- (4) The flow rate used for sizing the sprinkler system shall be the flow required by the room with the largest flow rate in accordance with Section 612.5.1.2(1), Section 612.5.1.2(2), and Section 612.5.1.2(3).
- (5) For the purpose of this section, it shall be permissible to reduce the flow rate for a room by subdividing the space into two or more rooms, where each room is evaluated separately with respect to the required design flow rate. Each room shall be bounded by walls and a ceiling. Openings in walls shall have a lintel not less than 8 inches (203 mm) in depth and each lintel shall form a solid barrier between the ceiling and the top of the opening.

612.5.2 Sprinkler Pipe Water Supply. The water supply for a multipurpose or stand alone sprinkler system shall be provided by the public water main, private water main, private well system, or storage tank. The water supply required shall be determined in accordance with Section 612.5.1.2 at a pressure not less than that used in accordance with Section 612.5.3.

612.5.2.1 Water Pressure from Individual Sources. Where a dwelling unit water supply is from a tank system, a private well system, or a combination of these, the available water pressure shall be based on the minimum pressure control setting of the pump.

612.5.2.2 Required Capacity. The water supply shall have the capacity to provide the required flow rate to the sprinklers for a period of time as follows:

- (1) Seven minutes for one story dwelling units less than 2000 square feet (185.81 m²) in area.
- (2) Ten minutes for multi-level dwelling units and one story dwelling units not less than 2000 square feet (185.81 m²) in area.

Where a well system, a water supply tank system, or a combination thereof is used a combination of well capacity and tank storage shall be permitted to meet the capacity requirement.

612.5.3 Sprinkler Pipe Sizing. The sprinkler piping shall be sized for the flow rate in accordance with Section 612.5.1. The flow rate required to supply the

plumbing fixtures shall not be required to be added to the sprinkler design flow for multipurpose or stand-alone piping systems. The sizing of the water supply to the plumbing fixtures shall be determined in accordance with this chapter. For multipurpose piping systems, the largest pipe size required based on either the sprinkler piping calculations or the water distribution piping calculations shall be installed.

612.5.3.1 Sprinkler Pipe Sizing Method. The sprinkler pipe shall be sized using the prescriptive method in Section 612.5.3.2 or by hydraulic calculation in accordance with NFPA 13D. The sprinkler pipe size from the water supply source to a sprinkler shall be not less than ¾ of an inch (20 mm) in diameter. Threaded adapter fittings at the point where sprinklers are attached to the piping shall be not less than ½ of an inch (15 mm) in diameter.

612.5.3.2 Prescriptive Pipe Sizing Method. The sprinkler pipe shall be sized by determining the available pressure to offset friction loss in piping and based on the piping material, diameter and length using the equation in Section 612.5.3.2.1 and the procedure in Section 612.5.3.2.2.

612.5.3.2.1 Available Pressure Equation. The available system pressure (P_t) for sizing the sprinkler piping shall be determined in accordance with the Equation 612.5.3.2.1.

[Equation 612.5.3.2.1]

$$P_t = P_{sup} - PL_{ws} - PL_m - PL_d - PL_e - P_{sp}$$

Where:

P_t = Pressure used for sizing the system in Table 612.5.3.2(4) through Table 612.5.3.2(9)

P_{sup} = Pressure available from the water supply source

PL_{ws} = Pressure loss in the water service pipe

PL_m = Pressure loss through the water meter

PL_d = Pressure loss from devices other than the water meter

PL_e = Pressure loss associated with changes in elevation

P_{sp} = Maximum pressure required by a sprinkler

612.5.3.2.2 Calculation Procedure. The following procedure shall be used to determine the minimum size of the residential sprinkler piping:

Step 1 - Determine P_{sup}

Obtain the supply pressure available from the water main from the water purveyor, or for an individual source, the available supply pres-

sure shall be in accordance with Section 612.5.2.1. The pressure shall be the flowing pressure available at the flow rate used when applying Table 612.5.3.2(1).

Step 2 – Determine PL_{ws}

Use Table 612.5.3.2(1) to determine the pressure loss in the water service pipe based on the size of the water service. Where the water service supplies more than one dwelling unit, 5 gpm (0.3 L/s) shall be added to the sprinkler flow rate.

Step 3 – Determine PL_m

Use Table 612.5.3.2(2) to determine the pressure loss from the water meter based on the water meter size.

Step 4 – Determine PL_d

Determine the pressure loss from devices, other than the water meter, installed in the piping system supplying sprinklers such as pressure-reducing valves, backflow preventers, water softeners, or water filters. Device pressure losses shall be based on the device manufacturer's specifications. The flow rate used to determine pressure loss shall be the sprinkler flow rate from Section 612.5.1.2. As an alternative to deducting pressure loss for a

device, an automatic bypass valve shall be installed to divert flow around the device when a sprinkler activates.

Step 5 – Determine PL_e

Use Table 612.5.3.2(3) to determine the pressure loss associated with changes in elevation. The elevation used in applying the table shall be the difference between the elevation where the water source pressure was measured and the elevation of the highest sprinkler.

Step 6 – Determine P_{sp}

Determine the maximum pressure required by an individual sprinkler based on the flow rate from Section 612.5.1.1. The minimum pressure required is specified in the sprinkler manufacturer's published data for the specific sprinkler model based on the selected flow rate.

Step 7 – Calculate P_t

Using Equation 612.5.3.2.1, calculate the available system pressure for sizing the sprinkler piping.

Step 8 – Determine the maximum allowable pipe length

Use Table 612.5.3.2(4) through Table 612.5.3.2(9) to select a material and size for the residential sprinkler piping. The piping

TABLE 612.5.3.2(1)
WATER SERVICE PRESSURE LOSS (PL_{ws})^{1, 2, 3}

| FLOW RATE (gpm) | ¾ INCH WATER SERVICE PRESSURE LOSS (psi) | | | | 1 INCH WATER SERVICE PRESSURE LOSS (psi) | | | | 1½ INCH WATER SERVICE PRESSURE LOSS (psi) | | | |
|-----------------|--|--------------------|---------------------|----------------------|--|--------------------|---------------------|----------------------|---|--------------------|---------------------|----------------------|
| | 40 FEET OR LESS | 41 FEET TO 75 FEET | 76 FEET TO 100 FEET | 101 FEET TO 150 FEET | 40 FEET OR LESS | 41 FEET TO 75 FEET | 76 FEET TO 100 FEET | 101 FEET TO 150 FEET | 40 FEET OR LESS | 41 FEET TO 75 FEET | 76 FEET TO 100 FEET | 101 FEET TO 150 FEET |
| 8 | 5.1 | 8.7 | 11.8 | 17.4 | 1.5 | 2.5 | 3.4 | 5.1 | 0.6 | 1.0 | 1.3 | 1.9 |
| 10 | 7.7 | 13.1 | 17.8 | 26.3 | 2.3 | 3.8 | 5.2 | 7.7 | 0.8 | 1.4 | 2.0 | 2.9 |
| 12 | 10.8 | 18.4 | 24.9 | NP | 3.2 | 5.4 | 7.3 | 10.7 | 1.2 | 2.0 | 2.7 | 4.0 |
| 14 | 14.4 | 24.5 | NP | NP | 4.2 | 7.1 | 9.6 | 14.3 | 1.6 | 2.7 | 3.6 | 5.4 |
| 16 | 18.4 | NP | NP | NP | 5.4 | 9.1 | 12.4 | 18.3 | 2.0 | 3.4 | 4.7 | 6.9 |
| 18 | 22.9 | NP | NP | NP | 6.7 | 11.4 | 15.4 | 22.7 | 2.5 | 4.3 | 5.8 | 8.6 |
| 20 | 27.8 | NP | NP | NP | 8.1 | 13.8 | 18.7 | 27.6 | 3.1 | 5.2 | 7.0 | 10.4 |
| 22 | NP | NP | NP | NP | 9.7 | 16.5 | 22.3 | NP | 3.7 | 6.2 | 8.4 | 12.4 |
| 24 | NP | NP | NP | NP | 11.4 | 19.3 | 26.2 | NP | 4.3 | 7.3 | 9.9 | 14.6 |
| 26 | NP | NP | NP | NP | 13.2 | 22.4 | NP | NP | 5.0 | 8.5 | 11.4 | 16.9 |
| 28 | NP | NP | NP | NP | 15.1 | 25.7 | NP | NP | 5.7 | 9.7 | 13.1 | 19.4 |
| 30 | NP | NP | NP | NP | 17.2 | NP | NP | NP | 6.5 | 11.0 | 14.9 | 22.0 |
| 32 | NP | NP | NP | NP | 19.4 | NP | NP | NP | 7.3 | 12.4 | 16.8 | 24.8 |
| 34 | NP | NP | NP | NP | 21.7 | NP | NP | NP | 8.2 | 13.9 | 18.8 | NP |
| 36 | NP | NP | NP | NP | 24.1 | NP | NP | NP | 9.1 | 15.4 | 20.9 | NP |

For SI units: 1 gallon per minute = 0.06 L/s, 1 pound-force per square inch = 6.8947 kPa, 1 inch = 25 mm, 1 foot = 304.8 mm

Notes:

¹ Values are applicable for underground piping materials and are based on polyethylene pipe having an SDR of 11 and a Hazen Williams C Factor of 150.

² Values include the following length allowances for fittings: 25 percent length increase for actual lengths up to 100 feet (30 480 mm) and 15 percent length increase for actual lengths over 100 feet (30 480 mm).

³ NP – Means not permitted.

material and size shall be acceptable where the developed length of pipe between the inside water service valve and the most remote sprinkler does not exceed the maximum allowable length specified by the applicable table. Interpolation of P_t between the tabular values shall be permitted.

The maximum allowable length of piping in Table 612.5.3.2(4) through Table 612.5.3.2(9) incorporates an adjustment for pipe fittings, and no additional consideration of friction losses associated with pipe fittings shall be required.

TABLE 612.5.3.2(2)
MINIMUM WATER METER PRESSURE LOSS (PL_m)^{1, 2}

| FLOW RATE (gpm) | ½ INCH METER PRESSURE LOSS (psi) | ¾ INCH METER PRESSURE LOSS (psi) | 1 INCH METER PRESSURE LOSS (psi) |
|-----------------|----------------------------------|----------------------------------|----------------------------------|
| 8 | 2 | 1 | 1 |
| 10 | 3 | 1 | 1 |
| 12 | 4 | 1 | 1 |
| 14 | 5 | 2 | 1 |
| 16 | 7 | 3 | 1 |
| 18 | 9 | 4 | 1 |
| 20 | 11 | 4 | 2 |
| 22 | NP | 5 | 2 |
| 24 | NP | 5 | 2 |
| 26 | NP | 6 | 2 |
| 28 | NP | 6 | 2 |
| 30 | NP | 7 | 2 |
| 32 | NP | 7 | 3 |
| 34 | NP | 8 | 3 |
| 36 | NP | 8 | 3 |

For SI units: 1 gallon per minute = 0.06 L/s, 1 pound-force per square inch = 6.8947 kPa, 1 inch = 25 mm

Notes:

¹ Table 612.5.3.2(2) establishes conservative values for water meter pressure loss for installations where the water meter loss is unknown. Where the actual water meter pressure loss is known, PL_m shall be the pressure loss as specified by the meter manufacturer.

² NP – Means not permitted.

612.6 Instructions and Signs. An owner's manual for the fire sprinkler system shall be provided to the owner. A sign or valve tag shall be installed at the main shutoff valve to the water distribution system stating the following: *"Warning, the water system for this home supplies fire sprinklers that require certain flow and pressure to fight a fire. Devices that restrict the flow, decrease the pressure, or automatically shut off the water to the fire sprinkler system, such as water softeners, filtration systems, and automatic shutoff valves shall not be added to this system without a review of the fire sprinkler system by a fire protection specialist. Do not remove this sign."*

612.7 Inspection and Testing. The inspection and testing of sprinkler systems shall be in accordance with Section 612.7.1 and Section 612.7.2.

612.7.1 Pre-Concealment Inspection. The following shall be verified prior to the concealment of any sprinkler system piping:

- (1) Sprinklers are installed in all areas in accordance with Section 612.3.1.
- (2) Where sprinkler water spray patterns are obstructed by construction features, luminaires or ceiling fans, additional sprinklers are installed in accordance with Section 612.3.6.
- (3) Sprinklers are the correct temperature rating and are installed at or beyond the required separation distances from heat sources in accordance with Section 612.3.3 and Section 612.3.3.1.
- (4) The minimum pipe size in accordance with the requirements of Table 612.5.3.2(4) through Table 612.5.3.2(9) or, where the piping system was hydraulically calculated in accordance with Section 612.5.3.1, the size used in the hydraulic calculation.
- (5) The pipe length does not exceed the length permitted by Table 612.5.3.2(4) through Table 612.5.3.2(9) or, where the piping system was hydraulically calculated in accordance with Section 612.5.3.1, pipe lengths and fittings shall not exceed those used in the hydraulic calculation.
- (6) Nonmetallic piping that conveys water to sprinklers is certified as having a pressure rating of not less than 130 psi (896 kPa) at 120°F (49°C).
- (7) Piping is properly supported.
- (8) The piping system is tested in accordance with Section 609.4.

612.7.2 Final Inspection. Upon completion of the residential sprinkler system, the system shall be inspected. The following shall be verified during the final inspection:

- (1) Sprinklers are not painted, damaged, or otherwise hindered from operation.
- (2) Where a pump is required to provide water to the system, the pump starts automatically upon system water demand.
- (3) Pressure reducing valves, water softeners, water filters, or other impairments to water flow that were not part of the original design have not been installed.
- (4) The sign or valve tag in accordance with Section 612.6 is installed and the owner's manual for the system is present.

TABLE 612.5.3.2(3)
ELEVATION LOSS (PL_e)

| ELEVATION (feet) | PRESSURE LOSS (psi) |
|------------------|---------------------|
| 5 | 2.2 |
| 10 | 4.4 |
| 15 | 6.5 |
| 20 | 8.7 |
| 25 | 10.9 |
| 30 | 13.0 |
| 35 | 15.2 |
| 40 | 17.4 |

For SI units: 1 foot = 304.8 mm, 1 pound-force per square inch = 6.8947 kPa

TABLE 612.5.3.2(4)
ALLOWABLE PIPE LENGTH FOR ¾ INCH TYPE M COPPER WATER TUBING*

| SPRINKLER FLOW RATE (gpm) | WATER DISTRIBUTION SIZE (inch) | AVAILABLE PRESSURE - P _t (psi) | | | | | | | | | |
|---------------------------------|---|--|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| | | 15 | 20 | 25 | 30 | 35 | 40 | 45 | 50 | 55 | 60 |
| | | ALLOWABLE LENGTH OF PIPE FROM SERVICE VALVE TO FARTHEST SPRINKLER (feet) | | | | | | | | | |
| 8 | ¾ | 217 | 289 | 361 | 434 | 506 | 578 | 650 | 723 | 795 | 867 |
| 9 | ¾ | 174 | 232 | 291 | 349 | 407 | 465 | 523 | 581 | 639 | 697 |
| 10 | ¾ | 143 | 191 | 239 | 287 | 335 | 383 | 430 | 478 | 526 | 574 |
| 11 | ¾ | 120 | 160 | 200 | 241 | 281 | 321 | 361 | 401 | 441 | 481 |
| 12 | ¾ | 102 | 137 | 171 | 205 | 239 | 273 | 307 | 341 | 375 | 410 |
| 13 | ¾ | 88 | 118 | 147 | 177 | 206 | 235 | 265 | 294 | 324 | 353 |
| 14 | ¾ | 77 | 103 | 128 | 154 | 180 | 205 | 231 | 257 | 282 | 308 |
| 15 | ¾ | 68 | 90 | 113 | 136 | 158 | 181 | 203 | 226 | 248 | 271 |
| 16 | ¾ | 60 | 80 | 100 | 120 | 140 | 160 | 180 | 200 | 220 | 241 |
| 17 | ¾ | 54 | 72 | 90 | 108 | 125 | 143 | 161 | 179 | 197 | 215 |
| 18 | ¾ | 48 | 64 | 81 | 97 | 113 | 129 | 145 | 161 | 177 | 193 |
| 19 | ¾ | 44 | 58 | 73 | 88 | 102 | 117 | 131 | 146 | 160 | 175 |
| 20 | ¾ | 40 | 53 | 66 | 80 | 93 | 106 | 119 | 133 | 146 | 159 |
| 21 | ¾ | 36 | 48 | 61 | 73 | 85 | 97 | 109 | 121 | 133 | 145 |
| 22 | ¾ | 33 | 44 | 56 | 67 | 78 | 89 | 100 | 111 | 122 | 133 |
| 23 | ¾ | 31 | 41 | 51 | 61 | 72 | 82 | 92 | 102 | 113 | 123 |
| 24 | ¾ | 28 | 38 | 47 | 57 | 66 | 76 | 85 | 95 | 104 | 114 |
| 25 | ¾ | 26 | 35 | 44 | 53 | 61 | 70 | 79 | 88 | 97 | 105 |
| 26 | ¾ | 24 | 33 | 41 | 49 | 57 | 65 | 73 | 82 | 90 | 98 |
| 27 | ¾ | 23 | 30 | 38 | 46 | 53 | 61 | 69 | 76 | 84 | 91 |
| 28 | ¾ | 21 | 28 | 36 | 43 | 50 | 57 | 64 | 71 | 78 | 85 |
| 29 | ¾ | 20 | 27 | 33 | 40 | 47 | 53 | 60 | 67 | 73 | 80 |
| 30 | ¾ | 19 | 25 | 31 | 38 | 44 | 50 | 56 | 63 | 69 | 75 |
| 31 | ¾ | 18 | 24 | 29 | 35 | 41 | 47 | 53 | 59 | 65 | 71 |
| 32 | ¾ | 17 | 22 | 28 | 33 | 39 | 44 | 50 | 56 | 61 | 67 |
| 33 | ¾ | 16 | 21 | 26 | 32 | 37 | 42 | 47 | 53 | 58 | 63 |
| 34 | ¾ | NP | 20 | 25 | 30 | 35 | 40 | 45 | 50 | 55 | 60 |
| 35 | ¾ | NP | 19 | 24 | 28 | 33 | 38 | 42 | 47 | 52 | 57 |
| 36 | ¾ | NP | 18 | 22 | 27 | 31 | 36 | 40 | 45 | 49 | 54 |
| 37 | ¾ | NP | 17 | 21 | 26 | 30 | 34 | 38 | 43 | 47 | 51 |
| 38 | ¾ | NP | 16 | 20 | 24 | 28 | 32 | 36 | 40 | 45 | 49 |
| 39 | ¾ | NP | 15 | 19 | 23 | 27 | 31 | 35 | 39 | 42 | 46 |
| 40 | ¾ | NP | NP | 18 | 22 | 26 | 29 | 33 | 37 | 40 | 44 |

For SI units: 1 pound-force per square inch = 6.8947 kPa, 1 gallon per minute = 0.06 L/s, 1 inch = 25 mm, 1 foot = 304.8 mm

* NP – Means not permitted.

TABLE 612.5.3.2(5)
ALLOWABLE PIPE LENGTH FOR 1 INCH TYPE M COPPER WATER TUBING

| SPRINKLER FLOW RATE (gpm) | WATER DISTRIBUTION SIZE (inch) | AVAILABLE PRESSURE - P_t (psi) | | | | | | | | | |
|---------------------------------|---|--|------|------|------|------|------|------|------|------|------|
| | | 15 | 20 | 25 | 30 | 35 | 40 | 45 | 50 | 55 | 60 |
| | | ALLOWABLE LENGTH OF PIPE FROM SERVICE VALVE TO FARTHEST SPRINKLER (feet) | | | | | | | | | |
| 8 | 1 | 806 | 1075 | 1343 | 1612 | 1881 | 2149 | 2418 | 2687 | 2955 | 3224 |
| 9 | 1 | 648 | 864 | 1080 | 1296 | 1512 | 1728 | 1945 | 2161 | 2377 | 2593 |
| 10 | 1 | 533 | 711 | 889 | 1067 | 1245 | 1422 | 1600 | 1778 | 1956 | 2134 |
| 11 | 1 | 447 | 596 | 745 | 894 | 1043 | 1192 | 1341 | 1491 | 1640 | 1789 |
| 12 | 1 | 381 | 508 | 634 | 761 | 888 | 1015 | 1142 | 1269 | 1396 | 1523 |
| 13 | 1 | 328 | 438 | 547 | 657 | 766 | 875 | 985 | 1094 | 1204 | 1313 |
| 14 | 1 | 286 | 382 | 477 | 572 | 668 | 763 | 859 | 954 | 1049 | 1145 |
| 15 | 1 | 252 | 336 | 420 | 504 | 588 | 672 | 756 | 840 | 924 | 1008 |
| 16 | 1 | 224 | 298 | 373 | 447 | 522 | 596 | 671 | 745 | 820 | 894 |
| 17 | 1 | 200 | 266 | 333 | 400 | 466 | 533 | 600 | 666 | 733 | 799 |
| 18 | 1 | 180 | 240 | 300 | 360 | 420 | 479 | 539 | 599 | 659 | 719 |
| 19 | 1 | 163 | 217 | 271 | 325 | 380 | 434 | 488 | 542 | 597 | 651 |
| 20 | 1 | 148 | 197 | 247 | 296 | 345 | 395 | 444 | 493 | 543 | 592 |
| 21 | 1 | 135 | 180 | 225 | 270 | 315 | 360 | 406 | 451 | 496 | 541 |
| 22 | 1 | 124 | 165 | 207 | 248 | 289 | 331 | 372 | 413 | 455 | 496 |
| 23 | 1 | 114 | 152 | 190 | 228 | 267 | 305 | 343 | 381 | 419 | 457 |
| 24 | 1 | 106 | 141 | 176 | 211 | 246 | 282 | 317 | 352 | 387 | 422 |
| 25 | 1 | 98 | 131 | 163 | 196 | 228 | 261 | 294 | 326 | 359 | 392 |
| 26 | 1 | 91 | 121 | 152 | 182 | 212 | 243 | 273 | 304 | 334 | 364 |
| 27 | 1 | 85 | 113 | 142 | 170 | 198 | 226 | 255 | 283 | 311 | 340 |
| 28 | 1 | 79 | 106 | 132 | 159 | 185 | 212 | 238 | 265 | 291 | 318 |
| 29 | 1 | 74 | 99 | 124 | 149 | 174 | 198 | 223 | 248 | 273 | 298 |
| 30 | 1 | 70 | 93 | 116 | 140 | 163 | 186 | 210 | 233 | 256 | 280 |
| 31 | 1 | 66 | 88 | 110 | 132 | 153 | 175 | 197 | 219 | 241 | 263 |
| 32 | 1 | 62 | 83 | 103 | 124 | 145 | 165 | 186 | 207 | 227 | 248 |
| 33 | 1 | 59 | 78 | 98 | 117 | 137 | 156 | 176 | 195 | 215 | 234 |
| 34 | 1 | 55 | 74 | 92 | 111 | 129 | 148 | 166 | 185 | 203 | 222 |
| 35 | 1 | 53 | 70 | 88 | 105 | 123 | 140 | 158 | 175 | 193 | 210 |
| 36 | 1 | 50 | 66 | 83 | 100 | 116 | 133 | 150 | 166 | 183 | 199 |
| 37 | 1 | 47 | 63 | 79 | 95 | 111 | 126 | 142 | 158 | 174 | 190 |
| 38 | 1 | 45 | 60 | 75 | 90 | 105 | 120 | 135 | 150 | 165 | 181 |
| 39 | 1 | 43 | 57 | 72 | 86 | 100 | 115 | 129 | 143 | 158 | 172 |
| 40 | 1 | 41 | 55 | 68 | 82 | 96 | 109 | 123 | 137 | 150 | 164 |

For SI units: 1 pound-force per square inch = 6.8947 kPa, 1 gallon per minute = 0.06 L/s, 1 inch = 25 mm, 1 foot = 304.8 mm

TABLE 612.5.3.2(6)
ALLOWABLE PIPE LENGTH FOR ¾ INCH IPS CPVC PIPE

| SPRINKLER FLOW RATE (gpm) | WATER DISTRIBUTION SIZE (inch) | AVAILABLE PRESSURE - P _t (psi) | | | | | | | | | |
|---------------------------------|---|--|-----|-----|-----|-----|-----|------|------|------|------|
| | | 15 | 20 | 25 | 30 | 35 | 40 | 45 | 50 | 55 | 60 |
| | | ALLOWABLE LENGTH OF PIPE FROM SERVICE VALVE TO FARTHEST SPRINKLER (feet) | | | | | | | | | |
| 8 | ¾ | 348 | 465 | 581 | 697 | 813 | 929 | 1045 | 1161 | 1278 | 1394 |
| 9 | ¾ | 280 | 374 | 467 | 560 | 654 | 747 | 841 | 934 | 1027 | 1121 |
| 10 | ¾ | 231 | 307 | 384 | 461 | 538 | 615 | 692 | 769 | 845 | 922 |
| 11 | ¾ | 193 | 258 | 322 | 387 | 451 | 515 | 580 | 644 | 709 | 773 |
| 12 | ¾ | 165 | 219 | 274 | 329 | 384 | 439 | 494 | 549 | 603 | 658 |
| 13 | ¾ | 142 | 189 | 237 | 284 | 331 | 378 | 426 | 473 | 520 | 568 |
| 14 | ¾ | 124 | 165 | 206 | 247 | 289 | 330 | 371 | 412 | 454 | 495 |
| 15 | ¾ | 109 | 145 | 182 | 218 | 254 | 290 | 327 | 363 | 399 | 436 |
| 16 | ¾ | 97 | 129 | 161 | 193 | 226 | 258 | 290 | 322 | 354 | 387 |
| 17 | ¾ | 86 | 115 | 144 | 173 | 202 | 230 | 259 | 288 | 317 | 346 |
| 18 | ¾ | 78 | 104 | 130 | 155 | 181 | 207 | 233 | 259 | 285 | 311 |
| 19 | ¾ | 70 | 94 | 117 | 141 | 164 | 188 | 211 | 234 | 258 | 281 |
| 20 | ¾ | 64 | 85 | 107 | 128 | 149 | 171 | 192 | 213 | 235 | 256 |
| 21 | ¾ | 58 | 78 | 97 | 117 | 136 | 156 | 175 | 195 | 214 | 234 |
| 22 | ¾ | 54 | 71 | 89 | 107 | 125 | 143 | 161 | 179 | 197 | 214 |
| 23 | ¾ | 49 | 66 | 82 | 99 | 115 | 132 | 148 | 165 | 181 | 198 |
| 24 | ¾ | 46 | 61 | 76 | 91 | 107 | 122 | 137 | 152 | 167 | 183 |
| 25 | ¾ | 42 | 56 | 71 | 85 | 99 | 113 | 127 | 141 | 155 | 169 |
| 26 | ¾ | 39 | 52 | 66 | 79 | 92 | 105 | 118 | 131 | 144 | 157 |
| 27 | ¾ | 37 | 49 | 61 | 73 | 86 | 98 | 110 | 122 | 135 | 147 |
| 28 | ¾ | 34 | 46 | 57 | 69 | 80 | 92 | 103 | 114 | 126 | 137 |
| 29 | ¾ | 32 | 43 | 54 | 64 | 75 | 86 | 96 | 107 | 118 | 129 |
| 30 | ¾ | 30 | 40 | 50 | 60 | 70 | 81 | 91 | 101 | 111 | 121 |
| 31 | ¾ | 28 | 38 | 47 | 57 | 66 | 76 | 85 | 95 | 104 | 114 |
| 32 | ¾ | 27 | 36 | 45 | 54 | 63 | 71 | 80 | 89 | 98 | 107 |
| 33 | ¾ | 25 | 34 | 42 | 51 | 59 | 68 | 76 | 84 | 93 | 101 |
| 34 | ¾ | 24 | 32 | 40 | 48 | 56 | 64 | 72 | 80 | 88 | 96 |
| 35 | ¾ | 23 | 30 | 38 | 45 | 53 | 61 | 68 | 76 | 83 | 91 |
| 36 | ¾ | 22 | 29 | 36 | 43 | 50 | 57 | 65 | 72 | 79 | 86 |
| 37 | ¾ | 20 | 27 | 34 | 41 | 48 | 55 | 61 | 68 | 75 | 82 |
| 38 | ¾ | 20 | 26 | 33 | 39 | 46 | 52 | 59 | 65 | 72 | 78 |
| 39 | ¾ | 19 | 25 | 31 | 37 | 43 | 50 | 56 | 62 | 68 | 74 |
| 40 | ¾ | 18 | 24 | 30 | 35 | 41 | 47 | 53 | 59 | 65 | 71 |

For SI units: 1 pound-force per square inch = 6.8947 kPa, 1 gallon per minute = 0.06 L/s, 1 inch = 25 mm, 1 foot = 304.8 mm

TABLE 612.5.3.2(7)
ALLOWABLE PIPE LENGTH FOR 1 INCH IPS CPVC PIPE

| SPRINKLER FLOW RATE (gpm) | WATER DISTRIBUTION SIZE (inch) | AVAILABLE PRESSURE - P_t (psi) | | | | | | | | | |
|---------------------------------|--------------------------------------|---|------|------|------|------|------|------|------|------|------|
| | | 15 | 20 | 25 | 30 | 35 | 40 | 45 | 50 | 55 | 60 |
| | | ALLOWABLE LENGTH OF PIPE FROM SERVICE VALVE TO FARTHEST SPRINKLER | | | | | | | | | |
| 8 | 1 | 1049 | 1398 | 1748 | 2098 | 2447 | 2797 | 3146 | 3496 | 3845 | 4195 |
| 9 | 1 | 843 | 1125 | 1406 | 1687 | 1968 | 2249 | 2530 | 2811 | 3093 | 3374 |
| 10 | 1 | 694 | 925 | 1157 | 1388 | 1619 | 1851 | 2082 | 2314 | 2545 | 2776 |
| 11 | 1 | 582 | 776 | 970 | 1164 | 1358 | 1552 | 1746 | 1940 | 2133 | 2327 |
| 12 | 1 | 495 | 660 | 826 | 991 | 1156 | 1321 | 1486 | 1651 | 1816 | 1981 |
| 13 | 1 | 427 | 570 | 712 | 854 | 997 | 1139 | 1281 | 1424 | 1566 | 1709 |
| 14 | 1 | 372 | 497 | 621 | 745 | 869 | 993 | 1117 | 1241 | 1366 | 1490 |
| 15 | 1 | 328 | 437 | 546 | 656 | 765 | 874 | 983 | 1093 | 1202 | 1311 |
| 16 | 1 | 291 | 388 | 485 | 582 | 679 | 776 | 873 | 970 | 1067 | 1164 |
| 17 | 1 | 260 | 347 | 433 | 520 | 607 | 693 | 780 | 867 | 954 | 1040 |
| 18 | 1 | 234 | 312 | 390 | 468 | 546 | 624 | 702 | 780 | 858 | 936 |
| 19 | 1 | 212 | 282 | 353 | 423 | 494 | 565 | 635 | 706 | 776 | 847 |
| 20 | 1 | 193 | 257 | 321 | 385 | 449 | 513 | 578 | 642 | 706 | 770 |
| 21 | 1 | 176 | 235 | 293 | 352 | 410 | 469 | 528 | 586 | 645 | 704 |
| 22 | 1 | 161 | 215 | 269 | 323 | 377 | 430 | 484 | 538 | 592 | 646 |
| 23 | 1 | 149 | 198 | 248 | 297 | 347 | 396 | 446 | 496 | 545 | 595 |
| 24 | 1 | 137 | 183 | 229 | 275 | 321 | 366 | 412 | 458 | 504 | 550 |
| 25 | 1 | 127 | 170 | 212 | 255 | 297 | 340 | 382 | 425 | 467 | 510 |
| 26 | 1 | 118 | 158 | 197 | 237 | 276 | 316 | 355 | 395 | 434 | 474 |
| 27 | 1 | 111 | 147 | 184 | 221 | 258 | 295 | 332 | 368 | 405 | 442 |
| 28 | 1 | 103 | 138 | 172 | 207 | 241 | 275 | 310 | 344 | 379 | 413 |
| 29 | 1 | 97 | 129 | 161 | 194 | 226 | 258 | 290 | 323 | 355 | 387 |
| 30 | 1 | 91 | 121 | 152 | 182 | 212 | 242 | 273 | 303 | 333 | 364 |
| 31 | 1 | 86 | 114 | 143 | 171 | 200 | 228 | 257 | 285 | 314 | 342 |
| 32 | 1 | 81 | 108 | 134 | 161 | 188 | 215 | 242 | 269 | 296 | 323 |
| 33 | 1 | 76 | 102 | 127 | 152 | 178 | 203 | 229 | 254 | 280 | 305 |
| 34 | 1 | 72 | 96 | 120 | 144 | 168 | 192 | 216 | 240 | 265 | 289 |
| 35 | 1 | 68 | 91 | 114 | 137 | 160 | 182 | 205 | 228 | 251 | 273 |
| 36 | 1 | 65 | 87 | 108 | 130 | 151 | 173 | 195 | 216 | 238 | 260 |
| 37 | 1 | 62 | 82 | 103 | 123 | 144 | 165 | 185 | 206 | 226 | 247 |
| 38 | 1 | 59 | 78 | 98 | 117 | 137 | 157 | 176 | 196 | 215 | 235 |
| 39 | 1 | 56 | 75 | 93 | 112 | 131 | 149 | 168 | 187 | 205 | 224 |
| 40 | 1 | 53 | 71 | 89 | 107 | 125 | 142 | 160 | 178 | 196 | 214 |

For SI units: 1 pound-force per square inch = 6.8947 kPa, 1 gallon per minute = 0.06 L/s, 1 inch = 25 mm, 1 foot = 304.8 mm

TABLE 612.5.3.2(8)
ALLOWABLE PIPE LENGTH FOR ¾ INCH PEX TUBING*

| SPRINKLER FLOW RATE (gpm) | WATER DISTRIBUTION SIZE (inch) | AVAILABLE PRESSURE - P _t (psi) | | | | | | | | | |
|---------------------------------|---|--|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| | | 15 | 20 | 25 | 30 | 35 | 40 | 45 | 50 | 55 | 60 |
| | | ALLOWABLE LENGTH OF PIPE FROM SERVICE VALVE TO FARTHEST SPRINKLER (feet) | | | | | | | | | |
| 8 | ¾ | 93 | 123 | 154 | 185 | 216 | 247 | 278 | 309 | 339 | 370 |
| 9 | ¾ | 74 | 99 | 124 | 149 | 174 | 199 | 223 | 248 | 273 | 298 |
| 10 | ¾ | 61 | 82 | 102 | 123 | 143 | 163 | 184 | 204 | 225 | 245 |
| 11 | ¾ | 51 | 68 | 86 | 103 | 120 | 137 | 154 | 171 | 188 | 205 |
| 12 | ¾ | 44 | 58 | 73 | 87 | 102 | 117 | 131 | 146 | 160 | 175 |
| 13 | ¾ | 38 | 50 | 63 | 75 | 88 | 101 | 113 | 126 | 138 | 151 |
| 14 | ¾ | 33 | 44 | 55 | 66 | 77 | 88 | 99 | 110 | 121 | 132 |
| 15 | ¾ | 29 | 39 | 48 | 58 | 68 | 77 | 87 | 96 | 106 | 116 |
| 16 | ¾ | 26 | 34 | 43 | 51 | 60 | 68 | 77 | 86 | 94 | 103 |
| 17 | ¾ | 23 | 31 | 38 | 46 | 54 | 61 | 69 | 77 | 84 | 92 |
| 18 | ¾ | 21 | 28 | 34 | 41 | 48 | 55 | 62 | 69 | 76 | 83 |
| 19 | ¾ | 19 | 25 | 31 | 37 | 44 | 50 | 56 | 62 | 69 | 75 |
| 20 | ¾ | 17 | 23 | 28 | 34 | 40 | 45 | 51 | 57 | 62 | 68 |
| 21 | ¾ | 16 | 21 | 26 | 31 | 36 | 41 | 47 | 52 | 57 | 62 |
| 22 | ¾ | NP | 19 | 24 | 28 | 33 | 38 | 43 | 47 | 52 | 57 |
| 23 | ¾ | NP | 17 | 22 | 26 | 31 | 35 | 39 | 44 | 48 | 52 |
| 24 | ¾ | NP | 16 | 20 | 24 | 28 | 32 | 36 | 40 | 44 | 49 |
| 25 | ¾ | NP | NP | 19 | 22 | 26 | 30 | 34 | 37 | 41 | 45 |
| 26 | ¾ | NP | NP | 17 | 21 | 24 | 28 | 31 | 35 | 38 | 42 |
| 27 | ¾ | NP | NP | 16 | 20 | 23 | 26 | 29 | 33 | 36 | 39 |
| 28 | ¾ | NP | NP | 15 | 18 | 21 | 24 | 27 | 30 | 33 | 36 |
| 29 | ¾ | NP | NP | NP | 17 | 20 | 23 | 26 | 28 | 31 | 34 |
| 30 | ¾ | NP | NP | NP | 16 | 19 | 21 | 24 | 27 | 29 | 32 |
| 31 | ¾ | NP | NP | NP | 15 | 18 | 20 | 23 | 25 | 28 | 30 |
| 32 | ¾ | NP | NP | NP | NP | 17 | 19 | 21 | 24 | 26 | 28 |
| 33 | ¾ | NP | NP | NP | NP | 16 | 18 | 20 | 22 | 25 | 27 |
| 34 | ¾ | NP | NP | NP | NP | NP | 17 | 19 | 21 | 23 | 25 |
| 35 | ¾ | NP | NP | NP | NP | NP | 16 | 18 | 20 | 22 | 24 |
| 36 | ¾ | NP | NP | NP | NP | NP | 15 | 17 | 19 | 21 | 23 |
| 37 | ¾ | NP | NP | NP | NP | NP | NP | 16 | 18 | 20 | 22 |
| 38 | ¾ | NP | NP | NP | NP | NP | NP | 16 | 17 | 19 | 21 |
| 39 | ¾ | NP | NP | NP | NP | NP | NP | NP | 16 | 18 | 20 |
| 40 | ¾ | NP | NP | NP | NP | NP | NP | NP | 16 | 17 | 19 |

For SI units: 1 pound-force per square inch = 6.8947 kPa, 1 gallon per minute = 0.06 L/s, 1 inch = 25 mm, 1 foot = 304.8 mm

* NP – Means not permitted.

TABLE 612.5.3.2(9)
ALLOWABLE PIPE LENGTH FOR 1 INCH PEX TUBING

| SPRINKLER FLOW RATE (gpm) | WATER DISTRIBUTION SIZE (inch) | AVAILABLE PRESSURE - P _f (psi) | | | | | | | | | |
|---------------------------------|---|--|-----|-----|-----|-----|-----|-----|------|------|------|
| | | 15 | 20 | 25 | 30 | 35 | 40 | 45 | 50 | 55 | 60 |
| | | ALLOWABLE LENGTH OF PIPE FROM SERVICE VALVE TO FARTHEST SPRINKLER (feet) | | | | | | | | | |
| 8 | 1 | 314 | 418 | 523 | 628 | 732 | 837 | 941 | 1046 | 1151 | 1255 |
| 9 | 1 | 252 | 336 | 421 | 505 | 589 | 673 | 757 | 841 | 925 | 1009 |
| 10 | 1 | 208 | 277 | 346 | 415 | 485 | 554 | 623 | 692 | 761 | 831 |
| 11 | 1 | 174 | 232 | 290 | 348 | 406 | 464 | 522 | 580 | 638 | 696 |
| 12 | 1 | 148 | 198 | 247 | 296 | 346 | 395 | 445 | 494 | 543 | 593 |
| 13 | 1 | 128 | 170 | 213 | 256 | 298 | 341 | 383 | 426 | 469 | 511 |
| 14 | 1 | 111 | 149 | 186 | 223 | 260 | 297 | 334 | 371 | 409 | 446 |
| 15 | 1 | 98 | 131 | 163 | 196 | 229 | 262 | 294 | 327 | 360 | 392 |
| 16 | 1 | 87 | 116 | 145 | 174 | 203 | 232 | 261 | 290 | 319 | 348 |
| 17 | 1 | 78 | 104 | 130 | 156 | 182 | 208 | 233 | 259 | 285 | 311 |
| 18 | 1 | 70 | 93 | 117 | 140 | 163 | 187 | 210 | 233 | 257 | 280 |
| 19 | 1 | 63 | 84 | 106 | 127 | 148 | 169 | 190 | 211 | 232 | 253 |
| 20 | 1 | 58 | 77 | 96 | 115 | 134 | 154 | 173 | 192 | 211 | 230 |
| 21 | 1 | 53 | 70 | 88 | 105 | 123 | 140 | 158 | 175 | 193 | 211 |
| 22 | 1 | 48 | 64 | 80 | 97 | 113 | 129 | 145 | 161 | 177 | 193 |
| 23 | 1 | 44 | 59 | 74 | 89 | 104 | 119 | 133 | 148 | 163 | 178 |
| 24 | 1 | 41 | 55 | 69 | 82 | 96 | 110 | 123 | 137 | 151 | 164 |
| 25 | 1 | 38 | 51 | 64 | 76 | 89 | 102 | 114 | 127 | 140 | 152 |
| 26 | 1 | 35 | 47 | 59 | 71 | 83 | 95 | 106 | 118 | 130 | 142 |
| 27 | 1 | 33 | 44 | 55 | 66 | 77 | 88 | 99 | 110 | 121 | 132 |
| 28 | 1 | 31 | 41 | 52 | 62 | 72 | 82 | 93 | 103 | 113 | 124 |
| 29 | 1 | 29 | 39 | 48 | 58 | 68 | 77 | 87 | 97 | 106 | 116 |
| 30 | 1 | 27 | 36 | 45 | 54 | 63 | 73 | 82 | 91 | 100 | 109 |
| 31 | 1 | 26 | 34 | 43 | 51 | 60 | 68 | 77 | 85 | 94 | 102 |
| 32 | 1 | 24 | 32 | 40 | 48 | 56 | 64 | 72 | 80 | 89 | 97 |
| 33 | 1 | 23 | 30 | 38 | 46 | 53 | 61 | 68 | 76 | 84 | 91 |
| 34 | 1 | 22 | 29 | 36 | 43 | 50 | 58 | 65 | 72 | 79 | 86 |
| 35 | 1 | 20 | 27 | 34 | 41 | 48 | 55 | 61 | 68 | 75 | 82 |
| 36 | 1 | 19 | 26 | 32 | 39 | 45 | 52 | 58 | 65 | 71 | 78 |
| 37 | 1 | 18 | 25 | 31 | 37 | 43 | 49 | 55 | 62 | 68 | 74 |
| 38 | 1 | 18 | 23 | 29 | 35 | 41 | 47 | 53 | 59 | 64 | 70 |
| 39 | 1 | 17 | 22 | 28 | 33 | 39 | 45 | 50 | 56 | 61 | 67 |
| 40 | 1 | 16 | 21 | 27 | 32 | 37 | 43 | 48 | 53 | 59 | 64 |

For SI units: 1 pound-force per square inch = 6.8947 kPa, 1 gallon per minute = 0.06 L/s, 1 inch = 25 mm, 1 foot = 304.8 mm

CHAPTER 7

SANITARY DRAINAGE

Part I – Drainage Systems.

701.0 General.

701.1 Applicability. This chapter shall govern the materials, design, and installation of sanitary drainage systems and building sewers.

» **701.2 Drainage Piping.** Materials for drainage piping shall be in accordance with one of the referenced standards in Table 701.2 except that:

- (1) No galvanized wrought-iron or galvanized steel pipe shall be used underground and shall be kept not less than 6 inches (152 mm) aboveground.
- (2) ABS and PVC DWV piping installations shall be installed in accordance with applicable standards referenced in Table 1701.1 and Chapter 14 “Firestop Protection.” Except for individual single-family dwelling units, materials exposed within ducts or plenums shall have a flame-spread index of not more than 25 and a smoke-developed index of not more than 50, where tested in accordance with ASTM E84 or UL 723.
- (3) No vitrified clay pipe or fittings shall be used aboveground or where pressurized by a pump or ejector. They shall be kept not less than 12 inches (305 mm) belowground.
- (4) Copper or copper alloy tube for drainage and vent piping shall have a weight of not less than that of copper or copper alloy drainage tube type DWV.
- (5) Stainless steel 304 pipe and fittings shall not be installed underground and shall be kept not less than 6 inches (152 mm) aboveground.
- (6) Cast-iron soil pipe and fittings shall be listed and tested in accordance with standards referenced in Table 1701.1. Such pipe and fittings shall be marked with the country of origin and identification of the original manufacturer in addition to markings required by referenced standards.

» **701.3 Drainage Fittings.** Materials for drainage fittings shall comply with the applicable standards referenced in Table 701.2 of the same diameter as the piping served, and such fittings shall be compatible with the type of pipe used.

» **701.3.1 Screwed Pipe.** Fittings on screwed pipe shall be of the recessed drainage type. Burred ends shall be reamed to the full bore of the pipe.

» **701.3.2 Threads.** The threads of drainage fittings shall be tapped so as to allow ¼ inch per foot (20.8 mm/m) grade.

» **701.3.3 Type.** Fittings used for drainage shall be of the drainage type, have a smooth interior water-way, and be constructed so as to allow ¼ inch per foot (20.8 mm/m) grade.

701.4 Continuous Wastes. Continuous wastes and fixture tailpieces shall be constructed from the materials specified in Section 701.2 for drainage piping, provided, however, that such connections where exposed or accessible shall be permitted to be of seamless drawn brass not less than No. 20 B & S Gauge (0.032 inches) (0.8 mm).

701.5 Lead. (See Table 1701.1) Sheet lead shall comply with the following:

- (1) For safe pans – not less than 4 pounds per square foot (lb/ft²) (19 kg/m²) or ¼ of an inch (1.6 mm) thick.
- (2) For flashings or vent terminals – not less than 3 lb/ft² (15 kg/m²) or 0.0472 of an inch (1.1989 mm) thick.
- (3) Lead bends and lead traps shall be not less than ⅛ of an inch (3.2 mm) in wall thickness.

701.6 Caulking Ferrules. Caulking ferrules shall be manufactured from copper or copper alloy and shall be in accordance with Table 701.6.

701.7 Soldering Bushings. Soldering bushings shall be of copper or copper alloy and shall be in accordance with Table 701.7.

TABLE 701.6
CAULKING FERRULES

| PIPE SIZE (inches) | INSIDE DIAMETER (inches) | LENGTH (inches) | MINIMUM WEIGHT EACH | |
|-----------------------|--------------------------------|--------------------|---------------------|--------|
| | | | pounds | ounces |
| 2 | 2¼ | 4½ | 1 | 0 |
| 3 | 3¼ | 4½ | 1 | 12 |
| 4 | 4¼ | 4½ | 2 | 8 |

For SI units: 1 inch = 25 mm, 1 pound = 0.453 kg, 1 ounce = 0.02834 kg

TABLE 701.7
SOLDERING BUSHINGS

| PIPE SIZE (inches) | MINIMUM WEIGHT EACH | | PIPE SIZE (inches) | MINIMUM WEIGHT EACH | |
|--------------------------|------------------------|--------|--------------------------|------------------------|--------|
| | pounds | ounces | | pounds | ounces |
| 1¼ | 0 | 6 | 2½ | 1 | 6 |
| 1½ | 0 | 8 | 3 | 2 | 0 |
| 2 | 0 | 14 | 4 | 3 | 8 |

For SI units: 1 inch = 25 mm, 1 pound = 0.453 kg, 1 ounce = 0.02834 kg

702.0 Fixture Unit Equivalents.

702.1 Trap Size. The unit equivalent of plumbing fixtures shown in Table 702.1 shall be based on the size of the trap required, and the unit equivalent of fixtures and devices not shown in Table 702.1 shall be based on the size of trap or trap arm.

Maximum drainage fixture units for a fixture trap and trap arm loadings for sizes up to 4 inches (100 mm) shall be in accordance with Table 702.2(1).



TABLE 701.2
MATERIALS FOR DRAIN, WASTE, VENT PIPE AND FITTINGS

| MATERIAL | UNDERGROUND DRAIN, WASTE, VENT PIPE AND FITTINGS | ABOVEGROUND DRAIN, WASTE, VENT PIPE AND FITTINGS | BUILDING SEWER PIPE AND FITTINGS | REFERENCED STANDARD(S) PIPE | REFERENCED STANDARD(S) FITTINGS |
|--|---|---|--|---|---|
| ABS (Schedule 40) | X | X | X | ASTM D2661, ASTM D2680* | ASTM D2661, ASTM D2680* |
| Cast-Iron | X | X | X | ASTM A74, ASTM A888, CISPI 301 | ASME B16.12, ASTM A74, ASTM A888, CISPI 301 |
| Co-Extruded ABS (Schedule 40) | X | X | X | ASTM F628 | ASTM D2661, ASTM D2680* |
| Co-Extruded Composite (Schedule 40) | X | X | X | ASTM F1488 | ASTM D2661, ASTM D2665, ASTM F794*, ASTM F1866 |
| Co-Extruded PVC (Schedule 40) | X | X | X | ASTM F891 | ASTM D2665, ASTM F794*, ASTM F1866 |
| Copper and Copper Alloys (Type DWV) | X | X | X | ASTM B43, ASTM B75, ASTM B251, ASTM B302, ASTM B306 | ASME B16.23, ASME B16.29 |
| Galvanized Malleable Iron | — | X | — | — | ASME B16.3 |
| Galvanized Steel | — | X | — | ASTM A53 | — |
| Polyethylene | — | — | X | ASTM F714 | — |
| PVC (Schedule 40) | X | X | X | ASTM D1785, ASTM D2665, ASTM F794* | ASTM D2665, ASTM F794*, ASTM F1866 |
| Stainless Steel 304 | — | X | — | ASME A112.3.1 | ASME A112.3.1 |
| Stainless Steel 316L | X | X | X | ASME A112.3.1 | ASME A112.3.1 |
| Vitrified Clay (Extra strength) | — | — | X | ASTM C700 | ASTM C700 |

* For building sewer applications.

TABLE 702.1
DRAINAGE FIXTURE UNIT VALUES (DFU)

| PLUMBING APPLIANCES, APPURTENANCES, OR FIXTURES | MINIMUM SIZE TRAP AND TRAP ARM ⁷ (inches) | PRIVATE | PUBLIC | ASSEMBLY ⁸ |
|--|--|-----------------------------|--------|-----------------------|
| Bathtub or Combination Bath/Shower | 1½ | 2.0 | 2.0 | — |
| Bidet | 1¼ | 1.0 | — | — |
| Bidet | 1½ | 2.0 | — | — |
| Clothes Washer, domestic, standpipe ⁵ | 2 | 3.0 | 3.0 | 3.0 |
| Dental Unit, cuspidor | 1¼ | — | 1.0 | 1.0 |
| Dishwasher, domestic, with independent drain ² | 1½ | 2.0 | 2.0 | 2.0 |
| Drinking Fountain or Water Cooler | 1¼ | 0.5 | 0.5 | 1.0 |
| Food Waste Disposer, commercial | 2 | — | 3.0 | 3.0 |
| Floor Drain, emergency | 2 | — | 0.0 | 0.0 |
| Floor Drain (for additional sizes see Section 702.0) | 2 | 2.0 | 2.0 | 2.0 |
| Shower, single-head trap | 2 | 2.0 | 2.0 | 2.0 |
| Multi-head, each additional | 2 | 1.0 | 1.0 | 1.0 |
| Lavatory | 1¼ | 1.0 | 1.0 | 1.0 |
| Lavatories in sets | 1½ | 2.0 | 2.0 | 2.0 |
| Washfountain | 1½ | — | 2.0 | 2.0 |
| Washfountain | 2 | — | 3.0 | 3.0 |
| Mobile Home, trap | 3 | 12.0 | — | — |
| Receptor, indirect waste ^{1,3} | 1½ | See footnote ^{1,3} | | |
| Receptor, indirect waste ^{1,4} | 2 | See footnote ^{1,4} | | |
| Receptor, indirect waste ¹ | 3 | See footnote ¹ | | |
| Sinks | — | — | — | — |
| Bar | 1½ | 1.0 | — | — |
| Bar ² | 1½ | — | 2.0 | 2.0 |
| Clinical | 3 | — | 6.0 | 6.0 |
| Commercial with food waste ² | 1½ | — | 3.0 | 3.0 |
| Exam Room | 1½ | — | 1.0 | — |
| Special Purpose ² | 1½ | 2.0 | 3.0 | 3.0 |
| Special Purpose | 2 | 3.0 | 4.0 | 4.0 |
| Special Purpose | 3 | — | 6.0 | 6.0 |
| Kitchen, domestic ² (with or without food waste disposer, dishwasher, or both) | 1½ | 2.0 | 2.0 | — |
| Laundry ² (with or without discharge from a clothes washer) | 1½ | 2.0 | 2.0 | 2.0 |
| Service or Mop Basin | 2 | — | 3.0 | 3.0 |
| Service or Mop Basin | 3 | — | 3.0 | 3.0 |
| Service, flushing rim | 3 | — | 6.0 | 6.0 |
| Wash, each set of faucets | — | — | 2.0 | 2.0 |
| Urinal, integral trap 1.0 GPF ² | 2 | 2.0 | 2.0 | 5.0 |
| Urinal, integral trap greater than 1.0 GPF | 2 | 2.0 | 2.0 | 6.0 |
| Urinal, exposed trap ² | 1½ | 2.0 | 2.0 | 5.0 |
| Water Closet, 1.6 GPF Gravity Tank ⁶ | 3 | 3.0 | 4.0 | 6.0 |
| Water Closet, 1.6 GPF Flushometer Tank ⁶ | 3 | 3.0 | 4.0 | 6.0 |
| Water Closet, 1.6 GPF Flushometer Valve ⁶ | 3 | 3.0 | 4.0 | 6.0 |
| Water Closet, greater than 1.6 GPF Gravity Tank ⁶ | 3 | 4.0 | 6.0 | 8.0 |
| Water Closet, greater than 1.6 GPF Flushometer Valve ⁶ | 3 | 4.0 | 6.0 | 8.0 |

For SI units: 1 inch = 25 mm

Notes:¹ Indirect waste receptors shall be sized based on the total drainage capacity of the fixtures that drain therein to, in accordance with Table 702.2(2).² Provide a 2 inch (50 mm) minimum drain.³ For refrigerators, coffee urns, water stations, and similar low demands.⁴ For commercial sinks, dishwashers, and similar moderate or heavy demands.⁵ Buildings having a clothes-washing area with clothes washers in a battery of three or more clothes washers shall be rated at 6 fixture units each for purposes of sizing common horizontal and vertical drainage piping.⁶ Water closets shall be computed as 6 fixture units where determining septic tank sizes based on Appendix H of this code.⁷ Trap sizes shall not be increased to the point where the fixture discharge is capable of being inadequate to maintain their self-scouring properties.⁸ Assembly [Public Use (see Table 422.1)].

702.2 Intermittent Flow. Drainage fixture units for intermittent flow into the drainage system shall be computed on the rated discharge capacity in gallons per minute (gpm) (L/s) in accordance with Table 702.2(2).

702.3 Continuous Flow. For a continuous flow into a drainage system, such as from a pump, sump ejector, air conditioning equipment, or similar device, 2 fixture units shall be equal to each gallon per minute (gpm) (L/s) of flow.

TABLE 702.2(1)
MAXIMUM DRAINAGE FIXTURE UNITS FOR A
TRAP AND TRAP ARM*

| SIZE OF TRAP AND TRAP ARM (inches) | DRAINAGE FIXTURE UNIT VALUES (DFU) |
|------------------------------------|------------------------------------|
| 1¼ | 1 unit |
| 1½ | 3 units |
| 2 | 4 units |
| 3 | 6 units |
| 4 | 8 units |

For SI Units: 1 inch = 25 mm

* **Exception:** On self-service laundries.

TABLE 702.2(2)
DISCHARGE CAPACITY IN GALLONS PER MINUTE FOR
INTERMITTENT FLOW ONLY*

| GPM | FIXTURE UNITS |
|-----------------------|------------------------|
| Up to 7½ | Equals 1 Fixture Unit |
| Greater than 7½ to 15 | Equals 2 Fixture Units |
| Greater than 15 to 30 | Equals 4 Fixture Units |
| Greater than 30 to 50 | Equals 6 Fixture Units |

For SI units: 1 gallon per minute = 0.06 L/s

* Discharge capacity exceeding 50 gallons per minute (3.15 L/s) shall be determined by the Authority Having Jurisdiction.

703.0 Size of Drainage Piping.

703.1 Minimum Size. The minimum sizes of vertical, horizontal, or both drainage piping shall be determined from the total of fixture units connected thereto, and additionally, in the case of vertical drainage pipes, in accordance with their length.

703.2 Maximum Number of Fixture Units. Table 703.2 shows the maximum number of fixture units allowed on a vertical or horizontal drainage pipe, building drain, or building sewer of a given size; the maximum number of fixture units allowed on a branch interval of a given size; and the maximum length (in feet and meters) of a vertical drainage pipe of a given size.

703.3 Sizing per Appendix C. For alternate method of sizing drainage piping, see Appendix C.

704.0 Fixture Connections (Drainage).

704.1 Inlet Fittings. Drainage piping shall be provided with approved inlet fittings for fixture connections, correctly located according to the size and type of fixture proposed to be connected.

704.2 Single Vertical Drainage Pipe. Two fixtures set back-to-back, or side-by-side, within the distance allowed between a trap and its vent shall be permitted to be served by a single vertical drainage pipe provided that each fixture wastes separately into an approved double-fixture fitting having inlet openings at the same level.

704.3 Commercial Sinks. Pot sinks, scullery sinks, dish-washing sinks, silverware sinks, and other similar fixtures shall be connected directly to the drainage system. A floor drain shall be provided adjacent to the fixture, and the fixture shall be connected on the sewer side of the floor drain trap, provided that no other drainage line is connected between the floor drain waste connection and the fixture drain. The fixture and floor drain shall be trapped and vented in accordance with this code.

705.0 Joints and Connections.

705.1 ABS and ABS Co-Extruded Plastic Pipe and Joints. Joining methods for ABS plastic pipe and fittings shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 705.1.1 through Section 705.1.3.

705.1.1 Mechanical Joints. Mechanical joints shall be designed to provide a permanent seal and shall be of the mechanical or push-on joint. The push-on joint shall include an elastomeric gasket in accordance with ASTM D3212 and shall provide a compressive force against the spigot and socket after assembly to provide a permanent seal.

705.1.2 Solvent Cement Joints. Solvent cement joints for ABS pipe and fittings shall be clean from dirt and moisture. Pipe shall be cut square and shall be deburred. Where surfaces to be joined are cleaned and free of dirt, moisture, oil, and other foreign material, solvent cement in accordance with ASTM D2235 shall be applied to all joint surfaces. Joints shall be made while both the inside socket surface and outside surface of pipe are wet with solvent cement. Hold joint in place and undisturbed for 1 minute after assembly.

705.1.3 Threaded Joints. Threads shall comply with ASME B1.20.1. A minimum of Schedule 80 shall be permitted to be threaded. Molded threads on adapter fittings for transition to threaded joints shall be permitted. Thread sealant compound shall be applied to male threads, insoluble in water, and nontoxic. The joint between the pipe and transition fitting shall be of the solvent cement type. Caution shall be used during assembly to prevent over tightening of the ABS components once the thread sealant compound has been applied.

705.2 Cast-Iron Pipe and Joints. Joining methods for cast-iron pipe and fittings shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 705.2.1 or Section 705.2.2.

705.2.1 Caulked Joints. Caulked joints shall be firmly packed with oakum or hemp and filled with molten lead to a depth of not less than 1 inch (25.4 mm) in one continuous pour. The lead shall be caulked

TABLE 703.2
MAXIMUM UNIT LOADING AND MAXIMUM LENGTH OF DRAINAGE AND VENT PIPING

| SIZE OF PIPE (inches) | 1¼ | 1½ | 2 | 3 | 4 | 5 | 6 | 8 | 10 | 12 |
|--------------------------------------|----|----------------|-----------------|-----------------|------------------|------------------|------------------|-------------------|-------------------|-------------------|
| Maximum Units | | | | | | | | | | |
| Drainage Piping ¹ | | | | | | | | | | |
| Vertical | 1 | 2 ² | 16 ³ | 48 ⁴ | 256 | 600 | 1380 | 3600 | 5600 | 8400 |
| Horizontal | 1 | 1 | 8 ³ | 35 ⁴ | 216 ⁵ | 428 ⁵ | 720 ⁵ | 2640 ⁵ | 4680 ⁵ | 8200 ⁵ |
| Maximum Length | | | | | | | | | | |
| Drainage Piping | | | | | | | | | | |
| Vertical, (feet) | 45 | 65 | 85 | 212 | 300 | 390 | 510 | 750 | — | — |
| Horizontal (unlimited) | | | | | | | | | | |
| Vent Piping | | | | | | | | | | |
| Horizontal and Vertical ⁶ | | | | | | | | | | |
| Maximum Units | 1 | 8 ³ | 24 | 84 | 256 | 600 | 1380 | 3600 | — | — |
| Maximum Lengths, (feet) | 45 | 60 | 120 | 212 | 300 | 390 | 510 | 750 | | |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm

Notes:

¹ Excluding trap arm.

² Except sinks, urinals, and dishwashers – exceeding 1 fixture unit.

³ Except six-unit traps or water closets.

⁴ Only four water closets or six-unit traps allowed on a vertical pipe or stack; and not to exceed three water closets or six-unit traps on a horizontal branch or drain.

⁵ Based on ¼ inch per foot (20.8 mm/m) slope. For ⅛ of an inch per foot (10.4 mm/m) slope, multiply horizontal fixture units by a factor of 0.8.

⁶ The diameter of an individual vent shall be not less than 1¼ inches (32 mm) nor less than one-half the diameter of the drain to which it is connected. Fixture unit load values for drainage and vent piping shall be computed from Table 702.1 and Table 702.2(2). Not to exceed one-third of the total permitted length of a vent shall be permitted to be installed in a horizontal position. Where vents are increased one pipe size for their entire length, the maximum length limitations specified in this table do not apply. This table is in accordance with the requirements of Section 901.3.

thoroughly at the inside and outside edges of the joint. After caulking, the finished joint shall not exceed ⅛ of an inch (3.2 mm) below the rim of the hub. No paint, varnish, or other coatings shall be permitted on the joining material until after the joint has been tested and approved.

» **705.2.2 Mechanical Joints and Compression Joints.** Mechanical joints for cast-iron pipe and fittings shall be of the elastomeric compression type or mechanical joint couplings. Compression type joints with an elastomeric gasket for cast-iron hub and spigot pipe shall comply with ASTM C564 and be tested in accordance with ASTM C1563. Hub and spigot shall be clean and free of dirt, mud, sand, and foreign materials. Cut pipe shall be free from sharp edges. Fold and insert gasket into hub. Lubricate the joint following manufacturer's instructions. Insert spigot into hub until the spigot end of the pipe bottom out in the hub. Use the same procedure for the installation of fittings.

A mechanical joint shielded coupling type for hubless cast-iron pipe and fittings shall have a metallic shield in accordance with ASTM A1056, ASTM C1277, ASTM C1540, or CISPI 310. The elastomeric gasket shall comply with ASTM C564. Hubless cast-iron pipe and fittings shall be clean and free of dirt, mud, sand, and foreign materials. Cut pipe shall be free from sharp edges. Gasket shall be placed on the end of the pipe or fitting and the stainless steel shield and clamp assembly on the end of the other pipe or fitting.

Pipe or fittings shall be seated against the center stop inside the elastomeric sleeve. Slide the stainless steel shield and clamp assembly into position centered over the gasket and tighten. Bands shall be tightened using an approved calibrated torque wrench specifically set by the manufacturer of the couplings.

705.3 Copper or Copper Alloy Pipe (DWV) and Joints. Joining methods for copper or copper alloy pipe and fittings shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 705.3.1 through Section 705.3.4. <<

705.3.1 Brazed Joints. Brazed joints between copper or copper alloy pipe and fittings shall be made with brazing alloys having a liquid temperature above 1000°F (538°C). The joint surfaces to be brazed shall be cleaned bright by either manual or mechanical means. Piping shall be cut square and reamed to full inside diameter. Brazing flux shall be applied to the joint surfaces where required by manufacturer's recommendation. Brazing filler metal in accordance with AWS A5.8 shall be applied at the point where the pipe or tubing enters the socket of the fitting. <<

705.3.2 Mechanical Joints. Mechanical joints in copper or copper alloy piping shall be made with a mechanical coupling with grooved end piping or approved joint designed for the specific application. <<

705.3.3 Soldered Joints. Soldered joints between copper or copper alloy pipe and fittings shall be made <<

in accordance with ASTM B828 with the following sequence of joint preparation and operation as follows: measuring and cutting, reaming, cleaning, fluxing, assembly and support, heating, applying the solder, cooling, and cleaning. Pipe shall be cut square and reamed to the full inside diameter including the removal of burrs on the outside of the pipe. Surfaces to be joined shall be cleaned bright by manual or mechanical means. Flux shall be applied to pipe and fittings and shall be in accordance with ASTM B813, and shall become noncorrosive and nontoxic after soldering. Insert pipe into the base of the fitting and remove excess flux. Pipe and fitting shall be supported to ensure a uniform capillary space around the joint. Heat shall be applied using an air or fuel torch with the flame perpendicular to the pipe using acetylene or an LP gas. Preheating shall depend on the size of the joint. The flame shall be moved to the fitting cup and alternate between the pipe and fitting. Solder in accordance with ASTM B32 shall be applied to the joint surfaces until capillary action draws the molten solder into the cup. Joint surfaces shall not be disturbed until cool and any remaining flux residue shall be cleaned.

» **705.3.4 Threaded Joints.** Threaded joints for copper or copper alloy pipe shall be made with pipe threads in accordance with ASME B1.20.1. Thread sealant tape or compound shall be applied only on male threads, and such material shall be approved types, insoluble in water, and nontoxic.

» **705.4 Galvanized Steel Pipe and Joints.** Joining methods for galvanized steel pipe and fittings shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 705.4.1 or Section 705.4.2.

» **705.4.1 Mechanical Joints.** Mechanical joints shall be made with an elastomeric gasket.

» **705.4.2 Threaded Joints.** Threaded joints shall be made with pipe threads in accordance with ASME B1.20.1. Thread sealant tape or compound shall be applied only on male threads, and such material shall be of approved types, insoluble in water, and nontoxic.

» **705.5 PVC and PVC Co-Extruded Plastic Pipe and Joining Methods.** Joining methods for PVC plastic pipe and fittings shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 705.5.1 through Section 705.5.3.

» **705.5.1 Mechanical Joints.** Mechanical joints shall be designed to provide a permanent seal and shall be of the mechanical or push-on joint type. The push-on joint shall include an elastomeric gasket in accordance with ASTM D3212 and shall provide a compressive force against the spigot and socket after assembly to provide a permanent seal.

» **705.5.2 Solvent Cement Joints.** Solvent cement joints for PVC pipe and fittings shall be clean from dirt and moisture. Pipe shall be cut square and pipe shall be deburred. Where surfaces to be joined are cleaned and free of dirt, moisture, oil, and other foreign material,

apply primer purple in color in accordance with ASTM F656. Primer shall be applied until the surface of the pipe and fitting is softened. Solvent cements in accordance with ASTM D2564 shall be applied to all joint surfaces. Joints shall be made while both the inside socket surface and outside surface of pipe are wet with solvent cement. Hold joint in place and undisturbed for 1 minute after assembly.

705.5.3 Threaded Joints. Threads shall comply with ASME B1.20.1. A minimum of Schedule 80 shall be permitted to be threaded. Molded threads on adapter fittings for transition to threaded joints shall be permitted. Thread sealant compound that is compatible with the pipe and fitting, insoluble in water, and nontoxic shall be applied to male threads. The joint between the pipe and transition fitting shall be of the solvent cement type. Caution shall be used during assembly to prevent over tightening of the PVC components once the thread sealant has been applied. Female PVC threaded fittings shall be used with plastic male threads only.

705.6 Stainless Steel Pipe and Joints. Joining methods for stainless steel pipe and fittings shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 705.6.1 or Section 705.6.2.

705.6.1 Mechanical Joints. Mechanical joints between stainless steel pipe and fittings shall be of the compression, grooved coupling, hydraulic pressed fittings, or flanged.

705.6.2 Welded Joints. Welded joints between stainless steel pipe and fittings shall comply with ASME A112.3.1 and shall be welded autogenously. Pipe shall be cleaned, free of scale and contaminating particles. Pipe shall be cut with a combination cutting and beveling tool that provides a square cut, and free of burrs. Mineral oil lubricant shall be used during the cutting and beveling process.

705.7 Vitrified Clay Pipe and Joints. Joining methods for vitrified clay pipe and fittings shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 705.7.1.

705.7.1 Mechanical Joints. Mechanical joints shall be designed to provide a permanent seal and shall be of the mechanical or push-on joint type. The push-on joint shall include an elastomeric gasket in accordance with ASTM C425 and shall provide a compressive force against the spigot and socket after assembly to provide a permanent seal.

705.8 Special Joints. Special joints shall comply with Section 705.8.1 through Section 705.8.4.

705.8.1 Slip Joints. In fixture drains and traps, slip joints of approved materials shall be permitted to be used in accordance with their approvals.

705.8.2 Expansion Joints. Expansion joints shall be accessible, except where in vent piping or drainage

stacks, and shall be permitted to be used where necessary to provide for expansion and contraction of the pipes.

» **705.8.3 Ground Joint, Flared, or Ferrule Connections.** Copper or copper alloy ground joint, flared, or ferrule-type connections that allow adjustment of tubing, but provide a rigid joint where made up, shall not be considered as slip joints.

» **705.8.4 Transition Joint.** A solvent cement transition joint between ABS and PVC building drain and building sewer shall be made using listed transition solvent cement in accordance with ASTM D3138.

» **705.9 Joints Between Various Materials.** Joints between various materials shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 705.9.1 through Section 705.9.4. Mechanical couplings used to join different materials shall be in accordance with ASTM C1173 for belowground use, ASTM C1460 for aboveground use, or ASTM C1461 for aboveground and belowground use.

» **705.9.1 Copper or Copper Alloy Pipe to Cast-Iron Pipe.** Joints from copper or copper alloy pipe or tubing to cast-iron pipe shall be made with a listed compression type joint or copper alloy ferrule. The copper or copper alloy pipe or tubing shall be soldered or brazed to the ferrule and the ferrule shall be joined to the cast-iron hub by a compression or caulked joint.

» **705.9.2 Copper or Copper Alloy Pipe to Threaded Pipe Joints.** Joints from copper or copper alloy pipe or tubing to threaded pipe shall be made by the use of a listed copper alloy adapter or dielectric fitting. The joint between the copper or copper alloy pipe and the fitting shall be a soldered or brazed, and the connection between the threaded and the fittings shall be made with a standard pipe size threaded joint.

» **705.9.3 Plastic Pipe to Other Materials.** Where connecting plastic pipe to other types of plastic or other types of piping material; approved listed adapter or transition fittings and listed for the specific transition intended shall be used.

» **705.9.4 Stainless Steel Pipe to Other Materials.** Where connecting stainless steel pipe to other types of piping, listed mechanical joints of the compression type and listed for the specific transition intended shall be used.

706.0 Changes in Direction of Drainage Flow.

706.1 Approved Fittings. Changes in direction of drainage piping shall be made by the appropriate use of approved fittings and shall be of the angles presented by a one-sixteenth bend, one-eighth bend, or one-sixth bend, or other approved fittings of equivalent sweep.

706.2 Horizontal to Vertical. Horizontal drainage lines, connecting with a vertical stack, shall enter through 45 degree (0.79 rad) wye branches, 60 degree (1.05 rad) wye

branches, combination wye and one-eighth bend branches, sanitary tee or sanitary tapped tee branches, or other approved fittings of equivalent sweep. No fitting having more than one inlet at the same level shall be used unless such fitting is constructed so that the discharge from one inlet cannot readily enter any other inlet. Double sanitary tees shall be permitted to be used where the barrel of the fitting is not less than two pipe sizes larger than the largest inlet, (pipe sizes recognized for this purpose are 2 inches, 2½ inches, 3 inches, 3½ inches, 4 inches, 4½ inches, 5 inches, 6 inches, etc.) (50 mm, 65 mm, 80 mm, 90 mm, 100 mm, 115 mm, 125 mm, 150 mm, etc.).

706.3 Horizontal to Horizontal. Horizontal drainage lines connecting with other horizontal drainage lines shall enter through 45 degree (0.79 rad) wye branches, combination wye and one-eighth bend branches, or other approved fittings of equivalent sweep.

706.4 Vertical to Horizontal. Vertical drainage lines connecting with horizontal drainage lines shall enter through 45 degree (0.79 rad) wye branches, combination wye and one-eighth bend branches, or other approved fittings of equivalent sweep. Branches or offsets of 60 degrees (1.05 rad) shall be permitted to be used where installed in a true vertical position.

707.0 Cleanouts.

707.1 Plug. Each cleanout fitting for cast-iron pipe shall consist of a cast-iron or copper alloy body and an approved plug. Each cleanout for galvanized wrought-iron, galvanized steel, copper, or copper alloy pipe shall consist of a plug as specified in Table 707.1, or a standard weight copper alloy cap, or an approved ABS or PVC plastic plug, or an approved stainless steel cleanout or plug. Plugs shall have raised square heads or approved countersunk rectangular slots.

**TABLE 707.1
CLEANOUTS**

| SIZE OF PIPE (inches) | SIZE OF CLEANOUT (inches) | THREADS (per inches) |
|--------------------------|------------------------------|-------------------------|
| 1½ | 1½ | 11½ |
| 2 | 1½ | 11½ |
| 2½ | 2½ | 8 |
| 3 | 2½ | 8 |
| 4 & larger | 3½ | 8 |

For SI units: 1 inch = 25 mm

707.2 Approved. Each cleanout fitting and each cleanout plug or cap shall be of an approved type.

707.3 Watertight and Gastight. Cleanouts shall be designed to be watertight and gastight.

707.4 Location. Each horizontal drainage pipe shall be provided with a cleanout at its upper terminal, and each run of piping, that is more than 100 feet (30 480 mm) in total developed length, shall be provided with a cleanout for each 100 feet (30 480 mm), or fraction thereof, in length of such piping. An additional cleanout shall be provided in a drainage

line for each aggregate horizontal change in direction exceeding 135 degrees (2.36 rad). A cleanout shall be installed above the fixture connection fitting, serving each urinal, regardless of the location of the urinal in the building.

Exceptions:

- (1) Cleanouts shall be permitted to be omitted on a horizontal drain line less than 5 feet (1524 mm) in length unless such line is serving sinks or urinals.
- (2) Cleanouts shall be permitted to be omitted on a horizontal drainage pipe installed on a slope of 72 degrees (1.26 rad) or less from the vertical angle (one-fifth bend).
- (3) Excepting the building drain, its horizontal branches, and urinals, a cleanout shall not be required on a pipe or piping that is above the floor level of the lowest floor of the building.
- (4) An approved type of two-way cleanout fitting, installed inside the building wall near the connection between the building drain and the building sewer or installed outside of a building at the lower end of a building drain and extended to grade, shall be permitted to be substituted for an upper terminal cleanout.

707.5 Cleaning. Each cleanout shall be installed so that it opens to allow cleaning in the direction of flow of the soil or waste or at right angles thereto and, except in the case of wye branch and end-of-line cleanouts, shall be installed vertically above the flow line of the pipe.

707.6 Extension. Each cleanout extension shall be considered as drainage piping and each 90 degree (1.57 rad) cleanout extension shall be extended from a wye-type fitting or other approved fitting of equivalent sweep.

707.7 Interceptor. Each cleanout for an interceptor shall be outside of such interceptor.

707.8 Access. Each cleanout, unless installed under an approved cover plate, shall be above grade, readily accessible, and so located as to serve the purpose for which it is intended. Cleanouts located under cover plates shall be so installed as to provide the clearances and accessibility required by this section.

707.9 Clearance. Each cleanout in piping 2 inches (50 mm) or less in size shall be so installed that there is a clearance of not less than 18 inches (457 mm) in front of the cleanout. Cleanouts in piping exceeding 2 inches (50 mm) shall have a clearance of not less than 24 inches (610 mm) in front of the cleanout. Cleanouts in under-floor piping shall be extended to or above the finished floor or shall be extended outside the building where there is less than 18 inches (457 mm) vertical overall, allowing for obstructions such as ducts, beams, and piping, and 30 inches of (762 mm) horizontal clearance from the means of access to such cleanout. No under-floor cleanout shall be located exceeding 5 feet (1524 mm) from an access door, trap door, or crawl hole.

707.10 Fittings. Cleanout fittings shall be not less in size than those given in Table 707.1.

707.11 Pressure Drainage Systems. Cleanouts shall be provided for pressure drainage systems as classified under Section 710.7.

707.12 Countersunk Cleanout Plugs. Countersunk cleanout plugs shall be installed where raised heads cause a hazard.

707.13 Hubless Blind Plugs. Where a hubless blind plug is used for a required cleanout, the complete coupling and plug shall be accessible for removal or replacement.

707.14 Trap Arms. Cleanouts for trap arms shall be installed in accordance with Section 1002.3.

708.0 Grade of Horizontal Drainage Piping.

708.1 General. Horizontal drainage piping shall be run in practical alignment and a uniform slope of not less than ¼ inch per foot (20.8 mm/m) or 2 percent toward the point of disposal provided that, where it is impractical due to the depth of the street sewer, to the structural features, or to the arrangement of a building or structure to obtain a slope of ¼ inch per foot (20.8 mm/m) or 2 percent, such pipe or piping 4 inches (100 mm) or larger in diameter shall be permitted to have a slope of not less than ⅛ inch per foot (10.4 mm/m) or 1 percent, where first approved by the Authority Having Jurisdiction.

709.0 Gravity Drainage Required.

709.1 General. Where practicable, plumbing fixtures shall be drained to the public sewer or private sewage disposal system by gravity.

710.0 Drainage of Fixtures Located Below the Next Upstream Manhole or Below the Main Sewer Level.

710.1 Backflow Protection. Fixtures installed on a floor level that is lower than the next upstream manhole cover of the public or private sewer shall be protected from backflow of sewage by installing an approved type of backwater valve. Fixtures on such floor level that are not below the next upstream manhole cover shall not be required to be protected by a backwater valve. Fixtures on floor levels above such elevation shall not discharge through the backwater valve. Cleanouts for drains that pass through a backwater valve shall be clearly identified with a permanent label stating "backwater valve downstream."

710.2 Sewage Discharge. Drainage piping serving fixtures that are located below the crown level of the main sewer shall discharge into an approved watertight sump or receiving tank, so located as to receive the sewage or wastes by gravity. From such sump or receiving tank, the sewage or other liquid wastes shall be lifted and discharged into the building drain or building sewer by approved ejectors, pumps, or other equally efficient approved mechanical devices.

710.3 Sewage Ejector and Pumps. A sewage ejector or sewage pump receiving the discharge of water closets or urinals:

- (1) Shall have a discharge capacity of not less than 20 gpm (1.26 L/s).
- (2) In single dwelling units, the ejector or pump shall be capable of passing a 1½ inch (38 mm) diameter solid ball, and the discharge piping of each ejector or pump shall have a backwater valve and gate valve, and be not less than 2 inches (50 mm) in diameter.
- (3) In other than single-dwelling units, the ejector or pump shall be capable of passing a 2 inch (51 mm) diameter solid ball, and the discharge piping of each ejector or pump shall have a backwater valve and gate valve, and be not less than 3 inches (80 mm) in diameter.

710.4 Discharge Line. The discharge line from such ejector, pump, or other mechanical device shall be of approved pressure rated material and be provided with an accessible backwater or swing check valve and gate or ball valve. Where the gravity drainage line to which such discharge line connects is horizontal, the method of connection shall be from the top through a wye branch fitting. The gate or ball valve shall be located on the discharge side of the backwater or check valve.

Gate or ball valves, where installed in drainage piping, shall be fullway type with working parts of corrosion-resistant metal. Sizes 4 inches (100 mm) or more in diameter shall have cast-iron bodies, and sizes less than 4 inches (100 mm), cast-iron or copper alloy bodies.

710.5 Size of Building Drains and Sewers. Building drains or building sewers receiving discharge from a pump or ejector shall be adequately sized to prevent overloading. Two fixture units shall be allowed for each gallon per minute (L/s) of flow.

710.6 Backwater Valves. Backwater valves, gate valves, fullway ball valves, unions, motors, compressors, air tanks, and other mechanical devices required by this section shall be located where they will be accessible for inspection and repair and, unless continuously exposed, shall be enclosed in a masonry pit fitted with an adequately sized removable cover.

Backwater valves shall comply with ASME A112.14.1, and have bodies of cast-iron, plastic, copper alloy, or other approved materials; shall have noncorrosive bearings, seats, and self-aligning discs; and shall be constructed so as to ensure a positive mechanical seal. Such backwater valves shall remain open during periods of low flows to avoid screening of solids and shall not restrict capacities or cause excessive turbulence during peak loads. Unless otherwise listed, valve access covers shall be bolted type with gasket, and each valve shall bear the manufacturer's name cast into the body and the cover.

710.7 Drainage and Venting Systems. The drainage and venting systems, in connection with fixtures, sumps, receiving tanks, and mechanical waste-lifting devices, shall be installed under the same requirements as provided for in this code for gravity systems.

710.8 Sump and Receiving Tank Construction. Sumps and receiving tanks shall be watertight and shall be constructed of concrete, metal, or other approved materials.

Where constructed of poured concrete, the walls and bottom shall be adequately reinforced and designed to recognized acceptable standards. Metal sumps or tanks shall be of such thickness as to serve their intended purpose and shall be treated internally and externally to resist corrosion.

710.9 Alarm. Such sumps and receiving tanks shall be automatically discharged and, where in a "public use" occupancy, shall be provided with dual pumps or ejectors arranged to function alternately in normal use and independently in case of overload or mechanical failure. The pumps shall have an audio and visual alarm, readily accessible, that signals pump failure or an overload condition. The lowest inlet shall have a clearance of not less than 2 inches (51 mm) from the high-water or "starting" level of the sump.

710.10 Sump and Receiving Tank Covers and Vents. Sumps and receiving tanks shall be provided with substantial covers having a bolt-and-gasket-type manhole or equivalent opening to permit access for inspection, repairs, and cleaning. The top shall be provided with a vent pipe that shall extend separately through the roof or, where permitted, be combined with other vent pipes. Such vent shall be large enough to maintain atmospheric pressure within the sump under normal operating conditions and, in no case, shall be less in size than that required by Table 703.2 for the number and type of fixtures discharging into the sump, nor less than 1½ inches (40 mm) in diameter. Where the foregoing requirements are met and the vent, after leaving the sump, is combined with vents from fixtures discharging into the sump, the size of the combined vent need not exceed that required for the total number of fixtures discharging into the sump. No vent from an air-operating sewage ejector shall combine with other vents.

710.11 Air Tanks. Air tanks shall be so proportioned as to be of equal cubical capacity to the ejectors connected therewith in which there shall be maintained an air pressure of not less than 2 pounds per foot (lb/ft) (3 kg/m) of height the sewage is to be raised. No water-operated ejectors shall be permitted.

710.12 Grinder Pump Ejector. Grinder pumps shall be permitted to be used.

710.12.1 Discharge Piping. The discharge piping shall be sized in accordance with the manufacturer's installation instructions and shall be not less than 1¼ inches (32 mm) in diameter. A check valve and fullway-type shutoff valve shall be located within the discharge line.

710.13 Macerating Toilet Systems and Pumped Waste Systems. Fixtures shall be permitted to discharge to a macerating toilet system or pumped waste system shall be permitted as an alternate to a sewage pump system where approved by the Authority Having Jurisdiction. Such systems shall comply with ASME A112.3.4/CSA B45.9 and shall be installed in accordance with the manufacturer's installation instructions.

710.13.1 Sumps. The sump shall be watertight and gastight.

710.13.2 Discharge Piping. The discharge piping shall be sized in accordance with manufacturer's instructions and shall be not less than $\frac{3}{4}$ of an inch (20 mm) in diameter. The developed length of the discharge piping shall not exceed the manufacturer's instructions. A check valve and fullway-type shutoff valve shall be located within the discharge line or internally within the device.

710.13.3 Venting. The plumbing fixtures that discharge into the macerating device shall be vented in accordance with this code. The sump shall be vented in accordance with the manufacturer's instructions and such vent shall be permitted to connect to the fixture venting.

711.0 Suds Relief.

711.1 General. Drainage connections shall not be made into a drainage piping system within 8 feet (2438 mm) of a vertical to horizontal change of direction of a stack containing suds-producing fixtures. Bathtubs, laundries, washing machine standpipes, kitchen sinks, and dishwashers shall be considered suds-producing fixtures. Where parallel vent stacks are required, they shall connect to the drainage stack at a point 8 feet (2438 mm) above the lowest point of the drainage stack.

Exceptions:

- (1) Single-family residences
- (2) Stacks receiving the discharge from less than three stories of plumbing fixtures

712.0 Testing.

712.1 Media. The piping of the plumbing, drainage, and venting systems shall be tested with water or air except that plastic pipe shall not be tested with air. The Authority Having Jurisdiction shall be permitted to require the removal of cleanouts, etc., to ascertain whether the pressure has reached all parts of the system. After the plumbing fixtures have been set and their traps filled with water, they shall be submitted to a final test.

712.2 Water Test. The water test shall be applied to the drainage and vent systems either in its entirety or in sections. Where the test is applied to the entire system, openings in the piping shall be tightly closed, except the highest opening, and the system filled with water to point of overflow. Where the system is tested in sections, each opening shall be tightly plugged, except the highest opening of the section under test, and each section shall be filled with water, but no section shall be tested with less than a 10 foot head of water (30 kPa). In testing successive sections, not less than the upper 10 feet (3048 mm) of the next preceding section shall be tested, so that no joint or pipe in the building (except the uppermost 10 feet (3048 mm) of the system) shall have been submitted to a test of less than a 10 foot head of water (30 kPa). The water shall be kept in the system, or in the portion under test, for not less than 15 minutes before inspection starts. The system shall then be tight at all points.

712.3 Air Test. The air test shall be made by attaching an air compressor testing apparatus to a suitable opening and, after closing all other inlets and outlets to the system, forcing air into the system until there is a uniform gauge pressure of 5 pounds-force per square inch (psi) (34 kPa) or sufficient to balance a column of mercury 10 inches (34 kPa) in height. The pressure shall be held without introduction of additional air for a period of not less than 15 minutes.

Part II – Building Sewers.

713.0 Sewer Required.

713.1 Where Required. A building in which plumbing fixtures are installed and premises having drainage piping thereon shall have a connection to a public or private sewer, except as provided in Section 713.2, and Section 713.4.

713.2 Private Sewage Disposal System. Where no public sewer intended to serve a lot or premises is available in a thoroughfare or right of way abutting such lot or premises, drainage piping from a building or works shall be connected to an approved private sewage disposal system.

713.3 Public Sewer. Within the limits prescribed by Section 713.4 hereof, the rearrangement or subdivision into smaller parcels of a lot that abuts and is served by a public sewer shall not be deemed cause to permit the construction of a private sewage disposal system, and plumbing or drainage systems on a smaller parcel or parcels shall connect to the public sewer.

713.4 Public Sewer Availability. The public sewer shall be permitted to be considered as not being available where such public sewer or a building or an exterior drainage facility connected thereto is located more than 200 feet (60 960 mm) from a proposed building or exterior drainage facility on a lot or premises that abuts and is served by such public sewer.

713.5 Permit. No permit shall be issued for the installation, alteration, or repair of a private sewage disposal system, or part thereof, on a lot for which a connection with a public sewer is available.

713.6 Lot. On every lot or premises hereafter connected to a public sewer, plumbing and drainage systems or parts thereof on such lot or premises shall be connected with such public sewer.

713.7 Installation. In cities, counties, or both where the installation of building sewers is under the jurisdiction of a department other than the Authority Having Jurisdiction, the provisions of this code relating to building sewers need not apply.

Exception: Single-family dwellings and buildings or structures accessory thereto, existing and connected to an approved private sewage disposal system prior to the time of connecting the premises to the public sewer shall be permitted, where no hazard, nuisance, or insanitary condition is evidenced and written permission has been obtained from the Authority Having Jurisdiction, remain connected

to such properly maintained private sewage disposal system where there is insufficient grade or fall to permit drainage to the sewer by gravity.

714.0 Damage to Public Sewer or Private Sewage Disposal System.

714.1 Unlawful Practices. It shall be unlawful for a person to deposit, by means whatsoever, into a plumbing fixture, floor drain, interceptor, sump, receptor, or device which is connected to a drainage system, public sewer, private sewer, septic tank, or cesspool, ashes; cinders; solids; rags; flammable, poisonous, or explosive liquids or gases; oils; grease; and whatsoever that is capable of causing damage to the public sewer, private sewer, or private sewage disposal system.

714.2 Prohibited Water Discharge. No rain, surface, or subsurface water shall be connected to or discharged into a drainage system, unless first approved by the Authority Having Jurisdiction.

714.3 Prohibited Sewer Connection. No cesspool, septic tank, seepage pit, or drain field shall be connected to a public sewer or to a building sewer leading to such public sewer.

714.4 Commercial Food Waste Disposer. The Authority Having Jurisdiction shall review before approval, the installation of a commercial food waste disposer connecting to a private sewage disposal system.

714.5 Tanks. An approved-type, watertight sewage or wastewater holding tank, the contents of which, due to their character, shall be periodically removed and disposed of at some approved off-site location, shall be installed where required by the Authority Having Jurisdiction or the Health Officer to prevent anticipated surface or subsurface contamination or pollution, damage to the public sewer, or other hazardous or nuisance conditions.

715.0 Building Sewer Materials.

715.1 Materials. The building sewer, beginning 2 feet (610 mm) from a building or structure, shall be of such materials as prescribed in this code.

715.2 Joining Methods and Materials. Joining methods and materials shall be as prescribed in this code.

715.3 Existing Sewers. Replacement of existing building sewer and building storm sewers using trenchless methodology and materials shall be installed in accordance with ASTM F1216.

716.0 Markings.

716.1 General. Pipe, brick, block, prefabricated septic tanks, prefabricated septic tank or seepage pit covers, or other parts or appurtenances incidental to the installation of building sewers or private sewage disposal systems shall be in accordance with the approval requirements of Chapter 3 of this code.

717.0 Size of Building Sewers.

717.1 General. The minimum size of a building sewer shall be determined on the basis of the total number of fixture units drained by such sewer, in accordance with Table 717.1. No building sewer shall be smaller than the building drain.

For alternate methods of sizing building sewers, see Appendix C.

TABLE 717.1
MAXIMUM/MINIMUM FIXTURE UNIT LOADING
ON BUILDING SEWER PIPING*

| SIZE OF PIPE (inches) | SLOPE, (inches per foot) | | |
|--------------------------|--|----------|------------|
| | 1/16 | 1/8 | 1/4 |
| 6 and smaller | (As specified in Table 703.2/ No minimum loading) | | |
| 8 | 1950/1500 | 2800/625 | 3900/275 |
| 10 | 3400/1600 | 4900/675 | 6800/300 |
| 12 | 5600/1700 | 8000/725 | 11 200/325 |

For SI units: 1 inch = 25 mm, 1 inch per foot = 83.3 mm/m

* See also Appendix H, Private Sewage Disposal Systems. For alternate methods of sizing drainage piping, see Appendix C.

718.0 Grade, Support, and Protection of Building Sewers.

718.1 Slope. Building sewers shall be run in practical alignment and at a uniform slope of not less than 1/4 inch per foot (20.8 mm/m) toward the point of disposal.

Exception: Where approved by the Authority Having Jurisdiction and where it is impractical, due to the depth of the street sewer or to the structural features or to the arrangement of a building or structure, to obtain a slope of 1/4 inch per foot (20.8 mm/m), such pipe or piping 4 inches (100 mm) through 6 inches (150 mm) shall be permitted to have a slope of not less than 1/8 inch per foot (10.4 mm/m) and such piping 8 inches (200 mm) and larger shall be permitted to have a slope of not less than 1/16 inch per foot (5.2 mm/m).

718.2 Support. Building sewer piping shall be laid on a firm bed throughout its entire length, and such piping laid in made or filled-in ground shall be laid on a bed of approved materials and shall be properly supported as required by the Authority Having Jurisdiction.

718.3 Protection from Damage. No building sewer or other drainage piping or part thereof, which is constructed of materials other than those approved for use under or within a building, shall be installed under or within 2 feet (610 mm) of a building or structure, or part thereof, nor less than 1 foot (305 mm) below the surface of the ground. The provisions of this subsection include structures such as porches and steps, whether covered or uncovered; breezeways; roofed porte cocheres; roofed patios; carports; covered walks; covered driveways; and similar structures or appurtenances.

719.0 Cleanouts.

719.1 Locations. Cleanouts shall be placed inside the building near the connection between the building drain and the building sewer or installed outside the building at the lower end of the building drain and extended to grade.

Additional building sewer cleanouts shall be installed at intervals not to exceed 100 feet (30 480 mm) in straight runs and for each aggregate horizontal change in direction exceeding 135 degrees (2.36 rad).

719.2 No Additional Cleanouts. Where a building sewer or a branch thereof does not exceed 10 feet (3048 mm) in length and is a straight-line projection from a building drain that is provided with a cleanout, no cleanout will be required at its point of connection to the building drain.

719.3 Building Sewer Cleanouts. Required building sewer cleanouts shall be extended to grade and shall be in accordance with the appropriate sections of cleanouts, Section 707.0, for sizing, construction, and materials. Where building sewers are located under buildings, the cleanout requirements of Section 707.0 shall apply.

719.4 Cleaning. Each cleanout shall be installed so that it opens to allow cleaning in the direction of flow of the soil or waste or at right angles thereto and, except in the case of wye branch and end-of-line cleanouts, shall be installed vertically above the flow line of the pipe.

719.5 Access. Cleanouts installed under concrete or asphalt paving shall be made accessible by yard boxes or by extending flush with paving with approved materials and shall be adequately protected.

719.6 Manholes. Approved manholes shall be permitted to be installed in lieu of cleanouts, where first approved by the Authority Having Jurisdiction. The maximum distance between manholes shall not exceed 300 feet (91 440 mm).

The inlet and outlet connections shall be made by the use of a flexible compression joint not less than 12 inches (305 mm) and not exceeding 3 feet (914 mm) from the manhole. No flexible compression joints shall be embedded in the manhole base.

720.0 Sewer and Water Pipes.

720.1 General. Building sewers or drainage piping of clay or materials that are not approved for use within a building shall not be run or laid in the same trench as the water pipes unless the following requirements are met:

- (1) The bottom of the water pipe, at points, shall be not less than 12 inches (305 mm) above the top of the sewer or drain line.
- (2) The water pipe shall be placed on a solid shelf excavated at one side of the common trench with a clear horizontal distance of not less than 12 inches (305 mm) from the sewer or drain line.
- (3) Water pipes crossing sewer or drainage piping constructed of clay or materials that are not approved for use within a building shall be laid not less than 12 inches (305 mm) above the sewer or drain pipe.

For the purpose of this section, "within a building" shall mean within the fixed limits of the building foundation.

721.0 Location.

721.1 Building Sewer. Except as provided in Section 721.2, no building sewer shall be located in a lot other than the lot that is the site of the building or structure served by such sewer nor shall a building sewer be located at a point having less than the minimum distances referenced in Table 721.1.

721.2 Abutting Lot. Nothing contained in this code shall be construed to prohibit the use of all or part of an abutting lot to:

- (1) Provide access to connect a building sewer to an available public sewer where proper cause and legal easement, not in violation of other requirements, has been first established to the satisfaction of the Authority Having Jurisdiction.
- (2) Provide additional space for a building sewer where proper cause, transfer of ownership, or change of boundary, not in violation of other requirements, has been first established to the satisfaction of the Authority Having Jurisdiction. The instrument recording such action shall constitute an agreement with the Authority Having Jurisdiction and shall clearly state and show that the areas so joined or used shall be maintained as a unit during the time they are so used. Such an agreement shall be recorded in the office of the County Recorder as part of the conditions of ownership of said properties, and shall be binding on heirs, successors, and assigns to such properties. A copy of the instrument recording such proceedings shall be filed with the Authority Having Jurisdiction.

722.0 Abandoned Sewers and Sewage Disposal Facilities.

722.1 Building (House) Sewer. An abandoned building (house) sewer, or part thereof, shall be plugged or capped in an approved manner within 5 feet (1524 mm) of the property line.

722.2 Cesspools, Septic Tanks, and Seepage Pits. A cesspool, septic tank, and seepage pit that has been abandoned or has been discontinued otherwise from further use, or to which no waste or soil pipe from a plumbing fixture is connected, shall have the sewage removed therefrom and be completely filled with earth, sand, gravel, concrete, or other approved material.

722.3 Filling. The top cover or arch over the cesspool, septic tank, or seepage pit shall be removed before filling, and the filling shall not extend above the top of the vertical portions of the sidewalls or above the level of the outlet pipe until inspection has been called and the cesspool, septic tank, or seepage pit has been inspected. After such inspection, the cesspool, septic tank, or seepage pit shall be filled to the level of the top of the ground.

722.4 Ownership. No person owning or controlling a cesspool, septic tank, or seepage pit on the premises of such

TABLE 721.1
MINIMUM HORIZONTAL DISTANCE REQUIRED FROM BUILDING SEWER (feet)

| | |
|--|--------------------|
| Buildings or structures ¹ | 2 |
| Property line adjoining private property | Clear ² |
| Water supply wells | 50 ³ |
| Streams | 50 |
| On-site domestic water service line | 1 ⁴ |
| Public water main | 10 ^{5,6} |

For SI units: 1 foot = 304.8 mm

Notes:

¹ Including porches and steps, whether covered or uncovered; breezeways; roofed portecocheres; roofed patios; carports; covered walks; covered driveways; and similar structures or appurtenances.

² See also Section 312.3.

³ Drainage piping shall clear domestic water supply wells by not less than 50 feet (15 240 mm). This distance shall be permitted to be reduced to not less than 25 feet (7620 mm) where the drainage piping is constructed of materials approved for use within a building.

⁴ See Section 720.0.

⁵ For parallel construction.

⁶ For crossings, approval by the Health Department or the Authority Having Jurisdiction shall be required.

person or in that portion of a public street, alley, or other public property abutting such premises, shall fail, refuse, or neglect to comply with the provisions of this section or upon receipt of notice so to comply from the Authority Having Jurisdiction.

722.5 Disposal Facilities. Where disposal facilities are abandoned consequent to connecting a premises with the public sewer, the permittee making the connection shall fill abandoned facilities in accordance with the Authority Having Jurisdiction within 30 days from the time of connecting to the public sewer.

723.0 Building Sewer Test.

723.1 General. Building sewers shall be tested by plugging the end of the building sewer at its points of connection with the public sewer or private sewage disposal system and completely filling the building sewer with water from the lowest to the highest point thereof, or by approved equivalent low-pressure air test. Plastic DWV piping systems shall not be tested by the air test method. The building sewer shall be watertight.

CHAPTER 8

INDIRECT WASTES

801.0 General.

801.1 Applicability. This chapter shall govern the materials, design, and installation of indirect waste piping, receptors, and connections; and provisions for discharge and disposal of condensate wastes, chemical wastes, industrial wastes, and clear water wastes.

» **801.2 Air Gap or Air Break Required.** Indirect waste piping shall discharge into the building drainage system through an air gap or air break as set forth in this code. Where a drainage air gap is required by this code, the minimum vertical distance as measured from the lowest point of the indirect waste pipe or the fixture outlet to the flood-level rim of the receptor shall be not less than 1 inch (25.4 mm).

» **801.3 Food and Beverage Handling Establishments.** Establishments engaged in the storage, preparation, selling, serving, processing, or other handling of food and beverage involving the following equipment that requires drainage shall provide indirect waste piping for refrigerators, refrigeration coils, freezers, walk-in coolers, iceboxes, ice-making machines, steam tables, egg boilers, coffee urns and brewers, hot-and-cold drink dispensers, and similar equipment.

» **801.3.1 Size of Indirect Waste Pipes.** Except for refrigeration coils and ice-making machines, the size of the indirect waste pipe shall be not smaller than the drain on the unit, but shall be not smaller than 1 inch (25 mm), and the maximum developed length shall not exceed 15 feet (4572 mm). Indirect waste pipe for ice-making machines shall be not less than the drain on the unit, and in no case less than $\frac{3}{4}$ of an inch (20 mm).

» **801.3.2 Walk-In Coolers.** For walk-in coolers, floor drains shall be permitted to be connected to a separate drainage line discharging into an outside receptor. The flood-level rim of the receptor shall be not less than 6 inches (152 mm) lower than the lowest floor drain. Such floor drains shall be trapped and individually vented. Cleanouts shall be provided at 90 degree (1.57 rad) turns and shall be accessibly located. Such waste shall discharge through an air gap or air break into a trapped and vented receptor, except that a full-size air gap is required where the indirect waste pipe is under vacuum.

» **801.3.3 Food-Handling Fixtures.** Food-preparation sinks, steam kettles, potato peelers, ice cream dipper wells, and similar equipment shall be indirectly connected to the drainage system by means of an air gap. Bins, sinks, and other equipment having drainage connections and used for the storage of unpackaged ice used for human ingestion, or used in direct contact with ready-to-eat food, shall be indirectly connected to the drainage system by means of an air gap. Each indirect waste pipe from food-handling fixtures or equipment shall be separately piped to the indirect waste receptor

and shall not combine with other indirect waste pipes. The piping from the equipment to the receptor shall be not less than the drain on the unit, and in no case less than $\frac{1}{2}$ of an inch (15 mm).

801.4 Bar and Fountain Sink Traps. Where the sink in a bar, soda fountain, or counter is so located that the trap serving the sink cannot be vented, the sink drain shall discharge through an air gap or air break (see Section 801.3.3) into an approved receptor that is vented. The developed length from the fixture outlet to the receptor shall not exceed 5 feet (1524 mm). <<

801.5 Connections from Water Distribution System. Indirect waste connections shall be provided for drains, overflows, or relief pipes from potable water pressure tanks, water heaters, boilers, and similar equipment that is connected to the potable water distribution system. Such indirect waste connections shall be made by means of a water-distribution air gap constructed in accordance with Table 603.3.1. <<

801.6 Sterilizers. Lines, devices, or apparatus such as stills, sterilizers, and similar equipment requiring waste connections and used for sterile materials shall be indirectly connected by means of an air gap. Each such indirect waste pipe shall be separately piped to the receptor and shall not exceed 15 feet (4572 mm). Such receptors shall be located in the same room. <<

801.7 Drip or Drainage Outlets. Appliances, devices, or apparatus not regularly classified as plumbing fixtures, but which have drip or drainage outlets, shall be permitted to be drained by indirect waste pipes discharging into an open receptor through either an air gap or air break (see Section 801.3.1). <<

802.0 Approvals.

802.1 General. No plumbing fixtures served by indirect waste pipes or receiving discharge therefrom shall be installed until first approved by the Authority Having Jurisdiction.

803.0 Indirect Waste Piping.

803.1 Materials. Pipe, tube, and fittings conveying indirect waste shall be of such materials and design as to perform their intended function to the satisfaction of the Authority Having Jurisdiction.

803.2 Copper and Copper Alloys. Joints and connections in copper and copper alloy pipe and tube shall be installed in accordance with Section 705.3.

803.3 Pipe Size and Length. Except as hereinafter provided, the size of indirect waste piping shall be in accordance with other sections of this code applicable to drainage and vent piping. No vent from indirect waste piping shall combine with a sewer-connected vent, but shall extend separately to the outside air. Indirect waste pipes <<

INDIRECT WASTES

exceeding 5 feet (1524 mm), but less than 15 feet (4572 mm) in length shall be directly trapped, but such traps need not be vented.

Indirect waste pipes less than 15 feet (4572 mm) in length shall be not less than the diameter of the drain outlet or tailpiece of the fixture, appliance, or equipment served, and in no case less than ½ of an inch (15 mm). Angles and changes of direction in such indirect waste pipes shall be provided with cleanouts so as to permit flushing and cleaning.

804.0 Indirect Waste Receptors.

804.1 Standpipe Receptors. Plumbing fixtures or other receptors receiving the discharge of indirect waste pipes shall be approved for the use proposed and shall be of such shape and capacity as to prevent splashing or flooding and shall be located where they are readily accessible for inspection and cleaning. No standpipe receptor for a clothes washer shall extend more than 30 inches (762 mm), or not less than 18 inches (457 mm) above its trap. No trap for a clothes washer standpipe receptor shall be installed below the floor, but shall be roughed in not less than 6 inches (152 mm) and not more than 18 inches (457 mm) above the floor. No indirect waste receptor shall be installed in a toilet room, closet, cupboard, or storeroom, nor in a portion of a building not in general use by the occupants thereof; except standpipes for clothes washers shall be permitted to be installed in toilet and bathroom areas where the clothes washer is installed in the same room.

805.0 Pressure Drainage Connections.

805.1 General. Indirect waste connections shall be provided for drains, overflows, or relief vents from the water supply system, and no piping or equipment carrying wastes or producing wastes or other discharges under pressure shall be directly connected to a part of the drainage system.

The foregoing shall not apply to an approved sump pump or to an approved pressure-wasting plumbing fixture or device where the Authority Having Jurisdiction has been satisfied that the drainage system is adequately sized to accommodate the anticipated discharge thereof.

806.0 Sterile Equipment.

806.1 General. Appliances, devices, or apparatus such as stills, sterilizers, and similar equipment requiring water and waste and used for sterile materials shall be drained through an air gap.

807.0 Appliances.

807.1 Non-Classified Apparatus. Commercial dishwashing machines, silverware washing machines, and other appliances, devices, equipment, or other apparatus not regularly classed as plumbing fixtures, which are equipped with pumps, drips, or drainage outlets, shall be permitted to be drained by indirect waste pipes discharging into an approved type of open receptor.

807.2 Undiluted Condensate Waste. Where undiluted condensate waste from a fuel-burning condensing appliance is discharged into the drainage system, the material in the drainage system shall be cast-iron, galvanized iron, plastic, or other materials approved for this use.

Exceptions:

- (1) Where the above condensate is discharged to an exposed fixture tailpiece and trap, such tailpiece and trap shall be permitted to be copper alloy.
- (2) Materials approved in Section 701.0 shall be permitted to be used where data is provided that the condensate waste is adequately diluted.

807.3 Domestic Dishwashing Machine. No domestic dishwashing machine shall be directly connected to a drainage system or food waste disposer without the use of an approved dishwasher air gap fitting on the discharge side of the dishwashing machine. Listed air gaps shall be installed with the flood-level (FL) marking at or above the flood level of the sink or drainboard, whichever is higher.

808.0 Cooling Water.

808.1 General. Where permitted by the Authority Having Jurisdiction, clean running water used exclusively as a cooling medium in an appliance, device, or apparatus shall be permitted to discharge into the drainage system through the inlet side of a fixture trap in the event that a suitable fixture is not available to receive such discharge. Such trap connection shall be by means of a pipe connected to the inlet side of an approved fixture trap, the upper end terminating in a funnel-shaped receptacle set adjacent, and not less than 6 inches (152 mm) above the overflow rim of the fixture.

809.0 Drinking Fountains.

809.1 General. Drinking fountains shall be permitted to be installed with indirect wastes.

810.0 Steam and Hot Water Drainage Condensers and Sumps.

810.1 High Temperature Discharge. No steam pipe shall be directly connected to a plumbing or drainage system, nor shall water having a temperature above 140°F (60°C) be discharged under pressure directly into a drainage system. Pipes from boilers shall discharge by means of indirect waste piping, as determined by the Authority Having Jurisdiction or the boiler manufacturer's recommendations. Such pipes shall be permitted to be indirectly connected by discharging into an open or closed condenser or an intercepting sump of an approved type that will prevent the entrance of steam or such water under pressure into the drainage system. Closed condensers or sumps shall be provided with a vent that shall be taken off the top and extended separately, full size above the roof. Condensers and sumps shall be properly trapped at the outlet with a

deep seal trap extending to within 6 inches (152 mm) of the bottom of the tank. The top of the deep seal trap shall have a $\frac{3}{4}$ of an inch (19.1 mm) opening located at the highest point of the trap to serve as a siphon breaker. Outlets shall be taken off from the side in such a manner as to allow a waterline to be maintained that will permanently occupy not less than one-half the capacity of the condenser or sump. Inlets shall enter above the waterline. Wearing plates or baffles shall be installed in the tank to protect the shell. The sizes of the blowoff line inlet, the water outlets, and the vent shall be as shown in Table 810.1. The contents of condensers receiving steam or hot water under pressure shall pass through an open sump before entering the drainage system.

TABLE 810.1
PIPE CONNECTIONS IN BLOWOFF CONDENSERS AND SUMPS
(inches)

| BOILER BLOWOFF | WATER OUTLET | VENT |
|-----------------|-----------------|------|
| $\frac{3}{4}$ * | $\frac{3}{4}$ * | 2 |
| 1 | 1 | 2½ |
| 1¼ | 1¼ | 3 |
| 1½ | 1½ | 4 |
| 2 | 2 | 5 |
| 2½ | 2½ | 6 |

For SI units: 1 inch = 25.4 mm

* To be used only with boilers of 100 square feet (9.29 m²) of heating surface or less.

810.2 Sumps, Condensers, and Intercepting Tanks. Sumps, condensers, or intercepting tanks that are constructed of concrete shall have walls and bottom not less than 4 inches (102 mm) in thickness, and the inside shall be cement plastered not less than $\frac{1}{2}$ of an inch (12.7 mm) in thickness. Condensers constructed of metal shall be not less than No. 12 U.S. standard gauge (0.109 inch) (2.77 mm), and such metal condensers shall be protected from external corrosion by an approved bituminous coating.

810.3 Cleaning. Sumps and condensers shall be provided with suitable means of access for cleaning and shall contain a volume of not less than twice the volume of water removed from the boiler or boilers connected thereto where the normal water level of such boiler or boilers is reduced not less than 4 inches (102 mm).

810.4 Strainers. An indirect waste interceptor receiving discharge-containing particles that would clog the receptor drain shall have a readily removable beehive strainer.

811.0 Chemical Wastes.

811.1 Pretreatment. Chemical or industrial liquid wastes that are likely to damage or increase maintenance costs on the sanitary sewer system, detrimentally affect sewage treatment, or contaminate surface or subsurface waters shall be pretreated to render them innocuous prior to discharge

into a drainage system. Detailed construction documents of the pretreatment facilities shall be required by the Authority Having Jurisdiction.

Piping conveying industrial, chemical, or process wastes from their point of origin to sewer-connected pretreatment facilities shall be of such material and design as to adequately perform its intended function to the satisfaction of the Authority Having Jurisdiction. Drainage discharge piping from pretreatment facilities or interceptors shall be in accordance with standard drainage installation procedures.

Copper or copper alloy tube shall not be used for chemical or industrial wastes as defined in this section.

811.2 Waste and Vent Pipes. Each waste pipe receiving or intended to receive the discharge of a fixture into which acid or corrosive chemical is placed, and each vent pipe connected thereto, shall be constructed of chlorinated polyvinyl chloride (CPVC), polypropylene (PP), polyvinylidene fluoride (PVDF), chemical-resistant glass, high-silicon iron pipe, or lead pipe with a wall thickness of not less than $\frac{1}{8}$ of an inch (3.2 mm); an approved type of ceramic glazed or unglazed vitrified clay; or other approved corrosion-resistant materials. PP pipe and fittings shall comply with ASTM F1412 or CSA B181.3. PVDF pipe and fittings shall comply with ASTM F1673 or CSA B181.3. Chemical-resistant glass pipe and fittings shall comply with ASTM C1053. High-silicon iron pipe and fittings shall comply with ASTM A861.

811.3 Joining Materials. Joining materials shall be of approved type and quality.

811.4 Access. Where practicable, piping shall be readily accessible and installed with the maximum of clearance from other services.

811.5 Permanent Record. The owner shall make and keep a permanent record of the location of piping and venting carrying chemical waste.

811.6 Chemical Vent. No chemical vent shall intersect vents for other services.

811.7 Discharge. Chemical wastes shall be discharged in a manner approved by the Authority Having Jurisdiction.

811.8 Diluted Chemicals. The provisions in this section relative to materials and methods of construction shall not apply to installations such as photographic or x-ray dark-rooms or research or control laboratories where minor amounts of adequately diluted chemicals are discharged.

812.0 Clear Water Wastes.

812.1 General. Water lifts, expansion tanks, cooling jackets, sprinkler systems, drip or overflow pans, or similar devices that discharge clear wastewater into the building drainage system shall discharge through an indirect waste.

813.0 Swimming Pools.

813.1 General. Pipes carrying wastewater from swimming or wading pools, including pool drainage and backwash from filters, shall be installed as an indirect waste.

INDIRECT WASTES

Where a pump is used to discharge waste pool water to the drainage system, the pump discharge shall be installed as an indirect waste.

814.0 Condensate Waste and Control.

814.1 Condensate Disposal. Condensate from air washers, air-cooling coils, condensing appliances, and the overflow from evaporative coolers and similar water-supplied equipment or similar air-conditioning equipment shall be collected and discharged to an approved plumbing fixture or disposal area. Where discharged into the drainage system, equipment shall drain by means of an indirect waste pipe. The waste pipe shall have a slope of not less than $\frac{1}{8}$ inch per foot (10.4 mm/m) or 1 percent slope and shall be of approved corrosion-resistant material not smaller than the outlet size in accordance with Section 814.3 or Section 814.4 for air-cooling coils or condensing appliances, respectively. Condensate or wastewater shall not drain over a public way.

814.1.1 Condensate Pumps. Where approved by the Authority Having Jurisdiction, condensate pumps shall be installed in accordance with the manufacturer's installation instructions. Pump discharge shall rise vertically to a point where it is possible to connect to a gravity condensate drain and discharged to an approved disposal point. Each condensing unit shall be provided with a separate sump and interlocked with the equipment to prevent the equipment from operating during a failure. Separate pumps shall be permitted to connect to a single gravity indirect waste where equipped with check valves and approved by the Authority Having Jurisdiction.

814.2 Condensate Control. Where an equipment or appliance is installed in a space where damage is capable of resulting from condensate overflow, other than damage to replaceable lay-in ceiling tiles, a drain line shall be provided and shall be drained in accordance with Section 814.1. An additional protection method for condensate overflow shall be provided in accordance with one of the following:

- (1) A water level detecting device that will shut off the equipment or appliance in the event the primary drain is blocked.
- (2) An additional watertight pan of corrosion-resistant material, with a separate drain line, installed beneath the cooling coil, unit, or the appliance to catch the overflow condensate due to a clogged primary condensate drain.
- (3) An additional drain line at a level that is higher than the primary drain line connection of the drain pan.
- (4) An additional watertight pan of corrosion-resistant material with a water level detection device installed beneath the cooling coil, unit, or the appliance to catch the overflow condensate due to a clogged primary condensate drain and to shut off the equipment.

The additional pan or the additional drain line connection shall be provided with a drain pipe of not less than $\frac{3}{4}$ of an inch (20 mm) nominal pipe size, discharging at a point that is readily observed.

814.2.1 Protection of Appurtenances. Where insulation or appurtenances are installed where damage is capable of resulting from a condensate drain pan overflow, such installations shall occur above the rim of the drain pan with supports. Where the supports are in contact with the condensate waste, the supports are in contact with the condensate waste, the supports shall be of approved corrosion-resistant material.

814.3 Condensate Waste Pipe Material and Sizing. Condensate waste pipes from air-cooling coils shall be sized in accordance with the equipment capacity as specified in Table 814.3. The material of the piping shall comply with the pressure and temperature rating of the appliance or equipment, and shall be approved for use with the liquid being discharged.

TABLE 814.3
MINIMUM CONDENSATE PIPE SIZE

| EQUIPMENT CAPACITY IN TONS OF REFRIGERATION | MINIMUM CONDENSATE PIPE DIAMETER (inches) |
|--|---|
| Up to 20 | $\frac{3}{4}$ |
| 21 – 40 | 1 |
| 41 – 90 | 1 $\frac{1}{4}$ |
| 91 – 125 | 1 $\frac{1}{2}$ |
| 126 – 250 | 2 |

For SI units: 1 ton of refrigerant = 3.52 kW, 1 inch = 25 mm

The size of condensate waste pipes is for one unit or a combination of units, or as recommended by the manufacturer. The capacity of waste pipes assumes a $\frac{1}{8}$ inch per foot (10.4 mm/m) or 1 percent slope, with the pipe running three-quarters full at the following pipe conditions:

| Outside Air – 20% | | Room Air – 80% | |
|-------------------|------|----------------|--------|
| DB | WB | DB | WB |
| 90°F | 73°F | 75°F | 62.5°F |

For SI units: °C = (°F-32)/1.8

Condensate drain sizing for other slopes or other conditions shall be approved by the Authority Having Jurisdiction.

Air-conditioning waste pipes shall be constructed of materials specified in Chapter 7.

814.3.1 Cleanouts. Condensate drain lines shall be configured or provided with a cleanout to permit the clearing of blockages and for maintenance without requiring the drain line to be cut.

814.4 Appliance Condensate Drains. Condensate drain lines from individual condensing appliances shall be sized as required by the manufacturer's instructions. Condensate drain lines serving more than one appliance shall be approved by the Authority Having Jurisdiction prior to installation.

» **814.5 Point of Discharge.** Air-conditioning condensate waste pipes shall connect indirectly, except where permitted in Section 814.6, to the drainage system through an air gap or air break to trapped and vented receptors, dry wells, leach pits, or the tailpiece of plumbing fixtures. A condensate drain shall be trapped in accordance with the appliance manufacturer's instructions or as approved.

814.6 Condensate Waste From Air-Conditioning Coils. Where the condensate waste from air-conditioning coils discharges by direct connection to a lavatory tailpiece or to an approved accessible inlet on a bathtub overflow, the connection shall be located in the area controlled by the same person controlling the air-conditioned space.

814.7 Plastic Fittings. Female plastic screwed fittings shall be used with plastic male fittings and plastic threads.

CHAPTER 9

VENTS

901.0 General.

901.1 Applicability. This chapter shall govern the materials, design, and installation of plumbing vent systems.

- » **901.2 Vents Required.** Each plumbing fixture trap, except as otherwise provided in this code, shall be protected against siphonage and backpressure, and air circulation shall be ensured throughout all parts of the drainage system by means of vent pipes installed in accordance with the requirements of this chapter and as otherwise required by this code.
- » **901.3 Trap Seal Protection.** The vent system shall be designed to prevent a trap seal from being exposed to a pressure differential that exceeds 1 inch water column (0.24 kPa) on the outlet side of the trap.

902.0 Vents Not Required.

902.1 Interceptor. Vent piping shall be permitted to be omitted on an interceptor where such interceptor acts as a primary settling tank and discharges through a horizontal indirect waste pipe into a secondary interceptor. The second interceptor shall be properly trapped and vented.

902.2 Bars, Soda Fountains, and Counter. Traps serving sinks that are part of the equipment of bars, soda fountains, and counters need not be vented where the location and construction of such bars, soda fountains, and counters is such as to make it impossible to do so. Where such conditions exist, said sinks shall discharge by means of approved indirect waste pipes into a floor sink or other approved type of receptor.

903.0 Materials.

903.1 Applicable Standards. Vent pipe and fittings shall comply with the applicable standards referenced in Table 701.2, except that:

- (1) No galvanized steel or 304 stainless steel pipe shall be installed underground and shall be not less than 6 inches (152 mm) aboveground.
- (2) ABS and PVC DWV piping installations shall be in accordance with the applicable standards referenced in Table 1701.1, and Chapter 14 "Firestop Protection." Except for individual single-family dwelling units, materials exposed within ducts or plenums shall have a flame-spread index of not more than 25 and a smoke-developed index of not more than 50 where tested in accordance with ASTM E84 or UL 723.

- » **903.2 Use of Copper or Copper Alloy Tubing.** Copper or copper alloy tube for underground drainage and vent piping shall have a weight of not less than that of copper or copper alloy drainage tube type DWV.

903.2.1 Aboveground. Copper or copper alloy tube for aboveground drainage and vent piping shall have a weight of not less than that of copper or copper alloy drainage tube type DWV.

903.2.2 Prohibited Use. Copper or copper alloy tube shall not be used for chemical or industrial wastes as defined in Section 811.0.

903.2.3 Marking. Copper or copper alloy tubing, in addition to the required incised marking, shall be marked in accordance with either ASTM B306 or ASTM B88 as listed in Table 1701.1. The colors shall be: Type K, green; Type L, blue; Type M, red; and Type DWV, yellow.

903.3 Changes in Direction. Changes in direction of vent piping shall be made by the appropriate use of approved fittings, and no such pipe shall be strained or bent. Burred ends shall be reamed to the full bore of the pipe.

904.0 Size of Vents.

904.1 Size. The size of vent piping shall be determined from its length and the total number of fixture units connected thereto, in accordance with Table 703.2. The diameter of an individual vent shall be not less than 1¼ inches (32 mm) nor less than one-half the diameter of the drain to which it is connected. In addition, the drainage piping of each building and each connection to a public sewer or a private sewage disposal system shall be vented by means of one or more vent pipes, the aggregate cross-sectional area of which shall be not less than that of the largest required building sewer, as determined from Table 703.2. Vent pipes from fixtures located upstream from pumps, ejectors, backwater valves, or other devices that obstruct the free flow of air and other gases between the building sewer and the outside atmosphere shall not be used for meeting the cross-sectional area venting requirements of this section.

Exception: Where connected to a common building sewer, the drainage piping of two or more buildings located on the same lot and under one ownership shall be permitted to be vented by means of piping sized in accordance with Table 703.2, provided the aggregate cross-sectional area of vents is not less than that of the largest required common building sewer.

904.2 Length. Not more than one-third of the total permitted length, in accordance with Table 703.2, of a minimum-sized vent shall be installed in a horizontal position.

Exception: Where a minimum-sized vent is increased one pipe size for its entire length, the maximum length limitation shall not apply.

905.0 Vent Pipe Grades and Connections.

905.1 Grade. Vent and branch vent pipes shall be free from drops or sags, and each such vent shall be level or shall be so graded and connected as to drip back by gravity to the drainage pipe it serves.

905.2 Horizontal Drainage Pipe. Where vents connect to a horizontal drainage pipe, each vent pipe shall have its invert taken off above the drainage centerline of such pipe downstream of the trap being served.

905.3 Vent Pipe Rise. Unless prohibited by structural conditions, each vent shall rise vertically to a point not less than 6 inches (152 mm) above the flood-level rim of the fixture served before offsetting horizontally, and where two or more vent pipes converge, each such vent pipe shall rise to a point not less than 6 inches (152 mm) in height above the flood-level rim of the plumbing fixture it serves before being connected to any other vent. Vents less than 6 inches (152 mm) above the flood-level rim of the fixture shall be installed with approved drainage fittings, material, and grade to the drain.

905.4 Roof Termination. Vent pipes shall extend undiminished in size above the roof, or shall be reconnected with a soil or waste vent of proper size.

905.5 Location of Opening. The vent pipe opening from a soil or waste pipe, except for water closets and similar fixtures, shall not be below the weir of the trap.

905.6 Common Vertical Pipe. Two fixtures shall be permitted to be served by a common vertical pipe where each such fixture wastes separately into an approved double fitting having inlet openings at the same level.

906.0 Vent Termination.

906.1 Roof Termination. Each vent pipe or stack shall extend through its flashing and shall terminate vertically not less than 6 inches (152 mm) above the roof nor less than 1 foot (305 mm) from a vertical surface.

906.2 Clearance. Each vent shall terminate not less than 10 feet (3048 mm) from, or not less than 3 feet (914 mm) above, an openable window, door, opening, air intake, or vent shaft, or not less than 3 feet (914 mm) in every direction from a lot line, alley and street excepted.

906.3 Use of Roof. Vent pipes shall be extended separately or combined, of full required size, not less than 6 inches (152 mm) above the roof or fire wall. Flagpoling of vents shall be prohibited except where the roof is used for assembly purposes or parking. Vents within 10 feet (3048 mm) of a part of the roof that is used for assembly purposes or parking shall extend not less than 7 feet (2134 mm) above such roof and shall be securely stayed.

906.4 Outdoor Installations. Vent pipes for outdoor installations shall extend not less than 10 feet (3048 mm) above the surrounding ground and shall be securely supported.

906.5 Joints. Joints at the roof around vent pipes shall be made watertight by the use of approved flashings or flashing material.

906.6 Lead. (See Table 1701.1) Sheet lead shall comply with the following:

- (1) For safe pans – not less than 4 pounds per square foot (lb/ft²) (19 kg/m²) or 1/16 of an inch (1.6 mm) thick.
- (2) For flashings or vent terminals – not less than 3 lb/ft² (15 kg/m²).
- (3) Lead bends and lead traps shall be not less than 1/8 of an inch (3.2 mm) in wall thickness.

906.7 Frost or Snow Closure. Where frost or snow closure is likely to occur in locations having minimum design temperature below 0°F (-17.8°C), vent terminals shall be not less than 2 inches (50 mm) in diameter, but in no event smaller than the required vent pipe. The change in diameter shall be made inside the building not less than 1 foot (305 mm) below the roof in an insulated space and terminate not less than 10 inches (254 mm) above the roof, or in accordance with the Authority Having Jurisdiction.

907.0 Vent Stacks and Relief Vents.

907.1 Drainage Stack. Each drainage stack that extends 10 or more stories shall be served by a parallel vent stack, which shall extend undiminished in size from its upper terminal and connect to the drainage stack at or immediately below the lowest fixture drain. Each such vent stack shall also be connected to the drainage stack at each fifth floor, counting down from the uppermost fixture drain, by means of a yoke vent, the size of which shall be not less in diameter than either the drainage or the vent stack, whichever is smaller.

907.2 Yoke Vent. The yoke vent connection to the vent stack shall be placed not less than 42 inches (1067 mm) above the floor level, and the yoke vent connection to the drainage stack shall be by means of a wye-branch fitting placed below the lowest drainage branch connection serving that floor.

908.0 Wet Venting.

908.1 Vertical Wet Venting. Wet venting is limited to vertical drainage piping receiving the discharge from the trap arm of one and two fixture unit fixtures that also serves as a vent not exceeding four fixtures. Wet-vented fixtures shall be within the same story; provided, further, that fixtures with a continuous vent discharging into a wet vent shall be within the same story as the wet-vented fixtures. No wet vent shall exceed 6 feet (1829 mm) in developed length.

908.1.1 Size. The vertical piping between two consecutive inlet levels shall be considered a wet-vented section. Each wet-vented section shall be not less than one pipe size exceeding the required minimum waste pipe size of the upper fixture or shall be one pipe size exceeding the required minimum pipe size for the sum of the fixture units served by such wet-vented section, whichever is larger, but in no case less than 2 inches (50 mm).

908.1.2 Vent Connection. Common vent sizing shall be the sum of the fixture units served but, in no case, smaller than the minimum vent pipe size required for a fixture served, or by Section 904.0.

908.2 Horizontal Wet Venting for a Bathroom Group. A bathroom group located on the same floor level shall be permitted to be vented by a horizontal wet vent where all of the conditions of Section 908.2.1 through Section 908.2.5 are met.

908.2.1 Vent Connection. The dry vent connection to the wet vent shall be an individual vent for the bidet, shower, or bathtub. One or two vented lavatory(s) shall be permitted to serve as a wet vent for a bathroom group. Only one wet-vented fixture drain or trap arm shall discharge upstream of the dry-vented fixture drain connection. Dry vent connections to the horizontal wet vent shall be in accordance with Section 905.2 and Section 905.3.

908.2.2 Size. The wet vent shall be sized based on the fixture unit discharge into the wet vent. The wet vent shall be not less than 2 inches (50 mm) in diameter for 4 drainage fixture units (dfu) or less, and not less than 3 inches (80 mm) in diameter for 5 dfu or more. The dry vent shall be sized in accordance with Table 702.1 and Table 703.2 based on the total fixture units discharging into the wet vent.

908.2.3 Trap Arm. The length of the trap arm shall not exceed the limits in Table 1002.2. The trap size shall be in accordance with Section 1003.3. The vent pipe opening from the horizontal wet vent, except for water closets and similar fixtures, shall not be below the weir of the trap.

908.2.4 Water Closet. The water closet fixture drain or trap arm connection to the wet vent shall be downstream of fixture drain or trap arm connections to the horizontal wet vent.

908.2.5 Additional Fixtures. Additional fixtures shall discharge downstream of the wet vent system and be conventionally vented. Only the fixtures within the bathroom group shall connect to the wet-vented horizontal branch.

909.0 Special Venting for Island Fixtures.

909.1 General. Traps for island sinks and similar equipment shall be roughed in above the floor and shall be permitted to be vented by extending the vent as high as possible, but not less than the drainboard height and then returning it downward and connecting it to the horizontal sink drain immediately downstream from the vertical fixture drain. The return vent shall be connected to the horizontal drain through a wye-branch fitting and shall, in addition, be provided with a foot vent taken off the vertical fixture vent by means of a wye branch immediately below the floor and extending to the nearest partition and then through the roof to the open air, or shall be permitted to be connected to other vents at a point not less than 6 inches

(152 mm) above the flood-level rim of the fixtures served. Drainage fittings shall be used on the vent below the floor level, and a slope of not less than ¼ inch per foot (20.8 mm/m) back to the drain shall be maintained. The return bend used under the drainboard shall be a one piece fitting or an assembly of a 45 degree (0.79 rad), a 90 degree (1.57 rad), and a 45 degree (0.79 rad) elbow in the order named. Pipe sizing shall be as elsewhere required in this code. The island sink drain, upstream of the returned vent, shall serve no other fixtures. An accessible cleanout shall be installed in the vertical portion of the foot vent.

910.0 Combination Waste and Vent Systems.

910.1 Where Permitted. Combination waste and vent systems shall be permitted where structural conditions preclude the installation of conventional systems as otherwise prescribed by this code.

910.2 Approval. Construction documents for each combination waste and vent system shall first be approved by the Authority Having Jurisdiction before a portion of such system is installed.

910.3 Vents. Each combination waste and vent system, as defined in Chapter 2, shall be provided with a vent or vents adequate to ensure free circulation of air. A branch exceeding 15 feet (4572 mm) in length shall be separately vented in an approved manner. The area of a vent installed in a combination waste and vent system shall be not less than one-half the inside cross-sectional area of the drain pipe served. The vent connection shall be downstream of the uppermost fixture.

910.4 Size. Each waste pipe and each trap in such a system shall be not less than two pipe sizes exceeding the sizes required by Chapter 7 of this code, and not less than two pipe sizes exceeding a fixture tailpiece or connection.

910.5 Vertical Waste Pipe. No vertical waste pipe shall be used in such a system, except the tailpiece or connection between the outlet of a plumbing fixture and the trap. Such tailpieces or connections shall be as short as possible, and in no case shall exceed 2 feet (610 mm).

Exception: Branch lines shall be permitted to have 45 degree (0.79 rad) vertical offsets.

910.6 Cleanouts. An accessible cleanout shall be installed in each vent for the combination waste and vent system. Cleanouts shall not be required on a wet-vented branch serving a single trap where the fixture tailpiece or connection is not less than 2 inches (50 mm) in diameter and provides ready access for cleaning through the trap.

910.7 Fixtures. No water closet or urinal shall be installed on such a system. Other one, two, or three unit fixtures remotely located from the sanitary system and adjacent to a combination waste and vent system shall be permitted to be connected to such system in the conventional manner by means of waste and vent pipes of regular sizes, providing that the two pipe size increase required in Section 910.4 is based on the total fixture unit load connected to the system.

See Appendix B of this code for explanatory notes on the design of combination waste and vent systems.

»» **911.0 Circuit Venting.**

»» **911.1 Circuit Vent Permitted.** A maximum of eight fixtures connected to a horizontal branch drain shall be permitted to be circuit vented. Each fixture drain shall connect horizontally to the horizontal branch being circuit vented. The horizontal branch drain shall be classified as a vent from the most downstream fixture drain connection to the most upstream fixture drain connection to the horizontal branch.

»» **911.1.1 Multiple Circuit-Vented Branches.** Circuit-vented horizontal branch drains are permitted to be connected together. Each group of a maximum of eight fixtures shall be considered a separate circuit vent and shall be in accordance with the requirements of this section.

»» **911.2 Vent Size and Connection.** The circuit vent shall be not less than 2 inches (50 mm) in diameter and the connection shall be located between the two most upstream fixture drains. The vent shall connect to the horizontal branch on the vertical. The circuit vent pipe shall not receive the discharge of a soil or waste.

»» **911.3 Slope and Size of Horizontal Branch.** The slope of the vent section of the horizontal branch drain shall be not more than 1 inch per foot (83.3 mm/m). The entire length of the vented section of the horizontal branch drain shall be sized for the total drainage discharge to the branch.

»» **911.3.1 Size of Multiple Circuit Vent.** Multiple circuit vented branches shall be permitted to connect on the same floor level. Each separate circuit-vented horizontal branch that is interconnected shall be sized independently in accordance with Section 911.3. The downstream circuit-vented horizontal branch shall be sized for the total discharge into the branch, including the upstream branches and the fixtures within the branch.

»» **911.4 Relief Vent.** A 2 inch (50 mm) relief vent shall be provided for circuit-vented horizontal branches receiving the discharge of four or more water closets and connecting to a drainage stack that receives the discharge of soil or waste from upper horizontal branches.

»» **911.4.1 Connection and Installation.** The relief vent shall connect to the horizontal branch drain between the stack and the most downstream fixture drain of the circuit vent. The relief vent shall be installed on the vertical to the horizontal branch.

»» **911.4.2 Fixture Drain or Branch.** The relief vent is permitted to be a fixture drain or fixture branch for a fixture located within the same branch interval as the circuit-vented horizontal branch. The discharge to a relief vent shall not exceed 4 fixture units.

»» **911.5 Additional Fixtures.** Fixtures, other than the circuit-vented fixtures, are permitted to discharge to the horizontal branch drain. Such fixtures shall be located on the same floor as the circuit-vented fixtures and shall be either individually or common vented.

912.0 Engineered Vent System.

912.1 General. The design and sizing of a vent system shall be permitted to be determined by accepted engineering practices. The system shall be designed by a registered design professional and approved in accordance with Section 301.5.

912.2 Minimum Requirements. An engineered vent system shall provide protection of the trap seal in accordance with Section 901.3.

CHAPTER 10

TRAPS AND INTERCEPTORS

1001.0 General.

1001.1 Applicability. This chapter shall govern the materials, design, and installation of traps and interceptors.

- » **1001.2 Where Required.** Each plumbing fixture, shall be separately trapped by an approved type of liquid seal trap. This section shall not apply to fixtures with integral traps. Not more than one trap shall be permitted on a trap arm.
- Food waste disposers installed with a set of restaurant, commercial, or industrial sinks shall be connected to a separate trap. Each domestic clothes washer and each laundry tub shall be connected to a separate and independent trap, except that a trap serving a laundry tub shall be permitted to also receive the waste from a clothes washer set adjacent thereto. The vertical distance between a fixture outlet and the trap weir shall be as short as practicable, but in no case shall the tailpiece from a fixture exceed 24 inches (610 mm) in length. One trap shall be permitted to serve a set of not more than three single compartment sinks or laundry tubs of the same depth or three lavatories immediately adjacent to each other and in the same room where the waste outlets are not more than 30 inches (762 mm) apart and the trap is centrally located where three compartments are installed.

1002.0 Traps Protected by Vent Pipes.

1002.1 Vent Pipes. Each plumbing fixture trap, except as otherwise provided in this code, shall be protected against siphonage, backpressure, and air circulation shall be assured throughout the drainage system by means of a vent pipe installed in accordance with the requirements of this code.

1002.2 Fixture Traps. Each fixture trap shall have a protecting vent so located that the developed length of the trap arm from the trap weir to the inner edge of the vent shall be within the distance given in Table 1002.2, but in no case less than two times the diameter of the trap arm.

1002.3 Change of Direction. A trap arm shall be permitted to change direction without the use of a cleanout where such change of direction does not exceed 90 degrees (1.57 rad). Horizontal changes in direction of trap arms shall be in accordance with Section 706.3.

Exception: For trap arms 3 inches (80 mm) in diameter and larger, the change of direction shall not exceed 135 degrees (2.36 rad) without the use of a cleanout.

1002.4 Vent Pipe Opening. The vent pipe opening from a soil or waste pipe, except for water closets and similar fixtures, shall not be below the weir of the trap.

1003.0 Traps — Described.

1003.1 General Requirements. Each trap, except for traps within an interceptor or similar device shall be self cleaning. Traps for bathtubs, showers, lavatories, sinks, laundry tubs, floor drains, urinals, drinking fountains, dental units, and similar fixtures shall be of standard design, weight and shall be of ABS, cast-brass, cast-iron, lead, PP, PVC, or other approved material. An exposed and readily accessible drawn-copper alloy tubing trap, not less than 17 B & S Gauge (0.045 inch) (1.143 mm), shall be permitted to be used on fixtures discharging domestic sewage.

Exception: Drawn-copper alloy tubing traps shall not be used for urinals. Each trap shall have the manufacturer's name stamped legibly in the metal of the trap, and each tubing trap shall have the gauge of the tubing in addition to the manufacturer's name. A trap shall have a smooth and uniform interior waterway.

1003.2 Slip Joint Fittings. A maximum of one approved slip joint fitting shall be permitted to be used on the outlet side of a trap, and no tubing trap shall be installed without a listed tubing trap adapter. Listed plastic trap adapters shall be permitted to be used to connect listed metal tubing traps.

TABLE 1002.2
HORIZONTAL LENGTHS OF TRAP ARMS
(EXCEPT FOR WATER CLOSETS AND SIMILAR FIXTURES)^{1, 2}

| TRAP ARM PIPE DIAMETER (inches) | DISTANCE TRAP TO VENT MINIMUM (inches) | LENGTH MAXIMUM (inches) |
|---------------------------------|--|-------------------------|
| 1¼ | 2½ | 30 |
| 1½ | 3 | 42 |
| 2 | 4 | 60 |
| 3 | 6 | 72 |
| 4 | 8 | 120 |
| Exceeding 4 | 2 x Diameter | 120 |

For SI units: 1 inch = 25.4 mm

Notes:

¹ Maintain ¼ inch per foot slope (20.8 mm/m).

² The developed length between the trap of a water closet or similar fixture (measured from the top of the closet flange to the inner edge of the vent) and its vent shall not exceed 6 feet (1829 mm).

TRAPS AND INTERCEPTORS

1003.3 Size. The size (nominal diameter) of a trap for a given fixture shall be sufficient to drain the fixture rapidly, but in no case less than nor more than one pipe size larger than given in Table 702.1. The trap shall be the same size as the trap arm to which it is connected.

1004.0 Traps.

1004.1 Prohibited. No form of trap that depends for its seal upon the action of movable parts shall be used. No trap that has concealed interior partitions, except those of plastic, glass, or similar corrosion-resisting material, shall be used. "S" traps, bell traps, and crown-vented traps shall be prohibited. No fixture shall be double trapped. Drum and bottle traps shall be installed for special conditions. No trap shall be installed without a vent, except as otherwise provided in this code.

1004.2 Movable Parts. Bladders, check valves or other type of devices with moveable parts shall be prohibited to serve as a trap.

1005.0 Trap Seals.

1005.1 General. Each fixture trap shall have a liquid seal of not less than 2 inches (51 mm) and not more than 4 inches (102 mm), except where a deeper seal is found necessary by the Authority Having Jurisdiction. Traps shall be set true with respect to their liquid seals and, where necessary, they shall be protected from freezing.

1006.0 Floor Drain Traps.

1006.1 General. Floor drains shall connect into a trap so constructed that it can be readily cleaned and of a size to serve efficiently the purpose for which it is intended. The drain inlet shall be so located that it is in full view. Where subject to reverse flow of sewage or liquid waste, such drains shall be equipped with an approved backwater valve.

1007.0 Trap Seal Protection.

1007.1 General. Floor drain or similar traps directly connected to the drainage system and subject to infrequent use shall be protected with a trap seal primer, except where not deemed necessary for safety or sanitation by the Authority Having Jurisdiction. Trap seal primers shall be accessible for maintenance.

1008.0 Building Traps.

1008.1 General. Building traps shall not be installed except where required by the Authority Having Jurisdiction. Each building trap where installed shall be provided with a cleanout and with a relieving vent or fresh-air intake on the inlet side of the trap, which need not be larger than one-half the diameter of the drain to which it connects. Such relieving vent or fresh-air intake shall be carried above grade and terminate in a screened outlet located outside the building.

1009.0 Interceptors (Clarifiers) and Separators.

1009.1 Where Required. Interceptors (clarifiers) (including grease, oil, sand, solid interceptors, etc.) shall be required by the Authority Having Jurisdiction where they are necessary for the proper handling of liquid wastes containing grease, flammable wastes, sand, solids, acid or alkaline substances, or other ingredients harmful to the building drainage system, the public or private sewer, or to public or private sewage disposal.

1009.2 Approval. The size, type, and location of each interceptor (clarifier) or separator shall be approved by the Authority Having Jurisdiction. Except where otherwise specifically permitted, no wastes other than those requiring treatment or separation shall be discharged into an interceptor (clarifier).

1009.3 Design. Interceptors (clarifiers) for sand and similar heavy solids shall be so designed and located as to be readily accessible for cleaning and shall have a water seal of not less than 6 inches (152 mm).

1009.4 Relief Vent. Interceptors (clarifiers) shall be so designed that they will not become air-bound where closed covers are used. Each interceptor (clarifier) shall be properly vented.

1009.5 Location. Each interceptor (clarifier) cover shall be readily accessible for servicing and maintaining the interceptor (clarifier) in working and operating condition. The use of ladders or the removal of bulky equipment in order to service interceptors (clarifiers) shall constitute a violation of accessibility. Location of interceptors (clarifiers) shall be shown on the approved building plan.

1009.6 Maintenance of Interceptors. Interceptors shall be maintained in efficient operating condition by periodic removal of accumulated grease, scum, oil, or other floating substances and solids deposited in the interceptor.

1009.7 Discharge. The waste pipe from oil and sand interceptors shall discharge as approved by the Authority Having Jurisdiction.

1010.0 Slaughterhouses, Packing Establishments, etc.

1010.1 General. A fish, fowl, and animal slaughterhouse or establishment; a fish, fowl, and meat packing or curing establishment; a soap factory, tallow-rendering, fat-rendering, and a hide-curing establishment shall be connected to and shall drain or discharge into an approved grease interceptor (clarifier).

1011.0 Minimum Requirements for Auto Wash Racks.

1011.1 General. A private or public wash rack, or floor or slab used for cleaning machinery or machine parts shall be adequately protected against storm or surface water and shall drain or discharge into an approved interceptor (clarifier).

1012.0 Commercial and Industrial Laundries.

1012.1 General. Laundry equipment in commercial and industrial buildings that does not have integral strainers shall discharge into an interceptor having a wire basket or similar device that is removable for cleaning and that will prevent passage into the drainage system of solids $\frac{1}{2}$ of an inch (12.7 mm) or larger in maximum dimension, such as string, rags, buttons, or other solid materials detrimental to the public sewerage system.

1013.0 Bottling Establishments.

1013.1 General. Bottling plants shall discharge their process wastes into an interceptor that will provide for the separation of broken glass or other solids, before discharging liquid wastes into the drainage system.

1014.0 Grease Interceptors.

1014.1 General. Where it is determined by the Authority Having Jurisdiction that waste pretreatment is required, an approved type of grease interceptor(s) in accordance with ASME A112.14.3, ASME A112.14.4, CSA B481, PDI G-101, or PDI G-102, and sized in accordance with Section 1014.2.1 or Section 1014.3.6, shall be installed in accordance with the manufacturer's installation instructions to receive the drainage from fixtures or equipment that produce grease-laden waste located in areas of establishments where food is prepared, or other establishments where grease is introduced into the drainage or sewage system in quantities that can effect line stoppage or hinder sewage treatment or private sewage disposal systems. A combination of hydromechanical, gravity grease interceptors, and engineered systems shall be allowed in order to meet this code and other applicable requirements of the Authority Having Jurisdiction where space or existing physical constraints of existing buildings necessitate such installations. A grease interceptor shall not be required for individual dwelling units or for private living quarters. Water closets, urinals, and other plumbing fixtures conveying human waste shall not drain into or through the grease interceptor.

1014.1.1 Trapped and Vented. Each fixture discharging into a grease interceptor shall be individually trapped and vented in an approved manner.

1014.1.2 Maintenance. Grease interceptors shall be maintained in efficient operating condition by periodic removal of the accumulated grease and latent material. No such collected grease shall be introduced into drainage piping or a public or private sewer. Where the Authority Having Jurisdiction determines that a grease interceptor is not being properly cleaned or maintained, the Authority Having Jurisdiction shall have the authority to mandate the installation of additional equipment or devices and to mandate a maintenance program.

1014.1.3 Food Waste Disposers and Dishwashers. No food waste disposer or dishwasher shall be connected to or discharge into a grease inter-

ceptor. Commercial food waste disposers shall be permitted to discharge directly into the building's drainage system.

Exception: Food waste disposers shall be permitted to discharge to grease interceptors that are designed to receive the discharge of food waste.

1014.2 Hydromechanical Grease Interceptors.

Plumbing fixtures or equipment connected to a Type A and B hydromechanical grease interceptor shall discharge through an approved type of vented flow control installed in a readily accessible and visible location. Flow control devices shall be designed and installed so that the total flow through such device or devices shall at no time be greater than the rated flow of the connected grease interceptor. No flow control device having adjustable or removable parts shall be approved. The vented flow control device shall be located such that no system vent shall be between the flow control and the grease interceptor inlet. The vent or air inlet of the flow control device shall connect with the sanitary drainage vent system, as elsewhere required by this code, or shall terminate through the roof of the building, and shall not terminate to the free atmosphere inside the building.

Exception: Listed grease interceptors with integral flow controls or restricting devices shall be installed in an accessible location in accordance with the manufacturer's installation instructions.

1014.2.1 Capacity. The total capacity in gallons (gal) (L) of fixtures discharging into a hydromechanical grease interceptor shall not exceed two and one-half times the certified gallon per minute (gpm) (L/s) flow rate of the interceptor in accordance with Table 1014.2.1.

For the purpose of this section, the term "fixture" shall mean and include each plumbing fixture, appliance, apparatus, or other equipment required to be connected to or discharged into a grease interceptor by a provision of this section.

1014.2.2 Vent. A vent shall be installed downstream of hydromechanical grease interceptors in accordance with the requirements of this code.

1014.3 Gravity Grease Interceptors. Required gravity grease interceptors shall comply with the provisions of Section 1014.3.1 through Section 1014.3.7.

1014.3.1 General. The provisions of this section shall apply to the design, construction, installation, and testing of commercial kitchen gravity grease interceptors.

1014.3.2 Waste Discharge Requirements. Waste discharge in establishments from fixtures and equipment which contain grease, including but not limited to, scullery sinks, pot and pan sinks, dishwashers, soup kettles, and floor drains located in areas where grease-containing materials exist, shall be permitted to be drained into the sanitary waste through the interceptor where approved by the Authority Having Jurisdiction.

TRAPS AND INTERCEPTORS

TABLE 1014.2.1
HYDROMECHANICAL GREASE INTERCEPTOR SIZING USING GRAVITY FLOW RATES¹

| DIAMETER OF GREASE WASTE PIPE (inches) | MAXIMUM FULL PIPE FLOW (gpm) ² | SIZE OF GREASE INTERCEPTOR | |
|---|---|-------------------------------------|-------------------------------------|
| | | ONE-MINUTE DRAINAGE PERIOD (gpm) | TWO-MINUTE DRAINAGE PERIOD (gpm) |
| 2 | 20 | 20 | 10 |
| 3 | 60 | 75 | 35 |
| 4 | 125 | 150 | 75 |
| 5 | 230 | 250 | 125 |
| 6 | 375 | 500 | 250 |

For SI units: 1 inch = 25 mm, 1 gallon per minute = 0.06 L/s

Notes:

¹ For interceptor sizing by fixture capacity see the example below.

² ¼ inch slope per foot (20.8 mm/m) based on Manning's formula with friction factor N = .012.

EXAMPLE 1014.2.1
SIZING HYDROMECHANICAL GREASE INTERCEPTOR(S) USING FIXTURE CAPACITY

Step 1: Determine the flow rate from each fixture.

[Length] X [Width] X [Depth] / [231] = Gallons X [.75 fill factor] / [Drain Period (1 minute or 2 minutes)]

Step 2: Calculate the total load from fixtures that discharge into the interceptor.

| FIXTURES | COMPARTMENTS | LOAD (gallons) | SIZE OF GREASE INTERCEPTOR ONE- MINUTE DRAINAGE PERIOD (gpm) | TWO-MINUTE DRAINAGE PERIOD (gpm) |
|-----------------------------------|--------------|----------------|---|-------------------------------------|
| Compartment size | — | — | — | — |
| 24 inches x 24 inches x 12 inches | 2 | 44.9 | — | — |
| Hydrant | — | 3 | — | — |
| Rated Appliance | — | 2 | — | — |
| — | — | 49.9 | 50 | 25 |

For SI units: 1 inch = 25.4 mm, 1 gallon per minute = 0.06 L/s, 1 gallon = 3.785 L

1014.3.2.1 Toilets and Urinals. Toilets, urinals, and other similar fixtures shall not drain through the interceptor.

1014.3.2.2 Inlet Pipe. Waste shall enter the interceptor through the inlet pipe.

1014.3.3 Design. Gravity interceptors shall be constructed in accordance with the applicable standard in Table 1701.1 or the design approved by the Authority Having Jurisdiction.

1014.3.4 Location. Each grease interceptor shall be so installed and connected that it shall be easily accessible for inspection, cleaning, and removal of the intercepted grease. A gravity grease interceptor in accordance with IAPMO Z1001, shall not be installed in a building where food is handled. Location of the grease interceptor shall meet the approval of the Authority Having Jurisdiction.

1014.3.4.1 Interceptors. Interceptors shall be placed as close as practical to the fixtures they serve.

1014.3.4.2 Business Establishment. Each business establishment for which a gravity grease interceptor is required shall have an interceptor which shall serve that establishment unless otherwise approved by the Authority Having Jurisdiction.

1014.3.4.3 Access. Each gravity grease interceptor shall be located so as to be readily accessible to the equipment required for maintenance.

1014.3.5 Construction Requirements. Gravity grease interceptors shall be designed to remove grease from effluent and shall be sized in accordance with this section. Gravity grease interceptors shall also be designed to retain grease until accumulations can be removed by pumping the interceptor. It is recommended that a sample box be located at the outlet end of gravity grease interceptors so that the Authority Having Jurisdiction can periodically sample effluent quality.

1014.3.6 Sizing Criteria. The volume of the interceptor shall be determined by using Table 1014.3.6. Where drainage fixture units (DFUs) are not known, the interceptor shall be sized based on the maximum DFUs allowed for the pipe size connected to the inlet of the interceptor. Refer to Table 703.2, Drainage Piping, Horizontal.

1014.3.7 Abandoned Gravity Grease Interceptors. Abandoned grease interceptors shall be pumped and filled as required for abandoned sewers and sewage disposal facilities in Section 722.0.

TABLE 1014.3.6
GRAVITY GREASE INTERCEPTOR SIZING

| DRAINAGE FIXTURE UNITS ^{1,3} (DFUs) | INTERCEPTOR VOLUME ² (gallons) |
|---|--|
| 8 | 500 |
| 21 | 750 |
| 35 | 1000 |
| 90 | 1250 |
| 172 | 1500 |
| 216 | 2000 |
| 307 | 2500 |
| 342 | 3000 |
| 428 | 4000 |
| 576 | 5000 |
| 720 | 7500 |
| 2112 | 10 000 |
| 2640 | 15 000 |

For SI units: 1 gallon = 3.785 L

Notes:

- ¹ The maximum allowable DFUs plumbed to the kitchen drain lines that will be connected to the grease interceptor.
- ² This size is based on: DFUs, the pipe size from this code; Table 703.2; Useful Tables for flow in half-full pipes (ref: Mohinder Nayyar Piping Handbook, 3rd Edition, 1992). Based on 30-minute retention time (ref.: George Tchobanoglous and Metcalf & Eddy. Wastewater Engineering Treatment, Disposal and Reuse, 3rd Ed. 1991 & Ronald Crites and George Tchobanoglous. Small and Decentralized Wastewater Management Systems, 1998). Rounded up to nominal interceptor volume.
- ³ Where the flow rate of directly connected fixture(s) or appliance(s) have no assigned DFU values, the additional grease interceptor volume shall be based on the known flow rate (gpm) (L/s) multiplied by 30 minutes.

1015.0 FOG (Fats, Oils, and Greases) Disposal System.

1015.1 Purpose. The purpose of this section is to provide the necessary criteria for the sizing, application, and installation of FOG disposal systems designated as a pretreatment or discharge water quality compliance strategy.

➤ **1015.2 Components, Materials, and Equipment.** FOG disposal systems, including components, materials, and equipment necessary for the proper function of the system, shall be in accordance with ASME A112.14.6.

➤ **1015.3 Sizing and Installation.** FOG disposal systems shall be sized and installed in accordance with the manufacturer's installation instructions.

➤ **1015.4 Performance.** FOG disposal systems shall produce an effluent quality not to exceed 5.84 grains per gallon (gr/gal) (100 mg/L) FOG in accordance with ASME A112.14.6.

EXAMPLE 1014.3.6

GRAVITY GREASE INTERCEPTOR SIZING EXAMPLE

Given: A restaurant with the following fixtures and equipment.

One food preparation sink; three floor drains - one in the food prep area, one in the grill area, and one receiving the indirect waste from the ice machine and a mop sink.

Kitchen Drain Line DFU Count (from Table 702.1):

| | |
|-------------------------------|------------------|
| 3 floor drains at 2 DFUs each | = 6 DFUs |
| Mop sink at 3 DFUs each | = 3 DFUs |
| Food prep sink at 3 DFUs each | = 3 DFUs |
| Total | = 12 DFUs |

Using Table 1014.3.6, the grease interceptor will be sized at 750 gallons (2389 L).

1016.0 Sand Interceptors.

1016.1 Discharge. Where the discharge of a fixture or drain contain solids or semi-solids heavier than water that would be harmful to a drainage system or cause a stoppage within the system, the discharge shall be through a sand interceptor. Multiple floor drains shall be permitted to discharge into one sand interceptor.

1016.2 Authority Having Jurisdiction. Sand interceptors are required where the Authority Having Jurisdiction deems it advisable to have a sand interceptor to protect the drainage system.

1016.3 Construction and Size. Sand interceptors shall be built of brick or concrete, prefabricated coated steel, or other watertight material. The interceptor shall have an interior baffle for full separation of the interceptor into two sections. The outlet pipe shall be the same size as the inlet pipe of the sand interceptor, the minimum being 3 inches (80 mm), and the baffle shall have two openings of the same diameter as the outlet pipe and at the same invert as the outlet pipe. These openings shall be staggered so that there cannot be a straight line flow between the inlet pipe and the outlet pipe. The invert of the inlet pipe shall be no lower than the invert of the outlet pipe.

The sand interceptor shall have a minimum dimension of 2 square feet (0.2 m²) for the net free opening of the inlet section and a minimum depth under the invert of the outlet pipe of 2 feet (610 mm).

For each 5 gpm (0.3 L/s) flow or fraction thereof over 20 gpm (1.26 L/s), the area of the sand interceptor inlet section is to be increased by 1 square foot (0.09 m²). The outlet section shall at all times have a minimum area of 50 percent of the inlet section.

The outlet section shall be covered by a solid removable cover, set flush with the finished floor, and the inlet section shall have an open grating, set flush with the finished floor and suitable for the traffic in the area in which it is located.

1016.4 Separate Use. Sand and similar interceptors for every solid shall be so designed and located as to be readily accessible for cleaning, shall have a water seal of not less than 6 inches (152 mm), and shall be vented.

1017.0 Oil and Flammable Liquid Interceptors.

1017.1 Interceptors Required. Repair garages and gasoline stations with grease racks or grease pits, and factories that have oily, flammable, or both types of wastes as a result of manufacturing, storage, maintenance, repair, or testing processes, shall be provided with an oil or flammable liquid interceptor that shall be connected to necessary floor drains. The separation or vapor compartment shall be independently vented to the outer air. Where two or more separation or vapor compartments are used, each shall be vented to the outer air or shall be permitted to connect to a header that is installed at a minimum of 6 inches (152 mm) above the spill line of the lowest floor drain and vented independently to the outer air. The minimum size of a flammable vapor vent shall be not less than 2 inches (50 mm), and, where vented through a sidewall, the vent shall be not less than 10 feet (3048 mm) above the adjacent level at an approved location. The interceptor shall be vented on the sewer side and shall not connect to a flammable vapor vent. Oil and flammable interceptors shall be provided with gastight cleanout covers that shall be readily accessible. The waste line shall be not less than 3 inches (80 mm) in diameter with a full-size cleanout to grade. Where an interceptor is provided with an overflow, it shall be provided with an overflow line [not less than 2 inches (50 mm) in diameter] to an approved waste oil tank having a minimum capacity of 550 gallons (2082 L) and meeting the requirements of the Authority Having Jurisdiction. The waste oil from the separator shall flow by gravity or shall be pumped to a higher elevation by an automatic pump. Pumps shall be adequately sized and accessible. Waste oil tanks shall have a 2 inch (50 mm) minimum pump-out connection at grade and a 1½ inch (40 mm) minimum vent to atmosphere at an approved location not less than 10 feet (3048 mm) above grade.

1017.2 Design of Interceptors. Each manufactured interceptor that is rated shall be stamped or labeled by the manufacturer with an indication of its full discharge rate in gpm (L/s). The full discharge rate to such an interceptor shall be determined at full flow. Each interceptor shall be rated equal to or greater than the incoming flow and shall be provided with an overflow line to an underground tank.

Interceptors not rated by the manufacturer shall have a depth of not less than 2 feet (610 mm) below the invert of the discharge drain. The outlet opening shall have not less than an 18 inch (457 mm) water seal and shall have a minimum capacity as follows: Where not more than three motor vehicles are serviced, stored, or both, interceptors shall have a minimum capacity of 6 cubic feet (0.2 m³), and 1 cubic foot (0.03 m³) of capacity shall be added for each vehicle up to 10 vehicles. Above 10 vehicles, the Authority

Having Jurisdiction shall determine the size of the interceptor required. Where vehicles are serviced and not stored, interceptor capacity shall be based on a net capacity of 1 cubic foot (0.03 m³) for each 100 square feet (9.29 m²) of surface to be drained into the interceptor, with a minimum of 6 cubic feet (0.2 m³).

CHAPTER 11

STORM DRAINAGE

1101.0 General.

1101.1 Applicability. This chapter shall govern the materials, design, and installation of storm water drainage systems.

» **1101.2 Where Required.** Roofs, paved areas, yards, courts, courtyards, vent shafts, light wells, or similar areas having rainwater, shall be drained into a separate storm sewer system, or into a combined sewer system where a separate storm sewer system is not available, or to some other place of disposal satisfactory to the Authority Having Jurisdiction. In the case of one- and two-family dwellings, storm water shall be permitted to be discharged on flat areas, such as streets or lawns, so long as the storm water shall flow away from the building and away from adjoining property, and shall not create a nuisance.

» **1101.3 Storm Water Drainage to Sanitary Sewer Prohibited.** Storm water shall not be drained into sewers intended for sanitary drainage.

» **1101.4 Material Uses.** Pipe, tube, and fittings conveying rainwater shall be of such materials and design as to perform their intended function to the satisfaction of the Authority Having Jurisdiction. Conductors within a vent or shaft shall be of cast-iron, galvanized steel, wrought iron, copper, copper alloy, lead, Schedule 40 ABS DWV, Schedule 40 PVC DWV, stainless steel 304 or 316L [stainless steel 304 pipe and fittings shall not be installed underground and shall be kept not less than 6 inches (152 mm) aboveground], or other approved materials, and changes in direction shall be in accordance with the requirements of Section 706.0. ABS and PVC DWV piping installations shall be installed in accordance with Chapter 14 "Firestop Protection." Except for individual single-family dwelling units, materials exposed within ducts or plenums shall have a flame-spread index of not more than 25 and a smoke developed index of not more than 50, where tested in accordance with ASTM E84 or UL 723.

» **1101.4.1 Copper and Copper Alloys.** Joints and connections in copper and copper alloy pipe and tube shall be installed in accordance with Section 705.3.

» **1101.4.2 Conductors.** Conductors installed aboveground in buildings shall be in accordance with the applicable standards referenced in Table 701.2 for aboveground drain, waste, and vent pipe. Conductors installed aboveground level shall be of seamless copper water tube, Type K, L, or M; Schedule 40 copper pipe or Schedule 40 copper alloy pipe; Type DWV copper drainage tube; service weight cast-iron soil pipe or hubless cast-iron soil pipe; standard weight galvanized steel pipe; stainless steel 304 or 316L [stainless steel 304 pipe and fittings shall not be installed underground and shall be kept not less than 6 inches (152 mm) aboveground]; or Schedule 40 ABS or Schedule 40 PVC plastic pipe.

1101.4.3 Leaders. Leaders installed outside shall be in accordance with the applicable standards referenced in Table 701.2 for aboveground drain, waste, and vent pipe; aluminum sheet metal; galvanized steel sheet metal; or copper sheet metal.

1101.4.4 Underground Building Storm Drains. Underground building storm drains shall comply with the applicable standards referenced in Table 701.2 for underground drain, waste, and vent pipe.

1101.4.5 Building Storm Sewers. Building storm sewers shall comply with the applicable standards referenced in Table 701.2 for building sewer pipe.

1101.4.6 Subsoil Drains. Subsoil drains shall be open jointed, perforated, or both and constructed of materials in accordance with Table 1101.4.6.

TABLE 1101.4.6
MATERIALS FOR SUBSOIL DRAIN PIPE AND FITTINGS

| MATERIAL | REFERENCED STANDARD(S) |
|---------------------------------|------------------------|
| PE | ASTM F405 |
| PVC | ASTM D2729 |
| Vitrified Clay (Extra strength) | ASTM C4, ASTM C700 |

1101.5 Expansion Joints Required. Expansion joints or sleeves shall be provided where warranted by temperature variations or physical conditions.

1101.6 Subsoil Drains. Subsoil drains shall be provided around the perimeter of buildings having basements, cellars, crawl spaces, or floors below grade. Such subsoil drains shall be permitted to be positioned inside or outside of the footing, shall be of perforated or open-jointed approved drain tile or pipe, not less than 3 inches (80 mm) in diameter, and shall be laid in gravel, slag, crushed rock, approved $\frac{3}{4}$ of an inch (19.1 mm) crushed, recycled glass aggregate, or other approved porous material with not less than 4 inches (102 mm) surrounding the pipe. Filter media shall be provided for exterior subsoil piping.

1101.6.1 Discharge. Subsoil drains shall be piped to a storm drain, to an approved water course, to the front street curb or gutter, to an alley, or the discharge from the subsoil drains shall be conveyed to the alley by a concrete gutter. Where a continuously flowing spring or groundwater is encountered, subsoil drains shall be piped to a storm drain or an approved water course.

1101.6.2 Sump. Where it is not possible to convey the drainage by gravity, subsoil drains shall discharge to an accessible sump provided with an approved automatic electric pump. The sump shall be not less than 15 inches (381 mm) in diameter, 18 inches (457 mm) in depth, and provided with a fitted cover. The sump pump shall have an adequate capacity to discharge

STORM DRAINAGE

water coming into the sump as it accumulates to the required discharge point, and the capacity of the pump shall be not less than 15 gallons per minute (gpm) (0.95 L/s). The discharge piping from the sump pump shall be not less than 1½ inches (40 mm) in diameter and have a union or other approved quick-disconnect assembly to make the pump accessible for servicing.

- » **1101.6.3 Splash Blocks.** For separate dwellings not serving continuously flowing springs or groundwater, the sump discharge pipe shall be permitted to discharge onto a concrete splash block with a minimum length of 24 inches (610 mm). This pipe shall be within 4 inches (102 mm) of the splash block and positioned to direct the flow parallel to the recessed line of the splash block.
- » **1101.6.4 Backwater Valve.** Subsoil drains subject to backflow where discharging into a storm drain shall be provided with a backwater valve in the drain line so located as to be accessible for inspection and maintenance.
- » **1101.6.5 Open Area.** Nothing in Section 1101.6 shall prevent drains that serve either subsoil drains or areaways of a detached building from discharging to a properly graded open area, provided that:
 - (1) They do not serve continuously flowing springs or groundwater.
 - (2) The point of discharge is not less than 10 feet (3048 mm) from a property line.
 - (3) It is impracticable to discharge such drains to a storm drain, to an approved water course, to the front street curb or gutter, or to an alley.
- » **1101.7 Building Subdrains.** Building subdrains located below the public sewer level shall discharge into a sump or receiving tank, the contents of which shall be automatically lifted and discharged into the drainage system as required for building sumps.
- » **1101.8 Areaway Drains.** Open subsurface space adjacent to a building, serving as an entrance to the basement or cellar of a building, shall be provided with a drain or drains. Such areaway drains shall be not less than 2 inches (50 mm) in diameter for areaways at a maximum of 100 square feet (9.29 m²) in area, and shall be discharged in the manner provided for subsoil drains not serving continuously flowing springs or groundwater (see Section 1101.6.1). Areaways in excess of 100 square feet (9.29 m²) shall not drain into subsoil drains. Areaway drains for areaways exceeding 100 square feet (9.29 m²) shall be sized in accordance with Table 1101.8.
- » **1101.9 Window Areaway Drains.** Window areaways at a maximum of 10 square feet (0.93 m²) in area shall be permitted to discharge to the subsoil drains through a 2 inch (50 mm) pipe. However, window areaways exceeding 10 square feet (0.93 m²) in area shall be handled in the manner provided for entrance areaways (see Section 1101.8).
- » **1101.10 Filling Stations and Motor Vehicle Washing Establishments.** Public filling stations and motor vehicle washing establishments shall have the paved

area sloped toward sumps or gratings within the property lines. Curbs not less than 6 inches (152 mm) high shall be placed where required to direct water to gratings or sumps.

1101.11 Paved Areas. Where the occupant creates surface water drainage, the sumps, gratings, or floor drains shall be piped to a storm drain or an approved water course. «

1101.12 Roof Drainage. Roof drainage shall comply with Section 1101.12.1 and Section 1101.12.2. «

1101.12.1 Primary Roof Drainage. Roof areas of a building shall be drained by roof drains or gutters. The location and sizing of drains and gutters shall be coordinated with the structural design and pitch of the roof. Unless otherwise required by the Authority Having Jurisdiction, roof drains, gutters, vertical conductors or leaders, and horizontal storm drains for primary drainage shall be sized based on a storm of 60 minutes duration and 100 year return period. Refer to Table D 101.1 (in Appendix D) for 100 year, 60 minute storms at various locations. «

1101.12.2 Secondary Drainage. Secondary (emergency) roof drainage shall be provided by one of the methods specified in Section 1101.12.2.1 or Section 1101.12.2.2. «

1101.12.2.1 Roof Scuppers or Open Side. Secondary roof drainage shall be provided by an open-sided roof or scuppers where the roof perimeter construction extends above the roof in such a manner that water will be entrapped. An open-sided roof or scuppers shall be sized to prevent the depth of ponding water from exceeding that for which the roof was designed as determined by Section 1101.12.1. Scupper openings shall be not less than 4 inches (102 mm) high and have a width equal to the circumference of the roof drain required for the area served, sized in accordance with Table 1101.12. «

1101.12.2.2 Secondary Roof Drain. Secondary roof drains shall be provided. The secondary roof drains shall be located not less than 2 inches (51 mm) above the roof surface. The maximum height of the roof drains shall be a height to prevent the depth of ponding water from exceeding that for which the roof was designed as determined by Section 1101.12.1. The secondary roof drains shall connect to a piping system in accordance with Section 1101.12.2.2.1 or Section 1101.12.2.2.2. «

1101.12.2.2.1 Separate Piping System. The secondary roof drainage system shall be a separate system of piping, independent of the primary roof drainage system. The discharge shall be above grade, in a location observable by the building occupants or maintenance personnel. Secondary roof drain systems shall be sized in accordance with Section 1101.12.1 based on the rainfall rate for which the primary system is sized. «

- » **1101.12.2.2.2 Combined System.** The secondary roof drains shall connect to the vertical piping of the primary storm drainage conductor downstream of the last horizontal offset located below the roof. The primary storm drainage system shall connect to the building storm water that connects to an underground public storm sewer. The combined secondary and primary roof drain systems shall be sized in accordance with Section 1103.0 based on double the rainfall rate for the local area.
- » **1101.13 Cleanouts.** Cleanouts for building storm drains shall comply with the requirements of Section 719.0 of this code.
- » **1101.13.1 Rain Leaders and Conductors.** Rain leaders and conductors connected to a building storm sewer shall have a cleanout installed at the base of the outside leader or outside conductor before it connects to the horizontal drain.
- » **1101.14 Rainwater Sumps.** Rainwater sumps serving "public use" occupancy buildings shall be provided with dual pumps arranged to function alternately in case of overload or mechanical failure. Pumps rated 600 V or less shall comply with UL 778 and shall be installed in accordance with the manufacturer's installation instructions.
- » **1101.15 Traps on Storm Drains and Leaders.** Leaders and storm drains, where connected to a combined sewer, shall be trapped. Floor and area drains connected to a storm drain shall be trapped.
- Exception:** Traps shall not be required where roof drains, rain leaders, and other inlets are at locations allowed under Section 906.0, Vent Termination.
- » **1101.15.1 Where Not Required.** No trap shall be required for leaders or conductors that are connected to a sewer carrying storm water exclusively.
- » **1101.15.2 Trap Size.** Traps, where installed for individual conductors, shall be the same size as the horizontal drain to which they are connected.
- » **1101.15.3 Method of Installation of Combined Sewer.** Individual storm-water traps shall be installed on the stormwater drain branch serving each storm-water inlet, or a single trap shall be installed in the main storm drain just before its connection with the combined building sewer. Such traps shall be provided with an accessible cleanout on the outlet side of the trap.
- » **1101.16 Leaders, Conductors, and Connections.** Leaders or conductors shall not be used as soil, waste, or vent pipes nor shall soil, waste, or vent pipes be used as leaders or conductors.
- » **1101.16.1 Protection of Leaders.** Leaders installed along alleyways, driveways, or other locations where exposed to damage shall be protected by metal guards, recessed into the wall, or constructed from ferrous pipe.
- 1101.16.2 Combining Storm with Sanitary Drainage.** The sanitary and storm drainage system of a building shall be entirely separate, except where a combined sewer is used, in which case the building storm drain shall be connected in the same horizontal plane through a single wye fitting to the combined building sewer not less than 10 feet (3048 mm) downstream from a soil stack.
- 1102.0 Roof Drains.**
- 1102.1 Applications.** Roof drains shall be constructed of aluminum, cast-iron, copper alloy of not more than 15 percent zinc, leaded nickel bronze, stainless steel, ABS, PVC, polypropylene, polyethylene, or nylon and shall comply with ASME A112.3.1 or ASME A112.6.4.
- 1102.2 Dome Strainers Required.** Roof drains shall have domed strainers.
- Exception:** Roof drain strainers for use on sun decks, parking decks, and similar areas that are normally serviced and maintained, shall be permitted to be of the flat surface type. Such roof drain strainers shall be level with the deck.
- 1102.3 Roof Drain Flashings.** Connection between the roof and roof drains that pass through the roof and into the interior of the building shall be made watertight by the use of proper flashing material.
- 1102.3.1 Lead Flashing.** Where lead flashing material is used, it shall be not less than 4 pounds per square foot (lb/ft²) (19 kg/m²).
- 1102.3.2 Copper Flashing.** Where copper flashing material is used, it shall be not less than 12 ounces per square foot (oz/ft²) (3.7 kg/m²).
- 1103.0 Size of Leaders, Conductors, and Storm Drains.**
- 1103.1 Vertical Conductors and Leaders.** Vertical conductors and leaders shall be sized on the basis of the maximum projected roof area and Table 1101.12.
- 1103.2 Size of Horizontal Storm Drains and Sewers.** The size of building storm drains or building storm sewers or their horizontal branches shall be based upon the maximum projected roof or paved area to be handled and Table 1101.8.
- 1103.3 Size of Roof Gutters.** The size of semi-circular gutters shall be based on the maximum projected roof area and Table 1103.3.
- 1103.4 Side Walls Draining onto a Roof.** Where vertical walls project above a roof so as to permit storm water to drain to the roof area below, the adjacent roof area shall be permitted to be computed from Table 1101.12 as follows:
- (1) For one wall – add 50 percent of the wall area to the roof area figures.
 - (2) For two adjacent walls of equal height – add 35 percent of the total wall areas.

STORM DRAINAGE

- (3) For two adjacent walls of unequal height – add 35 percent of the total common height and add 50 percent of the remaining height of the highest wall.
- (4) Two opposite walls of same height – add no additional area.
- (5) Two opposite walls of differing heights – add 50 percent of the wall area above the top of lower wall.
- (6) Walls on three sides – add 50 percent of the area of the inner wall below the top of the lowest wall, plus allowance for the area of the wall above the top of the lowest wall, in accordance with Section 1103.4(3) and Section 1103.4(5) above.
- (7) Walls on four sides – no allowance for wall areas below the top of the lowest wall – add for areas above the top of the lowest wall in accordance with Section 1103.4(1), Section 1103.4(3), Section 1103.4(5), and Section 1103.4(6) above.

» 1104.0 Values for Continuous Flow.

» **1104.1 General.** Where there is a continuous or semi-continuous discharge into the building storm drain or building storm sewer, as from a pump, ejector, air-conditioning plant, or similar device, 1 gpm (0.06 L/s) of such discharge shall be computed as being equivalent to 24 square feet (2.2 m²) of roof area, based upon a rate of rainfall of 4 inches per hour (in/h) (102 mm/h).

» 1105.0 Controlled-Flow Roof Drainage.

» **1105.1 Application.** In lieu of sizing the storm drainage system in accordance with Section 1103.0, the roof drainage shall be permitted to be sized on the basis of controlled flow and storage of the storm water on the roof, provided the following conditions are met:

- (1) The water from a 25 year-frequency storm shall not be stored on the roof exceeding 24 hours.
- (2) During the storm, the water depth on the roof shall not exceed the depths specified in Table 1105.1(1).
- (3) Not less than two drains shall be installed in roof areas of 10 000 square feet (929 m²) or less, and not less than one additional drain shall be installed for each 10 000 square feet (929 m²) of roof area exceeding 10 000 square feet (929 m²).
- (4) Each roof drain shall have a precalibrated, fixed (nonadjustable), and proportional weir (notched) in a standing water collar inside the strainer. No mechanical devices or valves shall be allowed.
- (5) Pipe sizing shall be based on the pre-calibrated rate of flow (gpm) (L/s) of the pre-calibrated weir for the maximum allowable water depth, and Table 1101.8 and Table 1101.12.
- (6) The height of stones or other granular material above the waterproofed surface shall not be considered in water depth measurement, and the roof surface in the vicinity of the drain shall not be recessed to create a reservoir.

- (7) Roof design, where controlled-flow roof drainage is used, shall be such that the design roof live load is not less than 30 lb/ft² (146 kg/m²) to provide a safety factor exceeding the 15 lb/ft² (73 kg/m²) represented by the depth of water stored on the roof in accordance with Table 1105.1(1).
- (8) Scuppers shall be provided in parapet walls. The distance of scupper bottoms above the roof level at the drains shall not exceed the maximum distances specified in Table 1105.1(2).
- (9) Scupper openings shall be not less than 4 inches (102 mm) high and have a width equal to the circumference of the roof drain required for the area served, sized in accordance with Table 1101.12.
- (10) Flashings shall extend above the top of the scuppers.
- (11) At a wall or parapet, 45 degree (0.79 rad) cants shall be installed.
- (12) Separate storm and sanitary drainage systems shall be provided within the building.
- (13) Calculations for the roof drainage system shall be submitted along with the plans to the Authority Having Jurisdiction for approval.

TABLE 1105.1(1)
CONTROLLED-FLOW MAXIMUM ROOF WATER DEPTH

| ROOF RISE* (inches) | MAXIMUM WATER DEPTH AT DRAIN (inches) |
|------------------------|---|
| Flat | 3 |
| 2 | 4 |
| 4 | 5 |
| 6 | 6 |

For SI units: 1 inch = 25.4 mm

* Vertical measurement from the roof surface at the drain to the highest point of the roof surface served by the drain, ignoring a local depression immediately adjacent to the drain.

TABLE 1105.1(2)
DISTANCE OF SCUPPER BOTTOMS ABOVE ROOF

| ROOF RISE* (inches) | ABOVE ROOF LEVEL AT DRAIN (inches) |
|------------------------|--|
| Flat | 3 |
| 2 | 4 |
| 4 | 5 |
| 6 | 6 |

For SI units: 1 inch = 25.4 mm

* Vertical measurement from the roof surface at the drain to the highest point of the roof surface served by the drain, ignoring a local depression immediately adjacent to the drain.

1105.2 Setback Roofs. Drains on setback roofs shall be permitted to be connected to the controlled-flow drainage systems provided:

- (1) The setback is designed for storing water, or
- (2) The square footage of the setback drainage area is converted as outlined in Section 1105.0 to gpm, and the storm-water pipe sizes in the controlled-flow system are based on the sum of the loads.

- (3) The branch from each of the roof drains that are not provided with controlled flow shall be sized in accordance with Table 1101.12.

» **1106.0 Testing.**

- » **1106.1 Testing Required.** New building storm drainage systems and parts of existing systems that have been altered, extended, or repaired shall be tested in accordance with Section 1106.2.1 or Section 1106.2.2 to disclose leaks and defects.

- » **1106.2 Methods of Testing Storm Drainage Systems.** Except for outside leaders and perforated or open-jointed drain tile, the piping of storm drain systems shall be tested upon completion of the rough piping installation by water or air, except that plastic pipe shall not be tested with air, and proved tight. The Authority Having Jurisdiction shall be permitted to require the removal of cleanout plugs to ascertain whether the pressure has reached parts of the system. One of the following test methods shall be used in accordance with Section 1106.2.1 through Section 1106.2.3.

- » **1106.2.1 Water Test.** After piping has been installed, the water test shall be applied to the drainage system, either to the entire system or to sections. Where the test is applied to the entire system, all openings in the piping shall be tightly closed except for the highest opening, and the system shall be filled with water to the point of overflow. Where the system is tested in sections, each opening shall be tightly plugged except for the highest opening of the section under test, and each section shall be filled with water, but no section shall be tested with less than a 10 foot (3048 mm) head of water. In testing successive sections, not less than the upper 10 feet (3048 mm) of the next preceding section shall be tested so that no joint of pipe in the building except the uppermost 10 feet (3048 mm) of a roof drainage system, which shall be filled with water to the flood level of the uppermost roof drain, shall have been submitted to a test of less than 10 foot (3048 mm) head of water. The water shall be kept in the system or in the portion under test for not less than 15 minutes before inspection starts; the system shall then be tight.

- » **1106.2.2 Air Test.** The air test shall be made by attaching an air compressor testing apparatus to a suitable opening after closing other inlets and outlets to the system, forcing air into the system until there is a uniform gauge pressure of 5 pounds-force per square inch (psi) (34 kPa) or sufficient pressure to balance a column of mercury 10 inches (34 kPa) in height. This pressure shall be held without introduction of additional air for a period of not less than 15 minutes.

- » **1106.2.3 Exceptions.** Where circumstances exist that make air and water tests described in Section 1106.2.1 and Section 1106.2.2 impractical, see Section 105.3.

TABLE 1101.8
SIZING OF HORIZONTAL RAINWATER PIPING^{1, 2}

| SIZE OF PIPE | FLOW ($\frac{1}{8}$ inch per foot slope) | MAXIMUM ALLOWABLE HORIZONTAL PROJECTED ROOF AREAS AT VARIOUS RAINFALL RATES (square feet) | | | | | |
|--------------|---|---|----------|----------|----------|----------|----------|
| | | 1 (in/h) | 2 (in/h) | 3 (in/h) | 4 (in/h) | 5 (in/h) | 6 (in/h) |
| inches | gpm | | | | | | |
| 3 | 34 | 3288 | 1644 | 1096 | 822 | 657 | 548 |
| 4 | 78 | 7520 | 3760 | 2506 | 1880 | 1504 | 1253 |
| 5 | 139 | 13 360 | 6680 | 4453 | 3340 | 2672 | 2227 |
| 6 | 222 | 21 400 | 10 700 | 7133 | 5350 | 4280 | 3566 |
| 8 | 478 | 46 000 | 23 000 | 15 330 | 11 500 | 9200 | 7670 |
| 10 | 860 | 82 800 | 41 400 | 27 600 | 20 700 | 16 580 | 13 800 |
| 12 | 1384 | 133 200 | 66 600 | 44 400 | 33 300 | 26 650 | 22 200 |
| 15 | 2473 | 238 000 | 119 000 | 79 333 | 59 500 | 47 600 | 39 650 |

| SIZE OF PIPE | FLOW ($\frac{1}{4}$ inch per foot slope) | MAXIMUM ALLOWABLE HORIZONTAL PROJECTED ROOF AREAS AT VARIOUS RAINFALL RATES (square feet) | | | | | |
|--------------|---|---|----------|----------|----------|----------|----------|
| | | 1 (in/h) | 2 (in/h) | 3 (in/h) | 4 (in/h) | 5 (in/h) | 6 (in/h) |
| inches | gpm | | | | | | |
| 3 | 48 | 4640 | 2320 | 1546 | 1160 | 928 | 773 |
| 4 | 110 | 10 600 | 5300 | 3533 | 2650 | 2120 | 1766 |
| 5 | 196 | 18 880 | 9440 | 6293 | 4720 | 3776 | 3146 |
| 6 | 314 | 30 200 | 15 100 | 10 066 | 7550 | 6040 | 5033 |
| 8 | 677 | 65 200 | 32 600 | 21 733 | 16 300 | 13 040 | 10 866 |
| 10 | 1214 | 116 800 | 58 400 | 38 950 | 29 200 | 23 350 | 19 450 |
| 12 | 1953 | 188 000 | 94 000 | 62 600 | 47 000 | 37 600 | 31 350 |
| 15 | 3491 | 336 000 | 168 000 | 112 000 | 84 000 | 67 250 | 56 000 |

| SIZE OF PIPE | FLOW ($\frac{1}{2}$ inch per foot slope) | MAXIMUM ALLOWABLE HORIZONTAL PROJECTED ROOF AREAS AT VARIOUS RAINFALL RATES (square feet) | | | | | |
|--------------|---|---|----------|----------|----------|----------|----------|
| | | 1 (in/h) | 2 (in/h) | 3 (in/h) | 4 (in/h) | 5 (in/h) | 6 (in/h) |
| inches | gpm | | | | | | |
| 3 | 68 | 6576 | 3288 | 2192 | 1644 | 1310 | 1096 |
| 4 | 156 | 15 040 | 7520 | 5010 | 3760 | 3010 | 2500 |
| 5 | 278 | 26 720 | 13 360 | 8900 | 6680 | 5320 | 4450 |
| 6 | 445 | 42 800 | 21 400 | 14 267 | 10 700 | 8580 | 7140 |
| 8 | 956 | 92 000 | 46 000 | 30 650 | 23 000 | 18 400 | 15 320 |
| 10 | 1721 | 165 600 | 82 800 | 55 200 | 41 400 | 33 150 | 27 600 |
| 12 | 2768 | 266 400 | 133 200 | 88 800 | 66 600 | 53 200 | 44 400 |
| 15 | 4946 | 476 000 | 238 000 | 158 700 | 119 000 | 95 200 | 79 300 |

For SI units: 1 inch = 25 mm, 1 gallon per minute = 0.06 L/s, $\frac{1}{8}$ inch per foot = 10.4 mm/m, 1 inch per hour = 25.4 mm/h, 1 square foot = 0.0929 m²

Notes:

¹ The sizing data for horizontal piping are based on the pipes flowing full.

² For rainfall rates other than those listed, determine the allowable roof area by dividing the area given in the 1 inch per hour (25.4 mm/h) column by the desired rainfall rate.

TABLE 1101.12
SIZING ROOF DRAINS, LEADERS, AND VERTICAL RAINWATER PIPING^{2,3}



| SIZE OF DRAIN, LEADER, OR PIPE | FLOW | MAXIMUM ALLOWABLE HORIZONTAL PROJECTED ROOF AREAS AT VARIOUS RAINFALL RATES (square feet) | | | | | | | | | | | |
|---|------|---|----------|----------|----------|----------|----------|----------|----------|----------|-----------|-----------|-----------|
| | | 1 (in/h) | 2 (in/h) | 3 (in/h) | 4 (in/h) | 5 (in/h) | 6 (in/h) | 7 (in/h) | 8 (in/h) | 9 (in/h) | 10 (in/h) | 11 (in/h) | 12 (in/h) |
| 2 | 30 | 2880 | 1440 | 960 | 720 | 575 | 480 | 410 | 360 | 320 | 290 | 260 | 240 |
| 3 | 92 | 8800 | 4400 | 2930 | 2200 | 1760 | 1470 | 1260 | 1100 | 980 | 880 | 800 | 730 |
| 4 | 192 | 18 400 | 9200 | 6130 | 4600 | 3680 | 3070 | 2630 | 2300 | 2045 | 1840 | 1675 | 1530 |
| 5 | 360 | 34 600 | 17 300 | 11 530 | 8650 | 6920 | 5765 | 4945 | 4325 | 3845 | 3460 | 3145 | 2880 |
| 6 | 563 | 54 000 | 27 000 | 17 995 | 13 500 | 10 800 | 9000 | 7715 | 6750 | 6000 | 5400 | 4910 | 4500 |
| 8 | 1208 | 116 000 | 58 000 | 38 660 | 29 000 | 23 200 | 19 315 | 16 570 | 14 500 | 12 890 | 11 600 | 10 545 | 9600 |

For SI units: 1 inch = 25 mm, 1 gallon per minute = 0.06 L/s, 1 inch per hour = 25.4 mm/h, 1 square foot = 0.0929 m²

Notes:

¹ Maximum discharge capacity, gpm (L/s) with approximately 1¼ inch (44 mm) head of water at the drain.

² For rainfall rates other than those listed, determine the allowable roof area by dividing the area given in the 1 inch per hour (25.4 mm/h) column by the desired rainfall rate.

³ Vertical piping shall be round, square, or rectangular. Square pipe shall be sized to enclose its equivalent roundpipe. Rectangular pipe shall have not less than the same cross-sectional area as its equivalent round pipe, except that the ratio of its side dimensions shall not exceed 3 to 1.

**TABLE 1103.3
SIZE OF GUTTERS**

| DIAMETER OF GUTTER ($\frac{1}{8}$ inch per foot slope) | MAXIMUM RAINFALL RATES BASED ON ROOF AREA (square feet) | | | | |
|--|--|----------|----------|----------|----------|
| inches | 2 (in/h) | 3 (in/h) | 4 (in/h) | 5 (in/h) | 6 (in/h) |
| 3 | 340 | 226 | 170 | 136 | 113 |
| 4 | 720 | 480 | 360 | 288 | 240 |
| 5 | 1250 | 834 | 625 | 500 | 416 |
| 6 | 1920 | 1280 | 960 | 768 | 640 |
| 7 | 2760 | 1840 | 1380 | 1100 | 918 |
| 8 | 3980 | 2655 | 1990 | 1590 | 1325 |
| 10 | 7200 | 4800 | 3600 | 2880 | 2400 |

| DIAMETER OF GUTTER ($\frac{1}{4}$ inch per foot slope) | MAXIMUM RAINFALL RATES BASED ON ROOF AREA (square feet) | | | | |
|--|--|----------|----------|----------|----------|
| inches | 2 (in/h) | 3 (in/h) | 4 (in/h) | 5 (in/h) | 6 (in/h) |
| 3 | 480 | 320 | 240 | 192 | 160 |
| 4 | 1020 | 681 | 510 | 408 | 340 |
| 5 | 1760 | 1172 | 880 | 704 | 587 |
| 6 | 2720 | 1815 | 1360 | 1085 | 905 |
| 7 | 3900 | 2600 | 1950 | 1560 | 1300 |
| 8 | 5600 | 3740 | 2800 | 2240 | 1870 |
| 10 | 10 200 | 6800 | 5100 | 4080 | 3400 |

| DIAMETER OF GUTTER ($\frac{1}{2}$ inch per foot slope) | MAXIMUM RAINFALL RATES BASED ON ROOF AREA (square feet) | | | | |
|--|--|----------|----------|----------|----------|
| inches | 2 (in/h) | 3 (in/h) | 4 (in/h) | 5 (in/h) | 6 (in/h) |
| 3 | 680 | 454 | 340 | 272 | 226 |
| 4 | 1440 | 960 | 720 | 576 | 480 |
| 5 | 2500 | 1668 | 1250 | 1000 | 834 |
| 6 | 3840 | 2560 | 1920 | 1536 | 1280 |
| 7 | 5520 | 3680 | 2760 | 2205 | 1840 |
| 8 | 7960 | 5310 | 3980 | 3180 | 2655 |
| 10 | 14 400 | 9600 | 7200 | 5750 | 4800 |

| DIAMETER OF GUTTER ($\frac{3}{4}$ inch per foot slope) | MAXIMUM RAINFALL RATES BASED ON ROOF AREA (square feet) | | | | |
|--|--|----------|----------|----------|----------|
| inches | 2 (in/h) | 3 (in/h) | 4 (in/h) | 5 (in/h) | 6 (in/h) |
| 3 | 960 | 640 | 480 | 384 | 320 |
| 4 | 2040 | 1360 | 1020 | 816 | 680 |
| 5 | 3540 | 2360 | 1770 | 1415 | 1180 |
| 6 | 5540 | 3695 | 2770 | 2220 | 1850 |
| 7 | 7800 | 5200 | 3900 | 3120 | 2600 |
| 8 | 11 200 | 7460 | 5600 | 4480 | 3730 |
| 10 | 20 000 | 13 330 | 10 000 | 8000 | 6660 |

For SI units: 1 inch = 25 mm, $\frac{1}{8}$ inch per foot = 5.2 mm/m, 1 inch per hour = 25.4 mm/h, 1 square foot = 0.0929 m²

CHAPTER 12

FUEL GAS PIPING

» 1201.0 General.

» **1201.1 Applicability.** The regulations of this chapter shall govern the installation of fuel gas piping in or in connection with a building, structure or within the property lines of premises up to 5 pounds-force per square inch (psi) (34 kPa), other than service pipe. Fuel oil piping systems shall be installed in accordance with NFPA 31.

» 1202.0 Coverage of Piping System.

» **1202.1 General.** Coverage of piping systems shall extend from the point of delivery to the appliance connections. For other than undiluted liquefied petroleum gas (LP-Gas) systems, the point of delivery shall be the outlet of the service meter assembly or the outlet of the service regulator or service shutoff valve where no meter is provided. For undiluted liquefied petroleum gas systems, the point of delivery shall be considered the outlet of the final pressure regulator, exclusive of the line gas regulators where no meter is installed. Where a meter is installed, the point of delivery shall be the outlet of the meter. [NFPA 54:1.1.1.1(A)]

» **1202.2 Piping System Requirements.** Piping systems requirements shall include design, materials, components, fabrications, assembly, installation, testing, inspection, operation, and maintenance. [NFPA 54:1.1.1.1(C)]

» **1202.3 Applications.** This code shall not apply to the following (reference standards for some of which appear in Chapter 17):

- » (1) Portable LP-Gas appliances and equipment that are not connected to a fixed fuel piping system.
- (2) Installation of appliances such as brooders, dehydrators, dryers, and irrigation equipment used for agricultural purposes.
- (3) Raw material (feedstock) applications, except for piping to special atmosphere generators.
- (4) Oxygen-fuel gas cutting and welding systems.
- » (5) Industrial gas applications using such gases as acetylene and acetylenic compounds, hydrogen, ammonia, carbon monoxide, oxygen, and nitrogen.
- (6) Petroleum refineries, pipeline compressor or pumping stations, loading terminals, compounding plants, refinery tank farms, and natural gas processing plants.
- (7) Large integrated chemical plants or portions of such plants where flammable or combustible liquids or gases are produced by chemical reactions or used in chemical reactions.
- (8) LP-Gas installations at utility gas plants.
- (9) Liquefied natural gas (LNG) installations.
- (10) Fuel gas piping in electric utility power plants.
- (11) Proprietary items of equipment, apparatus, or instruments such as gas-generating sets, compressors, and calorimeters.

(12) LP-Gas equipment for vaporization, gas mixing, and gas manufacturing.

(13) LP-Gas piping for buildings under construction or renovations that are not to become part of the permanent building piping system—that is, temporary fixed piping for building heat.

(14) Installation of LP-Gas systems for railroad switch heating.

(15) Installation of LP-Gas and compressed natural gas (CNG) systems on vehicles.

(16) Gas piping, meters, gas-pressure regulators, and other appurtenances used by the serving gas supplier in distribution of gas, other than undiluted LP-Gas. [NFPA 54:1.1.1.2]

1203.0 Inspection.

1203.1 Inspection Notification. Upon completion of the installation, alteration, or repair of gas piping, and prior to the use thereof, the Authority Having Jurisdiction shall be notified that such gas piping is ready for inspection.

1203.2 Excavation. Excavations required for the installation of underground piping shall be kept open until such time as the piping has been inspected and approved. Where such piping is covered or concealed before such approval, it shall be exposed upon the direction of the Authority Having Jurisdiction.

1203.3 Type of Inspections. The Authority Having Jurisdiction shall make the following inspections and either shall approve that portion of the work as completed or shall notify the permit holder wherein the same fails to be in accordance with this code.

1203.3.1 Rough Piping Inspection. This inspection shall be made after gas piping authorized by the permit has been installed and before such piping has been covered or concealed or fixture or appliance has been attached thereto. This inspection shall include a determination that the gas piping size, material, and installation meet the requirements of this code.

1203.3.2 Final Piping Inspection. This inspection shall be made after piping authorized by the permit has been installed and after portions thereof that are to be covered or concealed are so concealed and before fixture, appliance, or shutoff valve has been attached thereto. This inspection shall comply with Section 1213.1. Test gauges used in conducting tests shall be in accordance with Section 318.0.

1203.4 Inspection Waived. In cases where the work authorized by the permit consists of a minor installation of additional piping to piping already connected to a gas meter, the foregoing inspections shall be permitted to be waived at the

discretion of the Authority Having Jurisdiction. In this event, the Authority Having Jurisdiction shall make such inspection as deemed advisable in order to be assured that the work has been performed in accordance with the intent of this code.

1204.0 Certificate of Inspection.

1204.1 Issuance. Where upon final piping inspection, the installation is found to be in accordance with the provisions of this code, a certificate of inspection shall be permitted to be issued by the Authority Having Jurisdiction.

1204.2 Gas Supplier. A copy of the certificate of such final piping inspection shall be issued to the serving gas supplier supplying gas to the premises.

1204.3 Unlawful. It shall be unlawful for a serving gas supplier, or person furnishing gas, to turn on or cause to be turned on, a fuel gas or a gas meter or meters, until such certificate of final inspection, as herein provided, has been issued.

1205.0 Authority to Render Gas Service.

1205.1 Authorized Personnel. It shall be unlawful for a person, firm, or corporation, excepting an authorized agent or employee of a person, firm, or corporation engaged in the business of furnishing or supplying gas and whose service pipes supply or connect with the particular premises, to turn on or reconnect gas service in or on a premises where and when gas service is, at the time, not being rendered.

1205.2 Outlets. It shall be unlawful to turn on or connect gas in or on the premises unless outlets are securely connected to gas appliances or capped or plugged with screw joint fittings.

1206.0 Authority to Disconnect.

1206.1 Disconnection. The Authority Having Jurisdiction or the serving gas supplier is hereby authorized to disconnect gas piping or appliance or both that shall be found not to be in accordance with the requirements of this code or that are found defective and in such condition as to endanger life or property.

1206.2 Notice. Where such disconnection has been made, a notice shall be attached to such gas piping or appliance or both that shall state the same has been disconnected, together with the reasons thereof.

1206.3 Capped Outlets. It shall be unlawful to remove or disconnect gas piping or gas appliance without capping or plugging with a screw joint fitting, the outlet from which said pipe or appliance was removed. Outlets to which gas appliances are not connected shall be left capped and gastight on a piping system that has been installed, altered, or repaired.

Exception: Where an approved listed quick-disconnect device is used.

1207.0 Temporary Use of Gas.

1207.1 General. Where temporary use of gas is desired and the Authority Having Jurisdiction deems the use necessary, a

permit shall be permitted to be issued for such use for a period of time not to exceed that designated by the Authority Having Jurisdiction, provided that such gas piping system otherwise is in accordance with the requirements of this code regarding material, sizing, and safety.

1208.0 Gas Piping System Design, Materials, and Components.

1208.1 Installation of Piping System. Where required by the Authority Having Jurisdiction, a piping sketch or plan shall be prepared before proceeding with the installation. This plan shall show the proposed location of piping, the size of different branches, the various load demands, and the location of the point of delivery. [NFPA 54:5.1.1]

1208.1.1 Addition to Existing System. Where additional appliances are being connected to a gas piping system, the existing piping shall be checked to determine whether it has adequate capacity. Where inadequate, the existing system shall be enlarged as required, or separate gas piping of approved capacity shall be provided. [NFPA 54:5.1.2]

1208.2 Provision for Location of Point of Delivery. The location of the point of delivery shall be acceptable to the serving gas supplier. [NFPA 54:5.2]

1208.3 Interconnections Between Gas Piping Systems. Where two or more meters, or two or more service regulators where meters are not provided, are located on the same premises and supply separate users, the gas piping systems shall not be interconnected on the outlet side of the meters or service regulators. [NFPA 54:5.3.1]

1208.3.1 Interconnections for Standby Fuels. Where a supplementary gas for standby use is connected downstream from a meter or a service regulator where a meter is not provided, a device to prevent backflow shall be installed. A three-way valve installed to admit the standby supply, and at the same time shut off the regular supply, shall be permitted to be used for this purpose. [NFPA 54:5.3.2]

1208.4 Sizing of Gas Piping Systems. Gas piping systems shall be of such size and so installed as to provide a supply of gas to meet the maximum demand and supply gas to each appliance inlet at not less than the minimum supply pressure required by the appliance. [NFPA 54:5.4.1]

1208.4.1 Maximum Gas Demand. The volumetric flow rate of gas to be provided (in cubic feet per hour) shall be calculated using the manufacturer's input ratings of the appliance served, adjusted for altitude. Where the input rating is not indicated, the gas supplier, appliance manufacturer, or a qualified agency shall be contacted or the rating from Table 1208.4.1 shall be used for estimating the volumetric flow rate of gas to be supplied.

The total connected hourly load shall be used as the basis for piping sizing, assuming the appliances are operating at full capacity simultaneously.

Exception: Sizing shall be permitted to be based upon established load diversity factors. [NFPA 54:5.4.2]

TABLE 1208.4.1
APPROXIMATE GAS INPUT FOR
TYPICAL APPLIANCES
[NFPA 54: TABLE 5.4.2.1]

| APPLIANCE | INPUT (Btu/h approx.) |
|---|--------------------------|
| Space Heating Units | |
| Warm air furnace | |
| Single family | 100 000 |
| Multifamily, per unit | 60 000 |
| Hydronic boiler | |
| Single family | 100 000 |
| Multifamily, per unit | 60 000 |
| Space and Water Heating Units | |
| Hydronic boiler | |
| Single family | 120 000 |
| Multifamily, per unit | 75 000 |
| Water Heating Appliances | |
| Water heater, automatic storage | |
| 30 to 40 gallon tank | 35 000 |
| Water heater, automatic storage | |
| 50 gallon tank | 50 000 |
| Water heater, automatic instantaneous | |
| Capacity at 2 gallons per minute | 142 800 |
| Capacity at 4 gallons per minute | 285 000 |
| Capacity at 6 gallons per minute | 428 400 |
| Water heater, domestic, circulating or side-arm | 35 000 |
| Cooking Appliances | |
| Range, freestanding, domestic | 65 000 |
| Built-in oven or broiler unit, domestic | 25 000 |
| Built-in top unit, domestic | 40 000 |
| Other Appliances | |
| Refrigerator | 3000 |
| Clothes dryer, Type 1 (domestic) | 35 000 |
| Gas fireplace direct vent | 40 000 |
| Gas log | 80 000 |
| Barbecue | 40 000 |
| Gaslight | 2500 |

For SI units: 1000 British thermal units per hour = 0.293 kW

1208.4.2 Sizing Methods. Gas piping shall be sized in accordance with one of the following:

- (1) Pipe sizing tables or sizing equations in this chapter.
- (2) Other approved engineering methods acceptable to the Authority Having Jurisdiction.
- (3) Sizing tables included in a listed piping system manufacturer's instructions. [NFPA 54:5.4.3]

1208.4.3 Allowable Pressure Drop. The design pressure loss in a piping system under maximum proba-

ble flow conditions, from the point of delivery to the inlet connection of the appliance, shall be such that the supply pressure at the appliance is greater than or equal to the minimum pressure required by the appliance. [NFPA 54:5.4.4]

1208.5 Acceptable Piping Materials and Joining Methods. Materials used for piping systems shall be in accordance with the requirements of this chapter or shall be acceptable to the Authority Having Jurisdiction. [NFPA 54:5.6.1.1]

1208.5.1 Materials. Pipe, fittings, valves, or other materials shall not be used again unless they are free of foreign materials and have been ascertained to be approved for the service intended. [NFPA 54:5.6.1.2]

1208.5.1.1 Other Materials. Material not covered by the standards specifications listed herein shall be investigated and tested to determine that it is safe and approved for the proposed service and, in addition, shall be recommended for that service by the manufacturer and shall be acceptable to the Authority Having Jurisdiction. [NFPA 54:5.6.1.3]

1208.5.2 Metallic Pipe. Cast-iron pipe shall not be used. [NFPA 54:5.6.2.1]

1208.5.2.1 Steel and Wrought-Iron. Steel and wrought-iron pipe shall be not less than standard weight (Schedule 40) and shall comply with one of the following standards:

- (1) ASME B36.10
- (2) ASTM A53
- (3) ASTM A106 [NFPA 54:5.6.2.2]

1208.5.2.2 Copper and Copper Alloy. Copper and copper alloy pipe shall not be used where the gas contains more than an average of 0.3 grains of hydrogen sulfide per 100 standard cubic feet (scf) of gas (0.7 mg/100 L).

Threaded copper, copper alloy, or aluminum alloy pipe shall not be used with gases corrosive to such material.

1208.5.2.3 Aluminum Alloy. Aluminum alloy pipe shall comply with ASTM B241 (except that the use of alloy 5456 is prohibited) and shall be marked at each end of each length indicating compliance. Aluminum alloy pipe shall be coated to protect against external corrosion where it is in contact with masonry, plaster, insulation or is subject to repeated wettings by such liquids as water, detergents, or sewage. [NFPA 54:5.6.2.5]

Aluminum alloy pipe shall not be used in exterior locations or underground. [NFPA 54:5.6.2.6]

1208.5.3 Metallic Tubing. Seamless copper, aluminum alloy, or steel tubing shall not be used with gases corrosive to such material. [NFPA 54:5.6.3]

1208.5.3.1 Steel. Steel tubing shall comply with ASTM A254. [NFPA 54:5.6.3.1]

1208.5.3.2 Copper and Copper Alloy. Copper and copper alloy tubing shall not be used where the gas contains more than an average of 0.3 grains of hydrogen sulfide per 100 scf of gas (0.7 mg/100 L). Copper tubing shall comply with standard Type K or L of ASTM B88 or ASTM B280.

1208.5.3.3 Aluminum Alloy. Aluminum alloy tubing shall comply with ASTM B210 or ASTM B241. Aluminum alloy tubing shall be coated to protect against external corrosion where it is in contact with masonry, plaster, insulation, or is subject to repeated wettings by such liquids as water, detergent, or sewage. Aluminum alloy tubing shall not be used in exterior locations or underground. [NFPA 54:5.6.3.3]

1208.5.3.4 Corrugated Stainless Steel. Corrugated stainless steel tubing shall be listed in accordance with CSA LC-1. [NFPA 54:5.6.3.4]

1208.5.4 Plastic Pipe, Tubing, and Fittings. Polyethylene plastic pipe, tubing, and fittings used to supply fuel gas shall be in accordance with ASTM D2513. Pipe to be used shall be marked "gas" and "ASTM D2513." [NFPA 54:5.6.4.1.1]

1208.5.4.1 Regulator Vent Piping. Plastic pipe and fittings used to connect regulator vents to remote vent terminations shall be PVC in accordance with UL 651. PVC vent piping shall not be installed indoors. [NFPA 54:5.6.4.2]

1208.5.4.2 Anodeless Risers. Anodeless risers shall comply with Section 1208.5.4.2.1 through Section 1208.5.4.2.3. [NFPA 54:5.6.4.3]

1208.5.4.2.1 Factory-Assembled Anodeless Risers. Factory-assembled anodeless risers shall be recommended by the manufacturer for the gas used and shall be leak-tested by the manufacturer in accordance with written procedures. [NFPA 54:5.6.4.3(1)]

1208.5.4.2.2 Service Head Adapters and Field-Assembled Anodeless Risers. Service head adapters and field-assembled anodeless risers incorporating service head adapters shall be recommended by the manufacturer for the gas used and shall be design-certified to be in accordance with the requirements of Category I of ASTM D2513. The manufacturer shall provide the user qualified installation instructions. [NFPA 54:5.6.4.3(2)]

1208.5.4.2.3 Undiluted Liquefied Petroleum Gas Piping. The use of plastic pipe, tubing, and fittings in undiluted liquefied petroleum gas piping systems shall be in accordance with NFPA 58. [NFPA 54:5.6.4.3(3)]

1208.5.5 Workmanship and Defects. Gas pipe, tubing, and fittings shall be clear and free from cutting burrs and defects in structure or threading, and shall be thoroughly brushed and chip and scale blown. Defects in

pipe, tubing, and fittings shall not be repaired. Defective pipe, tubing, and fittings shall be replaced. [NFPA 54:5.6.5]

1208.5.6 Protective Coating. Where in contact with material or atmosphere exerting a corrosive action, metallic piping and fittings coated with a corrosion-resistant material shall be used. External or internal coatings or linings used on piping or components shall not be considered as adding strength. [NFPA 54:5.6.6]

1208.5.7 Metallic Pipe Threads. Metallic pipe and fitting threads shall be taper pipe threads and shall comply with ASME B1.20.1. [NFPA 54:5.6.7.1]

1208.5.7.1 Damaged Threads. Pipe with threads that are stripped, chipped, corroded, or otherwise damaged shall not be used. Where a weld opens during the operation of cutting or threading, that portion of the pipe shall not be used. [NFPA 54:5.6.7.2]

1208.5.7.2 Number of Threads. Field threading of metallic pipe shall be in accordance with Table 1208.5.7.2. [NFPA 54:5.6.7.3]

TABLE 1208.5.7.2
SPECIFICATIONS FOR THREADING METALLIC PIPE
[NFPA 54: TABLE 5.6.7.3]

| IRON PIPE SIZE (inches) | APPROXIMATE LENGTH OF THREADED PORTION (inches) | APPROXIMATE NUMBER OF THREADS TO BE CUT |
|-------------------------|---|---|
| ½ | ¾ | 10 |
| ¾ | ¾ | 10 |
| 1 | 7/8 | 10 |
| 1¼ | 1 | 11 |
| 1½ | 1 | 11 |
| 2 | 1 | 11 |
| 2½ | 1½ | 12 |
| 3 | 1½ | 12 |
| 4 | 1¾ | 13 |

For SI units: 1 inch = 25.4 mm

1208.5.7.3 Thread Joint Compounds. Thread joint compounds shall be resistant to the action of liquefied petroleum gas or to other chemical constituents of the gases to be conducted through the piping. [NFPA 54:5.6.7.4]

1208.5.8 Metallic Piping Joints and Fittings. The type of piping joint used shall be approved for the pressure-temperature conditions and shall be selected giving consideration to joint tightness and mechanical strength under the service conditions. The joint shall be able to sustain the maximum end force due to the internal pressure and additional forces due to temperature expansion or contraction, vibration, fatigue, or to the weight of the pipe and its contents. [NFPA 54:5.6.8]

1208.5.8.1 Pipe Joints. Pipe joints shall be threaded, flanged, brazed, welded, or press-connect

fittings made in accordance with CSA LC-4. Where nonferrous pipe is brazed, the brazing materials shall have a melting point in excess of 1000°F (538°C). Brazing alloys shall not contain more than 0.05 percent phosphorus.

1208.5.8.2 Tubing Joints. Tubing joints shall either be made with approved gas tubing fittings, be brazed with a material having a melting point in excess of 1000°F (538°C), or made by press-connect fittings in accordance with CSA LC-4. Brazing alloys shall not contain more than 0.05 percent phosphorus. [NFPA 54:5.6.8.2]

1208.5.8.3 Flared Joints. Flared joints shall be used in systems constructed from nonferrous pipe and tubing where experience or tests have demonstrated that the joint is approved for the conditions and where provisions are made in the design to prevent separation of the joints. [NFPA 54:5.6.8.3]

1208.5.8.4 Metallic Pipe Fittings (Including Valves, Strainers, Filters). Metallic pipe fittings shall comply with the following:

- (1) Threaded fittings in sizes exceeding 4 inches (100 mm) shall not be used unless acceptable to the Authority Having Jurisdiction.
- (2) Fittings used with steel or wrought-iron pipe shall be steel, copper alloy, malleable iron, or cast-iron.
- (3) Fittings used with copper or copper alloy pipe shall be copper or copper alloy.
- (4) Fittings used with aluminum alloy pipe shall be of aluminum alloy.
- (5) Cast-iron fittings shall comply with the following:
 - (a) Flanges shall be permitted.
 - (b) Bushings shall not be used.
 - (c) Fittings shall not be used in systems containing flammable gas-air mixtures.
 - (d) Fittings in sizes 4 inches (100 mm) and larger shall not be used indoors unless approved by the Authority Having Jurisdiction.
 - (e) Fittings in sizes 6 inches (150 mm) and larger shall not be used unless approved by the Authority Having Jurisdiction.
- (6) Aluminum alloy fitting threads shall not form the joint seal.
- (7) Zinc-aluminum alloy fittings shall not be used in systems containing flammable gas-air mixtures.
- (8) Special fittings such as couplings; proprietary-type joints; saddle tees; gland-type compression fittings; and flared, flareless, or compression-type tubing fittings shall be as follows:
 - (a) Used within the fitting manufacturer's pressure-temperature recommendations.

- (b) Used within the service conditions anticipated with respect to vibration, fatigue, thermal expansion, or contraction.
- (c) Installed or braced to prevent separation of the joint by gas pressure or external physical damage.
- (d) Acceptable to the Authority Having Jurisdiction.

1208.5.9 Plastic Piping, Joints, and Fittings. Plastic pipe, tubing, and fittings shall be installed in accordance with the manufacturer's installation instructions. Section 1208.5.9.1 through Section 1208.5.9.4 shall be observed where making such joints. [NFPA 54:5.6.9]

1208.5.9.1 Joint Design. The joint shall be designed and installed so that the longitudinal pullout resistance of the joint shall be equal to the tensile strength of the plastic piping material. [NFPA 54:5.6.9(1)]

1208.5.9.2 Heat-Fusion Joint. Heat-fusion joints shall be made in accordance with qualified procedures that have been established and proven by test to produce gastight joints as strong as the pipe or tubing being joined. Joints shall be made with the joining method recommended by the pipe manufacturer. Heat-fusion fittings shall be marked "ASTM D2513." [NFPA 54:5.6.9(2)]

1208.5.9.3 Compression-Type Mechanical Joints. Where compression-type mechanical joints are used, the gasket material in the fitting shall be compatible with the plastic piping and with the gas distributed by the system. An internal tubular rigid stiffener shall be used in conjunction with the fitting. The stiffener shall be flush with the end of the pipe or tubing and shall extend not less than the outside end of the compression fitting where installed. The stiffener shall be free of rough or sharp edges and shall not be a forced fit in the plastic. Split tubular stiffeners shall not be used. [NFPA 54:5.6.9(3)]

1208.5.9.4 Liquefied Petroleum Gas Piping Systems. Plastic piping joints and fittings for use in liquefied petroleum gas piping systems shall be in accordance with NFPA 58. [NFPA 54:5.6.9(4)]

1208.5.10 Flanges. Flanges shall comply with ASME B16.1, ASME B16.20, or MSS SP-6. The pressure-temperature ratings shall equal or exceed that required by the application. [NFPA 54:5.6.10]

1208.5.10.1 Flange Facings. Standard facings shall be permitted for use under this code. Where 150 psi (1034 kPa) steel flanges are bolted to Class 125 cast-iron flanges, the raised face on the steel flange shall be removed. [NFPA 54:5.6.10.1]

1208.5.10.2 Lapped Flanges. Lapped flanges shall be used aboveground or in exposed locations accessible for inspection. [NFPA 54:5.6.10.2]

1208.5.11 Flange Gaskets. The material for gaskets shall be capable of withstanding the design temperature

and pressure of the piping system and the chemical constituents of the gas being conducted without change to its chemical and physical properties. The effects of fire exposure to the joint shall be considered in choosing the material. [NFPA 54:5.6.11] Flange gaskets shall comply with the following requirements:

- (1) Acceptable materials include the following:
 - (a) Metal (plain or corrugated)
 - (b) Composition
 - (c) Aluminum o-rings and spiral-wound metal gaskets [NFPA 54:5.6.11.1]
- (2) Where a flanged joint is opened, the gasket shall be replaced. [NFPA 54:5.6.11.2]
- (3) Full-face gaskets shall be used with bronze and cast-iron flanges. [NFPA 54:5.6.11.3]

1208.6 Gas Meters. Gas meters shall be selected for the maximum expected pressure and permissible pressure drop. [NFPA 54:5.7.1]

1208.6.1 Location. Gas meters shall be located in ventilated spaces readily accessible for examination, reading, replacement, or necessary maintenance. [NFPA 54:5.7.2.1]

1208.6.1.1 Subject to Damage. Gas meters shall not be placed where they will be subjected to damage, such as adjacent to a driveway; under a fire escape; in public passages, halls, or coal bins; or where they will be subject to excessive corrosion or vibration. [NFPA 54:5.7.2.2]

1208.6.1.2 Extreme Temperatures. Gas meters shall not be located where they will be subjected to extreme temperatures or sudden extreme changes in temperature. Meters shall not be located in areas where they are subjected to temperatures beyond those recommended by the manufacturer. [NFPA 54:5.7.2.3]

1208.6.2 Supports. Gas meters shall be supported or connected to rigid piping so as not to exert a strain on the meters. Where flexible connectors are used to connect a gas meter to downstream piping at mobile homes in mobile home parks, the meter shall be supported by a post or bracket placed in a firm footing or by other means providing equivalent support. [NFPA 54:5.7.3]

1208.6.3 Meter Protection. Meters shall be protected against overpressure, backpressure, and vacuum. [NFPA 54:5.7.4]

1208.6.4 Identification. Gas piping at multiple meter installations shall be marked by a metal tag or other permanent means attached by the installing agency, designating the building or the part of the building being supplied. [NFPA 54:5.7.5]

1208.7 Gas Pressure Regulators. A line pressure regulator or gas appliance pressure regulator, as applicable, shall be installed where the gas supply pressure exceeds that at which the branch supply line or appliances are designed to operate or vary beyond design pressure limits. [NFPA 54:5.8.1]

1208.7.1 Overpressure Protection. Where the gas supply design pressure in piping systems located indoors exceeds 2 psi (14 kPa) and line pressure regulators are installed to reduce the supply pressure to 14 inches water column (3.5 kPa) or less, the following shall apply:

- (1) Regulators shall be provided with factory installed overpressure protection devices.
- (2) Overpressure protection devices shall limit the pressure downstream of the line pressure regulator to 2 psi (14 kPa) in the event of failure of the line pressure regulator. [NFPA 54:5.8.3]

1208.7.2 Listing. Line pressure regulators shall be listed in accordance with CSA Z21.80. [NFPA 54:5.8.2]

1208.7.3 Location. The gas pressure regulator shall be accessible for servicing. [NFPA 54:5.8.4]

1208.7.4 Regulator Protection. Pressure regulators shall be protected against physical damage. [NFPA 54:5.8.5]

1208.7.5 Venting of Line Pressure Regulators. Line pressure regulators shall comply with the following:

- (1) An independent vent to the exterior of the building, sized in accordance with the regulator manufacturer's instructions, shall be provided where the location of a regulator is such that a ruptured diaphragm will cause a hazard. Where more than one regulator is at a location, each regulator shall have a separate vent to the outdoors, or where approved by the Authority Having Jurisdiction, the vent lines shall be permitted to be manifolded in accordance with accepted engineering practices to minimize backpressure in the event of diaphragm failure. Materials for vent piping shall comply with Section 1208.5.

Exception: A regulator and vent limiting means combination listed in accordance with CSA Z21.80 shall be permitted to be used without a vent to the outdoors.

- (2) The vent shall be designed to prevent the entry of water, insects, or other foreign materials that will cause blockage.
- (3) The regulator vent shall terminate not less than 3 feet (914 mm) from a source of ignition.
- (4) At locations where regulators will be submerged during floods, a special antiflood-type breather vent fitting shall be installed, or the vent line shall be extended above the height of the expected flood waters.
- (5) A regulator shall not be vented to the appliance flue or exhaust system. [NFPA 54:5.8.6.1]

1208.7.6 Venting of Gas Appliance Pressure Regulators. Venting of gas appliance pressure regulators shall be in accordance with the following requirements:

- (1) Appliance pressure regulators requiring access to the atmosphere for successful operation shall be equipped with vent piping leading outdoors or, where the regulator vent is an integral part of the appliance,

into the combustion chamber adjacent to a continuous pilot, unless constructed or equipped with a vent-limiting means to limit the escape of gas from the vent opening in the event of diaphragm failure.

- (2) Vent limiting means shall be employed on listed appliance pressure regulators.
- (3) In the case of vents leading outdoors, means shall be employed to prevent water from entering this piping and also to prevent blockage of vents by insects and foreign matter.
- (4) Under no circumstances shall a regulator be vented to the appliance flue or exhaust system.
- (5) In the case of vents entering the combustion chamber, the vent shall be located so the escaping gas will be readily ignited by the pilot and the heat liberated thereby will not adversely affect the normal operation of the safety shutoff system. The terminus of the vent shall be securely held in a fixed position relative to the pilot. For manufactured gas, the need for a flame arrester in the vent piping shall be determined.
- (6) Vent lines from a gas appliance pressure regulator and bleed lines from a diaphragm-type valve shall not be connected to a common manifold terminating in a combustion chamber. Vent lines shall not terminate in positive-pressure-type combustion chambers. [NFPA 54:9.1.19]

» **1208.7.7 Discharge of Vents.** The discharge of vents shall be in accordance with the following requirements:

- (1) The discharge stacks, vents, or outlet parts of pressure-relieving and pressure-limiting devices shall be located so that gas is safely discharged to the outdoors.
- (2) Discharge stacks or vents shall be designed to prevent the entry of water, insects, or other foreign material that could cause blockage. The discharge stack or vent line shall be not less than the same size as the outlet of the pressure-relieving device. [NFPA 54:5.9.7]

» **1208.7.8 Bypass Piping.** Valved and regulated bypasses shall be permitted to be placed around gas line pressure regulators where continuity of service is imperative. [NFPA 54:5.8.7]

» **1208.7.9 Identification.** Line pressure regulators at multiple regulator installations shall be marked by a metal tag or other permanent means designating the building or the part of the building being supplied. [NFPA 54:5.8.8]

1208.8 Backpressure Protection. Protective devices shall be installed as close to the equipment as practical where the design of the equipment connected is such that air, oxygen, or standby gases are capable of being forced into the gas supply system. Gas and air combustion mixers incorporating double diaphragm "zero" or "atmosphere" governors or regulators shall require no further protection unless connected

directly to compressed air or oxygen at pressures of 5 psi (34 kPa) or more. [NFPA 54:5.10.1]

1208.8.1 Protective Devices. Protective devices shall include, but not be limited to the following:

- (1) Check valves.
- (2) Three-way valves (of the type that completely closes one side before starting to open the other side).
- (3) Reverse flow indicators controlling positive shutoff valves.
- (4) Normally closed air-actuated positive shutoff pressure regulators. [NFPA 54:5.10.2]

1208.9 Low-Pressure Protection. A protective device shall be installed between the meter and the appliance or equipment where the operation of the appliance or equipment is such that it is capable of producing a vacuum or a dangerous reduction in gas pressure at the meter. Such protective devices include, but are not limited to, mechanical, diaphragm-operated, or electrically operated low-pressure shutoff valves. [NFPA 54:5.11]

1208.10 Shutoff Valves. Shutoff valves shall be approved and shall be selected giving consideration to pressure drop, service involved, emergency use, and reliability of operation. Shutoff valves of size 1 inch (25 mm) National Pipe Thread and smaller shall be listed. [NFPA 54:5.12]

1208.11 Expansion and Flexibility. Piping systems shall be designed to prevent failure from thermal expansion or contraction. [NFPA 54:5.14.1]

1208.11.1 Special Local Conditions. Where local conditions include earthquake, tornado, unstable ground, or flood hazards, special consideration shall be given to increased strength and flexibility of piping supports and connections. [NFPA 54:5.14.2]

1209.0 Excess Flow Valve.

1209.1 General. Where automatic excess flow valves are installed, they shall be listed, sized, and installed in accordance with the manufacturer's installation instructions. [NFPA 54:5.13]

1210.0 Gas Piping Installation.

1210.1 Piping Underground. Underground gas piping shall be installed with approved clearance from other underground structures to avoid contact therewith, to allow maintenance, and to protect against damage from proximity to other structures. In addition, underground plastic piping shall be installed with approved clearance or shall be insulated from sources of heat so as to prevent the heat from impairing the serviceability of the pipe. [NFPA 54:7.1.1]

1210.1.1 Cover Requirements. Underground piping systems shall be installed with a cover not less than 12 inches (305 mm). Where external damage to the pipe or tubing from external forces is likely to result, the cover shall be not less than 18 inches (457 mm). Where a cover not less than 12 inches (305 mm) cannot be provided, the

pipe shall be installed in conduit or bridged (shielded). [NFPA 54:7.1.2.1]

1210.1.2 Trenches. The trench shall be graded so that the pipe has a firm, substantially continuous bearing on the bottom of the trench. [NFPA 54:7.1.2.2]

1210.1.2.1 Backfilling. Where flooding of the trench is done to consolidate the backfill, care shall be exercised to see that the pipe is not floated from its firm bearing on the trench bottom. [NFPA 54:7.1.2.3]

1210.1.3 Protection Against Corrosion. Gas piping in contact with earth or other material that is capable of corroding the piping shall be protected against corrosion in an approved manner. Where dissimilar metals are joined underground, an insulating coupling or fitting shall be used. Piping shall not be laid in contact with cinders. Uncoated threaded or socket-welded joints shall not be used in piping in contact with soil or where internal or external crevice corrosion is known to occur. [NFPA 54:7.1.3]

1210.1.4 Protection Against Freezing. Where the formation of hydrates or ice is known to occur, piping shall be protected against freezing. [NFPA 54:7.1.4]

1210.1.5 Piping Through Foundation Wall. Underground piping installed through the outer foundation or basement wall of a building shall be encased in a protective sleeve or protected by an approved device or method. The space between the gas piping and the sleeve and between the sleeve and the wall shall be sealed to prevent entry of gas and water. [NFPA 54:7.1.5]

1210.1.6 Piping Underground Beneath Buildings. Where gas piping is installed underground beneath buildings, the piping shall be one of the following:

- (1) Encased in an approved conduit designed to withstand the imposed loads and installed in accordance with Section 1210.1.6.1 or Section 1210.1.6.2.
- (2) A piping or encasement system listed for installation beneath buildings. [NFPA 54:7.1.6]

1210.1.6.1 Conduit with One End Terminating Outdoors. The conduit shall extend into an accessible portion of the building and, at the point where the conduit terminates in the building, the space between the conduit and the gas piping shall be sealed to prevent the possible entrance of a gas leakage. Where the end sealing is of a type that will retain the full pressure of the pipe, the conduit shall be designed for the same pressure as the pipe. The conduit shall extend not less than 4 inches (102 mm) outside the building, be vented outdoors above finished ground level, and be installed so as to prevent the entrance of water and insects. [NFPA 54:7.1.6.1]

1210.1.6.2 Conduit with Both Ends Terminating Indoors. Where the conduit originates and terminates within the same building, the conduit shall originate and terminate in an accessible portion of the building and shall not be sealed. [NFPA 54:7.1.6.2]

1210.1.7 Plastic Piping. Plastic piping shall be installed outdoors, underground only.

Exceptions:

- (1) Plastic piping shall be permitted to terminate aboveground where an anodeless riser is used.
- (2) Plastic piping shall be permitted to terminate with a wall head adapter aboveground in buildings, including basements, where the plastic piping is inserted in a piping material permitted for use in buildings. [NFPA 54:7.1.7.1]

1210.1.7.1 Connections Between Metallic and Plastic Piping. Connections made between metallic and plastic piping shall be made with fittings that are in accordance with one of the following:

- (1) ASTM D2513
- (2) ASTM F1973
- (3) ASTM F2509 [NFPA 54:7.1.7.2]

1210.1.7.2 Tracer Wire. An electrically continuous corrosion-resistant tracer wire (not less than AWG 14) or tape shall be buried with the plastic pipe to facilitate locating. One end of the tracer wire or tape shall be brought aboveground at a building wall or riser. [NFPA 54:7.1.7.3]

1210.2 Installation of Piping. Piping installed aboveground shall be securely supported and located where it will be protected from physical damage. Where passing through an exterior wall, the piping shall be protected against corrosion by coating or wrapping with an inert material approved for such applications. The piping shall be sealed around its circumference at the point of the exterior penetration to prevent the entry of water, insects, and rodents. Where piping is encased in a protective pipe sleeve, the annular spaces between the gas piping and the sleeve and between the sleeve and the wall opening shall be sealed. [NFPA 54:7.2.1]

1210.2.1 Building Structure. The installation of gas piping shall not cause structural stresses within building components to exceed allowable design limits. Approval shall be obtained before beams or joists are cut or notched. [NFPA 54:7.2.2]

Permission shall be obtained from the Authority Having Jurisdiction.

1210.2.2 Gas Piping to be Sloped. Piping for other than dry gas conditions shall be sloped not less than 1/4 inch in 15 feet (1.4 mm/m) to prevent traps. [NFPA 54:7.2.3]

1210.2.2.1 Ceiling Locations. Gas piping shall be permitted to be installed in accessible spaces between a fixed ceiling and a dropped ceiling, whether or not such spaces are used as a plenum. Valves shall not be located in such spaces.

Exception: Appliance or equipment shutoff valves required by this code shall be permitted to be installed in accessible spaces containing vented appliances.

1210.2.3 Prohibited Locations. Gas piping inside a building shall not be installed in or through a clothes chute, chimney or gas vent, dumbwaiter, elevator shaft, or air duct, other than combustion air ducts. [NFPA 54:7.2.4]

Exception: Ducts used to provide ventilation air in accordance with Section 506.0 or to above-ceiling spaces in accordance with Section 1210.2.2.1.

1210.2.4 Hangers, Supports, and Anchors. Piping shall be supported with metal pipe hooks, metal pipe straps, metal bands, metal brackets, metal hangers, or building structural components; approved for the size of piping; of adequate strength and quality; and located at intervals so as to prevent or damp out excessive vibration. Piping shall be anchored to prevent undue strains on connected appliances and equipment and shall not be supported by other piping. Pipe hangers and supports shall comply with the requirements of MSS SP-58. [NFPA 54:7.2.5.1]

1210.2.4.1 Spacing. Spacing of supports in gas piping installations shall not exceed the distance shown in Table 1210.2.4.1. Spacing of supports for CSST shall be in accordance with the CSST manufacturer's instructions. [NFPA 54:7.2.5.2]

TABLE 1210.2.4.1
SUPPORT OF PIPING
[NFPA 54: TABLE 7.2.5.2]

| STEEL PIPE, NOMINAL SIZE OF PIPE (inches) | SPACING OF SUPPORTS (feet) | NOMINAL SIZE OF TUBING SMOOTH-WALL (inches O.D.) | SPACING OF SUPPORTS (feet) |
|--|----------------------------------|---|----------------------------------|
| ½ | 6 | ½ | 4 |
| ¾ or 1 | 8 | ¾ or ¾ | 6 |
| 1¼ or larger (horizontal) | 10 | ¾ or 1 (horizontal) | 8 |
| 1¼ or larger (vertical) | Every floor level | 1 or larger (vertical) | Every floor level |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm

1210.2.4.2 Expansion and Contraction. Supports, hangers, and anchors shall be installed so as not to interfere with the free expansion and contraction of the piping between anchors. Parts of the supporting system shall be designed and installed so they are not disengaged by movement of the supported piping. [NFPA 54:7.2.5.3]

1210.2.5 Removal of Piping. Where piping containing gas is to be removed, the line shall be first disconnected from sources of gas and then thoroughly purged with air, water, or inert gas before cutting or welding is done. [NFPA 54:7.2.6]

1210.3 Concealed Piping in Buildings. Gas piping in concealed locations shall be installed in accordance with this section. [NFPA 54:7.3.1]

1210.3.1 Connections. Where gas piping is to be concealed, connections shall be of the following type:

- (1) Pipe fittings such as elbows, tees, couplings, and right/left nipple/couplings.

- (2) Joining tubing by brazing (see Section 1208.5.8.2).
- (3) Fittings listed for use in concealed spaces or that have been demonstrated to sustain, without leakage, forces due to temperature expansion or contraction, vibration, or fatigue based on their geographic location, application, or operation.
- (4) Where necessary to insert fittings in gas pipe that has been installed in a concealed location, the pipe shall be reconnected by welding, flanges, or the use of a right/left nipple/coupling.

1210.3.2 Piping in Partitions. Concealed gas piping shall not be located in solid partitions. [NFPA 54:7.3.3]

1210.3.3 Tubing in Partitions. This provision shall not apply to tubing that pierces walls, floors, or partitions. Tubing installed vertically and horizontally inside hollow walls or partitions without protection along its entire concealed length shall be in accordance with the following requirements:

- (1) A steel striker barrier not less than 0.0508 of an inch (1.3 mm) thick, or equivalent, shall be installed between the tubing and the finished wall and extend not less than 4 inches (102 mm) beyond concealed penetrations of plates, firestops, wall studs, and similar construction features.
- (2) The tubing shall be installed in single runs and shall not be rigidly secured. [NFPA 54:7.3.4]

1210.3.4 Piping in Floors. In industrial occupancies, gas piping in solid floors such as concrete shall be laid in channels in the floor and covered to permit access to the piping with minimum damage to the building. Where piping in floor channels is exposed to excessive moisture or corrosive substances, the piping shall be protected in an approved manner. [NFPA 54:7.3.5.1]

Exception: In other than industrial occupancies and where approved by the Authority Having Jurisdiction, gas piping embedded in concrete floor slabs constructed with portland cement shall be surrounded with not less than 1½ inches (38 mm) of concrete and shall not be in physical contact with other metallic structures such as reinforcing rods or electrically neutral conductors. Piping, fittings, and risers shall be protected against corrosion in accordance with Section 1208.5.6. Piping shall not be embedded in concrete slabs containing quick-set additives or cinder aggregate. [NFPA 54:7.3.5.2]

1210.4 Piping in Vertical Chases. Where gas piping exceeding 5 psi (34 kPa) is located within vertical chases in accordance with Section 1210.5(2), the requirements of Section 1210.4.1 through Section 1210.4.3 shall apply. [NFPA 54:7.4]

1210.4.1 Pressure Reduction. Where pressure reduction is required in branch connections in accordance with Section 1210.5, such reduction shall take place either inside the chase or immediately adjacent to the outside wall of the chase. Regulator venting and downstream overpressure protection shall comply with Section 1208.7.1 and Section 1208.7.5. The regulator shall be accessible for service and repair, and vented in accordance with one of the following:

- (1) Where the fuel gas is lighter than air, regulators equipped with a vent limiting means shall be permitted to be vented into the chase. Regulators not equipped with a vent limiting means shall be permitted to be vented either directly to the outdoors or to a point within the top 1 foot (305 mm) of the chase.
- (2) Where the fuel gas is heavier than air, the regulator vent shall be vented directly to the outdoors. [NFPA 54:7.4.1]

1210.4.2 Construction. Chase construction shall comply with local building codes with respect to fire resistance and protection of horizontal and vertical openings. [NFPA 54:7.4.2]

1210.4.3 Ventilation. A chase shall be ventilated to the outdoors and at the top. The openings shall have a minimum free area [in square inches (m²)] equal to the product of one-half of the maximum pressure in the piping [in psi (kPa)] times the largest nominal diameter of that piping [in inches (mm)], or the cross-sectional area of the chase, whichever is smaller. Where more than one fuel gas piping system is present, the free area for each system shall be calculated and the largest area used. [NFPA 54:7.4.3]

1210.5 Maximum Design Operating Pressure. The maximum design operating pressure for piping systems located inside buildings shall not exceed 5 psi (34 kPa) unless one or more of the following conditions are met:

- (1) The piping system is welded.
- (2) The piping is located in a ventilated chase or otherwise enclosed for protection against accidental gas accumulation.
- (3) The piping is located inside buildings or separate areas of buildings used exclusively for one of the following:
 - (a) Industrial processing or heating
 - (b) Research
 - (c) Warehousing
 - (d) Boiler or mechanical equipment rooms
- (4) The piping is a temporary installation for buildings under construction.
- (5) The piping serves appliances or equipment used for agricultural purposes.
- (6) The piping system is an LP-Gas piping system with a design operating pressure exceeding 20 psi (138 kPa) and in accordance with NFPA 58. LP-Gas systems designed to operate below -5°F (-21°C) or with butane or a propane-butane mix shall be designed to either accommodate liquid LP-Gas or to prevent LP-Gas vapor from condensing back into liquid. [NFPA 54:5.5]

1210.6 Appliance Overpressure Protection. The maximum operating pressure for piping systems serving appliances designed to operate at 14 inches water column (3.5 kPa) inlet pressure or less shall be 2 pounds-force per square inch gauge (psig) (14 kPa) unless an over-pressure protection device designed to limit pressure at the appliance to 2 psig (14 kPa) upon failure of the line gas pressure regulator is installed.

1210.7 Gas Pipe Turns. Changes in direction of gas pipe shall be made by the use of fittings, factory bends, or field bends. [NFPA 54:7.5]

1210.7.1 Metallic Pipe. Metallic pipe bends shall comply with the following:

- (1) Bends shall be made with bending equipment and procedures intended for that purpose.
- (2) Bends shall be smooth and free from buckling, cracks, or other evidence of mechanical damage.
- (3) The longitudinal weld of the pipe shall be near the neutral axis of the bend.
- (4) The pipe shall not be bent through an arc of more than 90 degrees (1.57 rad).
- (5) The inside radius of a bend shall be not less than six times the outside diameter of the pipe. [NFPA 54:7.5.1]

1210.7.2 Plastic Pipe. Plastic pipe bends shall comply with the following:

- (1) The pipe shall not be damaged, and the internal diameter of the pipe shall not be effectively reduced.
- (2) Joints shall not be located in pipe bends.
- (3) The radius of the inner curve of such bends shall be not less than 25 times the inside diameter of the pipe.
- (4) Where the piping manufacturer specifies the use of special bending equipment or procedures, such equipment or procedures shall be used. [NFPA 54:7.5.2]

1210.7.3 Elbows. Factory-made welding elbows or transverse segments cut therefrom shall have an arc length measured along the crotch of not less than 1 inch (25.4 mm) for pipe sizes 2 inches (50 mm) and larger. [NFPA 54:7.5.3]

1210.8 Drips and Sediment Traps. For other than dry gas conditions, a drip shall be provided at a point in the line of pipe where condensate is capable of collecting. Where required by the Authority Having Jurisdiction or the serving gas supplier, a drip shall also be provided at the outlet of the meter. This drip shall be so installed as to constitute a trap wherein an accumulation of condensate will shut off the flow of gas before it will run back into the meter. [NFPA 54:7.6.1]

1210.8.1 Location of Drips. Drips shall be installed in such locations that they will be readily accessible to permit cleaning or emptying. A drip shall not be located where the condensate is likely to freeze. [NFPA 54:7.6.2]

1210.8.2 Sediment Traps. The installation of sediment traps shall comply with Section 1212.8. [NFPA 54:7.6.3]

1210.9 Outlets. Outlets shall be located and installed in accordance with the following requirements:

- (1) The outlet fittings or piping shall be securely fastened in place.
- (2) Outlets shall not be located behind doors.
- (3) Outlets shall be located far enough from floors, walls, patios, slabs, and ceilings to permit the use of wrenches without straining, bending, or damaging the piping.
- (4) The unthreaded portion of gas piping outlets shall extend not less than 1 inch (25.4 mm) through finished ceilings or indoor or outdoor walls.
- (5) The unthreaded portion of gas piping outlets shall extend not less than 2 inches (51 mm) above the surface of floors or outdoor patios or slabs.

- (6) The provisions of Section 1210.9(4) and Section 1210.9(5) shall not apply to listed quick-disconnect devices of the flush-mounted type or listed gas convenience outlets. Such devices shall be installed in accordance with the manufacturer's installation instructions. [NFPA 54:7.7.1]

1210.9.1 Cap Outlets. Each outlet, including a valve, shall be closed gastight with a threaded plug or cap immediately after installation and shall be left closed until the appliance or equipment is connected thereto. Where an appliance or equipment is disconnected from an outlet, and the outlet is not to be used again immediately, it shall be capped or plugged gastight.

Exceptions:

- (1) Laboratory appliances installed in accordance with Section 1212.3.1 shall be permitted.
- (2) The use of a listed quick-disconnect device with integral shutoff or listed gas convenience outlet shall be permitted. [NFPA 54:7.7.2.1]

1210.9.1.1 Appliance Shutoff Valves. Appliance shutoff valves installed in fireplaces shall be removed and the piping capped gastight where the fireplace is used for solid-fuel burning. [NFPA 54:7.7.2.2]

1210.10 Branch Pipe Connection. Where a branch outlet is placed on a main supply line before it is known what size pipe will be connected to it, the outlet shall be of the same size as the line that supplies it. [NFPA 54:7.8]

1210.11 Manual Gas Shutoff Valves. An accessible gas shutoff valve shall be provided upstream of each gas pressure regulator. Where two gas pressure regulators are installed in series in a single gas line, a manual valve shall not be required at the second regulator. [NFPA 54:7.9.1]

1210.11.1 Valves Controlling Multiple Systems. Main gas shutoff valves controlling several gas piping systems shall be readily accessible for operation and installed so as to be protected from physical damage. They shall be marked with a metal tag or other permanent means attached by the installing agency so that the gas piping systems supplied through them are readily identified. [NFPA 54:7.9.2.1]

1210.11.1.1 Shutoff Valves for Multiple House Lines. In multiple-tenant buildings supplied through a master meter, through one service regulator where a meter is not provided, or where meters or service regulators are not readily accessible from the appliance or equipment location, an individual shutoff valve for each apartment or tenant line shall be provided at a convenient point of general accessibility. In a common system serving a number of individual buildings, shutoff valves shall be installed at each building. [NFPA 54:7.9.2.2]

1210.11.2 Emergency Shutoff Valves. An exterior shutoff valve to permit turning off the gas supply to each building in an emergency shall be provided. The emergency shutoff valves shall be plainly marked as such and their locations posted as required by the Authority Having Jurisdiction. [NFPA 54:7.9.2.3]

1210.11.3 Shutoff Valve for Laboratories. Each laboratory space containing two or more gas outlets installed on tables, benches, or in hoods in educational, research, commercial and industrial occupancies shall have a single shutoff valve through which such gas outlets are supplied. The shutoff valve shall be accessible and shall be located within the laboratory or located adjacent to the laboratory's egress door and shall be identified. [NFPA 54:7.9.2.4]

1210.12 Prohibited Devices. No device shall be placed inside the gas piping or fittings that will reduce the cross-sectional area or otherwise obstruct the free flow of gas, except where an allowance in the piping system design has been made for such a device and where approved by the Authority Having Jurisdiction. [NFPA 54:7.10]

1210.13 Systems Containing Gas-Air Mixtures Outside the Flammable Range. Where gas-air mixing machines are employed to produce mixtures above or below the flammable range, they shall be provided with stops to prevent adjustment of the mixture to within or approaching the flammable range. [NFPA 54:7.11]

1210.14 Systems Containing Flammable Gas-Air Mixtures. Systems containing flammable gas-air mixtures shall be in accordance with NFPA 54.

1211.0 Electrical Bonding and Grounding. <<

1211.1 Pipe and Tubing other than CSST. Each above-ground portion of a gas piping system other than CSST that is likely to become energized shall be electrically continuous and bonded to an effective ground-fault current path. Gas piping, other than CSST, shall be considered to be bonded where it is connected to appliances that are connected to the appliance grounding conductor of the circuit supplying that appliance. [NFPA 54:7.13.1] <<

1211.2 Bonding of CSST Gas Piping. CSST gas piping systems shall be bonded to the electrical service grounding electrode system. The bonding jumper shall connect to a metallic pipe or fitting between the point of delivery and the first downstream CSST fitting. The bonding jumper shall be not smaller than 6 AWG copper wire or equivalent. Gas piping systems that contain one or more segments of CSST shall be bonded in accordance with this section. [NFPA 54:7.13.2] <<

1211.3 Grounding Conductor or Electrode. Gas piping shall not be used as a grounding conductor or electrode. [NFPA 54:7.13.3] <<

1211.4 Lightning Protection System. Where a lightning protection system is installed, the bonding of the gas piping shall be in accordance with NFPA 780. [NFPA 54:7.13.4] <<

1211.5 Electrical Circuits. Electrical circuits shall not utilize gas piping or components as conductors. <<

Exception: Low-voltage (50V or less) control circuits, ignition circuits, and electronic flame detection device circuits shall be permitted to make use of piping or components as a part of an electric circuit. [NFPA 54:7.14]

1211.6 Electrical Connections. Electrical connections between wiring and electrically operated control devices in a piping system shall comply with the requirements of NFPA 70. [NFPA 54:7.15.1] <<

- » **1211.6.1 Safety Control.** An essential safety control depending on electric current as the operating medium shall be of a type that will shut off (fail safe) the flow of gas in the event of current failure. [NFPA 54:7.15.2]

» **1212.0 Appliance Connections to Building Piping.**

- » **1212.1 Connecting Gas Appliances.** Appliances shall be connected to the building piping in accordance with Section 1212.5 through Section 1212.7 by one of the following:

- (1) Rigid metallic pipe and fittings.
- (2) Semirigid metallic tubing and metallic fittings. Aluminum alloy tubing shall not be used in exterior locations.
- (3) A listed connector in accordance with CSA Z21.24. The connector shall be used in accordance with the manufacturer's installation instructions and shall be in the same room as the appliance. One connector shall be used for each appliance.
- (4) A listed connector in accordance with CSA Z21.75. One connector shall be used for each appliance.
- (5) CSST where installed in accordance with the manufacturer's installation instructions.
- (6) Listed nonmetallic gas hose connectors installed in accordance with Section 1212.3.

- (7) In Section 1212.1(2) through Section 1212.1(6), the connector or tubing shall be installed so as to be protected against physical and thermal damage. Aluminum alloy tubing and connectors shall be coated to protect against external corrosion where they are in contact with masonry, plaster, insulation, or are subject to repeated wettings by such liquids as water (except rainwater), detergents, or sewage. Connectors and tubing shall not be installed through an opening in an appliance housing, cabinet, or casing, unless the tubing or connector is protected against damage. [NFPA 54:9.6.1]

1212.1.1 Commercial Cooking Appliances. Commercial cooking appliances that are moved for cleaning and sanitation purposes shall be connected in accordance with the connector manufacturer's installation instructions using a listed appliance connector in accordance with CSA Z21.69. The commercial cooking appliance connector installation shall be configured in accordance with the manufacturer's installation instructions. [NFPA 54:9.6.1.1]

1212.1.2 Restraining Device. Movement of appliances with casters shall be limited by a restraining device installed in accordance with the connector and appliance manufacturer's installation instructions. [NFPA 54:9.6.1.2]

- » **1212.2 Suspended Low-Intensity Infrared Tube Heaters.** Suspended low-intensity infrared tube heaters shall be connected to the building piping system with a connector listed for the application in accordance with CSA Z21.24 and the following requirements:

- (1) The connector shall be installed in accordance with the tube heater installation instructions, and shall be in the same room as the appliance.
- (2) One connector shall be used per appliance. [NFPA 54:9.6.1.3]

1212.3 Use of Gas Hose Connectors. Listed gas hose connectors shall be installed in accordance with the manufacturer's installation instructions and in accordance with Section 1212.3.1 and Section 1212.3.2. [NFPA 54:9.6.2]

1212.3.1 Indoor. Indoor gas hose connectors shall be used to connect laboratory, shop, and ironing appliances or equipment requiring mobility during operation. An appliance or equipment shutoff valve shall be installed where the connector is attached to the building piping. The connector shall be of minimum length and shall not exceed 6 feet (1829 mm). The connector shall not be concealed and shall not extend from one room to another or pass through wall partitions, ceilings, or floors.

1212.3.2 Outdoor. Where outdoor gas hose connectors are used to connect portable outdoor appliances, the connector shall be listed in accordance with CSA Z21.54. An appliance shutoff valve, a listed quick-disconnect device, or a listed gas convenience outlet shall be installed where the connector is attached to the supply piping and in such a manner to prevent the accumulation of water or foreign matter. This connection shall be made only in the outdoor area where the appliance is to be used. [NFPA 54:9.6.2(2)]

The connector length shall not exceed 15 feet (4572 mm).

1212.4 Connection of Portable and Mobile Industrial Gas Appliances. Where portable industrial appliances, or appliances requiring mobility or subject to vibration, are connected to the building gas piping system by the use of a flexible hose, the hose shall be approved and safe for the conditions under which it is used. [NFPA 54:9.6.3.1]

1212.4.1 Swivel Joints or Couplings. Where industrial appliances requiring mobility are connected to the rigid piping by the use of swivel joints or couplings, the swivel joints or couplings shall be approved for the service required, and only the minimum number required shall be installed. [NFPA 54:9.6.3.2]

1212.4.2 Metal Flexible Connectors. Where industrial appliances subject to vibration are connected to the building piping system by the use of metal flexible connectors, the connectors shall be approved for the service required. [NFPA 54:9.6.3.3]

1212.4.3 Flexible Connectors. Where flexible connections are used, they shall be of the minimum practical length and shall not extend from one room to another or pass through walls, partitions, ceilings, or floors. Flexible connections shall not be used in a concealed location. They shall be protected against physical or thermal damage and shall be provided with gas shutoff valves in readily accessible locations in rigid piping upstream from the flexible connections. [NFPA 54:9.6.3.4]

1212.5 Appliance Shutoff Valves and Connections. Appliances connected to a piping system shall have an accessible, approved manual shutoff valve with a nondisplaceable valve member, or a listed gas convenience outlet. Appliance shutoff valves and convenience outlets shall serve a single appliance and shall be installed within 6 feet (1829 mm) of the appliance it serves. Where a connector is used, the valve shall

be installed upstream of the connector. A union or flanged connection shall be provided downstream from the valve to permit removal of appliance controls. Shutoff valves serving decorative appliances shall be permitted to be installed in fireplaces where listed for such use. [NFPA 54:9.6.4, 9.6.4.1]

Exceptions:


- (1) Shutoff valves shall be permitted to be accessibly located inside or under an appliance where such appliance is removed without removal of the shutoff valve.
- (2) Shutoff valves shall be permitted to be accessibly located inside wall heaters and wall furnaces listed for recessed installation where necessary maintenance is performed without removal of the shutoff valve.

» **1212.6 Quick-Disconnect Devices.** Quick-disconnect devices used to connect appliances to the building piping shall be listed to CSA Z21.41. Where installed indoors, an approved manual shutoff valve with a non-displaceable valve member shall be installed upstream of the quick-disconnect device. [NFPA 54:9.6.5]

» **1212.7 Gas Convenience Outlets.** Appliances shall be permitted to be connected to the building piping by means of a listed gas convenience outlet, in conjunction with a listed appliance connector, installed in accordance with the manufacturer's installation instructions.

Gas convenience outlets shall be listed in accordance with CSA Z21.90 and installed in accordance with the manufacturer's installation instructions. [NFPA 54:9.6.6]

» **1212.8 Sediment Trap.** Where a sediment trap is not incorporated as a part of the appliance, a sediment trap shall be installed downstream of the appliance shutoff valve as close to the inlet of the appliance as practical, before the flex connector, where used at the time of appliance installation. The sediment trap shall be either a tee fitting with a capped nipple in the bottom outlet, as illustrated in Figure 1212.8, or other device recognized as an effective sediment trap. Illuminating appliances, ranges, clothes dryers, decorative appliances for installation in vented fireplaces, gas fireplaces, and outdoor grills shall not be required to be so equipped.



For SI units: 1 inch = 25.4 mm

» **FIGURE 1212.8**
METHOD OF INSTALLING A
TEE FITTING SEDIMENT TRAP
[NFPA 54: FIGURE 9.6.7]

1212.9 Installation of Piping. Piping shall be installed in a manner not to interfere with inspection, maintenance, or servicing of the appliance. [NFPA 54:9.6.8]

1212.10 Liquefied Petroleum Gas Facilities and Piping. Liquefied petroleum gas facilities shall comply with NFPA 58.

1213.0 Pressure Testing and Inspection.

1213.1 Piping Installations. Prior to acceptance and initial operation, piping installations shall be visually inspected and pressure-tested to determine that the materials, design, fabrication, and installation practices are in accordance with the requirements of this code. [NFPA 54:8.1.1.1]

1213.1.1 Inspection Requirements. Inspection shall consist of visual examination during or after manufacture, fabrication, assembly, or pressure tests. [NFPA 54:8.1.1.2]

1213.1.2 Repairs and Additions. Where repairs or additions are made following the pressure test, the affected piping shall be tested. Minor repairs and additions are not required to be pressure-tested provided that the work is inspected and connections are tested with a non-corrosive leak-detecting fluid or other leak-detecting methods approved by the Authority Having Jurisdiction. [NFPA 54:8.1.1.3]

1213.1.3 New Branches. Where new branches are installed to new appliances, the newly installed branches shall be required to be pressure-tested. Connections between the new piping and the existing piping shall be tested with a noncorrosive leak-detecting fluid or approved leak-detecting methods. [NFPA 54:8.1.1.4]

1213.1.4 Piping System. A piping system shall be tested as a complete unit or in sections. Under no circumstances shall a valve in a line be used as a bulkhead between gas in one section of the piping system and test medium in an adjacent section, unless two valves are installed in series with a valved "telltale" located between these valves. A valve shall not be subjected to the test pressure unless it is determined that the valve, including the valve-closing mechanism, is designed to safely withstand the pressure. [NFPA 54:8.1.1.5]

1213.1.5 Regulators and Valves. Regulator and valve assemblies fabricated independently of the piping system in which they are to be installed shall be permitted to be tested with inert gas or air at the time of fabrication. [NFPA 54:8.1.1.6]

1213.1.6 Test Medium. The test medium shall be air, nitrogen, carbon dioxide, or an inert gas. OXYGEN SHALL NEVER BE USED. [NFPA 54:8.1.2]

1213.2 Test Preparation. Test preparation shall comply with Section 1213.2.1 through Section 1213.2.6.

1213.2.1 Pipe Joints. Pipe joints, including welds, shall be left exposed for examination during the test.

Exception: Covered or concealed pipe end joints that have been previously tested in accordance with this code. [NFPA 54:8.1.3.1]

1213.2.2 Expansion Joints. Expansion joints shall be provided with temporary restraints, where required, for the additional thrust load under test. [NFPA 54:8.1.3.2]

1213.2.3 Appliances and Equipment. Appliances and equipment that are not to be included in the test shall be either disconnected from the piping or isolated by blanks, blind flanges, or caps. Flanged joints at which blinds are inserted to blank off other equipment during the test shall not be required to be tested. [NFPA 54:8.1.3.3]

1213.2.4 Designed for (less than) Operating Pressures. Where the piping system is connected to appliances or equipment designed for operating pressures of less than the test pressure, such appliances or equipment shall be isolated from the piping system by disconnecting them and capping the outlets. [NFPA 54:8.1.3.4]

1213.2.5 Designed for (equal to or more than) Operating Pressures. Where the piping system is connected to appliances or equipment designed for operating pressures equal to or greater than the test pressure, such appliances and equipment shall be isolated from the piping system by closing the individual appliance or equipment shutoff valve(s). [NFPA 54:8.1.3.5]

1213.2.6 Safety. Testing of piping systems shall be performed in a manner that protects the safety of employees and the public during the test. [NFPA 54:8.1.3.6]

1213.3 Test Pressure. This inspection shall include an air, CO₂, or nitrogen pressure test, at which time the gas piping shall stand a pressure of not less than 10 psi (69 kPa) gauge pressure. Test pressures shall be held for a length of time satisfactory to the Authority Having Jurisdiction, but in no case less than 15 minutes with no perceptible drop in pressure. For welded piping, and for piping carrying gas at pressures in excess of 14 inches water column pressure (3.5 kPa), the test pressure shall be not less than 60 psi (414 kPa) and shall be continued for a length of time satisfactory to the Authority Having Jurisdiction, but in no case for less than 30 minutes. For CSST carrying gas at pressures in excess of 14 inches water column (3.5 kPa) pressure, the test pressure shall be 30 psi (207 kPa) for 30 minutes. These tests shall be made using air, CO₂, or nitrogen pressure and shall be made in the presence of the Authority Having Jurisdiction. Necessary apparatus for conducting tests shall be furnished by the permit holder. Test gauges used in conducting tests shall be in accordance with Section 318.0.

1213.4 Detection of Leaks and Defects. The piping system shall withstand the test pressure specified without showing evidence of leakage or other defects. Reduction of test pressures as indicated by pressure gauges shall be deemed to indicate the presence of a leak unless such reduction is readily attributed to some other cause. [NFPA 54:8.1.5.1]

1213.4.1 Detecting Leaks. The leakage shall be located by means of an approved gas detector, a noncorrosive leak detection fluid, or other approved leak detection methods. Matches, candles, open flames, or other methods that provide a source of ignition shall not be used. [NFPA 54:8.1.5.2]

1213.4.2 Repair or Replace. Where leakage or other defects are located, the affected portion of the piping sys-

tem shall be repaired or replaced and retested. [NFPA 54:8.1.5.3]

1213.5 Piping System Leak Test. Leak checks using fuel gas shall be permitted in piping systems that have been pressure-tested in accordance with Section 1213.0. [NFPA 54:8.2.1]

1213.5.1 Turning Gas On. During the process of turning gas on into a system of new gas piping, the entire system shall be inspected to determine that there are no open fittings or ends and that valves at unused outlets are closed and plugged or capped. [NFPA 54:8.2.2]

1213.5.2 Leak Check. Immediately after the gas is turned on into a new system or into a system that has been initially restored after an interruption of service, the piping system shall be checked for leakage. Where leakage is indicated, the gas supply shall be shut off until the necessary repairs have been made. [NFPA 54:8.2.3]

1213.5.3 Placing Appliances and Equipment in Operation. Appliances and equipment shall not be placed in operation until after the piping system has been checked in accordance with Section 1213.5.2; connections to the appliance are checked for leakage; and purged in accordance with Section 1213.6. [NFPA 54:8.2.4]

1213.6 Purging Requirements. The purging of piping shall be in accordance with Section 1213.6.1 through Section 1213.6.3. [NFPA 54:8.3]

1213.6.1 Piping Systems Required to be Purged Outdoors. The purging of piping systems shall be in accordance with the provisions of Section 1213.6.1.1 through Section 1213.6.1.4 where the piping system meets either of the following:

- (1) The design operating gas pressure exceeds 2 psig (14 kPa).
- (2) The piping being purged contains one or more sections of pipe or tubing meeting the size and length criteria of Table 1213.6.1. [NFPA 54:8.3.1]

1213.6.1.1 Removal from Service. Where existing gas piping is opened, the section that is opened shall be isolated from the gas supply and the line pressure vented in accordance with Section 1213.6.1.3. Where gas piping meeting the criteria of Table 1213.6.1 is removed from service, the residual fuel gas in the piping shall be displaced with an inert gas. [NFPA 54:8.3.1.1]

TABLE 1213.6.1
SIZE AND LENGTH OF PIPING
[NFPA 54: TABLE 8.3.1]*

| NOMINAL PIPING SIZE (inches) | LENGTH OF PIPING (feet) |
|---------------------------------|----------------------------|
| $\geq 2\frac{1}{2} < 3$ | > 50 |
| $\geq 3 < 4$ | > 30 |
| $\geq 4 < 6$ | > 15 |
| $\geq 6 < 8$ | > 10 |
| ≥ 8 | Any length |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm

* CSST EHD size of 62 is equivalent to nominal 2 inches (50 mm) pipe or tubing size.

1213.6.1.2 Placing in Operation. Where gas piping containing air and meeting the criteria of Table 1213.6.1 is placed in operation, the air in the piping shall first be displaced with an inert gas. The inert gas shall then be displaced with fuel gas in accordance with Section 1213.6.1.3. [NFPA 54:8.3.1.2]

1213.6.1.3 Outdoor Discharge of Purged Gases. The open end of a piping system being pressure vented or purged shall discharge directly to an outdoor location. Purging operations shall comply with the following requirements:

- (1) The point of discharge shall be controlled with a shutoff valve.
- (2) The point of discharge shall be located not less than 10 feet (3048 mm) from sources of ignition, not less than 10 feet (3048 mm) from building openings, and not less than 25 feet (7620 mm) from mechanical air intake openings.
- (3) During discharge, the open point of discharge shall be continuously attended and monitored with a combustible gas indicator that is in accordance with Section 1213.6.1.4.
- (4) Purging operations introducing fuel gas shall be stopped where 90 percent fuel gas by volume is detected within the pipe.
- (5) Persons not involved in the purging operations shall be evacuated from areas within 10 feet (3048 mm) of the point of discharge. [NFPA 54:8.3.1.3]

1213.6.1.4 Combustible Gas Indicator. Combustible gas indicators shall be listed and shall be calibrated in accordance with the manufacturer's instructions. Combustible gas indicators shall numerically display a volume scale from 0 percent to 100 percent in 1 percent or smaller increments. [NFPA 54:8.3.1.4]

1213.6.2 Piping Systems Allowed to be Purged Indoors or Outdoors. The purging of piping systems shall be in accordance with the provisions of Section 1213.6.2.1 where the piping system meets both of the following:

- (1) The design operating pressure is 2 psig (14 kPa) or less.
- (2) The piping being purged is constructed entirely from pipe or tubing not meeting the size and length criteria of Table 1213.6.1. [NFPA 54:8.3.2]

1213.6.2.1 Purging Procedure. The piping system shall be purged in accordance with one or more of the following:

- (1) The piping shall be purged with fuel gas and shall discharge to the outdoors.
- (2) The piping shall be purged with fuel gas and shall discharge to the indoors or outdoors through an appliance burner not located in a combustion chamber. Such burner shall be provided with a continuous source of ignition.

- (3) The piping shall be purged with fuel gas and shall discharge to the indoors or outdoors through a burner that has a continuous source of ignition and that is designed for such purpose.
- (4) The piping shall be purged with fuel gas that is discharge to the indoors or outdoors, and the point of discharge shall be monitored with a listed combustible gas detector in accordance with Section 1213.6.2.2. Purging shall be stopped where fuel gas is detected.
- (5) The piping shall be purged by the gas supplier in accordance with written procedures. [NFPA 54:8.3.2.1]

1213.6.2.2 Combustible Gas Detector. Combustible gas detectors shall be listed and shall be calibrated or tested in accordance with the manufacturer's instructions. Combustible gas detectors shall be capable of indicating the presence of fuel gas. [NFPA 54:8.3.2.2]

1213.6.3 Purging Appliances and Equipment. After the piping system has been placed in operation, appliances and equipment shall be purged before being placed into operation. [NFPA 54:8.3.3]

1214.0 Interconnections Between Gas Piping Systems.

1214.1 Interconnections Supplying Separate Users. Where two or more meters, or two or more service regulators where meters are not provided, are located on the same premises and supply separate users, the gas piping systems shall not be interconnected on the outlet side of the meters or service regulators. [NFPA 54:5.3.1]

1214.2 Interconnections for Standby Fuels. Where supplementary gas for standby use is connected downstream from a meter or a service regulator where a meter is not provided, a device to prevent backflow shall be installed. A three-way valve installed to admit the standby supply and at the same time shut off the regular supply shall be permitted to be used for this purpose. [NFPA 54:5.3.2]

1215.0 Required Gas Supply.

1215.1 General. The following regulations, shall comply with this section and Section 1216.0, shall be the standard for the installation of gas piping. Natural gas regulations and tables are based on the use of gas having a specific gravity of 0.60, supplied at 6 to 8 inches water column (1.5 kPa to 1.9 kPa) pressure at the outlet of the meter or regulator. For undiluted liquefied petroleum gas, gas piping shall be permitted to be sized at 11 inches water column (2.7 kPa) pressure at the outlet of the meter or regulator and specific gravity of 1.50. Where gas of a different specific gravity is to be delivered, the specific gravity conversion factors provided by the serving gas supplier shall be used in sizing piping systems from the pipe sizing tables in this chapter.

1215.2 Volume. The hourly volume of gas required at each piping outlet shall be taken as not less than the maximum hourly rating as specified by the manufacturer of the appliance or appliances to be connected to each such outlet.

1215.3 Gas Appliances. Where the gas appliances to be installed have not been definitely specified, Table 1208.4.1 shall be permitted to be used as a reference to estimate requirements of typical appliances.

To obtain the cubic feet per hour (m³/h) of gas required, divide the input of the appliances by the average Btu (kW•h) heating value per cubic foot (m³) of the gas. The average Btu (kW•h) per cubic foot (m³) of the gas in the area of the installation shall be permitted to be obtained from the serving gas supplier.

1215.4 Size of Piping Outlets. The size of the supply piping outlet for a gas appliance shall be not less than ½ of an inch (15 mm).

The size of a piping outlet for a mobile home shall be not less than ¾ of an inch (20 mm).

1216.0 Required Gas Piping Size.

1216.1 Pipe Sizing Methods. Where the pipe size is to be determined using a method in Section 1216.1.1 through Section 1216.1.3, the diameter of each pipe segment shall be obtained from the pipe sizing tables in Section 1216.2 or from the sizing equations in Section 1216.3. [NFPA 54:6.1]

1216.1.1 Longest Length Method. The pipe size of each section of gas piping shall be determined using the longest length of piping from the point of delivery to the most remote outlet and the load of the section (see calculation example in Figure 1216.1.1). [NFPA 54:6.1.1]

1216.1.2 Branch Length Method. Pipe shall be sized as follows:

- (1) The pipe size of each section of the longest pipe run from the point of delivery to the most remote outlet shall be determined using the longest run of piping and the load of the section.
- (2) The pipe size of each section of branch piping not previously sized shall be determined using the length of piping from the point of delivery to the most remote outlet in each branch and the load of the section. [NFPA 54:6.1.2]

1216.1.3 Hybrid Pressure. The pipe size for each section of higher pressure gas piping shall be determined using the longest length of piping from the point of delivery to the most remote line pressure regulator. The pipe size from the line pressure regulator to each outlet shall be determined using the length of piping from the regulator to the most remote outlet served by the regulator. [NFPA 54:6.1.3]

1216.2 Tables for Sizing Gas Piping Systems. Table 1216.2(1) through Table 1216.2(36) shall be used to size gas piping in conjunction with one of the methods described in Section 1216.1.1 through Section 1216.1.3. [NFPA 54:6.2]

1216.3 Sizing Equations. The inside diameter of smooth-wall pipe or tubing shall be determined by Equation 1216.3(1), Equation 1216.3(2), Table 1216.3, and using the equivalent pipe length determined by Section 1216.1.1 through Section 1216.1.3. [NFPA 54:6.4]

EQUATION 1216.3(1)
LOW-PRESSURE GAS FORMULA (LESS THAN 1.5 psi)
[NFPA 54:6.4.1]

$$D = \frac{Q^{0.381}}{19.17 \left(\frac{\Delta H}{Cr \times L} \right)^{0.206}}$$

Where:

- D = inside diameter of pipe, inches
 Q = input rate appliance(s), cubic feet per hour at 60°F and 30 inch mercury column
 L = equivalent length of pipe, feet
 ΔH = pressure drop, inches water column
 Cr = in accordance with Table 1216.3

EQUATION 1216.3(2)
HIGH-PRESSURE GAS FORMULA (1.5 psi AND ABOVE)
[NFPA 54:6.4.2]

$$D = \frac{Q^{0.381}}{18.93 \left[\frac{(P_1^2 - P_2^2) \cdot Y}{Cr \times L} \right]^{0.206}}$$

Where:

- D = inside diameter of pipe, inches
 Q = input rate appliance(s), cubic feet per hour at 60°F and 30 inch mercury column
 P_1 = upstream pressure, psia ($P_1 + 14.7$)
 P_2 = downstream pressure, psia ($P_2 + 14.7$)
 L = equivalent length of pipe, feet
 Cr = in accordance with Table 1216.3
 Y = in accordance with Table 1216.3

For SI units: 1 cubic foot = 0.0283 m³, 1000 British thermal units per hour = 0.293 kW, 1 inch = 25 mm, 1 foot = 304.8 mm, 1 pound-force per square inch = 6.8947 kPa, °C = (°F-32)/1.8, 1 inch mercury column = 3.39 kPa, 1 inch water column = 0.249 kPa

TABLE 1216.3
Cr AND Y FOR NATURAL GAS AND UNDILUTED PROPANE
AT STANDARD CONDITIONS
[NFPA 54: TABLE 6.4.2]

| GAS | FORMULA FACTORS | |
|-------------------|-----------------|--------|
| | Cr | Y |
| Natural Gas | 0.6094 | 0.9992 |
| Undiluted Propane | 1.2462 | 0.9910 |

1216.4 Sizing of Piping Sections. To determine the size of each section of pipe in a system within the range of Table 1216.2(1) through Table 1216.2(36), proceed as follows:


- (1) Measure the length of the pipe from the gas meter location to the most remote outlet on the system.
- (2) Select the length in feet column and row showing the distance, or the next longer distance where the table does not give the exact length.
- (3) Starting at the most remote outlet, find in the row just selected the gas demand for that outlet. Where the exact figure of demand is not shown, choose the next larger figure in the row.
- (4) At the top of this column will be found the correct size of pipe.
- (5) Using this same row, proceed in a similar manner for each section of pipe serving this outlet. For each section of pipe, determine the total gas demand supplied by that section. Where gas piping sections serve both heating and cooling appliances and the installation prevents both units from operating simultaneously, the larger of the two demand loads needs to be used in sizing these sections.
- (6) Size each section of branch piping not previously sized by measuring the distance from the gas meter location to the most remote outlet in that branch and follow the procedures of steps 2, 3, 4, and 5 above. Size branch piping in the order of their distance from the meter location, beginning with the most distant outlet not previously sized.

1216.5 Engineering Methods. For conditions other than those covered by Section 1216.1, such as longer runs or greater gas demands, the size of each gas piping system shall be determined by standard engineering methods acceptable to the Authority Having Jurisdiction, and each such system shall be so designed that the total pressure drop between the meter or other point of supply and an outlet where full demand is being supplied to all outlets, shall be in accordance with the requirements of Section 1208.4.

1216.6 Variable Gas Pressure. Where the gas pressure exceeds 14 inches (3.5 kPa) or less than 6 inches (1.5 kPa) of water column, or where diversity demand factors are used, the design, pipe, sizing, materials, location, and use of such systems first shall be approved by the Authority Having Jurisdiction. Piping systems designed for pressures exceeding the serving gas supplier's standard delivery pressure shall have prior verification from the gas supplier of the availability of the design pressure.

FIGURE 1216.1.1
EXAMPLE ILLUSTRATING USE OF TABLE 1208.4.1 AND TABLE 1216.2(1)

Problem: Determine the required pipe size of each section and outlet of the piping system shown in Figure 1216.1.1. Gas to be used has a specific gravity of 0.60 and 1100 British thermal units (Btu) per cubic foot (0.0114 kW•h/L), delivered at 8 inch water column (1.9 kPa) pressure.



For SI units: 1 foot = 304.8 mm, 1 gallon = 3.785 L, 1000 British thermal units per hour = 0.293 kW, 1 cubic foot per hour = 0.0283 m³/h

Solution:

- (1) Maximum gas demand of Outlet A —
 32 cubic feet per hour (0.91 m³/h) (from Table 1208.4.1).
 Maximum gas demand of Outlet B —
 3 cubic feet per hour (0.08 m³/h) (from Table 1208.4.1).
 Maximum gas demand of Outlet C —
 59 cubic feet per hour (1.67 m³/h) (from Table 1208.4.1).
 Maximum gas demand of Outlet D —
 136 cubic feet per hour (3.85 m³/h) [150 000 Btu/hour (44 kW) divided by 1100 Btu per cubic foot (0.0114 kW•h/L)].
- (2) The length of pipe from the gas meter to the most remote outlet (Outlet A) is 60 feet (18 288 mm).
- (3) Using the length in feet column row marked 60 feet (18 288 mm) in Table 1216.2(1):
 Outlet A, supplying 32 cubic feet per hour (0.91 m³/h), requires ½ of an inch (15 mm) pipe.
 Section 1, supplying Outlets A and B, or 35 cubic feet per hour (0.99 m³/h) requires ½ of an inch (15 mm) pipe.
 Section 2, supplying Outlets A, B, and C, or 94 cubic feet per hour (2.66 m³/h) requires ¾ of an inch (20 mm) pipe.
 Section 3, supplying Outlets A, B, C, and D, or 230 cubic feet per hour (6.51 m³/h), requires 1 inch (25 mm) pipe.
- (4) Using the column marked 60 feet (18 288 mm) in Table 1216.2(1) [no column for actual length of 55 feet (16 764 mm)]:
 Outlet B supplying 3 cubic feet per hour (0.08 m³/h), requires ½ of an inch (15 mm) pipe.
 Outlet C, supplying 59 cubic feet per hour (1.67 m³/h), requires ½ of an inch (15 mm) pipe.
- (5) Using the column marked 60 feet (18 288 mm) in Table 1216.2(1):
 Outlet D, supplying 136 cubic feet per hour (3.85 m³/h), requires ¾ of an inch (20 mm) pipe.

TABLE 1216.2(1)
SCHEDULE 40 METALLIC PIPE [NFPA 54: TABLE 6.2(b)]^{1, 2}

| | | | | | | | | | GAS: | | NATURAL | | | |
|------------------|--|-------|-------|-------|-------|-------|-------|--------|-------------------|--------|-----------------|---------|---------|---------|
| | | | | | | | | | INLET PRESSURE: | | LESS THAN 2 psi | | | |
| | | | | | | | | | PRESSURE DROP: | | 0.5 in. w.c. | | | |
| | | | | | | | | | SPECIFIC GRAVITY: | | 0.60 | | | |
| | PIPE SIZE (inch) | | | | | | | | | | | | | |
| NOMINAL: | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 2½ | 3 | 4 | 5 | 6 | 8 | 10 | 12 |
| ACTUAL ID: | 0.622 | 0.824 | 1.049 | 1.380 | 1.610 | 2.067 | 2.469 | 3.068 | 4.026 | 5.047 | 6.065 | 7.981 | 10.020 | 11.938 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | | | | | | |
| 10 | 172 | 360 | 678 | 1390 | 2090 | 4020 | 6400 | 11 300 | 23 100 | 41 800 | 67 600 | 139 000 | 252 000 | 399 000 |
| 20 | 118 | 247 | 466 | 957 | 1430 | 2760 | 4400 | 7780 | 15 900 | 28 700 | 46 500 | 95 500 | 173 000 | 275 000 |
| 30 | 95 | 199 | 374 | 768 | 1150 | 2220 | 3530 | 6250 | 12 700 | 23 000 | 37 300 | 76 700 | 139 000 | 220 000 |
| 40 | 81 | 170 | 320 | 657 | 985 | 1900 | 3020 | 5350 | 10 900 | 19 700 | 31 900 | 65 600 | 119 000 | 189 000 |
| 50 | 72 | 151 | 284 | 583 | 873 | 1680 | 2680 | 4740 | 9660 | 17 500 | 28 300 | 58 200 | 106 000 | 167 000 |
| 60 | 65 | 137 | 257 | 528 | 791 | 1520 | 2430 | 4290 | 8760 | 15 800 | 25 600 | 52 700 | 95 700 | 152 000 |
| 70 | 60 | 126 | 237 | 486 | 728 | 1400 | 2230 | 3950 | 8050 | 14 600 | 23 600 | 48 500 | 88 100 | 139 000 |
| 80 | 56 | 117 | 220 | 452 | 677 | 1300 | 2080 | 3670 | 7490 | 13 600 | 22 000 | 45 100 | 81 900 | 130 000 |
| 90 | 52 | 110 | 207 | 424 | 635 | 1220 | 1950 | 3450 | 7030 | 12 700 | 20 600 | 42 300 | 76 900 | 122 000 |
| 100 | 50 | 104 | 195 | 400 | 600 | 1160 | 1840 | 3260 | 6640 | 12 000 | 19 500 | 40 000 | 72 600 | 115 000 |
| 125 | 44 | 92 | 173 | 355 | 532 | 1020 | 1630 | 2890 | 5890 | 10 600 | 17 200 | 35 400 | 64 300 | 102 000 |
| 150 | 40 | 83 | 157 | 322 | 482 | 928 | 1480 | 2610 | 5330 | 9650 | 15 600 | 32 100 | 58 300 | 92 300 |
| 175 | 37 | 77 | 144 | 296 | 443 | 854 | 1360 | 2410 | 4910 | 8880 | 14 400 | 29 500 | 53 600 | 84 900 |
| 200 | 34 | 71 | 134 | 275 | 412 | 794 | 1270 | 2240 | 4560 | 8260 | 13 400 | 27 500 | 49 900 | 79 000 |
| 250 | 30 | 63 | 119 | 244 | 366 | 704 | 1120 | 1980 | 4050 | 7320 | 11 900 | 24 300 | 44 200 | 70 000 |
| 300 | 27 | 57 | 108 | 221 | 331 | 638 | 1020 | 1800 | 3670 | 6630 | 10 700 | 22 100 | 40 100 | 63 400 |
| 350 | 25 | 53 | 99 | 203 | 305 | 587 | 935 | 1650 | 3370 | 6100 | 9880 | 20 300 | 36 900 | 58 400 |
| 400 | 23 | 49 | 92 | 189 | 283 | 546 | 870 | 1540 | 3140 | 5680 | 9190 | 18 900 | 34 300 | 54 300 |
| 450 | 22 | 46 | 86 | 177 | 266 | 512 | 816 | 1440 | 2940 | 5330 | 8620 | 17 700 | 32 200 | 50 900 |
| 500 | 21 | 43 | 82 | 168 | 251 | 484 | 771 | 1360 | 2780 | 5030 | 8150 | 16 700 | 30 400 | 48 100 |
| 550 | 20 | 41 | 78 | 159 | 239 | 459 | 732 | 1290 | 2640 | 4780 | 7740 | 15 900 | 28 900 | 45 700 |
| 600 | 19 | 39 | 74 | 152 | 228 | 438 | 699 | 1240 | 2520 | 4560 | 7380 | 15 200 | 27 500 | 43 600 |
| 650 | 18 | 38 | 71 | 145 | 218 | 420 | 669 | 1180 | 2410 | 4360 | 7070 | 14 500 | 26 400 | 41 800 |
| 700 | 17 | 36 | 68 | 140 | 209 | 403 | 643 | 1140 | 2320 | 4190 | 6790 | 14 000 | 25 300 | 40 100 |
| 750 | 17 | 35 | 66 | 135 | 202 | 389 | 619 | 1090 | 2230 | 4040 | 6540 | 13 400 | 24 400 | 38 600 |
| 800 | 16 | 34 | 63 | 130 | 195 | 375 | 598 | 1060 | 2160 | 3900 | 6320 | 13 000 | 23 600 | 37 300 |
| 850 | 16 | 33 | 61 | 126 | 189 | 363 | 579 | 1020 | 2090 | 3780 | 6110 | 12 600 | 22 800 | 36 100 |
| 900 | 15 | 32 | 59 | 122 | 183 | 352 | 561 | 992 | 2020 | 3660 | 5930 | 12 200 | 22 100 | 35 000 |
| 950 | 15 | 31 | 58 | 118 | 178 | 342 | 545 | 963 | 1960 | 3550 | 5760 | 11 800 | 21 500 | 34 000 |
| 1000 | 14 | 30 | 56 | 115 | 173 | 333 | 530 | 937 | 1910 | 3460 | 5600 | 11 500 | 20 900 | 33 100 |
| 1100 | 14 | 28 | 53 | 109 | 164 | 316 | 503 | 890 | 1810 | 3280 | 5320 | 10 900 | 19 800 | 31 400 |
| 1200 | 13 | 27 | 51 | 104 | 156 | 301 | 480 | 849 | 1730 | 3130 | 5070 | 10 400 | 18 900 | 30 000 |
| 1300 | 12 | 26 | 49 | 100 | 150 | 289 | 460 | 813 | 1660 | 3000 | 4860 | 9980 | 18 100 | 28 700 |
| 1400 | 12 | 25 | 47 | 96 | 144 | 277 | 442 | 781 | 1590 | 2880 | 4670 | 9590 | 17 400 | 27 600 |
| 1500 | 11 | 24 | 45 | 93 | 139 | 267 | 426 | 752 | 1530 | 2780 | 4500 | 9240 | 16 800 | 26 600 |
| 1600 | 11 | 23 | 44 | 89 | 134 | 258 | 411 | 727 | 1480 | 2680 | 4340 | 8920 | 16 200 | 25 600 |
| 1700 | 11 | 22 | 42 | 86 | 130 | 250 | 398 | 703 | 1430 | 2590 | 4200 | 8630 | 15 700 | 24 800 |
| 1800 | 10 | 22 | 41 | 84 | 126 | 242 | 386 | 682 | 1390 | 2520 | 4070 | 8370 | 15 200 | 24 100 |
| 1900 | 10 | 21 | 40 | 81 | 122 | 235 | 375 | 662 | 1350 | 2440 | 3960 | 8130 | 14 800 | 23 400 |
| 2000 | NA | 20 | 39 | 79 | 119 | 229 | 364 | 644 | 1310 | 2380 | 3850 | 7910 | 14 400 | 22 700 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

Notes:

¹ Table entries are rounded to 3 significant digits.

² NA means a flow of less than 10 ft³/h (0.283 m³/h).

FUEL GAS PIPING

TABLE 1216.2(2)
SCHEDULE 40 METALLIC PIPE [NFPA 54: TABLE 6.2(c)]*

| | | | | | | GAS: NATURAL | | | |
|--|--|-------|-------|-------|-------|---------------------------------|--------|--------|--------|
| | | | | | | INLET PRESSURE: LESS THAN 2 psi | | | |
| | | | | | | PRESSURE DROP: 3.0 in. w.c. | | | |
| | | | | | | SPECIFIC GRAVITY: 0.60 | | | |
| INTENDED USE: INITIAL SUPPLY PRESSURE OF 8.0 IN. W.C. OR GREATER | | | | | | | | | |
| | PIPE SIZE (inch) | | | | | | | | |
| NOMINAL: | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 2½ | 3 | 4 |
| ACTUAL ID: | 0.622 | 0.824 | 1.049 | 1.380 | 1.610 | 2.067 | 2.469 | 3.068 | 4.026 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | |
| 10 | 454 | 949 | 1787 | 3669 | 5497 | 10 588 | 16 875 | 29 832 | 43 678 |
| 20 | 312 | 652 | 1228 | 2522 | 3778 | 7277 | 11 598 | 20 503 | 30 020 |
| 30 | 250 | 524 | 986 | 2025 | 3034 | 5844 | 9314 | 16 465 | 24 107 |
| 40 | 214 | 448 | 844 | 1733 | 2597 | 5001 | 7971 | 14 092 | 20 632 |
| 50 | 190 | 397 | 748 | 1536 | 2302 | 4433 | 7065 | 12 489 | 18 286 |
| 60 | 172 | 360 | 678 | 1392 | 2085 | 4016 | 6401 | 11 316 | 16 569 |
| 70 | 158 | 331 | 624 | 1280 | 1919 | 3695 | 5889 | 10 411 | 15 243 |
| 80 | 147 | 308 | 580 | 1191 | 1785 | 3437 | 5479 | 9685 | 14 181 |
| 90 | 138 | 289 | 544 | 1118 | 1675 | 3225 | 5140 | 9087 | 13 305 |
| 100 | 131 | 273 | 514 | 1056 | 1582 | 3046 | 4856 | 8584 | 12 568 |
| 125 | 116 | 242 | 456 | 936 | 1402 | 2700 | 4303 | 7608 | 11 139 |
| 150 | 105 | 219 | 413 | 848 | 1270 | 2446 | 3899 | 6893 | 10 093 |
| 175 | 96 | 202 | 380 | 780 | 1169 | 2251 | 3587 | 6342 | 9285 |
| 200 | 90 | 188 | 353 | 726 | 1087 | 2094 | 3337 | 5900 | 8638 |
| 250 | 80 | 166 | 313 | 643 | 964 | 1856 | 2958 | 5229 | 7656 |
| 300 | 72 | 151 | 284 | 583 | 873 | 1681 | 2680 | 4738 | 6937 |
| 350 | 66 | 139 | 261 | 536 | 803 | 1547 | 2465 | 4359 | 6382 |
| 400 | 62 | 129 | 243 | 499 | 747 | 1439 | 2294 | 4055 | 5937 |
| 450 | 58 | 121 | 228 | 468 | 701 | 1350 | 2152 | 3804 | 5570 |
| 500 | 55 | 114 | 215 | 442 | 662 | 1275 | 2033 | 3594 | 5262 |
| 550 | 52 | 109 | 204 | 420 | 629 | 1211 | 1931 | 3413 | 4997 |
| 600 | 50 | 104 | 195 | 400 | 600 | 1156 | 1842 | 3256 | 4767 |
| 650 | 47 | 99 | 187 | 384 | 575 | 1107 | 1764 | 3118 | 4565 |
| 700 | 46 | 95 | 179 | 368 | 552 | 1063 | 1695 | 2996 | 4386 |
| 750 | 44 | 92 | 173 | 355 | 532 | 1024 | 1632 | 2886 | 4225 |
| 800 | 42 | 89 | 167 | 343 | 514 | 989 | 1576 | 2787 | 4080 |
| 850 | 41 | 86 | 162 | 332 | 497 | 957 | 1526 | 2697 | 3949 |
| 900 | 40 | 83 | 157 | 322 | 482 | 928 | 1479 | 2615 | 3828 |
| 950 | 39 | 81 | 152 | 312 | 468 | 901 | 1436 | 2539 | 3718 |
| 1000 | 38 | 79 | 148 | 304 | 455 | 877 | 1397 | 2470 | 3616 |
| 1100 | 36 | 75 | 141 | 289 | 432 | 833 | 1327 | 2346 | 3435 |
| 1200 | 34 | 71 | 134 | 275 | 412 | 794 | 1266 | 2238 | 3277 |
| 1300 | 33 | 68 | 128 | 264 | 395 | 761 | 1212 | 2143 | 3138 |
| 1400 | 31 | 65 | 123 | 253 | 379 | 731 | 1165 | 2059 | 3014 |
| 1500 | 30 | 63 | 119 | 244 | 366 | 704 | 1122 | 1983 | 2904 |
| 1600 | 29 | 61 | 115 | 236 | 353 | 680 | 1083 | 1915 | 2804 |
| 1700 | 28 | 59 | 111 | 228 | 342 | 658 | 1048 | 1854 | 2714 |
| 1800 | 27 | 57 | 108 | 221 | 331 | 638 | 1017 | 1797 | 2631 |
| 1900 | 27 | 56 | 105 | 215 | 322 | 619 | 987 | 1745 | 2555 |
| 2000 | 26 | 54 | 102 | 209 | 313 | 602 | 960 | 1698 | 2485 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

* Table entries are rounded to 3 significant digits.

TABLE 1216.2(3)
SCHEDULE 40 METALLIC PIPE [NFPA 54: TABLE 6.2(d)]*

| | | | | | | | | | |
|---|--|-------|-------|-------|-------|---------------------------------|--------|--------|--------|
| | | | | | | GAS: NATURAL | | | |
| | | | | | | INLET PRESSURE: LESS THAN 2 psi | | | |
| | | | | | | PRESSURE DROP: 6.0 in. w.c. | | | |
| | | | | | | SPECIFIC GRAVITY: 0.60 | | | |
| INTENDED USE: INITIAL SUPPLY PRESSURE OF 11.0 IN. W.C. OR GREATER | | | | | | | | | |
| | PIPE SIZE (inch) | | | | | | | | |
| NOMINAL: | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 2½ | 3 | 4 |
| ACTUAL ID: | 0.622 | 0.824 | 1.049 | 1.380 | 1.610 | 2.067 | 2.469 | 3.068 | 4.026 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | |
| 10 | 660 | 1380 | 2600 | 5338 | 7999 | 15 405 | 24 553 | 43 405 | 63 551 |
| 20 | 454 | 949 | 1787 | 3669 | 5497 | 10 588 | 16 875 | 29 832 | 43 678 |
| 30 | 364 | 762 | 1435 | 2946 | 4415 | 8502 | 13 551 | 23 956 | 35 075 |
| 40 | 312 | 652 | 1228 | 2522 | 3778 | 7277 | 11 598 | 20 503 | 30 020 |
| 50 | 276 | 578 | 1089 | 2235 | 3349 | 6449 | 10 279 | 18 172 | 26 606 |
| 60 | 250 | 524 | 986 | 2025 | 3034 | 5844 | 9314 | 16 465 | 24 107 |
| 70 | 230 | 482 | 907 | 1863 | 2791 | 5376 | 8568 | 15 147 | 22 178 |
| 80 | 214 | 448 | 844 | 1733 | 2597 | 5001 | 7971 | 14 092 | 20 632 |
| 90 | 201 | 420 | 792 | 1626 | 2437 | 4693 | 7479 | 13 222 | 19 359 |
| 100 | 190 | 397 | 748 | 1536 | 2302 | 4433 | 7065 | 12 489 | 18 286 |
| 125 | 168 | 352 | 663 | 1361 | 2040 | 3928 | 6261 | 11 069 | 16 207 |
| 150 | 153 | 319 | 601 | 1234 | 1848 | 3559 | 5673 | 10 029 | 14 684 |
| 175 | 140 | 293 | 553 | 1135 | 1700 | 3275 | 5219 | 9227 | 13 509 |
| 200 | 131 | 273 | 514 | 1056 | 1582 | 3046 | 4856 | 8584 | 12 568 |
| 250 | 116 | 242 | 456 | 936 | 1402 | 2700 | 4303 | 7608 | 11 139 |
| 300 | 105 | 219 | 413 | 848 | 1270 | 2446 | 3899 | 6893 | 10 093 |
| 350 | 96 | 202 | 380 | 780 | 1169 | 2251 | 3587 | 6342 | 9285 |
| 400 | 90 | 188 | 353 | 726 | 1087 | 2094 | 3337 | 5900 | 8638 |
| 450 | 84 | 176 | 332 | 681 | 1020 | 1965 | 3131 | 5535 | 8105 |
| 500 | 80 | 166 | 313 | 643 | 964 | 1856 | 2958 | 5229 | 7656 |
| 550 | 76 | 158 | 297 | 611 | 915 | 1762 | 2809 | 4966 | 7271 |
| 600 | 72 | 151 | 284 | 583 | 873 | 1681 | 2680 | 4738 | 6937 |
| 650 | 69 | 144 | 272 | 558 | 836 | 1610 | 2566 | 4537 | 6643 |
| 700 | 66 | 139 | 261 | 536 | 803 | 1547 | 2465 | 4359 | 6382 |
| 750 | 64 | 134 | 252 | 516 | 774 | 1490 | 2375 | 4199 | 6148 |
| 800 | 62 | 129 | 243 | 499 | 747 | 1439 | 2294 | 4055 | 5937 |
| 850 | 60 | 125 | 235 | 483 | 723 | 1393 | 2220 | 3924 | 5745 |
| 900 | 58 | 121 | 228 | 468 | 701 | 1350 | 2152 | 3804 | 5570 |
| 950 | 56 | 118 | 221 | 454 | 681 | 1311 | 2090 | 3695 | 5410 |
| 1000 | 55 | 114 | 215 | 442 | 662 | 1275 | 2033 | 3594 | 5262 |
| 1100 | 52 | 109 | 204 | 420 | 629 | 1211 | 1931 | 3413 | 4997 |
| 1200 | 50 | 104 | 195 | 400 | 600 | 1156 | 1842 | 3256 | 4767 |
| 1300 | 47 | 99 | 187 | 384 | 575 | 1107 | 1764 | 3118 | 4565 |
| 1400 | 46 | 95 | 179 | 368 | 552 | 1063 | 1695 | 2996 | 4386 |
| 1500 | 44 | 92 | 173 | 355 | 532 | 1024 | 1632 | 2886 | 4225 |
| 1600 | 42 | 89 | 167 | 343 | 514 | 989 | 1576 | 2787 | 4080 |
| 1700 | 41 | 86 | 162 | 332 | 497 | 957 | 1526 | 2697 | 3949 |
| 1800 | 40 | 83 | 157 | 322 | 482 | 928 | 1479 | 2615 | 3828 |
| 1900 | 39 | 81 | 152 | 312 | 468 | 901 | 1436 | 2539 | 3718 |
| 2000 | 38 | 79 | 148 | 304 | 455 | 877 | 1397 | 2470 | 3616 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

* Table entries are rounded to 3 significant digits.

FUEL GAS PIPING

TABLE 1216.2(4)
SCHEDULE 40 METALLIC PIPE [NFPA 54: TABLE 6.2(e)]*

| | | | | | | GAS: NATURAL | | | |
|------------------|--|-------|-------|--------|--------|-------------------------|--------|--------|---------|
| | | | | | | INLET PRESSURE: 2.0 psi | | | |
| | | | | | | PRESSURE DROP: 1.0 psi | | | |
| | | | | | | SPECIFIC GRAVITY: 0.60 | | | |
| | PIPE SIZE (inch) | | | | | | | | |
| NOMINAL: | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 2½ | 3 | 4 |
| ACTUAL ID: | 0.622 | 0.824 | 1.049 | 1.380 | 1.610 | 2.067 | 2.469 | 3.068 | 4.026 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | |
| 10 | 1510 | 3040 | 5560 | 11 400 | 17 100 | 32 900 | 52 500 | 92 800 | 189 000 |
| 20 | 1070 | 2150 | 3930 | 8070 | 12 100 | 23 300 | 37 100 | 65 600 | 134 000 |
| 30 | 869 | 1760 | 3210 | 6590 | 9880 | 19 000 | 30 300 | 53 600 | 109 000 |
| 40 | 753 | 1520 | 2780 | 5710 | 8550 | 16 500 | 26 300 | 46 400 | 94 700 |
| 50 | 673 | 1360 | 2490 | 5110 | 7650 | 14 700 | 23 500 | 41 500 | 84 700 |
| 60 | 615 | 1240 | 2270 | 4660 | 6980 | 13 500 | 21 400 | 37 900 | 77 300 |
| 70 | 569 | 1150 | 2100 | 4320 | 6470 | 12 500 | 19 900 | 35 100 | 71 600 |
| 80 | 532 | 1080 | 1970 | 4040 | 6050 | 11 700 | 18 600 | 32 800 | 67 000 |
| 90 | 502 | 1010 | 1850 | 3810 | 5700 | 11 000 | 17 500 | 30 900 | 63 100 |
| 100 | 462 | 934 | 1710 | 3510 | 5260 | 10 100 | 16 100 | 28 500 | 58 200 |
| 125 | 414 | 836 | 1530 | 3140 | 4700 | 9060 | 14 400 | 25 500 | 52 100 |
| 150 | 372 | 751 | 1370 | 2820 | 4220 | 8130 | 13 000 | 22 900 | 46 700 |
| 175 | 344 | 695 | 1270 | 2601 | 3910 | 7530 | 12 000 | 21 200 | 43 300 |
| 200 | 318 | 642 | 1170 | 2410 | 3610 | 6960 | 11 100 | 19 600 | 40 000 |
| 250 | 279 | 583 | 1040 | 2140 | 3210 | 6180 | 9850 | 17 400 | 35 500 |
| 300 | 253 | 528 | 945 | 1940 | 2910 | 5600 | 8920 | 15 800 | 32 200 |
| 350 | 232 | 486 | 869 | 1790 | 2670 | 5150 | 8210 | 14 500 | 29 600 |
| 400 | 216 | 452 | 809 | 1660 | 2490 | 4790 | 7640 | 13 500 | 27 500 |
| 450 | 203 | 424 | 759 | 1560 | 2330 | 4500 | 7170 | 12 700 | 25 800 |
| 500 | 192 | 401 | 717 | 1470 | 2210 | 4250 | 6770 | 12 000 | 24 400 |
| 550 | 182 | 381 | 681 | 1400 | 2090 | 4030 | 6430 | 11 400 | 23 200 |
| 600 | 174 | 363 | 650 | 1330 | 2000 | 3850 | 6130 | 10 800 | 22 100 |
| 650 | 166 | 348 | 622 | 1280 | 1910 | 3680 | 5870 | 10 400 | 21 200 |
| 700 | 160 | 334 | 598 | 1230 | 1840 | 3540 | 5640 | 9970 | 20 300 |
| 750 | 154 | 322 | 576 | 1180 | 1770 | 3410 | 5440 | 9610 | 19 600 |
| 800 | 149 | 311 | 556 | 1140 | 1710 | 3290 | 5250 | 9280 | 18 900 |
| 850 | 144 | 301 | 538 | 1100 | 1650 | 3190 | 5080 | 8980 | 18 300 |
| 900 | 139 | 292 | 522 | 1070 | 1600 | 3090 | 4930 | 8710 | 17 800 |
| 950 | 135 | 283 | 507 | 1040 | 1560 | 3000 | 4780 | 8460 | 17 200 |
| 1000 | 132 | 275 | 493 | 1010 | 1520 | 2920 | 4650 | 8220 | 16 800 |
| 1100 | 125 | 262 | 468 | 960 | 1440 | 2770 | 4420 | 7810 | 15 900 |
| 1200 | 119 | 250 | 446 | 917 | 1370 | 2640 | 4220 | 7450 | 15 200 |
| 1300 | 114 | 239 | 427 | 878 | 1320 | 2530 | 4040 | 7140 | 14 600 |
| 1400 | 110 | 230 | 411 | 843 | 1260 | 2430 | 3880 | 6860 | 14 000 |
| 1500 | 106 | 221 | 396 | 812 | 1220 | 2340 | 3740 | 6600 | 13 500 |
| 1600 | 102 | 214 | 382 | 784 | 1180 | 2260 | 3610 | 6380 | 13 000 |
| 1700 | 99 | 207 | 370 | 759 | 1140 | 2190 | 3490 | 6170 | 12 600 |
| 1800 | 96 | 200 | 358 | 736 | 1100 | 2120 | 3390 | 5980 | 12 200 |
| 1900 | 93 | 195 | 348 | 715 | 1070 | 2060 | 3290 | 5810 | 11 900 |
| 2000 | 91 | 189 | 339 | 695 | 1040 | 2010 | 3200 | 5650 | 11 500 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa

* Table entries are rounded to 3 significant digits.

TABLE 1216.2(5)
SCHEDULE 40 METALLIC PIPE [NFPA 54: TABLE 6.2(f)]*

| | | | | | | GAS: NATURAL | | | |
|------------------|--|-------|-------|--------|--------|-------------------------|--------|---------|---------|
| | | | | | | INLET PRESSURE: 3.0 psi | | | |
| | | | | | | PRESSURE DROP: 2.0 psi | | | |
| | | | | | | SPECIFIC GRAVITY: 0.60 | | | |
| | PIPE SIZE (inch) | | | | | | | | |
| NOMINAL: | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 2½ | 3 | 4 |
| ACTUAL ID: | 0.622 | 0.824 | 1.049 | 1.380 | 1.610 | 2.067 | 2.469 | 3.068 | 4.026 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | |
| 10 | 2350 | 4920 | 9270 | 19 000 | 28 500 | 54 900 | 87 500 | 155 000 | 316 000 |
| 20 | 1620 | 3380 | 6370 | 13 100 | 19 600 | 37 700 | 60 100 | 106 000 | 217 000 |
| 30 | 1300 | 2720 | 5110 | 10 500 | 15 700 | 30 300 | 48 300 | 85 400 | 174 000 |
| 40 | 1110 | 2320 | 4380 | 8990 | 13 500 | 25 900 | 41 300 | 73 100 | 149 000 |
| 50 | 985 | 2060 | 3880 | 7970 | 11 900 | 23 000 | 36 600 | 64 800 | 132 000 |
| 60 | 892 | 1870 | 3520 | 7220 | 10 800 | 20 800 | 33 200 | 58 700 | 120 000 |
| 70 | 821 | 1720 | 3230 | 6640 | 9950 | 19 200 | 30 500 | 54 000 | 110 000 |
| 80 | 764 | 1600 | 3010 | 6180 | 9260 | 17 800 | 28 400 | 50 200 | 102 000 |
| 90 | 717 | 1500 | 2820 | 5800 | 8680 | 16 700 | 26 700 | 47 100 | 96 100 |
| 100 | 677 | 1420 | 2670 | 5470 | 8200 | 15 800 | 25 200 | 44 500 | 90 800 |
| 125 | 600 | 1250 | 2360 | 4850 | 7270 | 14 000 | 22 300 | 39 500 | 80 500 |
| 150 | 544 | 1140 | 2140 | 4400 | 6590 | 12 700 | 20 200 | 35 700 | 72 900 |
| 175 | 500 | 1050 | 1970 | 4040 | 6060 | 11 700 | 18 600 | 32 900 | 67 100 |
| 200 | 465 | 973 | 1830 | 3760 | 5640 | 10 900 | 17 300 | 30 600 | 62 400 |
| 250 | 412 | 862 | 1620 | 3330 | 5000 | 9620 | 15 300 | 27 100 | 55 300 |
| 300 | 374 | 781 | 1470 | 3020 | 4530 | 8720 | 13 900 | 24 600 | 50 100 |
| 350 | 344 | 719 | 1350 | 2780 | 4170 | 8020 | 12 800 | 22 600 | 46 100 |
| 400 | 320 | 669 | 1260 | 2590 | 3870 | 7460 | 11 900 | 21 000 | 42 900 |
| 450 | 300 | 627 | 1180 | 2430 | 3640 | 7000 | 11 200 | 19 700 | 40 200 |
| 500 | 283 | 593 | 1120 | 2290 | 3430 | 6610 | 10 500 | 18 600 | 38 000 |
| 550 | 269 | 563 | 1060 | 2180 | 3260 | 6280 | 10 000 | 17 700 | 36 100 |
| 600 | 257 | 537 | 1010 | 2080 | 3110 | 5990 | 9550 | 16 900 | 34 400 |
| 650 | 246 | 514 | 969 | 1990 | 2980 | 5740 | 9150 | 16 200 | 33 000 |
| 700 | 236 | 494 | 931 | 1910 | 2860 | 5510 | 8790 | 15 500 | 31 700 |
| 750 | 228 | 476 | 897 | 1840 | 2760 | 5310 | 8470 | 15 000 | 30 500 |
| 800 | 220 | 460 | 866 | 1780 | 2660 | 5130 | 8180 | 14 500 | 29 500 |
| 850 | 213 | 445 | 838 | 1720 | 2580 | 4960 | 7910 | 14 000 | 28 500 |
| 900 | 206 | 431 | 812 | 1670 | 2500 | 4810 | 7670 | 13 600 | 27 700 |
| 950 | 200 | 419 | 789 | 1620 | 2430 | 4670 | 7450 | 13 200 | 26 900 |
| 1000 | 195 | 407 | 767 | 1580 | 2360 | 4550 | 7240 | 12 800 | 26 100 |
| 1100 | 185 | 387 | 729 | 1500 | 2240 | 4320 | 6890 | 12 200 | 24 800 |
| 1200 | 177 | 369 | 695 | 1430 | 2140 | 4120 | 6570 | 11 600 | 23 700 |
| 1300 | 169 | 353 | 666 | 1370 | 2050 | 3940 | 6290 | 11 100 | 22 700 |
| 1400 | 162 | 340 | 640 | 1310 | 1970 | 3790 | 6040 | 10 700 | 21 800 |
| 1500 | 156 | 327 | 616 | 1270 | 1900 | 3650 | 5820 | 10 300 | 21 000 |
| 1600 | 151 | 316 | 595 | 1220 | 1830 | 3530 | 5620 | 10 000 | 20 300 |
| 1700 | 146 | 306 | 576 | 1180 | 1770 | 3410 | 5440 | 9610 | 19 600 |
| 1800 | 142 | 296 | 558 | 1150 | 1720 | 3310 | 5270 | 9320 | 19 000 |
| 1900 | 138 | 288 | 542 | 1110 | 1670 | 3210 | 5120 | 9050 | 18 400 |
| 2000 | 134 | 280 | 527 | 1080 | 1620 | 3120 | 4980 | 8800 | 18 000 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa

* Table entries are rounded to 3 significant digits.

FUEL GAS PIPING

TABLE 1216.2(6)
SCHEDULE 40 METALLIC PIPE [NFPA 54: TABLE 6.2(g)]*

| | | | | | | GAS: NATURAL | | | |
|---------------|--|-------|--------|--------|--------|-------------------------|---------|---------|---------|
| | | | | | | INLET PRESSURE: 5.0 psi | | | |
| | | | | | | PRESSURE DROP: 3.5 psi | | | |
| | | | | | | SPECIFIC GRAVITY: 0.60 | | | |
| | PIPE SIZE (Inch) | | | | | | | | |
| NOMINAL: | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 2½ | 3 | 4 |
| ACTUAL ID: | 0.622 | 0.824 | 1.049 | 1.380 | 1.610 | 2.067 | 2.469 | 3.068 | 4.026 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | |
| 10 | 3190 | 6430 | 11 800 | 24 200 | 36 200 | 69 700 | 111 000 | 196 000 | 401 000 |
| 20 | 2250 | 4550 | 8320 | 17 100 | 25 600 | 49 300 | 78 600 | 139 000 | 283 000 |
| 30 | 1840 | 3720 | 6790 | 14 000 | 20 900 | 40 300 | 64 200 | 113 000 | 231 000 |
| 40 | 1590 | 3220 | 5880 | 12 100 | 18 100 | 34 900 | 55 600 | 98 200 | 200 000 |
| 50 | 1430 | 2880 | 5260 | 10 800 | 16 200 | 31 200 | 49 700 | 87 900 | 179 000 |
| 60 | 1300 | 2630 | 4800 | 9860 | 14 800 | 28 500 | 45 400 | 80 200 | 164 000 |
| 70 | 1200 | 2430 | 4450 | 9130 | 13 700 | 26 400 | 42 000 | 74 300 | 151 000 |
| 80 | 1150 | 2330 | 4260 | 8540 | 12 800 | 24 700 | 39 300 | 69 500 | 142 000 |
| 90 | 1060 | 2150 | 3920 | 8050 | 12 100 | 23 200 | 37 000 | 65 500 | 134 000 |
| 100 | 979 | 1980 | 3620 | 7430 | 11 100 | 21 400 | 34 200 | 60 400 | 123 000 |
| 125 | 876 | 1770 | 3240 | 6640 | 9950 | 19 200 | 30 600 | 54 000 | 110 000 |
| 150 | 786 | 1590 | 2910 | 5960 | 8940 | 17 200 | 27 400 | 48 500 | 98 900 |
| 175 | 728 | 1470 | 2690 | 5520 | 8270 | 15 900 | 25 400 | 44 900 | 91 600 |
| 200 | 673 | 1360 | 2490 | 5100 | 7650 | 14 700 | 23 500 | 41 500 | 84 700 |
| 250 | 558 | 1170 | 2200 | 4510 | 6760 | 13 000 | 20 800 | 36 700 | 74 900 |
| 300 | 506 | 1060 | 1990 | 4090 | 6130 | 11 800 | 18 800 | 33 300 | 67 800 |
| 350 | 465 | 973 | 1830 | 3760 | 5640 | 10 900 | 17 300 | 30 600 | 62 400 |
| 400 | 433 | 905 | 1710 | 3500 | 5250 | 10 100 | 16 100 | 28 500 | 58 100 |
| 450 | 406 | 849 | 1600 | 3290 | 4920 | 9480 | 15 100 | 26 700 | 54 500 |
| 500 | 384 | 802 | 1510 | 3100 | 4650 | 8950 | 14 300 | 25 200 | 51 500 |
| 550 | 364 | 762 | 1440 | 2950 | 4420 | 8500 | 13 600 | 24 000 | 48 900 |
| 600 | 348 | 727 | 1370 | 2810 | 4210 | 8110 | 12 900 | 22 900 | 46 600 |
| 650 | 333 | 696 | 1310 | 2690 | 4030 | 7770 | 12 400 | 21 900 | 44 600 |
| 700 | 320 | 669 | 1260 | 2590 | 3880 | 7460 | 11 900 | 21 000 | 42 900 |
| 750 | 308 | 644 | 1210 | 2490 | 3730 | 7190 | 11 500 | 20 300 | 41 300 |
| 800 | 298 | 622 | 1170 | 2410 | 3610 | 6940 | 11 100 | 19 600 | 39 900 |
| 850 | 288 | 602 | 1130 | 2330 | 3490 | 6720 | 10 700 | 18 900 | 38 600 |
| 900 | 279 | 584 | 1100 | 2260 | 3380 | 6520 | 10 400 | 18 400 | 37 400 |
| 950 | 271 | 567 | 1070 | 2190 | 3290 | 6330 | 10 100 | 17 800 | 36 400 |
| 1000 | 264 | 551 | 1040 | 2130 | 3200 | 6150 | 9810 | 17 300 | 35 400 |
| 1100 | 250 | 524 | 987 | 2030 | 3030 | 5840 | 9320 | 16 500 | 33 600 |
| 1200 | 239 | 500 | 941 | 1930 | 2900 | 5580 | 8890 | 15 700 | 32 000 |
| 1300 | 229 | 478 | 901 | 1850 | 2770 | 5340 | 8510 | 15 000 | 30 700 |
| 1400 | 220 | 460 | 866 | 1780 | 2660 | 5130 | 8180 | 14 500 | 29 500 |
| 1500 | 212 | 443 | 834 | 1710 | 2570 | 4940 | 7880 | 13 900 | 28 400 |
| 1600 | 205 | 428 | 806 | 1650 | 2480 | 4770 | 7610 | 13 400 | 27 400 |
| 1700 | 198 | 414 | 780 | 1600 | 2400 | 4620 | 7360 | 13 000 | 26 500 |
| 1800 | 192 | 401 | 756 | 1550 | 2330 | 4480 | 7140 | 12 600 | 25 700 |
| 1900 | 186 | 390 | 734 | 1510 | 2260 | 4350 | 6930 | 12 300 | 25 000 |
| 2000 | 181 | 379 | 714 | 1470 | 2200 | 4230 | 6740 | 11 900 | 24 300 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa

* Table entries are rounded to 3 significant digits.

TABLE 1216.2(7)
SEMI-RIGID COPPER TUBING [NFPA 54: TABLE 6.2(h)]^{1, 2}

| | | | | | | | GAS: NATURAL | | | |
|----------------------|------------------|--|-------|-------|-------|-------|---------------------------------|-------|-------|-------|
| | | | | | | | INLET PRESSURE: LESS THAN 2 psi | | | |
| | | | | | | | PRESSURE DROP: 0.3 in. w.c. | | | |
| | | | | | | | SPECIFIC GRAVITY: 0.60 | | | |
| | TUBE SIZE (inch) | | | | | | | | | |
| NOMINAL: | K & L: | ¼ | ⅜ | ½ | ⅝ | ¾ | 1 | 1¼ | 1½ | 2 |
| | ACR: | ⅜ | ½ | ⅝ | ¾ | ⅞ | 1½ | 1¾ | — | — |
| OUTSIDE: | | 0.375 | 0.500 | 0.625 | 0.750 | 0.875 | 1.125 | 1.375 | 1.625 | 2.125 |
| INSIDE: ³ | | 0.305 | 0.402 | 0.527 | 0.652 | 0.745 | 0.995 | 1.245 | 1.481 | 1.959 |
| LENGTH (feet) | | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | |
| 10 | 20 | 42 | 85 | 148 | 210 | 448 | 806 | 1270 | 2650 | |
| 20 | 14 | 29 | 58 | 102 | 144 | 308 | 554 | 873 | 1820 | |
| 30 | 11 | 23 | 47 | 82 | 116 | 247 | 445 | 701 | 1460 | |
| 40 | 10 | 20 | 40 | 70 | 99 | 211 | 381 | 600 | 1250 | |
| 50 | NA | 17 | 35 | 62 | 88 | 187 | 337 | 532 | 1110 | |
| 60 | NA | 16 | 32 | 56 | 79 | 170 | 306 | 482 | 1000 | |
| 70 | NA | 14 | 29 | 52 | 73 | 156 | 281 | 443 | 924 | |
| 80 | NA | 13 | 27 | 48 | 68 | 145 | 262 | 413 | 859 | |
| 90 | NA | 13 | 26 | 45 | 64 | 136 | 245 | 387 | 806 | |
| 100 | NA | 12 | 24 | 43 | 60 | 129 | 232 | 366 | 761 | |
| 125 | NA | 11 | 22 | 38 | 53 | 114 | 206 | 324 | 675 | |
| 150 | NA | 10 | 20 | 34 | 48 | 103 | 186 | 294 | 612 | |
| 175 | NA | NA | 18 | 31 | 45 | 95 | 171 | 270 | 563 | |
| 200 | NA | NA | 17 | 29 | 41 | 89 | 159 | 251 | 523 | |
| 250 | NA | NA | 15 | 26 | 37 | 78 | 141 | 223 | 464 | |
| 300 | NA | NA | 13 | 23 | 33 | 71 | 128 | 202 | 420 | |
| 350 | NA | NA | 12 | 22 | 31 | 65 | 118 | 186 | 387 | |
| 400 | NA | NA | 11 | 20 | 28 | 61 | 110 | 173 | 360 | |
| 450 | NA | NA | 11 | 19 | 27 | 57 | 103 | 162 | 338 | |
| 500 | NA | NA | 10 | 18 | 25 | 54 | 97 | 153 | 319 | |
| 550 | NA | NA | NA | 17 | 24 | 51 | 92 | 145 | 303 | |
| 600 | NA | NA | NA | 16 | 23 | 49 | 88 | 139 | 289 | |
| 650 | NA | NA | NA | 15 | 22 | 47 | 84 | 133 | 277 | |
| 700 | NA | NA | NA | 15 | 21 | 45 | 81 | 128 | 266 | |
| 750 | NA | NA | NA | 14 | 20 | 43 | 78 | 123 | 256 | |
| 800 | NA | NA | NA | 14 | 20 | 42 | 75 | 119 | 247 | |
| 850 | NA | NA | NA | 13 | 19 | 40 | 73 | 115 | 239 | |
| 900 | NA | NA | NA | 13 | 18 | 39 | 71 | 111 | 232 | |
| 950 | NA | NA | NA | 13 | 18 | 38 | 69 | 108 | 225 | |
| 1000 | NA | NA | NA | 12 | 17 | 37 | 67 | 105 | 219 | |
| 1100 | NA | NA | NA | 12 | 16 | 35 | 63 | 100 | 208 | |
| 1200 | NA | NA | NA | 11 | 16 | 34 | 60 | 95 | 199 | |
| 1300 | NA | NA | NA | 11 | 15 | 32 | 58 | 91 | 190 | |
| 1400 | NA | NA | NA | 10 | 14 | 31 | 56 | 88 | 183 | |
| 1500 | NA | NA | NA | NA | 14 | 30 | 54 | 84 | 176 | |
| 1600 | NA | NA | NA | NA | 13 | 29 | 52 | 82 | 170 | |
| 1700 | NA | NA | NA | NA | 13 | 28 | 50 | 79 | 164 | |
| 1800 | NA | NA | NA | NA | 13 | 27 | 49 | 77 | 159 | |
| 1900 | NA | NA | NA | NA | 12 | 26 | 47 | 74 | 155 | |
| 2000 | NA | NA | NA | NA | 12 | 25 | 46 | 72 | 151 | |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

Notes:

¹ Table entries are rounded to 3 significant digits.

² NA means a flow of less than 10 ft³/h (0.283 m³/h).

³ Table capacities are based on Type K copper tubing inside diameter (shown), which has the smallest inside diameter of the copper tubing products.

FUEL GAS PIPING

TABLE 1216.2(8)
SEMI-RIGID COPPER TUBING [NFPA 54: TABLE 6.2(i)]^{1, 2}

| | | GAS: NATURAL | | | | | | | | |
|----------------------|--------|--|-------|-------|-------|-------|-------|-------|-------|-------|
| | | INLET PRESSURE: LESS THAN 2 psi | | | | | | | | |
| | | PRESSURE DROP: 0.5 in. w.c. | | | | | | | | |
| | | SPECIFIC GRAVITY: 0.60 | | | | | | | | |
| | | TUBE SIZE (inch) | | | | | | | | |
| NOMINAL: | K & L: | ¼ | ⅜ | ½ | ⅝ | ¾ | 1 | 1¼ | 1½ | 2 |
| | ACR: | ⅜ | ½ | ⅝ | ¾ | ⅞ | 1½ | 1¾ | — | — |
| OUTSIDE: | | 0.375 | 0.500 | 0.625 | 0.750 | 0.875 | 1.125 | 1.375 | 1.625 | 2.125 |
| INSIDE: ³ | | 0.305 | 0.402 | 0.527 | 0.652 | 0.745 | 0.995 | 1.245 | 1.481 | 1.959 |
| LENGTH (feet) | | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | |
| 10 | | 27 | 55 | 111 | 195 | 276 | 590 | 1060 | 1680 | 3490 |
| 20 | | 18 | 38 | 77 | 134 | 190 | 406 | 730 | 1150 | 2400 |
| 30 | | 15 | 30 | 61 | 107 | 152 | 326 | 586 | 925 | 1930 |
| 40 | | 13 | 26 | 53 | 92 | 131 | 279 | 502 | 791 | 1650 |
| 50 | | 11 | 23 | 47 | 82 | 116 | 247 | 445 | 701 | 1460 |
| 60 | | 10 | 21 | 42 | 74 | 105 | 224 | 403 | 635 | 1320 |
| 70 | | NA | 19 | 39 | 68 | 96 | 206 | 371 | 585 | 1220 |
| 80 | | NA | 18 | 36 | 63 | 90 | 192 | 345 | 544 | 1130 |
| 90 | | NA | 17 | 34 | 59 | 84 | 180 | 324 | 510 | 1060 |
| 100 | | NA | 16 | 32 | 56 | 79 | 170 | 306 | 482 | 1000 |
| 125 | | NA | 14 | 28 | 50 | 70 | 151 | 271 | 427 | 890 |
| 150 | | NA | 13 | 26 | 45 | 64 | 136 | 245 | 387 | 806 |
| 175 | | NA | 12 | 24 | 41 | 59 | 125 | 226 | 356 | 742 |
| 200 | | NA | 11 | 22 | 39 | 55 | 117 | 210 | 331 | 690 |
| 250 | | NA | NA | 20 | 34 | 48 | 103 | 186 | 294 | 612 |
| 300 | | NA | NA | 18 | 31 | 44 | 94 | 169 | 266 | 554 |
| 350 | | NA | NA | 16 | 28 | 40 | 86 | 155 | 245 | 510 |
| 400 | | NA | NA | 15 | 26 | 38 | 80 | 144 | 228 | 474 |
| 450 | | NA | NA | 14 | 25 | 35 | 75 | 135 | 214 | 445 |
| 500 | | NA | NA | 13 | 23 | 33 | 71 | 128 | 202 | 420 |
| 550 | | NA | NA | 13 | 22 | 32 | 68 | 122 | 192 | 399 |
| 600 | | NA | NA | 12 | 21 | 30 | 64 | 116 | 183 | 381 |
| 650 | | NA | NA | 12 | 20 | 29 | 62 | 111 | 175 | 365 |
| 700 | | NA | NA | 11 | 20 | 28 | 59 | 107 | 168 | 350 |
| 750 | | NA | NA | 11 | 19 | 27 | 57 | 103 | 162 | 338 |
| 800 | | NA | NA | 10 | 18 | 26 | 55 | 99 | 156 | 326 |
| 850 | | NA | NA | 10 | 18 | 25 | 53 | 96 | 151 | 315 |
| 900 | | NA | NA | NA | 17 | 24 | 52 | 93 | 147 | 306 |
| 950 | | NA | NA | NA | 17 | 24 | 50 | 90 | 143 | 297 |
| 1000 | | NA | NA | NA | 16 | 23 | 49 | 88 | 139 | 289 |
| 1100 | | NA | NA | NA | 15 | 22 | 46 | 84 | 132 | 274 |
| 1200 | | NA | NA | NA | 15 | 21 | 44 | 80 | 126 | 262 |
| 1300 | | NA | NA | NA | 14 | 20 | 42 | 76 | 120 | 251 |
| 1400 | | NA | NA | NA | 13 | 19 | 41 | 73 | 116 | 241 |
| 1500 | | NA | NA | NA | 13 | 18 | 39 | 71 | 111 | 232 |
| 1600 | | NA | NA | NA | 13 | 18 | 38 | 68 | 108 | 224 |
| 1700 | | NA | NA | NA | 12 | 17 | 37 | 66 | 104 | 217 |
| 1800 | | NA | NA | NA | 12 | 17 | 36 | 64 | 101 | 210 |
| 1900 | | NA | NA | NA | 11 | 16 | 35 | 62 | 98 | 204 |
| 2000 | | NA | NA | NA | 11 | 16 | 34 | 60 | 95 | 199 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

Notes:

¹ Table entries are rounded to 3 significant digits.

² NA means a flow of less than 10 ft³/h (0.283 m³/h).

³ Table capacities are based on Type K copper tubing inside diameter (shown), which has the smallest inside diameter of the copper tubing products.

TABLE 1216.2(9)
SEMI-RIGID COPPER TUBING [NFPA 54: TABLE 6.2(j)]^{1, 2}

| | | | | | | | GAS: NATURAL | | | |
|--|--------|--|-------|-------|-------|-------|---------------------------------|-------|-------|-------|
| | | | | | | | INLET PRESSURE: LESS THAN 2 psi | | | |
| | | | | | | | PRESSURE DROP: 1.0 in. w.c. | | | |
| | | | | | | | SPECIFIC GRAVITY: 0.60 | | | |
| INTENDED USE: TUBE SIZING BETWEEN HOUSE LINE REGULATOR AND THE APPLIANCE | | | | | | | | | | |
| | | TUBE SIZE (Inch) | | | | | | | | |
| NOMINAL: | K & L: | ¼ | ⅜ | ½ | ⅝ | ¾ | 1 | 1¼ | 1½ | 2 |
| | ACR: | ⅜ | ½ | ⅝ | ¾ | 7⁄8 | 1½ | 1¾ | — | — |
| OUTSIDE: | | 0.375 | 0.500 | 0.625 | 0.750 | 0.875 | 1.125 | 1.375 | 1.625 | 2.125 |
| INSIDE: ³ | | 0.305 | 0.402 | 0.527 | 0.652 | 0.745 | 0.995 | 1.245 | 1.481 | 1.959 |
| LENGTH (feet) | | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | |
| 10 | | 39 | 80 | 162 | 283 | 402 | 859 | 1550 | 2440 | 5080 |
| 20 | | 27 | 55 | 111 | 195 | 276 | 590 | 1060 | 1680 | 3490 |
| 30 | | 21 | 44 | 89 | 156 | 222 | 474 | 853 | 1350 | 2800 |
| 40 | | 18 | 38 | 77 | 134 | 190 | 406 | 730 | 1150 | 2400 |
| 50 | | 16 | 33 | 68 | 119 | 168 | 359 | 647 | 1020 | 2130 |
| 60 | | 15 | 30 | 61 | 107 | 152 | 326 | 586 | 925 | 1930 |
| 70 | | 13 | 28 | 57 | 99 | 140 | 300 | 539 | 851 | 1770 |
| 80 | | 13 | 26 | 53 | 92 | 131 | 279 | 502 | 791 | 1650 |
| 90 | | 12 | 24 | 49 | 86 | 122 | 262 | 471 | 742 | 1550 |
| 100 | | 11 | 23 | 47 | 82 | 116 | 247 | 445 | 701 | 1460 |
| 125 | | NA | 20 | 41 | 72 | 103 | 219 | 394 | 622 | 1290 |
| 150 | | NA | 18 | 37 | 65 | 93 | 198 | 357 | 563 | 1170 |
| 175 | | NA | 17 | 34 | 60 | 85 | 183 | 329 | 518 | 1080 |
| 200 | | NA | 16 | 32 | 56 | 79 | 170 | 306 | 482 | 1000 |
| 250 | | NA | 14 | 28 | 50 | 70 | 151 | 271 | 427 | 890 |
| 300 | | NA | 13 | 26 | 45 | 64 | 136 | 245 | 387 | 806 |
| 350 | | NA | 12 | 24 | 41 | 59 | 125 | 226 | 356 | 742 |
| 400 | | NA | 11 | 22 | 39 | 55 | 117 | 210 | 331 | 690 |
| 450 | | NA | 10 | 21 | 36 | 51 | 110 | 197 | 311 | 647 |
| 500 | | NA | NA | 20 | 34 | 48 | 103 | 186 | 294 | 612 |
| 550 | | NA | NA | 19 | 32 | 46 | 98 | 177 | 279 | 581 |
| 600 | | NA | NA | 18 | 31 | 44 | 94 | 169 | 266 | 554 |
| 650 | | NA | NA | 17 | 30 | 42 | 90 | 162 | 255 | 531 |
| 700 | | NA | NA | 16 | 28 | 40 | 86 | 155 | 245 | 510 |
| 750 | | NA | NA | 16 | 27 | 39 | 83 | 150 | 236 | 491 |
| 800 | | NA | NA | 15 | 26 | 38 | 80 | 144 | 228 | 474 |
| 850 | | NA | NA | 15 | 26 | 36 | 78 | 140 | 220 | 459 |
| 900 | | NA | NA | 14 | 25 | 35 | 75 | 135 | 214 | 445 |
| 950 | | NA | NA | 14 | 24 | 34 | 73 | 132 | 207 | 432 |
| 1000 | | NA | NA | 13 | 23 | 33 | 71 | 128 | 202 | 420 |
| 1100 | | NA | NA | 13 | 22 | 32 | 68 | 122 | 192 | 399 |
| 1200 | | NA | NA | 12 | 21 | 30 | 64 | 116 | 183 | 381 |
| 1300 | | NA | NA | 12 | 20 | 29 | 62 | 111 | 175 | 365 |
| 1400 | | NA | NA | 11 | 20 | 28 | 59 | 107 | 168 | 350 |
| 1500 | | NA | NA | 11 | 19 | 27 | 57 | 103 | 162 | 338 |
| 1600 | | NA | NA | 10 | 18 | 26 | 55 | 99 | 156 | 326 |
| 1700 | | NA | NA | 10 | 18 | 25 | 53 | 96 | 151 | 315 |
| 1800 | | NA | NA | NA | 17 | 24 | 52 | 93 | 147 | 306 |
| 1900 | | NA | NA | NA | 17 | 24 | 50 | 90 | 143 | 297 |
| 2000 | | NA | NA | NA | 16 | 23 | 49 | 88 | 139 | 289 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

Notes:

¹ Table entries are rounded to 3 significant digits.

² NA means a flow of less than 10 ft³/h (0.283 m³/h).

³ Table capacities are based on Type K copper tubing inside diameter (shown), which has the smallest inside diameter of the copper tubing products.

FUEL GAS PIPING

TABLE 1216.2(10)
SEMI-RIGID COPPER TUBING [NFPA 54: TABLE 6.2(k)]²

| | | GAS: NATURAL | | | | | | | | |
|----------------------|--------|--|-------|-------|-------|-------|-------|-------|--------|--------|
| | | INLET PRESSURE: LESS THAN 2 psi | | | | | | | | |
| | | PRESSURE DROP: 17.0 in. w.c. | | | | | | | | |
| | | SPECIFIC GRAVITY: 0.60 | | | | | | | | |
| | | TUBE SIZE (inch) | | | | | | | | |
| NOMINAL: | K & L: | ¼ | ⅜ | ½ | ⅝ | ¾ | 1 | 1¼ | 1½ | 2 |
| | ACR: | ⅜ | ½ | ⅝ | ¾ | ⅞ | 1½ | 1¾ | — | — |
| OUTSIDE: | | 0.375 | 0.500 | 0.625 | 0.750 | 0.875 | 1.125 | 1.375 | 1.625 | 2.125 |
| INSIDE: ¹ | | 0.305 | 0.402 | 0.527 | 0.652 | 0.745 | 0.995 | 1.245 | 1.481 | 1.959 |
| LENGTH (feet) | | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | |
| 10 | | 190 | 391 | 796 | 1390 | 1970 | 4220 | 7590 | 12 000 | 24 900 |
| 20 | | 130 | 269 | 547 | 956 | 1360 | 2900 | 5220 | 8230 | 17 100 |
| 30 | | 105 | 216 | 439 | 768 | 1090 | 2330 | 4190 | 6610 | 13 800 |
| 40 | | 90 | 185 | 376 | 657 | 932 | 1990 | 3590 | 5650 | 11 800 |
| 50 | | 79 | 164 | 333 | 582 | 826 | 1770 | 3180 | 5010 | 10 400 |
| 60 | | 72 | 148 | 302 | 528 | 749 | 1600 | 2880 | 4540 | 9460 |
| 70 | | 66 | 137 | 278 | 486 | 689 | 1470 | 2650 | 4180 | 8700 |
| 80 | | 62 | 127 | 258 | 452 | 641 | 1370 | 2460 | 3890 | 8090 |
| 90 | | 58 | 119 | 243 | 424 | 601 | 1280 | 2310 | 3650 | 7590 |
| 100 | | 55 | 113 | 229 | 400 | 568 | 1210 | 2180 | 3440 | 7170 |
| 125 | | 48 | 100 | 203 | 355 | 503 | 1080 | 1940 | 3050 | 6360 |
| 150 | | 44 | 90 | 184 | 321 | 456 | 974 | 1750 | 2770 | 5760 |
| 175 | | 40 | 83 | 169 | 296 | 420 | 896 | 1610 | 2540 | 5300 |
| 200 | | 38 | 77 | 157 | 275 | 390 | 834 | 1500 | 2370 | 4930 |
| 250 | | 33 | 69 | 140 | 244 | 346 | 739 | 1330 | 2100 | 4370 |
| 300 | | 30 | 62 | 126 | 221 | 313 | 670 | 1210 | 1900 | 3960 |
| 350 | | 28 | 57 | 116 | 203 | 288 | 616 | 1110 | 1750 | 3640 |
| 400 | | 26 | 53 | 108 | 189 | 268 | 573 | 1030 | 1630 | 3390 |
| 450 | | 24 | 50 | 102 | 177 | 252 | 538 | 968 | 1530 | 3180 |
| 500 | | 23 | 47 | 96 | 168 | 238 | 508 | 914 | 1440 | 3000 |
| 550 | | 22 | 45 | 91 | 159 | 226 | 482 | 868 | 1370 | 2850 |
| 600 | | 21 | 43 | 87 | 152 | 215 | 460 | 829 | 1310 | 2720 |
| 650 | | 20 | 41 | 83 | 145 | 206 | 441 | 793 | 1250 | 2610 |
| 700 | | 19 | 39 | 80 | 140 | 198 | 423 | 762 | 1200 | 2500 |
| 750 | | 18 | 38 | 77 | 135 | 191 | 408 | 734 | 1160 | 2410 |
| 800 | | 18 | 37 | 74 | 130 | 184 | 394 | 709 | 1120 | 2330 |
| 850 | | 17 | 35 | 72 | 126 | 178 | 381 | 686 | 1080 | 2250 |
| 900 | | 17 | 34 | 70 | 122 | 173 | 370 | 665 | 1050 | 2180 |
| 950 | | 16 | 33 | 68 | 118 | 168 | 359 | 646 | 1020 | 2120 |
| 1000 | | 16 | 32 | 66 | 115 | 163 | 349 | 628 | 991 | 2060 |
| 1100 | | 15 | 31 | 63 | 109 | 155 | 332 | 597 | 941 | 1960 |
| 1200 | | 14 | 29 | 60 | 104 | 148 | 316 | 569 | 898 | 1870 |
| 1300 | | 14 | 28 | 57 | 100 | 142 | 303 | 545 | 860 | 1790 |
| 1400 | | 13 | 27 | 55 | 96 | 136 | 291 | 524 | 826 | 1720 |
| 1500 | | 13 | 26 | 53 | 93 | 131 | 280 | 505 | 796 | 1660 |
| 1600 | | 12 | 25 | 51 | 89 | 127 | 271 | 487 | 768 | 1600 |
| 1700 | | 12 | 24 | 49 | 86 | 123 | 262 | 472 | 744 | 1550 |
| 1800 | | 11 | 24 | 48 | 84 | 119 | 254 | 457 | 721 | 1500 |
| 1900 | | 11 | 23 | 47 | 81 | 115 | 247 | 444 | 700 | 1460 |
| 2000 | | 11 | 22 | 45 | 79 | 112 | 240 | 432 | 681 | 1420 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

Notes:

¹ Table capacities are based on Type K copper tubing inside diameter (shown), which has the smallest inside diameter of the copper tubing products.

² Table entries are rounded to 3 significant digits.

TABLE 1216.2(11)
SEMI-RIGID COPPER TUBING [NFPA 54: TABLE 6.2(1)]²

| | | | | | | | GAS: NATURAL | | | |
|----------------------|--------|--|-------|-------|-------|-------|-------------------------|-------|--------|--------|
| | | | | | | | INLET PRESSURE: 2.0 psi | | | |
| | | | | | | | PRESSURE DROP: 1.0 psi | | | |
| | | | | | | | SPECIFIC GRAVITY: 0.60 | | | |
| | | TUBE SIZE (inch) | | | | | | | | |
| NOMINAL: | K & L: | ¼ | ⅜ | ½ | ⅝ | ¾ | 1 | 1¼ | 1½ | 2 |
| | ACR: | ⅜ | ½ | ⅝ | ¾ | ⅞ | 1½ | 1¾ | — | — |
| OUTSIDE: | | 0.375 | 0.500 | 0.625 | 0.750 | 0.875 | 1.125 | 1.375 | 1.625 | 2.125 |
| INSIDE: ¹ | | 0.305 | 0.402 | 0.527 | 0.652 | 0.745 | 0.995 | 1.245 | 1.481 | 1.959 |
| LENGTH (feet) | | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | |
| 10 | | 245 | 506 | 1030 | 1800 | 2550 | 5450 | 9820 | 15 500 | 32 200 |
| 20 | | 169 | 348 | 708 | 1240 | 1760 | 3750 | 6750 | 10 600 | 22 200 |
| 30 | | 135 | 279 | 568 | 993 | 1410 | 3010 | 5420 | 8550 | 17 800 |
| 40 | | 116 | 239 | 486 | 850 | 1210 | 2580 | 4640 | 7310 | 15 200 |
| 50 | | 103 | 212 | 431 | 754 | 1070 | 2280 | 4110 | 6480 | 13 500 |
| 60 | | 93 | 192 | 391 | 683 | 969 | 2070 | 3730 | 5870 | 12 200 |
| 70 | | 86 | 177 | 359 | 628 | 891 | 1900 | 3430 | 5400 | 11 300 |
| 80 | | 80 | 164 | 334 | 584 | 829 | 1770 | 3190 | 5030 | 10 500 |
| 90 | | 75 | 154 | 314 | 548 | 778 | 1660 | 2990 | 4720 | 9820 |
| 100 | | 71 | 146 | 296 | 518 | 735 | 1570 | 2830 | 4450 | 9280 |
| 125 | | 63 | 129 | 263 | 459 | 651 | 1390 | 2500 | 3950 | 8220 |
| 150 | | 57 | 117 | 238 | 416 | 590 | 1260 | 2270 | 3580 | 7450 |
| 175 | | 52 | 108 | 219 | 383 | 543 | 1160 | 2090 | 3290 | 6850 |
| 200 | | 49 | 100 | 204 | 356 | 505 | 1080 | 1940 | 3060 | 6380 |
| 250 | | 43 | 89 | 181 | 315 | 448 | 956 | 1720 | 2710 | 5650 |
| 300 | | 39 | 80 | 164 | 286 | 406 | 866 | 1560 | 2460 | 5120 |
| 350 | | 36 | 74 | 150 | 263 | 373 | 797 | 1430 | 2260 | 4710 |
| 400 | | 33 | 69 | 140 | 245 | 347 | 741 | 1330 | 2100 | 4380 |
| 450 | | 31 | 65 | 131 | 230 | 326 | 696 | 1250 | 1970 | 4110 |
| 500 | | 30 | 61 | 124 | 217 | 308 | 657 | 1180 | 1870 | 3880 |
| 550 | | 28 | 58 | 118 | 206 | 292 | 624 | 1120 | 1770 | 3690 |
| 600 | | 27 | 55 | 112 | 196 | 279 | 595 | 1070 | 1690 | 3520 |
| 650 | | 26 | 53 | 108 | 188 | 267 | 570 | 1030 | 1620 | 3370 |
| 700 | | 25 | 51 | 103 | 181 | 256 | 548 | 986 | 1550 | 3240 |
| 750 | | 24 | 49 | 100 | 174 | 247 | 528 | 950 | 1500 | 3120 |
| 800 | | 23 | 47 | 96 | 168 | 239 | 510 | 917 | 1450 | 3010 |
| 850 | | 22 | 46 | 93 | 163 | 231 | 493 | 888 | 1400 | 2920 |
| 900 | | 22 | 44 | 90 | 158 | 224 | 478 | 861 | 1360 | 2830 |
| 950 | | 21 | 43 | 88 | 153 | 217 | 464 | 836 | 1320 | 2740 |
| 1000 | | 20 | 42 | 85 | 149 | 211 | 452 | 813 | 1280 | 2670 |
| 1100 | | 19 | 40 | 81 | 142 | 201 | 429 | 772 | 1220 | 2540 |
| 1200 | | 18 | 38 | 77 | 135 | 192 | 409 | 737 | 1160 | 2420 |
| 1300 | | 18 | 36 | 74 | 129 | 183 | 392 | 705 | 1110 | 2320 |
| 1400 | | 17 | 35 | 71 | 124 | 176 | 376 | 678 | 1070 | 2230 |
| 1500 | | 16 | 34 | 68 | 120 | 170 | 363 | 653 | 1030 | 2140 |
| 1600 | | 16 | 33 | 66 | 116 | 164 | 350 | 630 | 994 | 2070 |
| 1700 | | 15 | 31 | 64 | 112 | 159 | 339 | 610 | 962 | 2000 |
| 1800 | | 15 | 30 | 62 | 108 | 154 | 329 | 592 | 933 | 1940 |
| 1900 | | 14 | 30 | 60 | 105 | 149 | 319 | 575 | 906 | 1890 |
| 2000 | | 14 | 29 | 59 | 102 | 145 | 310 | 559 | 881 | 1830 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa

Notes:

¹ Table capacities are based on Type K copper tubing inside diameter (shown), which has the smallest inside diameter of the copper tubing products.

² Table entries are rounded to 3 significant digits.

FUEL GAS PIPING

TABLE 1216.2(12)
SEMI-RIGID COPPER TUBING [NFPA 54: TABLE 6.2(m)]³

| | | | | | | | | | | |
|--|--------|--|-------|-------|-------|-------|-------------------------|--------|--------|--------|
| | | | | | | | GAS: NATURAL | | | |
| | | | | | | | INLET PRESSURE: 2.0 psi | | | |
| | | | | | | | PRESSURE DROP: 1.5 psi | | | |
| | | | | | | | SPECIFIC GRAVITY: 0.60 | | | |
| INTENDED USE: PIPE SIZING BETWEEN POINT OF DELIVERY AND THE HOUSE LINE REGULATOR. TOTAL LOAD SUPPLIED BY A SINGLE HOUSE LINE REGULATOR NOT EXCEEDING 150 CUBIC FEET PER HOUR. ² | | | | | | | | | | |
| | | TUBE SIZE (inch) | | | | | | | | |
| NOMINAL: | K & L: | ¼ | ⅜ | ½ | ⅝ | ¾ | 1 | 1¼ | 1½ | 2 |
| | ACR: | ⅜ | ½ | ⅝ | ¾ | ⅞ | 1⅛ | 1⅜ | — | — |
| OUTSIDE: | | 0.375 | 0.500 | 0.625 | 0.750 | 0.875 | 1.125 | 1.375 | 1.625 | 2.125 |
| INSIDE: ¹ | | 0.305 | 0.402 | 0.527 | 0.652 | 0.745 | 0.995 | 1.245 | 1.481 | 1.959 |
| LENGTH (feet) | | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | |
| 10 | | 303 | 625 | 1270 | 2220 | 3150 | 6740 | 12 100 | 19 100 | 39 800 |
| 20 | | 208 | 430 | 874 | 1530 | 2170 | 4630 | 8330 | 13 100 | 27 400 |
| 30 | | 167 | 345 | 702 | 1230 | 1740 | 3720 | 6690 | 10 600 | 22 000 |
| 40 | | 143 | 295 | 601 | 1050 | 1490 | 3180 | 5730 | 9030 | 18 800 |
| 50 | | 127 | 262 | 532 | 931 | 1320 | 2820 | 5080 | 8000 | 16 700 |
| 60 | | 115 | 237 | 482 | 843 | 1200 | 2560 | 4600 | 7250 | 15 100 |
| 70 | | 106 | 218 | 444 | 776 | 1100 | 2350 | 4230 | 6670 | 13 900 |
| 80 | | 98 | 203 | 413 | 722 | 1020 | 2190 | 3940 | 6210 | 12 900 |
| 90 | | 92 | 190 | 387 | 677 | 961 | 2050 | 3690 | 5820 | 12 100 |
| 100 | | 87 | 180 | 366 | 640 | 907 | 1940 | 3490 | 5500 | 11 500 |
| 125 | | 77 | 159 | 324 | 567 | 804 | 1720 | 3090 | 4880 | 10 200 |
| 150 | | 70 | 144 | 294 | 514 | 729 | 1560 | 2800 | 4420 | 9200 |
| 175 | | 64 | 133 | 270 | 472 | 670 | 1430 | 2580 | 4060 | 8460 |
| 200 | | 60 | 124 | 252 | 440 | 624 | 1330 | 2400 | 3780 | 7870 |
| 250 | | 53 | 110 | 223 | 390 | 553 | 1180 | 2130 | 3350 | 6980 |
| 300 | | 48 | 99 | 202 | 353 | 501 | 1070 | 1930 | 3040 | 6320 |
| 350 | | 44 | 91 | 186 | 325 | 461 | 984 | 1770 | 2790 | 5820 |
| 400 | | 41 | 85 | 173 | 302 | 429 | 916 | 1650 | 2600 | 5410 |
| 450 | | 39 | 80 | 162 | 283 | 402 | 859 | 1550 | 2440 | 5080 |
| 500 | | 36 | 75 | 153 | 268 | 380 | 811 | 1460 | 2300 | 4800 |
| 550 | | 35 | 72 | 146 | 254 | 361 | 771 | 1390 | 2190 | 4560 |
| 600 | | 33 | 68 | 139 | 243 | 344 | 735 | 1320 | 2090 | 4350 |
| 650 | | 32 | 65 | 133 | 232 | 330 | 704 | 1270 | 2000 | 4160 |
| 700 | | 30 | 63 | 128 | 223 | 317 | 676 | 1220 | 1920 | 4000 |
| 750 | | 29 | 60 | 123 | 215 | 305 | 652 | 1170 | 1850 | 3850 |
| 800 | | 28 | 58 | 119 | 208 | 295 | 629 | 1130 | 1790 | 3720 |
| 850 | | 27 | 57 | 115 | 201 | 285 | 609 | 1100 | 1730 | 3600 |
| 900 | | 27 | 55 | 111 | 195 | 276 | 590 | 1060 | 1680 | 3490 |
| 950 | | 26 | 53 | 108 | 189 | 268 | 573 | 1030 | 1630 | 3390 |
| 1000 | | 25 | 52 | 105 | 184 | 261 | 558 | 1000 | 1580 | 3300 |
| 1100 | | 24 | 49 | 100 | 175 | 248 | 530 | 954 | 1500 | 3130 |
| 1200 | | 23 | 47 | 95 | 167 | 237 | 505 | 910 | 1430 | 2990 |
| 1300 | | 22 | 45 | 91 | 160 | 227 | 484 | 871 | 1370 | 2860 |
| 1400 | | 21 | 43 | 88 | 153 | 218 | 465 | 837 | 1320 | 2750 |
| 1500 | | 20 | 42 | 85 | 148 | 210 | 448 | 806 | 1270 | 2650 |
| 1600 | | 19 | 40 | 82 | 143 | 202 | 432 | 779 | 1230 | 2560 |
| 1700 | | 19 | 39 | 79 | 138 | 196 | 419 | 753 | 1190 | 2470 |
| 1800 | | 18 | 38 | 77 | 134 | 190 | 406 | 731 | 1150 | 2400 |
| 1900 | | 18 | 37 | 74 | 130 | 184 | 394 | 709 | 1120 | 2330 |
| 2000 | | 17 | 36 | 72 | 126 | 179 | 383 | 690 | 1090 | 2270 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa

Notes:

¹ Table capacities are based on Type K copper tubing inside diameter (shown), which has the smallest inside diameter of the copper tubing products.

² Where this table is used to size the tubing upstream of a line pressure regulator, the pipe or tubing downstream of the line pressure regulator shall be sized using a pressure drop no greater than 1 inch water column (0.249 kPa).

³ Table entries are rounded to 3 significant digits.

TABLE 1216.2(13)
SEMI-RIGID COPPER TUBING [NFPA 54: TABLE 6.2(n)]²

| | | | | | | | GAS: NATURAL | | | |
|----------------------|--------|--|-------|-------|-------|-------|-------------------------|--------|--------|--------|
| | | | | | | | INLET PRESSURE: 5.0 psi | | | |
| | | | | | | | PRESSURE DROP: 3.5 psi | | | |
| | | | | | | | SPECIFIC GRAVITY: 0.60 | | | |
| | | TUBE SIZE (Inch) | | | | | | | | |
| NOMINAL: | K & L: | ¼ | ⅜ | ½ | ⅝ | ¾ | 1 | 1¼ | 1½ | 2 |
| | ACR: | ⅜ | ½ | ⅝ | ¾ | ⅞ | 1½ | 1¾ | — | — |
| OUTSIDE: | | 0.375 | 0.500 | 0.625 | 0.750 | 0.875 | 1.125 | 1.375 | 1.625 | 2.125 |
| INSIDE: ¹ | | 0.305 | 0.402 | 0.527 | 0.652 | 0.745 | 0.995 | 1.245 | 1.481 | 1.959 |
| LENGTH (feet) | | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | |
| 10 | | 511 | 1050 | 2140 | 3750 | 5320 | 11 400 | 20 400 | 32 200 | 67 100 |
| 20 | | 351 | 724 | 1470 | 2580 | 3650 | 7800 | 14 000 | 22 200 | 46 100 |
| 30 | | 282 | 582 | 1180 | 2070 | 2930 | 6270 | 11 300 | 17 800 | 37 000 |
| 40 | | 241 | 498 | 1010 | 1770 | 2510 | 5360 | 9660 | 15 200 | 31 700 |
| 50 | | 214 | 441 | 898 | 1570 | 2230 | 4750 | 8560 | 13 500 | 28 100 |
| 60 | | 194 | 400 | 813 | 1420 | 2020 | 4310 | 7750 | 12 200 | 25 500 |
| 70 | | 178 | 368 | 748 | 1310 | 1860 | 3960 | 7130 | 11 200 | 23 400 |
| 80 | | 166 | 342 | 696 | 1220 | 1730 | 3690 | 6640 | 10 500 | 21 800 |
| 90 | | 156 | 321 | 653 | 1140 | 1620 | 3460 | 6230 | 9820 | 20 400 |
| 100 | | 147 | 303 | 617 | 1080 | 1530 | 3270 | 5880 | 9270 | 19 300 |
| 125 | | 130 | 269 | 547 | 955 | 1360 | 2900 | 5210 | 8220 | 17 100 |
| 150 | | 118 | 243 | 495 | 866 | 1230 | 2620 | 4720 | 7450 | 15 500 |
| 175 | | 109 | 224 | 456 | 796 | 1130 | 2410 | 4350 | 6850 | 14 300 |
| 200 | | 101 | 208 | 424 | 741 | 1050 | 2250 | 4040 | 6370 | 13 300 |
| 250 | | 90 | 185 | 376 | 657 | 932 | 1990 | 3580 | 5650 | 11 800 |
| 300 | | 81 | 167 | 340 | 595 | 844 | 1800 | 3250 | 5120 | 10 700 |
| 350 | | 75 | 154 | 313 | 547 | 777 | 1660 | 2990 | 4710 | 9810 |
| 400 | | 69 | 143 | 291 | 509 | 722 | 1540 | 2780 | 4380 | 9120 |
| 450 | | 65 | 134 | 273 | 478 | 678 | 1450 | 2610 | 4110 | 8560 |
| 500 | | 62 | 127 | 258 | 451 | 640 | 1370 | 2460 | 3880 | 8090 |
| 550 | | 58 | 121 | 245 | 429 | 608 | 1300 | 2340 | 3690 | 7680 |
| 600 | | 56 | 115 | 234 | 409 | 580 | 1240 | 2230 | 3520 | 7330 |
| 650 | | 53 | 110 | 224 | 392 | 556 | 1190 | 2140 | 3370 | 7020 |
| 700 | | 51 | 106 | 215 | 376 | 534 | 1140 | 2050 | 3240 | 6740 |
| 750 | | 49 | 102 | 207 | 362 | 514 | 1100 | 1980 | 3120 | 6490 |
| 800 | | 48 | 98 | 200 | 350 | 497 | 1060 | 1910 | 3010 | 6270 |
| 850 | | 46 | 95 | 194 | 339 | 481 | 1030 | 1850 | 2910 | 6070 |
| 900 | | 45 | 92 | 188 | 328 | 466 | 1000 | 1790 | 2820 | 5880 |
| 950 | | 43 | 90 | 182 | 319 | 452 | 967 | 1740 | 2740 | 5710 |
| 1000 | | 42 | 87 | 177 | 310 | 440 | 940 | 1690 | 2670 | 5560 |
| 1100 | | 40 | 83 | 169 | 295 | 418 | 893 | 1610 | 2530 | 5280 |
| 1200 | | 38 | 79 | 161 | 281 | 399 | 852 | 1530 | 2420 | 5040 |
| 1300 | | 37 | 76 | 154 | 269 | 382 | 816 | 1470 | 2320 | 4820 |
| 1400 | | 35 | 73 | 148 | 259 | 367 | 784 | 1410 | 2220 | 4630 |
| 1500 | | 34 | 70 | 143 | 249 | 353 | 755 | 1360 | 2140 | 4460 |
| 1600 | | 33 | 68 | 138 | 241 | 341 | 729 | 1310 | 2070 | 4310 |
| 1700 | | 32 | 65 | 133 | 233 | 330 | 705 | 1270 | 2000 | 4170 |
| 1800 | | 31 | 63 | 129 | 226 | 320 | 684 | 1230 | 1940 | 4040 |
| 1900 | | 30 | 62 | 125 | 219 | 311 | 664 | 1200 | 1890 | 3930 |
| 2000 | | 29 | 60 | 122 | 213 | 302 | 646 | 1160 | 1830 | 3820 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa

Notes:

¹ Table capacities are based on Type K copper tubing inside diameter (shown), which has the smallest inside diameter of the copper tubing products.

² Table entries are rounded to 3 significant digits.

FUEL GAS PIPING

TABLE 1216.2(14)
CORRUGATED STAINLESS STEEL TUBING (CSST) [NFPA 54: TABLE 6.2(o)]^{1, 2}

| | | | | | | | | | | | | | | |
|-------------------|--|----|-----|-----|-----|-----|-----|-----|-----|---------------------------------|------|------|------|------|
| | | | | | | | | | | GAS: NATURAL | | | | |
| | | | | | | | | | | INLET PRESSURE: LESS THAN 2 psi | | | | |
| | | | | | | | | | | PRESSURE DROP: 0.5 in. w.c. | | | | |
| | | | | | | | | | | SPECIFIC GRAVITY: 0.60 | | | | |
| | TUBE SIZE (EHD) ³ | | | | | | | | | | | | | |
| FLOW DESIGNATION: | 13 | 15 | 18 | 19 | 23 | 25 | 30 | 31 | 37 | 39 | 46 | 48 | 60 | 62 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | | | | | | |
| 5 | 46 | 63 | 115 | 134 | 225 | 270 | 471 | 546 | 895 | 1037 | 1790 | 2070 | 3660 | 4140 |
| 10 | 32 | 44 | 82 | 95 | 161 | 192 | 330 | 383 | 639 | 746 | 1260 | 1470 | 2600 | 2930 |
| 15 | 25 | 35 | 66 | 77 | 132 | 157 | 267 | 310 | 524 | 615 | 1030 | 1200 | 2140 | 2400 |
| 20 | 22 | 31 | 58 | 67 | 116 | 137 | 231 | 269 | 456 | 536 | 888 | 1050 | 1850 | 2080 |
| 25 | 19 | 27 | 52 | 60 | 104 | 122 | 206 | 240 | 409 | 482 | 793 | 936 | 1660 | 1860 |
| 30 | 18 | 25 | 47 | 55 | 96 | 112 | 188 | 218 | 374 | 442 | 723 | 856 | 1520 | 1700 |
| 40 | 15 | 21 | 41 | 47 | 83 | 97 | 162 | 188 | 325 | 386 | 625 | 742 | 1320 | 1470 |
| 50 | 13 | 19 | 37 | 42 | 75 | 87 | 144 | 168 | 292 | 347 | 559 | 665 | 1180 | 1320 |
| 60 | 12 | 17 | 34 | 38 | 68 | 80 | 131 | 153 | 267 | 318 | 509 | 608 | 1080 | 1200 |
| 70 | 11 | 16 | 31 | 36 | 63 | 74 | 121 | 141 | 248 | 295 | 471 | 563 | 1000 | 1110 |
| 80 | 10 | 15 | 29 | 33 | 60 | 69 | 113 | 132 | 232 | 277 | 440 | 527 | 940 | 1040 |
| 90 | 10 | 14 | 28 | 32 | 57 | 65 | 107 | 125 | 219 | 262 | 415 | 498 | 887 | 983 |
| 100 | 9 | 13 | 26 | 30 | 54 | 62 | 101 | 118 | 208 | 249 | 393 | 472 | 843 | 933 |
| 150 | 7 | 10 | 20 | 23 | 42 | 48 | 78 | 91 | 171 | 205 | 320 | 387 | 691 | 762 |
| 200 | 6 | 9 | 18 | 21 | 38 | 44 | 71 | 82 | 148 | 179 | 277 | 336 | 600 | 661 |
| 250 | 5 | 8 | 16 | 19 | 34 | 39 | 63 | 74 | 133 | 161 | 247 | 301 | 538 | 591 |
| 300 | 5 | 7 | 15 | 17 | 32 | 36 | 57 | 67 | 95 | 148 | 226 | 275 | 492 | 540 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

Notes:

¹ Table entries are rounded to 3 significant digits.

² Table includes losses for four 90 degree (1.57 rad) bends and two end fittings. Tubing runs with larger numbers of bends, fittings, or both shall be increased by an equivalent length of tubing to the following equation: $L = 1.3 n$, where L is additional length (ft) of tubing and n is the number of additional fittings, bends, or both.

³ EHD = Equivalent Hydraulic Diameter, which is a measure of the relative hydraulic efficiency between different tubing sizes. The greater the value of EHD, the greater the gas capacity of the tubing.

TABLE 1216.2(15)
CORRUGATED STAINLESS STEEL TUBING (CSST) [NFPA 54: TABLE 6.2(p)]^{1, 2}

| | | | | | | | | | | | | | |
|---|--|-----|-----|-----|-----|-----|------|---------------------------------|------|------|------|------|--------|
| | | | | | | | | GAS: NATURAL | | | | | |
| | | | | | | | | INLET PRESSURE: LESS THAN 2 psi | | | | | |
| | | | | | | | | PRESSURE DROP: 3.0 in. w.c. | | | | | |
| | | | | | | | | SPECIFIC GRAVITY: 0.60 | | | | | |
| INTENDED USE: INITIAL SUPPLY PRESSURE OF 8.0 INCH WATER COLUMN OR GREATER | | | | | | | | | | | | | |
| | TUBE SIZE (EHD) ³ | | | | | | | | | | | | |
| FLOW DESIGNATION: | 13 | 15 | 18 | 19 | 23 | 25 | 30 | 31 | 37 | 46 | 48 | 60 | 62 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | | | | | |
| 5 | 120 | 160 | 277 | 327 | 529 | 649 | 1180 | 1370 | 2140 | 4430 | 5010 | 8800 | 10 100 |
| 10 | 83 | 112 | 197 | 231 | 380 | 462 | 828 | 958 | 1530 | 3200 | 3560 | 6270 | 7160 |
| 15 | 67 | 90 | 161 | 189 | 313 | 379 | 673 | 778 | 1250 | 2540 | 2910 | 5140 | 5850 |
| 20 | 57 | 78 | 140 | 164 | 273 | 329 | 580 | 672 | 1090 | 2200 | 2530 | 4460 | 5070 |
| 25 | 51 | 69 | 125 | 147 | 245 | 295 | 518 | 599 | 978 | 1960 | 2270 | 4000 | 4540 |
| 30 | 46 | 63 | 115 | 134 | 225 | 270 | 471 | 546 | 895 | 1790 | 2070 | 3660 | 4140 |
| 40 | 39 | 54 | 100 | 116 | 196 | 234 | 407 | 471 | 778 | 1550 | 1800 | 3180 | 3590 |
| 50 | 35 | 48 | 89 | 104 | 176 | 210 | 363 | 421 | 698 | 1380 | 1610 | 2850 | 3210 |
| 60 | 32 | 44 | 82 | 95 | 161 | 192 | 330 | 383 | 639 | 1260 | 1470 | 2600 | 2930 |
| 70 | 29 | 41 | 76 | 88 | 150 | 178 | 306 | 355 | 593 | 1170 | 1360 | 2420 | 2720 |
| 80 | 27 | 38 | 71 | 82 | 141 | 167 | 285 | 331 | 555 | 1090 | 1280 | 2260 | 2540 |
| 90 | 26 | 36 | 67 | 77 | 133 | 157 | 268 | 311 | 524 | 1030 | 1200 | 2140 | 2400 |
| 100 | 24 | 34 | 63 | 73 | 126 | 149 | 254 | 295 | 498 | 974 | 1140 | 2030 | 2280 |
| 150 | 19 | 27 | 52 | 60 | 104 | 122 | 206 | 240 | 409 | 793 | 936 | 1660 | 1860 |
| 200 | 17 | 23 | 45 | 52 | 91 | 106 | 178 | 207 | 355 | 686 | 812 | 1440 | 1610 |
| 250 | 15 | 21 | 40 | 46 | 82 | 95 | 159 | 184 | 319 | 613 | 728 | 1290 | 1440 |
| 300 | 13 | 19 | 37 | 42 | 75 | 87 | 144 | 168 | 234 | 559 | 665 | 1180 | 1320 |

For SI units: 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

Notes:

¹ Table entries are rounded to 3 significant digits.

² Table includes losses for four 90 degree (1.57 rad) bends and two end fittings. Tubing runs with larger numbers of bends, fittings, or both shall be increased by an equivalent length of tubing to the following equation: $L = 1.3 n$, where L is additional length (ft) of tubing and n is the number of additional fittings, bends, or both.

³ EHD = Equivalent Hydraulic Diameter, which is a measure of the relative hydraulic efficiency between different tubing sizes. The greater the value of EHD, the greater the gas capacity of the tubing.

FUEL GAS PIPING

TABLE 1216.2(16)
CORRUGATED STAINLESS STEEL TUBING (CSST) [NFPA 54: TABLE 6.2(q)]^{1, 2}

| | | | | | | | | | | | | | |
|--|--|-----|-----|-----|-----|-----|------|---------------------------------|------|------|------|--------|--------|
| | | | | | | | | GAS: NATURAL | | | | | |
| | | | | | | | | INLET PRESSURE: LESS THAN 2 psi | | | | | |
| | | | | | | | | PRESSURE DROP: 6.0 in. w.c. | | | | | |
| | | | | | | | | SPECIFIC GRAVITY: 0.60 | | | | | |
| INTENDED USE: INITIAL SUPPLY PRESSURE OF 11.0 INCH WATER COLUMN OR GREATER | | | | | | | | | | | | | |
| FLOW DESIGNATION: | TUBE SIZE (EHD) ³ | | | | | | | | | | | | |
| | 13 | 15 | 18 | 19 | 23 | 25 | 30 | 31 | 37 | 46 | 48 | 60 | 62 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | | | | | |
| 5 | 173 | 229 | 389 | 461 | 737 | 911 | 1690 | 1950 | 3000 | 6280 | 7050 | 12 400 | 14 260 |
| 10 | 120 | 160 | 277 | 327 | 529 | 649 | 1180 | 1370 | 2140 | 4430 | 5010 | 8800 | 10 100 |
| 15 | 96 | 130 | 227 | 267 | 436 | 532 | 960 | 1110 | 1760 | 3610 | 4100 | 7210 | 8260 |
| 20 | 83 | 112 | 197 | 231 | 380 | 462 | 828 | 958 | 1530 | 3120 | 3560 | 6270 | 7160 |
| 25 | 74 | 99 | 176 | 207 | 342 | 414 | 739 | 855 | 1370 | 2790 | 3190 | 5620 | 6400 |
| 30 | 67 | 90 | 161 | 189 | 313 | 379 | 673 | 778 | 1250 | 2540 | 2910 | 5140 | 5850 |
| 40 | 57 | 78 | 140 | 164 | 273 | 329 | 580 | 672 | 1090 | 2200 | 2530 | 4460 | 5070 |
| 50 | 51 | 69 | 125 | 147 | 245 | 295 | 518 | 599 | 978 | 1960 | 2270 | 4000 | 4540 |
| 60 | 46 | 63 | 115 | 134 | 225 | 270 | 471 | 546 | 895 | 1790 | 2070 | 3660 | 4140 |
| 70 | 42 | 58 | 106 | 124 | 209 | 250 | 435 | 505 | 830 | 1660 | 1920 | 3390 | 3840 |
| 80 | 39 | 54 | 100 | 116 | 196 | 234 | 407 | 471 | 778 | 1550 | 1800 | 3180 | 3590 |
| 90 | 37 | 51 | 94 | 109 | 185 | 221 | 383 | 444 | 735 | 1460 | 1700 | 3000 | 3390 |
| 100 | 35 | 48 | 89 | 104 | 176 | 210 | 363 | 421 | 698 | 1380 | 1610 | 2850 | 3210 |
| 150 | 28 | 39 | 73 | 85 | 145 | 172 | 294 | 342 | 573 | 1130 | 1320 | 2340 | 2630 |
| 200 | 24 | 34 | 63 | 73 | 126 | 149 | 254 | 295 | 498 | 974 | 1140 | 2030 | 2280 |
| 250 | 21 | 30 | 57 | 66 | 114 | 134 | 226 | 263 | 447 | 870 | 1020 | 1820 | 2040 |
| 300 | 19 | 27 | 52 | 60 | 104 | 122 | 206 | 240 | 409 | 793 | 936 | 1660 | 1860 |

For SI units: 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

Notes:

- ¹ Table entries are rounded to 3 significant digits.
- ² Table includes losses for four 90 degree (1.57 rad) bends and two end fittings. Tubing runs with larger numbers of bends, fittings, or both shall be increased by an equivalent length of tubing to the following equation: $L = 1.3 n$, where L is additional length (ft) of tubing and n is the number of additional fittings, bends, or both.
- ³ EHD = Equivalent Hydraulic Diameter, which is a measure of the relative hydraulic efficiency between different tubing sizes. The greater the value of EHD, the greater the gas capacity of the tubing.

TABLE 1216.2(17)

CORRUGATED STAINLESS STEEL TUBING (CSST) [NFPA 54: TABLE 6.2(r)]^{1, 2, 3, 4}

| | | | | | | | | | GAS: | | NATURAL | | | |
|-------------------|--|-----|-----|-----|------|------|------|------|-------------------|------|---------|--------|--------|--------|
| | | | | | | | | | INLET PRESSURE: | | 2.0 psi | | | |
| | | | | | | | | | PRESSURE DROP: | | 1.0 psi | | | |
| | | | | | | | | | SPECIFIC GRAVITY: | | 0.60 | | | |
| | TUBE SIZE (EHD) ⁵ | | | | | | | | | | | | | |
| FLOW DESIGNATION: | 13 | 15 | 18 | 19 | 23 | 25 | 30 | 31 | 37 | 39 | 46 | 48 | 60 | 62 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | | | | | | |
| 10 | 270 | 353 | 587 | 700 | 1100 | 1370 | 2590 | 2990 | 4510 | 5037 | 9600 | 10 700 | 18 600 | 21 600 |
| 25 | 166 | 220 | 374 | 444 | 709 | 876 | 1620 | 1870 | 2890 | 3258 | 6040 | 6780 | 11 900 | 13 700 |
| 30 | 151 | 200 | 342 | 405 | 650 | 801 | 1480 | 1700 | 2640 | 2987 | 5510 | 6200 | 10 900 | 12 500 |
| 40 | 129 | 172 | 297 | 351 | 567 | 696 | 1270 | 1470 | 2300 | 2605 | 4760 | 5380 | 9440 | 10 900 |
| 50 | 115 | 154 | 266 | 314 | 510 | 624 | 1140 | 1310 | 2060 | 2343 | 4260 | 4820 | 8470 | 9720 |
| 75 | 93 | 124 | 218 | 257 | 420 | 512 | 922 | 1070 | 1690 | 1932 | 3470 | 3950 | 6940 | 7940 |
| 80 | 89 | 120 | 211 | 249 | 407 | 496 | 892 | 1030 | 1640 | 1874 | 3360 | 3820 | 6730 | 7690 |
| 100 | 79 | 107 | 189 | 222 | 366 | 445 | 795 | 920 | 1470 | 1685 | 3000 | 3420 | 6030 | 6880 |
| 150 | 64 | 87 | 155 | 182 | 302 | 364 | 646 | 748 | 1210 | 1389 | 2440 | 2800 | 4940 | 5620 |
| 200 | 55 | 75 | 135 | 157 | 263 | 317 | 557 | 645 | 1050 | 1212 | 2110 | 2430 | 4290 | 4870 |
| 250 | 49 | 67 | 121 | 141 | 236 | 284 | 497 | 576 | 941 | 1090 | 1890 | 2180 | 3850 | 4360 |
| 300 | 44 | 61 | 110 | 129 | 217 | 260 | 453 | 525 | 862 | 999 | 1720 | 1990 | 3520 | 3980 |
| 400 | 38 | 52 | 96 | 111 | 189 | 225 | 390 | 453 | 749 | 871 | 1490 | 1730 | 3060 | 3450 |
| 500 | 34 | 46 | 86 | 100 | 170 | 202 | 348 | 404 | 552 | 783 | 1330 | 1550 | 2740 | 3090 |

For SI units: 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa**Notes:**

- ¹ Table does not include effect of pressure drop across the line regulator. Where regulator loss exceeds 0.75 psi (5.17 kPa), DO NOT USE THIS TABLE. Consult with regulator manufacturer for pressure drops and capacity factors. Pressure drops across a regulator are capable of varying with flow rate.
- ² CAUTION: Capacities shown in table are capable of exceeding maximum capacity for a selected regulator. Consult with regulator or tubing manufacturer for guidance.
- ³ Table includes losses for four 90 degree (1.57 rad) bends and two end fittings. Tubing runs with larger numbers of bends, fittings, or both shall be increased by an equivalent length of tubing according to the following equation: $L = 1.3 n$, where L is additional length (ft) of tubing and n is the number of additional fittings, bends, or both.
- ⁴ Table entries are rounded to 3 significant digits.
- ⁵ EHD = Equivalent Hydraulic Diameter, which is a measure of the relative hydraulic efficiency between different tubing sizes. The greater the value of EHD, the greater the gas capacity of the tubing.

FUEL GAS PIPING

TABLE 1216.2(18)
CORRUGATED STAINLESS STEEL TUBING (CSST) [NFPA 54: TABLE 6.2(s)]^{1, 2, 3, 4}

| | | | | | | | | | | | | | | | |
|-------------------|--|-----|------|------|------|------|------|------|------|-------------------|--------|---------|--------|--------|--|
| | | | | | | | | | | GAS: | | NATURAL | | | |
| | | | | | | | | | | INLET PRESSURE: | | 5.0 psi | | | |
| | | | | | | | | | | PRESSURE DROP: | | 3.5 psi | | | |
| | | | | | | | | | | SPECIFIC GRAVITY: | | 0.60 | | | |
| | TUBE SIZE (EHD) ⁵ | | | | | | | | | | | | | | |
| FLOW DESIGNATION: | 13 | 15 | 18 | 19 | 23 | 25 | 30 | 31 | 37 | 39 | 46 | 48 | 60 | 62 | |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | | | | | | | | |
| 10 | 523 | 674 | 1080 | 1300 | 2000 | 2530 | 4920 | 5660 | 8300 | 9140 | 18 100 | 19 800 | 34 400 | 40 400 | |
| 25 | 322 | 420 | 691 | 827 | 1290 | 1620 | 3080 | 3540 | 5310 | 5911 | 11 400 | 12 600 | 22 000 | 25 600 | |
| 30 | 292 | 382 | 632 | 755 | 1180 | 1480 | 2800 | 3230 | 4860 | 5420 | 10 400 | 11 500 | 20 100 | 23 400 | |
| 40 | 251 | 329 | 549 | 654 | 1030 | 1280 | 2420 | 2790 | 4230 | 4727 | 8970 | 10 000 | 17 400 | 20 200 | |
| 50 | 223 | 293 | 492 | 586 | 926 | 1150 | 2160 | 2490 | 3790 | 4251 | 8020 | 8930 | 15 600 | 18 100 | |
| 75 | 180 | 238 | 403 | 479 | 763 | 944 | 1750 | 2020 | 3110 | 3506 | 6530 | 7320 | 12 800 | 14 800 | |
| 80 | 174 | 230 | 391 | 463 | 740 | 915 | 1690 | 1960 | 3020 | 3400 | 6320 | 7090 | 12 400 | 14 300 | |
| 100 | 154 | 205 | 350 | 415 | 665 | 820 | 1510 | 1740 | 2710 | 3057 | 5650 | 6350 | 11 100 | 12 800 | |
| 150 | 124 | 166 | 287 | 339 | 548 | 672 | 1230 | 1420 | 2220 | 2521 | 4600 | 5200 | 9130 | 10 500 | |
| 200 | 107 | 143 | 249 | 294 | 478 | 584 | 1060 | 1220 | 1930 | 2199 | 3980 | 4510 | 7930 | 9090 | |
| 250 | 95 | 128 | 223 | 263 | 430 | 524 | 945 | 1090 | 1730 | 1977 | 3550 | 4040 | 7110 | 8140 | |
| 300 | 86 | 116 | 204 | 240 | 394 | 479 | 860 | 995 | 1590 | 1813 | 3240 | 3690 | 6500 | 7430 | |
| 400 | 74 | 100 | 177 | 208 | 343 | 416 | 742 | 858 | 1380 | 1581 | 2800 | 3210 | 5650 | 6440 | |
| 500 | 66 | 89 | 159 | 186 | 309 | 373 | 662 | 766 | 1040 | 1422 | 2500 | 2870 | 5060 | 5760 | |

For SI units: 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa

Notes:

- ¹ Table does not include effect of pressure drop across the line regulator. Where regulator loss exceeds 1 psi (7 kPa), DO NOT USE THIS TABLE. Consult with regulator manufacturer for pressure drops and capacity factors. Pressure drops across regulator are capable of varying with the flow rate.
- ² CAUTION: Capacities shown in table are capable of exceeding the maximum capacity of selected regulator. Consult tubing manufacturer for guidance.
- ³ Table includes losses for four 90 degree (1.57 rad) bends and two end fittings. Tubing runs with larger numbers of bends, fittings, or both shall be increased by an equivalent length of tubing to the following equation: $L = 1.3 n$, where L is additional length (feet) of tubing and n is the number of additional fittings, bends, or both.
- ⁴ Table entries are rounded to 3 significant digits.
- ⁵ EHD = Equivalent Hydraulic Diameter, which is a measure of the relative hydraulic efficiency between different tubing sizes. The greater the value of EHD, the greater the gas capacity of the tubing.

TABLE 1216.2(19)
POLYETHYLENE PLASTIC PIPE [NFPA 54: TABLE 6.2(t)]*

| | | | | | | | | |
|---------------|--|--------|--------|--------|---------------------------------|--------|--------|--------|
| | | | | | GAS: NATURAL | | | |
| | | | | | INLET PRESSURE: LESS THAN 2 psi | | | |
| | | | | | PRESSURE DROP: 0.3 in. w.c. | | | |
| | | | | | SPECIFIC GRAVITY: 0.60 | | | |
| | PIPE SIZE (inch) | | | | | | | |
| NOMINAL OD: | ½ | ¾ | 1 | 1 ¼ | 1 ½ | 2 | 3 | 4 |
| DESIGNATION: | SDR 9.3 | SDR 11 | SDR 11 | SDR 10 | SDR 11 | SDR 11 | SDR 11 | SDR 11 |
| ACTUAL ID: | 0.660 | 0.860 | 1.077 | 1.328 | 1.554 | 1.943 | 2.864 | 3.682 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | |
| 10 | 153 | 305 | 551 | 955 | 1440 | 2590 | 7170 | 13 900 |
| 20 | 105 | 210 | 379 | 656 | 991 | 1780 | 4920 | 9520 |
| 30 | 84 | 169 | 304 | 527 | 796 | 1430 | 3950 | 7640 |
| 40 | 72 | 144 | 260 | 451 | 681 | 1220 | 3380 | 6540 |
| 50 | 64 | 128 | 231 | 400 | 604 | 1080 | 3000 | 5800 |
| 60 | 58 | 116 | 209 | 362 | 547 | 983 | 2720 | 5250 |
| 70 | 53 | 107 | 192 | 333 | 503 | 904 | 2500 | 4830 |
| 80 | 50 | 99 | 179 | 310 | 468 | 841 | 2330 | 4500 |
| 90 | 46 | 93 | 168 | 291 | 439 | 789 | 2180 | 4220 |
| 100 | 44 | 88 | 159 | 275 | 415 | 745 | 2060 | 3990 |
| 125 | 39 | 78 | 141 | 243 | 368 | 661 | 1830 | 3530 |
| 150 | 35 | 71 | 127 | 221 | 333 | 598 | 1660 | 3200 |
| 175 | 32 | 65 | 117 | 203 | 306 | 551 | 1520 | 2940 |
| 200 | 30 | 60 | 109 | 189 | 285 | 512 | 1420 | 2740 |
| 250 | 27 | 54 | 97 | 167 | 253 | 454 | 1260 | 2430 |
| 300 | 24 | 48 | 88 | 152 | 229 | 411 | 1140 | 2200 |
| 350 | 22 | 45 | 81 | 139 | 211 | 378 | 1050 | 2020 |
| 400 | 21 | 42 | 75 | 130 | 196 | 352 | 974 | 1880 |
| 450 | 19 | 39 | 70 | 122 | 184 | 330 | 914 | 1770 |
| 500 | 18 | 37 | 66 | 115 | 174 | 312 | 863 | 1670 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

* Table entries are rounded to 3 significant digits.

FUEL GAS PIPING

TABLE 1216.2(20)
POLYETHYLENE PLASTIC PIPE [NFPA 54: TABLE 6.2(u)]*

| | | | | | | | | |
|---------------|--|--------|--------|--------|---------------------------------|--------|--------|--------|
| | | | | | GAS: NATURAL | | | |
| | | | | | INLET PRESSURE: LESS THAN 2 psi | | | |
| | | | | | PRESSURE DROP: 0.5 in. w.c. | | | |
| | | | | | SPECIFIC GRAVITY: 0.60 | | | |
| | PIPE SIZE (Inch) | | | | | | | |
| NOMINAL OD: | ½ | ¾ | 1 | 1 ¼ | 1 ½ | 2 | 3 | 4 |
| DESIGNATION: | SDR 9.3 | SDR 11 | SDR 11 | SDR 10 | SDR 11 | SDR 11 | SDR 11 | SDR 11 |
| ACTUAL ID: | 0.660 | 0.860 | 1.077 | 1.328 | 1.554 | 1.943 | 2.864 | 3.682 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | |
| 10 | 201 | 403 | 726 | 1260 | 1900 | 3410 | 9450 | 18 260 |
| 20 | 138 | 277 | 499 | 865 | 1310 | 2350 | 6490 | 12 550 |
| 30 | 111 | 222 | 401 | 695 | 1050 | 1880 | 5210 | 10 080 |
| 40 | 95 | 190 | 343 | 594 | 898 | 1610 | 4460 | 8630 |
| 50 | 84 | 169 | 304 | 527 | 796 | 1430 | 3950 | 7640 |
| 60 | 76 | 153 | 276 | 477 | 721 | 1300 | 3580 | 6930 |
| 70 | 70 | 140 | 254 | 439 | 663 | 1190 | 3300 | 6370 |
| 80 | 65 | 131 | 236 | 409 | 617 | 1110 | 3070 | 5930 |
| 90 | 61 | 123 | 221 | 383 | 579 | 1040 | 2880 | 5560 |
| 100 | 58 | 116 | 209 | 362 | 547 | 983 | 2720 | 5250 |
| 125 | 51 | 103 | 185 | 321 | 485 | 871 | 2410 | 4660 |
| 150 | 46 | 93 | 168 | 291 | 439 | 789 | 2180 | 4220 |
| 175 | 43 | 86 | 154 | 268 | 404 | 726 | 2010 | 3880 |
| 200 | 40 | 80 | 144 | 249 | 376 | 675 | 1870 | 3610 |
| 250 | 35 | 71 | 127 | 221 | 333 | 598 | 1660 | 3200 |
| 300 | 32 | 64 | 115 | 200 | 302 | 542 | 1500 | 2900 |
| 350 | 29 | 59 | 106 | 184 | 278 | 499 | 1380 | 2670 |
| 400 | 27 | 55 | 99 | 171 | 258 | 464 | 1280 | 2480 |
| 450 | 26 | 51 | 93 | 160 | 242 | 435 | 1200 | 2330 |
| 500 | 24 | 48 | 88 | 152 | 229 | 411 | 1140 | 2200 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

* Table entries are rounded to 3 significant digits.

TABLE 1216.2(21)
POLYETHYLENE PLASTIC PIPE [NFPA 54: TABLE 6.2(v)]*

| | | | | | GAS: | | NATURAL | |
|---------------|--|--------|--------|--------|-------------------|--------|---------|---------|
| | | | | | INLET PRESSURE: | | 2.0 psi | |
| | | | | | PRESSURE DROP: | | 1.0 psi | |
| | | | | | SPECIFIC GRAVITY: | | 0.60 | |
| | PIPE SIZE (inch) | | | | | | | |
| NOMINAL OD: | ½ | ¾ | 1 | 1 ¼ | 1 ½ | 2 | 3 | 4 |
| DESIGNATION: | SDR 9.3 | SDR 11 | SDR 11 | SDR 10 | SDR 11 | SDR 11 | SDR 11 | SDR 11 |
| ACTUAL ID: | 0.660 | 0.860 | 1.077 | 1.328 | 1.554 | 1.943 | 2.864 | 3.682 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | | | | | | | |
| 10 | 1860 | 3720 | 6710 | 11 600 | 17 600 | 31 600 | 87 300 | 169 000 |
| 20 | 1280 | 2560 | 4610 | 7990 | 12 100 | 21 700 | 60 000 | 116 000 |
| 30 | 1030 | 2050 | 3710 | 6420 | 9690 | 17 400 | 48 200 | 93 200 |
| 40 | 878 | 1760 | 3170 | 5490 | 8300 | 14 900 | 41 200 | 79 700 |
| 50 | 778 | 1560 | 2810 | 4870 | 7350 | 13 200 | 36 600 | 70 700 |
| 60 | 705 | 1410 | 2550 | 4410 | 6660 | 12 000 | 33 100 | 64 000 |
| 70 | 649 | 1300 | 2340 | 4060 | 6130 | 11 000 | 30 500 | 58 900 |
| 80 | 603 | 1210 | 2180 | 3780 | 5700 | 10 200 | 28 300 | 54 800 |
| 90 | 566 | 1130 | 2050 | 3540 | 5350 | 9610 | 26 600 | 51 400 |
| 100 | 535 | 1070 | 1930 | 3350 | 5050 | 9080 | 25 100 | 48 600 |
| 125 | 474 | 949 | 1710 | 2970 | 4480 | 8050 | 22 300 | 43 000 |
| 150 | 429 | 860 | 1550 | 2690 | 4060 | 7290 | 20 200 | 39 000 |
| 175 | 395 | 791 | 1430 | 2470 | 3730 | 6710 | 18 600 | 35 900 |
| 200 | 368 | 736 | 1330 | 2300 | 3470 | 6240 | 17 300 | 33 400 |
| 250 | 326 | 652 | 1180 | 2040 | 3080 | 5530 | 15 300 | 29 600 |
| 300 | 295 | 591 | 1070 | 1850 | 2790 | 5010 | 13 900 | 26 800 |
| 350 | 272 | 544 | 981 | 1700 | 2570 | 4610 | 12 800 | 24 700 |
| 400 | 253 | 506 | 913 | 1580 | 2390 | 4290 | 11 900 | 22 900 |
| 450 | 237 | 475 | 856 | 1480 | 2240 | 4020 | 11 100 | 21 500 |
| 500 | 224 | 448 | 809 | 1400 | 2120 | 3800 | 10 500 | 20 300 |
| 550 | 213 | 426 | 768 | 1330 | 2010 | 3610 | 9990 | 19 300 |
| 600 | 203 | 406 | 733 | 1270 | 1920 | 3440 | 9530 | 18 400 |
| 650 | 194 | 389 | 702 | 1220 | 1840 | 3300 | 9130 | 17 600 |
| 700 | 187 | 374 | 674 | 1170 | 1760 | 3170 | 8770 | 16 900 |
| 750 | 180 | 360 | 649 | 1130 | 1700 | 3050 | 8450 | 16 300 |
| 800 | 174 | 348 | 627 | 1090 | 1640 | 2950 | 8160 | 15 800 |
| 850 | 168 | 336 | 607 | 1050 | 1590 | 2850 | 7890 | 15 300 |
| 900 | 163 | 326 | 588 | 1020 | 1540 | 2770 | 7650 | 14 800 |
| 950 | 158 | 317 | 572 | 990 | 1500 | 2690 | 7430 | 14 400 |
| 1000 | 154 | 308 | 556 | 963 | 1450 | 2610 | 7230 | 14 000 |
| 1100 | 146 | 293 | 528 | 915 | 1380 | 2480 | 6870 | 13 300 |
| 1200 | 139 | 279 | 504 | 873 | 1320 | 2370 | 6550 | 12 700 |
| 1300 | 134 | 267 | 482 | 836 | 1260 | 2270 | 6270 | 12 100 |
| 1400 | 128 | 257 | 463 | 803 | 1210 | 2180 | 6030 | 11 600 |
| 1500 | 124 | 247 | 446 | 773 | 1170 | 2100 | 5810 | 11 200 |
| 1600 | 119 | 239 | 431 | 747 | 1130 | 2030 | 5610 | 10 800 |
| 1700 | 115 | 231 | 417 | 723 | 1090 | 1960 | 5430 | 10 500 |
| 1800 | 112 | 224 | 404 | 701 | 1060 | 1900 | 5260 | 10 200 |
| 1900 | 109 | 218 | 393 | 680 | 1030 | 1850 | 5110 | 9900 |
| 2000 | 106 | 212 | 382 | 662 | 1000 | 1800 | 4970 | 9600 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283 m³/h, 1 pound-force per square inch = 6.8947 kPa

* Table entries are rounded to 3 significant digits.

FUEL GAS PIPING

TABLE 1216.2(22)
POLYETHYLENE PLASTIC TUBING [NFPA 54: TABLE 6.2(w)]^{2, 3}

| | | |
|----------------------|---|---------------|
| | GAS: NATURAL | |
| | INLET PRESSURE: LESS THAN 2.0 psi | |
| | PRESSURE DROP: 0.3 in. w.c. | |
| | SPECIFIC GRAVITY: 0.60 | |
| | PLASTIC TUBING SIZE (CTS)¹ (inch) | |
| NOMINAL OD: | ½ | 1 |
| DESIGNATION: | SDR 7 | SDR 11 |
| ACTUAL ID: | 0.445 | 0.927 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | |
| 10 | 54 | 372 |
| 20 | 37 | 256 |
| 30 | 30 | 205 |
| 40 | 26 | 176 |
| 50 | 23 | 156 |
| 60 | 21 | 141 |
| 70 | 19 | 130 |
| 80 | 18 | 121 |
| 90 | 17 | 113 |
| 100 | 16 | 107 |
| 125 | 14 | 95 |
| 150 | 13 | 86 |
| 175 | 12 | 79 |
| 200 | 11 | 74 |
| 225 | 10 | 69 |
| 250 | NA | 65 |
| 275 | NA | 62 |
| 300 | NA | 59 |
| 350 | NA | 54 |
| 400 | NA | 51 |
| 450 | NA | 47 |
| 500 | NA | 45 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

Notes:

¹ CTS = Copper tube size.

² Table entries are rounded to 3 significant digits.

³ NA means a flow of less than 10 ft³/h (0.283 m³/h).

TABLE 1216.2(23)
POLYETHYLENE PLASTIC TUBING [NFPA 54: TABLE 6.2(x)]^{2, 3}

| | | |
|----------------------|---|---------------|
| | GAS: NATURAL | |
| | INLET PRESSURE: LESS THAN 2.0 psi | |
| | PRESSURE DROP: 0.5 in. w.c. | |
| | SPECIFIC GRAVITY: 0.60 | |
| | PLASTIC TUBING SIZE (CTS)¹ (inch) | |
| NOMINAL OD: | ½ | 1 |
| DESIGNATION: | SDR 7 | SDR 11 |
| ACTUAL ID: | 0.445 | 0.927 |
| LENGTH (feet) | CAPACITY IN CUBIC FEET OF GAS PER HOUR | |
| 10 | 72 | 490 |
| 20 | 49 | 337 |
| 30 | 39 | 271 |
| 40 | 34 | 232 |
| 50 | 30 | 205 |
| 60 | 27 | 186 |
| 70 | 25 | 171 |
| 80 | 23 | 159 |
| 90 | 22 | 149 |
| 100 | 21 | 141 |
| 125 | 18 | 125 |
| 150 | 17 | 113 |
| 175 | 15 | 104 |
| 200 | 14 | 97 |
| 225 | 13 | 91 |
| 250 | 12 | 86 |
| 275 | 11 | 82 |
| 300 | 11 | 78 |
| 350 | 10 | 72 |
| 400 | NA | 67 |
| 450 | NA | 63 |
| 500 | NA | 59 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 cubic foot per hour = 0.0283m³/h, 1 pound-force per square inch = 6.8947 kPa, 1 inch water column = 0.249 kPa

Notes:

¹ CTS = Copper tube size.

² Table entries are rounded to 3 significant digits.

³ NA means a flow of less than 10 ft³/h (0.283 m³/h).

TABLE 1216.2(24)
SCHEDULE 40 METALLIC PIPE [NFPA 54: TABLE 6.3(a)]*

| | | | | | | GAS: | | UNDILUTED PROPANE | |
|---|---------------------------------------|-------|--------|--------|--------|-------------------|---------|-------------------|---------|
| | | | | | | INLET PRESSURE: | | 10.0 psi | |
| | | | | | | PRESSURE DROP: | | 1.0 psi | |
| | | | | | | SPECIFIC GRAVITY: | | 1.50 | |
| INTENDED USE: PIPE SIZING BETWEEN FIRST STAGE (HIGH PRESSURE) REGULATOR AND SECOND STAGE (LOW PRESSURE) REGULATOR | | | | | | | | | |
| | PIPE SIZE (inch) | | | | | | | | |
| NOMINAL INSIDE: | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 2½ | 3 | 4 |
| ACTUAL: | 0.622 | 0.824 | 1.049 | 1.380 | 1.610 | 2.067 | 2.469 | 3.068 | 4.026 |
| LENGTH (feet) | CAPACITY IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| 10 | 3320 | 6950 | 13 100 | 26 900 | 40 300 | 77 600 | 124 000 | 219 000 | 446 000 |
| 20 | 2280 | 4780 | 9000 | 18 500 | 27 700 | 53 300 | 85 000 | 150 000 | 306 000 |
| 30 | 1830 | 3840 | 7220 | 14 800 | 22 200 | 42 800 | 68 200 | 121 000 | 246 000 |
| 40 | 1570 | 3280 | 6180 | 12 700 | 19 000 | 36 600 | 58 400 | 103 000 | 211 000 |
| 50 | 1390 | 2910 | 5480 | 11 300 | 16 900 | 32 500 | 51 700 | 91 500 | 187 000 |
| 60 | 1260 | 2640 | 4970 | 10 200 | 15 300 | 29 400 | 46 900 | 82 900 | 169 000 |
| 70 | 1160 | 2430 | 4570 | 9380 | 14 100 | 27 100 | 43 100 | 76 300 | 156 000 |
| 80 | 1080 | 2260 | 4250 | 8730 | 13 100 | 25 200 | 40 100 | 70 900 | 145 000 |
| 90 | 1010 | 2120 | 3990 | 8190 | 12 300 | 23 600 | 37 700 | 66 600 | 136 000 |
| 100 | 956 | 2000 | 3770 | 7730 | 11 600 | 22 300 | 35 600 | 62 900 | 128 000 |
| 125 | 848 | 1770 | 3340 | 6850 | 10 300 | 19 800 | 31 500 | 55 700 | 114 000 |
| 150 | 768 | 1610 | 3020 | 6210 | 9300 | 17 900 | 28 600 | 50 500 | 103 000 |
| 175 | 706 | 1480 | 2780 | 5710 | 8560 | 16 500 | 26 300 | 46 500 | 94 700 |
| 200 | 657 | 1370 | 2590 | 5320 | 7960 | 15 300 | 24 400 | 43 200 | 88 100 |
| 250 | 582 | 1220 | 2290 | 4710 | 7060 | 13 600 | 21 700 | 38 300 | 78 100 |
| 300 | 528 | 1100 | 2080 | 4270 | 6400 | 12 300 | 19 600 | 34 700 | 70 800 |
| 350 | 486 | 1020 | 1910 | 3930 | 5880 | 11 300 | 18 100 | 31 900 | 65 100 |
| 400 | 452 | 945 | 1780 | 3650 | 5470 | 10 500 | 16 800 | 29 700 | 60 600 |
| 450 | 424 | 886 | 1670 | 3430 | 5140 | 9890 | 15 800 | 27 900 | 56 800 |
| 500 | 400 | 837 | 1580 | 3240 | 4850 | 9340 | 14 900 | 26 300 | 53 700 |
| 550 | 380 | 795 | 1500 | 3070 | 4610 | 8870 | 14 100 | 25 000 | 51 000 |
| 600 | 363 | 759 | 1430 | 2930 | 4400 | 8460 | 13 500 | 23 900 | 48 600 |
| 650 | 347 | 726 | 1370 | 2810 | 4210 | 8110 | 12 900 | 22 800 | 46 600 |
| 700 | 334 | 698 | 1310 | 2700 | 4040 | 7790 | 12 400 | 21 900 | 44 800 |
| 750 | 321 | 672 | 1270 | 2600 | 3900 | 7500 | 12 000 | 21 100 | 43 100 |
| 800 | 310 | 649 | 1220 | 2510 | 3760 | 7240 | 11 500 | 20 400 | 41 600 |
| 850 | 300 | 628 | 1180 | 2430 | 3640 | 7010 | 11 200 | 19 800 | 40 300 |
| 900 | 291 | 609 | 1150 | 2360 | 3530 | 6800 | 10 800 | 19 200 | 39 100 |
| 950 | 283 | 592 | 1110 | 2290 | 3430 | 6600 | 10 500 | 18 600 | 37 900 |
| 1000 | 275 | 575 | 1080 | 2230 | 3330 | 6420 | 10 200 | 18 100 | 36 900 |
| 1100 | 261 | 546 | 1030 | 2110 | 3170 | 6100 | 9720 | 17 200 | 35 000 |
| 1200 | 249 | 521 | 982 | 2020 | 3020 | 5820 | 9270 | 16 400 | 33 400 |
| 1300 | 239 | 499 | 940 | 1930 | 2890 | 5570 | 8880 | 15 700 | 32 000 |
| 1400 | 229 | 480 | 903 | 1850 | 2780 | 5350 | 8530 | 15 100 | 30 800 |
| 1500 | 221 | 462 | 870 | 1790 | 2680 | 5160 | 8220 | 14 500 | 29 600 |
| 1600 | 213 | 446 | 840 | 1730 | 2590 | 4980 | 7940 | 14 000 | 28 600 |
| 1700 | 206 | 432 | 813 | 1670 | 2500 | 4820 | 7680 | 13 600 | 27 700 |
| 1800 | 200 | 419 | 789 | 1620 | 2430 | 4670 | 7450 | 13 200 | 26 900 |
| 1900 | 194 | 407 | 766 | 1570 | 2360 | 4540 | 7230 | 12 800 | 26 100 |
| 2000 | 189 | 395 | 745 | 1530 | 2290 | 4410 | 7030 | 12 400 | 25 400 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 pound-force per square inch = 6.8947 kPa

* Table entries are rounded to 3 significant digits.

FUEL GAS PIPING

TABLE 1216.2(25)
SCHEDULE 40 METALLIC PIPE [NFPA 54: TABLE 6.3(b)]*

| | | | | | | GAS: UNDILUTED PROPANE | | | |
|---|---------------------------------------|--------|--------|--------|--------|--------------------------|---------|---------|---------|
| | | | | | | INLET PRESSURE: 10.0 psi | | | |
| | | | | | | PRESSURE DROP: 3.0 psi | | | |
| | | | | | | SPECIFIC GRAVITY: 1.50 | | | |
| INTENDED USE: PIPE SIZING BETWEEN FIRST STAGE (HIGH PRESSURE) REGULATOR AND SECOND STAGE (LOW PRESSURE) REGULATOR | | | | | | | | | |
| | PIPE SIZE (Inch) | | | | | | | | |
| NOMINAL INSIDE: | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 2½ | 3 | 4 |
| ACTUAL: | 0.622 | 0.824 | 1.049 | 1.380 | 1.610 | 2.067 | 2.469 | 3.068 | 4.026 |
| LENGTH (feet) | CAPACITY IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| 10 | 5890 | 12 300 | 23 200 | 47 600 | 71 300 | 137 000 | 219 000 | 387 000 | 789 000 |
| 20 | 4050 | 8460 | 15 900 | 32 700 | 49 000 | 94 400 | 150 000 | 266 000 | 543 000 |
| 30 | 3250 | 6790 | 12 800 | 26 300 | 39 400 | 75 800 | 121 000 | 214 000 | 436 000 |
| 40 | 2780 | 5810 | 11 000 | 22 500 | 33 700 | 64 900 | 103 000 | 183 000 | 373 000 |
| 50 | 2460 | 5150 | 9710 | 19 900 | 29 900 | 57 500 | 91 600 | 162 000 | 330 000 |
| 60 | 2230 | 4670 | 8790 | 18 100 | 27 100 | 52 100 | 83 000 | 147 000 | 299 000 |
| 70 | 2050 | 4300 | 8090 | 16 600 | 24 900 | 47 900 | 76 400 | 135 000 | 275 000 |
| 80 | 1910 | 4000 | 7530 | 15 500 | 23 200 | 44 600 | 71 100 | 126 000 | 256 000 |
| 90 | 1790 | 3750 | 7060 | 14 500 | 21 700 | 41 800 | 66 700 | 118 000 | 240 000 |
| 100 | 1690 | 3540 | 6670 | 13 700 | 20 500 | 39 500 | 63 000 | 111 000 | 227 000 |
| 125 | 1500 | 3140 | 5910 | 12 100 | 18 200 | 35 000 | 55 800 | 98 700 | 201 000 |
| 150 | 1360 | 2840 | 5360 | 11 000 | 16 500 | 31 700 | 50 600 | 89 400 | 182 000 |
| 175 | 1250 | 2620 | 4930 | 10 100 | 15 200 | 29 200 | 46 500 | 82 300 | 167 800 |
| 200 | 1160 | 2430 | 4580 | 9410 | 14 100 | 27 200 | 43 300 | 76 500 | 156 100 |
| 250 | 1030 | 2160 | 4060 | 8340 | 12 500 | 24 100 | 38 400 | 67 800 | 138 400 |
| 300 | 935 | 1950 | 3680 | 7560 | 11 300 | 21 800 | 34 800 | 61 500 | 125 400 |
| 350 | 860 | 1800 | 3390 | 6950 | 10 400 | 20 100 | 32 000 | 56 500 | 115 300 |
| 400 | 800 | 1670 | 3150 | 6470 | 9690 | 18 700 | 29 800 | 52 600 | 107 300 |
| 450 | 751 | 1570 | 2960 | 6070 | 9090 | 17 500 | 27 900 | 49 400 | 100 700 |
| 500 | 709 | 1480 | 2790 | 5730 | 8590 | 16 500 | 26 400 | 46 600 | 95 100 |
| 550 | 673 | 1410 | 2650 | 5450 | 8160 | 15 700 | 25 000 | 44 300 | 90 300 |
| 600 | 642 | 1340 | 2530 | 5200 | 7780 | 15 000 | 23 900 | 42 200 | 86 200 |
| 650 | 615 | 1290 | 2420 | 4980 | 7450 | 14 400 | 22 900 | 40 500 | 82 500 |
| 700 | 591 | 1240 | 2330 | 4780 | 7160 | 13 800 | 22 000 | 38 900 | 79 300 |
| 750 | 569 | 1190 | 2240 | 4600 | 6900 | 13 300 | 21 200 | 37 400 | 76 400 |
| 800 | 550 | 1150 | 2170 | 4450 | 6660 | 12 800 | 20 500 | 36 200 | 73 700 |
| 850 | 532 | 1110 | 2100 | 4300 | 6450 | 12 400 | 19 800 | 35 000 | 71 400 |
| 900 | 516 | 1080 | 2030 | 4170 | 6250 | 12 000 | 19 200 | 33 900 | 69 200 |
| 950 | 501 | 1050 | 1970 | 4050 | 6070 | 11 700 | 18 600 | 32 900 | 67 200 |
| 1000 | 487 | 1020 | 1920 | 3940 | 5900 | 11 400 | 18 100 | 32 000 | 65 400 |
| 1100 | 463 | 968 | 1820 | 3740 | 5610 | 10 800 | 17 200 | 30 400 | 62 100 |
| 1200 | 442 | 923 | 1740 | 3570 | 5350 | 10 300 | 16 400 | 29 000 | 59 200 |
| 1300 | 423 | 884 | 1670 | 3420 | 5120 | 9870 | 15 700 | 27 800 | 56 700 |
| 1400 | 406 | 849 | 1600 | 3280 | 4920 | 9480 | 15 100 | 26 700 | 54 500 |
| 1500 | 391 | 818 | 1540 | 3160 | 4740 | 9130 | 14 600 | 25 700 | 52 500 |
| 1600 | 378 | 790 | 1490 | 3060 | 4580 | 8820 | 14 100 | 24 800 | 50 700 |
| 1700 | 366 | 765 | 1440 | 2960 | 4430 | 8530 | 13 600 | 24 000 | 49 000 |
| 1800 | 355 | 741 | 1400 | 2870 | 4300 | 8270 | 13 200 | 23 300 | 47 600 |
| 1900 | 344 | 720 | 1360 | 2780 | 4170 | 8040 | 12 800 | 22 600 | 46 200 |
| 2000 | 335 | 700 | 1320 | 2710 | 4060 | 7820 | 12 500 | 22 000 | 44 900 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 pound-force per square inch = 6.8947 kPa

* Table entries are rounded to 3 significant digits.

TABLE 1216.2(26)
SCHEDULE 40 METALLIC PIPE [NFPA 54: TABLE 6.3(c)]*

| | | | | | | GAS: UNDILUTED PROPANE | | | |
|---|---------------------------------------|-------|--------|--------|--------|-------------------------|--------|---------|---------|
| | | | | | | INLET PRESSURE: 2.0 psi | | | |
| | | | | | | PRESSURE DROP: 1.0 psi | | | |
| | | | | | | SPECIFIC GRAVITY: 1.50 | | | |
| INTENDED USE: PIPE SIZING BETWEEN 2 PSI SERVICE AND LINE PRESSURE REGULATOR | | | | | | | | | |
| | PIPE SIZE (Inch) | | | | | | | | |
| NOMINAL: | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 2½ | 3 | 4 |
| ACTUAL ID: | 0.622 | 0.824 | 1.049 | 1.380 | 1.610 | 2.067 | 2.469 | 3.068 | 4.026 |
| LENGTH (feet) | CAPACITY IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| 10 | 2680 | 5590 | 10 500 | 21 600 | 32 400 | 62 400 | 99 500 | 176 000 | 359 000 |
| 20 | 1840 | 3850 | 7240 | 14 900 | 22 300 | 42 900 | 68 400 | 121 000 | 247 000 |
| 30 | 1480 | 3090 | 5820 | 11 900 | 17 900 | 34 500 | 54 900 | 97 100 | 198 000 |
| 40 | 1260 | 2640 | 4980 | 10 200 | 15 300 | 29 500 | 47 000 | 83 100 | 170 000 |
| 50 | 1120 | 2340 | 4410 | 9060 | 13 600 | 26 100 | 41 700 | 73 700 | 150 000 |
| 60 | 1010 | 2120 | 4000 | 8210 | 12 300 | 23 700 | 37 700 | 66 700 | 136 000 |
| 70 | 934 | 1950 | 3680 | 7550 | 11 300 | 21 800 | 34 700 | 61 400 | 125 000 |
| 80 | 869 | 1820 | 3420 | 7020 | 10 500 | 20 300 | 32 300 | 57 100 | 116 000 |
| 90 | 815 | 1700 | 3210 | 6590 | 9880 | 19 000 | 30 300 | 53 600 | 109 000 |
| 100 | 770 | 1610 | 3030 | 6230 | 9330 | 18 000 | 28 600 | 50 600 | 103 000 |
| 125 | 682 | 1430 | 2690 | 5520 | 8270 | 15 900 | 25 400 | 44 900 | 91 500 |
| 150 | 618 | 1290 | 2440 | 5000 | 7490 | 14 400 | 23 000 | 40 700 | 82 900 |
| 175 | 569 | 1190 | 2240 | 4600 | 6890 | 13 300 | 21 200 | 37 400 | 76 300 |
| 200 | 529 | 1110 | 2080 | 4280 | 6410 | 12 300 | 19 700 | 34 800 | 71 000 |
| 250 | 469 | 981 | 1850 | 3790 | 5680 | 10 900 | 17 400 | 30 800 | 62 900 |
| 300 | 425 | 889 | 1670 | 3440 | 5150 | 9920 | 15 800 | 27 900 | 57 000 |
| 350 | 391 | 817 | 1540 | 3160 | 4740 | 9120 | 14 500 | 25 700 | 52 400 |
| 400 | 364 | 760 | 1430 | 2940 | 4410 | 8490 | 13 500 | 23 900 | 48 800 |
| 450 | 341 | 714 | 1340 | 2760 | 4130 | 7960 | 12 700 | 22 400 | 45 800 |
| 500 | 322 | 674 | 1270 | 2610 | 3910 | 7520 | 12 000 | 21 200 | 43 200 |
| 550 | 306 | 640 | 1210 | 2480 | 3710 | 7140 | 11 400 | 20 100 | 41 100 |
| 600 | 292 | 611 | 1150 | 2360 | 3540 | 6820 | 10 900 | 19 200 | 39 200 |
| 650 | 280 | 585 | 1100 | 2260 | 3390 | 6530 | 10 400 | 18 400 | 37 500 |
| 700 | 269 | 562 | 1060 | 2170 | 3260 | 6270 | 9990 | 17 700 | 36 000 |
| 750 | 259 | 541 | 1020 | 2090 | 3140 | 6040 | 9630 | 17 000 | 34 700 |
| 800 | 250 | 523 | 985 | 2020 | 3030 | 5830 | 9300 | 16 400 | 33 500 |
| 850 | 242 | 506 | 953 | 1960 | 2930 | 5640 | 9000 | 15 900 | 32 400 |
| 900 | 235 | 490 | 924 | 1900 | 2840 | 5470 | 8720 | 15 400 | 31 500 |
| 950 | 228 | 476 | 897 | 1840 | 2760 | 5310 | 8470 | 15 000 | 30 500 |
| 1000 | 222 | 463 | 873 | 1790 | 2680 | 5170 | 8240 | 14 600 | 29 700 |
| 1100 | 210 | 440 | 829 | 1700 | 2550 | 4910 | 7830 | 13 800 | 28 200 |
| 1200 | 201 | 420 | 791 | 1620 | 2430 | 4680 | 7470 | 13 200 | 26 900 |
| 1300 | 192 | 402 | 757 | 1550 | 2330 | 4490 | 7150 | 12 600 | 25 800 |
| 1400 | 185 | 386 | 727 | 1490 | 2240 | 4310 | 6870 | 12 100 | 24 800 |
| 1500 | 178 | 372 | 701 | 1440 | 2160 | 4150 | 6620 | 11 700 | 23 900 |
| 1600 | 172 | 359 | 677 | 1390 | 2080 | 4010 | 6390 | 11 300 | 23 000 |
| 1700 | 166 | 348 | 655 | 1340 | 2010 | 3880 | 6180 | 10 900 | 22 300 |
| 1800 | 161 | 337 | 635 | 1300 | 1950 | 3760 | 6000 | 10 600 | 21 600 |
| 1900 | 157 | 327 | 617 | 1270 | 1900 | 3650 | 5820 | 10 300 | 21 000 |
| 2000 | 152 | 318 | 600 | 1230 | 1840 | 3550 | 5660 | 10 000 | 20 400 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 pound-force per square inch = 6.8947 kPa

* Table entries are rounded to 3 significant digits.

FUEL GAS PIPING

TABLE 1216.2(27)
SCHEDULE 40 METALLIC PIPE [NFPA 54: TABLE 6.3(d)]*

| | | | | | | GAS: UNDILUTED PROPANE | | | |
|---|---------------------------------------|-------|-------|-------|-------|-------------------------------|--------|--------|--------|
| | | | | | | INLET PRESSURE: 11.0 in. w.c. | | | |
| | | | | | | PRESSURE DROP: 0.5 in. w.c. | | | |
| | | | | | | SPECIFIC GRAVITY: 1.50 | | | |
| INTENDED USE: PIPE SIZING BETWEEN SINGLE OR SECOND STAGE (LOW PRESSURE) REGULATOR AND APPLIANCE | | | | | | | | | |
| | PIPE SIZE (inch) | | | | | | | | |
| NOMINAL INSIDE: | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 2½ | 3 | 4 |
| ACTUAL ID: | 0.622 | 0.824 | 1.049 | 1.380 | 1.610 | 2.067 | 2.469 | 3.068 | 4.026 |
| LENGTH (feet) | CAPACITY IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| 10 | 291 | 608 | 1150 | 2350 | 3520 | 6790 | 10 800 | 19 100 | 39 000 |
| 20 | 200 | 418 | 787 | 1620 | 2420 | 4660 | 7430 | 13 100 | 26 800 |
| 30 | 160 | 336 | 632 | 1300 | 1940 | 3750 | 5970 | 10 600 | 21 500 |
| 40 | 137 | 287 | 541 | 1110 | 1660 | 3210 | 5110 | 9030 | 18 400 |
| 50 | 122 | 255 | 480 | 985 | 1480 | 2840 | 4530 | 8000 | 16 300 |
| 60 | 110 | 231 | 434 | 892 | 1340 | 2570 | 4100 | 7250 | 14 800 |
| 80 | 101 | 212 | 400 | 821 | 1230 | 2370 | 3770 | 6670 | 13 600 |
| 100 | 94 | 197 | 372 | 763 | 1140 | 2200 | 3510 | 6210 | 12 700 |
| 125 | 89 | 185 | 349 | 716 | 1070 | 2070 | 3290 | 5820 | 11 900 |
| 150 | 84 | 175 | 330 | 677 | 1010 | 1950 | 3110 | 5500 | 11 200 |
| 175 | 74 | 155 | 292 | 600 | 899 | 1730 | 2760 | 4880 | 9950 |
| 200 | 67 | 140 | 265 | 543 | 814 | 1570 | 2500 | 4420 | 9010 |
| 250 | 62 | 129 | 243 | 500 | 749 | 1440 | 2300 | 4060 | 8290 |
| 300 | 58 | 120 | 227 | 465 | 697 | 1340 | 2140 | 3780 | 7710 |
| 350 | 51 | 107 | 201 | 412 | 618 | 1190 | 1900 | 3350 | 6840 |
| 400 | 46 | 97 | 182 | 373 | 560 | 1080 | 1720 | 3040 | 6190 |
| 450 | 42 | 89 | 167 | 344 | 515 | 991 | 1580 | 2790 | 5700 |
| 500 | 40 | 83 | 156 | 320 | 479 | 922 | 1470 | 2600 | 5300 |
| 550 | 37 | 78 | 146 | 300 | 449 | 865 | 1380 | 2440 | 4970 |
| 600 | 35 | 73 | 138 | 283 | 424 | 817 | 1300 | 2300 | 4700 |
| 650 | 33 | 70 | 131 | 269 | 403 | 776 | 1240 | 2190 | 4460 |
| 700 | 32 | 66 | 125 | 257 | 385 | 741 | 1180 | 2090 | 4260 |
| 750 | 30 | 64 | 120 | 246 | 368 | 709 | 1130 | 2000 | 4080 |
| 800 | 29 | 61 | 115 | 236 | 354 | 681 | 1090 | 1920 | 3920 |
| 850 | 28 | 59 | 111 | 227 | 341 | 656 | 1050 | 1850 | 3770 |
| 900 | 27 | 57 | 107 | 220 | 329 | 634 | 1010 | 1790 | 3640 |
| 950 | 26 | 55 | 104 | 213 | 319 | 613 | 978 | 1730 | 3530 |
| 1000 | 25 | 53 | 100 | 206 | 309 | 595 | 948 | 1680 | 3420 |
| 1100 | 25 | 52 | 97 | 200 | 300 | 578 | 921 | 1630 | 3320 |
| 1200 | 24 | 50 | 95 | 195 | 292 | 562 | 895 | 1580 | 3230 |
| 1300 | 23 | 48 | 90 | 185 | 277 | 534 | 850 | 1500 | 3070 |
| 1400 | 22 | 46 | 86 | 176 | 264 | 509 | 811 | 1430 | 2930 |
| 1500 | 21 | 44 | 82 | 169 | 253 | 487 | 777 | 1370 | 2800 |
| 1600 | 20 | 42 | 79 | 162 | 243 | 468 | 746 | 1320 | 2690 |
| 1700 | 19 | 40 | 76 | 156 | 234 | 451 | 719 | 1270 | 2590 |
| 1800 | 19 | 39 | 74 | 151 | 226 | 436 | 694 | 1230 | 2500 |
| 1900 | 18 | 38 | 71 | 146 | 219 | 422 | 672 | 1190 | 2420 |
| 2000 | 18 | 37 | 69 | 142 | 212 | 409 | 652 | 1150 | 2350 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 inch water column = 0.249 kPa

* Table entries are rounded to 3 significant digits.

TABLE 1216.2(28)
SEMI-RIGID COPPER TUBING [NFPA 54: TABLE 6.3(e)]²

| | | | | | | | GAS: | | UNDILUTED PROPANE | |
|---|--------|---------------------------------------|-------|-------|-------|-------|-------------------|--------|-------------------|--------|
| | | | | | | | INLET PRESSURE: | | 10.0 psi | |
| | | | | | | | PRESSURE DROP: | | 1.0 psi | |
| | | | | | | | SPECIFIC GRAVITY: | | 1.50 | |
| INTENDED USE: TUBE SIZING BETWEEN FIRST STAGE (HIGH PRESSURE) REGULATOR AND SECOND STAGE (LOW PRESSURE) REGULATOR | | | | | | | | | | |
| | | TUBE SIZE (inch) | | | | | | | | |
| NOMINAL: | K & L: | ¼ | ⅜ | ½ | ⅝ | ¾ | 1 | 1¼ | 1½ | 2 |
| | ACR: | ⅜ | ½ | ⅝ | ¾ | ⅞ | 1½ | 1¾ | — | — |
| OUTSIDE: | | 0.375 | 0.500 | 0.625 | 0.750 | 0.875 | 1.125 | 1.375 | 1.625 | 2.125 |
| INSIDE: ¹ | | 0.305 | 0.402 | 0.527 | 0.652 | 0.745 | 0.995 | 1.245 | 1.481 | 1.959 |
| LENGTH (feet) | | CAPACITY IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| 10 | | 513 | 1060 | 2150 | 3760 | 5330 | 11 400 | 20 500 | 32 300 | 67 400 |
| 20 | | 352 | 727 | 1480 | 2580 | 3670 | 7830 | 14 100 | 22 200 | 46 300 |
| 30 | | 283 | 584 | 1190 | 2080 | 2940 | 6290 | 11 300 | 17 900 | 37 200 |
| 40 | | 242 | 500 | 1020 | 1780 | 2520 | 5380 | 9690 | 15 300 | 31 800 |
| 50 | | 215 | 443 | 901 | 1570 | 2230 | 4770 | 8590 | 13 500 | 28 200 |
| 60 | | 194 | 401 | 816 | 1430 | 2020 | 4320 | 7780 | 12 300 | 25 600 |
| 70 | | 179 | 369 | 751 | 1310 | 1860 | 3980 | 7160 | 11 300 | 23 500 |
| 80 | | 166 | 343 | 699 | 1220 | 1730 | 3700 | 6660 | 10 500 | 21 900 |
| 90 | | 156 | 322 | 655 | 1150 | 1630 | 3470 | 6250 | 9850 | 20 500 |
| 100 | | 147 | 304 | 619 | 1080 | 1540 | 3280 | 5900 | 9310 | 19 400 |
| 125 | | 131 | 270 | 549 | 959 | 1360 | 2910 | 5230 | 8250 | 17 200 |
| 150 | | 118 | 244 | 497 | 869 | 1230 | 2630 | 4740 | 7470 | 15 600 |
| 175 | | 109 | 225 | 457 | 799 | 1130 | 2420 | 4360 | 6880 | 14 300 |
| 200 | | 101 | 209 | 426 | 744 | 1060 | 2250 | 4060 | 6400 | 13 300 |
| 250 | | 90 | 185 | 377 | 659 | 935 | 2000 | 3600 | 5670 | 11 800 |
| 300 | | 81 | 168 | 342 | 597 | 847 | 1810 | 3260 | 5140 | 10 700 |
| 350 | | 75 | 155 | 314 | 549 | 779 | 1660 | 3000 | 4730 | 9840 |
| 400 | | 70 | 144 | 292 | 511 | 725 | 1550 | 2790 | 4400 | 9160 |
| 450 | | 65 | 135 | 274 | 480 | 680 | 1450 | 2620 | 4130 | 8590 |
| 500 | | 62 | 127 | 259 | 453 | 643 | 1370 | 2470 | 3900 | 8120 |
| 550 | | 59 | 121 | 246 | 430 | 610 | 1300 | 2350 | 3700 | 7710 |
| 600 | | 56 | 115 | 235 | 410 | 582 | 1240 | 2240 | 3530 | 7350 |
| 650 | | 54 | 111 | 225 | 393 | 558 | 1190 | 2140 | 3380 | 7040 |
| 700 | | 51 | 106 | 216 | 378 | 536 | 1140 | 2060 | 3250 | 6770 |
| 750 | | 50 | 102 | 208 | 364 | 516 | 1100 | 1980 | 3130 | 6520 |
| 800 | | 48 | 99 | 201 | 351 | 498 | 1060 | 1920 | 3020 | 6290 |
| 850 | | 46 | 96 | 195 | 340 | 482 | 1030 | 1850 | 2920 | 6090 |
| 900 | | 45 | 93 | 189 | 330 | 468 | 1000 | 1800 | 2840 | 5910 |
| 950 | | 44 | 90 | 183 | 320 | 454 | 970 | 1750 | 2750 | 5730 |
| 1000 | | 42 | 88 | 178 | 311 | 442 | 944 | 1700 | 2680 | 5580 |
| 1100 | | 40 | 83 | 169 | 296 | 420 | 896 | 1610 | 2540 | 5300 |
| 1200 | | 38 | 79 | 161 | 282 | 400 | 855 | 1540 | 2430 | 5050 |
| 1300 | | 37 | 76 | 155 | 270 | 383 | 819 | 1470 | 2320 | 4840 |
| 1400 | | 35 | 73 | 148 | 260 | 368 | 787 | 1420 | 2230 | 4650 |
| 1500 | | 34 | 70 | 143 | 250 | 355 | 758 | 1360 | 2150 | 4480 |
| 1600 | | 33 | 68 | 138 | 241 | 343 | 732 | 1320 | 2080 | 4330 |
| 1700 | | 32 | 66 | 134 | 234 | 331 | 708 | 1270 | 2010 | 4190 |
| 1800 | | 31 | 64 | 130 | 227 | 321 | 687 | 1240 | 1950 | 4060 |
| 1900 | | 30 | 62 | 126 | 220 | 312 | 667 | 1200 | 1890 | 3940 |
| 2000 | | 29 | 60 | 122 | 214 | 304 | 648 | 1170 | 1840 | 3830 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 pound-force per square inch = 6.8947 kPa

Notes:

¹ Table capacities are based on Type K copper tubing inside diameter (shown), which has the smallest inside diameter of the copper tubing products.

² Table entries are rounded to 3 significant digits.

FUEL GAS PIPING

TABLE 1216.2(29)
SEMI-RIGID COPPER TUBING [NFPA 54: TABLE 6.3(f)]^{2, 3}

| | | | | | | | GAS: UNDILUTED PROPANE | | | |
|---|--------|---------------------------------------|-------|-------|-------|-------|-------------------------------|-------|-------|-------|
| | | | | | | | INLET PRESSURE: 11.0 in. w.c. | | | |
| | | | | | | | PRESSURE DROP: 0.5 in. w.c. | | | |
| | | | | | | | SPECIFIC GRAVITY: 1.50 | | | |
| INTENDED USE: TUBE SIZING BETWEEN SINGLE OR SECOND STAGE (LOW PRESSURE) REGULATOR AND APPLIANCE | | | | | | | | | | |
| | | TUBE SIZE (inch) | | | | | | | | |
| NOMINAL: | K & L: | ¼ | ⅜ | ½ | ⅝ | ¾ | 1 | 1¼ | 1½ | 2 |
| | ACR: | ⅜ | ½ | ⅝ | ¾ | ⅞ | 1½ | 1¾ | — | — |
| OUTSIDE: | | 0.375 | 0.500 | 0.625 | 0.750 | 0.875 | 1.125 | 1.375 | 1.625 | 2.125 |
| INSIDE: ¹ | | 0.305 | 0.402 | 0.527 | 0.652 | 0.745 | 0.995 | 1.245 | 1.481 | 1.959 |
| LENGTH (feet) | | CAPACITY IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| 10 | | 45 | 93 | 188 | 329 | 467 | 997 | 1800 | 2830 | 5890 |
| 20 | | 31 | 64 | 129 | 226 | 321 | 685 | 1230 | 1950 | 4050 |
| 30 | | 25 | 51 | 104 | 182 | 258 | 550 | 991 | 1560 | 3250 |
| 40 | | 21 | 44 | 89 | 155 | 220 | 471 | 848 | 1340 | 2780 |
| 50 | | 19 | 39 | 79 | 138 | 195 | 417 | 752 | 1180 | 2470 |
| 60 | | 17 | 35 | 71 | 125 | 177 | 378 | 681 | 1070 | 2240 |
| 70 | | 16 | 32 | 66 | 115 | 163 | 348 | 626 | 988 | 2060 |
| 80 | | 15 | 30 | 61 | 107 | 152 | 324 | 583 | 919 | 1910 |
| 90 | | 14 | 28 | 57 | 100 | 142 | 304 | 547 | 862 | 1800 |
| 100 | | 13 | 27 | 54 | 95 | 134 | 287 | 517 | 814 | 1700 |
| 125 | | 11 | 24 | 48 | 84 | 119 | 254 | 458 | 722 | 1500 |
| 150 | | 10 | 21 | 44 | 76 | 108 | 230 | 415 | 654 | 1360 |
| 175 | | NA | 20 | 40 | 70 | 99 | 212 | 382 | 602 | 1250 |
| 200 | | NA | 18 | 37 | 65 | 92 | 197 | 355 | 560 | 1170 |
| 250 | | NA | 16 | 33 | 58 | 82 | 175 | 315 | 496 | 1030 |
| 300 | | NA | 15 | 30 | 52 | 74 | 158 | 285 | 449 | 936 |
| 350 | | NA | 14 | 28 | 48 | 68 | 146 | 262 | 414 | 861 |
| 400 | | NA | 13 | 26 | 45 | 63 | 136 | 244 | 385 | 801 |
| 450 | | NA | 12 | 24 | 42 | 60 | 127 | 229 | 361 | 752 |
| 500 | | NA | 11 | 23 | 40 | 56 | 120 | 216 | 341 | 710 |
| 550 | | NA | 11 | 22 | 38 | 53 | 114 | 205 | 324 | 674 |
| 600 | | NA | 10 | 21 | 36 | 51 | 109 | 196 | 309 | 643 |
| 650 | | NA | NA | 20 | 34 | 49 | 104 | 188 | 296 | 616 |
| 700 | | NA | NA | 19 | 33 | 47 | 100 | 180 | 284 | 592 |
| 750 | | NA | NA | 18 | 32 | 45 | 96 | 174 | 274 | 570 |
| 800 | | NA | NA | 18 | 31 | 44 | 93 | 168 | 264 | 551 |
| 850 | | NA | NA | 17 | 30 | 42 | 90 | 162 | 256 | 533 |
| 900 | | NA | NA | 17 | 29 | 41 | 87 | 157 | 248 | 517 |
| 950 | | NA | NA | 16 | 28 | 40 | 85 | 153 | 241 | 502 |
| 1000 | | NA | NA | 16 | 27 | 39 | 83 | 149 | 234 | 488 |
| 1100 | | NA | NA | 15 | 26 | 37 | 78 | 141 | 223 | 464 |
| 1200 | | NA | NA | 14 | 25 | 35 | 75 | 135 | 212 | 442 |
| 1300 | | NA | NA | 14 | 24 | 34 | 72 | 129 | 203 | 423 |
| 1400 | | NA | NA | 13 | 23 | 32 | 69 | 124 | 195 | 407 |
| 1500 | | NA | NA | 13 | 22 | 31 | 66 | 119 | 188 | 392 |
| 1600 | | NA | NA | 12 | 21 | 30 | 64 | 115 | 182 | 378 |
| 1700 | | NA | NA | 12 | 20 | 29 | 62 | 112 | 176 | 366 |
| 1800 | | NA | NA | 11 | 20 | 28 | 60 | 108 | 170 | 355 |
| 1900 | | NA | NA | 11 | 19 | 27 | 58 | 105 | 166 | 345 |
| 2000 | | NA | NA | 11 | 19 | 27 | 57 | 102 | 161 | 335 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 inch water column = 0.249 kPa

Notes:

¹ Table capacities are based on Type K copper tubing inside diameter (shown), which has the smallest inside diameter of the copper tubing products.

² Table entries are rounded to 3 significant digits.

³ NA means a flow of less than 10 000 Btu/h (2.93 kW).

TABLE 1216.2(30)
SEMI-RIGID COPPER TUBING [NFPA 54: TABLE 6.3(g)]²

| | | | | | | | GAS: UNDILUTED PROPANE | | | |
|--|--------|---------------------------------------|-------|-------|-------|-------|-------------------------|--------|--------|--------|
| | | | | | | | INLET PRESSURE: 2.0 psi | | | |
| | | | | | | | PRESSURE DROP: 1.0 psi | | | |
| | | | | | | | SPECIFIC GRAVITY: 1.50 | | | |
| INTENDED USE: TUBE SIZING BETWEEN 2 PSIG SERVICE AND LINE PRESSURE REGULATOR | | | | | | | | | | |
| | | TUBE SIZE (inch) | | | | | | | | |
| NOMINAL: | K & L: | ¼ | ⅜ | ½ | ⅝ | ¾ | 1 | 1¼ | 1½ | 2 |
| | ACR: | ⅜ | ½ | ⅝ | ¾ | ⅞ | 1½ | 1¾ | — | — |
| OUTSIDE: | | 0.375 | 0.500 | 0.625 | 0.750 | 0.875 | 1.125 | 1.375 | 1.625 | 2.125 |
| INSIDE: ¹ | | 0.305 | 0.402 | 0.527 | 0.652 | 0.745 | 0.995 | 1.245 | 1.481 | 1.959 |
| LENGTH (feet) | | CAPACITY IN THOUSANDS OF BTU PER HOUR | | | | | | | | |
| 10 | | 413 | 852 | 1730 | 3030 | 4300 | 9170 | 16 500 | 26 000 | 54 200 |
| 20 | | 284 | 585 | 1190 | 2080 | 2950 | 6310 | 11 400 | 17 900 | 37 300 |
| 30 | | 228 | 470 | 956 | 1670 | 2370 | 5060 | 9120 | 14 400 | 29 900 |
| 40 | | 195 | 402 | 818 | 1430 | 2030 | 4330 | 7800 | 12 300 | 25 600 |
| 50 | | 173 | 356 | 725 | 1270 | 1800 | 3840 | 6920 | 10 900 | 22 700 |
| 60 | | 157 | 323 | 657 | 1150 | 1630 | 3480 | 6270 | 9880 | 20 600 |
| 70 | | 144 | 297 | 605 | 1060 | 1500 | 3200 | 5760 | 9090 | 18 900 |
| 80 | | 134 | 276 | 562 | 983 | 1390 | 2980 | 5360 | 8450 | 17 600 |
| 90 | | 126 | 259 | 528 | 922 | 1310 | 2790 | 5030 | 7930 | 16 500 |
| 100 | | 119 | 245 | 498 | 871 | 1240 | 2640 | 4750 | 7490 | 15 600 |
| 125 | | 105 | 217 | 442 | 772 | 1100 | 2340 | 4210 | 6640 | 13 800 |
| 150 | | 95 | 197 | 400 | 700 | 992 | 2120 | 3820 | 6020 | 12 500 |
| 175 | | 88 | 181 | 368 | 644 | 913 | 1950 | 3510 | 5540 | 11 500 |
| 200 | | 82 | 168 | 343 | 599 | 849 | 1810 | 3270 | 5150 | 10 700 |
| 250 | | 72 | 149 | 304 | 531 | 753 | 1610 | 2900 | 4560 | 9510 |
| 300 | | 66 | 135 | 275 | 481 | 682 | 1460 | 2620 | 4140 | 8610 |
| 350 | | 60 | 124 | 253 | 442 | 628 | 1340 | 2410 | 3800 | 7920 |
| 400 | | 56 | 116 | 235 | 411 | 584 | 1250 | 2250 | 3540 | 7370 |
| 450 | | 53 | 109 | 221 | 386 | 548 | 1170 | 2110 | 3320 | 6920 |
| 500 | | 50 | 103 | 209 | 365 | 517 | 1110 | 1990 | 3140 | 6530 |
| 550 | | 47 | 97 | 198 | 346 | 491 | 1050 | 1890 | 2980 | 6210 |
| 600 | | 45 | 93 | 189 | 330 | 469 | 1000 | 1800 | 2840 | 5920 |
| 650 | | 43 | 89 | 181 | 316 | 449 | 959 | 1730 | 2720 | 5670 |
| 700 | | 41 | 86 | 174 | 304 | 431 | 921 | 1660 | 2620 | 5450 |
| 750 | | 40 | 82 | 168 | 293 | 415 | 888 | 1600 | 2520 | 5250 |
| 800 | | 39 | 80 | 162 | 283 | 401 | 857 | 1540 | 2430 | 5070 |
| 850 | | 37 | 77 | 157 | 274 | 388 | 829 | 1490 | 2350 | 4900 |
| 900 | | 36 | 75 | 152 | 265 | 376 | 804 | 1450 | 2280 | 4750 |
| 950 | | 35 | 72 | 147 | 258 | 366 | 781 | 1410 | 2220 | 4620 |
| 1000 | | 34 | 71 | 143 | 251 | 356 | 760 | 1370 | 2160 | 4490 |
| 1100 | | 32 | 67 | 136 | 238 | 338 | 721 | 1300 | 2050 | 4270 |
| 1200 | | 31 | 64 | 130 | 227 | 322 | 688 | 1240 | 1950 | 4070 |
| 1300 | | 30 | 61 | 124 | 217 | 309 | 659 | 1190 | 1870 | 3900 |
| 1400 | | 28 | 59 | 120 | 209 | 296 | 633 | 1140 | 1800 | 3740 |
| 1500 | | 27 | 57 | 115 | 201 | 286 | 610 | 1100 | 1730 | 3610 |
| 1600 | | 26 | 55 | 111 | 194 | 276 | 589 | 1060 | 1670 | 3480 |
| 1700 | | 26 | 53 | 108 | 188 | 267 | 570 | 1030 | 1620 | 3370 |
| 1800 | | 25 | 51 | 104 | 182 | 259 | 553 | 1000 | 1570 | 3270 |
| 1900 | | 24 | 50 | 101 | 177 | 251 | 537 | 966 | 1520 | 3170 |
| 2000 | | 23 | 48 | 99 | 172 | 244 | 522 | 940 | 1480 | 3090 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 pound-force per square inch = 6.8947 kPa

Notes:

¹ Table capacities are based on Type K copper tubing inside diameter (shown), which has the smallest inside diameter of the copper tubing products.

² Table entries are rounded to 3 significant digits.

FUEL GAS PIPING

TABLE 1216.2(31)
CORRUGATED STAINLESS STEEL TUBING (CSST) [NFPA 54: TABLE 6.3(h)]^{1, 2}

| | | | | | | | | | | | | | | |
|---|---------------------------------------|----|-----|-----|-----|-----|-----|-----|------|------|------|------|------|------|
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| INTENDED USE: CSST SIZING BETWEEN SINGLE OR SECOND STAGE (LOW PRESSURE) REGULATOR AND APPLIANCE SHUTOFF VALVE | | | | | | | | | | | | | | |
| TUBE SIZE (EHD) ³ | | | | | | | | | | | | | | |
| FLOW DESIGNATION: | 13 | 15 | 18 | 19 | 23 | 25 | 30 | 31 | 37 | 39 | 46 | 48 | 60 | 62 |
| LENGTH (feet) | CAPACITY IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | |
| 5 | 72 | 99 | 181 | 211 | 355 | 426 | 744 | 863 | 1420 | 1638 | 2830 | 3270 | 5780 | 6550 |
| 10 | 50 | 69 | 129 | 150 | 254 | 303 | 521 | 605 | 971 | 1179 | 1990 | 2320 | 4110 | 4640 |
| 15 | 39 | 55 | 104 | 121 | 208 | 248 | 422 | 490 | 775 | 972 | 1620 | 1900 | 3370 | 3790 |
| 20 | 34 | 49 | 91 | 106 | 183 | 216 | 365 | 425 | 661 | 847 | 1400 | 1650 | 2930 | 3290 |
| 25 | 30 | 42 | 82 | 94 | 164 | 192 | 325 | 379 | 583 | 762 | 1250 | 1480 | 2630 | 2940 |
| 30 | 28 | 39 | 74 | 87 | 151 | 177 | 297 | 344 | 528 | 698 | 1140 | 1350 | 2400 | 2680 |
| 40 | 23 | 33 | 64 | 74 | 131 | 153 | 256 | 297 | 449 | 610 | 988 | 1170 | 2090 | 2330 |
| 50 | 20 | 30 | 58 | 66 | 118 | 137 | 227 | 265 | 397 | 548 | 884 | 1050 | 1870 | 2080 |
| 60 | 19 | 26 | 53 | 60 | 107 | 126 | 207 | 241 | 359 | 502 | 805 | 961 | 1710 | 1900 |
| 70 | 17 | 25 | 49 | 57 | 99 | 117 | 191 | 222 | 330 | 466 | 745 | 890 | 1590 | 1760 |
| 80 | 15 | 23 | 45 | 52 | 94 | 109 | 178 | 208 | 307 | 438 | 696 | 833 | 1490 | 1650 |
| 90 | 15 | 22 | 44 | 50 | 90 | 102 | 169 | 197 | 286 | 414 | 656 | 787 | 1400 | 1550 |
| 100 | 14 | 20 | 41 | 47 | 85 | 98 | 159 | 186 | 270 | 393 | 621 | 746 | 1330 | 1480 |
| 150 | 11 | 15 | 31 | 36 | 66 | 75 | 123 | 143 | 217 | 324 | 506 | 611 | 1090 | 1210 |
| 200 | 9 | 14 | 28 | 33 | 60 | 69 | 112 | 129 | 183 | 283 | 438 | 531 | 948 | 1050 |
| 250 | 8 | 12 | 25 | 30 | 53 | 61 | 99 | 117 | 163 | 254 | 390 | 476 | 850 | 934 |
| 300 | 8 | 11 | 23 | 26 | 50 | 57 | 90 | 107 | 147 | 234 | 357 | 434 | 777 | 854 |

For SI units: 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 inch water column = 0.249 kPa

Notes:

- ¹ Table includes losses for four 90 degree (1.57 rad) bends and two end fittings. Tubing runs with larger numbers of bends, fittings, or both shall be increased by an equivalent length of tubing to the following equation: $L = 1.3 n$, where L is additional length (ft) of tubing and n is the number of additional fittings, bends, or both.
- ² Table entries are rounded to 3 significant digits.
- ³ EHD = Equivalent Hydraulic Diameter, which is a measure of the relative hydraulic efficiency between different tubing sizes. The greater the value of EHD, the greater the gas capacity of the tubing.

TABLE 1216.2(32)
CORRUGATED STAINLESS STEEL TUBING (CSST) [NFPA 54: TABLE 6.3(I)]^{1, 2, 3, 4}

| | | | | | | | | | | | | | | | |
|---|---------------------------------------|-----|-----|------|------|------|------|------|-------------------|------|-------------------|--------|--------|--------|--|
| | | | | | | | | | GAS: | | UNDILUTED PROPANE | | | | |
| | | | | | | | | | INLET PRESSURE: | | 2.0 psi | | | | |
| | | | | | | | | | PRESSURE DROP: | | 1.0 psi | | | | |
| | | | | | | | | | SPECIFIC GRAVITY: | | 1.50 | | | | |
| INTENDED USE: CSST SIZING BETWEEN 2 PSI SERVICE AND LINE PRESSURE REGULATOR | | | | | | | | | | | | | | | |
| | TUBE SIZE (EHD) ⁵ | | | | | | | | | | | | | | |
| FLOW DESIGNATION: | 13 | 15 | 18 | 19 | 23 | 25 | 30 | 31 | 37 | 39 | 46 | 48 | 60 | 62 | |
| LENGTH (feet) | CAPACITY IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | | |
| 10 | 426 | 558 | 927 | 1110 | 1740 | 2170 | 4100 | 4720 | 7130 | 7958 | 15 200 | 16 800 | 29 400 | 34 200 | |
| 25 | 262 | 347 | 591 | 701 | 1120 | 1380 | 2560 | 2950 | 4560 | 5147 | 9550 | 10 700 | 18 800 | 21 700 | |
| 30 | 238 | 316 | 540 | 640 | 1030 | 1270 | 2330 | 2690 | 4180 | 4719 | 8710 | 9790 | 17 200 | 19 800 | |
| 40 | 203 | 271 | 469 | 554 | 896 | 1100 | 2010 | 2320 | 3630 | 4116 | 7530 | 8500 | 14 900 | 17 200 | |
| 50 | 181 | 243 | 420 | 496 | 806 | 986 | 1790 | 2070 | 3260 | 3702 | 6730 | 7610 | 13 400 | 15 400 | |
| 75 | 147 | 196 | 344 | 406 | 663 | 809 | 1460 | 1690 | 2680 | 3053 | 5480 | 6230 | 11 000 | 12 600 | |
| 80 | 140 | 189 | 333 | 393 | 643 | 768 | 1410 | 1630 | 2590 | 2961 | 5300 | 6040 | 10 600 | 12 200 | |
| 100 | 124 | 169 | 298 | 350 | 578 | 703 | 1260 | 1450 | 2330 | 2662 | 4740 | 5410 | 9530 | 10 900 | |
| 150 | 101 | 137 | 245 | 287 | 477 | 575 | 1020 | 1180 | 1910 | 2195 | 3860 | 4430 | 7810 | 8890 | |
| 200 | 86 | 118 | 213 | 248 | 415 | 501 | 880 | 1020 | 1660 | 1915 | 3340 | 3840 | 6780 | 7710 | |
| 250 | 77 | 105 | 191 | 222 | 373 | 448 | 785 | 910 | 1490 | 1722 | 2980 | 3440 | 6080 | 6900 | |
| 300 | 69 | 96 | 173 | 203 | 343 | 411 | 716 | 829 | 1360 | 1578 | 2720 | 3150 | 5560 | 6300 | |
| 400 | 60 | 82 | 151 | 175 | 298 | 355 | 616 | 716 | 1160 | 1376 | 2350 | 2730 | 4830 | 5460 | |
| 500 | 53 | 72 | 135 | 158 | 268 | 319 | 550 | 638 | 1030 | 1237 | 2100 | 2450 | 4330 | 4880 | |

For SI units: 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 pound-force per square inch = 6.8947 kPa

Notes:

- ¹ Table does not include effect of pressure drop across the line regulator. Where regulator loss exceeds 0.5 psi (3.4 kPa) [based on 13 inch water column (3.2 kPa) outlet pressure], DO NOT USE THIS TABLE. Consult with regulator manufacturer for pressure drops and capacity factors. Pressure drops across a regulator are capable of varying with flow rate.
- ² CAUTION: Capacities shown in table are capable of exceeding the maximum capacity for a selected regulator. Consult with regulator or tubing manufacturer for guidance.
- ³ Table includes losses for four 90 degree (1.57 rad) bends and two end fittings. Tubing runs with larger numbers of bends, fittings, or both shall be increased by an equivalent length of tubing to the following equation: $L = 1.3 n$, where L is additional length (ft) of tubing and n is the number of additional fittings, bends, or both.
- ⁴ Table entries are rounded to 3 significant digits.
- ⁵ EHD = Equivalent Hydraulic Diameter, which is a measure of the relative hydraulic efficiency between different tubing sizes. The greater the value of EHD, the greater the gas capacity of the tubing.

FUEL GAS PIPING

TABLE 1216.2(33)
CORRUGATED STAINLESS STEEL TUBING (CSST) [NFPA 54: TABLE 6.3(j)]^{1, 2, 3, 4}

| | | | | | | | | | GAS: UNDILUTED PROPANE | | | | | |
|-------------------|---------------------------------------|------|------|------|------|------|------|------|-------------------------|--------|--------|--------|--------|--------|
| | | | | | | | | | INLET PRESSURE: 5.0 psi | | | | | |
| | | | | | | | | | PRESSURE DROP: 3.5 psi | | | | | |
| | | | | | | | | | SPECIFIC GRAVITY: 1.50 | | | | | |
| | TUBE SIZE (EHD) ⁵ | | | | | | | | | | | | | |
| FLOW DESIGNATION: | 13 | 15 | 18 | 19 | 23 | 25 | 30 | 31 | 37 | 39 | 46 | 48 | 60 | 62 |
| LENGTH (feet) | CAPACITY IN THOUSANDS OF BTU PER HOUR | | | | | | | | | | | | | |
| 10 | 826 | 1070 | 1710 | 2060 | 3150 | 4000 | 7830 | 8950 | 13 100 | 14 441 | 28 600 | 31 200 | 54 400 | 63 800 |
| 25 | 509 | 664 | 1090 | 1310 | 2040 | 2550 | 4860 | 5600 | 8400 | 9339 | 18 000 | 19 900 | 34 700 | 40 400 |
| 30 | 461 | 603 | 999 | 1190 | 1870 | 2340 | 4430 | 5100 | 7680 | 8564 | 16 400 | 18 200 | 31 700 | 36 900 |
| 40 | 396 | 520 | 867 | 1030 | 1630 | 2030 | 3820 | 4400 | 6680 | 7469 | 14 200 | 15 800 | 27 600 | 32 000 |
| 50 | 352 | 463 | 777 | 926 | 1460 | 1820 | 3410 | 3930 | 5990 | 6717 | 12 700 | 14 100 | 24 700 | 28 600 |
| 75 | 284 | 376 | 637 | 757 | 1210 | 1490 | 2770 | 3190 | 4920 | 5539 | 10 300 | 11 600 | 20 300 | 23 400 |
| 80 | 275 | 363 | 618 | 731 | 1170 | 1450 | 2680 | 3090 | 4770 | 5372 | 9990 | 11 200 | 19 600 | 22 700 |
| 100 | 243 | 324 | 553 | 656 | 1050 | 1300 | 2390 | 2760 | 4280 | 4830 | 8930 | 10 000 | 17 600 | 20 300 |
| 150 | 196 | 262 | 453 | 535 | 866 | 1060 | 1940 | 2240 | 3510 | 3983 | 7270 | 8210 | 14 400 | 16 600 |
| 200 | 169 | 226 | 393 | 464 | 755 | 923 | 1680 | 1930 | 3050 | 3474 | 6290 | 7130 | 12 500 | 14 400 |
| 250 | 150 | 202 | 352 | 415 | 679 | 828 | 1490 | 1730 | 2740 | 3124 | 5620 | 6390 | 11 200 | 12 900 |
| 300 | 136 | 183 | 322 | 379 | 622 | 757 | 1360 | 1570 | 2510 | 2865 | 5120 | 5840 | 10 300 | 11 700 |
| 400 | 117 | 158 | 279 | 328 | 542 | 657 | 1170 | 1360 | 2180 | 2498 | 4430 | 5070 | 8920 | 10 200 |
| 500 | 104 | 140 | 251 | 294 | 488 | 589 | 1050 | 1210 | 1950 | 2247 | 3960 | 4540 | 8000 | 9110 |

For SI units: 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 pound-force per square inch = 6.8947 kPa

Notes:

- ¹ Table does not include effect of pressure drop across the line regulator. Where regulator loss exceeds 0.5 psi (3.4 kPa) [based on 13 inch water column (3.2 kPa) outlet pressure], DO NOT USE THIS TABLE. Consult with regulator manufacturer for pressure drops and capacity factors. Pressure drops across a regulator are capable of varying with flow rate.
- ² CAUTION: Capacities shown in table are capable of exceeding the maximum capacity for a selected regulator. Consult with regulator or tubing manufacturer for guidance.
- ³ Table includes losses for four 90 degree (1.57 rad) bends and two end fittings. Tubing runs with larger numbers of bends, fittings, or both shall be increased by an equivalent length of tubing to the following equation: $L = 1.3 n$, where L is additional length (ft) of tubing and n is the number of additional fittings, bends, or both.
- ⁴ Table entries are rounded to 3 significant digits.
- ⁵ EHD = Equivalent Hydraulic Diameter, which is a measure of the relative hydraulic efficiency between different tubing sizes. The greater the value of EHD, the greater the gas capacity of the tubing.

TABLE 1216.2(34)
POLYETHYLENE PLASTIC PIPE [NFPA 54: TABLE 6.3(k)]*

| | | | | | | | | |
|---|---------------------------------------|--------|--------|--------|-------------------|--------|-------------------|--------|
| | | | | | GAS: | | UNDILUTED PROPANE | |
| | | | | | INLET PRESSURE: | | 11.0 in. w.c. | |
| | | | | | PRESSURE DROP: | | 0.5 in. w.c. | |
| | | | | | SPECIFIC GRAVITY: | | 1.50 | |
| INTENDED USE: PE SIZING BETWEEN INTEGRAL SECOND-STAGE REGULATOR AT TANK OR SECOND-STAGE (LOW PRESSURE) REGULATOR AND BUILDING | | | | | | | | |
| | PIPE SIZE (Inch) | | | | | | | |
| NOMINAL OD: | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 3 | 4 |
| DESIGNATION: | SDR 9.3 | SDR 11 | SDR 11 | SDR 10 | SDR 11 | SDR 11 | SDR 11 | SDR 11 |
| ACTUAL ID: | 0.660 | 0.860 | 1.077 | 1.328 | 1.554 | 1.943 | 2.864 | 3.682 |
| LENGTH (feet) | CAPACITY IN THOUSANDS OF BTU PER HOUR | | | | | | | |
| 10 | 340 | 680 | 1230 | 2130 | 3210 | 5770 | 16 000 | 30 900 |
| 20 | 233 | 468 | 844 | 1460 | 2210 | 3970 | 11 000 | 21 200 |
| 30 | 187 | 375 | 677 | 1170 | 1770 | 3180 | 8810 | 17 000 |
| 40 | 160 | 321 | 580 | 1000 | 1520 | 2730 | 7540 | 14 600 |
| 50 | 142 | 285 | 514 | 890 | 1340 | 2420 | 6680 | 12 900 |
| 60 | 129 | 258 | 466 | 807 | 1220 | 2190 | 6050 | 11 700 |
| 70 | 119 | 237 | 428 | 742 | 1120 | 2010 | 5570 | 10 800 |
| 80 | 110 | 221 | 398 | 690 | 1040 | 1870 | 5180 | 10 000 |
| 90 | 103 | 207 | 374 | 648 | 978 | 1760 | 4860 | 9400 |
| 100 | 98 | 196 | 353 | 612 | 924 | 1660 | 4590 | 8900 |
| 125 | 87 | 173 | 313 | 542 | 819 | 1470 | 4070 | 7900 |
| 150 | 78 | 157 | 284 | 491 | 742 | 1330 | 3690 | 7130 |
| 175 | 72 | 145 | 261 | 452 | 683 | 1230 | 3390 | 6560 |
| 200 | 67 | 135 | 243 | 420 | 635 | 1140 | 3160 | 6100 |
| 250 | 60 | 119 | 215 | 373 | 563 | 1010 | 2800 | 5410 |
| 300 | 54 | 108 | 195 | 338 | 510 | 916 | 2530 | 4900 |
| 350 | 50 | 99 | 179 | 311 | 469 | 843 | 2330 | 4510 |
| 400 | 46 | 92 | 167 | 289 | 436 | 784 | 2170 | 4190 |
| 450 | 43 | 87 | 157 | 271 | 409 | 736 | 2040 | 3930 |
| 500 | 41 | 82 | 148 | 256 | 387 | 695 | 1920 | 3720 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 inch water column = 0.249 kPa

* Table entries are rounded to 3 significant digits.

FUEL GAS PIPING

TABLE 1216.2(35)
POLYETHYLENE PLASTIC PIPE [NFPA 54: TABLE 6.3(I)]*

| | | | | | GAS: | | UNDILUTED PROPANE | |
|--|---------------------------------------|--------|--------|--------|-------------------|--------|-------------------|---------|
| | | | | | INLET PRESSURE: | | 2.0 psi | |
| | | | | | PRESSURE DROP: | | 1.0 psi | |
| | | | | | SPECIFIC GRAVITY: | | 1.50 | |
| INTENDED USE: PE PIPE SIZING BETWEEN 2 PSI SERVICE REGULATOR AND LINE PRESSURE REGULATOR | | | | | | | | |
| | PIPE SIZE (inch) | | | | | | | |
| NOMINAL OD: | ½ | ¾ | 1 | 1¼ | 1½ | 2 | 3 | 4 |
| DESIGNATION: | SDR 9.3 | SDR 11 | SDR 11 | SDR 10 | SDR 11 | SDR 11 | SDR 11 | SDR 11 |
| ACTUAL ID: | 0.660 | 0.860 | 1.077 | 1.328 | 1.554 | 1.943 | 2.864 | 3.682 |
| LENGTH (feet) | CAPACITY IN THOUSANDS OF BTU PER HOUR | | | | | | | |
| 10 | 3130 | 6260 | 11 300 | 19 600 | 29 500 | 53 100 | 147 000 | 284 000 |
| 20 | 2150 | 4300 | 7760 | 13 400 | 20 300 | 36 500 | 101 000 | 195 000 |
| 30 | 1730 | 3450 | 6230 | 10 800 | 16 300 | 29 300 | 81 100 | 157 000 |
| 40 | 1480 | 2960 | 5330 | 9240 | 14 000 | 25 100 | 69 400 | 134 100 |
| 50 | 1310 | 2620 | 4730 | 8190 | 12 400 | 22 200 | 61 500 | 119 000 |
| 60 | 1190 | 2370 | 4280 | 7420 | 11 200 | 20 100 | 55 700 | 108 000 |
| 70 | 1090 | 2180 | 3940 | 6830 | 10 300 | 18 500 | 51 300 | 99 100 |
| 80 | 1010 | 2030 | 3670 | 6350 | 9590 | 17 200 | 47 700 | 92 200 |
| 90 | 952 | 1910 | 3440 | 5960 | 9000 | 16 200 | 44 700 | 86 500 |
| 100 | 899 | 1800 | 3250 | 5630 | 8500 | 15 300 | 42 300 | 81 700 |
| 125 | 797 | 1600 | 2880 | 4990 | 7530 | 13 500 | 37 500 | 72 400 |
| 150 | 722 | 1450 | 2610 | 4520 | 6830 | 12 300 | 33 900 | 65 600 |
| 175 | 664 | 1330 | 2400 | 4160 | 6280 | 11 300 | 31 200 | 60 300 |
| 200 | 618 | 1240 | 2230 | 3870 | 5840 | 10 500 | 29 000 | 56 100 |
| 250 | 548 | 1100 | 1980 | 3430 | 5180 | 9300 | 25 700 | 49 800 |
| 300 | 496 | 994 | 1790 | 3110 | 4690 | 8430 | 23 300 | 45 100 |
| 350 | 457 | 914 | 1650 | 2860 | 4320 | 7760 | 21 500 | 41 500 |
| 400 | 425 | 851 | 1530 | 2660 | 4020 | 7220 | 12 000 | 38 600 |
| 450 | 399 | 798 | 1440 | 2500 | 3770 | 6770 | 18 700 | 36 200 |
| 500 | 377 | 754 | 1360 | 2360 | 3560 | 6390 | 17 700 | 34 200 |
| 550 | 358 | 716 | 1290 | 2240 | 3380 | 6070 | 16 800 | 32 500 |
| 600 | 341 | 683 | 1230 | 2140 | 3220 | 5790 | 16 000 | 31 000 |
| 650 | 327 | 654 | 1180 | 2040 | 3090 | 5550 | 15 400 | 29 700 |
| 700 | 314 | 628 | 1130 | 1960 | 2970 | 5330 | 14 700 | 28 500 |
| 750 | 302 | 605 | 1090 | 1890 | 2860 | 5140 | 14 200 | 27 500 |
| 800 | 292 | 585 | 1050 | 1830 | 2760 | 4960 | 13 700 | 26 500 |
| 850 | 283 | 566 | 1020 | 1770 | 2670 | 4800 | 13 300 | 25 700 |
| 900 | 274 | 549 | 990 | 1710 | 2590 | 4650 | 12 900 | 24 900 |
| 950 | 266 | 533 | 961 | 1670 | 2520 | 4520 | 12 500 | 24 200 |
| 1000 | 259 | 518 | 935 | 1620 | 2450 | 4400 | 12 200 | 23 500 |
| 1100 | 246 | 492 | 888 | 1540 | 2320 | 4170 | 11 500 | 22 300 |
| 1200 | 234 | 470 | 847 | 1470 | 2220 | 3980 | 11 000 | 21 300 |
| 1300 | 225 | 450 | 811 | 1410 | 2120 | 3810 | 10 600 | 20 400 |
| 1400 | 216 | 432 | 779 | 1350 | 2040 | 3660 | 10 100 | 19 600 |
| 1500 | 208 | 416 | 751 | 1300 | 1960 | 3530 | 9760 | 18 900 |
| 1600 | 201 | 402 | 725 | 1260 | 1900 | 3410 | 9430 | 18 200 |
| 1700 | 194 | 389 | 702 | 1220 | 1840 | 3300 | 9130 | 17 600 |
| 1800 | 188 | 377 | 680 | 1180 | 1780 | 3200 | 8850 | 17 100 |
| 1900 | 183 | 366 | 661 | 1140 | 1730 | 3110 | 8590 | 16 600 |
| 2000 | 178 | 356 | 643 | 1110 | 1680 | 3020 | 8360 | 16 200 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 pound-force per square inch = 6.8947 kPa

* Table entries are rounded to 3 significant digits.

TABLE 1216.2(36)
POLYETHYLENE PLASTIC TUBING [NFPA 54: TABLE 6.3(m)]²

| | | |
|---|---|----------------------|
| | GAS: UNDILUTED PROPANE | |
| | INLET PRESSURE: | 11.0 in. w.c. |
| | PRESSURE DROP: | 0.5 in. w.c. |
| | SPECIFIC GRAVITY: | 1.50 |
| INTENDED USE: PE TUBE SIZING BETWEEN INTEGRAL SECOND-STAGE REGULATOR AT TANK OR SECOND-STAGE (LOW PRESSURE) REGULATOR AND BUILDING | | |
| | PLASTIC TUBING SIZE (CTS)¹ (inch) | |
| NOMINAL OD: | ½ | 1 |
| DESIGNATION: | SDR 7 | SDR 11 |
| ACTUAL ID: | 0.445 | 0.927 |
| LENGTH (feet) | CAPACITY IN THOUSANDS OF BTU PER HOUR | |
| 10 | 121 | 828 |
| 20 | 83 | 569 |
| 30 | 67 | 457 |
| 40 | 57 | 391 |
| 50 | 51 | 347 |
| 60 | 46 | 314 |
| 70 | 42 | 289 |
| 80 | 39 | 269 |
| 90 | 37 | 252 |
| 100 | 35 | 238 |
| 125 | 31 | 211 |
| 150 | 28 | 191 |
| 175 | 26 | 176 |
| 200 | 24 | 164 |
| 225 | 22 | 154 |
| 250 | 21 | 145 |
| 275 | 20 | 138 |
| 300 | 19 | 132 |
| 350 | 18 | 121 |
| 400 | 16 | 113 |
| 450 | 15 | 106 |
| 500 | 15 | 100 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW, 1 inch water column = 0.249 kPa

Notes:

¹ CTS = Copper tube size.

² Table entries are rounded to 3 significant digits.

CHAPTER 13

HEALTH CARE FACILITIES AND MEDICAL GAS AND MEDICAL VACUUM SYSTEMS

Part I – General Requirements.

1301.0 General.

» **1301.1 Applicability.** This chapter applies to the special fixtures and systems in health care facilities; the special plumbing requirements for such facilities; and the installation, testing, and verification of Categories 1, 2, and 3 medical gas and medical vacuum piping systems, except as otherwise indicated in this chapter, from the central supply system to the station outlets or inlets in hospitals, clinics, and other health care facilities. Other plumbing in such facilities shall comply with other applicable sections of this code. For Category 3 medical gas systems, only oxygen and nitrous oxide shall be used.

» **1301.2 Where Not Applicable.** This chapter does not apply to the following except as otherwise addressed in this chapter:

- (1) Cylinder and container management, storage, and reserve requirements
- (2) Bulk supply systems
- (3) Electrical connections and requirements
- (4) Motor requirements and controls
- (5) Systems having nonstandard operating pressures
- (6) Waste anesthetic gas disposal (WAGD) systems
- (7) Surface-mounted medical gas rail systems
- (8) Breathing air replenishment (BAR) systems
- (9) Portable compressed gas systems
- (10) Medical support gas systems
- (11) Gas-powered device supply systems
- (12) Scavenging systems

» **1301.3 Conflict of Requirements.** The requirements of this chapter shall not be interpreted to conflict with the requirements of NFPA 99. For requirements of portions of medical gas and medical vacuum systems not addressed in this chapter or medical gas and medical vacuum systems beyond the scope of this chapter refer to NFPA 99.

» **1301.4 Terms.** Where the term “medical gas” occurs, the provisions shall apply to piped systems for oxygen, nitrous oxide, medical air, carbon dioxide, helium, nitrogen, instrument air, and mixtures thereof. Where the name of a specific gas service occurs, the provision shall apply to that gas. [NFPA 99:5.1.1.2]

Where the term “medical vacuum” occurs, the provisions shall apply to systems for piped medical-surgical vacuum. Where the name of a specific vacuum service occurs, the provision shall apply to that vacuum service. [NFPA 99:5.1.1.3]

» **1301.5 Where Required.** Construction and equipment requirements shall be applied to new construction and new equipment, except as otherwise addressed in this chapter. [NFPA 99:1.3.2]

» **1301.6 Existing Systems.** The altered, renovated, or modernized portion of an existing system or individual component shall be required to meet the installation and equipment requirements stated in this chapter. Where the alteration, renovation, or modernization adversely impacts existing performance requirements of a system or component, additional upgrading shall be required. An existing system that does not comply with the provisions of this chapter shall be permitted to be continued in use where the Authority Having Jurisdiction has determined that such use does not constitute a distinct hazard to life. [NFPA 99:1.3.2.1 – 1.3.2.3]

1302.0 Design Requirements.

1302.1 Building System Categories. Building systems in health care facilities shall be designed in accordance with Category 1 through Category 3 requirements as detailed in this chapter. [NFPA 99:4.1]

1302.2 Patient Care Rooms. The governing body of the facility or its designee shall establish the following areas in accordance with the type of patient care anticipated:

- (1) Critical care rooms
- (2) General care rooms
- (3) Basic care rooms [NFPA 99:1.3.4.1]

1302.3 Anesthetizing Locations. It shall be the responsibility of the governing body of the health care organization to designate anesthetizing locations. [NFPA 99:1.3.4.2]

Exception: Deep sedation and general anesthesia shall not be administered where using a Category 3 medical gas system. [NFPA 99:5.3.1.5]

1302.4 Wet Procedure Locations. It shall be the responsibility of the governing body of the health care organization to designate wet procedure locations. [NFPA 99:1.3.4.3]

1303.0 Health Care Facilities.

1303.1 Drinking Fountain Control Valves. Drinking fountain control valves shall be flush-mounted or fully recessed where installed in corridors or other areas where patients are transported on a gurney, bed, or wheelchair.

» **1303.2 Psychiatric Patient Rooms.** Piping and drain traps in psychiatric patient rooms shall be concealed. Fixtures and fittings shall be resistant to vandalism.

» **1303.3 Locations for Ice Storage.** Ice makers or ice storage containers shall be located in nursing stations or similarly supervised areas to minimize potential contamination.

» **1303.4 Sterilizers and Bedpan Steamers.** Sterilizers and bedpan steamers shall be installed in accordance with the manufacturer’s installation instructions and comply with Section 1303.4.1 and Section 1303.4.2.

» **1303.4.1 Drainage Connections.** Sterilizers and bedpan steamers shall be connected to the sanitary drainage system through an air gap in accordance with Section 801.2. The size of indirect waste piping shall be not less than the size of the drain connection on the fixture. Each such indirect waste pipe shall not exceed 15 feet (4572 mm) in length and shall be separately piped to a receptor. Such receptors shall be located in the same room as the equipment served. Except for bedpan steamers, such indirect waste pipes shall not require traps. A trap having a seal of not less than 3 inches (76 mm) shall be provided in the indirect waste pipe for a bedpan steamer.

» **1303.4.2 Vapor Vents and Stacks.** Where a sterilizer or bedpan steamer has provision for a vapor vent and such a vent is required by the manufacturer, the vent shall be extended to the outdoors above the roof. Sterilizer and bedpan steamer vapor vents shall be installed in accordance with the manufacturer's installation instructions and shall not be connected to a drainage system vent.

» **1303.5 Aspirators.** Provisions for aspirators or other water-supplied suction devices shall be installed with the specific approval of the Authority Having Jurisdiction. Where aspirators are used for removing body fluids, they shall include a collection container to collect liquids and solid particles. Aspirators shall indirectly discharge to the sanitary drainage system through an air gap in accordance with Section 806.1. The potable water supply to an aspirator shall be protected by a vacuum breaker or equivalent backflow protection device in accordance with Section 603.5.9.

» **1303.6 Drains.** Drains shall be installed on dryers, after-coolers, separators, and receivers.

1303.7 Clinical Sinks. Clinical sinks shall be installed in accordance with the manufacturer's installation instructions and shall comply with Section 1303.7.1.

1303.7.1 Drainage Connection. Clinical sinks shall be directly connected to the sanitary drainage system, and shall be provided with approved flushing devices installed in accordance with Section 413.1.

1303.8 Water Supply for Hospitals. Hospitals shall be provided with not less than two approved potable water sources that are installed in such a manner as to prevent the interruption of water service.

» **1304.0 Medical Gas and Medical Vacuum Piping Systems.**

» **1304.1 General.** The installation of medical gas and medical vacuum piping systems shall comply with the requirements of this chapter.

» **1304.2 Manufacturer's Instructions.** The installation of individual components shall comply with the manufacturer's installation instructions. Such instructions shall include directions and information deemed by the manufacturer to be adequate for attaining proper operation, testing, and maintenance of the medical gas and medical vacuum

systems. Copies of the manufacturer's instructions shall be left with the system owner. [NFPA 99:5.1.10.11.8]

1304.3 Supply Source. Medical gas and medical vacuum systems shall be supplied from a central supply source of not less than two units, primary and secondary, consisting of one of the following:

- (1) Two cylinder banks with not less than two cylinders in each bank.
- (2) Not less than two air compressors.
- (3) Not less than two vacuum pumps.
- (4) A proportioning system for medical air USP.

Exception: A single Category 3 medical gas source system shall not supply more than two adjoining single treatment facilities. [NFPA 99:5.3.1.1.4]

1304.4 Certification of Systems. Certification of medical gas and medical vacuum systems shall comply with the requirements of Section 1320.0.

1304.5 Construction Documents. Before a medical gas or medical vacuum system is installed or altered in a hospital, medical facility, or clinic, duplicate construction documents shall be filed with the Authority Having Jurisdiction. Approval of the plans shall be obtained prior to issuance of a permit by the Authority Having Jurisdiction.

1304.5.1 Requirements. Construction documents shall show the following:

- (1) Plot plan of the site, drawn to scale, indicating the location of existing or new cylinder storage areas, property lines, driveways, and existing or proposed buildings.
- (2) Piping layout of the proposed piping system or alteration, including alarms, valves, origin of gases, user outlets, and user inlets. The demand and loading of a piping, existing or future, shall also be indicated.
- (3) Complete specification of materials.

1304.5.2 Extent of Work. Construction documents submitted to the Authority Having Jurisdiction shall clearly indicate the nature and extent of the work proposed and shall show in detail that such work will be in accordance with the provisions of this chapter.

1304.5.3 Record. A record of as-built plans and valve identification records shall remain on the site.

1305.0 System Performance.

1305.1 Required Operating Pressures. Medical gas and medical vacuum systems shall be capable of delivering service in the pressure ranges listed in Table 1305.1.

1305.2 Minimum Flow Rates. Medical gas and medical vacuum systems shall be capable of supplying the flow rates listed in Table 1305.2.

1305.3 Minimum Station Outlets and Inlets. Station outlets and inlets for medical gas and medical vacuum systems shall be provided as listed in Table 1305.3.

TABLE 1305.1
STANDARD DESIGNATION COLORS AND OPERATING PRESSURES FOR MEDICAL GAS AND MEDICAL VACUUM SYSTEMS
[NFPA 99:TABLE 5.1.11]

| GAS SERVICE | ABBREVIATED NAME | COLORS (BACKGROUND/TEXT) | STANDARD GAUGE PRESSURE |
|---|--|--|-------------------------|
| Medical air | Med Air | Yellow/black | 50–55 psi |
| Carbon dioxide | CO ₂ | Gray/black or gray/white | 50–55 psi |
| Helium | He | Brown/white | 50–55 psi |
| Nitrogen | N ₂ | Black/white | 160–185 psi |
| Nitrous oxide | N ₂ O | Blue/white | 50–55 psi |
| Oxygen | O ₂ | Green/white or white/green | 50–55 psi |
| Oxygen/carbon dioxide mixtures | O ₂ /CO ₂ n% (n = % of CO ₂) | Green/white | 50–55 psi |
| Medical–surgical vacuum | Med Vac | White/black | 15 inch to 30 inch HgV |
| Waste anesthetic gas disposal | WAGD | Violet/white | Varies with system type |
| Other mixtures | Gas A%/ Gas B% | Colors as above; major gas for background/minor gas for text | None |
| Nonmedical air (Category 3 gas-powered device) | — | Yellow-and-white diagonal stripe/black | None |
| Nonmedical and Category 3 vacuum | — | White-and-black diagonal stripe/black boxed | None |
| Laboratory air | — | Yellow-and-white checker-board/black | None |
| Laboratory vacuum | — | White-and-black checkerboard/black boxed | None |
| Instrument air | — | Red/white | 160–185 psi |

For SI units: 1 pound-force per square inch = 6.8947 kPa, 1 inch of mercury vacuum (HgV) = 3.386 kPa

TABLE 1305.2
MINIMUM FLOW RATES (cubic feet per minute)

| MEDICAL SYSTEM | FLOW RATE |
|------------------------|---------------------------------|
| Oxygen | .71 CFM per outlet ¹ |
| Nitrous Oxide | .71 CFM per outlet ¹ |
| Medical Compressed Air | .71 CFM per outlet ¹ |
| Nitrogen | 15 CFM free air per outlet |
| Vacuum | 1 SCFM per inlet ² |
| Carbon Dioxide | .71 CFM per outlet ¹ |
| Helium | .71 CFM per outlet |

For SI units: 1 cubic foot per minute (CFM) = 0.47 L/s

Notes:

¹ A room designed for a permanently located respiratory ventilator or anesthesia machine shall have an outlet capable of a flow rate of 6.36 CFM (3.0 L/s) at the station outlet.

² For testing and certification purposes, individual station inlets shall be capable of a flow rate of 3 SCFM, while maintaining a system pressure of not less than 12 inches of mercury (41 kPa) at the nearest adjacent vacuum inlet.

1306.0 Qualifications of Installers.

» **1306.1 General.** The installation of medical gas and medical vacuum systems shall be made by qualified, competent technicians who are experienced in performing such installations. Installers of medical gas and medical vacuum piped distribution systems, appurtenant piping supporting pump and compressor source systems, and appurtenant piping supporting source gas manifold systems not including permanently installed bulk source systems,

shall be certified in accordance with ASSE 6010. [NFPA 99:5.1.10.11.10.1, 5.1.10.11.10.2]

1306.2 Brazing. Brazing shall be performed by individuals who are qualified in accordance with Section 1307.0. [NFPA 99:5.1.10.11.10.4]

1306.2.1 Documentation. Prior to installation work, the installer of medical gas and medical vacuum piping shall provide and maintain documentation on the job site for the qualification of brazing procedures and

TABLE 1305.3
MINIMUM OUTLETS AND INLETS PER STATION

| LOCATION | OXYGEN | MEDICAL VACUUM | MEDICAL AIR | NITROUS OXIDE | NITROGEN | HELIUM | CARBON DIOXIDE |
|--|-----------------|------------------------------|-----------------|---------------|----------|--------|----------------|
| Patient rooms for medical/surgical, obstetrics, and pediatrics | 1/bed | 1/bed | 1/bed | — | — | — | — |
| Examination/treatment for nursing units | 1/bed | 1/bed | — | — | — | — | — |
| Intensive care (all) | 3/bed | 3/bed | 2/bed | — | — | — | — |
| Nursery ¹ | 2/bed | 2/bed | 1/bed | — | — | — | — |
| General operating rooms | 2/room | 3/room ⁴ | 2/room | 1/room | 1/room | — | — |
| Cystoscopic and invasive special procedures | 2/room | 3/room ⁴ | 2/room | — | — | — | — |
| Recovery delivery and labor/delivery/recovery rooms ² | 2/bed 2/room | 2/bed 3/room ⁴ | 1/bed 1/room | — | — | — | — |
| Labor rooms | 1/bed | 1/bed | 1/bed | — | — | — | — |
| First aid and emergency treatment ³ | 1/bed | 1/bed ⁴ | 1/bed | — | — | — | — |
| Autopsy | — | 1/station | 1/station | — | — | — | — |
| Anesthesia workroom | 1/station | — | 1/station | — | — | — | — |

Notes:¹ Includes pediatric nursery.² Includes obstetric recovery.³ Emergency trauma rooms used for surgical procedures shall be classified as general operating rooms.⁴ Vacuum inlets required are in addition to inlets used as part of a scavenging system for removal of anesthetizing gases.

individual brazers that are required in accordance with Section 1307.0. [NFPA 99:5.1.10.11.10.5]

» **1306.3 Health Care Organization Personnel.** Health care organization personnel shall be permitted to install piping systems where the requirements of Section 1306.1 through Section 1306.2.1 are met during the installation. [NFPA 99:5.1.10.11.10.6]

» **1307.0 Brazing Procedures.**

1307.1 General. Brazing procedures and brazer performance for the installation of medical gas and medical vacuum piping shall be qualified in accordance with Section IX of the ASME Boiler and Pressure Vessel Code or AWS B2.2, both as modified in Section 1307.2 through Section 1307.7. [NFPA 99:5.1.10.11.11.1, 5.3.6.3.1]

» **1307.2 Examination.** Brazers shall be qualified by visual examination of the test coupon followed by sectioning. [NFPA 99:5.1.10.11.11.2, 5.3.6.3.2]

» **1307.3 Brazing Procedure Specification.** The brazing procedure specification shall address cleaning, joint clearance, overlap, internal purge gas, purge gas flow rate, and filler metal. [NFPA 99:5.1.10.11.11.3, 5.3.6.3.3]

» **1307.4 Documentation.** The brazing procedure qualification record and the record of brazer performance qualification shall document the filler metal used, cleaning, joint clearance, overlap, internal purge gas, and flow rate during brazing of the coupon, and absence of internal oxidation in the completed coupon. [NFPA 99:5.1.10.11.11.4, 5.3.6.3.4]

1307.5 Procedures. Brazing procedures qualified by a technically competent group or agency shall be permitted under the following conditions: «

- (1) The brazing procedure specification and the procedure qualification record meet the requirements of this code.
- (2) The employer obtains a copy of both the brazing procedure specification and the supporting qualification record from the group or agency and signs and dates these records, thereby accepting responsibility for the qualifications that were performed by the group or agency.
- (3) The employer qualifies not less than one brazer following each brazing procedure specification used. [NFPA 99:5.1.10.11.11.5, 5.3.6.3.5]

1307.6 Conditions of Acceptance. An employer shall be permitted to accept brazer qualification records of a previous employer under the following conditions: «

- (1) The brazer has been qualified following the same or an equivalent procedure that the new employer uses.
- (2) The new employer obtains a copy of the record of brazer performance qualification tests from the previous employer and signs and dates this record, thereby accepting responsibility for the qualifications performed by the previous employer. [NFPA 99:5.1.10.11.11.6, 5.3.6.3.6]

1307.7 Qualifications. Performance qualifications of brazers shall remain in effect indefinitely, unless the brazer does not braze with the qualified procedure for a period exceeding 6 months or there is a specific reason to question the ability of the brazer. [NFPA 99:5.1.10.11.11.7, 5.3.6.3.7] «

Part II – Medical Gas and Medical Vacuum System Piping.

»» 1308.0 Pipe Materials.

»» **1308.1 General.** The provisions of this section shall apply to field-installed piping for the distribution of medical gases and medical vacuum systems.

»» **1308.2 Cleaning.** Tubes, valves, fittings, station outlets, and other piping components in medical gas systems shall have been cleaned for oxygen service by the manufacturer prior to installation in accordance with CGA G-4.1 except that fittings shall be permitted to be cleaned by a supplier or agency other than the manufacturer. [NFPA 99:5.1.10.1.1, 5.3.6.2.2]

Where tube ends, fittings, or other components become contaminated before installation they shall be recleaned in accordance with Section 1311.0.

»» **1308.3 Delivery.** Each length of tube shall be delivered plugged or capped by the manufacturer and kept sealed until prepared for installation. Fittings, valves, and other components shall be delivered sealed, labeled, and kept sealed until prepared for installation. [NFPA 99:5.1.10.1.2, 5.1.10.1.3]

»» **1308.4 Tubes for Medical Gas Systems.** Tubes shall be hard-drawn seamless copper ASTM B819 medical gas tube, Type L, except Type K shall be used where operating pressures exceed a gauge pressure of 185 psi (1276 kPa) and the pipe sizes exceed DN80 [(NPS 3) (3¹/₈ inches O.D.)]. [NFPA 99:5.1.10.1.4]

ASTM B819 medical gas tube shall be identified by the manufacturer's markings "OXY," "MED," "OXY/MED," "OXY/ACR," or "ACR/MED" in blue (Type L) or green (Type K). [NFPA 99:5.1.10.1.5]

»» **1308.5 Tubes for Medical Vacuum Systems.** Piping for medical vacuum systems shall be constructed of one of the following:

- (1) Hard-drawn seamless copper tube in accordance with one of the following:
 - (a) ASTM B88 copper tube (Type K, L, or M)
 - (b) ASTM B280 copper ACR tube
 - (c) ASTM B819 copper medical gas tubing (Type K or L)
- (2) Stainless steel tube [NFPA 99:5.1.10.2.1]

Exceptions: Piping for Category 3 medical vacuum systems shall be permitted to be as follows:

- (1) Schedule 40 or Schedule 80 PVC plastic piping manufactured in accordance with ASTM D1785. [NFPA 99:5.3.8.2.3(1)]
- (2) Schedule 40 or Schedule 80 CPVC IPS (iron pipe size) plastic piping manufactured in accordance with ASTM F441. [NFPA 99:5.3.8.2.4(1)]
- (3) CPVC CTS (copper tube size) plastic pipe manufactured in accordance with ASTM D2846, 1/2 of an inch (15 mm) through 2 inches (50 mm) in diameter. [NFPA 99:5.3.8.2.4(3)]

1309.0 Joints and Connections.

1309.1 General. This section sets forth the requirements for pipe joint installations for a medical gas or medical vacuum system.

1309.2 Changes in Direction. Medical gas and medical vacuum systems shall have turns, offsets, and other changes in direction made using the following fittings or joining methods:

- (1) Brazed in accordance with Section 1309.3.
- (2) Memory metal fittings in accordance with Section 1309.4.1.
- (3) Axially swaged, elastic preload fittings in accordance with Section 1309.4.2.
- (4) Threaded in accordance with Section 1309.4.3.
- (5) Welded in accordance with Section 1309.5. [NFPA 99:5.1.10.3.1]

Exceptions: Fittings or joints for Category 3 medical vacuum systems shall be permitted in accordance with the following:

- (1) Flared fittings that comply with ASME B16.26. [NFPA 99:5.3.7.2.2(4)]
- (2) Compression fittings that do not exceed 3/4 of an inch (20 mm) in size. [NFPA 99:5.3.7.2.2(5)]
- (3) Soldered joints shall be made in accordance with ASTM B828 using a lead-free solder filler metal containing not more than 0.2 percent lead by volume in accordance with ASTM B32. [NFPA 99:5.3.7.2.3.3]
- (4) Schedule 40 or Schedule 80 PVC plastic pipe fittings manufactured in accordance with ASTM D2466 or ASTM D2467. Joints shall be solvent-cemented in accordance with ASTM D2672. [NFPA 99:5.3.8.2.3(2), 5.3.8.2.3(3)]
- (5) Schedule 40 or Schedule 80 CPVC IPS plastic pipe fittings manufactured in accordance with ASTM F438 or ASTM F439, or CPVC CTS plastic pipe fittings manufactured in accordance with ASTM D2846, 1/2 of an inch (15 mm) through 2 inches (50 mm) in diameter. Solvent cement used for joints shall be in accordance with ASTM F493. [NFPA 99:5.3.8.2.4(2) – 5.3.8.2.4(4)]

1309.2.1 Medical Vacuum Systems. Medical vacuum systems shall be permitted to have branch connections made using mechanically formed, drilled, and extruded tee-branch connections that are formed in accordance with the tool manufacturer's instructions. Such branch connections shall be joined by brazing in accordance with Section 1309.3. [NFPA 99:5.1.10.3.2]

1309.3 Brazed Joints and Fittings. Brazed joints shall be made using a brazing alloy that exhibits a melting temperature in excess of 1000°F (538°C) to retain the integrity of the piping system in the event of fire exposure. [NFPA 99:5.1.10.4.1.3, 5.3.6.4.2]

Fittings for tubes, turns, offsets, and other changes in direction shall be made with wrought-copper capillary fittings in accordance with ASME B16.22 or brazed fittings in accordance with ASME B16.50. [NFPA 99:5.1.10.4.1.1, 5.3.6.2.3]

Cast-copper alloy fittings shall not be permitted. [NFPA 99:5.1.10.4.1.2, 5.3.6.2.4]

1309.3.1 Tube Joints. Brazed tube joints shall be the socket type. [NFPA 99:5.1.10.4.1.4, 5.3.6.4.1]

1309.3.2 Filler Metals. Filler metals shall bond with and be metallurgically compatible with the base metals being joined. [NFPA 99:5.1.10.4.1.5, 5.3.6.4.3]

Filler metals shall comply with AWS A5.8. [NFPA 99:5.1.10.4.1.6, 5.3.6.4.4]

1309.3.3 Copper-to-Copper Joints. Copper-to-copper joints shall be brazed using a copper-phosphorus or copper-phosphorus-silver brazing filler metal (BCuP series) without flux. [NFPA 99:5.1.10.4.1.7, 5.3.6.4.5]

1309.3.4 Accessible. Joints to be brazed in place shall be accessible for necessary preparation, assembly, heating, filler application, cooling, cleaning, and inspection. [NFPA 99:5.1.10.4.1.9, 5.3.6.4.6]

1309.3.5 Tube Ends. Tube ends shall be cut square using a sharp tubing cutter to avoid deforming the tube. [NFPA 99:5.1.10.4.2.1, 5.3.6.5.1]

1309.3.5.1 Cutting Wheels. The cutting wheels on tubing cutters shall be free from grease, oil, or other lubricant not approved for oxygen service. [NFPA 99:5.1.10.4.2.2, 5.3.6.5.2]

1309.3.5.2 Cut Ends. The cut ends of the tube shall be rolled smooth or deburred with a sharp, clean deburring tool, taking care to prevent chips from entering the tube. [NFPA 99:5.1.10.4.2.3, 5.3.6.5.3]

1309.3.6 Cleaning Procedures. The interior surfaces of tubes, fittings, and other components that are cleaned for oxygen service shall be stored and handled to avoid contamination prior to assembly and brazing. [NFPA 99:5.1.10.4.3.1, 5.3.6.6.1]

1309.3.6.1 Exterior Surfaces. The exterior surfaces of tube ends shall be cleaned prior to brazing to remove surface oxides. [NFPA 99:5.1.10.4.3.2, 5.3.6.6.2]

Where cleaning the exterior surfaces of tube ends, no matter shall be permitted to enter the tube. [NFPA 99:5.1.10.4.3.3]

1309.3.6.2 Interior Surfaces. Where the interior surfaces of fitting sockets become contaminated prior to brazing, they shall be recleaned for oxygen in accordance with Section 1311.0 and shall be cleaned for brazing with a clean, oil-free wire brush. [NFPA 99:5.1.10.4.3.4]

1309.3.6.3 Abrasive Pads. Clean, nonshedding, abrasive pads shall be used to clean the exterior surfaces of the tube ends. [NFPA 99:5.1.10.4.3.5]

Exception: For Category 3 systems, nonabrasive pads shall be used to clean the exterior surfaces of tube ends. [NFPA 99:5.3.6.6.3]

1309.3.6.4 Prohibited. The use of steel wool or sand cloth shall be prohibited. [NFPA 99:5.1.10.4.3.6]

For Category 3 systems, the use of wire brushes shall also be prohibited.

The cleaning process shall not result in grooving of the surfaces to be joined. [NFPA 99:5.1.10.4.3.7, 5.3.6.6.5]

1309.3.6.5 Wiped. After being abraded, the surfaces shall be wiped using a clean, lint-free white cloth. [NFPA 99:5.1.10.4.3.8, 5.3.6.6.6]

1309.3.6.6 Examination. Tubes, fittings, valves, and other components shall be visually examined internally before being joined to verify that they have not become contaminated for oxygen service and that they are free of obstructions or debris. [NFPA 99:5.1.10.4.3.9, 5.3.6.6.7]

1309.3.6.7 On-Site Recleaning. The interior surfaces of tube ends, fittings, and other components that were cleaned for oxygen service by the manufacturer, but become contaminated prior to being installed, shall be permitted to be recleaned in accordance with Section 1311.0.

1309.3.6.8 Contamination. Material that has become contaminated shall be cleaned in accordance with Section 1311.0.

1309.3.6.9 Timeframe for Brazing. Joints shall be brazed within 8 hours after the surfaces are cleaned for brazing. [NFPA 99:5.1.10.4.3.13, 5.3.6.6.9]

1309.3.7 Brazing Dissimilar Metals. Flux shall only be used where brazing dissimilar metals, such as copper and bronze or brass, using a silver (BAg series) brazing filler metal. [NFPA 99:5.1.10.4.4.1, 5.3.6.7.1]

Cast metals shall not be field-brazed. [NFPA 99:5.3.6.7.2]

1309.3.7.1 Surface Cleaning. Surfaces shall be cleaned for brazing in accordance with Section 1309.3.6. [NFPA 99:5.1.10.4.4.2, 5.3.6.7.3]

1309.3.7.2 Flux. Flux shall be applied sparingly to minimize contamination of the inside of the tube with flux. [NFPA 99:5.1.10.4.4.3, 5.3.6.7.4]

The flux shall be applied and worked over the cleaned surfaces to be brazed using a stiff bristle brush to ensure complete coverage and wetting of the surfaces with flux. [NFPA 99:5.1.10.4.4.4, 5.3.6.7.5]

1309.3.7.3 Short Sections of Copper. Short sections of copper tube shall be brazed onto the non-copper component, and the interior of the subassembly shall be cleaned of flux prior to installation in the piping system. [NFPA 99:5.1.10.4.4.5, 5.3.6.7.6]

1309.3.7.4 Flux-Coated Brazing Rods. On joints DN20 (NPS ¾) (¼ of an inch O.D.) size and smaller, flux-coated brazing rods shall be permitted to be used in lieu of applying flux to the surfaces being joined. [NFPA 99:5.1.10.4.4.6, 5.3.6.7.7]

» **1309.3.8 Nitrogen Purge.** Where being brazed, joints shall be continuously purged with oil-free, dry nitrogen NF to prevent the formation of copper oxide on the inside surfaces of the joint. [NFPA 99:5.1.10.4.5.1, 5.3.6.8.1]

1309.3.8.1 Source. The source of the purge gas shall be monitored, and the installer shall be audibly alerted where the source content is low. [NFPA 99:5.1.10.4.5.2, 5.3.6.8.2]

1309.3.8.2 Flow Rate Control. The purge gas flow rate shall be controlled by the use of a pressure regulator and a flowmeter, or a combination thereof. [NFPA 99:5.1.10.4.5.3, 5.3.6.8.4]

Pressure regulators alone shall not be used to control purge gas flow rates. [NFPA 99:5.1.10.4.5.4, 5.3.6.8.5]

For Category 3 systems, the nitrogen purge gas flow rate shall not be high enough to produce a positive pressure in the piping system. [NFPA 99:5.3.6.8.3]

1309.3.8.3 Oxygen Analyzer. In order to assure that ambient air has been removed from the pipeline prior to brazing, an oxygen analyzer shall be used to verify the effectiveness of the purge. The oxygen analyzer shall read below 1 percent oxygen concentration before brazing begins. [NFPA 99:5.1.10.4.5.5]

1309.3.8.4 During Installation. During and after installation, openings in the piping system shall be kept sealed to maintain a nitrogen atmosphere within the piping to prevent debris or other contaminants from entering the system. [NFPA 99:5.1.10.4.5.6, 5.3.6.8.6]

1309.3.8.5 Discharge Opening. While a joint is being brazed, a discharge opening shall be provided on the opposite side of the joint from where the purge gas is being introduced. [NFPA 99:5.1.10.4.5.7, 5.3.6.8.7]

1309.3.8.6 Temperature of Joint. The flow of purge gas shall be maintained until the joint is cool to the touch. [NFPA 99:5.1.10.4.5.8, 5.3.6.8.8]

1309.3.8.7 Opening to be Sealed. After the joint has cooled, the purge discharge opening shall be sealed to prevent contamination of the inside of the tube and maintain the nitrogen atmosphere within the piping system. [NFPA 99:5.1.10.4.5.9, 5.3.6.8.9]

1309.3.8.8 Final Brazed Connection. The final brazed connection of new piping to an existing pipeline containing the system gas shall be permitted to be made without the use of a nitrogen purge. [NFPA 99:5.1.10.4.5.10]

1309.3.8.9 Final Tie-In Test. After a final brazed connection in a positive-pressure medical gas pipeline is made without a nitrogen purge, an outlet in the immediate downstream zone of the

affected portions of both the new and existing piping shall be tested in accordance with the following [NFPA 99:5.1.10.4.5.11]:

- (1) Each joint in the final connection between the new work and the existing system shall be leak-tested with the gas of system designation at the normal operating pressure by means of a leak detectant that is safe for use with oxygen and does not contain ammonia. [NFPA 99:5.1.12.3.9.2]
- (2) Vacuum joints shall be tested using an ultrasonic leak detector or other means that will allow detection of leaks in an active medical vacuum system. [NFPA 99:5.1.12.3.9.3]
- (3) For pressure gases, immediately after the final brazed connection is made and leak-tested, an outlet in the new piping and an outlet in the existing piping that are immediately downstream from the point or area of intrusion shall be purged in accordance with Section 1309.3.8.9(4). [NFPA 99:5.1.12.3.9.4]
- (4) Where traces of particulate matter have been deposited in the pipelines as a result of construction, a heavy, intermittent purging of the pipeline shall be done. [NFPA 99:5.1.12.3.6]
- (5) Before the new work is used for patient care, positive-pressure gases shall be tested for operational pressure and gas concentration in accordance with Section 1319.10 and Section 1319.11. [NFPA 99:5.1.12.3.9.5]
- (6) Permanent records of these tests shall be maintained. [NFPA 99:5.1.12.3.9.6]

1309.3.8.10 Autogenous Orbital Welding Process. Where using the autogenous orbital welding process, joints shall be continuously purged inside and outside with inert gas(es) in accordance with the qualified welding procedure. [NFPA 99:5.1.10.4.5.12]

1309.3.9 Assembling and Heating Brazed Joints. Tube ends shall be inserted fully into the socket or to a mechanically limited depth that is not less than the minimum cup depth (overlap) in accordance with ASME B16.50. [NFPA 99:5.1.10.4.6.1, 5.3.6.9.1]

1309.3.9.1 Heating of Joint. Where flux is permitted, the joint shall be heated slowly until the flux has liquefied. [NFPA 99:5.1.10.4.6.2, 5.3.6.9.2]

After flux is liquefied, or where flux is not permitted to be used, the joint shall be heated quickly to the brazing temperature, taking care not to overheat the joint. [NFPA 99:5.1.10.4.6.3, 5.3.6.9.3]

1309.3.10 Inspection of Brazed Joints. After brazing, the outside of joints shall be cleaned by washing with water and a wire brush to remove residue

and permit clear visual inspection of the joint. [NFPA 99:5.1.10.4.7.1, 5.3.6.10.1]

1309.3.10.1 Where Flux is Used. Where flux has been used, the wash water shall be hot. [NFPA 99:5.1.10.4.7.2, 5.3.6.10.2]

1309.3.10.2 Visually Inspected. Each brazed joint shall be visually inspected after cleaning the outside surfaces. [NFPA 99:5.1.10.4.7.3, 5.3.6.10.3]

1309.3.10.3 Prohibited Brazed Joints. Joints exhibiting the following conditions shall not be permitted:

- (1) Flux or flux residue (where flux or flux-coated BAg series rods are used with dissimilar metals).
- (2) Base metal melting or erosion.
- (3) Unmelted filler metal.
- (4) Failure of the filler metal to be clearly visible around the joint at the interface between the socket and the tube.
- (5) Cracks in the tube or component.
- (6) Cracks in the braze filler metal.
- (7) Failure of the joint to hold the test pressure under the installer-performed initial pressure test in accordance with Section 1319.5 and the standing pressure test in accordance with Section 1319.7 or Section 1319.8. [NFPA 99:5.1.10.4.7.4, 5.3.6.10.4]

1309.3.10.4 Defective Brazed Joints. Brazed joints that are identified as defective under the conditions of Section 1309.3.10.3(2) or Section 1309.3.10.3(5) shall be replaced. [NFPA 99:5.1.10.4.7.5, 5.3.6.10.5]

Brazed joints that are identified as defective under the conditions of Section 1309.3.10.3(1), Section 1309.3.10.3(3), Section 1309.3.10.3(4), Section 1309.3.10.3(6), or Section 1309.3.10.3(7) shall be permitted to be repaired, except that no joint shall be reheated more than once before being replaced. [NFPA 99:5.1.10.4.7.6, 5.3.6.10.6]

» **1309.4 Special Fittings.** The special fittings in Section 1309.4.1 through Section 1309.4.5 shall be permitted to be used in lieu of brazed joints.

» **1309.4.1 Memory Metal Fittings.** Memory metal fittings having a temperature rating not less than 1000°F (538°C) and a pressure rating not less than 300 psi (2068 kPa) shall be permitted to be used to join copper or stainless steel tube. Such fittings shall be installed by qualified technicians in accordance with the manufacturer's installation instructions. [NFPA 99:5.1.10.6]

1309.4.2 Axially Swaged Fittings. Axially swaged, elastic strain preload fittings providing metal-to-metal seals, having a temperature rating not less than

1000°F (538°C) and a pressure rating not less than 300 psi (2068 kPa), and where complete, are permanent and nonseparable shall be permitted to be used to join copper or stainless steel tube. Such fittings shall be installed by qualified technicians in accordance with the manufacturer's installation instructions. [NFPA 99:5.1.10.7]

1309.4.3 Threaded Fittings. Threaded fittings shall comply with the following requirements: «

- (1) Be limited to connections for pressure and vacuum indicators, alarm devices, check valves, and source equipment on the source side of the source valve.
- (2) Be tapered pipe threads in accordance with ASME B1.20.1.
- (3) Be made up with polytetrafluoroethylene tape or other thread sealant recommended for oxygen service, with the sealant applied to the male threads only and care taken to ensure sealant does not enter the pipe. [NFPA 99:5.1.10.8, 5.3.6.2.5]

1309.4.4 Dielectric Fittings. Dielectric fittings shall comply with the following requirements, and shall only be permitted where required by the manufacturer of special medical equipment to electrically isolate the equipment from the system distribution piping:

- (1) Be of brass or copper construction with an approved dielectric.
- (2) Be permitted to be a union.
- (3) Be clean for oxygen where used for medical gases. [NFPA 99:5.1.10.9.2]

1309.4.5 Other Types of Fittings. Approved metallic gas tube fittings that provide a permanent joint having the mechanical, thermal, and sealing integrity of a brazed joint shall be permitted to be used. [NFPA 99:5.1.10.9.1]

1309.5 Welded Joints. Welded joints for medical gas and medical-surgical vacuum systems shall be permitted to be made using a gas tungsten arc welding (GTAW) autogenous orbital procedure. [NFPA 99:5.1.10.5.1.1]

1309.5.1 Qualifications. Welders shall be qualified in accordance with Section IX of the ASME Boiler and Pressure Vessel Code. [NFPA 99:5.1.10.5.2.2]

1309.5.2 Welder Qualification Procedure. The GTAW autogenous orbital procedure and the welder qualification procedure shall be qualified in accordance with Section IX of the ASME Boiler and Pressure Vessel Code. Welder qualification procedures shall include a bend test and a tensile test in accordance with Section IX of the ASME Boiler and Pressure Vessel Code on each tube size diameter. [NFPA 99:5.1.10.5.1.2, 5.1.10.5.1.3]

1309.5.2.1 Purging of Joints. GTAW autogenous orbital welded joints shall be purged during welding with a commercially available mixture of 75 percent helium (+/- 5 percent) and 25 percent argon (+/- 5 percent). [NFPA 99:5.1.10.5.1.5]

1309.5.2.2 Test Coupons. Test coupons shall be welded and inspected, as a minimum, at the start of work and every 4 hours thereafter, or where the machine is idle for more than 30 minutes, and at the end of the work period. Test coupons shall be inspected on the I.D. and O.D. by a qualified quality control inspector, and shall be welded at change of operator, weld head, welding power supply, or gas source. [NFPA 99:5.1.10.5.1.7 – 5.1.10.5.1.9]

1309.5.3 Welding for Stainless Tube. Stainless tube shall be welded using metal inert gas (MIG) welding, tungsten inert gas (TIG) welding, or other welding techniques approved for joining stainless tube. [NFPA 99:5.1.10.5.2.1]

» **1309.6 Prohibited Joints.** The following joints shall be prohibited throughout medical gas and medical vacuum distribution pipeline systems [NFPA 99:5.1.10.10, 5.3.6.2.6]:

- (1) Flared and compression-type connections, including connections to station outlets and inlets, alarm devices, and other components. [NFPA 99:5.1.10.10(1), 5.3.6.2.6(1)]
- (2) Other straight-threaded connections, including unions. [NFPA 99:5.1.10.10(2), 5.3.6.2.6(3)]
- (3) The use of pipe-crimping tools to permanently stop the flow of medical gas and medical vacuum piping. [NFPA 99:5.1.10.10(3)]
- (4) Removable and nonremovable push-fit fittings that employ a quick assembly push fit connector. [NFPA 99:5.1.10.10(4)]
- (5) Push-lock connections for Category 3 medical gas systems. [NFPA 99:5.3.6.2.6(2)]

» **1310.0 Installation of Piping.**

1310.1 General. The installer shall furnish documentation certifying that installed piping materials for medical gas or medical vacuum systems are in accordance with Section 1308.0. [NFPA 99:5.1.10.1.6]

1310.2 Required Pipe Sizing. Medical gas and medical vacuum piping systems shall be designed and sized to deliver the required flow rates at the utilization pressures in accordance with Section 1310.2.1 through Section 1310.2.3. [NFPA 99:5.1.10.11.1.1, 5.3.6.11.1]

In no case, shall pipe sizing be less than as follows:

- (1) Mains and branches in medical gas piping systems shall be not less than DN15 (NPS $\frac{1}{2}$) ($\frac{3}{8}$ of an inch O.D.) size. [NFPA 99:5.1.10.11.1.2]

- (2) Mains and branches in medical-surgical vacuum systems shall be not less than DN20 (NPS $\frac{3}{4}$) ($\frac{7}{8}$ of an inch O.D.) size. [NFPA 99:5.1.10.11.1.3]
- (3) Drops to individual station outlets and inlets shall be not less than DN15 (NPS $\frac{1}{2}$) ($\frac{5}{8}$ of an inch O.D.) size. [NFPA 99:5.1.10.11.1.4]
- (4) Runouts to alarm panels and connecting tubing for gauges and alarm devices shall be permitted to be DN8 (NPS $\frac{1}{4}$) ($\frac{3}{8}$ of an inch O.D.) size. [NFPA 99:5.1.10.11.1.5]
- (5) Category 3 medical gas piping systems that utilize oxygen shall be not less than DN10 (NPS $\frac{3}{8}$) ($\frac{1}{2}$ of an inch O.D.) size, and systems that utilize nitrous oxide shall be not less than DN8 (NPS $\frac{1}{4}$) ($\frac{3}{8}$ of an inch O.D.) size. [NFPA 99:5.3.6.11.2]

« **1310.2.1 Maximum Demand.** Where the maximum demand for each medical gas or medical vacuum system does not exceed the values in Table 1310.2.1(2) through Table 1310.2.1(7), the size of pipe of each section of the system shall be determined in accordance with Section 1310.2.2. The size for systems beyond the range of Table 1310.2.1(2) through Table 1310.2.1(7) shall be determined in accordance with Section 1310.2.3.

« **1310.2.2 Sizing Procedures.** The size of each section of pipe in a system within the range of Table 1310.2.1(2) through Table 1310.2.1(7) shall be determined in accordance with the following:

- (1) Determine the total flow rate and number of outlets or inlets for each section of pipe in accordance with Table 1305.2 and Table 1305.3.
- (2) Measure the length of the section of pipe to each station outlet or inlet on the system. Multiply the measured pipe length by 1.5 (150 percent), to account for the number of fittings in the system, to determine the pipe equivalent length.
- (3) Beginning with the most remote outlet or inlet, multiply the total flow rate by the diversity factor specified in Table 1310.2.1(1) for each section of pipe to determine the sizing flow rate for the piping.
- (4) Select Table 1310.2.1(2) through Table 1310.2.1(7) based on the medical gas or medical vacuum being transported through the piping.
- (5) Select an estimated pipe size for determining the system pressure loss. Multiply the pipe equivalent length, for a given section of pipe, by the pressure loss for the sizing flow rate in the applicable table.

» **TABLE 1310.2.1(1)**
SYSTEM SIZING – FLOW REQUIREMENTS FOR STATION OUTLETS AND INLETS¹

| NUMBER OF OUTLETS AND INLETS TERMINAL UNITS PER FACILITY | DIVERSITY PERCENTAGE OF AVERAGE FLOW PER OUTLETS AND INLETS TERMINAL UNITS | MINIMUM PERMISSIBLE SYSTEM FLOW OF ALL PRESSURIZED MEDICAL GAS SYSTEMS ² (standard cubic feet per minute) |
|---|--|--|
| 1–10 | 100% | Actual Demand |
| 11–25 | 75% | 7.0 |
| 26–50 | 50% | 13.1 |
| 51–100 | 50% | 17.5 |

Notes:

¹ Flow rates of station outlets and inlets in accordance with Table 1305.2.

² The minimum system flow is the average outlets and inlets flow times the number of station outlets and inlets times the diversity percentage.

Divide that number by 100 to determine the system pressure loss for the section of pipe.

- (6) Add the pressure loss for each section of piping, from the source equipment location to the outlet or inlet, to determine the total system pressure loss to each outlet or inlet. The total system pressure loss in the piping to each outlet or inlet shall not exceed the values specified in Table 1310.2.2(1).

TABLE 1310.2.2(1)
MAXIMUM PERMITTED PRESSURE LOSS IN MEDICAL GAS
AND MEDICAL VACUUM SYSTEMS

| TYPE OF SYSTEM | MAXIMUM ALLOWABLE SYSTEM PRESSURE LOSS (psi) |
|----------------|--|
| Medical Air | 5 |
| Nitrogen | 15 |
| Nitrous Oxide | 5 |
| Carbon Dioxide | 5 |
| Oxygen | 5 |
| Medical Vacuum | 4 inches of mercury |

For SI units: 1 pound-force per square inch = 6.8947 kPa, 1 inch of mercury = 3.386 kPa

- » **1310.2.3 Engineering Methods.** For conditions other than those covered by Section 1310.2.1, such as longer runs of greater gas or vacuum demands, the size of each medical gas or medical vacuum piping system shall be determined by standard engineering methods acceptable to the Authority Having Jurisdiction, and each system shall be so designed that the total pressure drop or gain between the source equipment and an outlet or inlet shall not exceed the allowable pressures shown in Table 1305.1.

- » **1310.3 Pipe Protection.** Piping shall be protected against freezing, corrosion, and physical damage. [NFPA 99:5.1.10.11.2, 5.3.6.11.4.1]

- » **1310.3.1 Exposed Piping.** Piping exposed in corridors and other areas where subject to physical damage from the movement of carts, stretchers, beds, portable equipment, or vehicles shall be protected. [NFPA 99:5.1.10.11.2.1, 5.3.6.11.4.2]

1310.3.2 Underground Piping. Piping underground within buildings or embedded in concrete floors or walls shall be installed in a continuous conduit. [NFPA 99:5.1.10.11.2.2]

Exception: Category 3 medical gas piping shall not be installed within floor slabs. [NFPA 99:5.3.6.15]

- » **1310.3.3 Frost Protection.** Buried piping outside of buildings shall be installed below the local level of frost penetration. [NFPA 99:5.1.10.11.5.1, 5.3.6.13.1]

- » **1310.4 Location of Piping.** Piping risers shall be permitted to be installed in pipe shafts where protected from physical damage, effects of excessive heat, corrosion, or contact with oil. [NFPA 99:5.1.10.11.3.1]

1310.4.1 Prohibited Locations. Piping shall not be installed in kitchens, elevator shafts, elevator machine rooms, areas with open flames, electrical service equipment exceeding 600 volts, and areas prohibited under NFPA 70 except for the following locations:

- (1) Room locations for medical air compressor supply systems and medical-surgical vacuum pump supply systems.
- (2) Room locations for secondary distribution circuit panels and breakers having a voltage rating not exceeding 600 volts. [NFPA 99:5.1.10.11.3.2]
- (3) Medical gas piping, including oxygen and nitrous oxide piping, shall not be located where subject to contact with oil, including a possible flooding area in the case of a major oil leak. [NFPA 99:5.1.10.11.3.4, 5.3.6.11.3]

1310.4.2 Approved Locations. Medical gas piping shall be permitted to be installed in the same service trench or tunnel with fuel gas lines, fuel oil lines, electrical lines, steam lines, and similar utilities provided that the space is ventilated (naturally or mechanically) and the ambient temperature around the medical gas piping does not exceed 130°F (54°C). [NFPA 99:5.1.10.11.3.3]

1310.5 Pipe Support. Piping shall be supported from the building structure. [NFPA 99:5.1.10.11.4.1, 5.3.6.12.1]

1310.5.1 Hangers and Supports. Hangers and supports shall be installed in accordance with MSS SP-58. [NFPA 99:5.1.10.11.4.2, 5.3.6.12.2]

1310.5.2 Copper Tube. Hangers and supports for copper tube shall be sized for copper tube. [NFPA 99:5.1.10.11.4.3, 5.3.6.12.3]

1310.5.3 Damp Locations. In damp locations, copper tube hangers or supports that are in contact with the tube shall be plastic-coated or otherwise be electrically insulated from the tube by a material that will not absorb moisture. [NFPA 99:5.1.10.11.4.4, 5.3.6.12.4]

1310.5.4 Maximum Spacing. Maximum support spacing for metallic piping shall be in accordance with Table 1310.5.4(1). [NFPA 99:5.1.10.11.4.5, 5.3.6.12.5] Maximum support spacing for plastic pipe shall be in accordance with Table 1310.5.4(2). [NFPA 99:5.3.8.3.4]

1310.5.5 Seismic Provisions. Where required, medical gas and medical vacuum piping shall be seismically restrained against earthquakes in accordance with the applicable building code. [NFPA 99:5.1.10.11.4.6]

TABLE 1310.5.4(1)
MAXIMUM METALLIC PIPE SUPPORT SPACING
[NFPA 99: TABLE 5.1.10.11.4.5, 5.3.6.12.5]

| PIPE SIZE | | | HANGER SPACING (feet) |
|---|----------|-----------------------|-----------------------|
| DN8 | (NPS ¼) | (¾ of an inch O.D.) | 5 |
| DN10 | (NPS ⅜) | (½ of an inch O.D.) | 6 |
| DN15 | (NPS ½) | (¾ of an inch O.D.) | 6 |
| DN20 | (NPS ¾) | (7⁄8 of an inch O.D.) | 7 |
| DN25 | (NPS 1) | (1½ of an inch O.D.) | 8 |
| DN32 | (NPS 1¼) | (1¾ of an inch O.D.) | 9 |
| DN40 and larger | (NPS 1½) | (1¾ of an inch O.D.) | 10 |
| Vertical risers, all sizes, every floor, but not to exceed: | | | 15 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm

TABLE 1310.5.4(2)
MAXIMUM PLASTIC PIPE SUPPORT SPACING
[NFPA 99: TABLE 5.3.8.3.4]

| PIPE SIZE | | | HANGER SPACING (feet) |
|--|----------|----------------------|--------------------------|
| DN15 | (NPS ½) | (⅝ of an inch O.D.) | 4 |
| DN20 | (NPS ¾) | (⅞ of an inch O.D.) | 4 |
| DN25 | (NPS 1) | (1⅛ of an inch O.D.) | 4.33 |
| DN32 | (NPS 1¼) | (1⅜ of an inch O.D.) | 4.33 |
| DN40 | (NPS 1½) | (1⅞ of an inch O.D.) | 4.67 |
| DN50 | (NPS 2) | (2⅜ of an inch O.D.) | 4.67 |
| DN65 and larger | (NPS 2½) | (2⅞ of an inch O.D.) | 5 |
| Vertical risers, all sizes, every floor, but not to exceed: | | | 10 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm

» **1310.6 Backfilling and Trenching.** The installation procedure for underground piping shall protect the piping from physical damage while being backfilled. [NFPA 99:5.1.10.11.5.2, 5.3.6.13.2]

1310.6.1 Conduit, Cover, or Enclosure. Underground piping shall comply with the following where protected by a conduit, cover, or other enclosure:

- (1) Access shall be provided at the joints for visual inspection and leak testing.
- (2) The conduit, cover, or enclosure shall be self-draining and not retain groundwater in prolonged contact with the pipe. [NFPA 99:5.1.10.11.5.3, 5.3.6.13.3]

1310.6.2 Excessive Stresses. Buried piping that will be subject to surface loads shall be buried at a depth that will protect the piping or its enclosure from excessive stresses. [NFPA 99:5.1.10.11.5.4, 5.3.6.13.4]

1310.6.3 Minimum Backfill. The minimum back-filled cover above the top of the piping or its enclosure for buried piping outside of buildings shall be 36 inches (914 mm), except that the minimum cover shall be permitted to be reduced to 18 inches (457 mm) where there is no potential for damage from surface loads or surface conditions. [NFPA 99:5.1.10.11.5.5, 5.3.6.13.5]

1310.6.4 Trenches. Trenches shall be excavated so that the piping or its enclosure has firm, substantially continuous bearing on the bottom of the trench. [NFPA 99:5.1.10.11.5.6, 5.3.6.13.6]

1310.6.5 Composition of Backfill. Backfill shall be clean, free from material that is capable of damaging the pipe, and compacted. [NFPA 99:5.1.10.11.5.7, 5.3.6.13.7]

1310.6.6 Marker. A continuous warning tape or marker placed immediately above the piping or its enclosure shall clearly identify the pipeline by specific name. [NFPA 99:5.1.10.11.5.8, 5.3.6.13.8]

1310.6.7 Warning. A continuous warning means shall be provided above the pipeline at approximately

one-half the depth of burial. [NFPA 99:5.1.10.11.5.9, 5.3.6.13.9]

1310.6.8 Wall Sleeve. Where underground piping is installed through a wall sleeve, the outdoor end of the sleeve shall be sealed watertight to prevent the entrance of groundwater into the building. [NFPA 99:5.1.10.11.5.10, 5.3.6.13.10]

« **1310.7 Connectors.** Hose and flexible connectors, both metallic and nonmetallic, shall not be longer than necessary and shall not penetrate or be concealed in walls, floors, ceilings, or partitions. [NFPA 99:5.1.10.11.6.1, 5.3.6.16.1]

Hose and flexible connectors for Category 3 medical gas shall be gas specific and not be permitted to conduct any other gas, gas mixture, or liquid. [NFPA 99:5.3.6.16.5]

Exception: Flexible connectors, used in Category 3 systems, of other than all-metal construction that connect manifolds to the gas distribution piping shall not exceed 5 feet (1524 mm) in length. [NFPA 99:5.3.6.21.9]

1310.7.1 Flexible Connectors. Hose and flexible connectors, metallic or nonmetallic, shall have a burst gauge pressure of not less than 1000 psi (6895 kPa). [NFPA 99:5.1.10.11.6.2, 5.3.6.16.2]

1310.7.2 Metallic Flexible Joints. Metallic flexible joints shall be permitted in the pipeline where required for expansion joints, seismic protection, thermal expansion, or vibration control and shall be as follows:

- (1) For wetted surfaces, made of bronze, copper, or stainless steel.
- (2) Cleaned at the factory for oxygen service and received on the job site with certification of cleanliness.
- (3) Approved for service at 300 psig (2068 kPa) or more and able to withstand temperatures of 1000°F (538°C).
- (4) Provided with brazing extensions to allow brazing into the pipeline in accordance with Section 1309.3.
- (5) Supported with pipe hangers and supports as required for their additional weight. [NFPA 99:5.1.10.11.6.3]

« **1310.8 Prohibited System Interconnections.** Two or more medical gas or medical vacuum piping systems shall not be interconnected for installation, testing, or other reason. [NFPA 99:5.1.10.11.7.1]

1310.8.1 Leak Testing. Leak testing shall be accomplished by separately charging and testing each individual piping system. [NFPA 99:5.1.10.11.7.2]

« **1310.9 Changes in System Use.** Where a positive-pressure medical gas piping distribution system, originally used or constructed for the use at one pressure and for one gas, is converted for operation at another pressure or for another gas, the provisions of Section 1308.0 shall apply as if the system were new. [NFPA 99:5.1.10.11.9.1]

1310.9.1 Medical Vacuum System. A medical vacuum system shall not be permitted to be converted for use as a medical gas system. [NFPA 99:5.1.10.11.9.2]

TABLE 1310.2.1(2)
PRESSURE LOSS FOR MEDICAL AIR

| FLOW RATE (SCFM) ¹ | PRESSURE DROP (psi) PER 100 FEET ² | | |
|----------------------------------|---|-------------|-------------|
| | ½ INCH PIPE | ¾ INCH PIPE | 1 INCH PIPE |
| 0.35 | 0.004 | 0.001 | — |
| 0.71 | 0.012 | 0.003 | — |
| 1.06 | 0.023 | 0.005 | — |
| 1.41 | 0.037 | 0.007 | — |
| 1.77 | 0.055 | 0.011 | — |
| 2.12 | 0.075 | 0.015 | — |
| 2.47 | 0.097 | 0.019 | — |
| 2.82 | 0.123 | 0.024 | — |
| 3.18 | 0.151 | 0.029 | — |
| 3.53 | 0.181 | 0.035 | — |
| 4.24 | 0.249 | 0.048 | — |
| 4.94 | 0.326 | 0.063 | — |
| 5.65 | 0.413 | 0.080 | — |
| 6.36 | 0.507 | 0.098 | — |
| 7.06 | 0.611 | 0.118 | 0.030 |
| 7.77 | 0.723 | 0.139 | 0.035 |
| 8.47 | 0.843 | 0.162 | 0.041 |
| 9.18 | 0.969 | 0.187 | 0.047 |
| 9.89 | 1.108 | 0.212 | 0.053 |
| 10.59 | 1.252 | 0.240 | 0.060 |
| 12.36 | 1.647 | 0.315 | 0.079 |
| 14.12 | 2.090 | 0.398 | 0.100 |
| 15.89 | 2.580 | 0.490 | 0.123 |
| 17.66 | 3.116 | 0.591 | 0.148 |
| 19.42 | — | 0.701 | 0.176 |
| 21.19 | — | 0.818 | 0.205 |
| 22.95 | — | 0.944 | 0.236 |
| 24.72 | — | 1.078 | 0.268 |
| 28.25 | — | 1.369 | 0.341 |
| 31.78 | — | 1.690 | 0.421 |
| 35.31 | — | 2.043 | 0.509 |
| 38.84 | — | 2.425 | 0.603 |
| 42.37 | — | 2.838 | 0.705 |
| 45.90 | — | 3.280 | 0.814 |
| 49.43 | — | 3.751 | 0.929 |
| 52.97 | — | 4.249 | 1.052 |
| 56.50 | — | — | 1.181 |
| 60.03 | — | — | 1.318 |
| 63.56 | — | — | 1.461 |
| 67.09 | — | — | 1.611 |
| 70.62 | — | — | 1.768 |
| 81.21 | — | — | 2.276 |
| 88.28 | — | — | 2.647 |
| 95.34 | — | — | 3.044 |

For SI units: 1 standard cubic foot per minute = 28.32 SLPM, 1 inch = 25 mm, 1 foot = 304.8 mm, 1 pound-force per square inch = 6.8947 kPa

Notes:

¹ Based on pressure of 14.7 psig (101 kPa) at 68°F (20°C).

² Based on pressure of 55 psig (379 kPa) at 68°F (20°C).

TABLE 1310.2.1(3)
PRESSURE LOSS FOR NITROGEN

| FLOW RATE (SCFM) ¹ | PRESSURE DROP (psi) PER 100 FEET ² | | |
|----------------------------------|---|-------------|-------------|
| | ½ INCH PIPE | ¾ INCH PIPE | 1 INCH PIPE |
| 5.30 | 0.126 | 0.024 | — |
| 10.59 | 0.430 | 0.082 | — |
| 15.89 | 0.886 | 0.168 | — |
| 21.19 | 1.485 | 0.281 | — |
| 26.48 | 2.220 | 0.419 | — |
| 31.78 | 3.089 | 0.581 | — |
| 37.08 | 4.087 | 0.766 | — |
| 42.37 | — | 0.975 | — |
| 47.67 | — | 1.206 | — |
| 52.97 | — | 1.460 | 0.361 |
| 58.26 | — | 1.736 | 0.429 |
| 63.56 | — | 2.033 | 0.502 |
| 68.85 | — | 2.352 | 0.580 |
| 74.15 | — | 2.692 | 0.663 |
| 79.45 | — | 3.054 | 0.752 |
| 84.74 | — | 3.436 | 0.845 |
| 90.04 | — | 3.840 | 0.943 |
| 95.34 | — | 4.264 | 1.046 |
| 100.63 | — | 4.709 | 1.154 |
| 105.93 | — | — | 1.267 |
| 116.52 | — | — | 1.508 |
| 127.12 | — | — | 1.768 |
| 137.71 | — | — | 2.046 |
| 148.30 | — | — | 2.344 |
| 158.90 | — | — | 2.660 |
| 169.49 | — | — | 2.994 |
| 180.08 | — | — | 3.347 |
| 190.67 | — | — | 3.719 |
| 201.27 | — | — | 4.108 |
| 211.86 | — | — | 4.516 |
| 222.45 | — | — | 4.942 |
| 233.05 | — | — | — |
| 243.64 | — | — | — |
| 254.23 | — | — | — |
| 264.83 | — | — | — |
| 275.42 | — | — | — |
| 286.01 | — | — | — |
| 296.60 | — | — | — |
| 307.20 | — | — | — |
| 317.79 | — | — | — |

For SI units: 1 standard cubic foot per minute = 28.32 SLPM, 1 inch = 25 mm, 1 foot = 304.8 mm, 1 pound-force per square inch = 6.8947 kPa

Notes:

¹ Based on pressure of 14.7 psig (101 kPa) at 68°F (20°C).

² Based on pressure of 55 psig (379 kPa) at 68°F (20°C).

TABLE 1310.2.1(4)
PRESSURE LOSS FOR NITROUS OXIDE
AND CARBON DIOXIDE

| FLOW RATE (SCFM) ¹ | PRESSURE DROP (psi) PER 100 FEET ² | | |
|----------------------------------|---|-------------|-------------|
| | ½ INCH PIPE | ¾ INCH PIPE | 1 INCH PIPE |
| 0.35 | 0.004 | — | — |
| 0.71 | 0.014 | — | — |
| 1.06 | 0.029 | — | — |
| 1.41 | 0.047 | — | — |
| 1.77 | 0.070 | — | — |
| 2.12 | 0.096 | — | — |
| 2.47 | 0.125 | — | — |
| 2.82 | 0.159 | — | — |
| 3.18 | 0.195 | — | — |
| 3.53 | 0.235 | 0.045 | — |
| 4.24 | 0.324 | 0.062 | — |
| 4.94 | 0.425 | 0.081 | — |
| 5.65 | 0.539 | 0.103 | — |
| 6.36 | 0.664 | 0.127 | — |
| 7.06 | 0.802 | 0.153 | 0.038 |
| 7.77 | 0.950 | 0.181 | 0.045 |
| 8.47 | 1.110 | 0.211 | 0.053 |
| 9.18 | 1.281 | 0.243 | 0.061 |
| 9.89 | 1.463 | 0.278 | 0.070 |
| 10.59 | 1.656 | 0.314 | 0.079 |
| 12.36 | 2.186 | 0.413 | 0.103 |
| 14.12 | 2.752 | 0.525 | 0.131 |
| 15.89 | 3.442 | 0.648 | 0.162 |
| 17.66 | 4.166 | 0.783 | 0.195 |
| 19.42 | — | 0.929 | 0.231 |
| 21.19 | — | 0.744 | 0.270 |
| 22.95 | — | 0.858 | 0.312 |
| 24.72 | — | 0.980 | 0.356 |
| 28.25 | — | 1.244 | 0.453 |
| 31.78 | — | 1.537 | 0.560 |
| 35.31 | — | 1.858 | 0.677 |
| 38.84 | — | 2.205 | 0.804 |
| 42.37 | — | 2.581 | 0.941 |
| 45.90 | — | 2.982 | 1.088 |
| 49.43 | — | 3.411 | 1.245 |
| 52.97 | — | 4.249 | 1.411 |
| 56.50 | — | — | 1.587 |
| 60.03 | — | — | 1.772 |
| 63.56 | — | — | 1.967 |
| 67.09 | — | — | 2.174 |
| 70.62 | — | — | 2.385 |
| 79.45 | — | — | 2.959 |
| 88.28 | — | — | 3.589 |

For SI units: 1 standard cubic foot per minute = 28.32 SLPM, 1 inch = 25 mm, 1 foot = 304.8 mm, 1 pound-force per square inch = 6.8947 kPa

Notes:

¹ Based on pressure of 14.7 psig (101 kPa) at 68°F (20°C).

² Based on pressure of 55 psig (379 kPa) at 68°F (20°C).

TABLE 1310.2.1(5)
PRESSURE LOSS FOR OXYGEN

| FLOW RATE (SCFM) ¹ | PRESSURE DROP (psi) PER 100 FEET ² | | |
|----------------------------------|---|-------------|-------------|
| | ½ INCH PIPE | ¾ INCH PIPE | 1 INCH PIPE |
| 0.35 | 0.004 | — | — |
| 0.71 | 0.013 | 0.003 | — |
| 1.06 | 0.025 | 0.005 | — |
| 1.41 | 0.041 | 0.008 | — |
| 1.77 | 0.060 | 0.012 | — |
| 2.12 | 0.082 | 0.016 | — |
| 2.47 | 0.107 | 0.021 | — |
| 2.82 | 0.135 | 0.026 | — |
| 3.18 | 0.166 | 0.032 | — |
| 3.53 | 0.199 | 0.038 | — |
| 4.24 | 0.274 | 0.053 | — |
| 4.94 | 0.359 | 0.069 | — |
| 5.65 | 0.454 | 0.087 | — |
| 6.36 | 0.558 | 0.107 | — |
| 7.06 | 0.672 | 0.129 | 0.033 |
| 7.77 | 0.795 | 0.153 | 0.039 |
| 8.47 | 0.927 | 0.179 | 0.045 |
| 9.18 | 1.066 | 0.205 | 0.052 |
| 9.89 | 1.218 | 0.233 | 0.059 |
| 10.59 | 1.377 | 0.263 | 0.066 |
| 12.36 | 1.811 | 0.346 | 0.087 |
| 14.12 | 2.298 | 0.438 | 0.110 |
| 15.89 | 2.837 | 0.539 | 0.135 |
| 17.66 | 3.456 | 0.650 | 0.163 |
| 19.42 | — | 0.771 | 0.193 |
| 21.19 | — | 0.900 | 0.225 |
| 22.95 | — | 1.038 | 0.260 |
| 24.72 | — | 1.185 | 0.295 |
| 28.25 | — | 1.505 | 0.375 |
| 31.78 | — | 1.859 | 0.463 |
| 35.31 | — | 2.247 | 0.559 |
| 38.84 | — | 2.667 | 0.663 |
| 42.37 | — | 3.121 | 0.775 |
| 45.90 | — | 3.607 | 0.895 |
| 49.43 | — | 4.125 | 1.022 |
| 52.97 | — | — | 1.157 |
| 56.50 | — | — | 1.299 |
| 60.03 | — | — | 1.449 |
| 63.56 | — | — | 1.607 |
| 67.09 | — | — | 1.772 |
| 70.62 | — | — | 1.944 |
| 81.21 | — | — | 2.503 |
| 91.81 | — | — | 3.127 |
| 102.40 | — | — | 3.813 |

For SI units: 1 standard cubic foot per minute = 28.32 SLPM, 1 inch = 25 mm, 1 foot = 304.8 mm, 1 pound-force per square inch = 6.8947 kPa

Notes:

¹ Based on pressure of 14.7 psig (101 kPa) at 68°F (20°C).

² Based on pressure of 55 psig (379 kPa) at 68°F (20°C).

TABLE 1310.2.1(6)
PRESSURE LOSS FOR VACUUM

| FLOW RATE (SCFM) ¹ | VACUUM LOSS (inch of mercury) PER 100 FEET FOR COPPER TUBE ² | | | | |
|----------------------------------|---|-------------|--------------|--------------|-------------|
| | ¾ INCH TUBE | 1 INCH TUBE | 1¼ INCH TUBE | 1½ INCH TUBE | 2 INCH TUBE |
| 0.35 | 0.019 | — | — | — | — |
| 0.71 | 0.061 | — | — | — | — |
| 1.06 | 0.120 | — | — | — | — |
| 1.41 | 0.194 | — | — | — | — |
| 1.77 | 0.284 | — | — | — | — |
| 2.12 | 0.387 | — | — | — | — |
| 2.47 | 0.504 | — | — | — | — |
| 2.82 | 0.634 | — | — | — | — |
| 3.18 | 0.777 | — | — | — | — |
| 3.53 | 0.932 | 0.238 | — | — | — |
| 4.24 | 1.277 | 0.325 | — | — | — |
| 4.94 | 1.669 | 0.424 | — | — | — |
| 5.65 | 2.106 | 0.534 | — | — | — |
| 6.36 | 2.586 | 0.655 | — | — | — |
| 7.06 | 3.110 | 0.787 | 0.272 | — | — |
| 7.77 | 3.674 | 0.929 | 0.321 | — | — |
| 8.47 | 4.280 | 1.081 | 0.373 | — | — |
| 9.18 | 4.927 | 1.243 | 0.429 | — | — |
| 9.89 | — | 1.416 | 0.488 | — | — |
| 10.59 | — | 1.597 | 0.551 | 0.242 | — |
| 11.30 | — | 1.789 | 0.616 | 0.270 | — |
| 12.01 | — | 1.990 | 0.685 | 0.300 | — |
| 12.71 | — | 2.200 | 0.757 | 0.332 | — |
| 13.42 | — | 2.419 | 0.832 | 0.365 | — |
| 14.12 | — | 2.648 | 0.911 | 0.399 | — |
| 14.83 | — | 2.886 | 0.992 | 0.435 | — |
| 15.54 | — | 3.132 | 1.077 | 0.471 | — |
| 16.24 | — | 3.388 | 1.164 | 0.510 | — |
| 16.95 | — | 3.652 | 1.254 | 0.549 | — |
| 17.66 | — | 3.925 | 1.348 | 0.590 | — |
| 18.36 | — | 4.207 | 1.444 | 0.632 | 0.167 |
| 19.07 | — | 4.498 | 1.543 | 0.675 | 0.179 |
| 19.77 | — | 4.797 | 1.646 | 0.720 | 0.190 |
| 20.48 | — | — | 1.751 | 0.766 | 0.202 |
| 21.19 | — | — | 1.859 | 0.813 | 0.214 |
| 24.72 | — | — | 2.441 | 1.066 | 0.281 |
| 28.25 | — | — | 3.092 | 1.350 | 0.356 |
| 31.78 | — | — | 3.811 | 1.662 | 0.438 |
| 35.31 | — | — | 4.596 | 2.004 | 0.527 |
| 38.84 | — | — | — | 2.373 | 0.624 |
| 42.37 | — | — | — | 2.770 | 0.728 |
| 45.90 | — | — | — | 3.194 | 0.838 |

TABLE 1310.2.1(6)
PRESSURE LOSS FOR VACUUM (continued)

| FLOW RATE (SCFM) ¹ | VACUUM LOSS (inch of mercury) PER 100 FEET FOR COPPER TUBE ² | | | | |
|----------------------------------|---|-------------|--------------|--------------|-------------|
| | ¾ INCH TUBE | 1 INCH TUBE | 1¼ INCH TUBE | 1½ INCH TUBE | 2 INCH TUBE |
| 49.43 | — | — | — | 3.645 | 0.956 |
| 52.97 | — | — | — | 4.122 | 1.081 |
| 56.50 | — | — | — | 4.626 | 1.212 |
| 63.56 | — | — | — | — | 1.495 |
| 70.62 | — | — | — | — | 1.803 |
| 77.68 | — | — | — | — | 2.138 |
| 84.74 | — | — | — | — | 2.497 |
| 91.81 | — | — | — | — | 2.882 |
| 98.87 | — | — | — | — | 3.291 |
| 105.93 | — | — | — | — | 3.724 |
| 112.99 | — | — | — | — | 4.181 |

For SI units: 1 standard cubic foot per minute = 28.32 SLPM, 1 inch = 25 mm, 1 foot = 304.8 mm, 1 inch of mercury = 3.386 kPa

Notes:

¹ Based on pressure of 14.7 psig (101 kPa) at 68°F (20°C).

² Based on pressure of 19 inches of mercury gauge vacuum (64 kPa) at 68°F (20°C).

TABLE 1310.2.1(7)
PRESSURE LOSS FOR VACUUM (CATEGORY 3)

| FLOW RATE (SCFM) ¹ | VACUUM LOSS (inch of mercury) PER 100 FEET FOR PLASTIC TUBE ² | | | | |
|----------------------------------|--|-------------|--------------|--------------|-------------|
| | ¾ INCH TUBE | 1 INCH TUBE | 1¼ INCH TUBE | 1½ INCH TUBE | 2 INCH TUBE |
| 0.35 | 0.005 | — | — | — | — |
| 0.71 | 0.010 | — | — | — | — |
| 1.06 | 0.015 | — | — | — | — |
| 1.41 | 0.021 | — | — | — | — |
| 1.77 | 0.026 | — | — | — | — |
| 2.12 | 0.060 | 0.010 | — | — | — |
| 2.47 | 0.077 | 0.020 | — | — | — |
| 2.82 | 0.096 | 0.025 | — | — | — |
| 3.18 | 0.118 | 0.031 | 0.011 | — | — |
| 3.53 | 0.141 | 0.036 | 0.013 | — | — |
| 4.24 | 0.192 | 0.050 | 0.017 | — | — |
| 4.94 | 0.249 | 0.064 | 0.023 | 0.010 | — |
| 5.65 | 0.313 | 0.081 | 0.028 | 0.012 | — |
| 6.36 | 0.383 | 0.099 | 0.035 | 0.015 | — |
| 7.06 | 0.459 | 0.118 | 0.041 | 0.018 | — |
| 7.77 | 0.541 | 0.139 | 0.049 | 0.021 | — |
| 8.47 | 0.628 | 0.161 | 0.056 | 0.024 | — |
| 9.18 | 0.722 | 0.185 | 0.065 | 0.027 | — |
| 9.89 | 0.821 | 0.210 | 0.073 | 0.031 | — |
| 10.59 | 0.925 | 0.237 | 0.083 | 0.035 | — |
| 11.30 | 1.035 | 0.265 | 0.092 | 0.039 | 0.010 |
| 12.01 | 1.151 | 0.294 | 0.102 | 0.043 | 0.011 |
| 12.71 | 1.270 | 0.324 | 0.113 | 0.048 | 0.012 |

TABLE 1310.2.1(7)
PRESSURE LOSS FOR VACUUM (CATEGORY 3) (continued)

| FLOW RATE (SCFM) ¹ | VACUUM LOSS (inch of mercury) PER 100 FEET FOR PLASTIC TUBE ² | | | | |
|----------------------------------|--|-------------|--------------|--------------|-------------|
| | ¾ INCH TUBE | 1 INCH TUBE | 1¼ INCH TUBE | 1½ INCH TUBE | 2 INCH TUBE |
| 13.42 | 1.396 | 0.356 | 0.124 | 0.052 | 0.014 |
| 14.12 | 1.525 | 0.389 | 0.135 | 0.057 | 0.015 |
| 14.83 | 1.662 | 0.424 | 0.147 | 0.062 | 0.016 |
| 15.54 | 1.803 | 0.460 | 0.160 | 0.068 | 0.017 |
| 16.24 | 1.948 | 0.496 | 0.172 | 0.073 | 0.019 |
| 16.95 | 2.099 | 0.535 | 0.186 | 0.078 | 0.020 |
| 17.66 | 2.256 | 0.574 | 0.199 | 0.084 | 0.022 |
| 18.36 | 2.415 | 0.615 | 0.213 | 0.090 | 0.023 |
| 19.07 | 2.581 | 0.657 | 0.228 | 0.096 | 0.025 |
| 19.77 | 2.750 | 0.699 | 0.243 | 0.102 | 0.026 |
| 20.48 | 2.925 | 0.744 | 0.258 | 0.109 | 0.028 |
| 21.19 | 3.106 | 0.790 | 0.274 | 0.115 | 0.030 |
| 24.72 | 4.074 | 1.034 | 0.358 | 0.151 | 0.039 |
| 28.25 | — | 1.307 | 0.452 | 0.190 | 0.049 |
| 31.78 | — | 1.608 | 0.556 | 0.234 | 0.060 |
| 35.31 | — | 1.936 | 0.669 | 0.281 | 0.072 |
| 38.84 | — | 2.291 | 0.791 | 0.332 | 0.085 |
| 42.37 | — | 2.672 | 0.922 | 0.387 | 0.099 |
| 45.90 | — | 3.078 | 1.062 | 0.446 | 0.113 |
| 49.43 | — | 3.510 | 1.211 | 0.508 | 0.129 |
| 52.97 | — | 3.969 | 1.368 | 0.574 | 0.146 |
| 56.50 | — | 4.450 | 1.534 | 0.643 | 0.163 |
| 63.56 | — | — | 1.890 | 0.792 | 0.201 |
| 70.62 | — | — | 2.278 | 0.954 | 0.242 |
| 77.68 | — | — | 2.699 | 1.130 | 0.286 |
| 84.74 | — | — | 3.151 | 1.318 | 0.334 |
| 91.81 | — | — | 3.634 | 1.520 | 0.385 |
| 98.87 | — | — | 4.148 | 1.734 | 0.439 |
| 105.93 | — | — | 4.691 | 1.961 | 0.496 |
| 112.99 | — | — | — | 2.200 | 0.556 |

For SI units: 1 standard cubic foot per minute = 28.32 SLPm, 1 inch = 25 mm, 1 foot = 304.8 mm, 1 inch of mercury = 3.386 kPa

Notes:

¹ Based on pressure of 14.7 psig (101 kPa) at 68°F (20°C).

² Based on pressure of 19 inches of mercury gauge vacuum (64 kPa) at 68°F (20°C).

1310.10 Breaching or Penetrating Medical Gas

Piping. Positive pressure patient medical gas piping shall not be breached or penetrated by any means or process that will result in residual copper particles or other debris remaining in the piping or affect the oxygen-clean interior of the piping. The breaching or penetrating process shall ensure that debris created by the process remains contained within the work area. [NFPA 99:5.1.10.11.12]

» **1310.11 Labeling and Identification.** Color and pressure requirements shall be in accordance with Table 1305.1. Medical gas piping shall not be painted. [NFPA 99:5.1.11.1.3]

» **1310.11.1 Pipe Labeling.** Piping shall be labeled by stenciling or adhesive markers that identify the patient medical gas or medical vacuum system and include the following:

- (1) The name of the medical gas or medical vacuum system or the chemical symbol shall comply with Table 1305.1.
- (2) The medical gas or medical vacuum system color code shall comply with Table 1305.1.
- (3) Where positive-pressure gas piping systems operate at pressures other than the standard gauge pressure in Table 1305.1, the pipe labeling shall include the operating pressure in addition to the name of the gas. [NFPA 99:5.1.11.1.1]

1310.11.2 Location of Pipe Labeling. Pipe labels shall be located as follows:

- (1) At intervals of not more than 20 feet (6096 mm).
- (2) Not less than once in or above every room.
- (3) On both sides of walls or partitions penetrated by the piping.

- (4) Not less than once in every story height traversed by risers. [NFPA 99:5.1.11.1.2]

» 1311.0 Cleaning for Medical Gas Piping Systems.

- » **1311.1 Cleaning.** The interior surfaces of tube ends, fittings, and other components that were cleaned for oxygen service by the manufacturer, but become contaminated prior to being installed, shall be permitted to be recleaned on-site by the installer by thoroughly scrubbing the interior surfaces with a clean, hot water-alkaline solution, such as sodium carbonate or trisodium phosphate, using a solution of 1 pound (0.5 kg) of sodium carbonate or trisodium phosphate to 3 gallons (11 L) of potable water and thoroughly rinsing them with clean, hot potable water. Other aqueous cleaning solutions shall be permitted to be used for on-site recleaning provided that they are as recommended in CGA G-4.1. [NFPA 99:5.1.10.4.3.10, 5.1.10.4.3.11]
- » **1311.2 Contaminated Materials.** Material that has become contaminated internally and is not clean for oxygen service shall not be installed. [NFPA 99:5.1.10.4.3.12, 5.3.6.6.8]

» 1312.0 Shutoff Valves.

- » **1312.1 General.** New or replacement shutoff valves for medical gas or medical vacuum systems shall be as follows:
- (1) Quarter turn, full ported, ball type.
 - (2) Brass or bronze construction.
 - (3) Have extensions for brazing.
 - (4) Have a handle indicating open or closed.
 - (5) Consist of three pieces permitting in-line serviceability. [NFPA 99:5.1.4.3]

Exception: Shutoff valves for medical vacuum service shall be permitted to be ball or butterfly type. [NFPA 99:5.1.4.3.2]

1312.1.1 Location. Shutoff valves, except valves in zone valve box assemblies, shall be located in secured areas such as locked piped chases, or be locked or latched in their operating position. [NFPA 99:5.1.4.2]

- » **1312.1.2 Installation.** Shutoff valves accessible to other than authorized personnel shall be installed in valve boxes with frangible or removable windows large enough to permit manual operation of valves. Shutoff valves for use in certain areas, such as psychiatric or pediatric areas, shall be permitted to be secured with the approval of the Authority Having Jurisdiction to prevent inappropriate access. [NFPA 99:5.1.4.2.1, 5.1.4.2.2]

1312.1.3 Emergency Shutoff Valves. Where a central Category 3 medical gas (oxygen and nitrous oxide) supply is remote from a single treatment facility, the main supply line shall be provided with an emergency shutoff valve so located in the single treatment facility as to be accessible from all use-point locations in an emergency. Where a central Category 3 medical gas (oxygen and nitrous oxide) supply system supplies two treatment facilities, each facility shall be provided with an emergency shutoff valve so located in the treat-

ment facility as to be accessible from all use-point locations in an emergency. [NFPA 99:5.3.6.19.1, 5.3.6.19.2]

1312.1.3.1 Remote Activated. A remotely activated shutoff valve at a supply manifold shall not be used for emergency shutoff. For clinical purposes, such a remote valve actuator shall not fail-closed in the event of a loss of electric power. Where remote actuators are the type that fail-open, it shall be mandatory that cylinder shutoff valves be closed where the system is not in use. [NFPA 99:5.3.6.19.4]

1312.1.4 Labeled. Shutoff valves shall be labeled in accordance with Section 1312.9.

1312.2 Source Valves. A shutoff valve shall be placed at the immediate connection of each source system to the piped distribution system to permit the entire source, including accessory devices to be isolated from the facility. [NFPA 99:5.1.4.4]

1312.2.1 Location. The source valve shall be located in the immediate vicinity of the source equipment. [NFPA 99:5.1.4.4.1]

1312.3 Main Valves. A shutoff valve shall be provided in the main supply line inside of the building, except where one or more of the following conditions exist:

- (1) The source and source valve are located inside the building served.
- (2) The source system is physically mounted to the wall of the building served, and the pipeline enters the building in the immediate vicinity of the source valve. [NFPA 99:5.1.4.5]

1312.3.1 Access. The main line valve shall be located to permit access by authorized personnel only. [NFPA 99:5.1.4.5.1]

1312.3.2 Location. The main line valve shall be located on the facility side of the source valve and outside of the source room, enclosure, or where the main line first enters the building. [NFPA 99:5.1.4.5.2]

1312.4 Riser Valves. Risers supplied from the main line shall be provided with a shutoff valve in the riser adjacent to the main line. [NFPA 99:5.1.4.6]

1312.4.1 Location. Riser valves shall be permitted to be located above ceilings, but shall remain accessible and not be obstructed. [NFPA 99:5.1.4.6.1]

1312.5 Service Valves. Service valves shall be installed to allow servicing or modification of lateral branch piping from a main or riser without shutting down the entire main, riser, or facility. [NFPA 99:5.1.4.7]

1312.5.1 Branch Piping. Not more than one service valve shall be required for each branch off of a riser regardless of how many zone valve boxes are installed on that lateral. [NFPA 99:5.1.4.7.1]

Service valves shall be placed in the branch piping prior to a zone valve box assembly on that branch. [NFPA 99:5.1.4.7.2]

1312.5.2 Location. Service valves shall be located in one of the following areas:

- (1) Behind a locked access door
- (2) Locked open above a ceiling
- (3) Locked open in a secure area [NFPA 99:5.1.4.7.3]

» **1312.6 Zone Valves.** Station outlets and inlets shall be supplied through a zone valve as follows:

- (1) The zone valve shall be placed such that a wall intervenes between the valve and outlets or inlets that it controls.
- (2) The zone valve shall serve only outlets and inlets located on that same story.
- (3) The zone valve shall not be located in the same room with the station outlets or inlets that it controls. [NFPA 99:5.1.4.8]

» **1312.6.1 Readily Operable.** Zone valves shall be readily operable from a standing position in the corridor on the same floor they serve. [NFPA 99:5.1.4.8.1]

» **1312.6.2 Arrangement.** Zone valves shall be so arranged that shutting off the supply of medical gas or medical vacuum to one zone, operating room, or anesthetizing location will not affect the supply of medical gas or medical vacuum to another zone, room, location, or the rest of the system. [NFPA 99:5.1.4.8.2, 5.1.4.8.7.2]

1312.6.3 Indicators. A pressure or vacuum indicator shall be provided on the station outlet or inlet side of each zone valve. [NFPA 99:5.1.4.8.3]

» **1312.6.4 Location.** A zone valve shall be located immediately outside each vital life-support area, critical care area, and anesthetizing location of moderate sedation, deep sedation, or general anesthesia, in each medical gas, medical vacuum line, or both, and located so as to be readily accessible in an emergency. [NFPA 99:5.1.4.8.7]

» **1312.6.4.1 Special Installations.** Gas-delivery columns, hose reels, ceiling tracks, control panels, pendants, booms, or other special installations shall be located downstream of the zone valve. [NFPA 99:5.1.4.8.7.1]

» **1312.7 In-Line Shutoff Valves.** In-line shutoff valves intended for use to isolate piping for maintenance or modification shall meet the following requirements:

- (1) Be located in a restricted area
- (2) Be locked or latched open
- (3) Be identified in accordance with Section 1312.9 [NFPA 99:5.1.4.9.1]

» **1312.8 Future Piping.** Shutoff valves provided for the connection of future piping shall meet the following requirements:

- (1) Be located in a restricted area
- (2) Be locked or latched closed
- (3) Be identified in accordance with Section 1312.9 [NFPA 99:5.1.4.10]

1312.8.1 Downstream Piping. Downstream piping shall be closed with a brazed cap with tubing allowance for cutting and rebrazing. [NFPA 99:5.1.4.10.2]

1312.9 Identification. Shutoff valves shall be identified as follows:

- (1) The name or chemical symbol for the specific medical gas or medical vacuum system.
- (2) The room or areas served.
- (3) A caution to not close or open valve except in emergency. [NFPA 99:5.1.11.2.1]

1312.9.1 Nonstandard Operating Pressures.

Where positive pressure gas piping systems operate at pressures other than the standard gauge pressure of 50 psi (345 kPa) to 55 psi (379 kPa), or a gauge pressure of 160 psi (1103 kPa) to 185 psi (1276 kPa) for nitrogen, the shutoff valve identification shall also include the nonstandard operating pressure. [NFPA 99:5.1.11.2.2]

1312.9.2 Labeling. Shutoff valves shall be labeled in substance as follows:

Source valve(s) shall be labeled in substance as follows:

SOURCE VALVE FOR THE (SOURCE NAME)
[NFPA 99:5.1.11.2.3]

Main line valve(s) shall be labeled in substance as follows:

**MAIN LINE VALVE FOR THE
(MEDICAL GAS/VACUUM NAME)
SERVING (NAME OF BUILDING)**
[NFPA 99:5.1.11.2.4]

Riser valve(s) shall be labeled in substance as follows:

**RISER FOR THE (MEDICAL GAS/
VACUUM NAME) SERVING (NAME OF THE
AREA/BUILDING SERVED BY THE
PARTICULAR RISER)**
[NFPA 99:5.1.11.2.5]

Service valve(s) shall be labeled in substance as follows:

**SERVICE VALVE FOR THE
(MEDICAL GAS/VACUUM NAME) SERVING
(NAME OF THE AREA/BUILDING
SERVED BY THE PARTICULAR VALVE)**
[NFPA 99:5.1.11.2.6]

In-line shutoff valve(s) shall be labeled in substance as follows:

**CAUTION
IN-LINE SHUTOFF VALVE FOR THE
(MEDICAL GAS/VACUUM NAME)
DO NOT CLOSE EXCEPT IN EMERGENCY
THIS VALVE CONTROLS SUPPLY TO
(NAME OF THE AREA/BUILDING SERVED
BY THE PARTICULAR VALVE)**

I Part III – Systems, Equipment, and Components.**1313.0 Central Supply Systems.**

1313.1 General. Central supply systems and medical gas outlets for oxygen, medical air, nitrous oxide, carbon dioxide, and other patient medical gases shall be piped into areas where the gases will be used under the direction of licensed medical professionals for purposes congruent with the following:

- (1) Direct respiration by patients.
- (2) Clinical application of the gas to a patient.
- (3) Medical device applications directly related to respiration.
- (4) Power for medical devices used directly on patients.
- (5) Calibration of medical devices used in accordance with Section 1313.1(1) through Section 1313.1(4). [NFPA 99:5.1.3.5.2]

» **1313.1.1 Materials.** Materials used in central supply systems shall comply with the following requirements:

- (1) In those portions of systems intended to handle oxygen at gauge pressures that exceed 350 pounds-force per square inch (psi) (2413 kPa), the interconnecting hose shall contain no polymeric materials.
- (2) In those portions of systems intended to handle oxygen or nitrous oxide material, construction shall be compatible with oxygen under the temperatures and pressures to which the components are capable of being exposed in the containment and use of oxygen, nitrous oxide, mixtures of these gases, or mixtures containing more than 23.5 percent oxygen. [NFPA 99:5.1.3.5.4 – 5.1.3.5.4(2), 5.3.6.21.8 – 5.3.6.21.8(2)]

» **1313.1.2 Pressure-Relief Valve Requirements.** Pressure-relief valves shall be installed in accordance with Section 1316.2. Each central supply system shall have a pressure-relief valve set at 50 percent above normal line pressure, installed downstream of the pressure regulator and upstream of the shutoff valve. This pressure-relief valve shall be permitted to be set at a higher pressure, provided another pressure-relief valve set at 50 percent above normal line pressure is installed in the main supply line.

→ » **1314.0 Medical Air Systems.**

» **1314.1 Medical Air Compressors.** Medical air compressors shall be installed in a well-lit, ventilated, and clean location and shall be accessible. The location shall be provided with drainage facilities in accordance with this code. The medical air compressor area shall be located separately from medical gas cylinder system sources, and shall be readily accessible for maintenance.

» **1314.1.1 Capacity.** Medical air compressors shall be sufficient to serve the peak calculated demand with the largest single compressor out of service. In no case shall there be less than two compressors. [NFPA 99:5.1.3.6.3.10(B)]

1314.1.2 Required Components. Medical air compressor systems shall consist of the components listed in Section 1314.1.2.1 or Section 1314.1.2.2.

1314.1.2.1 Category 1 and 2 Systems. Category 1 and Category 2 medical air compressor systems shall consist of the following:

- (1) Components shall be arranged to permit service and a continuous supply of medical air in the event of a single fault failure. Component arrangement shall be permitted to vary in accordance with the technology(ies) employed, provided an equal level of operating redundancy and medical air quality is maintained. [NFPA 99:5.1.3.6.3.10(A)]
- (2) An automatic means to prevent backflow from on-cycle compressors through off-cycle compressors. [NFPA 99:5.1.3.6.3.2(2)]
- (3) A manual shutoff valve to isolate each compressor from the centrally piped system and from other compressors for maintenance or repair without loss of pressure in the system. [NFPA 99:5.1.3.6.3.2(3)]
- (4) Intake filter-mufflers of the dry type. [NFPA 99:5.1.3.6.3.2(4)]
- (5) Pressure relief valves set at 50 percent above line pressure. [NFPA 99:5.1.3.6.3.2(5)]
- (6) Piping and components between the compressor and the source shutoff valve that do not contribute to contaminant levels. [NFPA 99:5.1.3.6.3.2(6)]
- (7) Materials and devices used between the medical air intake and the medical air source valve shall be permitted to be of a design or construction appropriate for the service as determined by the manufacturer. [NFPA 99:5.1.3.6.3.2(7)]

1314.1.2.2 Category 3 Systems. Category 3 medical air compressor systems shall consist of the following:

- (1) Disconnect switches.
- (2) Motor-starting devices.
- (3) Motor overload protection devices.
- (4) One or more compressors.
- (5) For single, duplex, or multiple compressor systems, means for activation and deactivation of each individual compressor.
- (6) Where multiple compressors are used, manual or automatic means to alternate individual compressors.
- (7) Where multiple compressors are used, manual or automatic means to activate the additional unit(s) where the in-service unit(s) are incapable of maintaining the required pressure.
- (8) Intake filter-mufflers of the dry type.

- (9) Receivers with a manual or automatic drain.
- (10) Shutoff valves.
- (11) Compressor discharge check valves (for multiple compressors).
- (12) Air dryers that maintain not less than 40 percent relative humidity at operating pressure and temperature.
- (13) In-line final particulate or coalescing filters rated at 0.01 micron (0.01 μm), with filter status indicator to ensure the delivery of compressed air with a maximum allowable 0.05 ppm liquid oil.
- (14) Pressure regulators.
- (15) Pressure-relief valve.
- (16) Pressure indicator.
- (17) Moisture indicator. [NFPA 99:5.3.7.6.1]

1314.1.3 Air Sources. Air sources for medical air compressors shall comply with Section 1314.1.3.1 or Section 1314.1.3.2.

1314.1.3.1 Category 1 and 2 Systems. The medical air compressors shall draw their air from a source of clean air. [NFPA 99:5.1.3.6.3.12(A)]

Where an air source equal to or better than outside air is available, it shall be permitted to be used for the medical air compressors in accordance with the following provisions:

- (1) This alternate source of supply air shall be available on a continuous 24 hours-per-day, 7 days-per-week basis.
- (2) Ventilating systems having fans with motors or drive belts located in the air stream shall not be used as a source of medical air intake. [NFPA 99:5.1.3.6.3.12(E)]

1314.1.3.2 Category 3 Systems. Air sources for a compressor(s) located inside a building shall comply with the following provisions:

- (1) Be located within a space where no chemical-based materials are stored or used.
- (2) Be located in a space that is not used for patient medical treatment.
- (3) Not be taken from a room or space in which there is an open or semi-open discharge from a medical vacuum or scavenging system. [NFPA 99:5.3.7.6.5.1]

Air sources for a compressor(s) located outside the building shall be drawn from locations where no contamination from medical vacuum or scavenging system discharges or particulate matter is anticipated. [NFPA 99:5.3.7.6.5.2]

1314.1.4 Air Intakes. Compressor intake piping shall be constructed in accordance with Section 1308.5. [NFPA 99:5.1.3.6.3.12(F)]

1314.1.4.1 Location. Compressor air intakes shall be located as follows:

- (1) Not less than 25 feet (7620 mm) from ventilating system exhausts, fuel storage vents, combustion vents, plumbing vents, medical vacuum and WAGD discharges, or areas that are capable of collecting vehicular exhausts or other noxious fumes. [NFPA 99:5.1.3.6.3.12(B)]
- (2) Not less than 20 feet (6096 mm) above ground level. [NFPA 99:5.1.3.6.3.12(C)]
- (3) Not less than 10 feet (3048 mm) from a door, window, or opening in the building. [NFPA 99:5.1.3.6.3.12(D)]

1314.1.4.2 Separate Compressors. Air intakes for separate compressors shall be permitted to be joined together to one common intake where the following conditions are met:

- (1) The common intake is sized to minimize backpressure in accordance with the manufacturer's instructions.
- (2) Each compressor is capable of being isolated by manual or check valve, blind flange, or tube cap to prevent open inlet piping where the compressor(s) is removed for service from the consequent backflow of room air into the other compressor(s). [NFPA 99:5.1.3.6.3.12(G)]

1314.1.4.3 Screening. The end of the intake shall be turned down and screened or otherwise protected against the entry of vermin, debris, or precipitation by screening fabricated or composed of a noncorroding material. [NFPA 99:5.1.3.6.3.12(H)]

1314.2 Medical Air Receivers. Receivers for medical air shall meet the following requirements [NFPA 99:5.1.3.6.3.6]:

- (1) Be made of corrosion-resistant materials or otherwise be made corrosion resistant. [NFPA 99:5.1.3.6.3.6(1)]
- (2) Comply with Section VIII of the ASME Boiler and Pressure Vessel Code. [NFPA 99:5.1.3.6.3.6(2), 5.3.7.6.2.2]
- (3) Be equipped with a pressure-relief valve, automatic drain, manual drain, sight glass, and pressure indicator. [NFPA 99:5.1.3.6.3.6(3)]
- (4) Be of a capacity sufficient to prevent the compressor from short cycling. [NFPA 99:5.1.3.6.3.6(4), 5.3.7.6.2.1]

1314.2.1 Valves. Medical air receivers shall be provided with approved valves to allow the flow of compressed air to enter and exit out of separate receiver ports during normal operation and allow the receiver to be bypassed during service without shutting down the supply of medical air. [NFPA 99:5.1.3.6.3.10(D)]

1315.0 Medical Vacuum System.

1315.1 General. The vacuum plant shall be installed in a well-lit, ventilated, and clean location with accessibility. The location shall be provided with drainage facilities in accordance with this code. The vacuum plant, where

installed as a source, shall be located separately from other medical vacuum system sources, and shall be readily accessible for maintenance.

» **1315.2 Medical-Surgical Vacuum Sources.** Medical-surgical vacuum sources shall consist of the following:

- (1) Two or more vacuum pumps sufficient to serve the peak calculated demand with the largest single vacuum pump out of service.
- (2) An automatic means to prevent backflow from on-cycle vacuum pumps through off-cycle vacuum pumps.
- (3) A shutoff valve or other isolation means to isolate each vacuum pump from the centrally piped system and other vacuum pumps for maintenance or repair without loss of vacuum in the system.
- (4) A vacuum receiver.
- (5) Piping between the vacuum pump(s), discharge(s), receiver(s), and the vacuum source shutoff valve shall be in accordance with Section 1308.5, except that brass, galvanized, or black steel pipe shall be permitted to be used in accordance with the manufacturer's instructions.
- (6) Materials and devices used between the medical vacuum exhaust and the medical vacuum source shall be permitted to be of a design or construction appropriate for the service, as determined by the manufacturer's instructions. [NFPA 99:5.1.3.7.1.2]

» **1315.3 Vacuum Pumps.** Additional pumps shall automatically activate when the pump(s) in operation is incapable of maintaining the required vacuum. [NFPA 99:5.1.3.7.6.1]

Automatic or manual alternation of pumps shall allow division of operating time. Where automatic alternation of pumps is not provided, the facility staff shall arrange a schedule for manual alternation. [NFPA 99:5.1.3.7.6.2]

» **1315.4 Vacuum Receivers.** Receivers for vacuum shall meet the following requirements:

- (1) Be made of materials approved by the manufacturer.
- (2) Comply with Section VIII of the ASME Boiler and Pressure Vessel Code.
- (3) Withstand a gauge pressure of 60 psi (414 kPa) and 30 inch gauge HgV (102 kPa).
- (4) Be equipped with a manual drain.
- (5) Be of a capacity based on the technology of the pumps. [NFPA 99:5.1.3.7.3]

» **1315.5 Vacuum Source Exhausts.** Medical-surgical vacuum pumps shall exhaust in a manner and location that will minimize the hazards of noise and contamination to the facility and its environment. [NFPA 99:5.1.3.7.7.1]

1315.5.1 Location. The exhaust shall be located as follows:

- (1) Outdoors.
- (2) Not less than 10 feet (3048 mm) from a door, window, air intake, or other openings in buildings or places of public assembly.

(3) At a level different from air intakes.

(4) Where prevailing winds, adjacent buildings, topography, or other influences that will not divert the exhaust into occupied areas or prevent dispersion of the exhaust. [NFPA 99:5.1.3.7.7.2]

1315.5.2 Screening. The end of the exhaust shall be turned down and screened or otherwise be protected against the entry of vermin, debris, or precipitation by screening fabricated or composed of a noncorroding material. [NFPA 99:5.1.3.7.7.3]

1315.5.3 Dips and Loops. The exhaust shall be free of dips and loops that are capable of trapping condensate or oil, or provided with a drip leg and valved drain at the bottom of the low point. [NFPA 99:5.1.3.7.7.4]

1315.5.4 Multiple Pumps. Vacuum exhausts from multiple pumps shall be permitted to be joined together to one common exhaust where in accordance with the following [NFPA 99:5.1.3.7.7.5]:

- (1) The common exhaust is sized to minimize back-pressure in accordance with the pump manufacturer's instructions. [NFPA 99:5.1.3.7.7.5(1), 5.3.8.3.11(7)]
- (2) Each pump shall be isolated by manual or check valve, blind flange, or tube cap to prevent open exhaust piping where the pump(s) is removed for service and consequent flow of exhaust air into the room. [NFPA 99:5.1.3.7.7.5(2), 5.3.8.3.11(8)]

1316.0 Pressure-Regulating Equipment.

1316.1 Where Required. Pressure-regulating equipment shall be installed in the supply main upstream of the final line-pressure valve. Where multiple piping systems for the same gas at different operating pressures are required, separate pressure-regulating equipment, relief valves, and source shutoff valves shall be provided for each pressure.

1316.2 Pressure-Relief Valves. Pressure-relief valves shall close automatically where excess pressure has been released.

1316.2.1 Venting. Pressure-relief valves set at 50 percent shall be vented to the outside from gas systems, except medical air, or where the total capacity of the supply system is in excess of 3000 cubic feet (84.95 m³) of gas.

1316.2.2 Design. Pressure-relief valves shall be brass, bronze, or stainless steel and designed for the gas service. [NFPA 99:5.3.6.21.6]

1316.2.3 Isolation. A pressure-relief valve shall not be isolated from its intended use by a valve.

1316.3 Pressure Gauges. Pressure and vacuum indicators shall be readable from a standing position. Pressure and vacuum indicators shall be provided at the following locations:

- (1) Adjacent to the alarm-initiating device for source main-line pressure and vacuum alarms in the master alarm system.

- (2) At or in area alarm panels to indicate the pressure, vacuum, or both at the alarm activating device for each system that is monitored by the panel.
- (3) On the station outlet or inlet side of zone valves. [NFPA 99:5.1.8.2.1, 5.1.8.2.2]

» 1317.0 Station Outlets and Inlets.

- » **1317.1 General.** Station outlets and inlets shall be installed in strict accordance with the manufacturer's installation instructions. Each station outlet and inlet for medical gases and medical vacuums shall be gas-specific. [NFPA 99:5.1.5.1, 5.3.6.17.1]

1317.2 Required Valves. Each station outlet shall consist of a primary and secondary valve (or assembly). [NFPA 99:5.1.5.2, 5.3.6.17.2]

Each station inlet shall consist of a primary valve (or assembly). [NFPA 99:5.1.5.3]

1317.2.1 Secondary Valve. The secondary valve (or assembly) shall close automatically to stop the flow of medical gas (or medical vacuum, where provided) where the primary valve (or assembly) is removed. [NFPA 99:5.1.5.4, 5.3.6.17.3]

- » **1317.3 Post Installation.** After installation of the piping, but before installation of the station outlets and inlets and other medical gas and medical gas system components (e.g., pressure-actuating switches for alarms, manifolds, pressure gauges, or pressure relief valves), the line shall be blown clear by means of oil-free, dry nitrogen NF.

- » **1317.4 Identification.** Station outlets and inlets shall be identified as to the name or chemical symbol for the specific medical gas or medical vacuum provided. [NFPA 99:5.1.11.3.1]

» 1318.0 Warning Systems.

- » **1318.1 Category 1 and 2 Systems.** Master, area, and local alarm systems used for medical gas and medical vacuum systems shall include the following:

- (1) Separate visual indicators for each condition monitored, except as permitted for local alarms that are displayed on master alarm panels.
- (2) Visual indicators that remain in alarm until the situation that has caused the alarm is resolved.
- (3) A cancelable audible indication of each alarm condition that produces a sound level of not less than 80 decibels at 3 feet (914 mm).
- (4) A means to visually identify a lamp or LED failure.
- (5) Visual and audible indication that the communication with an alarm initiating device is disconnected.
- (6) Labeling of each indicator, indicating the condition monitored.
- (7) Labeling of each alarm panel for its area of surveillance.
- (8) Reinitiation of the audible signal where another alarm condition occurs while the audible alarm is silenced.

- (9) Power for master, area alarms, sensors, and switches from the life safety branch of the emergency electrical system as described in NFPA 99.
- (10) Power for local alarms, dew point sensors, and carbon monoxide sensors permitted to be from the same essential electrical branch as is used to power the air compressor system.
- (11) Where used for communications, wiring from switches or sensors that is supervised or protected as required by NFPA 70 for life safety and critical branch circuits in which protection is one of the following types:
 - (a) Conduit
 - (b) Free air
 - (c) Wire
 - (d) Cable tray
 - (e) Raceways
- (12) Communication devices that do not use electrical wiring for signal transmission shall be supervised such that failure of communication shall initiate an alarm.
- (13) Assurance by the responsible authority of the facility that the labeling of alarms, where room numbers or designations are used, is accurate and up-to-date.
- (14) Provisions for automatic restart after a power loss of 10 seconds (e.g., during generator startup) without giving false signals or requiring manual reset.
- (15) Alarm switches, sensors, or both installed so as to be removable. [NFPA 99:5.1.9.1]

1318.2 Category 3 Systems. Warning systems for medical gas systems (oxygen and nitrous oxide) in Category 3 facilities shall include the following:

- (1) Alarms for the following:
 - (a) Oxygen main line pressure low or high.
 - (b) Oxygen changeover to secondary bank or about to change over (where automatic).
 - (c) Nitrous oxide main line pressure low or high.
 - (d) Nitrous oxide changeover to secondary bank or about to changeover (where automatic).
- (2) Warning systems shall have not less than one single alarm panel in each treatment facility served by the medical gas source equipment.
- (3) Alarm panels shall be located in an area of continuous surveillance while the facility is in operation.
- (4) Pressure switches, sensors, or both that monitor main line pressure shall be mounted at the source equipment with pressure alarm indicators (lamp or LED) at the alarm panel.
- (5) Audible and noncancelable alarm visual signals shall indicate where the pressure in the main line increases or decreases 20 percent from the normal operating pressure.
- (6) Visual indications shall remain until the situation that caused the alarm is resolved.

- (7) Pressure switches, sensors, or both shall be installed downstream of emergency shutoff valves, and other shutoff valves in the system, and shall cause an alarm for the medical gas where the pressure decreases or increases 20 percent from the normal operating pressure.
- (8) A cancelable audible indication of each alarm condition that produces a sound at the alarm panel shall reinitiate the audible signal where another alarm condition occurs while the audible signal is silenced. [NFPA 99:5.3.6.22]

» **1318.3 Components.** Functioning of alarm components shall be verified in accordance with the testing and monitoring requirements of the manufacturer and the Authority Having Jurisdiction.

Part IV – Testing, Inspection, and Certification.

» 1319.0 Testing and Inspection.

» **1319.1 Where Required.** Inspection and testing shall be performed on components, or portions thereof, of new piped medical gas or vacuum systems, additions, renovations, temporary installations, or repaired systems in accordance with Section 1319.2 through Section 1319.12.2, and certified in accordance with Section 1320.0.

» **1319.2 Breached Systems.** Systems that are breached and components that are subject to additions, renovations, or replacement shall be inspected and tested. Systems shall be deemed breached at the point of pipeline intrusion by physical separation or by system component removal, replacement, or addition. Breached portions of the systems subject to inspection and testing shall be confined to the specific altered zone and components in the immediate zone or area that is located upstream for medical vacuum systems and downstream for pressure gases at the point or area of intrusion. [NFPA 99:5.1.12.1.3 – 5.1.12.1.5]

» **1319.3 Reports.** Inspection and testing reports shall be submitted directly to the party that contracted for the testing, who shall submit the report through channels to the responsible facility authority and others that are required. Reports shall contain detailed listings of findings and results. [NFPA 99:5.1.12.1.6, 5.1.12.1.7]

» **1319.4 Initial Piping Blow Down.** Piping in medical gas and medical vacuum distribution systems shall be blown clear by means of oil-free, dry nitrogen NF after installation of the distribution piping, and before installation of station outlet and inlet rough-in assemblies and other system components. [NFPA 99:5.1.12.2.2, 5.3.6.23.2.2]

» **1319.5 Initial Pressure Tests – Medical Gas and Medical Vacuum Systems.** Each section of the piping in medical gas and medical vacuum systems shall be pressure tested by a party qualified in accordance with Section 1306.1, and using oil-free, dry nitrogen NF. [NFPA 99:5.1.12.2.3.1, 5.3.6.23.2.3(A)]

Initial pressure tests shall be conducted in accordance with the following:

- (1) After blow down of the distribution piping.
- (2) After installation of station outlet and inlet rough-in assemblies. Test caps shall be permitted to be used.
- (3) Prior to the installation of components of the distribution piping system that would be damaged by the test pressure. [NFPA 99:5.1.12.2.3.2, 5.3.6.23.2.3(B)]

1319.5.1 Shutoff Valve. The source shutoff valve for the piping system shall remain closed during tests. [NFPA 99:5.1.12.2.3.3, 5.3.6.23.2.3(C)]

1319.5.2 Required Test Pressure. The test pressure for pressure medical gases and medical vacuum systems shall be one and one-half times the system working pressure, and not less than a gauge pressure of 150 psi (1034 kPa). [NFPA 99:5.1.12.2.3.4, 5.3.6.23.2.3(D)] The test pressure shall be maintained until each joint has been examined for leakage by means of a leak detectant that is safe for use with oxygen and does not contain ammonia. [NFPA 99:5.1.12.2.3.5, 5.3.6.23.2.3(E)]

1319.5.3 Leaks. Leaks shall be located, repaired (where permitted), replaced (where required), and retested. [NFPA 99:5.1.12.2.3.6, 5.3.6.23.2.3(F)]

1319.6 Cross-Connection Tests – Medical Gas and Medical Vacuum Systems. A party qualified in accordance with Section 1306.1 shall determine that no cross-connections exist between medical gas and medical vacuum piping systems. [NFPA 99:5.1.12.2.4, 5.3.6.23.2.4]

1319.6.1 Atmospheric Pressure. Piping systems shall be reduced to atmospheric pressure. [NFPA 99:5.1.12.2.4.1, 5.3.6.23.2.4(A)]

1319.6.2 Sources of Test Gas. Sources of test gas shall be disconnected from piping systems except for the one system being tested. [NFPA 99:5.1.12.2.4.2, 5.3.6.23.2.4(D)]

1319.6.3 System to be Charged. The system under test shall be charged with oil-free, dry nitrogen NF to a gauge pressure of 50 psi (345 kPa). [NFPA 99:5.1.12.2.4.3, 5.3.6.23.2.4(C), 5.3.6.23.2.4(E)]

1319.6.4 Check Outlets and Inlets. After the installation of the individual faceplates with approved adapters matching outlet and inlet labels, each individual outlet and inlet (in each installed medical gas and medical vacuum piping system) shall be checked to determine that the test gas is being dispensed from the piping system being tested. [NFPA 99:5.1.12.2.4.4, 5.3.6.23.2.4(F)]

1319.6.5 Repeat Test. The cross-connection test shall be repeated for each installed medical gas and medical vacuum piping system. [NFPA 99:5.1.12.2.4.5, 5.3.6.23.2.4(G)]

1319.6.6 Identification of System. The proper labeling and identification of system outlets and inlets shall be confirmed during these tests. [NFPA 99:5.1.12.2.4.6, 5.3.6.23.2.4(H)]

» **1319.7 Standing Pressure Tests – Medical Gas Piping Systems.** After successful completion of the initial pressure tests in accordance with Section 1319.5, medical gas distribution piping shall be subjected to a standing pressure test by a party qualified in accordance with Section 1306.1. [NFPA 99:5.1.12.2.6, 5.3.6.23.2.6]

1319.7.1 Time Frame for Testing. Tests shall be conducted after the final installation of station outlet valve bodies, face plates, and other distribution system components. [NFPA 99:5.1.12.2.6.1, 5.3.6.23.2.6(A)]

1319.7.2 Source Valve. The source valve shall be closed during testing. [NFPA 99:5.1.12.2.6.2, 5.3.6.23.2.6(B)]

1319.7.3 Length of Testing. The piping systems shall be subjected to a 24 hour standing pressure test using oil-free, dry nitrogen NF. [NFPA 99:5.1.12.2.6.3, 5.3.6.23.2.6(C)]

1319.7.4 Test Pressure. Test pressures shall be 20 percent above the normal system operating line pressure. [NFPA 99:5.1.12.2.6.4, 5.3.6.23.2.6(D)]

1319.7.5 Conclusion of Test. At the conclusion of the tests, there shall not be a change in the test pressure except that attributed to changes in ambient temperature. [NFPA 99:5.1.12.2.6.5]

For Category 3 systems, there shall not be a change in the test pressure that exceeds a gauge pressure of 5 psi (34 kPa). [NFPA 99:5.3.6.23.2.6(E)]

1319.7.6 Leaks. Leaks shall be located, repaired (where permitted), or replaced (where required), and retested. [NFPA 99:5.1.12.2.6.6, 5.3.6.23.2.6(F)]

1319.7.7 Proof of Testing. The 24 hour standing pressure test shall be witnessed by the Authority Having Jurisdiction or its designee. A form indicating that this test has been performed and witnessed shall be provided to the verifier at the start of the tests required in Section 1319.12. [NFPA 99:5.1.12.2.6.7]

» **1319.8 Standing Pressure Tests – Medical Vacuum Piping Systems.** After successful completion of the initial pressure tests under Section 1319.5, medical vacuum distribution piping shall be subjected to a standing vacuum test. [NFPA 99:5.1.12.2.7]

1319.8.1 Timeframe for Testing. Tests shall be conducted after installation of all components of the medical vacuum system. [NFPA 99:5.1.12.2.7.1]

1319.8.2 Length of Testing. The piping systems shall be subjected to a 24 hour standing vacuum test. [NFPA 99:5.1.12.2.7.2]

1319.8.3 Test Pressure. Test pressure shall be between 12 inch gauge HgV (41 kPa) and full vacuum. [NFPA 99:5.1.12.2.7.3]

1319.8.4 Disconnection of Testing Source. During the test, the source of test vacuum shall be disconnected from the piping system. [NFPA 99:5.1.12.2.7.4]

1319.8.5 Conclusion of Test. At the conclusion of the test, there shall not be a change in the vacuum except that attributed to changes in ambient temperature. [NFPA 99:5.1.12.2.7.5]

1319.8.6 Leaks. Leaks shall be located, repaired (where permitted), or replaced (where required), and retested. [NFPA 99:5.1.12.2.7.7]

1319.8.7 Proof of Testing. The 24 hour standing pressure test of the medical vacuum system shall be witnessed by the Authority Having Jurisdiction or its designee. A form indicating that this test has been performed and witnessed shall be provided to the verifier at the start of the tests required in Section 1319.12. [NFPA 99:5.1.12.2.7.6]

1319.9 Purge Tests. The outlets in each medical gas piping system shall be purged by a party qualified in accordance with Section 1306.1, using oil-free, dry nitrogen NF to remove particulate matter from the piping. [NFPA 99:5.1.12.2.5, 5.3.6.23.2.5]

1319.9.1 Procedure. Using appropriate adapters, each outlet shall be purged with an intermittent high-volume flow of test gas until the purge produces no discoloration in a clean white cloth. [NFPA 99:5.1.12.2.5.1, 5.3.6.23.2.5(B)]

1319.9.2 Location. Purging shall start at the closest outlet or inlet to the zone valve and continue to the furthest outlet or inlet within the zone. [NFPA 99:5.1.12.2.5.2]

Exception: For Category 3 medical gas piping systems, purging shall start at the furthest outlet in the system and proceed toward the source equipment. [NFPA 99:5.3.6.23.2.5(C)]

1319.10 Operational Pressure Test. Operational pressure tests shall be performed at each station outlet and inlet or terminal where the user makes connections and disconnections. [NFPA 99:5.1.12.3.10]

1319.10.1 Test Gas. Tests shall be performed with the gas of system designation or the operating vacuum. [NFPA 99:5.1.12.3.10.1]

1319.10.2 Medical Gas Outlets. Gas outlets with a gauge pressure of 50 psi (345 kPa), including, but not limited to, oxygen, nitrous oxide, medical air, and carbon dioxide, shall deliver 3.5 standard cubic feet per minute (SCFM) (100 SLPM) with a pressure drop of not more than 5 psi (34 kPa) and static pressure of 50 psi (345 kPa) to 55 psi (379 kPa). [NFPA 99:5.1.12.3.10.2]

1319.10.3 Medical-Surgical Vacuum Inlets. Medical-surgical vacuum inlets shall draw 3 SCFM (85 NL/min) without reducing the vacuum pressure below 12 inch mercury gauge (HgV) (41 kPa) at any adjacent station inlet. [NFPA 99:5.1.12.3.10.4]

1319.10.4 Oxygen and Medical Air Outlets. Oxygen and medical air outlets serving critical care areas shall allow a transient flow rate of 6 SCFM (170 SLPM) for 3 seconds. [NFPA 99:5.1.12.3.10.5]

1319.11 Medical Gas Concentration Test. After purging each system in accordance with Section 1319.9, the following shall be performed:

- (1) Each pressure gas source and outlet shall be analyzed for concentration of gas, by volume.
- (2) Analysis shall be conducted with instruments designed to measure the specific gas dispensed.
- (3) Allowable concentrations shall be as indicated in Table 1319.11. [NFPA 99:5.1.12.3.11]

**TABLE 1319.11
GAS CONCENTRATIONS
[NFPA 99:5.1.12.3.11]**

| MEDICAL GAS | CONCENTRATION |
|---------------|---|
| Oxygen | >99% oxygen |
| Nitrous oxide | >99% nitrous oxide |
| Nitrogen | <1% oxygen or >99% nitrogen |
| Medical air | 19.5% - 23.5% oxygen |
| Other gases | As specified by +/-1%, unless otherwise specified |

- (3) Checking for identification and labeling of pipelines, station outlets, and control valves.
- (4) Testing for cross-connection, flow rate, system pressure drop, and system performance.
- (5) Functional testing of pressure relief valves and safety valves.
- (6) Functional testing of sources of supply.
- (7) Functional testing of alarm systems, including accuracy of system components.
- (8) Purge flushing of system and filling with specific source gases.
- (9) Testing for purity and cleanliness of source gases.
- (10) Testing for specific gas identity at each station outlet.

1320.3 Report Items. A report that includes the specific items addressed in Section 1320.2, and other information required by this chapter, shall be delivered to the Authority Having Jurisdiction prior to acceptance of the system. ←

» **1319.12 System Verification.** Verification tests shall be performed after tests in accordance with Section 1319.5 through Section 1319.11 have been completed. [NFPA 99:5.1.12.3.1.1, 5.3.6.23.3.1(C)]

1319.12.1 Test Gas. The test gas shall be oil-free, dry nitrogen NF or the system gas where permitted. [NFPA 99:5.1.12.3.1.2, 5.3.6.23.3.1(D)]

1319.12.2 Approved Tester. Verification testing shall be conducted by a party technically competent and experienced in the field of medical gas and medical vacuum pipeline testing and meeting the requirements of ASSE 6030. [NFPA 99:5.1.12.3.1.3, 5.3.6.23.3.1(A)]

Testing shall be performed by a party other than the installing contractor, the system supplier, or the system manufacturer. [NFPA 99:5.1.12.3.1.4, 5.3.6.23.3.1(B)]

Where systems have not been installed by in-house personnel, testing shall be permitted by personnel of that organization who meet the requirements of this section. [NFPA 99:5.1.12.3.1.5]

» **1320.0 System Certification.**

» **1320.1 Certification.** Prior to a medical gas or medical vacuum system being placed in service, such system shall be certified in accordance with Section 1320.2.

» **1320.2 Certification Tests.** Certification tests, verified and attested to by the certification agency, shall include the following:

- (1) Verifying in accordance with the installation requirements.
- (2) Testing and checking for leakage, correct zoning, and identification of control valves.

CHAPTER 14

FIRESTOP PROTECTION

»» 1401.0 General.

»» 1401.1 **Applicability.** Piping penetrations of required fire-resistance-rated walls, partitions, floors, floor/ceiling assemblies, roof/ceiling assemblies, or shaft enclosures shall be protected in accordance with the requirements of the building code, and this chapter.

»» 1402.0 Construction Documents.

»» 1402.1 **Penetrations.** Construction documents shall indicate with sufficient detail how penetrations of fire-resistance-rated assemblies shall be firestopped prior to obtaining design approval.

»» 1403.0 Installation.

»» 1403.1 **Materials.** Firestop systems shall be installed in accordance with this chapter, the building code, and the manufacturer's installation instructions.

»» 1404.0 Combustible Piping Installations.

»» 1404.1 **General Requirements.** Combustible piping installations shall be protected in accordance with the appropriate fire resistance rating requirements in the building code that list the acceptable area, height, and type of construction for use in specific occupancies to assure compliance and integrity of the fire resistance rating prescribed.

»» 1404.2 **Fire-Resistance Rating.** Where penetrating a fire-resistance-rated wall, partition, floor, floor-ceiling assembly, roof-ceiling assembly, or shaft enclosure, the fire resistance rating of the assembly shall be restored to its original rating.

»» 1404.3 **Firestop Systems.** Penetrations shall be protected by an approved penetration firestop system installed as tested in accordance with ASTM E119, ASTM E814, UL 263, or UL 1479 with a positive pressure differential of not less than 0.01 of an inch of water (0.002 kPa). Systems shall have an F rating of not less than 1 hour but not less than the required fire resistance rating of the assembly being penetrated. Systems protecting floor penetrations shall have a T rating of not less than 1 hour but not less than the required fire resistance rating of the floor being penetrated. Floor penetrations contained within the cavity of a wall at the location of the floor penetration do not require a T rating. No T rating shall be required for floor penetrations by piping that is not in direct contact with combustible material.

»» 1404.4 **Connections.** Where piping penetrates a rated assembly, combustible piping shall not connect to non-combustible piping unless it is capable of being demonstrated that the transition is in accordance with Section 1404.3.

1404.5 **Insulation and Coverings.** Insulation and coverings on or in the penetrating item shall not be permitted unless the specific insulating or covering material has been tested as part of the penetrating firestop system.

1404.6 **Sleeves.** Where sleeves are used, the sleeves shall be securely fastened to the fire-resistance-rated assembly. The (inside) annular space between the sleeve and the penetrating item and the (outside) annular space between the sleeve and the fire-resistance-rated assembly shall be firestopped in accordance with this chapter.

1405.0 Noncombustible Piping Installations.

1405.1 **General Requirements.** Noncombustible piping installations shall be protected in accordance with the appropriate fire resistance rating requirements in the building code that list the acceptable area, height, and type of construction for use in specific occupancies to ensure compliance and integrity of the fire-resistance rating prescribed.

1405.2 **Fire-Resistance Rating.** Where penetrating a fire-resistance-rated wall, partition, floor, floor-ceiling assembly, roof-ceiling assembly, or shaft enclosure, the fire-resistance rating of the assembly shall be restored to its original rating.

Exceptions:

- (1) Concrete, mortar, or grout shall be permitted to be used to fill the annular spaces around cast-iron, copper, copper alloy, or steel piping that penetrates concrete or masonry fire-resistant-rated assemblies. The nominal diameter of the penetrating item shall not exceed 6 inches (150 mm), and the opening size shall not exceed 144 square inches (0.093 m²).

The thickness of concrete, mortar, or grout shall be the full thickness of the assembly or the thickness necessary to provide a fire-resistance rating not less than the required fire-resistance rating of the assembly penetrated.

- (2) The material used to fill the annular space shall prevent the passage of flame and hot gases capable of igniting cotton waste for the time period equivalent to the fire-resistance rating of the assembly, where tested to standard(s) referenced in Section 1405.3.

1405.3 **Firestop Systems.** Penetrations shall be protected by an approved penetration firestop system installed as tested in accordance with ASTM E119, ASTM E814, UL 263, or UL 1479 with a positive pressure differential of not less than 0.01 of an inch of water (0.002 kPa). Systems shall have an F rating of not less than 1 hour but not less than the required fire-resistance rating of the assembly being penetrated. Systems protecting floor penetrations shall have a T rating of not less than 1 hour but not

FIRESTOP PROTECTION

less than the required fire-resistance rating of the floor being penetrated. Floor penetrations contained within the cavity of a wall at the location of the floor penetration do not require a T rating. No T rating shall be required for floor penetrations by piping that is not in direct contact with combustible material.

- » **1405.4 Connections.** Where piping penetrates a rated assembly, combustible piping shall not connect to noncombustible piping unless it is capable of being demonstrated that the transition is in accordance with the requirements of Section 1405.3.
- » **1405.5 Unshielded Couplings.** Unshielded couplings shall not be used to connect noncombustible piping unless it is capable of being demonstrated that the fire-resistive integrity of the penetration is maintained.
- » **1405.6 Sleeves.** Where sleeves are used, the sleeves shall be securely fastened to the fire-resistance-rated assembly. The (inside) annular space between the sleeve and the penetrating item and the (outside) annular space between the sleeve and the fire-resistance-rated assembly shall be firestopped in accordance with this chapter.
- » **1405.7 Insulation and Coverings.** Insulation and coverings on or in the penetrating item shall not be permitted unless the specific insulating or covering material has been tested as part of the penetrating firestop system.
- » **1406.0 Required Inspection.**
- » **1406.1 General.** Prior to being concealed, piping penetrations shall be inspected by the Authority Having Jurisdiction to verify compliance with the fire-resistance rating prescribed in the building code.
- » **1406.2 Examination.** The Authority Having Jurisdiction shall conduct a thorough examination of sufficient representative installations, including destructive inspection, to provide verification of satisfactory compliance with this chapter, the appropriate manufacturer's installation instructions applied by the installer, construction documents, specifications, and applicable manufacturer's product information.
- » **1406.3 Penetrations.** The Authority Having Jurisdiction shall determine the type, size, and quantity of penetrations to be inspected.
- » **1406.4 Field Installations.** The Authority Having Jurisdiction shall compare the field installations with the documentation supplied by the installer to determine the following:
 - (1) The required F ratings (1 hour, 2 hour, 3 hour, or 4 hour) and T ratings (0 hour, 1 hour, 2 hour, 3 hour, or 4 hour) of the penetration firestop systems are at least the same as the hourly rating of the assembly being penetrated.
 - (2) The penetrating firestop system includes the penetrating item as documented through testing of the systems conducted by an independent testing agency.
 - (3) The penetrating firestop system is installed as tested.

CHAPTER 15

ALTERNATE WATER SOURCES FOR NONPOTABLE APPLICATIONS

» 1501.0 General.

» 1501.1 **Applicability.** The provisions of this chapter shall apply to the construction, alteration, and repair of alternate water source systems for nonpotable applications.

» 1501.1.1 **Allowable Use of Alternate Water.** Where approved or required by the Authority Having Jurisdiction, alternate water sources [reclaimed (recycled) water, gray water, and on-site treated nonpotable water] shall be permitted to be used in lieu of potable water for the applications identified in this chapter.

» 1501.2 **System Design.** Alternate water source systems shall be designed in accordance with this chapter by a registered design professional or who demonstrates competency to design the alternate water source system as required by the Authority Having Jurisdiction. Components, piping, and fittings used in an alternate water source system shall be listed.

→ Exceptions:

- (1) A registered design professional is not required to design gray water systems having a maximum discharge capacity of 250 gallons per day (gal/d) (0.011 L/s) for single family and multi-family dwellings.
- (2) A registered design professional is not required to design an on-site treated nonpotable water system for single family dwellings having a maximum discharge capacity of 250 gal/d (0.011 L/s).

» 1501.3 **Permit.** It shall be unlawful for a person to construct, install, alter, or cause to be constructed, installed, or altered an alternate water source system in a building or on a premise without first obtaining a permit to do such work from the Authority Having Jurisdiction.

» 1501.4 **Component Identification.** System components shall be properly identified as to the manufacturer.

» 1501.5 **Maintenance and Inspection.** Alternate water source systems and components shall be inspected and maintained in accordance with Section 1501.5.1 through Section 1501.5.3.

» 1501.5.1 **Frequency.** Alternate water source systems and components shall be inspected and maintained in accordance with Table 1501.5 unless more frequent inspection and maintenance is required by the manufacturer.

» 1501.5.2 **Maintenance Log.** A maintenance log for gray water and on-site treated nonpotable water systems is required to have a permit in accordance with Section 1501.3 and shall be maintained by the property owner and be available for inspection. The property owner or designated appointee shall ensure that a record of testing, inspection and maintenance in accordance with Table 1501.5 is maintained in the log. The log will indicate the frequency of inspection and maintenance for each system.

1501.5.3 **Maintenance Responsibility.** The required maintenance and inspection of alternate water source systems shall be the responsibility of the property owner, unless otherwise required by the Authority Having Jurisdiction.

1501.6 **Operation and Maintenance Manual.** An operation and maintenance manual for gray water and on-site treated water systems required to have a permit in accordance with Section 1501.3 shall be supplied to the building owner by the system designer. The operating and maintenance manual shall include the following:

- (1) Detailed diagram of the entire system and the location of system components.
- (2) Instructions on operating and maintaining the system.
- (3) Details on maintaining the required water quality as determined by the Authority Having Jurisdiction.
- (4) Details on deactivating the system for maintenance, repair, or other purposes.
- (5) Applicable testing, inspection, and maintenance frequencies in accordance with Table 1501.5.
- (6) A method of contacting the manufacturer(s).

1501.7 **Minimum Water Quality Requirements.** The minimum water quality for alternate water source systems shall meet the applicable water quality requirements for the intended application as determined by the Authority Having Jurisdiction. In the absence of water quality requirements, the EPA/625/R-04/108 contains recommended water reuse guidelines to assist regulatory agencies develop, revise, or expand alternate water source water quality standards.

Exception: Water treatment is not required for gray water used for subsurface irrigation.

1501.8 **Material Compatibility.** Alternate water source systems shall be constructed of materials that are compatible with the type of pipe and fitting materials, water treatment, and water conditions in the system.

1501.9 **System Controls.** Controls for pumps, valves, and other devices that contain mercury that come in contact with alternate water source water supply shall not be permitted.

1501.10 **Commercial, Industrial, and Institutional Restroom Signs.** A sign shall be installed in restrooms in commercial, industrial, and institutional occupancies using reclaimed (recycled) water and on-site treated water, for water closets, urinals, or both. Each sign shall contain ½ of an inch (12.7 mm) letters of a highly visible color on a contrasting background. The location of the sign(s) shall be such that the sign(s) are visible to users. The location of the sign(s) shall be approved by the Authority Having Jurisdiction and shall contain the following text:

TO CONSERVE WATER, THIS BUILDING USES
* _____ * TO FLUSH TOILETS AND URINALS.

TABLE 1501.5
MINIMUM ALTERNATE WATER SOURCE TESTING, INSPECTION, AND MAINTENANCE FREQUENCY

| DESCRIPTION | MINIMUM FREQUENCY |
|--|--|
| Inspect and clean filters and screens, and replace (where necessary). | Every 3 months |
| Inspect and verify that disinfection, filters and water quality treatment devices and systems are operational and maintaining minimum water quality requirements as determined by the Authority Having Jurisdiction. | In accordance with manufacturer's instructions, and the Authority Having Jurisdiction. |
| Inspect pumps and verify operation. | After initial installation and every 12 months thereafter |
| Inspect valves and verify operation. | After initial installation and every 12 months thereafter |
| Inspect pressure tanks and verify operation. | After initial installation and every 12 months thereafter |
| Clear debris from and inspect storage tanks, locking devices, and verify operation. | After initial installation and every 12 months thereafter |
| Inspect caution labels and marking. | After initial installation and every 12 months thereafter |
| Inspect and maintain mulch basins for gray water irrigation systems. | As needed to maintain mulch depth and prevent ponding and runoff. |
| Cross-connection inspection and test* | After initial installation and every 12 months thereafter |

* The cross-connection test shall be performed in the presence of the Authority Having Jurisdiction in accordance with the requirements of this chapter.

1501.10.1 Equipment Room Signs. Each room containing reclaimed (recycled) water and on-site treated water equipment shall have a sign posted in a location that is visible to anyone working on or near nonpotable water equipment with the following wording in 1 inch (25.4 mm) letters:

CAUTION: NONPOTABLE * _____ *, DO NOT DRINK. DO NOT CONNECT TO DRINKING WATER SYSTEM. NOTICE: CONTACT BUILDING MANAGEMENT BEFORE PERFORMING ANY WORK ON THIS WATER SYSTEM.

* _____ *Shall indicate RECLAIMED (RECYCLED) WATER or ON-SITE TREATED WATER, accordingly.

1501.11 Inspection and Testing. Alternate water source systems shall be inspected and tested in accordance with Section 1501.11.1 and Section 1501.11.2.

1501.11.1 Supply System Inspection and Test. Alternate water source systems shall be inspected and tested in accordance with this code for testing of potable water piping.

1501.11.2 Annual Cross-Connection Inspection and Testing. An initial and subsequent annual inspection and test shall be performed on both the potable and alternate water source systems. The potable and alternate water source system shall be isolated from each other and independently inspected and tested to ensure there is no cross-connection in accordance with Section 1501.11.2.1 through Section 1501.11.2.4.

1501.11.2.1 Visual System Inspection. Prior to commencing the cross-connection testing, a

dual system inspection shall be conducted by the Authority Having Jurisdiction and other authorities having jurisdiction as follows:

- (1) Meter locations of the alternate water source and potable water lines shall be checked to verify that no modifications were made, and that no cross-connections are visible.
- (2) Pumps and equipment, equipment room signs, and exposed piping in equipment room shall be checked.
- (3) Valves shall be checked to ensure that the valve lock seals are still in place and intact. Valve control door signs shall be checked to verify that no signs have been removed.

1501.11.2.2 Cross-Connection Test. The procedure for determining cross-connection shall be followed by the applicant in the presence of the Authority Having Jurisdiction and other authorities having jurisdiction to determine whether a cross-connection has occurred as follows:

- (1) The potable water system shall be activated and pressurized. The alternate water source system shall be shut down, depressurized, and drained.
- (2) The potable water system shall remain pressurized for a minimum period of time specified by the Authority Having Jurisdiction while the alternate water source system is empty. The minimum period the alternate water source system is to remain depressurized shall be determined on a case-by-case basis, taking into account the size and complexity of the potable and the alternate water source distribution systems, but in no case shall that period be less than 1 hour.

- (3) The drain on the alternate water source system shall be checked for flow during the test and fixtures, potable and alternate water source, shall be tested and inspected for flow. Flow from an alternate water source system outlet indicates a cross-connection. No flow from a potable water outlet shall indicate that it is connected to the alternate water source system.
- (4) The potable water system shall then be depressurized and drained.
- (5) The alternate water source system shall then be activated and pressurized.
- (6) The alternate water source system shall remain pressurized for a minimum period of time specified by the Authority Having Jurisdiction while the potable water system is empty. The minimum period the potable water system is to remain depressurized shall be determined on a case-by-case basis, but in no case shall that period be less than 1 hour.
- (7) Fixtures, potable and alternate water source, shall be tested and inspected for flow. Flow from a potable water system outlet indicates a cross-connection. No flow from an alternate water source outlet will indicate that it is connected to the potable water system.
- (8) The drain on the potable water system shall be checked for flow during the test and at the end of the test.
- (9) Where there is no flow detected in the fixtures which would indicate a cross-connection, the potable water system shall be repressurized.

1501.11.2.3 Discovery of Cross-Connection. In the event that a cross-connection is discovered, the following procedure, in the presence of the Authority Having Jurisdiction, shall be activated immediately:

- (1) The alternate water source piping to the building shall be shut down at the meter, and the alternate water source riser shall be drained.
- (2) Potable water piping to the building shall be shut down at the meter.
- (3) The cross-connection shall be uncovered and disconnected.
- (4) The building shall be retested in accordance with Section 1501.11.2.1 and Section 1501.11.2.2.
- (5) The potable water system shall be chlorinated with 50 parts-per-million (ppm) chlorine for 24 hours.
- (6) The potable water system shall be flushed after 24 hours, and a standard bacteriological test shall be performed. Where test results are acceptable, the potable water system shall be permitted to be recharged.

1501.11.2.4 Annual Inspection. An annual inspection of the alternate water source system, following the procedures listed in Section 1501.11.2.1 shall be required. Annual cross-connection testing, following the procedures listed in Section 1501.11.2.2 shall be required by the Authority Having Jurisdiction, unless site conditions do not require it. In no event shall the test occur less than once in 4 years. Alternate testing requirements shall be permitted by the Authority Having Jurisdiction.

1501.12 Separation Requirements. Underground alternate water source service piping other than gray water shall be separated from the building sewer in accordance with this code. Treated nonpotable water pipes shall be permitted to be run or laid in the same trench as potable water pipes with a 12 inch (305 mm) minimum vertical and horizontal separation where both pipe materials are approved for use within a building. Where horizontal piping materials do not comply with this requirement the minimum separation shall be increased to 60 inches (1524 mm). The potable water piping shall be installed at an elevation above the treated nonpotable water piping.

1501.13 Abandonment. Alternate water source systems that are no longer in use or fail to be maintained in accordance with Section 1501.5 shall be abandoned. Abandonment shall comply with Section 1501.13.1 and Section 1501.13.2.

1501.13.1 General. An abandoned system or part thereof covered under the scope of this chapter shall be disconnected from remaining systems, drained, plugged, and capped in an approved manner.

1501.13.2 Underground Tank. An underground water storage tank that has been abandoned or otherwise discontinued from use in a system covered under the scope of this chapter shall be completely drained and filled with earth, sand, gravel, concrete, or other approved material or removed in a manner satisfactory to the Authority Having Jurisdiction.

1501.14 Sizing. Unless otherwise provided for in this chapter, alternate water source piping shall be sized in accordance with Chapter 6 for sizing potable water piping.

1502.0 Gray Water Systems. <<

1502.1 General. The provisions of this section shall apply to the construction, alteration, and repair of gray water systems. <<

1502.2 System Requirements. Gray water shall be permitted to be diverted away from a sewer or private sewage disposal system, and discharge to a subsurface irrigation or subsoil irrigation system. The gray water shall be permitted to discharge to a mulch basin for single family and multi-family dwellings. Gray water shall not be used to irrigate root crops or food crops intended for human consumption that come in contact with soil. <<

1502.2.1 Surge Capacity. Gray water systems shall be designed to have the capacity to accommodate peak <<

ALTERNATE WATER SOURCES FOR NON-POTABLE APPLICATIONS

flow rates and distribute the total amount of estimated gray water on a daily basis to a subsurface irrigation field, subsoil irrigation field, or mulch basin without surfacing, ponding, or runoff. A surge tank is required for systems that are unable to accommodate peak flow rates and distribute the total amount of gray water by gravity drainage. The water discharge for gray water systems shall be determined in accordance with Section 1502.8.1 or Section 1502.8.2.

» **1502.2.2 Diversion.** The gray water system shall connect to the sanitary drainage system downstream of fixture traps and vent connections through an approved gray water diverter valve. The gray water diverter valve shall be installed in an accessible location and clearly indicate the direction of flow.

» **1502.2.3 Backwater Valves.** Gray water drains subject to backflow shall be provided with a backwater valve so located as to be accessible for inspection and maintenance.

» **1502.3 Connections to Potable and Reclaimed (Recycled) Water Systems.** Gray water systems shall have no direct connection to a potable water supply, on-site treated nonpotable water supply, or reclaimed (recycled) water systems. Potable, on-site treated nonpotable, or reclaimed (recycled) water is permitted to be used as makeup water for a non-pressurized storage tank provided

the connection is protected by an air gap in accordance with this code.

« **1502.4 Location.** No gray water system or part thereof shall be located on a lot other than the lot that is the site of the building or structure that discharges the gray water, nor shall a gray water system or part thereof be located at a point having less than the minimum distances indicated in Table 1502.4.

« **1502.5 Plot Plan Submission.** No permit for a gray water system shall be issued until a plot plan with data satisfactory to the Authority Having Jurisdiction has been submitted and approved.

« **1502.6 Prohibited Location.** Where there is insufficient lot area or inappropriate soil conditions for adequate absorption to prevent the ponding, surfacing, or runoff of the gray water, as determined by the Authority Having Jurisdiction, no gray water system shall be permitted. A gray water system is not permitted on a property in a geologically sensitive area as determined by the Authority Having Jurisdiction.

« **1502.7 Drawings and Specifications.** The Authority Having Jurisdiction shall require the following information to be included with or in the plot plan before a permit is issued for a gray water system, or at a time during the construction thereof:

TABLE 1502.4
LOCATION OF GRAY WATER SYSTEM⁷

| MINIMUM HORIZONTAL DISTANCE IN CLEAR REQUIRED FROM | SURGE TANK (feet) | SUBSURFACE AND SUBSOIL IRRIGATION FIELD AND MULCH BED (feet) |
|--|-------------------|--|
| Building structures ¹ | 5 ^{2, 9} | 2 ^{3, 8} |
| Property line adjoining private property | 5 | 5 ⁸ |
| Water supply wells ⁴ | 50 | 100 |
| Streams and lakes ⁴ | 50 | 50 ⁵ |
| Sewage pits or cesspools | 5 | 5 |
| Sewage disposal field ¹⁰ | 5 | 4 ⁶ |
| Septic tank | 0 | 5 |
| On-site domestic water service line | 5 | 5 |
| Pressurized public water main | 10 | 10 ⁷ |

For SI units: 1 foot = 304.8 mm

Notes:

¹ Including porches and steps, whether covered or uncovered, breezeways, roofed carports, roofed patios, carports, covered walks, covered driveways, and similar structures or appurtenances.

² The distance shall be permitted to be reduced to 0 feet for aboveground tanks where first approved by the Authority Having Jurisdiction.

³ Reference to a 45 degree (0.79 rad) angle from foundation.

⁴ Where special hazards are involved, the distance required shall be increased as directed by the Authority Having Jurisdiction.

⁵ These minimum clear horizontal distances shall apply between the irrigation or disposal field and the ocean mean higher high tide line.

⁶ Add 2 feet (610 mm) for each additional foot of depth in excess of 1 foot (305 mm) below the bottom of the drain line.

⁷ For parallel construction or for crossings, approval by the Authority Having Jurisdiction shall be required.

⁸ The distance shall be permitted to be reduced to 1½ feet (457 mm) for drip and mulch basin irrigation systems.

⁹ The distance shall be permitted to be reduced to 0 feet for surge tanks of 75 gallons (284 L) or less.

¹⁰ Where irrigation or disposal fields are installed in sloping ground, the minimum horizontal distance between a part of the distribution system and the ground surface shall be 15 feet (4572 mm).

- (1) Plot plan drawn to scale and completely dimensioned, showing lot lines and structures, direction and approximate slope of surface, location of present or proposed retaining walls, drainage channels, water supply lines, wells, paved areas and structures on the plot, number of bedrooms and plumbing fixtures in each structure, location of private sewage disposal system and expansion area or building sewer connecting to the public sewer, and location of the proposed gray water system.
- (2) Details of construction necessary to ensure compliance with the requirements of this chapter, together with a full description of the complete installation, including installation methods, construction, and materials in accordance with the Authority Having Jurisdiction.
- (3) Details for holding tanks shall include dimensions, structural calculations, bracings, and such other pertinent data as required.
- (4) A log of soil formations and groundwater level as determined by test holes dug in proximity to proposed irrigation area, together with a statement of water absorption characteristics of the soil at the proposed site as determined by approved percolation tests.
Exception: The Authority Having Jurisdiction shall permit the use of Table 1502.10 in lieu of percolation tests.
- (5) Distance between the plot and surface waters such as lakes, ponds, rivers or streams, and the slope between the plot and the surface water, where in close proximity.

» **1502.8 Procedure for Estimating Gray Water Discharge.** Gray water systems shall be designed to distribute the total amount of estimated gray water on a daily basis. The water discharge for gray water systems shall be determined in accordance with Section 1502.8.1 or Section 1502.8.2.

» **1502.8.1 Single Family Dwellings and Multi-Family Dwellings.** The gray water discharge for single family and multi-family dwellings shall be calculated by water use records, calculations of local daily per person interior water use, or the following procedure:

- (1) The number of occupants of each dwelling unit shall be calculated as follows:

| | |
|-------------------------|-------------|
| First Bedroom | 2 occupants |
| Each additional bedroom | 1 occupant |
- (2) The estimated gray water flows of each occupant shall be calculated as follows:

| | |
|-----------------------------------|------------------------------------|
| Showers, bathtubs, and lavatories | 25 gallons (95 L) per day/occupant |
| Laundry | 15 gallons (57 L) per day/occupant |
- (3) The total number of occupants shall be multiplied by the applicable estimated gray water discharge as provided above and the type of fixtures connected to the gray water system.

1502.8.2 Commercial, Industrial, and Institutional Occupancies. The gray water discharge for commercial, industrial, and institutional occupancies shall be calculated by utilizing the procedure in Section 1502.8.1, water use records, or other documentation to estimate gray water discharge.

1502.9 Gray Water System Components. Gray water system components shall comply with Section 1502.9.1 through Section 1502.9.7.

1502.9.1 Surge Tanks. Where installed, surge tanks shall be in accordance with the following:

- (1) Surge tanks shall be constructed of solid, durable materials not subject to excessive corrosion or decay and shall be watertight. Surge tanks constructed of steel shall be approved by the Authority Having Jurisdiction, provided such tanks are in accordance with approved applicable standards.
- (2) Each surge tank shall be vented in accordance with this code. The vent size shall be determined based on the total gray water fixture units as outlined in this code.
- (3) Each surge tank shall have an access opening with lockable gasketed covers or approved equivalent to allow for inspection and cleaning.
- (4) Each surge tank shall have its rated capacity permanently marked on the unit. In addition, a sign stating GRAY WATER, DANGER — UNSAFE WATER shall be permanently marked on the holding tank.
- (5) Each surge tank shall have an overflow drain. The overflow drains shall have permanent connections to the building drain or building sewer, upstream of septic tanks. The overflow drain shall not be equipped with a shutoff valve.
- (6) The overflow drain pipes shall not be less in size than the inlet pipe. Unions or equally effective fittings shall be provided for piping connected to the surge tank.
- (7) Surge tank shall be structurally designed to withstand anticipated earth or other loads. Surge tank covers shall be capable of supporting an earth load of not less than 300 pounds per square foot (lb/ft²) (1465 kg/m²) where the tank is designed for underground installation.
- (8) Where a surge tank is installed underground, the system shall be designed so that the tank overflow will gravity drain to the existing sewer line or septic tank. The tank shall be protected against sewer line backflow by a backwater valve installed in accordance with this code.
- (9) Surge tanks shall be installed on dry, level, well-compacted soil where underground or on a level 3 inch (76 mm) thick concrete slab where above-ground.
- (10) Surge tanks shall be anchored to prevent against overturning where installed aboveground. Underground tanks shall be ballasted, anchored, or

otherwise secured, to prevent the tank from floating out of the ground where empty. The combined weight of the tank and hold down system shall meet or exceed the buoyancy forces of the tank.

» **1502.9.2 Gray Water Pipe and Fitting Materials.**

Aboveground and underground building drainage and vent pipe and fittings for gray water systems shall comply with the requirements for aboveground and underground sanitary building drainage and vent pipe and fittings in this code. These materials shall extend not less than 2 feet (610 mm) outside the building.

» **1502.9.3 Subsoil Irrigation Field Materials.**

Subsoil irrigation field piping shall be constructed of perforated high-density polyethylene pipe, perforated ABS pipe, perforated PVC pipe, or other approved materials, provided that sufficient openings are available for distribution of the gray water into the trench area. Material, construction, and perforation of the pipe shall be in accordance with the appropriate absorption field drainage piping standards and shall be approved by the Authority Having Jurisdiction.

» **1502.9.4 Subsurface Irrigation Field and Mulch Basin Supply Line Materials.**

Materials for gray water piping outside the building shall be polyethylene or PVC. Drip feeder lines shall be PVC or polyethylene tubing.

» **1502.9.5 Valves.** Valves shall be accessible.

» **1502.9.6 Trap.** Gray water piping discharging into the surge tank or having a direct connection to the sanitary drain or sewer piping shall be downstream of an approved water seal type trap(s). Where no such trap(s) exists, an approved vented running trap shall be installed upstream of the connection to protect the building from possible waste or sewer gases.

» **1502.9.7 Backwater Valve.** A backwater valve shall be installed on gray water drain connections to the sanitary drain or sewer.

» **1502.10 Subsurface Irrigation System Zones.** Irrigation or disposal fields shall be permitted to have one or more valved zones. Each zone shall be of a size to receive the gray water anticipated in that zone.

» **1502.10.1 Required Area of Subsurface Irrigation Fields, Subsoil Irrigation Fields and Mulch Basins.** The minimum effective irrigation area of subsurface irrigation fields, subsoil irrigation fields, and mulch basins shall be determined by Table 1502.10 for the type of soil found in the excavation, based upon a calculation of estimated gray water discharge pursuant to Section 1502.8. For a subsoil irrigation field, the area shall be equal to the aggregate length of the perforated pipe sections within the valved zone multiplied by the width of the proposed subsoil irrigation field.

» **1502.10.2 Determination of Maximum Absorption Capacity.** The irrigation field and mulch basin size shall be based on the maximum absorption capacity of the soil and determined using Table

1502.10. For soils not listed in Table 1502.10, the maximum absorption capacity for the proposed site shall be determined by percolation tests or other method acceptable to the Authority Having Jurisdiction. A gray water system shall not be permitted, where the percolation test shows the absorption capacity of the soil is unable to accommodate the maximum discharge of the proposed gray water irrigation system.

» **1502.10.3 Groundwater Level.** No excavation for an irrigation field, disposal field, or mulch basin shall extend within 3 feet (914 mm) vertical of the highest known seasonal groundwater level, nor to a depth where gray water contaminates the groundwater or surface water. The applicant shall supply evidence of groundwater depth to the satisfaction of the Authority Having Jurisdiction.

TABLE 1502.10
DESIGN OF SIX TYPICAL SOILS

| TYPE OF SOIL | MINIMUM SQUARE FEET OF IRRIGATION AREA PER 100 GALLONS OF ESTIMATED GRAY WATER DISCHARGE PER DAY | MAXIMUM ABSORPTION CAPACITY IN GALLONS PER SQUARE FOOT OF IRRIGATION/ LEACHING AREA FOR A 24-HOUR PERIOD |
|---|--|--|
| Coarse sand or gravel | 20 | 5.0 |
| Fine sand | 25 | 4.0 |
| Sandy loam | 40 | 2.5 |
| Sandy clay | 60 | 1.7 |
| Clay with considerable sand or gravel | 90 | 1.1 |
| Clay with small amounts of sand or gravel | 120 | 0.8 |

For SI units: 1 square foot = 0.0929 m², 1 gallon per day = 0.000043 L/s

» **1502.11 Subsurface and Subsoil Irrigation Field, and Mulch Basin Design and Construction.** Subsurface and subsoil irrigation field, and mulch basin design and construction shall be in accordance with Section 1502.11.1 through Section 1502.11.3. Where a gray water irrigation system design is predicated on soil tests, the subsurface or subsoil irrigation field or mulch basin shall be installed at the same location and depth as the tested area.

» **1502.11.1 Subsurface Irrigation Field.** A subsurface irrigation field shall comply with Section 1502.11.1.1 through Section 1502.11.1.6.

» **1502.11.1.1 Minimum Depth.** Supply piping, including drip feeders, shall be not less than 2 inches (51 mm) below finished grade and covered with mulch or soil.

» **1502.11.1.2 Filter.** Not less than 140 mesh (105 micron) filter with a capacity of 25 gallons per

minute (gpm) (1.58 L/s), or equivalent shall be installed. Where a filter backwash is installed, the backwash and flush discharge shall discharge into the building sewer or private sewage disposal system. Filter backwash and flush water shall not be used.

1502.11.1.3 Emitter Size. Emitters shall be installed in accordance with the manufacturer's installation instructions. Emitters shall have a flow path of not less than 1200 microns (μ) (1200 μ m) and shall not have a coefficient of manufacturing variation (Cv) exceeding 7 percent. Irrigation system design shall be such that emitter flow variation shall not exceed 10 percent.

1502.11.1.4 Number of Emitters. The minimum number of emitters and the maximum discharge of each emitter in an irrigation field shall be in accordance with Table 1502.11.

1502.11.1.5 Controls. The system design shall provide user controls, such as valves, switches, timers, and other controllers, to rotate the distribution of gray water between irrigation zones.

1502.11.1.6 Maximum Pressure. Where pressure at the discharge side of the pump exceeds 20 pounds-force per square inch (psi) (138 kPa), a pressure-reducing valve able to maintain downstream pressure not exceeding 20 psi (138 kPa) shall be installed downstream from the pump and before an emission device.

**TABLE 1502.11
SUBSURFACE IRRIGATION DESIGN
CRITERIA FOR SIX TYPICAL SOILS**

| TYPE OF SOIL | MAXIMUM EMITTER DISCHARGE (gallons per day) | MINIMUM NUMBER OF EMITTERS PER GALLON OF ESTIMATED GRAY WATER DISCHARGE PER DAY* (gallons per day) |
|--------------|---|--|
| Sand | 1.8 | 0.6 |
| Sandy loam | 1.4 | 0.7 |
| Loam | 1.2 | 0.9 |
| Clay loam | 0.9 | 1.1 |
| Silty clay | 0.6 | 1.6 |
| Clay | 0.5 | 2.0 |

For SI units: 1 gallon per day = 0.000043 L/s

* The estimated gray water discharge per day shall be determined in accordance with Section 1502.8 of this code.

1502.11.2 Mulch Basin. A mulch basin shall comply with Section 1502.11.2.1 through Section 1502.11.2.4.

1502.11.2.1 Single Family and Multi-Family Dwellings. The gray water discharge to a mulch basin is limited to single family and multi-family dwellings.

1502.11.2.2 Size. Mulch basins shall be of sufficient size to accommodate peak flow rates and

distribute the total amount of estimated gray water on a daily basis without surfacing, ponding or runoff. Mulch basins shall have a depth of not less than 10 inches (254 mm) below finished grade. The mulch basin size shall be based on the maximum absorption capacity of the soil and determined using Table 1502.10.

1502.11.2.3 Minimum Depth. Gray water supply piping, including drip feeders, shall be not less than 2 inches (51 mm) below finished grade and covered with mulch.

1502.11.2.4 Maintenance. The mulch basin shall be maintained periodically to retain the required depth and area, and to replenish the required mulch cover.

1502.11.3 Subsoil Irrigation Field. Subsoil irrigation fields shall comply with Section 1502.11.3.1 through Section 1502.11.3.3.

**TABLE 1502.11.3
SUBSOIL IRRIGATION FIELD CONSTRUCTION**

| DESCRIPTION | MINIMUM | MAXIMUM |
|---|-----------|-----------------------|
| Number of drain lines per valved zone | 1 | - |
| Length of each perforated line | - | 100 feet |
| Bottom width of trench | 12 inches | 18 inches |
| Spacing of lines, center to center | 4 feet | - |
| Depth of earth cover of lines | 10 inches | - |
| Depth of filter material cover of lines | 2 inches | - |
| Depth of filter material beneath lines | 3 inches | - |
| Grade of perforated lines level | level | 3 inches per 100 feet |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 inch per foot = 83.3 mm/m

1502.11.3.1 Minimum Pipe Size. Subsoil irrigation field distribution piping shall be not less than 3 inches (80 mm) diameter.

1502.11.3.2 Filter Material and Backfill. Filter material, clean stone, gravel, slag, or similar material acceptable to the Authority Having Jurisdiction, varying in size from $\frac{3}{4}$ of an inch (19.1 mm) to 2½ inches (64 mm) shall be placed in the trench to the depth and grade in accordance with Table 1502.11.3. The perforated section of subsoil irrigation field distribution piping shall be laid on the filter material in an approved manner. The perforated section shall then be covered with filter material to the minimum depth in accordance with Table 1502.11.3. The filter material shall then be covered with porous material to prevent closure of voids with earth backfill. No earth backfill shall be placed over the filter material cover until after inspection and acceptance.

1502.11.3.3 Subsoil Irrigation Field Construction. Subsoil irrigation fields shall be

constructed in accordance with Table 1502.11.3. Where necessary on sloping ground to prevent excessive line slopes, irrigation lines shall be stepped. The lines between each horizontal leaching section shall be made with approved watertight joints and installed on natural or unfilled ground.

» **1502.12 Gray Water System Color and Marking Information.** Pressurized gray water distribution systems shall be identified as containing nonpotable water in accordance with Section 601.3 of this code.

» **1502.13 Other Collection and Distribution Systems.** Other collection and distribution systems shall be approved by the local Authority Having Jurisdiction, as allowed by Section 301.3 of this code.

» **1502.13.1 Higher Requirements.** Nothing contained in this chapter shall be construed to prevent the Authority Having Jurisdiction from requiring compliance with higher requirements than those contained herein, where such higher requirements are essential to maintain a safe and sanitary condition.

» **1502.14 Testing.** Building drains and vents for gray water systems shall be tested in accordance with this code. Surge tanks shall be filled with water to the overflow line prior to and during inspection. Seams and joints shall be left exposed, and the tank shall remain watertight. A flow test shall be performed through the system to the point of gray water discharge. Lines and components shall be watertight up to the point of the irrigation perforated and drip lines.

» **1502.15 Maintenance.** Gray water systems and components shall be maintained in accordance with Table 1501.5.

» **1503.0 Reclaimed (Recycled) Water Systems.**

» **1503.1 General.** The provisions of this section shall apply to the installation, construction, alteration, and repair of reclaimed (recycled) water systems intended to supply uses such as water closets, urinals, trap primers for floor drains and floor sinks, aboveground and subsurface irrigation, industrial or commercial cooling or air conditioning and other uses approved by the Authority Having Jurisdiction.

» **1503.2 Permit.** It shall be unlawful for a person to construct, install, alter, or cause to be constructed, installed, or altered a reclaimed (recycled) water system within a building or on a premises without first obtaining a permit to do such work from the Authority Having Jurisdiction.

» **1503.2.1 Plumbing Plan Submission.** No permit for a reclaimed (recycled) water system shall be issued until complete plumbing plans, with data satisfactory to the Authority Having Jurisdiction, have been submitted and approved.

» **1503.3 System Changes.** No changes or connections shall be made to either the reclaimed (recycled) water system or the potable water system within a site containing a reclaimed (recycled) water system without approval by the Authority Having Jurisdiction.

1503.4 Connections to Potable or Reclaimed (Recycled) Water Systems. Reclaimed (recycled) water systems shall have no connection to a potable water supply or alternate water source system. Potable water is permitted to be used as makeup water for a reclaimed (recycled) water storage tank provided the water supply inlet is protected by an air gap or reduced-pressure principle backflow preventer in accordance with this code.

1503.5 Initial Cross-Connection Test. A cross-connection test is required in accordance with Section 1501.11.2. Before the building is occupied or the system is activated, the installer shall perform the initial cross-connection test in the presence of the Authority Having Jurisdiction and other authorities having jurisdiction. The test shall be ruled successful by the Authority Having Jurisdiction before final approval is granted.

1503.6 Reclaimed (Recycled) Water System Materials. Reclaimed (recycled) water supply and distribution system materials shall comply with the requirements of this code for potable water supply and distribution systems, unless otherwise provided for in this section.

1503.7 Reclaimed (Recycled) Water System Color and Marking Information. Reclaimed (recycled) water systems shall have a colored background and marking information in accordance with Section 601.3 of this code.

1503.8 Valves. Valves, except fixture supply control valves, shall be equipped with a locking feature.

1503.9 Hose Bibbs. Hose bibbs shall not be allowed on reclaimed (recycled) water piping systems located in areas accessible to the public. Access to reclaimed (recycled) water at points in the system accessible to the public shall be through a quick-disconnect device that differs from those installed on the potable water system. Hose bibbs supplying reclaimed (recycled) water shall be marked with the words: "CAUTION: NONPOTABLE RECLAIMED WATER, DO NOT DRINK," and the symbol in Figure 1503.9.



FIGURE 1503.9

1503.10 Required Appurtenances. The reclaimed (recycled) water system and the potable water system within the building shall be provided with the required appurtenances (e.g., valves, air/vacuum relief valves, etc.) to allow for deactivation or drainage as required for a cross-connection test in accordance with Section 1501.11.2.

» 1503.11 Same Trench as Potable Water Pipes.

Reclaimed (recycled) water pipes shall be permitted to be run or laid in the same trench as potable water pipes with 12 inches (305 mm) minimum vertical and horizontal separation where both pipe materials are approved for use within a building. Where piping materials do not meet this requirement the minimum horizontal separation shall be increased to 60 inches (1524 mm). The potable water piping shall be installed at an elevation above the reclaimed (recycled) water piping. Reclaimed (recycled) water pipes laid in the same trench or crossing building sewer or drainage piping shall be installed in accordance with this code for potable water piping.

» 1503.12 Signs. Signs in rooms and water closet tanks in buildings using reclaimed (recycled) water shall be in accordance with Section 1501.10 and Section 1501.10.1.

» 1503.13 Inspection and Testing. Reclaimed (recycled) water systems shall be inspected and tested in accordance with Section 1501.11.

» 1504.0 On-Site Treated Nonpotable Water Systems.

» 1504.1 General. The provisions of this section shall apply to the installation, construction, alteration, and repair of on-site treated nonpotable water systems intended to supply uses such as water closets, urinals, trap primers for floor drains and floor sinks, above and belowground irrigation, and other uses approved by the Authority Having Jurisdiction.

» 1504.2 Plumbing Plan Submission. No permit for an on-site treated nonpotable water system shall be issued until complete plumbing plans, with data satisfactory to the Authority Having Jurisdiction, have been submitted and approved.

» 1504.3 System Changes. No changes or connections shall be made to either the on-site treated nonpotable water system or the potable water system within a site containing an on-site treated nonpotable water system without approval by the Authority Having Jurisdiction.

» 1504.4 Connections to Potable or Reclaimed (Recycled) Water Systems. On-site treated nonpotable water systems shall have no connection to a potable water supply or reclaimed (recycled) water source system. Potable or reclaimed (recycled) water is permitted to be used as makeup water for a non-pressurized storage tank provided the makeup water supply is protected by an air gap in accordance with this code.

» 1504.5 Initial Cross-Connection Test. A cross-connection test is required in accordance with Section 1501.11.2. Before the building is occupied or the system is activated, the installer shall perform the initial cross-connection test in the presence of the Authority Having Jurisdiction and other authorities having jurisdiction. The test shall be ruled successful by the Authority Having Jurisdiction before final approval is granted.

1504.6 On-Site Treated Nonpotable Water System Materials. On-site treated nonpotable water supply and distribution system materials shall comply with the requirements of this code for potable water supply and distribution systems, unless otherwise provided for in this section.

1504.7 On-Site Treated Nonpotable Water Devices and Systems. Devices or equipment used to treat on-site treated nonpotable water in order to maintain the minimum water quality requirements determined by the Authority Having Jurisdiction shall be listed or labeled (third-party certified) by a listing agency (accredited conformity assessment body) or approved for the intended application. Devices or equipment used to treat on-site treated nonpotable water for use in water closet and urinal flushing, surface irrigation, and similar applications shall be listed or labeled to NSF 350 or approved by the Authority Having Jurisdiction.

1504.8 On-Site Treated Nonpotable Water System Color and Marking Information. On-site treated water systems shall have a colored background and marking information in accordance with Section 601.3 of this code.

1504.9 Valves. Valves, except fixture supply control valves, shall be equipped with a locking feature.

1504.10 Design and Installation. The design and installation of on-site treated nonpotable systems shall be in accordance with Section 1504.10.1 through Section 1504.10.5.

1504.10.1 Listing Terms and Installation Instructions. On-site treated nonpotable water systems shall be installed in accordance with the terms of its listing and the manufacturer's installation instructions.

1504.10.2 Minimum Water Quality. On-site treated nonpotable water supplied to toilets or urinals or for other uses in which it is sprayed or exposed shall be disinfected. Acceptable disinfection methods shall include chlorination, ultraviolet sterilization, ozone, or other methods as approved by the Authority Having Jurisdiction. The minimum water quality for on-site treated nonpotable water systems shall meet the applicable water quality requirements for the intended applications as determined by the public health Authority Having Jurisdiction.

1504.10.3 Deactivation and Drainage. The on-site treated nonpotable water system and the potable water system within the building shall be provided with the required appurtenances (e.g., valves, air/vacuum relief valves, etc.) to allow for deactivation or drainage as required for a cross-connection test in accordance with Section 1501.11.2.

1504.10.4 Near Underground Potable Water Pipe. On-site treated nonpotable water pipes shall be permitted to be run or laid in the same trench as potable water pipes with a 12 inch (305 mm) minimum vertical and horizontal separation where both pipe materials are

ALTERNATE WATER SOURCES FOR NONPOTABLE APPLICATIONS

approved for use within a building. Where piping materials do not meet this requirement the minimum separation shall be increased to 60 inches (1524 mm). The potable water piping shall be installed at an elevation above the on-site treated nonpotable water piping.

» **1504.10.5 Required Filters.** A filter permitting the passage of particulates no larger than 100 microns (100 μm) shall be provided for on-site treated nonpotable water supplied to water closets, urinals, trap primers, and drip irrigation system.

» **1504.11 Signs.** Signs in buildings using on-site treated nonpotable water shall comply with Section 1501.10 and Section 1501.10.1.

» **1504.12 Inspection and Testing.** On-site treated nonpotable water systems shall be inspected and tested in accordance with Section 1501.11.

CHAPTER 16

NONPOTABLE RAINWATER CATCHMENT SYSTEMS

» 1601.0 General.

» **1601.1 Applicability.** The provisions of this chapter shall apply to the installation, construction, alteration, and repair of nonpotable rainwater catchment systems.

1601.1.1 Allowable Use of Alternate Water. Where approved or required by the Authority Having Jurisdiction, rainwater shall be permitted to be used in lieu of potable water for the applications identified in this chapter.

1601.2 System Design. Rainwater catchment systems shall be designed in accordance with this chapter by a person registered or licensed to perform plumbing design work or who demonstrates competency to design the rainwater catchment system as required by the Authority Having Jurisdiction. Components, piping, and fittings used in a rainwater catchment system shall be listed.

Exceptions:

- (1) A person registered or licensed to perform plumbing design work is not required to design rainwater catchment systems used for irrigation with a maximum storage capacity of 360 gallons (1363 L).
- (2) A person registered or licensed to perform plumbing design work is not required to design rainwater catchment systems for single family dwellings where outlets, piping, and system components are located on the exterior of the building.

1601.3 Permit. It shall be unlawful for a person to construct, install, alter, or cause to be constructed, installed, or altered a rainwater catchment system in a building or on a premise without first obtaining a permit to do such work from the Authority Having Jurisdiction.

Exceptions:

- (1) A permit is not required for exterior rainwater catchment systems used for outdoor drip and subsurface irrigation with a maximum storage capacity of 360 gallons (1363 L).
- (2) A plumbing permit is not required for rainwater catchment systems for single family dwellings where outlets, piping, and system components are located on the exterior of the building. This does not exempt the need for permits where required for electrical connections, tank supports, or enclosures.

1601.4 Component Identification. System components shall be properly identified as to the manufacturer.

1601.5 Maintenance and Inspection. Rainwater catchment systems and components shall be inspected and maintained in accordance with Section 1601.5.1 through Section 1601.5.3.

1601.5.1 Frequency. Rainwater catchment systems and components shall be inspected and maintained in accordance with Table 1601.5 unless more frequent inspection and maintenance is required by the manufacturer.

TABLE 1601.5
MINIMUM ALTERNATE WATER SOURCE TESTING, INSPECTION, AND MAINTENANCE FREQUENCY

| DESCRIPTION | MINIMUM FREQUENCY |
|---|---|
| Inspect and clean filters and screens, and replace (where necessary). | Every 3 months |
| Inspect and verify that disinfection, filters, and water quality treatment devices and systems are operational and maintaining minimum water quality requirements as determined by the Authority Having Jurisdiction. | In accordance with manufacturer's instructions and the Authority Having Jurisdiction. |
| Inspect and clear debris from rainwater gutters, downspouts, and roof washers. | Every 6 months |
| Inspect and clear debris from roof or other aboveground rainwater collection surfaces. | Every 6 months |
| Remove tree branches and vegetation overhanging a roof or other aboveground rainwater collection surfaces. | As needed |
| Inspect pumps and verify operation. | After initial installation and every 12 months thereafter |
| Inspect valves and verify operation. | After initial installation and every 12 months thereafter |
| Inspect pressure tanks and verify operation. | After initial installation and every 12 months thereafter |
| Clear debris from and inspect storage tanks, locking devices, and verify operation. | After initial installation and every 12 months thereafter |
| Inspect caution labels and marking. | After initial installation and every 12 months thereafter |
| Cross-connection inspection and test* | After initial installation and every 12 months thereafter |
| Test water quality of rainwater catchment systems required by Section 1602.9.4 to maintain a minimum water quality | Every 12 months. After system renovation or repair. |

* The cross-connection test shall be performed in the presence of the Authority Having Jurisdiction in accordance with the requirements of this chapter.

1601.5.2 Maintenance Log. A maintenance log for rainwater catchment systems is required to have a permit in accordance with Section 1601.3 and shall be maintained by the property owner and be available for inspection. The property owner or designated appointee shall ensure that a record of testing, inspection, and maintenance in accordance with Table 1601.5 is maintained in the log. The log will indicate the frequency of inspection and maintenance for each system.

1601.5.3 Maintenance Responsibility. The required maintenance and inspection of rainwater catchment systems shall be the responsibility of the property owner, unless otherwise required by the Authority Having Jurisdiction.

1601.6 Operation and Maintenance Manual. An operation and maintenance manual for rainwater catchment systems required to have a permit in accordance with Section 1601.3, shall be supplied to the building owner by the system designer. The operating and maintenance manual shall include the following:

- (1) Detailed diagram of the entire system and the location of system components.
- (2) Instructions on operating and maintaining the system.
- (3) Details on maintaining the required water quality as determined by the Authority Having Jurisdiction.
- (4) Details on deactivating the system for maintenance, repair, or other purposes.
- (5) Applicable testing, inspection, and maintenance frequencies in accordance with Table 1601.5.
- (6) A method of contacting the manufacturer(s).

1601.7 Minimum Water Quality Requirements. The minimum water quality for rainwater catchment systems shall comply with the applicable water quality requirements for the intended application as determined by the Authority Having Jurisdiction. Water quality for nonpotable rainwater catchment systems shall comply with Section 1602.9.4.

Exceptions:

- (1) Water treatment is not required for rainwater catchment systems used for aboveground irrigation with a maximum storage capacity of 360 gallons (1363 L).
- (2) Water treatment is not required for rainwater catchment systems used for subsurface or drip irrigation.

1601.8 Material Compatibility. Rainwater catchment systems shall be constructed of materials that are compatible with the type of pipe and fitting materials, water treatment, and water conditions in the system.

1601.9 System Controls. Controls for pumps, valves, and other devices that contain mercury that come in contact with rainwater supply shall not be permitted.

1601.10 Separation Requirements. Underground rainwater catchment service piping shall be separated from the building sewer in accordance with Section 609.2. Treated nonpotable water pipes shall be permitted to be run or laid in the same trench as potable water pipes with a 12 inch (305 mm) minimum vertical and horizontal separation where both pipe materials are approved for use within a building. Where horizontal piping materials do not meet this requirement the

minimum separation shall be increased to 60 inches (1524 mm). The potable water piping shall be installed at an elevation above the treated nonpotable water piping.

1601.11 Abandonment. Rainwater catchment systems that are no longer in use, or fail to be maintained in accordance with Section 1601.5, shall be abandoned. Abandonment shall comply with Section 1601.11.1 and Section 1601.11.2.

1601.11.1 General. An abandoned system or part thereof covered under the scope of this chapter shall be disconnected from remaining systems, drained, plugged, and capped in an approved manner.

1601.11.2 Underground Tank. An underground water storage tank that has been abandoned or otherwise discontinued from use in a system covered under the scope of this chapter shall be completely drained and filled with earth, sand, gravel, concrete, or other approved material or removed in a manner satisfactory to the Authority Having Jurisdiction.

1601.12 Sizing. Unless otherwise provided for in this chapter, rainwater catchment piping shall be sized in accordance with Chapter 6 for sizing potable water piping.

1602.0 Nonpotable Rainwater Catchment Systems. <<

1602.1 General. The installation, construction, alteration, and repair of rainwater catchment systems intended to supply uses such as water closets, urinals, trap primers for floor drains and floor sinks, irrigation, industrial processes, water features, cooling tower makeup and other uses shall be approved by the Authority Having Jurisdiction. Additional design criteria is capable of being found in ARCSA/ASPE 63. <<

1602.2 Plumbing Plan Submission. No permit for a rainwater catchment system shall be issued until complete plumbing plans, with data satisfactory to the Authority Having Jurisdiction, have been submitted and approved. <<

1602.3 System Changes. No changes or connections shall be made to either the rainwater catchment system or the potable water system within a site containing a rainwater catchment system requiring a permit without approval by the Authority Having Jurisdiction. <<

1602.4 Connections to Potable or Reclaimed (Recycled) Water Systems. Rainwater catchment systems shall have no direct connection to a potable water supply or alternate water source system. Potable or reclaimed (recycled) water is permitted to be used as makeup water for a rainwater catchment system provided the potable or reclaimed (recycled) water supply connection is protected by an air gap or reduced-pressure principle backflow preventer in accordance with this code. <<

1602.5 Initial Cross-Connection Test. Where a portion of a rainwater catchment system is installed within a building, a cross-connection test is required in accordance with Section 1602.11.2. Before the building is occupied or the system is activated, the installer shall perform the initial cross-connection test in the presence of the Authority Having Jurisdiction and other authorities having jurisdiction. The test shall be ruled successful by the Authority Having Jurisdiction before final approval is granted. <<

- » **1602.6 Sizing.** The design and size of rainwater drains, gutters, conductors, and leaders shall comply with Chapter 11 of this code.
- » **1602.7 Rainwater Catchment System Materials.** Rainwater catchment system materials shall comply with Section 1602.7.1 through Section 1602.7.4.
- » **1602.7.1 Water Supply and Distribution Materials.** Rainwater catchment water supply and distribution materials shall comply with the requirements of this code for potable water supply and distribution systems, unless otherwise provided for in this section.
- » **1602.7.2 Rainwater Catchment System Drainage Materials.** Materials used in rainwater catchment drainage systems, including gutters, downspouts, conductors, and leaders shall be in accordance with the requirements of this code for storm drainage.
- » **1602.7.3 Storage Tanks.** Rainwater storage tanks shall comply with Section 1602.9.5.
- » **1602.7.4 Collections Surfaces.** The collection surface shall be constructed of a hard, impervious material.
- » **1602.8 Rainwater Catchment System Color and Marking Information.** Rainwater catchment systems shall have a colored background in accordance with Section 601.3. Rainwater catchment systems shall be marked, in lettering in accordance with Section 601.3.3, with the words: "CAUTION: NONPOTABLE RAINWATER WATER, DO NOT DRINK."
- » **1602.9 Design and Installation.** The design and installation of nonpotable rainwater catchment systems shall be in accordance with Section 1602.9.1 through Section 1602.9.12.
- » **1602.9.1 Outside Hose Bibbs.** Outside hose bibbs shall be allowed on rainwater piping systems. Hose bibbs supplying rainwater shall be marked with the words: "CAUTION: NONPOTABLE WATER, DO NOT DRINK" and Figure 1602.9.



FIGURE 1602.9

- » **1602.9.2 Deactivation and Drainage for Cross-Connection Test.** The rainwater catchment system and the potable water system within the building shall be provided with the required appurtenances (e.g., valves, air or vacuum relief valves, etc.) to allow for deactivation or drainage as required for a cross-connection test in accordance with Section 1602.11.2.

1602.9.3 Rainwater Catchment System Surfaces. Rainwater shall be collected from roof surfaces or other manmade, aboveground collection surfaces. ←

1602.9.3.1 Other Surfaces. Natural precipitation collected from surface water runoff, vehicular parking surfaces, or manmade surfaces at or below grade shall be in accordance with the stormwater requirements for on-site treated nonpotable water systems in Section 1504.0.

1602.9.3.2 Prohibited Discharges. Overflows and bleed-off pipes from roof-mounted equipment and appliances shall not discharge onto roof surfaces that are intended to collect rainwater. ←

1602.9.4 Minimum Water Quality. The minimum water quality for harvested rainwater shall meet the applicable water quality requirements for the intended applications as determined by the Authority Having Jurisdiction. In the absence of water quality requirements determined by the Authority Having Jurisdiction, the minimum treatment and water quality shall be in accordance with Table 1602.9.4. ←

1602.9.5 Rainwater Storage Tanks. Rainwater storage tanks shall be constructed and installed in accordance with Section 1602.9.5.1 through Section 1602.9.5.8. ←

1602.9.5.1 Construction. Rainwater storage shall be constructed of solid, durable materials not subject to excessive corrosion or decay and shall be watertight. Storage tanks shall be approved by the Authority Having Jurisdiction, provided such tanks are in accordance with approved applicable standards.

1602.9.5.2 Location. Rainwater storage tanks shall be permitted to be installed above or below grade. ←

1602.9.5.3 Above Grade. Above grade storage tanks shall be of an opaque material, approved for aboveground use in direct sunlight or shall be shielded from direct sunlight. Tanks shall be installed in an accessible location to allow for inspection and cleaning. The tank shall be installed on a foundation or platform that is constructed to accommodate loads in accordance with the building code. ←

1602.9.5.4 Below Grade. Rainwater storage tanks installed below grade shall be structurally designed to withstand anticipated earth or other loads. Holding tank covers shall be capable of supporting an earth load of not less than 300 pounds per square foot (lb/ft²) (1465 kg/m²) where the tank is designed for underground installation. Below grade rainwater tanks installed underground shall be provided with manholes. The manhole opening shall be not less than 20 inches (508 mm) in diameter and located not less than 4 inches (102 mm) above the ←

TABLE 1602.9.4
MINIMUM WATER QUALITY

| APPLICATION | MINIMUM TREATMENT | MINIMUM WATER QUALITY |
|--|--|---|
| Car washing | Debris excluder or other approved means in accordance with Section 1602.9.10, and 100 micron in accordance with Section 1602.9.11 for drip irrigation. | N/A |
| Subsurface and drip irrigation | Debris excluder or other approved means in accordance with Section 1602.9.10, and 100 micron in accordance with Section 1602.9.11 for drip irrigation. | N/A |
| Spray irrigation where the maximum storage volume is less than 360 gallons | Debris excluder or other approved means in accordance with Section 1602.9.10, and disinfection in accordance with Section 1602.9.8. | N/A |
| Spray irrigation where the maximum storage volume is equal to or more than 360 gallons | Debris excluder or other approved means in accordance with Section 1602.9.10. | Escherichia coli: < 100 CFU/100 mL, and Turbidity: < 10 NTU |
| Urinal and water closet flushing, clothes washing, and trap priming | Debris excluder or other approved means in accordance with Section 1602.9.10, and 100 micron in accordance with Section 1602.9.11. | Escherichia coli: < 100 CFU/100 mL, and Turbidity: < 10 NTU |
| Ornamental fountains and other water features | Debris excluder or other approved means in accordance with Section 1602.9.10. | Escherichia coli: < 100 CFU/100 mL, and Turbidity: < 10 NTU |
| Cooling tower make up water | Debris excluder or other approved means in accordance with Section 1602.9.10, and 100 micron in accordance with Section 1602.9.11. | Escherichia coli: < 100 CFU/100 mL, and Turbidity: < 10 NTU |

For SI units: 1 micron = 1 μ m, 1 gallon = 3.785 L

surrounding grade. The surrounding grade shall be sloped away from the manhole. Underground tanks shall be ballasted, anchored, or otherwise secured, to prevent the tank from floating out of the ground where empty. The combined weight of the tank and hold down system shall meet or exceed the buoyancy force of the tank.

1602.9.5.5 Drainage and Overflow. Rainwater storage tanks shall be provided with a means of draining and cleaning. The overflow drain shall not be equipped with a shutoff valve. The overflow outlet shall discharge in accordance with this code for storm drainage systems. Where discharging to the storm drainage system, the overflow drain shall be protected from backflow of the storm drainage system by a backwater valve or other approved method.

1602.9.5.5.1 Overflow Outlet Size. The overflow outlet shall be sized to accommodate the flow of the rainwater entering the tank and not less than the aggregate cross-sectional area of inflow pipes.

1602.9.5.6 Opening and Access Protection. Rainwater tank openings shall be protected to prevent the entrance of insects, birds, or rodents into the tank.

Rainwater tank access openings exceeding 12 inches (305 mm) in diameter shall be secured to prevent tampering and unintended entry by either a lockable device or other approved method.

1602.9.5.7 Marking. Rainwater tanks shall be permanently marked with the capacity and the lan-

guage: "NONPOTABLE RAINWATER." Where openings are provided to allow a person to enter the tank, the opening shall be marked with the following language: "DANGER-CONFINED SPACE."

1602.9.5.8 Storage Tank Venting. Where venting by means of drainage or overflow piping is not provided, or is considered insufficient, a vent shall be installed on each tank. The vent shall extend from the top of the tank and terminate not less than 6 inches (152 mm) above grade and shall be not less than 1½ inches (40 mm) in diameter. The vent terminal shall be directed downward and covered with a ¾ of an inch (2.4 mm) mesh screen to prevent the entry of vermin and insects.

1602.9.6 Pumps. Pumps serving rainwater catchment systems shall be listed. Pumps supplying water to water closets, urinals, and trap primers shall be capable of delivering not less than 15 pounds-force per square inch (psi) (103 kPa) residual pressure at the highest and most remote outlet served. Where the water pressure in the rainwater supply system within the building exceeds 80 psi (552 kPa), a pressure reducing valve reducing the pressure to 80 psi (552 kPa) or less to water outlets in the building shall be installed in accordance with this code.

1602.9.7 Roof Drains. Primary and secondary roof drains, conductors, leaders, and gutters shall be designed and installed in accordance with this code.

1602.9.8 Water Quality Devices and Equipment. Devices and equipment used to treat rainwater to maintain the minimum water quality requirements determined by the Authority Having Jurisdiction shall be listed or

labeled (third-party certified) by a listing agency (accredited conformity assessment body) and approved for the intended application.

- » **1602.9.9 Freeze Protection.** Tanks and piping installed in locations subject to freezing shall be provided with an approved means of freeze protection.
- » **1602.9.10 Debris Removal.** The rainwater catchment conveyance system shall be equipped with a debris excluder or other approved means to prevent the accumulation of leaves, needles, other debris and sediment from entering the storage tank. Devices or methods used to remove debris or sediment shall be accessible and sized and installed in accordance with manufacturer's installation instructions.
- » **1602.9.11 Required Filters.** A filter permitting the passage of particulates not larger than 100 microns (100 µm) shall be provided for rainwater supplied to water closets, urinals, trap primers, and drip irrigation system.
- » **1602.9.12 Roof Gutters.** Gutters shall maintain a minimum slope and be sized in accordance with Section 1103.3.
- » **1602.10 Signs.** Signs in buildings using rainwater shall be in accordance with Section 1602.10.1 and Section 1602.10.2.
- » **1602.10.1 Commercial, Industrial, and Institutional Restroom Signs.** A sign shall be installed in restrooms in commercial, industrial, and institutional occupancies using nonpotable rainwater for water closets, urinals, or both. Each sign shall contain ½ of an inch (12.7 mm) letters of a highly visible color on a contrasting background. The location of the sign(s) shall be such that the sign(s) shall be visible to users. The number and location of the signs shall be approved by the Authority Having Jurisdiction and shall contain the following text:
TO CONSERVE WATER, THIS BUILDING USES
RAINWATER TO FLUSH TOILETS AND URINALS.
- » **1602.10.2 Equipment Room Signs.** Each equipment room containing nonpotable rainwater equipment shall have a sign posted with the following wording in 1 inch (25.4 mm) letters:
CAUTION NONPOTABLE RAINWATER, DO NOT
DRINK. DO NOT CONNECT TO DRINKING WATER
SYSTEM. NOTICE: CONTACT BUILDING MAN-
AGEMENT BEFORE PERFORMING ANY WORK
ON THIS WATER SYSTEM.

This sign shall be posted in a location that is visible to anyone working on or near rainwater water equipment.

- » **1602.11 Inspection and Testing.** Rainwater catchment systems shall be inspected and tested in accordance with Section 1602.11.1 and Section 1602.11.2.
- » **1602.11.1 Supply System Inspection and Test.** Rainwater catchment systems shall be inspected and tested in accordance with the applicable provisions of this code for testing of potable water and storm drainage systems. Storage tanks shall be filled with water to the overflow opening for a period of 24 hours, and during

inspection, or by other means as approved by the Authority Having Jurisdiction. Seams and joints shall be exposed during inspection and checked for watertightness.

1602.11.2 Annual Cross-Connection Inspection and Testing. An initial and subsequent annual inspection and test in accordance with Section 1602.5 shall be performed on both the potable and rainwater catchment water systems. The potable and rainwater catchment water systems shall be isolated from each other and independently inspected and tested to ensure there is no cross-connection in accordance with Section 1602.11.2.1 through Section 1602.11.2.4.

1602.11.2.1 Visual System Inspection. Prior to commencing the cross-connection testing, a dual system inspection shall be conducted by the Authority Having Jurisdiction and other authorities having jurisdiction as follows:

- (1) Pumps, equipment, equipment room signs, and exposed piping in an equipment room shall be checked.

1602.11.2.2 Cross-Connection Test. The procedure for determining cross-connection shall be followed by the applicant in the presence of the Authority Having Jurisdiction and other authorities having jurisdiction to determine whether a cross-connection has occurred as follows:

- (1) The potable water system shall be activated and pressurized. The rainwater catchment water system shall be shut down and completely drained.
- (2) The potable water system shall remain pressurized for a minimum period of time specified by the Authority Having Jurisdiction while the rainwater catchment water system is empty. The minimum period the rainwater catchment water system is to remain depressurized shall be determined on a case-by-case basis, taking into account the size and complexity of the potable and rainwater catchment water distribution systems, but in no case shall that period be less than 1 hour.
- (3) Fixtures, potable and rainwater, shall be tested and inspected for flow. Flow from a rainwater catchment water system outlet shall indicate a cross-connection. No flow from a potable water outlet shall indicate that it is connected to the rainwater water system.
- (4) The drain on the rainwater catchment water system shall be checked for flow during the test and at the end of the period.
- (5) The potable water system shall then be completely drained.
- (6) The rainwater catchment water system shall then be activated and pressurized.
- (7) The rainwater catchment water system shall remain pressurized for a minimum period of time specified by the Authority Having Jurisdiction.

diction while the potable water system is empty. The minimum period the potable water system is to remain depressurized shall be determined on a case-by-case basis, but in no case shall that period be less than 1 hour.

- (8) Fixtures, potable and rainwater catchment, shall be tested and inspected for flow. Flow from a potable water system outlet shall indicate a cross-connection. No flow from a rainwater catchment water outlet shall indicate that it is connected to the potable water system.
- (9) The drain on the potable water system shall be checked for flow during the test and at the end of the period.
- (10) Where there is no flow detected in the fixtures which would indicate a cross-connection, the potable water system shall be repressurized.

» **1602.11.2.3 Discovery of Cross-Connection.**

In the event that a cross-connection is discovered, the following procedure, in the presence of the Authority Having Jurisdiction, shall be activated immediately:

- (1) Rainwater catchment water piping to the building shall be shut down at the meter, and the rainwater water riser shall be drained.
- (2) Potable water piping to the building shall be shut down at the meter.
- (3) The cross-connection shall be uncovered and disconnected.
- (4) The building shall be retested following procedures listed in Section 1602.11.2.1 and Section 1602.11.2.2.
- (5) The potable water system shall be chlorinated with 50 ppm chlorine for 24 hours.
- (6) The potable water system shall be flushed after 24 hours, and a standard bacteriological test shall be performed. Where test results are acceptable, the potable water system shall be permitted to be recharged.

» **1602.11.2.4 Annual Inspection.** An annual inspection of the rainwater catchment water system, following the procedures listed in Section 1602.11.2.1 shall be required. Annual cross-connection testing, following the procedures listed in Section 1602.11.2.2 shall be required by the Authority Having Jurisdiction, unless site conditions do not require it. In no event shall the test occur less than once in 4 years.

Alternate testing requirements shall be permitted by the Authority Having Jurisdiction.

CHAPTER 17

REFERENCED STANDARDS

1701.0 General.

1701.1 Standards. The standards listed in Table 1701.1 are intended for use in the design, testing, and installation of materials, devices, appliances, and equipment regulated by this code. These standards are mandatory where required by sections in this code.

Organization abbreviations referred to in Table 1701.1 are defined in a list found at the end of the table.

TABLE 1701.1
REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|---|--|------------------------------------|-------------------------------------|
| AHAM FWD-1-2009 | Food Waste Disposers | Appliances | 301.2.2, 301.3 |
| APSP 1-2003* | Public Swimming Pools | Swimming Pools, Spas, and Hot Tubs | 301.2.2, 301.3 |
| <i>ARCSA/ASPE 63-2013*</i> | Rainwater Catchment Systems | Miscellaneous | 1602.1, K 104.9.1, L 504.9.1 |
| ASCE 25-2006* | Earthquake-Actuated Automatic Gas Shutoff Devices | Fuel Gas | 301.2.2, 301.3 |
| <i>ASHRAE 90.1-2013*</i> | Energy Standard for Buildings Except Low-Rise Residential Buildings | Miscellaneous | L 603.2.1, Table L 603.3.2 |
| ASHRAE 90.2-2007* | Energy-Efficient Design of Low-Rise Residential Buildings | Miscellaneous | 301.2.2, 301.3 |
| ASME A13.1-2007 (R2013)* | Scheme for the Identification of Piping Systems | Piping | 301.2.2, 301.3 |
| <i>ASME A112.1.2-2012*</i> | Air Gaps in Plumbing Systems (For Plumbing Fixtures and Water-Connected Receptors) | Fittings | Table 603.2 |
| <i>ASME A112.1.3-2000 (R2010)*</i> | Air Gap Fittings for Use with Plumbing Fixtures, Appliances, and Appurtenances | Fittings | Table 603.2 |
| <i>ASME A112.3.1-2007 (R2012)*</i> | Stainless Steel Drainage Systems for Sanitary DWV, Storm, and Vacuum Applications, Above- and Below-Ground (Notes 1 and 7) | Piping, Ferrous | 418.1, 705.6.2, 1102.1, Table 701.2 |
| <i>ASME A112.3.4-2013/CSA B45.9-2013*</i> | Plumbing Fixtures with Pumped Waste and Macerating Toilet Systems | Fixtures | 710.13 |
| ASME A112.4.1-2009* | Water Heater Relief Valve Drain Tubes | Appliances | 301.2.2, 301.3 |
| ASME A112.4.2-2009* | Water Closet Personal Hygiene Devices | Fixtures | 301.2.2, 301.3 |
| ASME A112.4.3-1999 (R2010)* | Plastic Fittings for Connecting Water Closets to the Sanitary Drainage System | Fittings | 301.2.2, 301.3 |
| <i>ASME A112.4.14-2004 (R2010)*</i> | Manually Operated, Quarter-Turn Shutoff Valves for Use in Plumbing Systems | Valves | 606.1 |
| ASME A112.6.1M-1997 (R2012)* | Floor-Affixed Supports for Off-the-Floor Plumbing Fixtures for Public Use | Fixtures | 301.2.2, 301.3 |
| ASME A112.6.2-2000 (R2010)* | Framing-Affixed Supports for Off-the-Floor Water Closets with Concealed Tanks | Fixtures | 301.2.2, 301.3 |
| <i>ASME A112.6.3-2001 (R2007)*</i> | Floor and Trench Drains | DWV Components | 418.1 |
| <i>ASME A112.6.4-2003 (R2012)*</i> | Roof, Deck, and Balcony Drains | DWV Components | 1102.1 |
| <i>ASME A112.6.7-2010*</i> | Sanitary Floor Sinks | Fixtures | 421.1 |
| ASME A112.6.9-2005 (R2010)* | Siphonic Roof Drains | DWV Components | 301.2.2, 301.3 |
| <i>ASME A112.14.1-2003 (R2012)*</i> | Backwater Valves | Valves | 710.6 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|---|---|---------------------|--|
| <i>ASME A112.14.3-2000 (R2004)*</i> | Grease Interceptors | Fixtures | 1014.1 |
| <i>ASME A112.14.4-2001 (R2012)*</i> | Grease Removal Devices | Fixtures | 1014.1 |
| <i>ASME A112.14.6-2010*</i> | FOG (Fats, Oils, and Greases) Disposal Systems | Fixtures | 1015.2, 1015.4 |
| <i>ASME A112.18.1-2012/CSA B125.1-2012*</i> | Plumbing Supply Fittings | Fittings | 402.9, 407.2.1, 407.2.2, 408.2, 408.3, 417.1, 417.2, 417.3, 417.4, 420.2, 420.3, 603.5.19, L 402.5.1, L 402.5.2.1, L 402.6, L 402.6.2, L 402.6.3 |
| ASME A112.18.2-2011/CSA B125.2-2011* | Plumbing Waste Fittings | Fittings | 301.2.2, 301.3 |
| <i>ASME A112.18.3-2002 (R2012)*</i> | Performance Requirements for Backflow Protection Devices and Systems in Plumbing Fixture Fittings | Backflow Protection | 417.3, 417.4 |
| <i>ASME A112.18.6-2009/CSA B125.6-2009*</i> | Flexible Water Connectors | Piping | 604.5, 604.13 |
| <i>ASME A112.18.9-2011*</i> | Protectors/Insulators for Exposed Waste and Supplies on Accessible Fixtures | Miscellaneous | 403.3 |
| <i>ASME A112.19.1-2013/CSA B45.2-2013*</i> | Enamelled Cast Iron and Enamelled Steel Plumbing Fixtures | Fixtures | 407.1, 408.1, 409.1, 415.1, 420.1 |
| <i>ASME A112.19.2-2013/CSA B45.1-2013*</i> | Ceramic Plumbing Fixtures | Fixtures | 407.1, 408.1, 409.1, 410.1, 411.1, 411.2, 411.2.2, 412.1, 415.1, 420.1, L 402.2.1, L 402.2.2, L 402.3 |
| <i>ASME A112.19.3-2008/CSA B45.4-2008*</i> | Stainless Steel Plumbing Fixtures | Fixtures | 407.1, 408.1, 409.1, 410.1, 411.1, 415.1, 420.1, L 402.3.1 |
| <i>ASME A112.19.5-2011/CSA B45.15-2011*</i> | Flush Valves and Spuds for Water Closets, Urinals, and Tanks | Fixtures | 413.3 |
| <i>ASME A112.19.7-2012/CSA B45.10-2012*</i> | Hydromassage Bathtub Systems | Fixtures | 409.1, 409.6, 413.3 |
| ASME A112.19.10-2003 (R2008)* | Dual Flush Devices for Water Closets | Fixtures | 301.2.2, 301.3 |
| <i>ASME A112.19.12-2006 (R2011)*</i> | Wall Mounted, Pedestal Mounted, Adjustable, Elevating, Tilting, and Pivoting Lavatory, Sink, and Shampoo Bowl Carrier Systems and Drain Waste Systems | Fixtures | 407.1, 420.1 |
| <i>ASME A112.19.14-2013*</i> | Six-Liter Water Closets Equipped with a Dual Flushing Device | Fixtures | 411.2.1, L 402.2.1 |
| <i>ASME A112.19.15-2012*</i> | Bathtubs/Whirlpool Bathtubs with Pressure Sealed Doors | Fixtures | 409.1 |
| <i>ASME A112.19.19-2006 (R2011)*</i> | Vitreous China Nonwater Urinals | Fixtures | 412.1, L 402.3.1 |
| ASME A112.21.3M-1985 (R2007)* | Hydrants for Utility and Maintenance Use (Note 1) | Valves | 301.2.2, 301.3 |
| ASME A112.36.2M-1991 (R2012)* | Cleanouts (Note 1) | DWV Components | 301.2.2, 301.3 |
| <i>ASME B1.20.1-2013*</i> | Pipe Threads, General Purpose, Inch | Joints | 605.1.5, 605.2.3, 605.5.2, 605.12.3, 705.1.3, 705.3.4, 705.4.2, 705.5.3, 1208.5.7, 1309.4.3(2) |
| ASME B1.20.3-1976 (R2013)* | Dryseal Pipe Threads, (Inch) | Joints | 301.2.2, 301.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|-----------------------------------|---|-----------------|--------------------------|
| <i>ASME B16.1-2010*</i> | Gray Iron Pipe Flanges and Flanged Fittings: Classes 25, 125, and 250 | Fittings | 1208.5.10 |
| <i>ASME B16.3-2011*</i> | Malleable Iron Threaded Fittings: Classes 150 and 300 | Fittings | Table 604.1, Table 701.2 |
| <i>ASME B16.4-2011*</i> | Gray Iron Threaded Fittings: Classes 125 and 250 | Fittings | Table 604.1 |
| ASME B16.5-2013* | Pipe Flanges and Flanged Fittings: NPS 1/2 through NPS 24 Metric/Inch | Fittings | 301.2.2, 301.3 |
| <i>ASME B16.12-2009*</i> | Cast Iron Threaded Drainage Fittings (Note 1) | Fittings | Table 701.2 |
| <i>ASME B16.15-2013*</i> | Cast Copper Alloy Threaded Fittings: Classes 125 and 250 | Fittings | Table 604.1 |
| <i>ASME B16.18-2012*</i> | Cast Copper Alloy Solder Joint Pressure Fittings (Note 1) | Fittings | Table 604.1 |
| <i>ASME B16.20-2012*</i> | Metallic Gaskets For Pipe Flanges: Ring-Joint, Spiral-Wound, and Jacketed | Joints | 1208.5.10 |
| ASME B16.21-2011* | Nonmetallic Flat Gaskets for Pipe Flanges | Joints | 301.2.2, 301.3 |
| <i>ASME B16.22-2013*</i> | Wrought Copper and Copper Alloy Solder-Joint Pressure Fittings | Fittings | 1309.3, Table 604.1 |
| <i>ASME B16.23-2011*</i> | Cast Copper Alloy Solder Joint Drainage Fittings: DWV | Fittings | Table 701.2 |
| ASME B16.24-2011* | Cast Copper Alloy Pipe Flanges and Flanged Fittings: Classes 150, 300, 600, 900, 1500, and 2500 | Fittings | 301.2.2, 301.3 |
| <i>ASME B16.26-2013*</i> | Cast Copper Alloy Fittings for Flared Copper Tubes | Fittings | 1309.2, Table 604.1 |
| <i>ASME B16.29-2012*</i> | Wrought Copper and Wrought Copper Alloy Solder-Joint Drainage Fittings – DWV (Note 1) | Fittings | Table 701.2 |
| ASME B16.33-2012* | Manually Operated Metallic Gas Valves for Use in Gas Piping Systems Up to 175 psi (Sizes NPS 1/2 through NPS 2) | Valves | 301.2.2, 301.3 |
| <i>ASME B16.34-2013*</i> | Valves – Flanged, Threaded, and Welding End | Valves | 606.1 |
| ASME B16.39-2009* | Malleable Iron Threaded Pipe Unions: Classes 150, 250 and 300 (Includes Revision Services) | Fittings | 301.2.2, 301.3 |
| ASME B16.40-2013* | Manually Operated Thermoplastic Gas Shutoffs and Valves in Gas Distribution Systems | Valves | 301.2.2, 301.3 |
| ASME B16.47-2011* | Large Diameter Steel Flanges: NPS 26 through NPS 60 Metric/Inch | Fittings | 301.2.2, 301.3 |
| <i>ASME B16.50-2013*</i> | Wrought Copper and Copper Alloy Braze-Joint Pressure Fittings | Fittings | 1309.3, 1309.3.9 |
| <i>ASME B16.51-2013*</i> | Copper and Copper Alloy Press-Connect Pressure Fittings | Fittings | Table 604.1 |
| ASME B31.1-2012* | Power Piping | Piping | 301.2.2, 301.3 |
| <i>ASME B31.3-2012*</i> | Process Piping | Piping | F 1201.1 |
| <i>ASME B36.10M-2004 (R2010)*</i> | Welded and Seamless Wrought Steel Pipe | Piping, Ferrous | 1208.5.2.1(1) |
| ASME B36.19-2004 (R2010)* | Stainless Steel Pipe | Piping, Ferrous | 301.2.2, 301.3 |
| ASME BPVC Section IV-2013* | Rules for Construction of Heating Boilers | Miscellaneous | 301.2.2, 301.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|---|---|------------------------|-----------------------------------|
| <i>ASME BPVC Section VIII-2013*</i> | Rules for Construction of Pressure Vessels Division 1 | Miscellaneous | 1314.2(2), 1315.4(2), E 413.6.2 |
| <i>ASME BPVC Section IX-2013*</i> | Welding, Brazing, and Fusing Qualifications | Certification | 225.0, 1307.1, 1309.5.1, 1309.5.2 |
| <i>ASSE 1001-2008*</i> | Atmospheric Type Vacuum Breakers | Backflow Protection | Table 603.2 |
| <i>ASSE 1002-2008*</i> | Anti-Siphon Fill Valves for Water Closet Tanks | Backflow Protection | 413.3, Table 603.2 |
| ASSE 1003-2009* | Water Pressure Reducing Valves for Domestic Water Distribution Systems | Valves | 301.2.2, 301.3 |
| <i>ASSE 1004-2008*</i> | Backflow Prevention Requirements for Commercial Dishwashing Machines | Backflow Protection | 414.2 |
| <i>ASSE 1008-2006*</i> | Plumbing Aspects of Residential Food Waste Disposer Units | Appliances | 419.1 |
| <i>ASSE 1010-2004*</i> | Water Hammer Arresters | Water Supply Component | 609.10 |
| <i>ASSE 1011-2004*</i> | Hose Connection Vacuum Breakers | Backflow Protection | Table 603.2 |
| ASSE 1012-2009* | Backflow Preventers with an Intermediate Atmospheric Vent | Backflow Protection | 301.2.2, 301.3 |
| <i>ASSE 1013-2011*</i> | Reduced Pressure Principle Backflow Preventers and Reduced Pressure Principle Fire Protection Backflow Preventers | Backflow Protection | Table 603.2 |
| <i>ASSE 1014-2005*</i> | Backflow Prevention Devices for Hand-Held Shower | Backflow Protection | 417.3 |
| <i>ASSE 1015-2011*</i> | Double Check Backflow Prevention Assemblies and Double Check Fire Protection Backflow Prevention Assemblies | Backflow Protection | Table 603.2 |
| <i>ASSE 1016-2011/ ASME A112.1016-2011/ CSA B125.16-2011*</i> | Automatic Compensating Valves for Individual Showers and Tub/Shower Combinations | Valves | 408.3, L 402.6.3 |
| ASSE 1017-2009* | Temperature Actuated Mixing Valves for Hot Water Distribution Systems | Valves | 301.2.2, 301.3 |
| ASSE 1018-2001* | Trap Seal Primer Valves - Potable Water Supplied | Valves | 301.2.2, 301.3 |
| <i>ASSE 1019-2011*</i> | Wall Hydrant with Backflow Protection and Freeze Resistance | Backflow Protection | Table 603.2 |
| <i>ASSE 1020-2004*</i> | Pressure Vacuum Breaker Assembly | Backflow Protection | Table 603.2 |
| <i>ASSE 1022-2003*</i> | Backflow Preventer for Beverage Dispensing Equipment | Backflow Protection | 603.5.12, Table 603.2 |
| ASSE 1023-1979 | Hot Water Dispensers Household Storage Type - Electrical | Appliances | 301.2.2, 301.3 |
| ASSE 1024-2004* | Dual Check Backflow Preventers | Backflow Protection | 301.2.2, 301.3 |
| ASSE 1032-2004 (R2011)* | Dual Check Valve Type Backflow Preventers for Carbonated Beverage Dispensers, Post Mix Type | Backflow Protection | 301.2.2, 301.3 |
| ASSE 1035-2008* | Laboratory Faucet Backflow Preventers | Backflow Protection | 301.2.2, 301.3 |
| <i>ASSE 1037-1990</i> | Pressurized Flushing Devices (Flushometers) for Plumbing Fixtures | Backflow Protection | 413.2 |
| ASSE 1044-2001* | Trap Seal Primer Devices - Drainage Types and Electronic Design Types | DWV Components | 301.2.2, 301.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|-------------------------------|---|---------------------|---|
| <i>ASSE 1047-2011*</i> | Reduced Pressure Detector Fire Protection Backflow Prevention Assemblies | Backflow Protection | Table 603.2 |
| <i>ASSE 1048-2011*</i> | Double Check Detector Fire Protection Backflow Prevention Assemblies | Backflow Protection | Table 603.2 |
| <i>ASSE 1052-2004*</i> | Hose Connection Backflow Preventers | Backflow Protection | Table 603.2 |
| <i>ASSE 1053-2004</i> | Dual Check Backflow Preventer Wall Hydrants – Freeze Resistant Type | Backflow Protection | Table 603.2 |
| ASSE 1055-2009* | Chemical Dispensing Systems | Backflow Protection | 301.2.2, 301.3 |
| <i>ASSE 1056-2013*</i> | Spill Resistant Vacuum Breaker Assemblies | Backflow Protection | Table 603.2 |
| <i>ASSE 1057-2012</i> | Freeze Resistant Sanitary Yard Hydrants with Backflow Protection | Backflow Protection | Table 603.2 |
| <i>ASSE 1060-2006*</i> | Outdoor Enclosures for Fluid Conveying Components | Miscellaneous | 603.4.7 |
| <i>ASSE 1061-2011*</i> | Push-Fit Fittings | Fittings | 605.1.3.3, 605.2.1, Table 604.1 |
| ASSE 1062-2006* | Temperature Actuated, Flow, Reduction (TAFR) Valves for Individual Fixture Fittings | Valves | 301.2.2, 301.3 |
| ASSE 1066-1997 | Individual Pressure Balancing In-Line Valves for Individual Fixture Fittings (Note 6) | Valves | 301.2.2, 301.3 |
| <i>ASSE 1069-2005*</i> | Automatic Temperature Control Mixing Valves | Valves | 408.3 |
| <i>ASSE 1070-2004*</i> | Water Temperature Limiting Devices | Valves | 407.3, 409.4, 410.3 |
| ASSE 1071-2012 | Temperature Actuated Mixing Valves for Plumbed Emergency Equipment | Valves | 301.2.2, 301.3 |
| <i>ASSE 1079-2012</i> | Dielectric Pipe Unions | Joints | 605.15, 605.16.1, 605.16.3 |
| <i>ASSE Series 5000-2009*</i> | Cross-Connection Control Professional Qualifications | Certification | 603.2 |
| <i>ASSE Series 6000-2012*</i> | Professional Qualifications Standard for Medical Gas Systems Personnel | Certification | 1306.1, 1319.12.2 |
| <i>ASSE Series 7000-2013*</i> | Residential Potable Water Fire Protection System Installers & Inspectors for One and Two Family Dwellings | Miscellaneous | 612.1 |
| ASTM A47/A47M-1999 (R2009) | Ferritic Malleable Iron Castings | Piping, Ferrous | 301.2.2, 301.3 |
| ASTM A48/A48M-2003 (R2012) | Gray Iron Castings | Piping, Ferrous | 301.2.2, 301.3 |
| <i>ASTM A53/A53M-2012</i> | Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless | Piping, Ferrous | 1208.5.2.1(2), Table 604.1, Table 701.2 |
| <i>ASTM A74-2013a</i> | Cast Iron Soil Pipe and Fittings (Notes 1 and 7) | Piping, Ferrous | Table 701.2 |
| <i>ASTM A106/A106M-2013</i> | Seamless Carbon Steel Pipe for High-Temperature Service | Piping, Ferrous | 1208.5.2.1(3) |
| ASTM A126-2004 (R2009) | Gray Iron Castings for Valves, Flanges, and Pipe Fittings | Piping, Ferrous | 301.2.2, 301.3 |
| ASTM A197/A197M-2000 (R2011) | Cupola Malleable Iron | Piping, Ferrous | 301.2.2, 301.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|--|--|----------------------|--|
| <i>ASTM A254/A254M-2012</i> | Copper-Brazed Steel Tubing | Piping, Ferrous | 1208.5.3.1, E 409.1 |
| <i>ASTM A269-2013</i> | Seamless and Welded Austenitic Stainless Steel Tubing for General Service | Piping, Ferrous | F 801.2, Table 604.1 |
| <i>ASTM A312/A312M-2013b</i> | Seamless, Welded, and Heavily Cold Worked Austenitic Stainless Steel Pipes | Piping, Ferrous | Table 604.1 |
| ASTM A377-2003 (R2008) ^{e1} | Ductile-Iron Pressure Pipe | Piping, Ferrous | 301.2.2, 301.3 |
| <i>ASTM A479/A479M-2013b</i> | Stainless Steel Bars and Shapes for Use in Boilers and Other Pressure Vessels | Piping, Ferrous | F 801.3 |
| ASTM A518/A518M-1999 (R2012) | Corrosion-Resistant High-Silicon Iron Castings | Piping, Ferrous | 301.2.2, 301.3 |
| ASTM A536-1984 (R2009) | Ductile Iron Castings | Piping, Ferrous | 301.2.2, 301.3 |
| ASTM A653/A653M-2013 | Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process | Piping, Ferrous | 301.2.2, 301.3 |
| ASTM A733-2013 | Welded and Seamless Carbon Steel and Austenitic Stainless Steel Pipe Nipples | Piping, Ferrous | 301.2.2, 301.3 |
| <i>ASTM A861-2004 (R2013)</i> | High-Silicon Iron Pipe and Fittings (Note 1) | Piping, Ferrous | 811.2 |
| <i>ASTM A888-2013a</i> | Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste, and Vent Piping Applications (Note 7) | Piping, Ferrous | Table 701.2 |
| ASTM A1045-2010 | Flexible Poly (Vinyl Chloride) (PVC) Gaskets used in Connection of Vitreous China Plumbing Fixtures to Sanitary Drainage Systems | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM A1056-2012</i> | Cast Iron Couplings used for Joining Hubless Cast Iron Soil Pipe and Fittings | Piping, Ferrous | 705.2.2 |
| ASTM B29-2003 (R2009) | Refined Lead | Joints | 301.2.2, 301.3 |
| <i>ASTM B32-2008</i> | Solder Metal (Note 2) | Joints | 605.1.4, 705.3.3, 1309.2 |
| <i>ASTM B42-2010</i> | Seamless Copper Pipe, Standard Sizes | Piping, Copper Alloy | Table 604.1 |
| <i>ASTM B43-2009</i> | Seamless Red Brass Pipe, Standard Sizes | Piping, Copper Alloy | Table 604.1, Table 701.2 |
| <i>ASTM B75/B75M-2011</i> | Seamless Copper Tube (Note 7) | Piping, Copper Alloy | Table 604.1, Table 701.2 |
| <i>ASTM B88-2009</i> | Seamless Copper Water Tube | Piping, Copper Alloy | 604.4, 903.2.3, 1208.5.3.2, 1308.5(1)(a), E 409.1, Table 604.1 |
| <i>ASTM B135-2010</i> | Seamless Brass Tube | Piping, Copper Alloy | Table 604.1 |
| <i>ASTM B152/B152M-2013</i> | Copper Sheet, Strip, Plate, and Rolled Bar | Miscellaneous | 408.7.4 |
| ASTM B187/B187M-2011 | Copper, Bus Bar, Rod, and Shapes and General Purpose Rod, Bar, and Shapes | Miscellaneous | 301.2.2, 301.3 |
| <i>ASTM B210-2012</i> | Aluminum and Aluminum-Alloy Drawn Seamless Tubes | Piping, Ferrous | 1208.5.3.3 |
| <i>ASTM B241/B241M-2012^{e1}</i> | Aluminum and Aluminum-Alloy Seamless Pipe and Seamless Extruded Tube | Piping, Ferrous | 1208.5.2.3, 1208.5.3.3 |
| <i>ASTM B251-2010</i> | General Requirements for Wrought Seamless Copper and Copper-Alloy Tube (Note 7) | Piping, Copper Alloy | Table 604.1, Table 701.2 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|---------------------------------------|---|----------------------|-----------------------------------|
| <i>ASTM B280-2013</i> | Seamless Copper Tube for Air Conditioning and Refrigeration Field Service | Piping, Copper Alloy | 1208.5.3.2, 1308.5(1)(b), E 409.1 |
| <i>ASTM B302-2012</i> | Threadless Copper Pipe, Standard Sizes (Note 7) | Piping, Copper Alloy | Table 604.1, Table 701.2 |
| <i>ASTM B306-2013</i> | Copper Drainage Tube (DWV) (Note 7) | Piping, Copper Alloy | 903.2.3, Table 701.2 |
| ASTM B370-2012 | Copper Sheet and Strip for Building Construction | Miscellaneous | 301.2.2, 301.3 |
| <i>ASTM B447-2012a</i> | Welded Copper Tube | Piping, Copper Alloy | Table 604.1 |
| ASTM B584-2013 | Copper Alloy Sand Castings for General Applications (Note 3) | Piping, Copper Alloy | 301.2.2, 301.3 |
| ASTM B587-2012 | Welded Brass Tube | Piping, Copper Alloy | 301.2.2, 301.3 |
| ASTM B687-1999 (R2011) | Brass, Copper, and Chromium-Plated Pipe Nipples | Piping, Copper Alloy | 301.2.2, 301.3 |
| <i>ASTM B813-2010</i> | Liquid and Paste Fluxes for Soldering of Copper and Copper Alloy Tube | Joints | 605.1.4, 705.3.3 |
| <i>ASTM B819-2000 (R2011)</i> | Seamless Copper Tube for Medical Gas Systems | Piping, Copper Alloy | 1308.4, 1308.5(1)(c) |
| <i>ASTM B828-2002 (R2010)</i> | Making Capillary Joints by Soldering of Copper and Copper Alloy Tube and Fittings | Joints | 605.1.4, 705.3.3, 1309.2 |
| <i>ASTM C4-2004 (R2009)</i> | Clay Drain Tile and Perforated Clay Drain Tile | Piping, Non-Metallic | Table 1101.4.6 |
| ASTM C14-2011 | Nonreinforced Concrete Sewer, Storm Drain, and Culvert Pipe (Note 7) | Piping, Non-Metallic | 301.2.2, 301.3 |
| ASTM C412-2011 | Concrete Drain Tile | Piping, Non-Metallic | 301.2.2, 301.3 |
| <i>ASTM C425-2004 (R2013)</i> | Compression Joints for Vitrified Clay Pipe and Fittings | Joints | 705.7.1 |
| ASTM C443-2012 | Joints for Concrete Pipe and Manholes, Using Rubber Gaskets | Joints | 301.2.2, 301.3 |
| ASTM C444-2003 (R2009) | Perforated Concrete Pipe | Piping, Non-Metallic | 301.2.2, 301.3 |
| ASTM C478-2013 | Precast Reinforced Concrete Manhole Sections | Miscellaneous | 301.2.2, 301.3 |
| <i>ASTM C564-2012</i> | Rubber Gaskets for Cast Iron Soil Pipe and Fittings | Joints | 705.2.2 |
| <i>ASTM C700-2013</i> | Vitrified Clay Pipe, Extra Strength, Standard Strength, and Perforated (Note 7) | Piping, Non-Metallic | Table 701.2, Table 1101.4.6 |
| <i>ASTM C1053-2000 (R2010)</i> | Borosilicate Glass Pipe and Fittings for Drain, Waste, and Vent (DWV) Applications (Note 1) | Piping, Non-Metallic | 811.2 |
| <i>ASTM C1173-2010^{e1}</i> | Flexible Transition Couplings for Underground Piping Systems | Joints | 705.9 |
| ASTM C1227-2013 | Precast Concrete Septic Tanks | DWV Components | 301.2.2, 301.3 |
| <i>ASTM C1277-2012</i> | Shielded Couplings Joining Hubless Cast Iron Soil Pipe and Fittings | DWV Components | 301.2.4, 705.2.2 |
| ASTM C1440-2008 (R2013) ^{e1} | Thermoplastic Elastomeric (TPE) Gasket Materials for Drain, Waste, and Vent (DWV), Sewer, Sanitary and Storm Plumbing Systems | Joints | 301.2.2, 301.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|--------------------------------------|---|-----------------|--|
| <i>ASTM C1460-2012</i> | Shielded Transition Couplings for Use With Dissimilar DWV Pipe and Fittings Above Ground | Joints | 705.9 |
| <i>ASTM C1461-2008 (R2013)</i> | Mechanical Couplings Using Thermoplastic Elastomeric (TPE) Gaskets for Joining Drain, Waste, and Vent (DWV), Sewer, Sanitary, and Storm Plumbing Systems for Above and Below Ground Use | Joints | 705.9 |
| <i>ASTM C1540-2011</i> | Heavy Duty Shielded Couplings Joining Hubless Cast Iron Soil Pipe and Fittings | Joints | 705.2.2 |
| <i>ASTM C1563-2004</i> | Gaskets for Use in Connection with Hub & Spigot Cast Iron Soil Pipe and Fittings for Sanitary Drain, Waste, Vent, and Storm Piping Applications | Joints | 705.2.2 |
| ASTM D1784-2011 | Rigid Poly (Vinyl Chloride) (PVC) Compounds and Chlorinated Poly (Vinyl Chloride) (CPVC) Compounds | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM D1785-2012*</i> | Poly (Vinyl Chloride) (PVC) Plastic Pipe, Schedules 40, 80, and 120 (Note 7) | Piping, Plastic | 1308.5, Table 604.1, Table 701.2 |
| <i>ASTM D2235-2004 (R2011)*</i> | Solvent Cement for Acrylonitrile-Butadiene-Styrene (ABS) Plastic Pipe and Fittings | Joints | 705.1.2 |
| <i>ASTM D2239-2012a*</i> | Polyethylene (PE) Plastic Pipe (SIDR-PR) Based on Controlled Inside Diameter | Piping, Plastic | Table 604.1 |
| <i>ASTM D2241-2009*</i> | Poly (Vinyl Chloride) (PVC) Pressure-Rated Pipe (SDR Series) | Piping, Plastic | Table 604.1 |
| ASTM D2321-2011* | Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications (Note 7) | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM D2464-2013*</i> | Threaded Poly (Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 80 (Note 1) | Fittings | Table 604.1 |
| <i>ASTM D2466-2013*</i> | Poly (Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 40 (Note 1) | Fittings | 1309.2, Table 604.1 |
| <i>ASTM D2467-2013a*</i> | Poly (Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 80 (Note 1) | Fittings | 1309.2, Table 604.1 |
| <i>ASTM D2513-2013*</i> | Polyethylene (PE) Gas Pressure Pipe, Tubing, and Fittings (Note 1) | Piping, Plastic | 1208.5.4, 1208.5.4.2.2, 1208.5.9.2, 1210.1.7.1(1), E 409.3 |
| <i>ASTM D2517-2006 (R2011)*</i> | Reinforced Epoxy Resin Gas Pressure Pipe and Fittings | Piping, Plastic | E 409.3 |
| <i>ASTM D2564-2012*</i> | Solvent Cements for Poly (Vinyl Chloride) (PVC) Plastic Piping Systems | Joints | 605.12.2, 705.5.2 |
| <i>ASTM D2609-2002 (R2008)*</i> | Plastic Insert Fittings for Polyethylene (PE) Plastic Pipe (Note 1) | Fittings | Table 604.1 |
| ASTM D2657-2007* | Heat Fusion Joining of Polyolefin Pipe and Fittings (Note 1) | Joints | 301.2.2, 301.3 |
| <i>ASTM D2661-2011*</i> | Acrylonitrile-Butadiene-Styrene (ABS) Schedule 40 Plastic Drain, Waste, and Vent Pipe and Fittings (Notes 1 and 7) | Piping, Plastic | Table 701.2 |
| <i>ASTM D2665-2012*</i> | Poly (Vinyl Chloride) (PVC) Plastic Drain, Waste, and Vent Pipe and Fittings (Note 7) | Piping, Plastic | Table 701.2 |
| <i>ASTM D2672-1996a (R2009)*</i> | Joints for IPS PVC Pipe Using Solvent Cement | Joints | 1309.2 |
| <i>ASTM D2680-2001 (R2009)*</i> | Acrylonitrile-Butadiene-Styrene (ABS) and Poly (Vinyl Chloride) (PVC) Composite Sewer Piping (Note 7) | Piping, Plastic | Table 701.2 |
| <i>ASTM D2683-2010^{e1}*</i> | Socket-Type Polyethylene Fittings for Outside Diameter-Controlled Polyethylene Pipe and Tubing | Fittings | Table 604.1 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|--|--|-----------------|---|
| <i>ASTM D2729-2011*</i> | Poly (Vinyl Chloride) (PVC) Sewer Pipe and Fittings (Notes 1 and 7) | Piping, Plastic | Table 1101.4.6 |
| <i>ASTM D2737-2012a*</i> | Polyethylene (PE) Plastic Tubing | Piping, Plastic | Table 604.1 |
| ASTM D2751-2005* | Acrylonitrile-Butadiene-Styrene (ABS) Sewer Pipe and Fittings (Notes 1 and 7) | Piping, Plastic | 301.2.2, 301.3 |
| ASTM D2774-2012* | Underground Installation of Thermoplastic Pressure Piping | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM D2846/D2846M-2009b^{e1}*</i> | Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Hot- and Cold-Water Distribution Systems | Piping, Plastic | 605.2.2, 605.3.1, 1308.5, 1309.2, Table 604.1 |
| ASTM D2855-1996 (R2010)* | Making Solvent-Cemented Joints with Poly (Vinyl Chloride) (PVC) Pipe and Fittings | Joints | 301.2.2, 301.3 |
| ASTM D2996-2001 (R2007) ^{e1} * | Filament-Wound "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Pipe | Piping, Plastic | 301.2.2, 301.3 |
| ASTM D3034-2008* | Type PSM Poly (Vinyl Chloride) (PVC) Sewer Pipe and Fittings (Note 7) | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM D3035-2012^{e2}*</i> | Polyethylene (PE) Plastic Pipe (DR-PR) Based on Controlled Outside Diameter | Piping, Plastic | Table 604.1 |
| ASTM D3122-1995 (R2009)* | Solvent Cements for Styrene-Rubber (SR) Plastic Pipe and Fittings | Joints | 301.2.2, 301.3 |
| <i>ASTM D3138-2004 (R2011)*</i> | Solvent Cements for Transition Joints Between Acrylonitrile-Butadiene-Styrene (ABS) and Poly (Vinyl Chloride) (PVC) Non-Pressure Piping Components | Joints | 705.8.4 |
| <i>ASTM D3139-1998 (R2011)*</i> | Joints for Plastic Pressure Pipes Using Flexible Elastomeric Seals | Joints | 605.12.1 |
| <i>ASTM D3212-2007 (R2013)*</i> | Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals | Joints | 705.1.1, 705.5.1 |
| <i>ASTM D3261-2012^{e1}*</i> | Butt Heat Fusion Polyethylene (PE) Plastic Fittings for Polyethylene (PE) Plastic Pipe and Tubing | Fittings | Table 604.1 |
| ASTM D3311-2011* | Drain, Waste, and Vent (DWV) Plastic Fittings Patterns (Note 1) | Fittings | 301.2.2, 301.3 |
| ASTM D3965-2011 | Rigid Acrylonitrile-Butadiene-Styrene (ABS) Materials for Pipe and Fittings | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM D4068-2009*</i> | Chlorinated Polyethylene (CPE) Sheeting for Concealed Water-Containment Membrane | Miscellaneous | 408.7.2 |
| ASTM D4101-2011 | Polypropylene Injection and Extrusion Materials | Miscellaneous | 301.2.2, 301.3 |
| <i>ASTM D4551-2012*</i> | Poly (Vinyl Chloride) (PVC) Plastic Flexible Concealed Water-Containment Membrane | Miscellaneous | 408.7.1 |
| ASTM D6104-1997 (R2011) | Determining the Performance of Oil/Water Separators Subjected to Surface Run-Off | Miscellaneous | 301.2.2, 301.3 |
| <i>ASTM E84-2013a*</i> | Surface Burning Characteristics of Building Materials | Miscellaneous | 701.2(2), 903.1(2), 1101.4 |
| <i>ASTM E119-2012a*</i> | Fire Tests of Building Construction and Materials | Miscellaneous | 1404.3, 1405.3 |
| <i>ASTM E814-2013a*</i> | Fire Tests of Penetration Firestop Systems | Miscellaneous | 208.0, 222.0, 1404.3, 1405.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|---|--|-----------------|-------------------------------------|
| ASTM F402-2005 (R2012)* | Safe Handling of Solvent Cements, Primers, and Cleaners Used for Joining Thermoplastic Pipe and Fittings | Joints | 301.2.2, 301.3 |
| <i>ASTM F405-2013*</i> | Corrugated Polyethylene (PE) Pipe and Fittings | Piping, Plastic | Table 1101.4.6 |
| ASTM F409-2012* | Thermoplastic Accessible and Replaceable Plastic Tube and Tubular Fittings (Note 1) | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM F437-2009*</i> | Threaded Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80 | Fittings | Table 604.1 |
| <i>ASTM F438-2009*</i> | Socket-Type Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 40 | Fittings | 1309.2, Table 604.1 |
| <i>ASTM F439-2013*</i> | Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80 | Fittings | 1309.2, Table 604.1 |
| <i>ASTM F441/F441M-2013^{e1}*</i> | Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe, Schedules 40 and 80 | Piping, Plastic | 1308.5, Table 604.1 |
| <i>ASTM F442/F442M-2013^{e1}*</i> | Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe (SDR-PR) | Piping, Plastic | 605.2.2, Table 604.1 |
| ASTM F446-1985 (R2009) | Grab Bars and Accessories Installed in the Bathing Area | Miscellaneous | 301.2.2, 301.3 |
| ASTM F480-2012* | Thermoplastic Well Casing Pipe and Couplings Made in Standard Dimension Ratios (SDR), SCH 40 and SCH 80 | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM F493-2010*</i> | Solvent Cements for Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe and Fittings | Joints | 605.2.2, 605.3.1, 1309.2 |
| <i>ASTM F628-2012^{e1}*</i> | Acrylonitrile-Butadiene-Styrene (ABS) Schedule 40 Plastic Drain, Waste, and Vent Pipe with a Cellular Core (Notes 1 and 7) | Piping, Plastic | Table 701.2 |
| <i>ASTM F656-2010*</i> | Primers for Use in Solvent Cement Joints of Poly (Vinyl Chloride) (PVC) Plastic Pipe and Fittings | Joints | 605.2.2, 605.3.1, 605.12.2, 705.5.2 |
| ASTM F667-2012* | 3 through 24 in. Corrugated Polyethylene Pipe and Fittings | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM F714-2013*</i> | Polyethylene (PE) Plastic Pipe (DR-PR) Based on Outside Diameter | Piping, Plastic | Table 701.2 |
| <i>ASTM F794-2003 (R2009)*</i> | Poly (Vinyl Chloride) (PVC) Profile Gravity Sewer Pipe and Fittings Based on Controlled Inside Diameter (Note 7) | Piping, Plastic | Table 701.2 |
| ASTM F810-2012* | Smoothwall Polyethylene (PE) Pipe for Use in Drainage and Waste Disposal Absorption Fields | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM F876-2013a*</i> | Crosslinked Polyethylene (PEX) Tubing | Piping, Plastic | 605.9.1, Table 604.1 |
| <i>ASTM F877-2011a*</i> | Crosslinked Polyethylene (PEX) Hot- and Cold-Water Distribution Systems | Piping, Plastic | Table 604.1 |
| <i>ASTM F891-2010*</i> | Coextruded Poly (Vinyl Chloride) (PVC) Plastic Pipe with a Cellular Core (Note 7) | Piping, Plastic | Table 701.2 |
| ASTM F894-2013* | Polyethylene (PE) Large Diameter Profile Wall Sewer and Drain Pipe (Note 7) | Piping, Plastic | 301.2.2, 301.3 |
| ASTM F949-2010* | Poly (Vinyl Chloride) (PVC) Corrugated Sewer Pipe with a Smooth Interior and Fittings (Note 7) | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM F1055-2013*</i> | Electrofusion Type Polyethylene Fittings for Outside Diameter Controlled Polyethylene and Crosslinked Polyethylene (PEX) Pipe and Tubing | Fittings | Table 604.1 |
| <i>ASTM F1216-2009*</i> | Rehabilitation of Existing Pipelines and Conduits by the Inversion and Curing of a Resin-Impregnated Tube | Piping, Plastic | 715.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|--------------------------------------|--|-----------------|--------------------------------|
| <i>ASTM F1281-2011*</i> | Crosslinked Polyethylene/Aluminum/Crosslinked Polyethylene (PEX-AL-PEX) Pressure Pipe | Piping, Plastic | Table 604.1 |
| <i>ASTM F1282-2010*</i> | Polyethylene/Aluminum/Polyethylene (PE-AL-PE) Composite Pressure Pipe | Piping, Plastic | Table 604.1 |
| ASTM F1336-2007* | Poly (Vinyl Chloride) (PVC) Gasketed Sewer Fittings | Fittings | 301.2.2, 301.3 |
| <i>ASTM F1412-2009*</i> | Polyolefin Pipe and Fittings for Corrosive Waste Drainage Systems | Piping, Plastic | 811.2 |
| ASTM F1476-2007 (R2013)* | Performance of Gasketed Mechanical Couplings for Use in Piping Applications | Joints | 301.2.2, 301.3 |
| <i>ASTM F1488-2009^{e1}*</i> | Coextruded Composite Pipe (Note 7) | Piping, Plastic | Table 701.2 |
| ASTM F1499-2012* | Coextruded Composite Drain, Waste, and Vent Pipe (DWV) | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM F1673-2010*</i> | Polyvinylidene Fluoride (PVDF) Corrosive Waste Drainage Systems | Piping, Plastic | 811.2 |
| ASTM F1743-2008* | Rehabilitation of Existing Pipelines and Conduits by Pulled-in-Place Installation of Cured-in-Place Thermosetting Resin Pipe (CIPP) | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM F1807-2013a*</i> | Metal Insert Fittings Utilizing a Copper Crimp Ring for SDR9 Cross-linked Polyethylene (PEX) Tubing and SDR9 Polyethylene of Raised Temperature (PE-RT) Tubing | Fittings | Table 604.1 |
| <i>ASTM F1866-2007*</i> | Poly (Vinyl Chloride) (PVC) Plastic Schedule 40 Drainage and DWV Fabricated Fittings | Fittings | Table 701.2 |
| ASTM F1924-2012* | Plastic Mechanical Fittings for Use on Outside Diameter Controlled Polyethylene Gas Distribution Pipe and Tubing | Fittings | 301.2.2, 301.3 |
| ASTM F1948-2012* | Metallic Mechanical Fittings for Use on Outside Diameter Controlled Thermoplastic Gas Distribution Pipe and Tubing | Fittings | 301.2.2, 301.3 |
| <i>ASTM F1960-2012*</i> | Cold Expansion Fittings with PEX Reinforcing Rings for Use with Cross-linked Polyethylene (PEX) Tubing | Fittings | Table 604.1 |
| <i>ASTM F1961-2009*</i> | Metal Mechanical Cold Flare Compression Fittings with Disc Spring for Crosslinked Polyethylene (PEX) Tubing | Fittings | Table 604.1 |
| <i>ASTM F1970-2012^{e1}*</i> | Special Engineered Fittings, Appurtenances or Valves for Use in Poly (Vinyl Chloride) (PVC) or Chlorinated Poly (Vinyl Chloride) (CPVC) Systems | Piping, Plastic | 606.1, Table 604.1 |
| <i>ASTM F1973-2013^{e1}*</i> | Factory Assembled Anodeless Risers and Transition Fittings in Polyethylene (PE) and Polyamide 11 (PA11) and Polyamide 12 (PA12) Fuel Gas Distribution Systems | Fuel Gas | 1210.1.7.1(2) |
| <i>ASTM F1974-2009*</i> | Metal Insert Fittings for Polyethylene/ Aluminum/Polyethylene and Crosslinked Polyethylene/Aluminum/Crosslinked Polyethylene Composite Pressure Pipe | Fittings | 605.7.1, 605.10.1, Table 604.1 |
| ASTM F1986-2001 (R2011)* | Multilayer Pipe Type 2, Compression Fittings, and Compression Joints for Hot and Cold Drinking-Water Systems | Fittings | 301.2.2, 301.3 |
| <i>ASTM F2080-2012*</i> | Cold-Expansion Fittings with Metal Compression-Sleeves for Cross-linked Polyethylene (PEX) Pipe | Fittings | Table 604.1 |
| <i>ASTM F2098-2008*</i> | Stainless Steel Clamps for Securing SDR9 Cross-linked Polyethylene (PEX) Tubing to Metal Insert and Plastic Insert Fittings | Joints | Table 604.1 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|-------------------------|---|------------------------------|------------------------------|
| <i>ASTM F2159-2011*</i> | Plastic Insert Fittings Utilizing a Copper Crimp Ring for SDR9 Cross-linked Polyethylene (PEX) Tubing and SDR9 Polyethylene of Raised Temperature (PE-RT) Tubing | Joints | Table 604.1 |
| ASTM F2165-2013* | Flexible Pre-Insulated Piping | Piping, Plastic | 301.2.2, 301.3 |
| ASTM F2206-2011* | Fabricated Fittings of Butt-Fused Polyethylene (PE) Plastic Pipe, Fittings, Sheet Stock, Plate Stock, or Block Stock | DWV Components | 301.2.2, 301.3 |
| <i>ASTM F2262-2009*</i> | Crosslinked Polyethylene/Aluminum/ Crosslinked Polyethylene Tubing OD Controlled SDR9 | Piping, Plastic | Table 604.1 |
| ASTM F2306/F2306M-2013* | Specification for 12 to 60 in. [300 to 1500 mm] Annular Corrugated Profile-Wall Polyethylene (PE) Pipe and Fittings for Gravity-Flow Storm Sewer and Subsurface Drainage Applications | Piping, Plastic | 301.2.2, 301.3 |
| <i>ASTM F2389-2010*</i> | Pressure-Rated Polypropylene (PP) Piping Systems | Piping, Plastic | 605.11.1, 606.1, Table 604.1 |
| <i>ASTM F2434-2009*</i> | Metal Insert Fittings Utilizing a Copper Crimp Ring for SDR9 Cross-linked Polyethylene (PEX) Tubing and SDR9 Cross-linked Polyethylene/Aluminum/Cross-linked Polyethylene (PEX-AL-PEX) Tubing | Fittings | 605.10.1, Table 604.1 |
| <i>ASTM F2509-2012*</i> | Field-Assembled Anodeless Riser Kits for Use on Outside Diameter Controlled Polyethylene Gas Distribution Pipe and Tubing | Fuel Gas | 1210.1.7.1(3) |
| <i>ASTM F2620-2012*</i> | Standard Practice for Heat Fusion Joining of Polyethylene Pipe and Fittings | Joints | 605.6.1.1, 605.6.1.3 |
| <i>ASTM F2735-2009</i> | Plastic Insert Fittings for SDR9 Cross-linked Polyethylene (PEX) and Polyethylene of Raised Temperature (PE-RT) Tubing | Fittings | Table 604.1 |
| <i>ASTM F2769-2010</i> | Polyethylene of Raised Temperature (PE-RT) Plastic Hot and Cold-Water Tubing and Distribution Systems | Piping and Fittings, Plastic | Table 604.1 |
| <i>ASTM F2831-2012*</i> | Internal Non Structural Epoxy Barrier Coating Material Used in Rehabilitation of Metallic Pressurized Piping Systems | Miscellaneous | 320.1 |
| <i>ASTM F2855-2012*</i> | Chlorinated Poly (Vinyl Chloride)/Aluminum/Chlorinated Poly (Vinyl Chloride) (CPVC/AL/CPVC) Composite Pressure Tubing | Piping, Plastic | 605.3.1, Table 604.1 |
| <i>AWS A5.8-2011*</i> | Filler Metals for Brazing and Braze Welding | Joints | 605.1.1, 705.3.1, 1309.3.2 |
| <i>AWS A5.9-2012*</i> | Bare Stainless Steel Welding Electrodes and Rods | Joints | 605.13.2 |
| <i>AWS B2.2-2010*</i> | Brazing Procedure and Performance Qualification | Certification | 1307.1 |
| AWS B2.4-2012* | Welding Procedure and Performance Qualification for Thermoplastics | Joints, Certification | 301.2.2, 301.3 |
| <i>AWWA C110-2012*</i> | Ductile-Iron and Gray-Iron Fittings | Fittings | Table 604.1 |
| <i>AWWA C111-2012*</i> | Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings | Joints | 605.4.1, 605.4.2 |
| <i>AWWA C151-2009*</i> | Ductile-Iron Pipe, Centrifugally Cast | Piping, Ferrous | Table 604.1 |
| <i>AWWA C153-2011*</i> | Ductile-Iron Compact Fittings | Fittings | Table 604.1 |
| AWWA C203-2008* | Coal-Tar Protective Coatings and Linings for Steel Water Pipelines - Enamel and Tape – Hot Applied | Miscellaneous | 301.2.2, 301.3 |
| <i>AWWA C210-2007*</i> | Liquid-Epoxy Coating Systems for the Interior and Exterior of Steel Water Pipelines | Miscellaneous | 604.9 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|---|---|---------------------|--|
| AWWA C213-2007* | Fusion-Bonded Epoxy Coating for the Interior and Exterior of Steel Water Pipelines | Miscellaneous | 301.2.2, 301.3 |
| AWWA C215-2010* | Extruded Polyolefin Coatings for the Exterior of Steel Water Pipelines | Miscellaneous | 301.2.2, 301.3 |
| <i>AWWA C500-2009*</i> | Metal-Seated Gate Valves for Water Supply Service | Valves | 606.1 |
| <i>AWWA C504-2010*</i> | Rubber Seated Butterfly Valves, 3 in. (75 mm) through 72 in. (1800 mm) | Valves | 606.1 |
| <i>AWWA C507-2011*</i> | Ball Valves, 6 in. through 60 in. (150 mm through 1,500 mm) | Valves | 606.1 |
| <i>AWWA C510-2007*</i> | Double Check Valve Backflow Prevention Assembly | Backflow Protection | Table 603.2 |
| <i>AWWA C511-2007*</i> | Reduced-Pressure Principle Backflow Prevention Assembly | Backflow Protection | Table 603.2 |
| AWWA C606-2011* | Grooved and Shouldered Joints | Joints | 301.2.2, 301.3 |
| <i>AWWA C900-2007*</i> | Polyvinyl Chloride (PVC) Pressure Pipe and Fabricated Fittings, 4 in. through 12 in. (100 mm through 300 mm), for Water Transmission and Distribution | Piping, Plastic | Table 604.1 |
| <i>AWWA C901-2008*</i> | Polyethylene (PE) Pressure Pipe and Tubing, 1/2 in. (13 mm) through 3 in. (76 mm), for Water Service | Piping, Plastic | Table 604.1 |
| <i>AWWA C904-2006*</i> | Cross-Linked Polyethylene (PEX) Pressure Pipe, 1/2 in. (12 mm) through 3 in. (76 mm), for Water Service | Piping, Plastic | Table 604.1 |
| AWWA C907-2012* | Injection-Molded Polyvinyl Chloride (PVC) Pressure Fittings, 4 in. through 12 in. (100 mm through 300 mm), for Water, Wastewater, and Reclaimed Water Service | Fittings | 301.2.2, 301.3 |
| CGA C-9-2013 | Standard Color Marking of Compressed Gas Containers for Medical Use | Miscellaneous | 301.2.2, 301.3 |
| <i>CGA G-4.1-2009</i> | Cleaning Equipment for Oxygen Service | Miscellaneous | 1308.2, 1311.1 |
| <i>CGA S-1.3-2008</i> | Pressure Relief Device Standards-Part 3-Stationary Storage Containers for Compressed Gases | Fuel Gas | F 501.8 |
| <i>CGA V-1-2013</i> | Compressed Gas Cylinder Valve Outlet and Inlet Connections | Valves | F 601.6, F 701.4 |
| <i>CISPI 301-2012</i> | Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste, and Vent Piping Applications (Notes 1 and 7) | Piping, Ferrous | Table 701.2 |
| <i>CISPI 310-2012</i> | Couplings for Use in Connection with Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste, and Vent Piping Applications | Joints | 301.2.4, 705.2.2 |
| CSA A257-2009 | Concrete Pipe and Manhole Sections | Piping | 301.2.2, 301.3 |
| CSA B45.0-2002 (R2008) | General Requirements for Plumbing Fixtures | Fixtures | 301.2.2, 301.3 |
| <i>CSA B45.5-2011/IAPMO Z124-2011*</i> | Plastic Plumbing Fixtures | Fixtures | 407.1, 408.1, 409.1, 411.1, 412.1, 420.1, L 402.3, L 402.3.1 |
| CSA B45.8-2013/IAPMO Z403-2013* | Terrazzo, Concrete, and Natural Stone Plumbing Fixtures | Fixtures | 301.2.2, 301.3 |
| <i>CSA B45.11-2011/IAPMO Z401-2011*</i> | Glass Plumbing Fixtures | Fixtures | 407.1 |
| CSA B45.12-2013/IAPMO Z402-2013* | Aluminum and Copper Plumbing Fixtures | Fixtures | 301.2.2, 301.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|-------------------------------------|--|---------------------|---|
| CSA B64-2011 | Backflow Preventers and Vacuum Breakers | Backflow Protection | 301.2.2, 301.3 |
| <i>CSA B64.1.1-2011</i> | Atmospheric Vacuum Breakers (AVB) | Backflow Protection | Table 603.2 |
| <i>CSA B64.1.2-2011</i> | Pressure Vacuum Breakers (PVB) | Backflow Protection | Table 603.2 |
| CSA B64.2-2011 | Hose Connection Vacuum Breakers (HCVB) | Backflow Protection | 301.2.2, 301.3 |
| <i>CSA B64.2.1.1-2011</i> | Hose Connection Dual Check Vacuum Breakers (HCDVB) | Backflow Protection | Table 603.2 |
| <i>CSA B64.4-2011</i> | Reduced Pressure Principle (RP) Backflow Preventers | Backflow Protection | Table 603.2 |
| <i>CSA B64.4.1-2011</i> | Reduced Pressure Principle Backflow Preventers for Fire Protection Systems (RPF) | Backflow Protection | Table 603.2 |
| <i>CSA B64.5-2011</i> | Double Check Valve (DVCA) Backflow Preventers | Backflow Protection | Table 603.2 |
| <i>CSA B64.5.1-2011</i> | Double Check Valve Backflow Preventers for Fire Protection Systems (DVCAF) | Backflow Protection | Table 603.2 |
| CSA B64.7-2011 | Laboratory Faucet Vacuum Breakers (LFVB) | Backflow Protection | 301.2.2, 301.3 |
| CSA B66-2010 | Design, Material, and Manufacturing Requirements for Prefabricated Septic Tanks and Sewage Holding Tanks | DWV Components | 301.2.2, 301.3 |
| <i>CSA B79-2008 (R2013)</i> | Commercial and Residential Drains and Cleanouts | DWV Components | 418.1 |
| <i>CSA B125.3-2012</i> | Plumbing Fittings | Fittings | 407.3, 409.4, 410.3, 413.2, 413.3, 606.1, Table 603.2 |
| CSA B128.1-2006/B128.2-2006 (R2011) | Design and Installation of Non-Potable Water Systems/Maintenance and Field Testing of Non-Potable Water Systems (Note 1) | Miscellaneous | 301.2.2, 301.3 |
| <i>CSA B137.1-2013</i> | Polyethylene (PE) Pipe, Tubing, and Fittings for Cold-Water Pressure Services | Piping, Plastic | Table 604.1 |
| <i>CSA B137.5-2013</i> | Crosslinked Polyethylene (PEX) Tubing Systems for Pressure Applications | Piping, Plastic | Table 604.1 |
| <i>CSA B137.6-2013</i> | Chlorinated Polyvinylchloride (CPVC) Pipe, Tubing, and Fittings for Hot- and Cold-Water Distribution Systems | Piping, Plastic | Table 604.1 |
| <i>CSA B137.9-2013</i> | Polyethylene/Aluminum/Polyethylene (PE-AL-PE) Composite Pressure-Pipe Systems | Piping, Plastic | Table 604.1 |
| <i>CSA B137.10-2013</i> | Crosslinked Polyethylene/Aluminum/Crosslinked Polyethylene (PEX-AL-PEX) Composite Pressure-Pipe Systems | Piping, Plastic | Table 604.1 |
| <i>CSA B137.11-2013</i> | Polypropylene (PP-R) Pipe and Fittings for Pressure Applications | Piping, Plastic | 605.11.1, Table 604.1 |
| <i>CSA B181.3-2011</i> | Polyolefin and Polyvinylidene Fluoride (PVDF) Laboratory Drainage Systems | Piping, Plastic | 811.2 |
| CSA B242-2005 (R2011) | Groove- and Shoulder-Type Mechanical Pipe Couplings | Fittings | 301.2.2, 301.3 |
| CSA B356-2010 | Water Pressure Reducing Valves for Domestic Water Supply Systems | Valves | 301.2.2, 301.3 |
| <i>CSA B481-2012</i> | Grease Interceptors | DWV Components | 1014.1 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|------------------------------------|---|--|---------------------------------|
| CSA G401-2007 (R2013) | Corrugated Steel Pipe Products | Piping, Ferrous | 301.2.2, 301.3 |
| <i>CSA LC 1b-2011*</i> | Fuel Gas Piping Systems Using Corrugated Stainless Steel Tubing (CSST) (same as CSA 6.26b) | Fuel Gas | 1208.5.3.4 |
| CSA LC 3-2000 (R2005)* | Appliance Stands and Drain Pans | Miscellaneous | 301.2.2, 301.3 |
| <i>CSA LC 4a-2013*</i> | Press-Connect Metallic Fittings for Use in Fuel Gas Distribution Systems (same as CSA 6.32a) | Fuel Gas | 1208.5.8.1, 1208.5.8.2 |
| <i>CSA Z21.10.1-2013*</i> | Gas Water Heaters – Volume I, Storage Water Heaters with Input Ratings of 75 000 Btu Per Hour or Less (same as CSA 4.1) | Fuel Gas, Appliances | Table 501.1(2) |
| <i>CSA Z21.10.3-2013*</i> | Gas-Fired Water Heaters – Volume III, Storage Water Heaters with Input Ratings Above 75 000 Btu Per Hour, Circulating and Instantaneous (same as CSA 4.3) | Fuel Gas, Appliances | Table 501.1(2), Table L 603.3.2 |
| CSA Z21.12b-1994 (R2010)* | Draft Hoods | Fuel Gas, Appliances | 301.2.2, 301.3 |
| CSA Z21.13-2013* | Gas-Fired Low Pressure Steam and Hot Water Boilers (same as CSA 4.9) | Fuel Gas, Appliances | 301.2.2, 301.3 |
| CSA Z21.15b-2013* | Manually Operated Gas Valves for Appliances, Appliance Connector Valves, and Hose End Valves (same as CSA 9.1b) | Fuel Gas | 301.2.2, 301.3 |
| <i>CSA Z21.22b-2001 (R2008)*</i> | Relief Valves for Hot Water Supply Systems (same as CSA 4.4b) | Valves | 607.5, 608.7 |
| <i>CSA Z21.24a-2009 (R2011)*</i> | Connectors for Gas Appliances (same as CSA 6.10a) | Fuel Gas | 1212.1(3), 1212.2 |
| <i>CSA Z21.40.1a-1997 (R2012)*</i> | Gas-Fired, Heat Activated Air-Conditioning and Heat Pump Appliances (same as CSA 2.91a) | Fuel Gas, Appliances | 301.2.2, 301.3 |
| <i>CSA Z21.41-2011*</i> | Quick-Disconnect Devices for Use with Gas Fuel Appliances (same as CSA 6.9) | Fuel Gas | 1212.6 |
| CSA Z21.47-2012* | Gas-Fired Central Furnaces (same as CSA 2.3) | Fuel Gas, Appliances | 301.2.2, 301.3 |
| <i>CSA Z21.54b-2009*</i> | Gas Hose Connectors for Portable Outdoor Gas-Fired Appliances (same as CSA 8.4b) | Fuel Gas | 1212.3.2 |
| CSA Z21.56-2013* | Gas-Fired Pool Heaters (same as CSA 4.7) | Fuel Gas, Swimming Pools, Spas, and Hot Tubs | 301.2.2, 301.3 |
| <i>CSA Z21.69a-2012*</i> | Connectors for Movable Gas Appliances (same as CSA 6.16a) | Fuel Gas | 1212.1.1 |
| <i>CSA Z21.75a-2009*</i> | Connectors for Outdoor Gas Appliances and Manufactured Homes (same as CSA 6.27a) | Appliances | 1212.1(4) |
| <i>CSA Z21.80a-2012*</i> | Line Pressure Regulators (same as CSA 6.22a) | Fuel Gas | 1208.7.2, 1208.7.5(1) |
| CSA Z21.81a-2007 (R2010)* | Cylinder Connection Devices (same as CSA 6.25a) | Fuel Gas | 301.2.2, 301.3 |
| CSA Z21.86-2008* | Vented Gas-Fired Space Heating Appliances (same as CSA 2.32) | Fuel Gas, Appliances | 301.2.2, 301.3 |
| <i>CSA Z21.90b-2006 (R2011)*</i> | Gas Convenience Outlets and Optional Enclosures (same as CSA 6.24b) | Fuel Gas | 1212.7 |
| CSA Z21.93-2013* | Excess Flow Valves for Natural and LP Gas with Pressures up to 5 psig (same as CSA 6.30) | Fuel Gas | 301.2.2, 301.3 |
| CSA Z83.11b-2009 (R2011)* | Gas Food Service Equipment (same as CSA 1.8b) | Fuel Gas, Appliances | 301.2.2, 301.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|---------------------------------------|---|---------------------|--------------------------|
| CSA Z317.1-2009 | Special Requirements for Plumbing Installations in Health Care Facilities | Miscellaneous | 301.2.2, 301.3 |
| <i>Energy Star-2007 (version 2.0)</i> | Specification for Commercial Dishwashers | Appliances | L 403.1 |
| <i>Energy Star-2011 (version 6.0)</i> | Specification for Clothes Washers | Appliances | L 403.2 |
| <i>Energy Star-2012 (version 5.0)</i> | Specification for Residential Dishwashers | Appliances | L 403.1 |
| <i>EPA WaterSense-2007</i> | High-Efficiency Lavatory Faucet Specification | Fixtures | L 402.5.1 |
| <i>EPA WaterSense-2009</i> | Specification for Flushing Urinals | Fixtures | L 402.3, Table L 402.1 |
| <i>EPA WaterSense-2011</i> | Specification for Tank-Type Toilets | Fixtures | L 402.2.1, Table L 402.1 |
| IAPMO IGC 154-2013 | Shower and Tub/Shower Enclosures and Shower Panels | Fixtures | 301.2.2, 301.3 |
| IAPMO IGC 157-2013 ^{e1} | Ball Valves | Valves | 301.2.2, 301.3 |
| IAPMO IGC 193-2010 | Safety Plates, Plate Straps, Notched Plates and Safety Collars | Miscellaneous | 301.2.2, 301.3 |
| IAPMO IGC 226-2006a | Drinking Water Fountains With or Without Chiller or Heater | Fixtures | 301.2.2, 301.3 |
| <i>IAPMO IGC 276-2011</i> | Bundled Expanded Polystyrene Synthetic Aggregate Units | DWV Components | H 301.1(5) |
| IAPMO PS 23-2006a | Dishwasher Drain Airgaps | Backflow Protection | 301.2.2, 301.3 |
| IAPMO PS 25-2002 | Metallic Fittings for Joining Polyethylene Pipe for Water Service and Yard Piping | Joints | 301.2.2, 301.3 |
| IAPMO PS 34-2003 | Encasement Sleeve for Potable Water Pipe and Tubing | Piping | 301.2.2, 301.3 |
| IAPMO PS 36-1990 | Lead Free Sealing Compounds for Threaded Joints | Joints | 301.2.2, 301.3 |
| IAPMO PS 37-1990 | Black Plastic PVC or PE Pressure-Sensitive Corrosion Preventive Tape | Miscellaneous | 301.2.2, 301.3 |
| IAPMO PS 42-2013 ^{e1} | Pipe Alignment and Secondary Support Systems | Miscellaneous | 301.2.2, 301.3 |
| IAPMO PS 50-2010 | Flush Valves with Dual Flush Device For Water Closets or Water Closet Tank with an Integral Flush Valves with a Dual Flush Device | Fixtures | 301.2.2, 301.3 |
| IAPMO PS 51-2013 | Expansion Joints for DWV Piping Systems | Joints | 301.2.2, 301.3 |
| IAPMO PS 52-2009 | Pump/Dose, Sumps and Sewage Ejector Tanks with or without a Pump | DWV Components | 301.2.2, 301.3 |
| IAPMO PS 53-2013 | Grooved Mechanical Pipe Couplings and Grooved Fittings | Joints | 301.2.2, 301.3 |
| IAPMO PS 54-2011a | Metallic and Plastic Utility Boxes | Miscellaneous | 301.2.2, 301.3 |
| IAPMO PS 57-2002 | PVC Hydraulically Actuated Diaphragm Type Water Control Valves | Valves | 301.2.2, 301.3 |
| IAPMO PS 59-2013 | Wastewater Diverter Valves and Diversion Systems | DWV Components | 301.2.2, 301.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|---------------------------------|--|------------------------------------|---------------------|
| IAPMO PS 60-1996 | Sewage Holding Tank Containing Sewage Ejector Pump for Direct Mounted Water Closet | DWV Components | 301.2.2, 301.3 |
| <i>IAPMO PS 63-2013</i> | Plastic Leaching Chambers | DWV Components | H 301.1(5) |
| IAPMO PS 64-2012a ^{e1} | Roof Pipe Flashings | Miscellaneous | 301.2.2, 301.3 |
| <i>IAPMO PS 65-2002</i> | Airgap Units for Water Conditioning Equipment Installation | Backflow Protection | 611.2 |
| IAPMO PS 66-2000 | Dielectric Waterway Fittings | Fittings | 301.2.2, 301.3 |
| IAPMO PS 67-2010 | Early-Closure Replacement Flappers or Early-Closure Replacement Flapper with Mechanical Assemblies | Fixtures | 301.2.2, 301.3 |
| IAPMO PS 69-2006 | Bathwaste and Overflow Assemblies with Tub Filler Spout | DWV Components | 301.2.2, 301.3 |
| IAPMO PS 72-2007 ^{e1} | Valves with Atmospheric Vacuum Breakers | Valves | 301.2.2, 301.3 |
| IAPMO PS 73-1993 | Dental Vacuum Pumps | Miscellaneous | 301.2.2, 301.3 |
| <i>IAPMO PS 76-2012a</i> | Trap Primers for Fill Valves and Flushometer Valves | DWV Components | L 412.1 |
| IAPMO PS 79-2005 | Multiport Electronic Trap Primer | DWV Components | 301.2.2, 301.3 |
| IAPMO PS 80-2008 | Clarifiers | DWV Components | 301.2.2, 301.3 |
| IAPMO PS 81-2006 | Precast Concrete Seepage Pit Liners and Covers | DWV Components | 301.2.2, 301.3 |
| IAPMO PS 82-1995 | Fiberglass (Glass Fiber Reinforced Thermosetting Resin) Fittings | Fittings | 301.2.2, 301.3 |
| IAPMO PS 85-1995 | Tools for Mechanically Formed Tee Connections in Copper Tubing | Miscellaneous | 301.2.2, 301.3 |
| IAPMO PS 86-1995 | Rainwater Diverter Valve for Non-Roofed Area Slabs | DWV Components | 301.2.2, 301.3 |
| IAPMO PS 87-1995 | Diverter and Shutoff Valves for Pool/Spas | Swimming Pools, Spas, and Hot Tubs | 301.2.2, 301.3 |
| IAPMO PS 89-1995 | Soaking and Hydrotherapy (Whirlpool) Bathtubs with Hydraulic Seatlift | Fixtures | 301.2.2, 301.3 |
| IAPMO PS 90-2012 ^{e1} | Elastomeric Test Caps, Cleanout Caps, and Combination Test Caps/Shielded Couplings | DWV Components | 301.2.2, 301.3 |
| IAPMO PS 91-2005a | Plastic Stabilizers for Use with Plastic Closet Bends | DWV Components | 301.2.2, 301.3 |
| <i>IAPMO PS 92-2013</i> | Heat Exchangers and Indirect Water Heaters | Miscellaneous | L 606.1 |
| IAPMO PS 94-2012 | Insulated Protectors for P-Traps, Supply Stops and Risers | Miscellaneous | 301.2.2, 301.3 |
| IAPMO PS 95-2001 | Drain, Waste, and Vent Hangers and Plastic Pipe Support Hooks | DWV Components | 301.2.2, 301.3 |
| IAPMO PS 96-2002 | Passive Direct Solar Water Heaters | Appliances | 301.2.2, 301.3 |
| IAPMO PS 98-1996 | Prefabricated Fiberglass Church Baptisteries | Fixtures | 301.2.2, 301.3 |
| IAPMO PS 100-1996 | Porous Filter Protector for Sub-Drain Weep Holes | DWV Components | 301.2.2, 301.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|--|---|--|---------------------|
| IAPMO PS 101-1997 | Suction Relief Valves | Valves | 301.2.2, 301.3 |
| IAPMO PS 104-1997 | Pressure Relief Connection for Dispensing Equipment | Valves | 301.2.2, 301.3 |
| IAPMO PS 105-1997 | Polyethylene Distribution Boxes | DWV Components | 301.2.2, 301.3 |
| IAPMO PS 106-2013b | Tileable Shower Receptors and Shower Kits | Fixtures | 301.2.2, 301.3 |
| IAPMO PS 107-1998 | Aramid Reinforced Rubber Hose for Use in Non-Potable Water Radiant Heating and Snowmelting | Miscellaneous | 301.2.2, 301.3 |
| IAPMO PS 108-1998 | Restaurant Fire Suppression Systems | Miscellaneous | 301.2.2, 301.3 |
| IAPMO PS 110-2006a | PVC Cold Water Compression Fittings | Fittings | 301.2.2, 301.3 |
| IAPMO PS 111-1999 | PVC Cold Water Gripper Fittings | Fittings | 301.2.2, 301.3 |
| IAPMO PS 112-1999 | PVC Plastic Valves for Cold Water Distribution Systems Outside a Building and CPVC Plastic Valves for Hot and Cold Water Distribution Systems | Valves | 301.2.2, 301.3 |
| IAPMO PS 113-2010 | Hydraulically Powered Household Food Waste Disposers | Appliances | 301.2.2, 301.3 |
| IAPMO PS 114-1999 ^{e1} | Remote Floor Box Industrial Water Supply, Air Supply, Drainage | Miscellaneous | 301.2.2, 301.3 |
| IAPMO PS 115-2007 | Hot Water On-Demand or Automatic Activated Hot Water Pumping Systems | Miscellaneous | 301.2.2, 301.3 |
| IAPMO PS 116-1999 | Hot Water Circulating Devices Which Do Not Use a Pump | Miscellaneous | 301.2.2, 301.3 |
| IAPMO PS 117-2012a ^{e1} | Press and Nail Connections | Fittings | 301.2.2, 301.3 |
| IAPMO PS 119-2012a ^{e1} | Water-Powered Sump Pumps | Miscellaneous | 301.2.2, 301.3 |
| IAPMO Z124.5-2013^{e1}* | Plastic Toilet Seats | Fixtures | 411.3 |
| IAPMO Z124.7-2013* | Prefabricated Plastic Spa Shells | Fixtures, Swimming Pools, Spas, and Hot Tubs | 301.2.2, 301.3 |
| IAPMO Z124.8-2013 ^{e1} * | Plastic Liners for Bathtubs and Shower Receptors | Fixtures | 301.2.2, 301.3 |
| IAPMO Z1000-2013* | Prefabricated Septic Tanks | DWV Components | 301.2.2, 301.3 |
| IAPMO Z1001-2013* | Prefabricated Gravity Grease Interceptors | DWV Components | 1014.3.4 |
| IAPMO Z1033-2013^{e1}* | Flexible PVC Hoses and Tubing for Pools, Hot Tubs, Spas, and Jetted Bathtubs | Fixtures, Swimming Pools, Spas, and Hot Tubs | 409.6.1 |
| IAPMO Z1088-2013* | Pre-Pressurized Water Expansion Tanks | Miscellaneous | 301.2.2, 301.3 |
| ICC A117.1-2009* | Accessible and Usable Buildings and Facilities | Miscellaneous | 403.2, 408.6 |
| ISEA Z358.1-2009* | Emergency Eyewash and Shower Equipment | Miscellaneous | 416.1, 416.2 |
| ISO/TEC Guide 65-1996 | General Requirements for Bodies Operating Product Certification Systems | Certification | 301.2.2, 301.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|-----------------------------|--|----------------------|--|
| <i>MSS SP-6-2012</i> | Finishes for Contact Faces of Pipe Flanges and Connecting-End Flanges of Valves and Fittings | Fuel Gas | 1208.5.10 |
| MSS SP-25-2013* | Marking System for Valves, Fittings, Flanges, and Unions | Miscellaneous | 301.2.2, 301.3 |
| MSS SP-42-2013 | Corrosion-Resistant Gate, Globe, Angle, and Check Valves with Flanged and Butt Weld Ends (Classes 150, 300, & 600) | Piping, Ferrous | 301.2.2, 301.3 |
| MSS SP-44-2010 | Steel Pipeline Flanges | Fittings | 301.2.2, 301.3 |
| <i>MSS SP-58-2009*</i> | Pipe Hangers and Supports – Materials, Design, Manufacture, Selection, Application, and Installation | Miscellaneous | 1210.2.4, 1310.5.1 |
| <i>MSS SP-67-2011</i> | Butterfly Valves | Valves | 606.1 |
| <i>MSS SP-70-2011</i> | Gray Iron Gate Valves, Flanged and Threaded Ends | Valves | 606.1 |
| <i>MSS SP-71-2011</i> | Gray Iron Swing Check Valves, Flanged and Threaded Ends | Valves | 606.1 |
| <i>MSS SP-72-2010a</i> | Ball Valves with Flanged or Butt-Welding Ends for General Service | Valves | 606.1 |
| <i>MSS SP-78-2011</i> | Gray Iron Plug Valves, Flanged and Threaded Ends | Valves | 606.1 |
| <i>MSS SP-80-2013</i> | Bronze Gate, Globe, Angle, and Check Valves | Valves | 606.1 |
| MSS SP-83-2006 | Class 3000 Steel Pipe Unions Socket Welding and Threaded | Joints | 301.2.2, 301.3 |
| MSS SP-104-2012 | Wrought Copper Solder-Joint Pressure Fittings | Fittings | 301.2.2, 301.3 |
| MSS SP-106-2012 | Cast Copper Alloy Flanges and Flanged Fittings: Class 125, 150, and 300 | Fittings | 301.2.2, 301.3 |
| MSS SP-109-2012 | Weld-Fabricated Copper Solder-Joint Pressure Fittings | Fittings | 301.2.2, 301.3 |
| <i>MSS SP-110-2010</i> | Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends | Valves | 606.1 |
| <i>MSS SP-122-2012</i> | Plastic Industrial Ball Valves | Valves | 606.1 |
| MSS SP-123-2013 | Non-Ferrous Threaded and Solder-Joint Unions for Use with Copper Water Tube | Joints | 301.2.2, 301.3 |
| <i>NFPA 13D-2013*</i> | Installation of Sprinkler Systems in One- and Two-Family Dwellings and Manufactured Homes | Miscellaneous | 612.1, 612.5.3.1 |
| NFPA 13R-2013* | Installation of Sprinkler Systems in Low-Rise Residential Occupancies | Miscellaneous | 301.2.2, 301.3 |
| <i>NFPA 30A-2012*</i> | Motor Fuel Dispensing Facilities and Repair Garages | Miscellaneous | 507.14.2 |
| <i>NFPA 31-2011*</i> | Installation of Oil-Burning Equipment | Fuel Gas, Appliances | 505.3, 1201.1, E 401.1, E 412.1, E 413.6, E 413.6.1, E 414.1, E 415.2, E 415.3 |
| <i>NFPA 51-2013*</i> | Design and Installation of Oxygen-Fuel Gas Systems for Welding, Cutting, and Allied Processes | Fuel Gas | 507.9 |
| <i>NFPA 54/Z223.1-2012*</i> | National Fuel Gas Code | Fuel Gas | 1210.14, E 401.1, E 408.1, E 414.1, E 415.1 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|------------------------|--|----------------------|---|
| <i>NFPA 58-2014*</i> | Liquefied Petroleum Gas Code | Fuel Gas | 1208.5.4.2.3, 1208.5.9.4, 1210.5(6), 1212.10, E 401.1, E 401.2, E 406.1, E 411.1, E 414.1, E 415.1 |
| <i>NFPA 70-2014*</i> | National Electrical Code | Miscellaneous | 1211.6, 1310.4.1, 1318.1(11), F 701.1 |
| NFPA 80-2013* | Fire Doors and Other Opening Protectives | Miscellaneous | 301.2.2, 301.3 |
| NFPA 85-2011* | Boiler and Combustion Systems Hazards Code | Appliances | 301.2.2, 301.3 |
| <i>NFPA 88A-2011*</i> | Parking Structures | Miscellaneous | 507.14.1 |
| <i>NFPA 99-2012*</i> | Health Care Facilities Code | Piping | 1301.3, 1318.1(9) |
| NFPA 130-2014* | Fixed Guideway Transit and Passenger Rail Systems | Miscellaneous | 301.2.2, 301.3 |
| <i>NFPA 211-2013*</i> | Chimneys, Fireplaces, Vents, and Solid Fuel-Burning Appliances | Fuel Gas, Appliances | 509.5.2, 509.5.3, 509.5.6.1, 509.5.6.3 |
| NFPA 220-2012* | Types of Building Construction | Miscellaneous | 301.2.2, 301.3 |
| <i>NFPA 409-2011*</i> | Aircraft Hangars | Miscellaneous | 507.15 |
| NFPA 501A-2013* | Fire Safety Criteria for Manufactured Home Installations, Sites, and Communities | Miscellaneous | 301.2.2, 301.3 |
| NFPA 502-2014* | Road Tunnels, Bridges, and Other Limited Access Highways | Miscellaneous | 301.2.2, 301.3 |
| <i>NFPA 780-2014*</i> | Installation of Lightning Protection Systems | Fuel Gas | 1211.4 |
| NFPA 1981-2013* | Open-Circuit Self-Contained Breathing Apparatus (SCBA) for Emergency Services | Miscellaneous | 301.2.2, 301.3 |
| <i>NFPA 1989-2013*</i> | Breathing Air Quality for Emergency Services Respiratory Protection | Miscellaneous | F 1201.7 |
| NFPA 5000-2012* | Building Construction and Safety Code | Miscellaneous | 301.2.2, 301.3 |
| NSF 2-2012* | Food Equipment | Appliances | 301.2.2, 301.3 |
| <i>NSF 3-2010*</i> | Commercial Warewashing Equipment | Appliances | 414.1 |
| NSF 4-2009* | Commercial Cooking, Rethermalization, and Powered Hot Food Holding and Transport Equipment | Appliances | 301.2.2, 301.3 |
| NSF 5-2012* | Water Heaters, Hot Water Supply Boilers, and Heat Recovery Equipment | Appliances | 301.2.2, 301.3 |
| NSF 12-2012* | Automatic Ice Making Equipment | Appliances | 301.2.2, 301.3 |
| <i>NSF 14-2012*</i> | Plastics Piping System Components and Related Materials | Piping, Plastic | 301.2.3, 604.1, 611.3 |
| NSF 18-2012* | Manual Food and Beverage Dispensing Equipment | Appliances | 301.2.2, 301.3 |
| NSF 29-2009* | Detergent and Chemical Feeders for Commercial Spray-Type Dishwashing Machines | Appliances | 301.2.2, 301.3 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|------------------------|---|-------------------------|---|
| NSF 40-2013* | Residential Wastewater Treatment Systems | DWV Components | 301.2.2, 301.3 |
| NSF 41-2011* | Non-Liquid Saturated Treatment Systems | DWV Components | 301.2.2, 301.3 |
| <i>NSF 42-2013*</i> | Drinking Water Treatment Units – Aesthetic Effects | Appliances | 611.1, 611.3 |
| <i>NSF 44-2013*</i> | Residential Cation Exchange Water Softeners | Appliances | 611.1, 611.3, L 410.1 |
| NSF 46-2012* | Evaluation of Components and Devices Used in Wastewater Treatment Systems | DWV Components | 301.2.2, 301.3 |
| <i>NSF 53-2013*</i> | Drinking Water Treatment Units – Health Effects | Appliances | 611.1, 611.3, K 104.2.1, L 504.2.1 |
| <i>NSF 55-2013*</i> | Ultraviolet Microbiological Water Treatment Systems | Appliances | 611.1, 611.3 |
| <i>NSF 58-2013*</i> | Reverse Osmosis Drinking Water Treatment Systems | Appliances | 611.1, 611.2, 611.3, L 410.3 |
| <i>NSF 61-2012*</i> | Drinking Water System Components – Health Effects | Water Supply Components | 415.1, 417.1, 604.1, 604.9, 606.1, 607.2, 608.2 |
| <i>NSF 62-2013*</i> | Drinking Water Distillation Systems | Appliances | 611.1, 611.3 |
| NSF 169-2012* | Special Purpose Food Equipment and Devices | Appliances | 301.2.2, 301.3 |
| <i>NSF 350-2012*</i> | Onsite Residential and Commercial Water Reuse Treatment Systems | Miscellaneous | 1504.7 |
| <i>NSF 359-2011*</i> | Valves for Crosslinked Polyethylene (PEX) Water Distribution Tubing Systems | Valves | 606.1 |
| <i>PDI G-101-2012</i> | Testing and Rating Procedure for Hydro Mechanical Grease Interceptors with Appendix of Installation and Maintenance | DWV Components | 1014.1 |
| <i>PDI G-102-2010</i> | Testing and Certification for Grease Interceptors with FOG Sensing and Alarm Devices | Certification | 1014.1 |
| <i>PDI-WH 201-2010</i> | Water Hammer Arresters | Water Supply Components | 609.10 |
| PSAI Z4.1-2005* | For Sanitation – In Places of Employment – Minimum Requirements | Miscellaneous | 301.2.2, 301.3 |
| SAE J512-1997 | Automotive Tube Fittings | Fittings | 301.2.2, 301.3 |
| SAE J1670-2008 | Type “F” Clamps for Plumbing Applications | Joints | 301.2.2, 301.3 |
| TCNA A118.10-2011* | Load Bearing, Bonded, Waterproof Membranes for Thin-Set Ceramic Tile and Dimension Stone Installation | Miscellaneous | 301.2.2, 301.3 |
| TCNA A137.1-2012* | Specifications for Ceramic Tile | Miscellaneous | 301.2.2, 301.3 |
| <i>UL 17-2008</i> | Vent or Chimney Connector Dampers for Oil-Fired Appliances (with revisions through September 25, 2013) | Vent Dampers | 509.13.1 |
| <i>UL 70-2001</i> | Septic Tanks, Bituminous-Coated Metal | DWV Components | H 501.14(1) |
| <i>UL 80-2007*</i> | Steel Tanks for Oil-Burner Fuels and Other Combustible Liquids (with revisions through January 16, 2014) | Fuel Gas | E 413.6.2 |
| <i>UL 103-2010*</i> | Factory-Built Chimneys for Residential Type and Building Heating Appliances (with revisions through July 27, 2012) | Fuel Gas, Appliances | 509.5.1.1, 509.5.1.2 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|---------------------|---|----------------------|----------------------------|
| UL 125-2009* | Flow Control Valves for Anhydrous Ammonia and LP-Gas (with revisions through November 10, 2011) | Fuel Gas | 301.2.2, 301.3 |
| UL 132-2007* | Safety Relief Valves for Anhydrous Ammonia and LP-Gas (with revisions through July 23, 2010) | Fuel Gas | 301.2.2, 301.3 |
| UL 144-2012* | LP-Gas Regulators | Fuel Gas | 301.2.2, 301.3 |
| <i>UL 174-2004*</i> | Household Electric Storage Tank Water Heaters (with revisions through September 21, 2012) | Appliances | Table 501.1(2) |
| UL 252-2010* | Compressed Gas Regulators (with revisions through September 4, 2013) | Fuel Gas | 301.2.2, 301.3 |
| <i>UL 263-2011*</i> | Fire Tests of Building Construction and Materials | Miscellaneous | 1404.3, 1405.3 |
| UL 296-2003* | Oil Burners (with revisions through September 17, 2013) | Fuel Gas, Appliances | 301.2.2, 301.3 |
| UL 343-2008 | Pumps for Oil-Burning Appliances (with revisions through June 12, 2013) | Fuel Gas, Appliances | 301.2.2, 301.3 |
| <i>UL 378-2006</i> | Draft Equipment (with revisions through September 17, 2013) | Fuel Gas, Appliances | 509.13.1 |
| <i>UL 399-2008*</i> | Drinking Water Coolers (with revisions through October 18, 2013) | Appliances | 415.1 |
| UL 404-2010* | Gauges, Indicating Pressure, for Compressed Gas Service | Fuel Gas | 301.2.2, 301.3 |
| UL 429-2013 | Electrically Operated Valves | Valves | 301.2.2, 301.3 |
| <i>UL 430-2009*</i> | Waste Disposers (with revisions through October 3, 2013) | Appliances | 419.1 |
| <i>UL 441-2010*</i> | Gas Vents (with revisions through May 18, 2010) | Fuel Gas | 509.1 |
| UL 443-2006* | Steel Auxiliary Tanks for Oil-Burner Fuel (with revisions through March 8, 2013) | Fuel Gas | 301.2.2, 301.3 |
| UL 499-2005* | Electric Heating Appliances (with revisions through February 11, 2013) | Appliances | 301.2.2, 301.3 |
| UL 536-1997 | Flexible Metallic Hose (with revisions through June 9, 2003) | Fuel Gas | 301.2.2, 301.3 |
| UL 563-2009* | Ice Makers (with revisions through November 29, 2013) | Appliances | 301.2.2, 301.3 |
| UL 565-2013 | Liquid-Level Gauges for Anhydrous Ammonia and LP-Gas | Fuel Gas | 301.2.2, 301.3 |
| UL 569-2013* | Pigtails and Flexible Hose Connectors for LP-Gas | Fuel Gas | 301.2.2, 301.3 |
| <i>UL 641-2010*</i> | Type L Low-Temperature Venting Systems (with revisions through June 12, 2013) | Fuel Gas | 509.1 |
| <i>UL 651-2011*</i> | Schedule 40, 80, Type EB and A Rigid PVC Conduit and Fittings (with revisions through March 30, 2012) | Piping, Plastic | 1208.5.4.1 |
| <i>UL 723-2008*</i> | Test for Surface Burning Characteristics of Building Materials (with revisions through August 12, 2013) | Miscellaneous | 701.2(2), 903.1(2), 1101.4 |
| UL 726-1995 | Oil-Fired Boiler Assemblies (with revisions through October 9, 2013) | Fuel Gas, Appliances | 301.2.2, 301.3 |
| <i>UL 732-1995*</i> | Oil-Fired Storage Tank Water Heaters (with revisions through October 9, 2013) | Fuel Gas, Appliances | Table 501.1(2) |
| <i>UL 749-2013*</i> | Household Dishwashers (with revisions through May 24, 2013) | Appliances | 414.1 |
| <i>UL 778-2010*</i> | Motor-Operated Water Pumps (with revisions through May 25, 2012) | Appliances | 1101.14 |
| UL 834-2004* | Heating, Water Supply, and Power Boilers—Electric (with revisions through December 9, 2013) | Appliances | 301.2.2, 301.3 |
| <i>UL 921-2006*</i> | Commercial Dishwashers (with revisions through July 6, 2012) | Appliances | 414.1 |

REFERENCED STANDARDS

| STANDARD NUMBER | STANDARD TITLE | APPLICATION | REFERENCED SECTIONS |
|-----------------------------|---|--|------------------------------|
| <i>UL 959-2010*</i> | Medium Heat Appliance Factory-Built Chimneys | Fuel Gas, Appliances | 509.5.1.2 |
| UL 1081-2008* | Swimming Pool Pumps, Filters, and Chlorinators (with revisions through May 31, 2013) | Swimming Pools, Spas, and Hot Tubs | 301.2.2, 301.3 |
| UL 1206-2003 * | Electric Commercial Clothes-Washing Equipment (with revisions through November 30, 2012) | Appliances | 301.2.2, 301.3 |
| UL 1261-2001* | Electric Water Heaters for Pools and Tubs (with revisions through July 31, 2012) | Appliances, Swimming Pools, Spas, and Hot Tubs | 301.2.2, 301.3 |
| UL 1331-2005 | Station Inlets and Outlets (with revisions through August 18, 2010) | Medical Gas | 301.2.2, 301.3 |
| <i>UL 1453-2004*</i> | Electric Booster and Commercial Storage Tank Water Heaters (with revisions through July 15, 2011) | Appliances | Table 501.1(2) |
| UL 1469-2006 | Strength of Body and Hydraulic Pressure Loss Testing of Backflow Special Check Valves (with revisions through March 19, 2010) | Backflow Protection | 301.2.2, 301.3 |
| <i>UL 1479-2003*</i> | Fire Tests of Through-Penetration Firestops (with revisions through October 19, 2012) | Miscellaneous | 208.0, 222.0, 1404.3, 1405.3 |
| UL 1795-2009 | Hydromassage Bathtubs (with revisions through January 13, 2012) | Fixtures | 301.2.2, 301.3 |
| UL 1951-2011* | Electric Plumbing Accessories | Miscellaneous | 301.2.2, 301.3 |
| UL 2157-1997* | Electric Clothes Washing Machines and Extractors (with revisions through February 16, 2010) | Appliances | 301.2.2, 301.3 |
| <i>UL 2523-2009*</i> | Solid Fuel-Fired Hydronic Heating Appliances, Water Heaters, and Boilers (with revisions through February 8, 2013) | Fuel Gas, Appliances | Table 501.1(2) |
| WQA S-300-2000 | Point-of-Use Low Pressure Reverse Osmosis Drinking Water Systems | Appliances | 301.2.2, 301.3 |

*ANSI designated as an American National Standard.

Italic/Bold referenced standards indicate where such standards are located in the narrative of the code.

Notes:

- ¹ Although this standard is referenced in Table 1701.1, some of the pipe, tubing, fittings, valves, or fixtures included in the standard are not acceptable for use under the provisions of the Uniform Plumbing Code.
- ² See Section 605.1.4 and Section 705.3.3 for restrictions.
- ³ Alloy C85200 for cleanout plugs.
- ⁴ Limited to domestic sewage.
- ⁵ Type II only.
- ⁶ ASSE 1066 is not intended to limit the maximum outlet temperature at point of use.
- ⁷ See Section 314.0 for trenching, excavation, and backfilling requirements where installing building drains and sewers. Engineers shall be permitted to consult ASTM D2321, for thermoplastic pipe, where preparing construction documents for sewer mains or specific projects.

ABBREVIATIONS IN TABLE 1701.1

| | |
|--------------------|--|
| AHAM | Association of Home Appliance Manufacturers, 1111 19th Street, N.W., Suite 402, Washington DC 20036. |
| ANSI | American National Standards Institute, Inc., 25 W. 43rd Street, 4th Floor, New York, NY 10036. |
| APSP | Association of Pool and Spa Professionals, 2111 Eisenhower Avenue, Suite 500, Alexandria, VA 22314-4679. |
| ASCE | American Society of Civil Engineers, 1801 Alexander Bell Drive, Reston, VA 20191-4400. |
| ASHRAE | American Society of Heating, Refrigerating and Air Conditioning Engineers, Inc., 1791 Tullie Circle, NE, Atlanta, GA 30329-2305. |
| ASME | American Society of Mechanical Engineers, Two Park Avenue, New York, NY 10016-5990. |
| ASPE | American Society of Plumbing Engineers, 6400 Schafer Court, Suite 350, Rosemont, IL 60018. |
| ASSE | American Society of Sanitary Engineering, 18927 Hickory Creek Drive, Suite 220, Mokena IL 60448. |
| ASTM | ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA 19428-2959. |
| AWS | American Welding Society, 8669 NW 36 Street, #130 Miami, FL 33166-6672. |
| AWWA | American Water Works Association, 6666 W. Quincy Avenue, Denver, CO 80235. |
| CGA | Compressed Gas Association, 14501 George Carter Way, Suite 103, Chantilly, VA 20151. |
| CISPI | Cast-Iron Soil Pipe Institute, 2401 Fieldcrest Drive, Mundelein, IL 60060. |
| CSA | Canadian Standards Association, 5060 Spectrum Way, Suite 100, Mississauga, Ontario, Canada, L4W 5N6. |
| e1 | An editorial change since the last revision or reapproval. |
| ENERGY STAR | 1200 Pennsylvania Avenue, N.W., Washington, D.C. 20460. |
| EPA | |
| WATERSENSE | U.S. Environmental Protection Agency, Office of Wastewater Management (4204M), 1200 Pennsylvania Avenue, N.W., Washington, D.C. 20460. |
| IAPMO | International Association of Plumbing and Mechanical Officials, 5001 E. Philadelphia Street, Ontario, CA 91761. |
| ICC | International Code Council, 500 New Jersey Ave, NW, 6th Floor, Washington, DC 20001. |
| ISEA | International Safety Equipment Association, 1901 N. Moore Street, Arlington, VA 22209-1762. |
| ISO | International Organization for Standardization, 1 ch. de la Voie-Creuse, Casa Postale 56, CH-1211 Geneva 20, Switzerland. |
| MSS | Manufacturers Standardization Society of the Valve and Fittings Industry, 127 Park Street, N.E., Vienna, VA 22180. |
| NFPA | National Fire Protection Association, 1 Batterymarch Park, P.O. Box 9101, Quincy, MA 02169-7471. |
| NSF | NSF International, 789 Dixboro Road, Ann Arbor, MI 48113-0140. |
| PDI | Plumbing and Drainage Institute, 800 Turnpike Street, Suite 300, North Andover, MA 01845. |
| PSAI | Portable Sanitation Association International, 2626 E 82nd Street, Suite 175, Bloomington, MN 55425. |
| SAE | Society of Automotive Engineers, 400 Commonwealth Drive, Warrendale, PA 15096. |
| TCNA | Tile Council of North America, Inc. 100 Clemson Research Blvd., Anderson, SC 29625. |
| UL | Underwriters Laboratories, Inc., 333 Pfingsten Road, Northbrook, IL 60062. |
| WQA | Water Quality Association, 4151 Naperville Road, Lisle, IL 60532-3696. |

APPENDICES

The appendices are intended to supplement the provisions of the installation requirements of this code. The definitions in Chapter 2 are also applicable to the appendices.

CONTENTS

| | Page |
|--|------|
| Appendix A | |
| Recommended Rules for Sizing the Water Supply System..... | 285 |
| Appendix B | |
| Explanatory Notes on Combination Waste and Vent Systems | 295 |
| Appendix C | |
| Alternate Plumbing Systems | 297 |
| Appendix D | |
| Sizing Storm Water Drainage Systems..... | 305 |
| Appendix E | |
| Manufactured/Mobile Home Parks and Recreational Vehicle Parks..... | 313 |
| Appendix F | |
| Firefighter Breathing Air Replenishment Systems | 323 |
| Appendix G | |
| I Sizing of Venting Systems | 327 |
| Appendix H | |
| Private Sewage Disposal Systems | 337 |
| Appendix I | |
| Installation Standard | 347 |
| Appendix J | |
| Combination of Indoor and Outdoor Combustion and Ventilation Opening Design..... | 355 |
| Appendix K | |
| Potable Rainwater Catchment Systems..... | 357 |
| Appendix L | |
| Sustainable Practices..... | 363 |

APPENDIX A

RECOMMENDED RULES FOR SIZING THE WATER SUPPLY SYSTEM

A 101.0 General.

A 101.1 Applicability. This appendix provides a general procedure for sizing a water supply system. Because of the variable conditions encountered, it is impractical to lay down definite detailed rules of procedure for determining the sizes of water supply pipes in an appendix, which shall necessarily be limited in length. For a more adequate understanding of the problems involved, refer to Water-Distributing Systems for Buildings, Report BMS 79 of the National Bureau of Standards; and Plumbing Manual, Report BMS 66, also published by the National Bureau of Standards.

» A 102.0 Preliminary Information.

» **A 102.1 Daily Service Pressure.** Obtain the necessary information regarding the minimum daily service pressure in the area where the building is to be located.

» **A 102.2 Water Meter.** Where the building supply is to be metered, obtain information regarding friction loss relative to the rate of flow for meters in the range of sizes likely to be used. Friction-loss data is capable of being obtained from most manufacturers of water meters. Friction losses for disk-type meters shall be permitted to be obtained from Chart A 102.2.

» **A 102.3 Local Information.** Obtain available local information regarding the use of different kinds of pipe with

respect both to durability and to decrease in capacity with length of service in the particular water supply.

A 103.0 Demand Load.


» **A 103.1 Supply Demand.** Estimate the supply demand for the building main, the principal branches and risers of the system by totaling the fixture units on each, Table A 103.1, and then by reading the corresponding ordinate from Chart A 103.1(1) or Chart A 103.1(2), whichever is applicable.

» **A 103.2 Continuous Supply Demand.** Estimate continuous supply demands in gallons per minute (gpm) (L/s) for lawn sprinklers, air conditioners, etc., and add the sum to the total demand for fixtures. The result is the estimated supply demand of the building supply.

A 104.0 Permissible Friction Loss.

» **A 104.1 Residual Pressure.** Decide what is the desirable minimum residual pressure that shall be maintained at the highest fixture in the supply system. Where the highest group of fixtures contains flushometer valves, the residual pressure for the group shall be not less than 15 pounds-force per square inch (psi) (103 kPa). For flush tank supplies, the available residual pressure shall be not less than 8 psi (55 kPa).

CHART A 102.2
FRICTION LOSSES FOR DISK-TYPE WATER METERS



For SI units: 1 inch = 25 mm, 1 pound-force per square inch = 6.8947 kPa, 1 gallon per minute = 0.06 L/s

- » **A 104.2 Elevation.** Determine the elevation of the highest fixture or group of fixtures above the water (street) main. Multiply this difference in elevation by 0.43. The result is the loss in static pressure in psi (kPa).
- » **A 104.3 Available Pressure.** Subtract the sum of loss in static pressure and the residual pressure to be maintained at the highest fixture from the average minimum daily service pressure. The result will be the pressure available for friction loss in the supply pipes, where no water meter is used. Where a meter is to be installed, the friction loss in the meter for the estimated maximum demand should also be subtracted from the service pressure to determine the pressure loss available for friction loss in the supply pipes.
- » **A 104.4 Developed Length.** Determine the developed length of pipe from the water (street) main to the highest fixture. Where close estimates are desired, compute with the aid of Table A 104.4, the equivalent length of pipe for fittings in the line from the water (street) main to the highest fixture and add the sum to the developed length. The pressure available for friction loss in psi (kPa), divided by the developed lengths of pipe from the water (street) main to the highest fixture, times 100, will be the average permissible friction loss per 100 feet (30 480 mm) length of pipe.
- » **A 105.0 Size of Building Supply.**
- » **A 105.1 Diameter.** Knowing the permissible friction loss per 100 feet (30 480 mm) of pipe and the total demand, the diameter of the building supply pipe shall be permitted to be obtained from Chart A 105.1(1), Chart A 105.1(2), Chart A 105.1(3), or Chart A 105.1(4), whichever is applicable. The diameter of pipe on or next above the coordinate point corresponding to the estimated total demand and the permissible friction loss will be the size needed up to the first branch from the building supply pipe.
- » **A 105.2 Copper and Copper Alloy Piping.** Where copper tubing or copper alloy pipe is to be used for the supply piping and where the character of the water is such that slight changes in the hydraulic characteristics are expected, Chart A 105.1(1) shall be permitted to be used.
- » **A 105.3 Hard Water.** Chart A 105.1(2) shall be used for ferrous pipe with the most favorable water supply in regards to corrosion and caking. Where the water is hard or corrosive, Chart A 105.1(3) or Chart A 105.1(4) will be applicable. For extremely hard water, it will be advisable to make additional allowances for the reduction of capacity of hot-water lines in service.
- » **A 106.0 Size of Principal Branches and Risers.**
- » **A 106.1 Size.** The required size of branches and risers shall be permitted to be obtained in the same manner as the building supply, by obtaining the demand load on each branch or riser and using the permissible friction loss computed in Section A 104.0.
- » **A 106.2 Branches.** Where fixture branches to the building supply are sized for the same permissible friction loss per 100 feet (30 480 mm) of pipe as the branches and risers to the highest level in the building, and lead to inadequate

water supply to the upper floor of a building, one of the following shall be provided:

- (1) Selecting the sizes of pipe for the different branches so that the total friction loss in each lower branch is approximately equal to the total loss in the riser, including both friction loss and loss in static pressure.
- (2) Throttling each such branch by means of a valve until the preceding balance is obtained.
- (3) Increasing the size of the building supply and risers above the minimum required to meet the maximum permissible friction loss.

A 106.3 Water Closets. The size of branches and mains serving flushometer tanks shall be consistent with sizing procedures for flush tank water closets. <<

A 107.0 General. <<

A 107.1 Velocities. Velocities shall not exceed 10 feet per second (ft/s) (3 m/s), except as otherwise approved by the Authority Having Jurisdiction. <<

A 107.2 Pressure-Reducing Valves. Where a pressure-reducing valve is used in the building supply, the developed length of supply piping and the permissible friction loss shall be computed from the building side of the valve. <<

A 107.3 Fittings. The allowances in Table A 104.4 for fittings are based on non-recessed threaded fittings. For recessed threaded fittings and streamlined soldered fittings, one-half of the allowances given in the table will be ample. <<

TABLE A 103.1
WATER SUPPLY FIXTURE UNITS (WSFU) AND MINIMUM FIXTURE BRANCH PIPE SIZES³

| APPLIANCES, APPURTENANCES, OR FIXTURES ² | MINIMUM FIXTURE BRANCH PIPE SIZE ^{1,4} (Inches) | PRIVATE | PUBLIC | ASSEMBLY ⁶ |
|--|---|---------|--------|-----------------------|
| Bathtub or Combination Bath/Shower (fill) | ½ | 4.0 | 4.0 | — |
| ¾ inch Bathtub Fill Valve | ¾ | 10.0 | 10.0 | — |
| Bidet | ½ | 1.0 | — | — |
| Clothes Washer | ½ | 4.0 | 4.0 | — |
| Dental Unit, cuspidor | ½ | — | 1.0 | — |
| Dishwasher, domestic | ½ | 1.5 | 1.5 | — |
| Drinking Fountain or Water Cooler | ½ | 0.5 | 0.5 | 0.75 |
| Hose Bibb | ½ | 2.5 | 2.5 | — |
| Hose Bibb, each additional ⁷ | ½ | 1.0 | 1.0 | — |
| Lavatory | ½ | 1.0 | 1.0 | 1.0 |
| Lawn Sprinkler, each head ⁵ | — | 1.0 | 1.0 | — |
| Mobile Home, each (minimum) | — | 12.0 | — | — |
| Sinks | — | — | — | — |
| Bar | ½ | 1.0 | 2.0 | — |
| Clinical Faucet | ½ | — | 3.0 | — |
| Clinical Flushometer Valve with or without faucet | 1 | — | 8.0 | — |
| Kitchen, domestic | ½ | 1.5 | 1.5 | — |
| Laundry | ½ | 1.5 | 1.5 | — |
| Service or Mop Basin | ½ | 1.5 | 3.0 | — |
| Washup, each set of faucets | ½ | — | 2.0 | — |
| Shower per head | ½ | 2.0 | 2.0 | — |
| Urinal, 1.0 GPF Flushometer Valve | ¾ | 3.0 | 4.0 | 5.0 |
| Urinal, greater than 1.0 GPF Flushometer Valve | ¾ | 4.0 | 5.0 | 6.0 |
| Urinal, flush tank | ½ | 2.0 | 2.0 | 3.0 |
| Wash Fountain, circular spray | ¾ | — | 4.0 | — |
| Water Closet, 1.6 GPF Gravity Tank | ½ | 2.5 | 2.5 | 3.5 |
| Water Closet, 1.6 GPF Flushometer Tank | ½ | 2.5 | 2.5 | 3.5 |
| Water Closet, 1.6 GPF Flushometer Valve | 1 | 5.0 | 5.0 | 8.0 |
| Water Closet, greater than 1.6 GPF Gravity Tank | ½ | 3.0 | 5.5 | 7.0 |
| Water Closet, greater than 1.6 GPF Flushometer Valve | 1 | 7.0 | 8.0 | 10.0 |

For SI units: 1 inch = 25 mm

Notes:

¹ Size of the cold branch pipe, or both the hot and cold branch pipes.

² Appliances, appurtenances, or fixtures not included in this table shall be permitted to be sized by reference to fixtures having a similar flow rate and frequency of use.

³ The listed fixture unit values represent their total load on the cold water building supply. The separate cold water and hot water fixture unit value for fixtures having both cold and hot water connections shall be permitted to each be taken as three-quarters of the listed total value of the fixture.

⁴ The listed minimum supply branch pipe sizes for individual fixtures are the nominal (I.D.) pipe size.


⁵ For fixtures or supply connections likely to impose continuous flow demands, determine the required flow in gallons per minute (gpm) (L/s) and add it separately to the demand in gpm (L/s) for the distribution system or portions thereof.

⁶ Assembly [Public Use (see Table 422.1)].

⁷ Reduced fixture unit loading for additional hose bibbs is to be used where sizing total building demand and for pipe sizing where more than one hose bibb is supplied by a segment of water distribution pipe. The fixture branch to each hose bibb shall be sized on the basis of 2.5 fixture units.




CHART A 103.1(1)
ESTIMATE CURVES FOR DEMAND LOAD



For SI units: 1 gallon per minute = 0.06 L/s



CHART A 103.1(2)
ENLARGED SCALE DEMAND LOAD



For SI units: 1 gallon per minute = 0.06 L/s


TABLE A 104.4
ALLOWANCE IN EQUIVALENT LENGTH OF PIPE FOR FRICTION LOSS IN VALVES AND THREADED FITTINGS*
EQUIVALENT LENGTH OF PIPE FOR VARIOUS FITTINGS

| DIAMETER OF FITTING (inches) | 90° STANDARD ELBOW (feet) | 45° STANDARD ELBOW (feet) | 90° STANDARD TEE (feet) | COUPLING OR STRAIGHT RUN OF TEE (feet) | GATE VALVE (feet) | GLOBE VALVE (feet) | ANGLE VALVE (feet) |
|------------------------------------|---------------------------------|---------------------------------|-------------------------------|---|----------------------|-----------------------|-----------------------|
| $\frac{3}{8}$ | 1.0 | 0.6 | 1.5 | 0.3 | 0.2 | 8 | 4 |
| $\frac{1}{2}$ | 2.0 | 1.2 | 3.0 | 0.6 | 0.4 | 15 | 8 |
| $\frac{3}{4}$ | 2.5 | 1.5 | 4.0 | 0.8 | 0.5 | 20 | 12 |
| 1 | 3.0 | 1.8 | 5.0 | 0.9 | 0.6 | 25 | 15 |
| 1 $\frac{1}{4}$ | 4.0 | 2.4 | 6.0 | 1.2 | 0.8 | 35 | 18 |
| 1 $\frac{1}{2}$ | 5.0 | 3.0 | 7.0 | 1.5 | 1.0 | 45 | 22 |
| 2 | 7.0 | 4.0 | 10.0 | 2.0 | 1.3 | 55 | 28 |
| 2 $\frac{1}{2}$ | 8.0 | 5.0 | 12.0 | 2.5 | 1.6 | 65 | 34 |
| 3 | 10.0 | 6.0 | 15.0 | 3.0 | 2.0 | 80 | 40 |
| 4 | 14.0 | 8.0 | 21.0 | 4.0 | 2.7 | 125 | 55 |
| 5 | 17.0 | 10.0 | 25.0 | 5.0 | 3.3 | 140 | 70 |
| 6 | 20.0 | 12.0 | 30.0 | 6.0 | 4.0 | 165 | 80 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm, 1 degree = 0.017 rad


* Allowances are based on nonrecessed threaded fittings. Use one-half the allowances for recessed threaded fittings or streamlined solder fittings.

CHART A 105.1(1)




For SI units: 1 inch = 25 mm, 1 gallon per minute = 0.06 L/s, 1 pound-force per square inch = 6.8947 kPa, 1 foot = 304.8 mm,
1 foot per second = 0.3048 m/s

CHART A 105.1(2)




For SI units: 1 inch = 25 mm, 1 gallon per minute = 0.06 L/s, 1 pound-force per square inch = 6.8947 kPa, 1 foot = 304.8 mm, 1 foot per second = 0.3048 m/s

CHART A 105.1(3)



For SI units: 1 inch = 25 mm, 1 gallon per minute = 0.06 L/s, 1 pound-force per square inch = 6.8947 kPa, 1 foot = 304.8 mm, 1 foot per second = 0.3048 m/s

CHART A 105.1(4)



For SI units: 1 inch = 25 mm, 1 gallon per minute = 0.06 L/s, 1 pound-force per square inch = 6.8947 kPa, 1 foot = 304.8 mm, 1 foot per second = 0.3048 m/s

» A 108.0 Sizing.

» A 108.1 Example. Assume an office building of four stories and basement; pressure on the building side of the pressure-reducing valve of 55 psi (379 kPa) (after an allowance for reduced pressure falloff at peak demand); an elevation of highest fixture above the pressure-reducing valve of 45 feet (13 716 mm); a developed length of pipe from the pressure-reducing valve to the most distant fixture of 200 feet (60 960 mm); and fixtures to be installed with flush valves for water closets and stall urinals as follows:

Where the pipe material and water supply are such that Chart A 105.1(2) applies, the required diameter of the building supply is 3½ inches (90 mm) and the required diameter of the branch to the hot-water heater is 1½ inches (40 mm).

The sizes of the various branches and risers shall be permitted to be determined in the same manner as the size of the building supply or the branch to the hot-water system, by estimating the demand for the riser or branch from Chart A 103.1(1) or Chart A 103.1(2) and applying the total demand estimate from the branch, riser, or section thereof to the appropriate flowchart.

» A 108.1 EXAMPLE

| FIXTURE UNITS AND ESTIMATED DEMANDS | | | | | | | |
|-------------------------------------|--------------------|---------------------|-------------|---|--------------------|--|-----------------------------|
| BUILDING SUPPLY DEMAND | | | | BRANCH TO HOT WATER SYSTEM | | | |
| KIND OF FIXTURES | NUMBER OF FIXTURES | FIXTURE UNIT DEMAND | TOTAL UNITS | BUILDING SUPPLY DEMAND (gallons per minute) | NUMBER OF FIXTURES | FIXTURE UNIT DEMAND CALCULATION | DEMAND (gallons per minute) |
| Water Closets | 130 | 8.0 | 1040 | — | — | — | — |
| Urinals | 30 | 4.0 | 120 | — | — | — | — |
| Showerheads | 12 | 2.0 | 24 | — | 12 | $12 \times 2 \times \frac{3}{4} = 18$ | — |
| Lavatories | 100 | 1.0 | 100 | — | 100 | $100 \times 1 \times \frac{3}{4} = 75$ | — |
| Service Sinks | 27 | 3.0 | 81 | — | 27 | $27 \times 3 \times \frac{3}{4} = 61$ | — |
| Total | — | — | 1365 | 252 | — | 154 | 55 |

For SI units: 1 gallon per minute = 0.06 L/s, 1 pound-force per square foot = 6.8947 kPa

Allowing for 15 psi (103 kPa) at the highest fixture under the maximum demand of 252 gallons per minute (15.88 L/s), the pressure available for friction loss is found by the following:

$$55 - [15 + (45 \times 0.43)] = 20.65 \text{ psi (142.38 kPa)}$$

The allowable friction loss per 100 feet (30 480 mm) of pipe is therefore:

$$100 \times 20.65 \div 200 = 10.32 \text{ psi (71.15 kPa)}$$

APPENDIX B

EXPLANATORY NOTES ON COMBINATION WASTE AND VENT SYSTEMS

(See Section 910.0 for specific limitations)

B 101.0 General.

B 101.1 Applicability. This appendix provides general guidelines for the design and installation of a combination waste and vent system.

- » **B 101.2 General Requirements.** Combination waste and vent systems, as outlined in Section 910.0 of this code, cover the horizontal wet venting of a series of traps by means of a common waste and vent pipe. Pipe sizes not less than two pipe sizes larger than those required for a conventional system are designed to maintain a wetted perimeter or flow line low enough in the waste pipe to allow adequate air movement in the upper portion, thus balancing the system. Sinks, lavatories, and other fixtures that rough in above the floor, shall not be permitted on a combination waste and vent system, which, at best, is merely an expedient designed to be used in locations where it would be structurally impractical to provide venting in the conventional manner.

Combination waste and vent systems are intended primarily for extensive floor or shower drain installations where separate venting is not practical, for floor sinks in markets, demonstration or work tables in school buildings, or for similar applications where the fixtures are not adjacent to walls or partitions. Due to its oversize characteristics, such a waste system is not self-scouring and, consequently, care shall be exercised as to the type of fixtures connected thereto and to the location of cleanouts. In view of its grease-producing potential, restaurant kitchen equipment shall not be connected to a combination waste and vent system.

- » **B 101.3 Caution.** Caution shall be exercised to exclude appurtenances delivering large quantities or surges of water (such as pumps, sand interceptors, etc.) from combination waste and vent systems in order that adequate venting will be maintained. Small fixtures with a waste-producing potential of less than $7\frac{1}{2}$ gallons per minute (gpm) (0.47 L/s) shall be permitted to be safely assigned a loading value of one unit. Long runs shall be laid at the minimum permissible slope in order to keep tailpieces as short as possible. Tailpieces shall not exceed 2 feet (610 mm) in length, which shall necessitate slopes up to 45 degrees (0.79 rad) (see definition of horizontal pipe) on some branches.
- » **B 101.4 Pneumatics.** It is essential that the pneumatics of such a system be properly engineered, as the air pressure within the line shall at all times balance that of outside atmosphere in order to prevent either trap seal loss or air locking between traps. Long mains shall be provided with additional relief vents located at intervals not exceeding 100 feet (30 480 mm). Each such relief vent shall equal not less than one-half of the inside cross-sectional area of the drain pipe served.

B 101.5 Trap Sizes. Trap sizes are required to be equivalent to the branches they serve (two pipe sizes larger than normal), and tailpieces between fixtures or floor drains and such traps shall be reduced to normal size.

B 101.6 Layout Drawings. Duplicate layout drawings of each such proposed piping system shall be presented to the Authority Having Jurisdiction and approval obtained before an installation is made. Complicated layouts shall be checked by qualified personnel.

B 101.6.1 Example of Sizing. A floor drain normally requires a 2 inch (50 mm) trap and waste. On a combination waste and vent system, both trap and waste shall be increased two pipe sizes (through $2\frac{1}{2}$ inches and 3 inches) (65 mm and 80 mm), which would make the trap 3 inches (80 mm). Pipe sizes recognized for this purpose are 2 inches, $2\frac{1}{2}$ inches, 3 inches, $3\frac{1}{2}$ inches, 4 inches, $4\frac{1}{2}$ inches, 5 inches, 6 inches, etc. (50 mm, 65 mm, 80 mm, 90 mm, 100 mm, 115 mm, 125 mm, 150 mm, etc.). The tailpiece between the floor drain and its trap shall be 2 inches (50 mm) (or normal size) to ensure that the amount of wastewater entering the trap partially fills the waste branch. A 3 inch (80 mm) floor drain would thus require a 4 inch (100 mm) trap, and a 4 inch (100 mm) floor drain would require a 5 inch (125 mm) trap for the reasons previously stated.

WHERE IN DOUBT, CHECK WITH YOUR LOCAL Authority Having Jurisdiction.

APPENDIX C

ALTERNATE PLUMBING SYSTEMS

C 101.0 General.

C 101.1 Applicability. The intent of this appendix is to provide clarification of procedures for the design and approval of engineered plumbing systems, alternate materials, and equipment not specifically covered in other parts of the code.

C 101.2 Provisions. The provisions of this appendix apply to the design, installation, and inspection of an engineered plumbing system, alternate material, and equipment.

C 101.3 Authority Having Jurisdiction. The Authority Having Jurisdiction has the right to require descriptive details of an engineered plumbing system, alternate material, or equipment including pertinent technical data to be filed.

C 101.4 Standards and Specifications. Components, materials, and equipment shall comply with standards and specifications listed in Table 1701.1 of this code and other national consensus standards applicable to plumbing systems and materials.

C 101.5 Alternate Materials and Equipment. Where such standards and specifications are not available, alternate materials and equipment shall be approved in accordance with the provisions of Section 301.3 of this code.

» C 201.0 Definitions.

C 201.1 General. For the purposes of this code, these definitions shall apply to this appendix:

Branch Interval. A length of soil or waste stack corresponding in general to a story height, but in no case less than 8 feet (2438 mm), within which the horizontal branches from one floor or story of the building are connected to the stack.

Engineered Plumbing System. A system designed for a specific building project with drawings and specifications indicating plumbing materials to be installed, all as prepared by a registered design professional.

» C 301.0 Engineered Plumbing Systems.

» **C 301.1 Inspection and Installation.** In other than one- and two-family dwellings, the designer of the system is to provide periodic inspection of the installation on a schedule approved by the Authority Having Jurisdiction. Prior to the final approval, the designer shall verify to the Authority Having Jurisdiction that the installation is in accordance with the approved plans, specifications, and data and such amendments thereto. The designer shall certify to the Authority Having Jurisdiction that the installation is in accordance with the applicable engineered design criteria.

» **C 301.2 Owner Information.** The designer of the system shall provide the building owner with information concerning the system, considerations applicable for subsequent modifications to the system, and maintenance requirements as applicable.

C 302.0 Water Heat Exchangers. <<

C 302.1 Protection from Contamination. Heat exchangers used for heat transfer, heat recovery, or solar heating shall protect the potable water system from being contaminated by the heat-transfer medium. <<

C 302.2 Single-Wall Heat Exchangers. Single-wall heat exchangers shall comply with the following requirements: <<

- (1) The heat-transfer medium is either potable water or contains essentially nontoxic transfer fluids having a toxicity rating or class of 1 (see Section 207.0).
- (2) The pressure of the heat-transfer medium is maintained at less than the normal minimum operating pressure of the potable water system.

Exception: Steam in accordance with Section C 302.2(1) above.

- (3) The equipment is permanently labeled to indicate that only additives recognized as safe by the FDA shall be used in the heat-transfer medium.

C 302.3 Alternate Designs. Other heat exchanger designs shall be permitted where approved by the Authority Having Jurisdiction. <<

C 303.0 Fixture Unit Values for Private or Private Use Bathroom Groups. <<

C 303.1 Fixtures. Table C 303.1(1) and Table C 303.1(2) reflect the fixture unit loads for the fixtures in bathrooms as groups, rather than as individual fixtures. Such fixtures include water closets, lavatories, and bathtubs or showers. The tables reflect diversity in the use of fixtures within a bathroom and between multiple bathrooms. <<

C 303.2 Water Supply Fixture Unit Values. The listed water supply fixture unit values in Table C 303.1(1) reflect the load of entire bathroom groups on the cold water building supply. Individual hot and cold water branch piping to the fixtures shall be permitted to be sized in accordance with Chapter 6 and Appendix A. <<

C 303.3 Drainage Fixture Unit Values. The listed drainage fixture unit values in Table C 303.1(2) reflect the load of entire bathroom groups on the sanitary drainage system. Where fixtures within bathrooms connect to different branches of the drainage system, the fixture unit values for the individual fixtures shall be used, as listed in Table 702.1 of this code. <<

C 304.0 Drainage System Sizing. <<

C 304.1 Drainage Fixture Units. Drainage fixture unit values shall be sized in accordance with Section 702.0 and Table 702.1. <<

TABLE C 303.1(1)
WATER SUPPLY FIXTURE UNITS (WSFU) FOR BATHROOM GROUPS^{1, 2}

| | PRIVATE USE BATHROOM GROUP | | SERVING 3 OR MORE PRIVATE USE BATHROOM GROUPS | |
|---|-------------------------------|------------------|---|-----|
| | COLD | HOT ³ | COLD | HOT |
| Bathroom Groups Having up to 1.6 GPF Gravity-Tank Water Closets | | | | |
| Half-Bath or Powder Room | 3.5 | 0.8 | 2.5 | 0.5 |
| 1 Bathroom Group | 5.0 | 2.5 | 3.5 | 1.8 |
| 1½ Bathrooms | 6.0 | 2.5 | — | — |
| 2 Bathrooms | 7.0 | 3.5 | — | — |
| 2½ Bathrooms | 8.0 | 3.6 | — | — |
| 3 Bathrooms | 9.0 | 4.5 | — | — |
| Each Additional ½ Bath | 0.5 | 0.1 | — | — |
| Each Additional Bathroom Group | 1.0 | 0.5 | — | — |
| Bathroom Groups Having up to 1.6 GPF Pressure-Tank Water Closets | | | | |
| Half-Bath or Powder Room | 3.5 | 0.8 | 2.5 | 0.5 |
| 1 Bathroom Group | 5.0 | 2.5 | 3.5 | 1.8 |
| 1½ Bathrooms | 6.0 | 2.5 | — | — |
| 2 Bathrooms | 7.0 | 3.5 | — | — |
| 2½ Bathrooms | 8.0 | 3.6 | — | — |
| 3 Bathrooms | 9.0 | 4.5 | — | — |
| Each Additional ½ Bath | 0.5 | 0.1 | — | — |
| Each Additional Bathroom Group | 1.0 | 0.5 | — | — |
| Bathroom Group (1.6 GPF Flushometer Value) | 6.0 | 2.5 | 4.0 | 1.7 |
| Kitchen Group (Sink and Dishwasher) | 2.0 | 2.0 | 1.5 | 1.5 |
| Laundry Group (Sink and Clothes Washer) | 5.0 | 5.0 | 3.0 | 3.0 |

Notes:

¹ A bathroom group, for the purposes of this table, consists of one water closet, up to two lavatories, and either one bathtub or one shower.

² A half-bath or powder room, for the purposes of this table, consists of one water closet and one lavatory.

³ Multi-unit dwellings with individual water heaters use the same WSFU as for individual dwellings.

» **C 304.2 Size of Building Drain and Building Sewer.**

The maximum number of drainage fixture units allowed on the building drain or building sewer of a given size shall be in accordance with Table C 304.2. The size of a building drain or building sewer serving a water closet shall be not less than 3 inches (80 mm).

» **C 304.3 Size of Horizontal Branch or Vertical Stack.** The maximum number of drainage fixture units allowed on a horizontal branch or vertical soil or waste stack of a given size shall be in accordance with Table C 304.3. Stacks shall be sized based on the total accumulated connected load at each story or branch interval.

» **C 304.3.1 Horizontal Stack Offsets.** Horizontal stack offsets shall be sized in accordance with Table C 304.2 as required for building drains.

» **C 304.3.2 Vertical Stack Offsets.** Vertical stack offsets shall be sized in accordance with Table C 304.3 as required for stacks.

» **C 304.4 Horizontal Stack Offset and Horizontal Branch Connections.** Horizontal branch connections shall not connect to a horizontal stack offset or within 2 feet (610 mm) above or below the offset where such horizontal

offset is located more than four branch intervals below the top of the stack.

C 401.0 Vent System Sizing.

« **C 401.1 Size of Vents.** The size of vent piping shall be determined from the developed length and the total number of drainage fixture units connected in accordance with Table C 401.1. Vents shall be not less than one-half the required size of the drainage pipe size served as determined by Table C 304.3 for horizontal fixture branches and stacks nor less than 1¼ inches (32 mm) in diameter. The drainage system shall be vented by not less than one vent pipe which shall be not less than one-half the size of the required building drain and which shall extend from the building drain or extension of building drain to the outdoors. Vents shall be installed in accordance with Chapter 9.

« **C 401.2 Vent Stack.** A vent stack shall be required for a drainage stack that extends five or more branch intervals above the building drain or horizontal branch. The developed length of the vent stack shall be measured from the lowest connection of a branch vent to the termination outdoors.

TABLE C 303.1(2)
DRAINAGE FIXTURE UNIT VALUES (DFU) FOR BATHROOM GROUPS^{1, 2}

«

| | PRIVATE USE BATHROOM GROUP | SERVING 3 OR MORE PRIVATE USE BATHROOM GROUP |
|---|----------------------------|--|
| Bathroom Groups having 1.6 GPF Gravity-Tank Water Closets | | |
| Half-Bath or Powder Room | 3.0 | 2.0 |
| 1 Bathroom Group | 5.0 | 3.0 |
| 1½ Bathrooms | 6.0 | — |
| 2 Bathrooms | 7.0 | — |
| 2½ Bathrooms | 8.0 | — |
| 3 Bathrooms | 9.0 | — |
| Each Additional ½ Bath | 0.5 | — |
| Each Additional Bathroom Group | 1.0 | — |
| Bathroom Groups having 1.6 GPF Pressure-Tank Water Closets | | |
| Half-Bath or Powder Room | 3.5 | 2.5 |
| 1 Bathroom Group | 5.5 | 3.5 |
| 1½ Bathrooms | 6.5 | — |
| 2 Bathrooms | 7.5 | — |
| 2½ Bathrooms | 8.5 | — |
| 3 Bathrooms | 9.5 | — |
| Each Additional ½ Bath | 0.5 | — |
| Each Additional Bathroom Group | 1.0 | — |
| Bathroom Groups having 3.5 GPF Gravity-Tank Water Closets | | |
| Half-Bath or Powder Room | 3.0 | 2.0 |
| 1 Bathroom Group | 6.0 | 4.0 |
| 1½ Bathrooms | 8.0 | — |
| 2 Bathrooms | 10.0 | — |
| 2½ Bathrooms | 11.0 | — |
| 3 Bathrooms | 12.0 | — |
| Each Additional ½ Bath | 0.5 | — |
| Each Additional Bathroom | 1.0 | — |
| Bathroom Group (1.6 GPF Flushometer Valve) | 3.0 | — |
| Bathroom Group (3.5 GPF Flushometer Valve) | 4.0 | — |

Notes:

¹ A bathroom group, for the purposes of this table, consists of not more than one water closet, up to two lavatories, and either one bathtub or one shower.

² A half-bath or powder room, for the purposes of this table, consists of one water closet and one lavatory.

» **C 401.3 Branch Vents.** Where branch vents exceed 40 feet (12 192 mm) in developed length, such vent shall be increased by one pipe size for the entire developed length of the vent pipe.

» **C 401.4 Venting Horizontal Offsets.** Drainage stacks with horizontal offsets shall be vented where five or more branch intervals are located above the offset. The upper and lower section of the horizontal offset shall be vented in accordance with Section C 401.4.1 and Section C 401.4.2.

» **C 401.4.1 Venting Upper Section.** The vent for the upper section of the stack shall be vented as a separate stack with a vent stack connection installed at the base of the drainage stack. Such vent stack shall connect below the lowest horizontal branch or building drain. Where vent stack connects to the building drain, the connection shall be located downstream of the drainage

stack and within a distance of 10 times the diameter of the drainage stack.

» **C 401.4.2 Venting Lower Section.** The vent for the lower section of the stack shall be vented by a yoke vent connecting between the offset and the next lower horizontal branch by means of a wye-branch fitting. The size of the yoke vent and connection shall be not less in diameter than the required size for the vent serving the drainage stack. The yoke vent connection shall be permitted to be a vertical extension of the drainage stack.

» **C 501.0 Vacuum Drainage Systems.**

» **C 501.1 General.** This section regulates the design and installation provisions for vacuum waste drainage systems. Plans for vacuum waste drainage systems shall be submitted to the Authority Having Jurisdiction for approval and shall

«

«

TABLE C 304.2
BUILDING DRAINS AND BUILDING SEWERS¹

| DIAMETER OF PIPE (inches) | MAXIMUM NUMBER OF DRAINAGE FIXTURE UNITS FOR SANITARY BUILDING DRAINS AND RUNOUTS FROM STACKS | | | |
|---------------------------------|---|------|-----------------|-----------------|
| | SLOPE (inches per foot) | | | |
| | 1/16 | 1/8 | 1/4 | 1/2 |
| 2 | — | — | 21 | 26 |
| 2½ | — | — | 24 | 31 |
| 3 | — | 20 | 42 ² | 50 ² |
| 4 | — | 180 | 216 | 250 |
| 5 | — | 390 | 480 | 575 |
| 6 | — | 700 | 840 | 1000 |
| 8 | 1400 | 1600 | 1920 | 2300 |
| 10 | 2500 | 2900 | 3500 | 4200 |
| 12 | 2900 | 4600 | 5600 | 6700 |
| 15 | 7000 | 8300 | 10 000 | 12 000 |

For SI units: 1 inch = 25 mm, 1 inch per foot = 83.3 mm/m

Notes:

- ¹ On-site sewers that serve more than one building shall be permitted to be sized according to the current standards and specifications of the administrative authority for public sewers.
- ² A maximum of two water closets or two bathroom groups, except in single-family dwellings, where a maximum of three water closets or three bathroom groups shall be permitted to be installed.

TABLE C 304.3
HORIZONTAL FIXTURE BRANCHES AND STACKS

| DIAMETER OF PIPE (inches) | MAXIMUM NUMBER OF DRAINAGE FIXTURE UNITS | | | |
|---------------------------------|---|--|--|---------------------------------|
| | HORIZONTAL FIXTURE BRANCH ¹ | ONE STACK OF THREE OR FEWER BRANCH INTERVALS | STACKS WITH MORE THAN THREE BRANCH INTERVALS | |
| | | | TOTAL FOR STACK | TOTAL AT ONE BRANCH INTERVAL |
| 1½ | 3 | 4 | 8 | 2 |
| 2 | 6 | 10 | 24 | 6 |
| 2½ | 12 | 20 | 42 | 9 |
| 3 | 20 ² | 48 ² | 72 ² | 20 ² |
| 4 | 160 | 240 | 500 | 90 |
| 5 | 360 | 540 | 1100 | 200 |
| 6 | 620 | 960 | 1900 | 350 |
| 8 | 1400 | 2200 | 3600 | 600 |
| 10 | 2500 | 3800 | 5600 | 1000 |
| 12 | 3900 | 6000 | 8400 | 1500 |
| 15 | 7000 | 6000 | 8400 | 1500 |

For SI units: 1 inch = 25 mm

Notes:

- ¹ Does not include branches of the building drain.
- ² A maximum of two water closets or bathroom groups within each branch interval or more than six water closets or bathroom groups on the stack.

be considered an engineered designed system. Such plans shall be prepared by a registered design professional to perform plumbing design work. Details are necessary to ensure compliance with the requirements of this section, together with a full description of the complete installation including quality, grade of materials, equipment, construction, and methods of assembly and installation. Components, materials, and equipment shall comply with standards and specifications listed in Table 1701.1 of this code or approved by the Authority Having Jurisdiction and other national consensus standards applicable to plumbing

systems and materials. Where such standards and specifications are not available, alternate materials and equipment shall be approved in accordance with Section 301.3.

C 501.2 System Design. Vacuum waste drainage systems shall be designed and installed in accordance with the manufacturer's installation instructions. A vacuum waste drainage system shall include a vacuum generating system, waste collection center, piping network, vacuum valve, and control components used to isolate the vacuum piping network from atmospheric pressure and to collect waste at its point of origin. Where a vacuum system pro-

TABLE C 401.1
SIZE AND LENGTH OF VENTS

«

| SIZE OF SOIL OR WASTE STACK (Inches) | FIXTURE UNITS CONNECTED | DIAMETER OF VENT REQUIRED (inches) | | | | | | | | |
|---|-------------------------------|------------------------------------|-----|-----|-----|-----|------|------|------|------|
| | | 1¼ | 1½ | 2 | 2½ | 3 | 4 | 5 | 6 | 8 |
| | | MAXIMUM LENGTH OF VENT (feet) | | | | | | | | |
| 1½ | 8 | 50 | 150 | — | — | — | — | — | — | — |
| 2 | 12 | 30 | 75 | 200 | — | — | — | — | — | — |
| 2 | 20 | 26 | 50 | 150 | — | — | — | — | — | — |
| 2½ | 42 | — | 30 | 100 | 300 | — | — | — | — | — |
| 3 | 10 | — | 30 | 100 | 100 | 600 | — | — | — | — |
| 3 | 30 | — | — | 60 | 200 | 500 | — | — | — | — |
| 3 | 60 | — | — | 50 | 80 | 400 | — | — | — | — |
| 4 | 100 | — | — | 35 | 100 | 260 | 1000 | — | — | — |
| 4 | 200 | — | — | 30 | 90 | 250 | 900 | — | — | — |
| 4 | 500 | — | — | 20 | 70 | 180 | 700 | — | — | — |
| 5 | 200 | — | — | — | 35 | 80 | 350 | 1000 | — | — |
| 5 | 500 | — | — | — | 30 | 70 | 300 | 900 | — | — |
| 5 | 1100 | — | — | — | 20 | 50 | 200 | 700 | — | — |
| 6 | 350 | — | — | — | 25 | 50 | 200 | 400 | 1300 | — |
| 6 | 620 | — | — | — | 15 | 30 | 125 | 300 | 1100 | — |
| 6 | 960 | — | — | — | — | 24 | 100 | 250 | 1000 | — |
| 6 | 1900 | — | — | — | — | 20 | 70 | 200 | 700 | — |
| 8 | 600 | — | — | — | — | — | 50 | 150 | 500 | 1300 |
| 8 | 1400 | — | — | — | — | — | 40 | 100 | 400 | 1200 |
| 8 | 2200 | — | — | — | — | — | 30 | 80 | 350 | 1100 |
| 8 | 3600 | — | — | — | — | — | 25 | 60 | 250 | 800 |
| 10 | 1000 | — | — | — | — | — | — | 75 | 125 | 1000 |
| 10 | 2500 | — | — | — | — | — | — | 50 | 100 | 500 |
| 10 | 3800 | — | — | — | — | — | — | 30 | 80 | 350 |
| 10 | 5600 | — | — | — | — | — | — | 25 | 60 | 250 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm

vides the only means of sanitation, duplicate vacuum generating equipment set to operate automatically shall be installed to allow the system to continue in operation during periods of maintenance.

» **C 501.2.1 Vacuum Generating System.** The vacuum generating station shall include vacuum pumps to create a constant vacuum pressure within the piping network and storage tanks. Operation of pumps, collection tanks, and alarms shall be automated by controls. The vacuum pumps shall be activated on demand and accessible for repair or replacement. The vent from the vacuum pump shall be provided for vacuum pump air exhaust, and shall be of a size capable of handling the total air volume of the vacuum pump.

» **C 501.2.2 Waste Collection Center or Storage Tanks.** Vacuum collection center or storage tanks shall be of such capacity as to provide storage of waste to prevent fouling of the system. Such collection or storage tank shall be capable of withstanding 150 percent of the rated vacuum (negative pressure) created by the vacuum source without leakage or collapse.

Waste collection center or storage tanks shall be accessible for adjustment, repair, or replacement.

« **C 501.2.3 Piping Network.** The piping network shall be under a continuous vacuum and shall be designed to withstand 150 percent of the vacuum (negative pressure) created by the vacuum source within the system without leakage or collapse. Sizing the piping network shall be in accordance with the manufacturer's instructions. The water closet outlet fitting shall connect with a piping network having not less than a 1½ inch (40 mm) nominal inside diameter.

« **C 501.2.4 Vacuum Interface Valve.** A closed vacuum interface valve shall be installed to separate the piping network vacuum from atmospheric pressure. A control device shall open the vacuum interface valve where a signal is generated to remove waste from the plumbing fixture.

« **C 501.2.5 Control Components.** Where a pneumatic signal is generated at the controller, a vacuum from the system to open the extraction valve shall be designed to operate where vacuum pressure exists to

remove the accumulated waste. Each tank shall incorporate a level indicator switch that automatically controls the discharge pump and warns of malfunction or blockage as follows:

- (1) Start discharge.
- (2) Stop discharge.
- (3) Activate an audible alarm where the level of effluent is usually high.
- (4) Warning of system shutdown where tank is full.

» **C 501.3 Fixtures.** Fixtures utilized in a vacuum waste drainage system shall be in accordance with referenced standards listed in Table 1701.1. Components shall be of corrosion resistant materials. The water closet outlet shall be able to pass a 1 inch (25.4 mm) diameter ball and shall have a smooth, impervious surface. The waste outlet and passages shall be free of obstructions, recesses, or chambers that are capable of permitting fouling. The mechanical valve and its seat shall be of such materials and design to provide a leak-free connection where at atmospheric pressure or under vacuum. The flushing mechanism shall be so designed as to ensure proper cleansing of the interior surfaces during the flushing cycle at a minimum operating flow rate. Mechanical seal mechanisms shall withdraw completely from the path of the waste discharge during flushing operation. Each mechanical seal vacuum water closet shall be equipped with a listed vacuum breaker. The vacuum breaker shall be mounted with the critical level or marking not less than 1 inch (25.4 mm) above the flood-level rim of the fixture. Vacuum breakers shall be installed on the discharge side of the last control valve in the potable water supply line and shall be located so as to be protected from physical damage and contamination.

» **C 501.4 Drainage Fixture Units.** Drainage fixture units shall be determined by the manufacturer's instructions. The pump discharge load from the collector tanks shall be in accordance with this appendix.

» **C 501.5 Water Supply Fixture Units.** Water supply fixture units shall be determined by the manufacturer's instructions.

» **C 501.6 Materials.** Materials used for water distribution pipe and fittings shall be in accordance with Table 604.1. Materials used for aboveground drainage shall be in accordance with Table 701.2 and shall have a smooth bore, and be constructed of non-porous material.

» **C 501.7 Traps and Cleanouts.** Traps and cleanouts shall be installed in accordance with Chapter 7 and Chapter 10.

» **C 501.8 Testing.** The entire vacuum waste system shall be subjected to a vacuum test of 29 inches of mercury (98 kPa) or not less than the working pressure of the system for 30 minutes. The system shall be gastight and watertight at all points. Verification of test results shall be submitted to the Authority Having Jurisdiction.

» **C 501.9 Manufacturer's Instructions.** Manufacturer's instructions shall be provided for the purpose of providing information regarding safe and proper operating instructions whether or not as part of the condition of listing in order to

determine compliance. Such instructions shall be submitted and approved by the Authority Having Jurisdiction.

C 601.0 Single-Stack Vent System. <<

C 601.1 Where Permitted. Single-stack venting shall be designed by a registered design professional as an engineered design. A drainage stack shall be permitted to serve as a single-stack vent system where sized and installed in accordance with Section C 601.2 through Section C 601.9. The drainage stack and branch piping in a single-stack vent system shall provide for the flow of liquids, solids, and air without the loss of fixture trap seals.

C 601.2 Stack Size. Drainage stacks shall be sized in accordance with Table C 601.2. Not more than two water closets shall be permitted to discharge to a 3 inch (80 mm) stack. Stacks shall be uniformly sized based on the total connected drainage fixture unit load, with no reductions in size.

C 601.2.1 Stack Vent. The drainage stack vent shall have a stack vent of the same size terminating to the outdoors.

C 601.3 Branch Size. Horizontal branches connecting to a single-stack vent system shall be sized in accordance with Table 703.2.

Exceptions:

- (1) Not more than one water closet within 18 inches (457 mm) of the stack horizontally shall be permitted on a 3 inch (80 mm) horizontal branch.
- (2) A water closet within 18 inches (457 mm) of a stack horizontally and one other fixture with up to 1½ inch (40 mm) fixture drain size shall be permitted on a 3 inch (80 mm) horizontal branch where connected to the stack through a sanitary tee.

C 601.4 Length of Horizontal Branches. Water closets shall be not more than 4 feet (1219 mm) horizontally from the stack.

Exception: Water closets shall be permitted to be up to 8 feet (2438 mm) horizontally from the stack where connected to the stack through a sanitary tee.

C 601.4.1 Other Fixtures. Fixtures other than water closets shall be not less than 12 feet (3658 mm) horizontally from the stack.

C 601.4.2 Length of Vertical Piping. The length of a vertical piping from a fixture trap to a horizontal branch shall not be considered in computing the fixture's horizontal distance from the stack.

C 601.5 Maximum Vertical Drops from Fixtures. Vertical drops from fixture traps to horizontal branch piping shall be one size larger than the trap size, but not less than 2 inch (50 mm) in diameter. Vertical drops shall be 4 feet (1219 mm) maximum length. Fixture drains that are not increased in size, or have a vertical drop exceeding 4 feet (1219 mm) shall be individually vented.

C 601.6 Additional Venting Required. Additional venting shall be provided where more than one water closet is on a horizontal branch and where the distance from a

fixture trap to the stack exceeds the limits in Section C 601.4. Where additional venting is required, the fixture(s) shall be vented by individual vents, common vents, wet vents, circuit vents, or a combination waste and vent pipe. The dry vent extensions for the additional venting shall connect to a branch vent, vent stack, stack vent, or be extended outdoors and terminate to the open air.

- » **C 601.7 Stack Offsets.** Where there are no fixture drain connections below a horizontal offset in a stack, the offset does not need to be vented. Where there are fixture drain connections below a horizontal offset in a stack, the offset shall be vented. There shall be no fixture connections to a stack within 2 feet (610 mm) above and below a horizontal offset.
- » **C 601.8 Separate Stack Required.** Where stacks are more than two stories high, a separate stack shall be provided for the fixtures on the lower two stories. The stack for the lower two stories shall be permitted to be connected to the branch of the building drain that serves the stack for the upper stories at a point that is not less than 10 pipe diameters downstream from the base of the upper stack.
- » **C 601.9 Sizing Building Drains and Sewers.** In a single-stack vent system, the building drain and branches thereof shall be sized in accordance with Table 703.2, and the building sewer shall be sized in accordance with Table 717.1.

TABLE C 601.2
SINGLE STACK SIZE*



| MAXIMUM CONNECTED DRAINAGE FIXTURE UNITS | | | |
|--|---------------------------------------|--|--|
| STACK SIZE (inches) | STACKS LESS THAN 75 FEET IN HEIGHT | STACK 75 FEET TO LESS THAN 160 FEET IN HEIGHT | STACK 160 FEET OR GREATER IN HEIGHT |
| 3 | 24 | NP | NP |
| 4 | 225 | 24 | NP |
| 5 | 480 | 225 | 24 |
| 6 | 1015 | 480 | 225 |
| 8 | 2320 | 1015 | 480 |
| 10 | 4500 | 2320 | 1015 |
| 12 | 8100 | 4500 | 2320 |
| 15 | 13 600 | 8100 | 4500 |

For SI units: 1 inch = 25 mm, 1 foot = 304.8 mm

* NP = Not permitted

APPENDIX D

SIZING STORM WATER DRAINAGE SYSTEMS

D 101.0 General.

D 101.1 Applicability. This appendix provides general guidelines for the sizing of storm water drainage systems based on maximum rates of rainfall for various cities. The rainfall rates in Table D 101.1 shall be permitted to be used for design unless higher values are established locally.

D 102.0 Sizing by Flow Rate.

D 102.1 General. Storm drainage systems shall be permitted to be sized by storm water flow rates, using the gallons per minute per square foot [(L/s)/m²] of rainfall listed in Table D 101.1 for the local area. Multiplying the listed gallons per minute per square foot [(L/s)/m²] by the roof area being drained (in square feet) (m²) by each inlet produces the gallons per minute (gpm) (L/s) of required flow for sizing each drain inlet. The flow rates shall be permitted to be added to determine the flows in each of the drainage systems. Required pipe sizes for various flow rates are listed in Table 1101.8 and Table 1101.12.

D 103.0 Sizing by Roof Area.

D 103.1 General. Storm drainage systems shall be permitted to be sized using the roof area served by each of

the drainage system. Maximum allowable roof areas with various rainfall rates are listed in Table 1101.8 and Table 1101.12, along with the required pipe sizes. Using this method, it shall be permitted to interpolate between two listed rainfall rate columns (inches per hour) (mm/h). To determine the allowable roof area for a listed pipe size at a listed slope, divide the allowable square feet (m²) of roof for a 1 inch per hour (in/h) (25.4 mm/h) rainfall rate by the listed rainfall rate for the local area. For example, the allowable roof area for a 6 inch (150 mm) drain at 1/8 inch per foot (10.4 mm/m) slope with a rainfall rate of 3.2 in/h (81 mm/h) is $21\,400/3.2 = 6688$ square feet (621.3 m²).

D 104.0 Capacity of Rectangular Scuppers.

D 104.1 General. Table D 104.1 lists the discharge capacity of rectangular roof scuppers of various widths with various heads of water. The maximum allowable level of water on the roof shall be obtained from the registered design professional, based on the design of the roof.

TABLE D 101.1
MAXIMUM RATES OF RAINFALL FOR VARIOUS CITIES*

| STATES AND CITIES | STORM DRAINAGE 60-MINUTE DURATION, 100-YEAR RETURN | |
|-------------------|--|------------------------------------|
| | inches per hour | gallons per minute per square foot |
| ALABAMA | — | — |
| Birmingham | 3.7 | 0.038 |
| Huntsville | 3.3 | 0.034 |
| Mobile | 4.5 | 0.047 |
| Montgomery | 3.8 | 0.039 |
| ALASKA | — | — |
| Aleutian Islands | 1.0 | 0.010 |
| Anchorage | 0.6 | 0.006 |
| Bethel | 0.8 | 0.008 |
| Fairbanks | 1.0 | 0.010 |
| Juneau | 0.6 | 0.006 |
| ARIZONA | — | — |
| Flagstaff | 2.3 | 0.024 |
| Phoenix | 2.2 | 0.023 |
| Tucson | 3.0 | 0.031 |
| ARKANSAS | — | — |
| Eudora | 3.8 | 0.039 |
| Ft. Smith | 3.9 | 0.041 |
| Jonesboro | 3.5 | 0.036 |
| Little Rock | 3.7 | 0.038 |

TABLE D 101.1
MAXIMUM RATES OF RAINFALL FOR VARIOUS CITIES* (continued)

| STATES AND CITIES | STORM DRAINAGE 60-MINUTE DURATION, 100-YEAR RETURN | |
|--|--|------------------------------------|
| | inches per hour | gallons per minute per square foot |
| CALIFORNIA | — | — |
| Eureka | 1.5 | 0.016 |
| Lake Tahoe | 1.3 | 0.014 |
| Los Angeles | 2.0 | 0.021 |
| Lucerne Valley | 2.5 | 0.026 |
| Needles | 1.5 | 0.016 |
| Palmdale | 3.0 | 0.031 |
| Redding | 1.5 | 0.016 |
| San Diego | 1.5 | 0.016 |
| San Francisco | 1.5 | 0.016 |
| San Luis Obispo | 1.5 | 0.016 |
| COLORADO | — | — |
| Craig | 1.5 | 0.016 |
| Denver | 2.2 | 0.023 |
| Durango | 1.8 | 0.019 |
| Stratton | 3.0 | 0.031 |
| CONNECTICUT | — | — |
| Hartford | 2.8 | 0.029 |
| New Haven | 3.0 | 0.031 |
| DELAWARE | — | — |
| Dover | 3.5 | 0.036 |
| Rehobeth Beach | 3.6 | 0.037 |
| DISTRICT OF COLUMBIA | — | — |
| Washington | 4.0 | 0.042 |
| FLORIDA | — | — |
| Daytona Beach | 4.0 | 0.042 |
| Ft. Myers | 4.0 | 0.042 |
| Jacksonville | 4.3 | 0.045 |
| Melbourne | 4.0 | 0.042 |
| Miami | 4.5 | 0.047 |
| Palm Beach | 5.0 | 0.052 |
| Tampa | 4.2 | 0.044 |
| Tallahassee | 4.1 | 0.043 |
| GEORGIA | — | — |
| Atlanta | 3.5 | 0.036 |
| Brunswick | 4.0 | 0.042 |
| Macon | 3.7 | 0.038 |
| Savannah | 4.0 | 0.042 |
| Thomasville | 4.0 | 0.042 |
| HAWAII | — | — |
| Rainfall rates in the Hawaiian Islands vary from 1½ inches per hour to 8 inches per hour, depending on location and elevation. Consult local data. | | |
| IDAHO | — | — |
| Boise | 1.0 | 0.010 |
| Idaho Falls | 1.2 | 0.012 |
| Lewiston | 1.0 | 0.010 |
| Twin Falls | 1.1 | 0.011 |

TABLE D 101.1
MAXIMUM RATES OF RAINFALL FOR VARIOUS CITIES* (continued)

| STATES AND CITIES | STORM DRAINAGE 60-MINUTE DURATION, 100-YEAR RETURN | |
|----------------------|--|------------------------------------|
| | inches per hour | gallons per minute per square foot |
| ILLINOIS | — | — |
| Chicago | 2.7 | 0.028 |
| Harrisburg | 3.1 | 0.032 |
| Peoria | 2.9 | 0.030 |
| Springfield | 3.0 | 0.031 |
| INDIANA | — | — |
| Evansville | 3.0 | 0.031 |
| Indianapolis | 2.8 | 0.029 |
| Richmond | 2.7 | 0.028 |
| South Bend | 2.7 | 0.028 |
| IOWA | — | — |
| Council Bluffs | 3.7 | 0.038 |
| Davenport | 3.0 | 0.031 |
| Des Moines | 3.4 | 0.035 |
| Sioux City | 3.6 | 0.037 |
| KANSAS | — | — |
| Goodland | 3.5 | 0.036 |
| Salina | 3.8 | 0.039 |
| Topeka | 3.8 | 0.039 |
| Wichita | 3.9 | 0.041 |
| KENTUCKY | — | — |
| Bowling Green | 2.9 | 0.030 |
| Lexington | 2.9 | 0.030 |
| Louisville | 2.8 | 0.029 |
| Paducah | 3.0 | 0.031 |
| LOUISIANA | — | — |
| Monroe | 3.8 | 0.039 |
| New Orleans | 4.5 | 0.047 |
| Shreveport | 4.0 | 0.042 |
| MAINE | — | — |
| Bangor | 2.2 | 0.023 |
| Kittery | 2.4 | 0.025 |
| Millinocket | 2.0 | 0.021 |
| MARYLAND | — | — |
| Baltimore | 3.6 | 0.037 |
| Frostburg | 2.9 | 0.030 |
| Ocean City | 3.7 | 0.038 |
| MASSACHUSETTS | — | — |
| Adams | 2.6 | 0.027 |
| Boston | 2.7 | 0.028 |
| Springfield | 2.7 | 0.028 |
| MICHIGAN | — | — |
| Detroit | 2.5 | 0.026 |
| Grand Rapids | 2.6 | 0.027 |
| Kalamazoo | 2.7 | 0.028 |

TABLE D 101.1
MAXIMUM RATES OF RAINFALL FOR VARIOUS CITIES* (continued)

| STATES AND CITIES | STORM DRAINAGE 60-MINUTE DURATION, 100-YEAR RETURN | |
|----------------------|--|------------------------------------|
| | inches per hour | gallons per minute per square foot |
| Sheboygan | 2.1 | 0.022 |
| Traverse City | 2.2 | 0.023 |
| MINNESOTA | — | — |
| Duluth | 2.6 | 0.027 |
| Grand Forks | 2.5 | 0.026 |
| Minneapolis | 3.0 | 0.031 |
| Worthington | 3.4 | 0.035 |
| MISSISSIPPI | — | — |
| Biloxi | 4.5 | 0.047 |
| Columbus | 3.5 | 0.036 |
| Jackson | 3.8 | 0.039 |
| MISSOURI | — | — |
| Independence | 3.7 | 0.038 |
| Jefferson City | 3.4 | 0.035 |
| St. Louis | 3.2 | 0.033 |
| Springfield | 3.7 | 0.038 |
| MONTANA | — | — |
| Billings | 1.8 | 0.019 |
| Glendive | 2.5 | 0.026 |
| Great Falls | 1.8 | 0.019 |
| Missoula | 1.3 | 0.014 |
| NEBRASKA | — | — |
| Omaha | 3.6 | 0.037 |
| North Platte | 3.5 | 0.036 |
| Scotts Bluff | 2.8 | 0.029 |
| NEVADA | — | — |
| Las Vegas | 1.5 | 0.016 |
| Reno | 1.2 | 0.012 |
| Winnemucca | 1.0 | 0.010 |
| NEW HAMPSHIRE | — | — |
| Berlin | 2.2 | 0.023 |
| Manchester | 2.5 | 0.026 |
| NEW JERSEY | — | — |
| Atlantic City | 3.4 | 0.035 |
| Paterson | 3.0 | 0.031 |
| Trenton | 3.2 | 0.033 |
| NEW MEXICO | — | — |
| Albuquerque | 2.0 | 0.021 |
| Carlsbad | 2.6 | 0.027 |
| Gallup | 2.1 | 0.022 |
| NEW YORK | — | — |
| Binghamton | 2.4 | 0.025 |
| Buffalo | 2.3 | 0.024 |

TABLE D 101.1
MAXIMUM RATES OF RAINFALL FOR VARIOUS CITIES* (continued)

| STATES AND CITIES | STORM DRAINAGE 60-MINUTE DURATION, 100-YEAR RETURN | |
|-----------------------|--|------------------------------------|
| | inches per hour | gallons per minute per square foot |
| New York City | 3.1 | 0.032 |
| Schenectady | 2.5 | 0.026 |
| Syracuse | 2.4 | 0.025 |
| NORTH CAROLINA | — | — |
| Asheville | 3.2 | 0.033 |
| Charlotte | 3.4 | 0.035 |
| Raleigh | 4.0 | 0.042 |
| Wilmington | 4.4 | 0.046 |
| NORTH DAKOTA | — | — |
| Bismarck | 2.7 | 0.028 |
| Fargo | 2.9 | 0.030 |
| Minot | 2.6 | 0.027 |
| OHIO | — | — |
| Cincinnati | 2.8 | 0.029 |
| Cleveland | 2.4 | 0.025 |
| Columbus | 2.7 | 0.028 |
| Toledo | 2.6 | 0.027 |
| Youngstown | 2.4 | 0.025 |
| OKLAHOMA | — | — |
| Boise City | 3.4 | 0.035 |
| Muskogee | 4.0 | 0.042 |
| Oklahoma City | 4.1 | 0.043 |
| OREGON | — | — |
| Medford | 1.3 | 0.014 |
| Ontario | 1.0 | 0.010 |
| Portland | 1.3 | 0.014 |
| PENNSYLVANIA | — | — |
| Erie | 2.4 | 0.025 |
| Harrisburg | 2.9 | 0.030 |
| Philadelphia | 3.2 | 0.033 |
| Pittsburgh | 2.5 | 0.026 |
| Scranton | 2.8 | 0.029 |
| RHODE ISLAND | — | — |
| Newport | 3.0 | 0.031 |
| Providence | 2.9 | 0.030 |
| SOUTH CAROLINA | — | — |
| Charleston | 4.1 | 0.043 |
| Columbia | 3.5 | 0.036 |
| Greenville | 3.3 | 0.034 |
| SOUTH DAKOTA | — | — |
| Lemmon | 2.7 | 0.028 |
| Rapid City | 2.7 | 0.028 |
| Sioux Falls | 3.4 | 0.035 |

APPENDIX D

TABLE D 101.1
MAXIMUM RATES OF RAINFALL FOR VARIOUS CITIES* (continued)

| STATES AND CITIES | STORM DRAINAGE 60-MINUTE DURATION, 100-YEAR RETURN | |
|----------------------|--|------------------------------------|
| | inches per hour | gallons per minute per square foot |
| TENNESSEE | — | — |
| Knoxville | 3.1 | 0.032 |
| Memphis | 3.5 | 0.036 |
| Nashville | 3.0 | 0.031 |
| TEXAS | — | — |
| Corpus Christi | 4.6 | 0.048 |
| Dallas | 4.2 | 0.044 |
| El Paso | 2.0 | 0.021 |
| Houston | 4.6 | 0.048 |
| Lubbock | 3.3 | 0.034 |
| San Antonio | 4.4 | 0.046 |
| UTAH | — | — |
| Bluff | 2.0 | 0.021 |
| Cedar City | 1.5 | 0.016 |
| Salt Lake City | 1.3 | 0.014 |
| VERMONT | — | — |
| Bennington | 2.5 | 0.026 |
| Burlington | 2.3 | 0.024 |
| Rutland | 2.4 | 0.025 |
| VIRGINIA | — | — |
| Charlottesville | 3.4 | 0.035 |
| Norfolk | 4.0 | 0.042 |
| Richmond | 4.0 | 0.042 |
| Roanoke | 3.3 | 0.034 |
| WASHINGTON | — | — |
| Seattle | 1.0 | 0.010 |
| Spokane | 1.0 | 0.010 |
| Walla Walla | 1.0 | 0.010 |
| WEST VIRGINIA | — | — |
| Charleston | 2.9 | 0.030 |
| Martinsburg | 3.0 | 0.031 |
| Morgantown | 2.7 | 0.028 |
| WISCONSIN | — | — |
| Green Bay | 2.5 | 0.026 |
| Lacrosse | 2.9 | 0.030 |
| Milwaukee | 2.7 | 0.028 |
| Wausau | 2.5 | 0.026 |
| WYOMING | — | — |
| Casper | 1.9 | 0.020 |
| Cheyenne | 2.5 | 0.026 |
| Evanston | 1.3 | 0.014 |
| Rock Springs | 1.4 | 0.015 |

For SI units: 1 inch per hour = 25.4 mm/h, 1 gallon per minute per square foot = 0.618 [(L/s)m²]

*The rainfall rates in this table are based on U.S. Weather Bureau Technical Paper No. 40, Chart 14: 100-Year 60-Minute Rainfall (inches).

TABLE D 104.1
DISCHARGE FROM RECTANGULAR SCUPPERS (gallons per minute)^{1, 2, 3, 4}

| WATER HEAD (inches) | WIDTH OF SCUPPER (inches) | | | | | |
|------------------------|---------------------------|-----|-----|-----|-----|-----|
| | 6 | 12 | 18 | 24 | 30 | 36 |
| ½ | 6 | 13 | 19 | 25 | 32 | 38 |
| 1 | 17 | 35 | 53 | 71 | 89 | 107 |
| 1½ | 31 | 64 | 97 | 130 | 163 | 196 |
| 2 | — | 98 | 149 | 200 | 251 | 302 |
| 2½ | — | 136 | 207 | 278 | 349 | 420 |
| 3 | — | 177 | 271 | 364 | 458 | 551 |
| 3½ | — | — | 339 | 457 | 575 | 693 |
| 4 | — | — | 412 | 556 | 700 | 844 |

For SI units: 1 inch = 25.4 mm, 1 gallon per minute = 0.06 L/s

Notes:

- ¹ Table D 104.1 is based on discharge over a rectangular weir with end contractions.
- ² Head is the depth of water above bottom of the scupper opening.
- ³ The height of the scupper opening shall be not less than two times the design head.
- ⁴ Coordinate the allowable head of water with the structural design of the roof.

APPENDIX E

MANUFACTURED/MOBILE HOME PARKS AND RECREATIONAL VEHICLE PARKS

→ E 101.0 Manufactured/Mobile Home (M/H) Park.

E 101.1 Applicability. The M/H park plumbing and drainage systems shall be designed and installed in accordance with the requirements of this appendix and the requirements of this code.

» E 101.2 Definitions. For purposes of this chapter, the following definitions shall apply:

Manufactured/Mobile Home. A structure transportable in one or more sections, which in the traveling mode is 8 feet (2438 mm) or more in width and 40 feet (12 192 mm) or more in length or, where erected on site, is 320 square feet (29.73 m²) or more, and which is built on a permanent chassis, and designed to be used as a dwelling with or without a permanent foundation where connected to the required utilities. It includes the plumbing, heating, air conditioning, and electrical systems contained therein. For further clarification of definition, see Federal Regulation 24 CFR.

Manufactured/Mobile Home Accessory Building or Structure. A building or structure that is an addition to or supplements the facilities provided to a M/H. It is not a self-contained, separate, habitable building or structure. Examples are awnings, cabanas, ramadas, storage structures, carports, fences, windbreaks, or porches.

Manufactured/Mobile Home Lot. A portion of a M/H park designed for the accommodation of one M/H and its accessory buildings or structures for the exclusive use of the occupants.

Manufactured/Mobile Home Park. A parcel (or contiguous parcels) of land that has been so designated and improved that it contains two or more M/H lots available to the general public for the placement thereon of M/H for occupancy.

Recreational Vehicle (RV). A vehicular-type unit primarily designed as temporary living quarters for recreational, camping, travel, or seasonal use, that either has its own motive power, or is mounted on or towed by another vehicle. The basic entities are camping trailer, fifth-wheel trailer, motor home, park trailer, travel trailer, and truck camper.

Recreational Vehicle Park. A plot of land upon which two or more recreational vehicle sites are located, established, or maintained for occupancy by recreational vehicles of the general public as temporary living quarters for recreation or vacation purpose.

Recreational Vehicle Site. Within a recreational vehicle park, a plot of ground intended for the accommodation of a recreational vehicle, a tent, or other individual camping unit on a temporary basis.

» E 102.0 Construction Documents.

» E 102.1 General Requirements. Before plumbing or sewage disposal facilities are installed or altered in a M/H

park, duplicate construction documents shall be filed and proper permits obtained from the department or departments having jurisdiction. Plans shall show in detail:

- (1) Plot plan of the park drawn to scale, indicating elevations, property lines, driveways, existing or proposed buildings, and the sizes of M/H lots.
- (2) Complete specification and piping layout of proposed plumbing systems or alteration.
- (3) Complete specification and layout of proposed sewage disposal system or alteration.
- (4) The nature and extent of the work proposed, showing clearly that such work will conform to the provisions of this code.

E 201.0 Manufactured/Mobile Home Park Drainage System Construction. <<

E 201.1 Drainage Systems. A drainage system shall be provided in M/H parks for conveying and disposing of sewage. Where feasible, connection shall be made to a public system. New improvements shall be designed, constructed, and maintained in accordance with applicable laws and regulations. Where the drainage lines of the M/H park are not connected to a public sewer, proposed sewage disposal facilities shall be approved by the Authority Having Jurisdiction prior to construction.

E 202.0 Materials. <<

E 202.1 General. Pipe and fittings installed underground in M/H park drainage systems shall be of material approved for the purpose. M/H lot drainage inlets and extensions to grade shall be of material approved for underground use within a building.

E 203.0 Drainage (Sewage) Lines. <<

E 203.1 General. Drainage (sewage) collection lines shall be located in trenches at an approved depth to be free of breakage from traffic or other movements and shall be separated from the park water supply system as specified in this code. Drainage (sewage) lines shall have a minimum size and slope as specified in Table E 203.1(1) and Table E 203.1(2).

E 204.0 M/H Lot Drainage Inlet and Lateral. <<

E 204.1 Size. Each lot shall be provided with a drainage inlet not less than 3 inches (80 mm) in diameter.

E 204.2 Lateral Line. The lateral line from the inlet to the sewage drain line shall slope not less than 1/4 inch per foot (20.8 mm/m). Joints shall be watertight.

TABLE E 203.1(1)
DRAINAGE PIPE DIAMETER AND NUMBER OF
FIXTURE UNITS ON DRAINAGE SYSTEM

| SIZE OF DRAINAGE (inches) | MAXIMUM NUMBER OF FIXTURE UNITS |
|------------------------------|------------------------------------|
| 2* | 8 |
| 3 | 35 |
| 4 | 256 |
| 5 | 428 |
| 6 | 720 |
| 8 | 2640 |
| 10 | 4680 |
| 12 | 8200 |

For SI units: 1 inch = 25 mm

* Except six unit fixtures

TABLE E 203.1(2)
MINIMUM GRADE AND SLOPE OF DRAINAGE PIPE

| PIPE SIZE | SLOPE (per 100 feet) | PIPE SIZE | SLOPE (per 100 feet) |
|-----------|-------------------------|-----------|-------------------------|
| inches | inches | inches | inches |
| 2 | 25 | 6 | 8 |
| 3 | 25 | 8 | 4 |
| 4 | 15 | 10 | 3½ |
| 5 | 11 | 12 | 3 |

For SI units: 1 inch = 25 mm, 1 inch per foot = 83.3 mm/m

» **E 204.3 Materials.** Materials used for drainage connections between a M/H and the lot drainage inlet shall be semi-rigid, corrosion-resistant, non-absorbent, and durable. The inner surface shall be smooth.

» **E 204.4 Inlet.** Provision shall be made for plugging or capping the sewage drain inlet where a M/H does not occupy the lot. Surface drainage shall be diverted away from the inlet. The rim of the inlet shall extend at a maximum of 4 inches (102 mm) aboveground elevation.

» **E 205.0 Location of Lot Drain Inlet.**

» **E 205.1 General.** Each lot drainage inlet shall be located in the rear third section and within 4 feet (1219 mm) of the proposed location of the M/H.

» **E 206.0 Pipe Size.**

» **E 206.1 Inlet, System, and Lateral Sizing.** Each M/H lot drainage inlet shall be assigned a waste loading value of 12 drainage fixture units, and each park drainage system shall be sized in accordance with Table E 203.1(1) or as provided herein. Drainage laterals shall be not less than 3 inches (80 mm) in diameter.

» **E 206.2 Engineered Design.** A park drainage system that exceeds the fixture unit loading of Table E 203.1(1) or in which the grade and slope of drainage pipe does not meet the minimum specified in Table E 203.1(2) shall be designed by a registered design professional.

E 207.0 M/H Drain Connector.

E 207.1 General. A M/H shall be connected to the lot drainage inlet by means of a drain connector consisting of approved pipe not less than Schedule 40, approved fittings and connectors, and not less in size than the M/H drainage outlet. An approved cleanout shall be provided between the M/H and the lot drainage inlet. The fitting connected to the lot drainage inlet shall be a directional fitting to discharge the flow into the drainage inlet.

E 207.2 Grade and Gastightness. A drain connector shall be installed or maintained with a grade not less than ¼ inch per foot (20.8 mm/m). A drain connector shall be gastight and no longer than necessary to make the connection between the M/H outlet and the drain inlet on the lot. A flexible connector shall be permitted to be used at the lot drainage inlet area. Each lot drainage inlet shall be capped gastight where not in use.

E 301.0 M/H Park Water Supply.

E 301.1 Potable Water Supply. An accessible and approved supply of potable water shall be provided in each M/H park. Where a public supply of water of approved quantity, quality, and pressure is available at or within the boundary of the park site, connection shall be made thereto and its supply used exclusively. Where an approved public water supply is not available, a private water supply system shall be developed and used as approved by the Authority Having Jurisdiction.

E 302.0 Lot Service Outlet Size.

E 302.1 General. Each M/H lot shall be provided with a water service outlet delivering potable water. The water service outlet riser shall be not less than ¾ of an inch (20 mm) nominal pipe size and capable of delivering 12 water supply fixture units.

E 303.0 Location of Water Service.

E 303.1 General. Each lot water service outlet shall be located in the rear third section and within 4 feet (1219 mm) of the proposed location of the M/H.

E 304.0 Pressure.

E 304.1 General. Each M/H park water distribution system shall be so designed and maintained as to provide a pressure of not less than 20 pounds-force per square inch (psi) (138 kPa) at each M/H lot at maximum operating conditions.

E 305.0 Water Distribution Piping.

E 305.1 General. Park water distribution systems shall be designed to deliver a minimum of 12 water supply fixture units to each lot and installed with materials in accordance with Chapter 6, Appendix A, or both of this code.

» E 306.0 Shutoff Valve.

- » E 306.1 General. A separate water shutoff valve shall be installed in each water service outlet at each M/H lot. Where a listed backflow protective device is installed, the service shutoff shall be located on the supply side of such device.

» E 307.0 Backflow Preventer.

- » E 307.1 General. Where a condition exists in the plumbing of a M/H that creates a cross-connection, a listed backflow preventer shall be installed in the water service line to the M/H at or near the water service outlet. Where a hose bibb or outlet is installed on the supply outlet riser in addition to the service connector, a listed backflow preventer shall be installed on each additional outlet.

» E 308.0 Pressure-Relief Valve.

- » E 308.1 General. Where it is required to install a backflow preventer at the M/H lot service outlet, a listed pressure-relief valve shall be installed in the water service line on the discharge side of the backflow preventer. Pressure-relief valves shall be set to release at a pressure at a maximum of 150 psi (1034 kPa). Pressure-relief valves shall discharge toward the ground. Backflow preventers and pressure-relief valves shall be not less than 12 inches (305 mm) above the ground.

» E 309.0 Mechanical Protection.

- » E 309.1 General. Park water service outlets, backflow preventers, and pressure-relief valves shall be protected from damage by vehicles or other causes. Such protection shall be permitted to consist of posts, fencing, or other permanent barriers.

» E 310.0 M/H Water Connector.

- » E 310.1 General. An M/H shall be connected to the park water service outlet by a flexible connector, such as copper or copper alloy or other approved material not less than ¾ of an inch nominal (20 mm) interior diameter.

» E 311.0 Water-Conditioning Equipment.

- » E 311.1 Permit Required. A permit shall be obtained from the Authority Having Jurisdiction prior to installing water-conditioning equipment on an M/H lot. Approval of the park operator is required on applications for a permit to install such equipment. Where the water-conditioning equipment is of the regenerating type, and the park drainage system discharges into a public sewer, approval of the sanitary district or agency having jurisdiction over the public sewer is required.
- » E 311.2 Approval. Regenerating water-conditioning equipment shall be listed and labeled by an approved listing agency.

E 311.3 Installation. Regenerating units shall discharge the effluent of regeneration into a trap not less than 1½ inches (40 mm) in diameter connected to the M/H park drainage system. An approved air gap shall be installed on the discharge line a minimum of 12 inches (305 mm) above the ground.

E 312.0 Testing.

E 312.1 General. Installations shall be tested and inspected in accordance with Chapter 3 of this code.

E 401.0 Fuel Supply.

E 401.1 Fuel Gas Piping Systems. Fuel gas piping systems serving manufactured homes, accessory buildings, or structures and communities shall be designed and constructed in accordance with the applicable provisions of NFPA 54 and NFPA 58. NFPA 31 shall apply to oil fuel-burning systems and shall comply with the criteria of the Authority Having Jurisdiction. [NFPA 501A:4.1.1]

E 401.2 Gas Supply Connections. Gas supply connections at sites, where provided from an underground gas supply piping system, shall be located and arranged to permit attachment to a manufactured home (M/H) occupying the site. For the installation of liquefied petroleum gas (LP-Gas) storage systems, the applicable provisions of NFPA 58 shall be followed. [NFPA 501A:4.1.2]

E 401.3 Location of Gas Supply Connection. The gas supply to the M/H shall be located within 4 feet (1219 mm) of the M/H stand.

Exception: Gas supply connections for manufactured homes located on all-weather wood, concrete, concrete block foundation systems or on foundations constructed in accordance with the local building code or, in the absence of a local code, with a recognized model building code. [NFPA 501A:4.1.3]

E 401.4 Recreational Vehicle Park Fuel Gas Equipment and Installations. Fuel gas equipment and installations shall comply with this appendix, except as otherwise permitted or required by this code.

E 402.0 Single and Multiple Manufactured Home Site Fuel Supply Systems.

E 402.1 Underground Installations. Underground gas piping system installations shall comply with the building code, Section E 402.1.1, and Section E 402.1.2. [NFPA 501A:4.2.1]

E 402.1.1 Open-Ended Gastight Conduit. Underground gas piping shall not be installed beneath that portion of a M/H site reserved for the location of a manufactured home or M/H accessory building or structure unless installed in the open-ended gastight conduit of Section E 402.1.2. [NFPA 501A:4.2.1.1]

E 402.1.2 Requirements. Open-ended gastight conduit shall comply with the following:

- (1) The conduit shall be not less than Schedule 40 pipe that is approved for underground installation beneath buildings.

- (2) The interior diameter of the conduit shall be not less than ½ of an inch (15 mm) larger than the outside diameter of the gas piping.
- (3) The conduit shall extend to a point not less than 4 inches (102 mm) beyond the outside wall of the M/H, accessory building, or structure, and the outer ends shall not be sealed.
- (4) Where the conduit terminates within a M/H, accessory building, or structure, it shall be accessible, and the space between the conduit and the gas piping shall be sealed to prevent leakage of gas into the building. [NFPA 501A:4.2.1.2 – 4.2.1.2.4]

» E 403.0 Manufactured Home Site Gas Shutoff Valve.

- » E 403.1 General. Each M/H site shall have a listed gas shutoff valve installed upstream of the M/H site gas outlet. The gas shutoff valve shall be located on the outlet riser at a height of not less than 6 inches (152 mm) above grade. A gas shutoff valve shall not be located under a M/H. The outlet shall be equipped with a cap or plug to prevent discharge of gas where the M/H site outlet is not connected to a M/H. [NFPA 501A:4.2.2.1 – 4.2.2.4]

Exception: Gas shutoff valves for manufactured homes located on foundations constructed in accordance with the local building code or, in the absence of a local code, with a recognized model building code. [NFPA 501A:4.2.2]

» E 404.0 Gas Meters.

- » E 404.1 Support of Meters. Where installed, gas meters shall be supported by a post or bracket placed on a firm footing or other means providing equivalent support and shall not depend on the gas outlet riser for support. [NFPA 501A:4.2.3.1]
- » E 404.2 Location of Meters. Each gas meter shall be installed in an accessible location and shall be provided with unions or other fittings so that the meter is removed easily and placed in an upright position. Meters shall not be installed in unventilated or inaccessible locations or closer than 3 feet (914 mm) to sources of ignition. [NFPA 501A:4.2.3.2]
- » E 404.3 Meter Shutoff Valve or Cock. Gas meter installations shall be provided with shutoff valves or cocks located adjacent to and on the inlet side of the meters. In the case of a single meter installation utilizing an LP-Gas container, the container service valve shall be permitted to be used in lieu of the shutoff valve or cock. Gas meter installations shall be provided with test tees located adjacent to and on the outlet side of the meters. [NFPA 501A:4.2.4]

» E 405.0 Cathodic Protection Requirements.

- » E 405.1 General. Cathodic protection shall be installed for corrosion control of buried or submerged metallic gas piping in accordance with the following requirements:

- (1) Where amphoteric metals are included in a buried or submerged pipeline containing a metal of different anodic potential the following protection shall be provided:
 - (a) The buried or submerged pipeline shall be cathodically protected at a negative (cathodic) voltage of 0.85 volt measured between the structure surface and a saturated copper-copper sulfate half cell contacting the electrolyte.
 - (b) The amphoteric metals shall be electrically isolated from the remainder of the pipeline with insulating flanges, or equivalent, and cathodically protected.
- (2) The amount of cathodic protection shall be such that the protective coating and the pipe are not damaged.

E 406.0 Manufactured Home Community LP-Gas Supply Systems. <<

- E 406.1 General. Where 10 or more customers are served by one LP-Gas supply system, the installation of the gas supply system shall be in accordance with 49 CFR 192. Other types of liquefied petroleum gas supply systems and the storage and handling of LP-Gas shall be in accordance with NFPA 58 (see Section E 411.0). [NFPA 501A:4.3.2]

E 407.0 Required Gas Supply. <<

- E 407.1 General. The minimum hourly volume of gas required at each M/H site outlet or a section of the M/H community gas piping system shall be calculated as shown in Table E 407.1. [NFPA 501A:4.3.4.1]

E 408.0 Gas Pipe Sizing and Pressure. <<

- E 408.1 Size. The size of each section of a gas piping system shall be determined in accordance with NFPA 54, or by other standard engineering methods acceptable to the Authority Having Jurisdiction. [NFPA 501A:4.3.5.1]
- E 408.2 Pressure. Where connected appliances are operated at their rated capacity, the gas supply pressure shall be not less than 7 inches of water column (1.7 kPa). The gas supply pressure shall not exceed 14 inches of water column (3.5 kPa). [NFPA 501A:4.3.5.2]

E 409.0 Gas Piping Materials. <<

- E 409.1 Metal. Metal gas pipe shall be standard-weight wrought iron or steel (galvanized or black), yellow brass containing not more than 75 percent copper, or internally tinned or treated copper of iron pipe size. Galvanizing shall not be considered protection against corrosion.

Seamless copper or steel tubing shall be permitted to be used with gases not corrosive to such material. Steel tubing shall comply with ASTM A254. Copper tubing shall comply with ASTM B88 or ASTM B280. Copper tubing (unless tin-lined) shall not be used where the gas contains more than an average of 0.3 grains of hydrogen sulfide per 100 standard cubic feet (scf) of gas (0.7 mg/100 L). [NFPA 501A:4.3.6.1]

» **TABLE E 407.1**
DEMAND FACTORS FOR USE IN CALCULATING GAS PIPING
SYSTEMS IN M/H COMMUNITIES*
[NFPA 501A: TABLE 4.3.4.1]

| NUMBER OF M/H SITES | BRITISH THERMAL UNITS PER HOUR PER M/H SITE |
|------------------------|--|
| 1 | 125 000 |
| 2 | 117 000 |
| 3 | 104 000 |
| 4 | 96 000 |
| 5 | 92 000 |
| 6 | 87 000 |
| 7 | 83 000 |
| 8 | 81 000 |
| 9 | 79 000 |
| 10 | 77 000 |
| 11–20 | 66 000 |
| 21–30 | 62 000 |
| 31–40 | 58 000 |
| 41–60 | 55 000 |
| Over 60 | 50 000 |

For SI units: 1000 British thermal units per hour = 0.293 kW

* In extreme climate areas, additional capacities shall be considered.

» **E 409.2 Protection Coatings for Metal Gas Piping.**

Buried or submerged metallic gas piping shall be protected from corrosion by approved coatings or wrapping materials. Gas pipe protective coatings shall be approved types, machine applied, and shall comply with recognized standards. Field wrapping shall provide equivalent protection and is restricted to those short sections and fittings that are stripped for threading or welding. Risers shall be coated or wrapped to a point of not less than 6 inches (152 mm) above ground. [NFPA 501A:4.3.6.2]

» **E 409.3 Plastic.** Plastic piping shall be used underground and shall be in accordance with the requirements of ASTM D2513 or ASTM D2517, as well as the design pressure and design limitations of 49 CFR 192.123, and shall otherwise comply with the installation requirements thereof. [NFPA 501A:4.3.6.3]

» **E 410.0 Gas Piping Installations.**

» **E 410.1 Minimum Burial Below Ground Level and Clearances.** Gas piping installed below ground level shall have an earth cover of not less than 18 inches (457 mm) and shall be installed with not less than 12 inches (305 mm) of clearance from other underground utility systems. [NFPA 501A:4.3.7.1]

» **E 410.2 Metallic Gas Piping.** Metallic gas piping systems shall be installed in accordance with approved construction documents, including provisions for cathodic protection. Each cathodic protection system shall be designed and installed in accordance with the provisions of 49 CFR 192. [NFPA 501A:4.3.7.2.1, 4.3.7.2.2]

« **E 410.2.1 Cathodic Protection.** Where the cathodic protection system is designed to protect the gas piping system, the gas piping system shall be electrically isolated from other underground metallic systems or installations. Where the gas piping system is cathodically protected against corrosion, a dielectric fitting shall be used in the M/H gas connection to insulate the M/H from the underground gas piping system. [NFPA 501A:4.3.7.2.3, 4.3.7.2.4]

« **E 410.2.2 Underground Metallic Systems.** Where a cathodic protection system is designed to provide underground metallic systems and installations with protection against corrosion, such systems and installations shall be electrically bonded together and protected as a whole. [NFPA 501A:4.3.7.2.5]

« **E 410.3 Plastic Gas Piping.** Plastic gas piping shall be used underground and shall be installed with an electrically conductive wire for locating the pipe. The wire used to locate the plastic pipe shall be copper, not less than No. 18 AWG, with insulation approved for direct burial. Portions of a plastic gas piping system consisting of metallic pipe shall be cathodically protected against corrosion. [NFPA 501A:4.3.7.3]

« **E 410.4 Gas Piping System Shutoff Valve.** An accessible and identifiable shutoff valve controlling the flow of gas to the entire M/H community gas piping system shall be installed in a location approved by the Authority Having Jurisdiction and near the point of connection to the service piping or to the supply connection of an LP-Gas container. [NFPA 501A:4.3.7.4]

« **E 411.0 Liquefied Petroleum Gas Equipment.**

« **E 411.1 General.** LP-Gas equipment shall be installed in accordance with the applicable provisions of NFPA 58. [NFPA 501A:4.3.8]

« **E 412.0 Oil Supply.**

« **E 412.1 General.** The following three methods of supplying oil to an individual M/H site shall be permitted:

- (1) Supply from an outside underground tank (see Section E 413.6).
- (2) Supply from a centralized oil distribution system designed and installed in accordance with accepted engineering practices and in accordance with NFPA 31.
- (3) Supply from an outside aboveground tank (see Section E 413.6). [NFPA 501A:4.3.9]

« **E 412.2 Minimum Oil Supply Tank Size.** Oil supply tanks shall have a minimum capacity equal to 20 percent of the average annual oil consumption. [NFPA 501A:4.3.10]

« **E 412.3 Oil Supply Connections.** Oil supply connections at M/H sites, where provided from a centralized oil distribution system, shall be located and arranged to permit attachment to a M/H utilizing the stand. [NFPA 501A:4.3.11.1] The installation of such facilities shall comply with the following requirements:

- (1) The main distribution pipeline shall be permitted to be connected to a tank or tanks having an aggregate

capacity not to exceed 20 000 gallons (75 708 L) at a point below the liquid level.

- (2) Where this piping is so connected, a readily accessible internal or external shutoff valve shall be installed in the piping as close as practicable to the tank.
- (3) Where external and aboveground, the shutoff valve and its tank connections shall be made of steel.
- (4) Connections between the tank(s) and the main pipeline shall be made with double swing joints or flexible connectors, or shall otherwise be arranged to permit the tank(s) to settle without damaging the system.
- (5) Where located aboveground, the connections shall be located within the diked area.
- (6) A readily accessible and identified manual shutoff valve shall be installed in each branch supply pipeline that enters a building, mobile home, travel trailer, or other structure. This valve shall be permitted to be either inside or outside of the structure. Where outside, the valve shall be protected from weather and damage. Where inside, the valve shall be located directly adjacent to the point at which the supply line enters the structure.
- (7) A device shall be provided in the supply line at or ahead of the point where it enters the interior of the structure that will automatically shut off the oil supply, where the supply line between this device and the appliance is broken. This device shall be located on the appliance side of the manual shutoff valve. This device shall be solidly supported and protected from damage.
- (8) Means shall be provided to limit the oil pressure at the appliance inlet to not exceed 3 pounds-force per square inch gauge (psig) (21 kPa). Where a pressure-reducing valve is used, it shall be a type approved for the service.
- (9) A device shall be provided that automatically shuts off the oil supply to the appliance where the oil pressure at the appliance inlet exceeds 8 psig (55 kPa).

Exceptions:

- (a) Where the distribution system is supplied from a gravity tank and the maximum hydrostatic head of oil in the tank is such that the pressure at the appliance inlet shall not exceed 8 psig (55 kPa).
 - (b) Where a means is provided to automatically shut off the oil supply where the pressure-regulating device fails to regulate the pressure as required.
- (10) Appliances equipped with primary safety controls specifically listed for the appliance shall be connected to a centralized oil distribution system. [NFPA 31:9.2.10 – 9.2.15]

» **E 413.0 Fuel Supply Systems Installation.**

- » **E 413.1 Flexible Gas Connector.** Each gas supply connector shall be listed for outside M/H use, shall be not more than 6 feet (1829 mm) in length, and shall have a capacity rating to supply the connected load.

Exception: Gas supply connections for manufactured homes located on an all-weather wood, concrete, concrete block foundation system or on a foundation constructed in accordance with the local building code or, in the absence of a local code, with a recognized model building code. [NFPA 501A:4.4.1]

E 413.2 Use of Approved Pipe and Fittings of Extension. Where it is necessary to extend the M/H inlet to permit connection of the 6 foot (1829 mm) listed connector to the site gas outlet, the extension shall be of approved materials of the same size as the M/H inlet and shall be supported at not more than 4 foot (1219 mm) intervals to the M/H. [NFPA 501A:4.4.2]

E 413.3 Mechanical Protection. Gas outlet risers, regulators, meters, valves, or other exposed equipment shall be protected against accidental damage. [NFPA 501A:4.4.3]

E 413.4 Special Rules on Atmospherically Controlled Regulators. Atmospherically controlled regulators shall be installed in such a manner that moisture cannot enter the regulator vent and accumulate above the diaphragm. Where the regulator vent is obstructed due to snow and icing conditions; shields, hoods, or other approved devices shall be provided to guard against closing of the vent opening. [NFPA 501A:4.4.4]

E 413.5 Fuel Gas Piping Test. The M/H fuel gas piping system shall be tested with air before it is connected to the gas supply. The M/H gas piping system shall be subjected to a pressure test with appliance shutoff valves in their closed positions. [NFPA 501A:4.4.5]

E 413.5.1 Procedures. The fuel gas piping test shall consist of air pressure of not less than 10 inches water column or more than 14 inches water column (2.5 kPa to 3.5 kPa). The fuel gas piping system shall be isolated from the air pressure source and shall maintain this pressure for not less than 10 minutes without perceptible leakage. Upon satisfactory completion of the fuel gas piping test, the appliance valves shall be opened, and the gas appliance connectors shall be tested with soapy water or bubble solution while under the pressure remaining in the piping system. Solutions used for testing for leakage shall not contain corrosive chemicals. Pressure shall be measured with either a manometer, slope gauge, or gauge that is calibrated in either water inch (mm) or psi (kPa), with increments of either $\frac{1}{10}$ of an inch (2.5 mm) or $\frac{1}{10}$ psi (0.7 kPa gauge), as applicable. Upon satisfactory completion of the fuel gas piping test, the M/H gas supply connector shall be installed, and the connections shall be tested with soapy water or bubble solution. [NFPA 501A:4.4.5.1]

E 413.5.2 Warning. The following warning shall be supplied to the installer:

WARNING

Do not overpressurize the fuel gas piping system. Damage to valves, regulators, and appliances is capable of occurring due to pressurization beyond the maximums specified. [NFPA 501A:4.4.5.2]

E 413.5.3 Vents. Gas appliance vents shall be visually inspected to ensure that they have not been dis-

lodged in transit and are connected securely to the appliance. [NFPA 501A:4.4.5.3]

- » **E 413.6 Oil Tanks.** Not more than one 660 gallon (2498 L) tank or two tanks with aggregate capacity of 660 gallons (2498 L) or less shall be connected to one oil-burning appliance. Two supply tanks, where used, shall be cross-connected and provided with a single fill and single vent in accordance with NFPA 31, and shall be on a common slab and rigidly secured one to the other. Tanks having a capacity of 660 gallons (2498 L) or less shall be securely supported by rigid, noncombustible supports to prevent settling, sliding, or lifting. [NFPA 501A:4.4.6]

- » **E 413.6.1 Installation.** Oil supply tanks shall be installed in accordance with the applicable provisions of NFPA 31. [NFPA 501A:4.4.6.1]

- » **E 413.6.2 Capacity.** A tank with a capacity not larger than 60 gallons (227 L) shall be permitted to be a DOT-5 shipping container (drum) and so marked, or a tank constructed in accordance with the provisions of UL 80. Tanks other than DOT-5 shipping containers having a capacity of not more than 660 gallons (2498 L) shall be constructed in accordance with the provisions of UL 80. Pressure tanks shall be constructed in accordance with Section VIII of the ASME Boiler and Pressure Vessel Code. [NFPA 501A:4.4.6.2]

- » **E 413.6.3 Location.** Tanks, as described in Section E 413.6 and Section E 413.6.2, that are adjacent to buildings shall be located not less than 10 feet (3048 mm) from a property line that is permitted to be built upon. [NFPA 501A:4.4.6.3]

- » **E 413.6.4 Vent.** Tanks with a capacity not larger than 660 gallons (2498 L) shall be equipped with an open vent not smaller than 1½ inch (40 mm) iron pipe size; tanks with a 500 gallon (1892 L) or less capacity shall have a vent of 1¼ inch (32 mm) iron pipe size. [NFPA 501A:4.4.6.4]

- » **E 413.6.5 Liquid Level.** Tanks shall be provided with a means of determining the liquid level. [NFPA 501A:4.4.6.5]

- » **E 413.6.6 Fill Opening.** The fill opening shall be a size and in a location that permits filling without spillage. [NFPA 501A:4.4.6.6]

- » **E 414.0 Manufactured Home Accessory Building Fuel Supply Systems.**

- » **E 414.1 General.** Fuel gas supply systems installed in a M/H accessory building or structure shall be in accordance with the applicable provisions of NFPA 54 and NFPA 58. Fuel oil supply systems shall comply with the applicable provisions of NFPA 31. [NFPA 501A:4.5]

- » **E 415.0 Community Building Fuel Supply Systems in Manufactured Home Communities.**

- » **E 415.1 Fuel Gas Piping and Equipment Installations.** Fuel gas piping and equipment installed within a permanent building in a M/H community shall be in accordance with nationally recognized appliance and fuel gas piping codes and standards adopted by the Authority

Having Jurisdiction. Where the state or other political subdivision does not assume jurisdiction, such fuel gas piping and equipment installations shall be designed and installed in accordance with the applicable provisions of NFPA 54 or NFPA 58. [NFPA 501A:4.6.1]

- » **E 415.2 Oil Supply Systems in M/H Communities.** Oil burning equipment and installation within a M/H community shall be designed and constructed in accordance with the applicable codes and standards adopted by the Authority Having Jurisdiction. Where the state or other political subdivision does not assume jurisdiction, such installations shall be designed and constructed in accordance with the applicable provisions of NFPA 31. [NFPA 501A:4.6.2]

- » **E 415.3 Oil-Burning Equipment and Installation.** Oil burning equipment and installation within a building constructed in a M/H community in accordance with the local building code or a nationally recognized building code shall be in accordance with nationally recognized codes and standards adopted by the Authority Having Jurisdiction. Where the state or other political subdivision does not assume jurisdiction, such oil-burning equipment and installations shall be designed and installed in accordance with the applicable provisions of NFPA 31. [NFPA 501A:4.6.3]

- » **E 415.4 Inspections and Tests.** Inspections and tests for fuel gas piping shall be made in accordance with Chapter 1 and Chapter 12 of this code.

- » **E 501.0 Recreational Vehicle Parks.**

- » **E 501.1 Plumbing Systems.** Plumbing systems shall be installed in accordance with the plumbing codes of the Authority Having Jurisdiction and with this appendix.

- » **E 601.0 Recreational Vehicle Park Toilet and Shower Facilities.**

- » **E 601.1 Water Closets and Urinals.** Water closets and urinals shall be provided at one or more locations in a recreational vehicle park. They shall be of convenient access and shall be located within a 500 foot (152 m) radius from a recreational vehicle site not provided with an individual sewer connection.

- » **E 602.0 Markings.**

- » **E 602.1 General.** Facilities for males and females shall be appropriately marked.

- » **E 603.0 Number of Water Closets.**

- » **E 603.1 General.** Not less than one water closet shall be provided for each sex up to the first 25 sites. For each additional 25 sites not provided with sewer connections, an additional water closet shall be provided.

- » **E 604.0 Interior Finish.**

- » **E 604.1 General.** The interior finish of walls shall be moisture resistant to a height of not less than 4 feet (1219 mm) to facilitate washing and cleaning.

»» **E 605.0 Floors and Drains.**

- »» **E 605.1 General.** The floors shall be constructed of material impervious to water and shall be easily cleanable. A building having water-supplied water closets shall be provided with a floor drain in the toilet room. This drain shall be provided with means to protect the trap seal in accordance with this code.

»» **E 606.0 Lavatories.**

- »» **E 606.1 General.** Where water-supplied water closets are provided, an equal number of lavatories shall be provided for up to six water closets. One additional lavatory shall be provided for each two water closets where more than six water closets are required. Each lavatory basin shall have a piped supply of potable water and shall drain into the drainage system.

»» **E 607.0 Urinals.**

- »» **E 607.1 General.** Where separate facilities are provided for men and women, urinals shall be acceptable for not more than one-third of the water closets required in the men's facilities, except that one urinal shall be permitted to be used to replace a water closet in a minimum park. Individual stall or wall-hung types of urinals shall be installed. Floor-type trough units shall be prohibited.

»» **E 608.0 Approved Water Closets.**

- »» **E 608.1 General.** Water closets shall be of an approved, elongated bowl type and shall be provided with seats with open fronts.

»» **E 609.0 Water Closet Compartment.**

- »» **E 609.1 General.** Each water closet shall be in a separate compartment and shall be provided with a latched door for privacy. A holder or dispenser for toilet paper shall be provided. Dividing walls or partitions shall be not less than 5 feet (1524 mm) high and shall be separated from the floor by a space not exceeding 12 inches (305 mm).

»» **E 610.0 Compartment Size.**

- »» **E 610.1 General.** Water closet compartments shall be not less than 30 inches (762 mm) in width [no water closet shall be set closer than 15 inches (381 mm) from its center to a side wall] and shall be not less than 30 inches (762 mm) of clear space in front of each water closet.

»» **E 611.0 Receptacle.**

- »» **E 611.1 General.** Each toilet room for women shall be provided with a receptacle for sanitary napkins. The receptacle shall be of durable, impervious, readily cleanable material, and shall be provided with a lid.

»» **E 612.0 Shower Size.**

- »» **E 612.1 General.** Each shower, where provided, shall have a floor area of 36 inches by 36 inches (914 mm by 914

mm), shall be capable of encompassing a 30 inch (762 mm) diameter circle and shall be of the individual type. The shower area shall be visually screened from view with a minimum floor area of 36 by 36 inches (914 mm by 914 mm) per shower. Each shall be provided with individual dressing areas screened from view and shall contain a minimum of one clothing hook and stool (or bench area).

E 613.0 Drainage System Connection.

- E 613.1 General.** Each shower area shall be designed to minimize the flow of water into the dressing area and shall be connected to the drainage system by means of a properly trapped and vented inlet. Each such area shall have an impervious, skid-resistant surface; wooden racks (duck boards) over shower floors shall be prohibited.

E 614.0 Ceiling Height and Doors.

- E 614.1 General.** A toilet facility shall have a ceiling height of not less than 7 feet (2134 mm) and, unless artificial light is provided, a window or skylight area equal to not less than 10 percent of the floor area shall be provided.

Doors to the exterior shall open outward, be self-closing, and shall be visually screened by means of a vestibule or wall to prevent direct view of the interior where the exterior doors are open. Such screening shall not be required on single toilet units.

E 615.0 Ventilation.

- E 615.1 General.** A toilet facility shall have permanent, non-closable, screened opening(s), having a total area not less than 5 percent of the floor area and opening directly to the exterior in order to provide proper ventilation. Listed exhaust fan(s), vented to the exterior, the rating of which in cubic feet per minute (L/s) is not less than 25 percent of the total volume of the room(s) served, shall be considered as meeting the requirements of this section. Openable windows and vents to the outside shall be provided with fly-proof screens of not less than number 16 mesh.

E 701.0 Recreational Vehicle Park Potable Water Supply and Distribution.

- E 701.1 Quality.** The supply or supplies of water shall comply with the potable water standards of the state, local health authority or, in the absence thereof, with the Drinking Water Standard of the Federal Environmental Protection Agency.

E 702.0 Sources.

- E 702.1 General.** Water approved by a regulating agency shall be acceptable. Where an approved public water supply system is available, it shall be used. Where the park has its own water supply system, the components of the system shall be approved. A water supply system that is used on a seasonal basis shall be provided with means for draining.

» E 703.0 Prohibited Connections.

» E 703.1 General. The potable water supply shall not be connected to a nonpotable or unapproved water supply, nor be subjected to backflow or backsiphonage.

» E 704.0 Supply.

» E 704.1 General. The water supply system shall be designed and constructed in accordance with the following:

- (1) A minimum of 25 gallons (95 L) per day per site for sites without individual water connections.
- (2) A minimum of 50 gallons (189 L) per day per site for sites with individual water connections.
- (3) A minimum of 50 gallons (189 L) per day per site where water-supplied water closets are provided in restrooms.

» E 705.0 Pressure and Volume.

» E 705.1 General. Where water is distributed under pressure to an individual site, the water supply system shall be designed to provide a minimum flow pressure of not less than 20 psi (138 kPa) with a minimum flow of 2 gallons per minute (gpm) (0.1 L/s) at an outlet. The pressure shall not exceed 80 psi (552 kPa).

» E 706.0 Outlets.

» E 706.1 General. Water outlets shall be convenient to access and, where not piped to individual RV sites, shall not exceed 300 feet (91 440 mm) from a site. Provisions shall be made to prevent accumulation of standing water or the creation of muddy conditions at each water outlet.

» E 707.0 Storage Tanks.

» E 707.1 General. Water storage tanks shall be constructed of impervious materials, protected against contamination, and provided with locked, watertight covers. Overflow or ventilation openings shall be down-facing and provided with corrosion-resistant screening of not less than number 24 mesh to prevent the entrance of insects and vermin. Water storage tanks shall not have direct connections to sewers.

» E 801.0 Recreational Vehicle Park Water Connections for Individual Recreational Vehicles.

» E 801.1 Location. Where provided, the water connections for potable water to individual recreational vehicle sites shall be located on the left rear half of the site (left side of RV) within 4 feet (1219 mm) of the stand.

» E 802.0 Water Riser Pipe.

» E 802.1 General. Each potable water connection shall consist of a water riser pipe that is equipped with a threaded male spigot located not less than 12 inches (305 mm) but not more than 24 inches (610 mm) above grade level for the

attachment of a standard water hose. The water riser pipe shall be protected from physical damage in accordance with this code. This connection shall be equipped with a listed antisiphon backflow prevention device.

E 803.0 Drinking Fountains.

E 803.1 General. Where provided, drinking fountains shall be in accordance with the requirements of this code.

E 901.0 Recreational Vehicle Park Drainage System.

E 901.1 Where Required. An approved drainage system shall be provided in RV parks for conveying and disposing of sewage. Where available, parks shall be connected to a public sewer system.

E 902.0 Materials.

E 902.1 General. Pipe and fittings installed in the drainage system shall be of material listed, approved, and installed in accordance with this code.

E 903.0 Pipe Sizes.

E 903.1 General. The minimum diameters of drainage laterals, branches, and mains serving RV sites shall be in accordance with Table E 903.1.

TABLE E 903.1
PIPE SIZES

| MAXIMUM NUMBER OF RECREATIONAL VEHICLE STANDS SERVED | MINIMUM PIPE SIZES (inches) |
|--|--------------------------------|
| 5 | 3 |
| 36 | 4 |
| 71 | 5 |
| 120 | 6 |
| 440 | 8 |

For SI units: 1 inch = 25 mm

E 904.0 Sewer Lines.

E 904.1 General. Sewer lines shall be located to prevent damage from vehicular traffic.

E 905.0 Cleanouts.

E 905.1 General. Cleanouts shall be provided in accordance with Chapter 7 of this code.

E 1001.0 Recreational Vehicle Site Drainage System Inlet.

E 1001.1 Sewer Riser Pipe. Where provided, the site drainage system inlet connections for individual RVs shall be located so as to prevent damage by the parking of RVs or automobiles and shall consist of a sewer riser extending vertically to grade. The minimum diameter of the sewer

riser pipe shall be not less than 3 inches (80 mm) in diameter, and shall be provided with a 4 inch (100 mm) inlet or not less than a 3 inch (80 mm) female fitting.

» E 1002.0 Location.

» E 1002.1 General. Where provided, the sewer inlet to individual RV sites shall be located on the left rear half of the site (left side of the RV) within 4 feet (1219 mm) of the stand.

» E 1003.0 Protection.

» E 1003.1 General. The sewer riser pipe shall be firmly imbedded in the ground and protected against damage from movement. It shall be provided with a tight-fitting plug or cap, which shall be secured by a durable chain (or equivalent) to prevent loss.



» E 1101.0 Recreational Vehicle Park Sanitary Disposal Stations.

» E 1101.1 Where Required. One RV sanitary disposal station shall be provided for each 100 RV sites, or part thereof, which are not equipped with individual drainage system connections.

» E 1102.0 Access.

» E 1102.1 General. Each station shall be level and convenient of access from the service road and shall provide easy ingress and egress for recreational vehicles.

» E 1103.0 Construction.

» E 1103.1 General. Unless other approved means are used, each station shall have a concrete slab with the drainage system inlet located so as to be on the road (left) side of the recreational vehicle. The slab shall be not less than 3 feet by 3 feet (914 mm by 914 mm), not less than 3½ inches (89 mm) thick and properly reinforced. The slab surface is to be troweled to a smooth finish and sloped from each side inward to a drainage system inlet.

The drainage system inlet shall consist of a 4 inch (102 mm), self-closing, foot-operated hatch of approved material with the cover milled to fit tight. The hatch body shall be set in the concrete of the slab with the lip of the opening flush with its surface to facilitate the cleansing of the slab with water. The hatch shall be properly connected to a drainage system inlet, which shall discharge to an approved sanitary sewage disposal facility.

» E 1104.0 Flushing Device.

» E 1104.1 General. Where the recreational vehicle park is provided with a piped water supply system, means for flushing the recreational vehicle holding tank and the sanitary disposal station slab shall be provided that consists of a piped supply of water under pressure, terminating in an outlet located and installed so as to prevent damage by

automobiles or recreational vehicles. The flushing device shall consist of a properly supported riser terminating not less than 2 feet (610 mm) above the ground surface, with a ¾ of an inch (20 mm) valved outlet adaptable for a flexible hose.

The water supply to the flushing device shall be protected from backflow by means of a listed vacuum breaker or backflow prevention device located downstream from the last shutoff valve.

Adjacent to the flushing arrangement shall be posted a sign of durable material not less than 2 feet by 2 feet (610 mm by 610 mm) in size. Inscribed thereon in clearly legible letters shall be the following:

“DANGER – NOT TO BE USED FOR DRINKING OR DOMESTIC PURPOSES.”

E 1201.0 Recreational Vehicle Park Water Supply «

E 1201.1 Potable Watering Stations. A potable watering station, where provided for filling recreational vehicle potable water tanks, shall be located not less than 50 feet (15 240 mm) from a sanitary disposal station. Where such is provided, adjacent to the potable water outlet there shall be a posted sign of durable material not less than 2 feet by 2 feet (610 mm by 610 mm) in size. Inscribed thereon in clear legible letters on a contrasting background shall be:

“POTABLE WATER. NOT TO BE USED FOR FLUSHING WASTE TANKS.”

The potable water shall be protected from backflow by means of a listed vacuum breaker located downstream from the last shutoff valve.



APPENDIX F

FIREFIGHTER BREATHING AIR REPLENISHMENT SYSTEMS

F 101.0 General.

F 101.1 Applicability. This chapter covers minimum requirements for the installation of firefighter breathing air replenishment systems.

F 201.0 Definitions.

F 201.1 General. For purposes of this chapter, the following definitions shall apply:

High-Rise Building. A building where the floor of an occupiable story exceeds 75 feet (22 860 mm) above the lowest level of fire department vehicle access. [NFPA 5000:3.3.69.10]

Interior Cylinder Fill Panels. Lockable interior panels that provide firefighters the ability to regulate breathing air pressure and refill self-contained breathing apparatus (SCBA) cylinders.

Interior Cylinder Fill Stations and Enclosures. Free-standing fill containment stations that provide firefighters the ability to regulate breathing air pressure and refill SCBA cylinders.

Open-Circuit Self-Contained Breathing Apparatus. A SCBA in which exhalation is vented to the atmosphere and not rebreathed. [NFPA 1981:3.3.34]

Self-Contained Breathing Apparatus (SCBA). An atmosphere-supplying respirator that supplies a respirable air atmosphere to the user from a breathing air source that is independent of the ambient environment and designed to be carried by the user. [NFPA 1981:3.3.46]

For the purposes of this appendix, where this term is used without a qualifier, it indicates an open-circuit self-contained breathing apparatus or combination SCBA/SARs. For the purposes of this appendix, combination SCBA/SARs are encompassed by the terms self-contained breathing apparatus or SCBA.

Welding Procedure Specification (WPS). A written qualified welding procedure prepared to provide direction for making production welds to code requirements. [ASME B31.1:100.2]

F 301.0 System Components.

F 301.1 General. Firefighter breathing air replenishment systems shall contain, as a minimum, the following components:

- (1) Exterior fire department connection panel
- (2) Interior fire department air fill panel or station
- (3) Interconnected piping distribution system
- (4) Pressure monitoring switch

F 401.0 Required Installations.

F 401.1 General. A firefighter air system shall be installed in the following buildings:

- (1) High-rise buildings.
- (2) Underground structures that are three or more floors below grade with an area greater than 20 000 square feet (1858 m²).
- (3) Large area structures with an area greater than 200 000 square feet (18 580 m²) and where the travel distance from the building centerline to the closest exit is greater than 500 feet (152 m), such as warehouses, manufacturing complexes, malls, or convention centers.
- (4) Underground transportation or pedestrian tunnels exceeding 500 feet (152 m) in length.

F 501.0 Exterior Fire Department Connection Panel and Enclosure.

F 501.1 Purpose. The exterior fire department connection panel shall provide the fire department's mobile air operator access to the system and shall be compatible with the fire department's mobile air unit.

F 501.2 Number of Panels. Each building or structure shall have a minimum of two panels.

F 501.3 Location. Each panel shall be attached to the building or on a remote monument at the exterior of the building with a minimum 6 foot (1829 mm) radius and 180-degree (3.14 rad) clear unobstructed access to the front of the panel. The panel shall be weather-resistant or secured inside of a weather-resistant enclosure. The panel shall be located on opposite sides of the building within 50 feet (15 240 mm) of an approved roadway or driveway, or other locations approved by the Authority Having Jurisdiction.

F 501.4 Construction. The fire department connection panel shall be installed in a metal cabinet constructed of not less than 18-gauge carbon steel or equivalent. The cabinet shall be provided with a coating or other means to protect the cabinet from corrosion.

F 501.5 Vehicle Protection. Where the panel is located in an area subject to vehicle traffic, impact protection shall be provided.

F 501.6 Enclosure Marking. The front of the enclosure shall be marked, "FIREFIGHTER AIR SYSTEM". The lettering shall be in a color that contrasts with the enclosure front and in letters that are not less than 2 inches (51 mm) high with a $\frac{3}{8}$ of an inch (9.5 mm) brush stroke.

F 501.7 Enclosure Components. The exterior fire department connection panel shall contain the necessary gauges, isolation valves, pressure-relief valves, pressure-regulating valves, check valves, tubing, fittings, supports, connectors, adapters, and other necessary components as required to allow the fire department's mobile air unit to connect and augment the system with a constant source of breathing air. Each fire department connection panel shall contain not less than two inlet air connections.

F 501.8 Pressure-Relief Valve. Pressure-relief valves shall be installed downstream of the pressure regulator inlet. The relief valve shall meet the requirements of CGA S-1.3 and shall not be field adjustable. The relief valve shall have a set-to-open pressure not exceeding 1.1 times the design pressure of the system. Pressure-relief valve discharge shall terminate so that the exhaust air stream cannot impinge upon personnel in the area. Valves, plugs, or caps shall not be installed in the discharge of a pressure-relief valve. Where discharge piping is used, the end shall not be threaded.

F 501.9 Security. The fire department connection panel enclosure shall be locked by an approved means.

F 601.0 Interior Cylinder Fill Panels.

F 601.1 Cabinet Requirements. Each cylinder fill panel shall be installed in a metal cabinet constructed of not less than 18-gauge carbon steel or equivalent. The depth of the cabinet shall not create an exit obstruction where installed in building stairwells. With the exception of the shutoff valve, pressure gauges, fill hoses, and ancillary components; no system components shall be visible and shall be contained behind a not less than 18-gauge interior panel.

F 601.2 Clearance and Access. The panel shall be located not less than 36 inches (914 mm) but not more than 60 inches (1524 mm) above the finished floor or a stairway landing. Clear unobstructed access shall be provided to each panel.

F 601.3 Door. The door shall be arranged such that where the door is open, it does not reduce the required exit width or create an obstruction in the path of egress.

F 601.4 Cabinet Marking. The front of each cylinder fill panel shall be marked, "FIREFIGHTER AIR SYSTEM". The lettering shall be in a color that contrasts with the cabinet front and in letters that are not less than 2 inches (51 mm) high with a $\frac{3}{8}$ of an inch (9.5 mm) brush stroke.

F 601.5 Cabinet Components. The cabinet shall be of a size to allow for the installation of the components in Section F 601.5.1.

F 601.5.1 Cylinder Fill Panel. The cylinder fill panel shall contain the gauges, isolation valves, pressure-relief valves, pressure-regulating valves, check valves, tubing, fittings, supports, connectors, hoses, adapters, and other components to refill SCBA cylinders.

F 601.6 Cylinder Filling Hose. The design of the cabinet shall provide a means for storing the hose to prevent kinking. Where the hose is coiled, the brackets shall be installed so that the hose bend radius is maintained at 4 inches (102 mm) or greater. Fill hose connectors for connection to SCBA cylinders shall comply with the requirements of CGA V-1, number 346 or 347. No other SCBA cylinder fill connections shall be permitted.

F 601.7 Security. Each panel cover shall be maintained and locked by an approved means.

F 701.0 Interior Cylinder Fill Stations and Enclosures.

F 701.1 Location. The location of the closet or room for each air fill station shall be approved by the Authority Having Jurisdiction. Where approved by the Authority Having Jurisdiction, the space shall be permitted to be utilized for other firefighting purposes. The door to each room enclosing the air filling station enclosure shall be readily accessible at all times. Not less than a 6 foot (1829 mm) radius and 180-degree (3.14 rad) clear unobstructed access to the front of the air filling station shall be provided. The enclosure shall have emergency lighting installed in accordance with NFPA 70.

F 701.2 Security. Each air fill station shall be installed within a lockable enclosure, closet, or room by an approved means. Access to fill equipment and controls shall be restricted to authorized personnel by key or other means.

F 701.3 Components. The air fill station shall contain the gauges, isolation valves, pressure-relief valves, pressure-regulating valves, check valves, tubing, fittings, supports, connectors, hoses, adapters, and other components to refill SCBA cylinders.

F 701.4 Cylinder Filling Hose. Where hoses are used, the design of the cabinet shall provide a means for storing the hose to prevent kinking. Where the hose is coiled, the brackets shall be installed so that the hose bend radius is maintained at 4 inches (102 mm) or greater. Fill hose connectors for connection to SCBA cylinders shall comply with the requirements of CGA V-1, no. 346 or 347. For high-pressure SCBA cylinders of 4500 pounds-force per square inch (psi) (31 026 kPa), no. 347 connectors shall be used. For low-pressure SCBA cylinders of 3000 psi (20 684 kPa) and 2200 psi (15 168 kPa), no. 346 connectors shall be used. No other SCBA cylinder fill connections shall be permitted.

F 701.5 Enclosure and Air Filling Station Marking. Each enclosure, closet, or room shall be marked, "FIREFIGHTERS AIR SYSTEM." The lettering shall be in a color that contrasts with the cabinet front and in letters that are not less than 2 inches (51 mm) high with a $\frac{3}{8}$ of an inch (9.5 mm) brush stroke.

F 801.0 Materials.

F 801.1 General. Pressurized components shall be compatible for use with high-pressure breathing air equipment and self-contained breathing air apparatus. Pressurized breathing air components shall be rated for not less than a working pressure of 5000 psi (34 474 kPa).

F 801.2 Tubing. Tubing shall be stainless steel in accordance with ASTM A269, or other approved materials that are compatible with breathing air at the system pressure. Routing of tubing and bends shall be such as to protect the tubing from mechanical damage.

F 801.3 Fittings. Fittings shall be constructed of stainless steel in accordance with ASTM A479, or other approved materials that are compatible with breathing air at the system pressure.

F 801.4 Prohibited Materials. The use of nonmetallic materials, carbon steel, iron pipe, malleable iron, high-strength gray iron, or alloy steel shall be prohibited for breathing air pipe and tubing materials.

F 801.5 Pressure Monitoring Switch. An electric low-pressure monitoring switch shall be installed in the piping system to monitor the air pressure. The pressure switch shall transmit a supervisory signal to the central alarm monitoring station where the pressure of the breathing air system is less than 80 percent of the system operating pressure. Activation of the pressure switch shall also activate an audible alarm and visual strobe located at the building annunciator panel. A weather-resistant sign shall be provided in conjunction with the audible alarm stating, "FIREFIGHTER AIR SYSTEM – LOW AIR PRESSURE ALARM." Where not part of a building annunciator panel, the lettering shall be in a contrasting color, and the letters shall be not less than 2 inches (51 mm) high with a $\frac{3}{16}$ of an inch (9.5 mm) brush stroke.

F 801.6 Isolation Valve. A system isolation valve shall be installed downstream of each air fill station and shall be located in the panel or within 3 feet (914 mm) of the station. The isolation valve shall be marked with its function in letters that are not less than $\frac{3}{16}$ of an inch (4.8 mm) high with a $\frac{1}{16}$ of an inch (1.6 mm) brush stroke.

F 901.0 System Requirements.

F 901.1 Protection. Components of the firefighter breathing air replenishment system installed in a building or structure shall be protected by not less than a 2 hour fire-resistive construction. Components shall be protected from physical damage.

F 901.2 Markings. Components shall be clearly identified by means of stainless steel or plastic labels or tags indicating their function. This shall include not less than all fire department connection panels, air fill stations, air storage system, gauges, valves, air connections, air outlets, enclosures, and doors.

F 901.3 Tubing Markings. Tubing shall be clearly marked, "FIREFIGHTERS AIR SYSTEM" and "HIGH PRESSURE BREATHING AIR" by means of signs or self-adhesive labels. Signs shall be 1 inch (25.4 mm) high and shall be secured to the tubing. Signs shall be made of copper alloy, stainless steel, or plastic and engraved with $\frac{3}{16}$ of an inch (9.5 mm) letters with a $\frac{1}{16}$ of an inch (1.6 mm) stroke lettering. Signs or labels shall be placed at not less than 20 foot (6096 mm) intervals and at each fitting, whether the tubing is concealed or in plain view. Tubing shall have a sign or label at an accessible point.

F 901.4 Support. Pipe and tubing shall be supported at intervals not less than that shown in Table 313.3 of this code. Pipe and tubing shall be supported in accordance with Section 313.0 of this code.

F 1001.0 Design Criteria.

F 1001.1 Fill Time. The system shall be designed to fill, at the most remote fill station or panel, not less than two 66 cubic foot (ft³) (1.87 m³) compressed breathing air cylinders

to a pressure not to exceed 4500 psi (31 026 kPa) simultaneously in 3 minutes or less. Where greater capacity is required, the Authority Having Jurisdiction shall specify the required system capacity.

F 1001.2 Fill Panels or Stations Location. Cylinder fill panels or stations shall be installed in the interior of buildings in accordance with Section F 1001.2.1 through Section F 1001.2.3.

F 1001.2.1 High-Rise Buildings. An interior cylinder fill panel or station shall be installed commencing on the third floor and every third floor thereafter above grade. For underground floors in buildings with more than five underground floors, an interior cylinder fill panel or station shall be installed commencing on the third floor below grade and every three floors below grade thereafter, except for the bottom-most floor.

F 1001.2.2 Underground Structures. For underground floors in buildings with more than five underground floors, an interior cylinder fill panel or station shall be installed commencing on the third floor below grade and every three floors below grade thereafter, except for the bottom-most floor.

F 1001.2.3 Installation Locations. The specific location or locations on each floor shall be approved by the Authority Having Jurisdiction.

F 1101.0 System Assembly Requirements.

F 1101.1 General. The system shall be an all-welded system except where the tubing joints are readily accessible and at the individual air fill panels or stations. Where mechanical high-pressure tube fittings are used, they shall be approved for the type of materials to be joined and rated for the maximum pressure of the system.

F 1101.2 Welding Requirements. Prior to and during the welding of sections of tubing, a continuous, regulated dry nitrogen or argon purge at 3 psi (21 kPa) shall be maintained to eliminate contamination with products of the oxidation or welding flux. The purge shall commence not less than 2 minutes prior to welding operations and continue until the welded joint is at ambient temperature. Welding procedures shall comply with the following requirements:

- (1) Qualification of the WPS to be used, and of the performance of welders and operators, is required.
- (2) No welding shall be done where there is impingement of rain, snow, sleet, or high wind on the weld area.
- (3) Tack welds permitted to remain in the finished weld shall be made by a qualified welder. Tack welds made by an unqualified welder shall be removed. Tack welds which remain shall be made with an electrode and WPS which is the same as or equivalent to the electrode and WPS to be used for the first pass. The stopping and starting ends shall be prepared by grinding or other means so that they are capable of being satisfactorily incorporated into the final weld. Tack welds which have cracked shall be removed.
- (4) Arc strikes outside the area of the intended weld shall be avoided on a base metal. [ASME B31.1:127.4.1]

F 1101.3 Prevention of Contamination. The system components shall not be exposed to contaminants, including but not limited to, oils, solvents, dirt, and construction materials. Where contamination of system components has occurred, the affected component shall not be installed in the system.

F 1201.0 System Acceptance and Certification.

F 1201.1 Static Pressure Testing. Following fabrication, assembly, and installation of the piping distribution system, exterior connection panel, and interior cylinder fill panels, the Authority Having Jurisdiction shall witness the pneumatic testing of the complete system at a test pressure of not less than 7500 psi (51 711 kPa) using oil-free dry air, nitrogen, or argon. A pneumatic test of not less than 24 hours shall be performed. During this test, all fittings, joints, and system components shall be inspected for leaks. A solution compatible with the system component materials shall be used on each joint and fitting. Defects in the system or leaks detected shall be documented on an inspection report, repaired or replaced. As an alternate, a pressure-decay test in accordance with ASME B31.3 shall be permitted.

F 1201.2 Low Pressure Switch Test. Upon successful completion of the 24 hour static pressure test, the system's low-pressure monitoring switch shall be calibrated to not less than 3000 psi (20 684 kPa) descending, and tested to verify that the signal is annunciated at the building's main fire alarm panel and by means of an audible alarm and visual strobe located in a visible location.

F 1201.3 Compatibility Check. Each air fill panel and station, and each exterior fire department connection panel, shall be tested for compatibility with the fire department's SCBA fill fittings.

F 1201.4 Material Certifications. The pipe or tubing material certifications shall be provided to the Authority Having Jurisdiction.

F 1201.5 Air Sampling. Before the system is placed into service, a minimum of two samples shall be taken from separate air fill panels and submitted to an independent certified gas analysis laboratory to verify the system's cleanliness and that the air is in accordance with the following requirements for breathing air:

- (1) Breathing air shall have oxygen content not less than 19.5 percent and not greater than 23.5 percent by volume.
- (2) Breathing air shall not have a concentration of carbon monoxide exceeding 5.0 parts per million (ppm) by volume.
- (3) Breathing air shall not have a concentration of carbon dioxide exceeding 1000 ppm by volume.
- (4) Breathing air shall not have a concentration of condensed oil and particulate exceeding 7.2 E-11 pounds per cubic inch (lb/in³) (2.0 mg/m³) at 72°F (22°C) and 30 inches of Hg (102 kPa).
- (5) Where breathing air supply for respirators is stored at pressures exceeding 15 bar (1500 kPa), the breathing

air shall not have a concentration of water exceeding 24 ppm by volume.

- (6) Breathing air shall not have a nonmethane volatile organic compound (VOC) content exceeding 25 ppm as methane equivalents.
- (7) Breathing air shall not have a pronounced or unusual odor.
- (8) Breathing air shall have a concentration of nitrogen not less than 75 percent and not more than 81 percent. [NFPA 1989:5.6]

The written report of the analysis shall be submitted to the Authority Having Jurisdiction, documenting that the breathing air is in accordance with this section.

F 1201.5.1 Air Quality Analysis. During the period of air quality analysis, the air fill panel inlet shall be secured so that no air is capable of being introduced into the system and each air fill panel shall be provided with a sign stating, "AIR QUALITY ANALYSIS IN PROGRESS, DO NOT FILL OR USE ANY AIR FROM THIS SYSTEM." This sign shall be not less than 8½ inches (216 mm) by 11 inches (279 mm) with not less than 1 inch (25.4 mm) lettering.

F 1201.6 Annual Air Sampling. The breathing air within the system shall be sampled and certified annually and inspected in accordance with the procedure in Section F 1201.5.

F 1201.7 Final Proof Test. The Authority Having Jurisdiction shall witness the filling of two empty 66 cubic foot (ft³) (1.87 m³) capacity SCBA cylinders in 3 minutes or less, using compressed air supplied by fire department equipment connected to the exterior fire department connection panel. The SCBA cylinders shall be filled at the air fill panel or station farthest from the exterior fire department connection panel. Following this, not less than two air samples shall then be taken from separate air filling stations and submitted to an independent certified gas analyst laboratory to verify the system's cleanliness and that the air is in accordance with the requirements of NFPA 1989. The written report shall be provided to the Authority Having Jurisdiction certifying that the air analysis is in accordance with the above requirements.

APPENDIX G SIZING OF VENTING SYSTEMS

(The content of this Appendix is based on Annex F of NFPA 54)

G 101.0 General.

G 101.1 Applicability. This appendix provides general guidelines for sizing venting systems serving appliances equipped with draft hoods, Category I appliances, and appliances listed for use with Type B vents.

» G 101.2 Examples Using Single Appliance Venting Tables. See Figure G 101.2(1) through Figure G 101.2(14).




Table 510.1.2(1) is used where sizing a Type B double-wall gas vent connected directly to the appliance.

Note: The appliance is permitted to be either Category I draft hood-equipped or fan-assisted type.

FIGURE G 101.2(1)

TYPE B DOUBLE-WALL VENT SYSTEM SERVING A SINGLE APPLIANCE WITH A TYPE B DOUBLE-WALL VENT




Table 510.1.2(2) is used where sizing a single-wall metal vent connector attached to a Type B double-wall gas vent.

Note: The appliance is permitted to be either Category I draft hood-equipped or fan-assisted type.

FIGURE G 101.2(2)

TYPE B DOUBLE-WALL VENT SYSTEM SERVING A SINGLE APPLIANCE WITH A SINGLE-WALL METAL VENT CONNECTOR




Table 510.1.2(3) is used where sizing a Type B double-wall gas vent connector attached to a tile-lined masonry chimney.

Notes:

1. A is the equivalent cross-sectional area of the tile liner.
2. The appliance is permitted to be either Category I draft hood-equipped or fan-assisted type.

FIGURE G 101.2(3)

VENT SYSTEM SERVING A SINGLE APPLIANCE WITH A MASONRY CHIMNEY AND A TYPE B DOUBLE-WALL VENT CONNECTOR





Table 510.1.2(4) is used where sizing a single-wall vent connector attached to a tile-lined masonry chimney.

Notes:

1. A is the equivalent cross-sectional area of the tile liner.
2. The appliance is permitted to be either Category I draft hood-equipped or fan-assisted type.

FIGURE G 101.2(4)
VENT SYSTEM SERVING A SINGLE APPLIANCE
USING A MASONRY CHIMNEY AND A SINGLE-WALL
METAL VENT CONNECTOR



Asbestos cement Type B or single-wall metal vent serving a single draft hood-equipped appliance. [See Table 510.1.2(5)]

FIGURE G 101.2(5)
ASBESTOS CEMENT TYPE B OR SINGLE-WALL METAL
VENT SYSTEM SERVING A SINGLE DRAFT HOOD-EQUIPPED
APPLIANCE




Table 510.2(1) is used where sizing Type B double-wall gas vent connectors attached to a Type B double-wall common vent.

Note: Each appliance is permitted to be either Category I draft hood-equipped or fan-assisted type.

FIGURE G 101.2(6)
VENT SYSTEM SERVING TWO OR MORE APPLIANCES WITH
TYPE B DOUBLE-WALL VENT AND TYPE B DOUBLE-WALL
VENT CONNECTORS




Table 510.2(2) is used where sizing single-wall vent connectors attached to a Type B double-wall common vent.

Note: Each appliance is permitted to be either Category I draft hood-equipped or fan-assisted type.

FIGURE G 101.2(7)
VENT SYSTEM SERVING TWO OR MORE APPLIANCES WITH
TYPE B DOUBLE-WALL VENT AND SINGLE-WALL METAL
VENT CONNECTORS





Table 510.2(3) is used where sizing Type B double-wall vent connectors attached to a tile-lined masonry chimney.

Notes:

1. A is the equivalent cross-sectional area of the tile liner.
2. The appliance is permitted to be either Category I draft hood-equipped or fan-assisted type.

FIGURE G 101.2(8)

MASONRY CHIMNEY SERVING TWO OR MORE APPLIANCES WITH TYPE B DOUBLE-WALL VENT CONNECTORS



Asbestos cement Type B or single-wall metal pipe vent serving two or more draft hood-equipped appliances. [See Table 510.2(5)]

FIGURE G 101.2(10)

ASBESTOS CEMENT TYPE B OR SINGLE-WALL METAL VENT SYSTEMS SERVING TWO OR MORE DRAFT HOOD-EQUIPPED APPLIANCES





Table 510.2(4) is used where sizing single-wall metal vent connectors attached to a tile-lined masonry chimney.

Notes:

1. A is the equivalent cross-sectional area of the tile liner.
2. Each appliance is permitted to be either Category I draft hood-equipped or fan-assisted type.

FIGURE G 101.2(9)

MASONRY CHIMNEY SERVING TWO OR MORE APPLIANCES WITH SINGLE-WALL METAL VENT CONNECTORS




Example: Manifolded common vent connector L_M shall not exceed 18 times the common vent connector manifold inside diameter; that is, a 4 inch (102 mm) inside diameter common vent connector manifold shall not exceed 72 inches (1829 mm) in length.

Note: This is an illustration of a typical manifolded vent connector. Different appliance, vent connector, or common vent types are possible.

FIGURE G 101.2(11)

USE OF MANIFOLDED COMMON VENT CONNECTORS



Example: Offset common vent

Note: This is an illustration of a typical offset vent. Different appliance, vent connector, or vent types are possible.

FIGURE G 101.2(12)
USE OF OFFSET COMMON VENT




FIGURE G 101.2(13)
MULTISTORY GAS VENT DESIGN PROCEDURE
FOR EACH SEGMENT OF SYSTEM




FIGURE G 101.2(14)
PRINCIPLES OF DESIGN OF MULTISTORY VENTS USING
VENT CONNECTOR AND COMMON VENT DESIGN TABLES

G 101.3 Example 1: Single Draft Hood-Equipped Appliance. An installer has a 120 000 British thermal units per hour (Btu/h) (35 kW) input appliance with a 5 inch (127 mm) diameter draft hood outlet that needs to be vented into a 10 foot (3048 mm) high Type B vent system. What size vent shall be used assuming: (1) a 5 foot (1524 mm) lateral single-wall metal vent connector is used with two 90 degree (1.57 rad) elbows or (2) a 5 foot (1524 mm) lateral single-wall metal vent connector is used with three 90 degree (1.57 rad) elbows in the vent system? (See Figure G 101.3)

Solution:

Table 510.1.2(2) shall be used to solve this problem because single-wall metal vent connectors are being used with a Type B vent, as follows:

- (1) Read down the first column in Table 510.1.2(2) until the row associated with a 10 foot (3048 mm) height and 5 foot (1524 mm) lateral is found. Read across this row until a vent capacity exceeding 120 000 Btu/h (35

kW) is located in the shaded columns labeled NAT Max for draft hood-equipped appliances. In this case, a 5 inch (127 mm) diameter vent has a capacity of 122 000 Btu/h (35.7 kW) and shall be permitted to be used for this application.


- (2) Where three 90 degree (1.57 rad) elbows are used in the vent system, the maximum vent capacity listed in the tables shall be reduced by 10 percent. This implies that the 5 inch (127 mm) diameter vent has an adjusted capacity of 110 000 Btu/h (32 kW). In this case, the vent system shall be increased to 6 inches (152 mm) in diameter. See the following calculations:

122 000 Btu/h (35.7 kW) x 0.90 = 110 000 Btu/h (32 kW) for 5 inch (127 mm) vent

From Table 510.1.2(2), select 6 inch (152 mm) vent.

186 000 Btu/h (54.5 kW) x 0.90 = 167 000 Btu/h (49 kW)

This figure is exceeding the required 120 000 Btu/h (35 kW). Therefore, use a 6 inch (152 mm) vent and connector where three elbows are used.



For SI units: 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW

»» **FIGURE G 101.3**
SINGLE DRAFT HOOD-EQUIPPED APPLIANCE – EXAMPLE 1


- »» **G 101.4 Example 2: Single Fan-Assisted Appliance.** An installer has an 80 000 Btu/h (23.4 kW) input fan-assisted appliance that shall be installed using 10 feet (3048 mm) of lateral connector attached to a 30 foot high (9144 mm) Type B vent. Two 90 degree (1.57 rad) elbows are needed for the installation. Is a single-wall metal vent connector permitted to be used for this application? (See Figure G 101.4)

Solution:

Table 510.1.2(2) refers to the use of single-wall metal vent connectors with Type B vent. In the first column find the row associated with a 30 foot (9144 mm) height and a 10 foot

(3048 mm) lateral. Read across this row, looking at the FAN Min and FAN Max columns, to find that a 3 inch (76 mm) diameter single-wall metal vent connector is not recommended. Moving to the next larger size single-wall connector [4 inch (102 mm)] we find that a 4 inch (102 mm) diameter single-wall metal connector has a recommended maximum vent capacity of 144 000 Btu/h (42 kW). The 80 000 Btu/h (23.4 kW) fan-assisted appliance is outside this range, so the conclusion is that a single-wall metal connector shall not be used to vent the appliance using a 10 foot (3048 mm) of lateral for the connector. However, if the 80,000 Btu/hr (23.4 kW) input appliance is moved within 5 feet (1524 mm) of the vertical vent, a 4 inch (102 mm) single-wall metal connector shall be used to vent the appliance. Table 510.1.2(2) shows the acceptable range of vent capacities for a 4 inch (102 mm) vent with 5 feet (1524 mm) of lateral to be between 72 000 Btu/h (21.1 kW) and 157 000 Btu/h (46 kW).

Where the appliance cannot be moved closer to the vertical vent, then a Type B vent shall be used as the connector material. In this case, Table 510.1.2(1) shows that, for a 30 foot (9144 mm) high vent with 10 feet (3048 mm) of lateral, the acceptable range of vent capacities for a 4 inch (102 mm) diameter vent attached to a fan-assisted appliance is between 37 000 Btu/h (10.8 kW) and 150 000 Btu/h (44 kW).



For SI units: 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW

»» **FIGURE G 101.4**
SINGLE FAN-ASSISTED APPLIANCE – EXAMPLE 2

- G 101.5 Example 3: Interpolating Between Table Values.** An installer has an 80 000 Btu/h (23.4 kW) input appliance with a 4 inch (102 mm) diameter draft hood outlet that needs to be vented into a 12 foot (3658 mm) high Type B vent. The vent connector has a 5 foot (1524 mm) lateral length and is also Type B vent. Is this appliance permitted to be vented using a 4 inch (102 mm) diameter vent? ««

Solution:

Table 510.1.2(1) is used in the case of an all Type B Vent system. However, since there is no entry in Table 510.1.2(1) for a height of 12 feet (3658 mm), interpolation shall be used. Read down the 4 inch (102 mm) diameter NAT Max column to the row associated with a 10 foot (3048 mm) height and 5 foot (1524 mm) lateral to find the capacity value of 77 000 Btu/h (22.6 kW). Read further down to the 15 foot (4572 mm) height, 5 foot (1524 mm) lateral row to find the capacity value of 87 000 Btu/h (25.5 kW). The difference between the 15 foot (4572 mm) height capacity value and the 10 foot (3048 mm) height capacity value is 10 000 Btu/h (3 kW). The capacity for a vent system with a 12 foot (3658 mm) height is equal to the capacity for a 10 foot (3048 mm) height plus two-fifths of the difference between the 10 foot (3048 mm) and 15 foot (4572 mm) height values, or 77 000 Btu/h (22.6 kW) + $\frac{2}{5} \times 10\,000$ Btu/h (3 kW) = 81 000 Btu/h (23.7 kW). Therefore, a 4 inch (102 mm) diameter vent shall be used in the installation.


» **G 101.6 Example 4: Common Venting Two Draft Hood-Equipped Appliances.** A 35 000 Btu/h (10.3 kW) water heater is to be common vented with a 150 000 Btu/h (44 kW) furnace, using a common vent with a total height of 30 feet (9144 mm). The connector rise is 2 feet (610 mm) for the water heater with a horizontal length of 4 feet (1219 mm). The connector rise for the furnace is 3 feet (914 mm) with a horizontal length of 8 feet (2438 mm). Assume single-wall metal connectors will be used with Type B vent. What size connectors and combined vent should be used in this installation? (See Figure G 101.6)

Solution:

Table 510.2(2) shall be used to size single-wall metal vent connectors attached to Type B vertical vents. In the vent connector capacity portion of Table 510.2(2), find the row associated with a 30 foot (9144 mm) vent height. For a 2 foot (610 mm) rise on the vent connector for the water heater, read the shaded columns for draft hood-equipped appliances to find that a 3 inch (76 mm) diameter vent connector has a capacity of 37 000 Btu/h (10.8 kW). Therefore, a 3 inch (76 mm) single-wall metal vent connector shall be used with the water heater. For a draft hood-equipped furnace with a 3 foot (914 mm) rise, read across the row to find that a 5 inch (127 mm) diameter vent connector has a maximum capacity of 120 000 Btu/h (35 kW) (which is too small for the furnace), and a 6 inch (152 mm) diameter vent connector has a maximum vent capacity of 172 000 Btu/h (50 kW). Therefore, a 6 inch (152 mm) diameter vent connector shall be used with the 150 000 Btu/h (44 kW) furnace. Since both vent connector horizontal lengths are less than the maximum lengths listed in Section 510.2.1, the table values shall be used without adjustments.

In the common vent capacity portion of Table 510.2(2), find the row associated with a 30 foot (9144 mm) vent height and read over to the NAT + NAT portion of the 6

inch (152 mm) diameter column to find a maximum combined capacity of 257 000 Btu/h (75 kW). Since the two appliances total 185 000 Btu/h (54 kW), a 6 inch (152 mm) common vent shall be used.



For SI units: 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW


FIGURE G 101.6
COMMON VENTING TWO DRAFT HOOD-EQUIPPED
APPLIANCES – EXAMPLE 4

» **G 101.7 Example 5(a): Common Venting a Draft Hood-Equipped Water Heater with a Fan-Assisted Furnace into a Type B Vent.** In this case, a 35 000 Btu/h (10.3 kW) input draft hood-equipped water heater with a 4 inch (102 mm) diameter draft hood outlet, 2 feet (610 mm) of connector rise, and 4 feet (1219 mm) of horizontal length is to be common vented with a 100 000 Btu/h (29 kW) fan-assisted furnace with a 4 inch (102 mm) diameter flue collar, 3 feet (914 mm) of connector rise, and 6 feet (1829 mm) of horizontal length. The common vent consists of a 30 foot (9144 mm) height of Type B vent. What are the recommended vent diameters for each connector and the common vent? The installer would like to use a single-wall metal vent connector. (See Figure G 101.7)

Solution:

Water Heater Vent Connector Diameter. Since the water heater vent connector horizontal length of 4 feet (1219 mm) is less than the maximum value listed in Table 510.2(2), the venting table values shall be used without adjustment. Using the Vent Connector Capacity portion of Table 510.2(2), read down the Total Vent Height (H) column to 30 feet (9144 mm) and read across the 2 feet (610 mm) Connector Rise (R) row to the first Btu/h rating in the NAT Max column that is equal to or exceeding the water heater input rating. The table shows that a 3 inch (76 mm) vent connector has a maximum input rating of 37 000 Btu/h (10.8 kW). Although this rating is exceeding the water heater input rating, a 3 inch (76 mm) vent connector is prohibited by Section 510.2.17. A 4 inch (102 mm) vent

connector has a maximum input rating of 67 000 Btu/h (19.6 kW) and is equal to the draft hood outlet diameter. A 4 inch (102 mm) vent connector is selected. Since the water heater is equipped with a draft hood, there are no minimum input rating restrictions.



For SI units: 1 foot = 304.8 mm, 1000 British thermal units per hour = 0.293 kW

FIGURE G 101.7
COMMON VENTING A DRAFT HOOD-EQUIPPED WATER HEATER WITH A FAN-ASSISTED FURNACE INTO A TYPE B DOUBLE-WALL COMMON VENT – EXAMPLE 5(a)

Furnace Vent Connector Diameter. Using the Vent Connector Capacity portion of Table 510.2(2), read down the Total Vent Height (H) column to 30 feet (9144 mm) and across the 3 feet (914 mm) Connector Rise (R) row. Since the furnace has a fan-assisted combustion system, find the first FAN Max column with a Btu/h rating exceeding the furnace input rating. The 4 inch (102 mm) vent connector has a maximum input rating of 119 000 Btu/h (34.9 kW) and a minimum input rating of 85 000 Btu/h (24.9 kW).

The 100 000 Btu/h (29 kW) furnace in this example falls within this range, so a 4 inch (102 mm) connector is used. Since the furnace vent connector horizontal length of 6 feet (1829 mm) is less than the maximum value listed in Section 510.2.1, the venting table values shall be used without adjustment. Where the furnace had an input rating of 80 000 Btu/h (23.4 kW), a Type B vent connector is needed in order to meet the minimum capacity limit.

Common Vent Diameter. The total input to the common vent is 135 000 Btu/h (40 kW). Using the Common Vent Capacity portion of Table 510.2(2), read down the Vent Height (H) column to 30 feet (9144 mm) and across this row to find the smallest vent diameter in the FAN + NAT column that has a Btu/h rating equal to or exceeding 135 000 Btu/h (40 kW). The 4 inch (102 mm) common vent has a capacity of 132 000 Btu/h (39 kW) and the 5 inch (127 mm) common vent has a capacity of 202 000 Btu/h (59 kW). Therefore, the 5 inch (127 mm) common vent shall be used in this example.

Summary: In this example, the installer shall use a 4 inch (102 mm) diameter, single-wall metal vent connector for the water heater and a 4 inch (102 mm) diameter, single-wall metal vent connector for the furnace. The common vent shall be a 5 inch (127 mm) diameter Type B vent.

G 101.8 Example 5(b): Common Venting into an Interior Masonry Chimney.

In this case, the water heater and fan-assisted furnace of Example 5(a) are to be common-vented into a clay-tile-lined masonry chimney with a 30 foot (9144 mm) height. The chimney is not exposed to the outdoors below the roof line. The internal dimensions of the clay tile liner are nominally 8 inches (203 mm) by 12 inches (305 mm). Assuming the same vent connector heights, laterals, and materials found in Example 5(a), what are the recommended vent connector diameters, and is this an acceptable installation?

Solution:

Table 510.2(4) is used to size common venting installations involving single-wall connectors into masonry chimneys.

Water Heater Vent Connector Diameter. Using Table 510.2(4), Vent Connector Capacity, read down the Vent Height (H) column to 30 feet (9144 mm), and read across the 2 feet (610 mm) Connector Rise (R) row to the first Btu/h rating in the NAT Max column that is equal to or exceeding the water heater input rating. The table shows that a 3 inch (76 mm) vent connector has a maximum input of 31 000 Btu/h (9 kW), while a 4 inch (102 mm) vent connector has a maximum input of 57 000 Btu/h (16.7 kW). A 4 inch (102 mm) vent connector is be used.

Furnace Vent Connector Diameter. Using the Vent Connector Capacity portion of Table 510.2(4), read down the total Vent Height (H) column to 30 feet (9144 mm) and across the 3 feet (914 mm) Connector Rise (R) row. Because the furnace has a fan-assisted combustion system, find the first FAN Max column with a Btu/h rating exceeding the furnace input rating. The 4 inch (102 mm) vent connector has a maximum input rating of 127 000 Btu/h (37 kW) and a minimum input rating of 95 000 Btu/h (27.8 kW). The 100 000 Btu/h (29 kW) furnace in this example falls within this range, so a 4 inch (102 mm) connector is used.

Masonry Chimney. From Table G 101.8, the equivalent area for a nominal liner size of 8 inches (203 mm) by 12 inches (305 mm) is 63.6 square inches (0.041 m²). Using Table 510.2(4), Common Vent Capacity, read down the FAN + NAT column under the Minimum Internal Area of Chimney value of 63 to the row for 30 foot (9144 mm) height to find a capacity value of 739 000 Btu/h (217 kW). The combined input rating of the furnace and water heater, 135 000 Btu/h (40 kW), is less than the table value so this is an acceptable installation.

Section 510.2.16 requires the common vent area to not exceed seven times the smallest listed appliance categorized vent area, flue collar area, or draft hood outlet area. Both appliances in this installation have 4 inch (102 mm) diame-

TABLE G 101.8
MASONRY CHIMNEY LINER DIMENSIONS WITH CIRCULAR
EQUIVALENTS*

| NOMINAL LINER SIZE (Inches) | INSIDE DIMENSIONS OF LINER (Inches) | INSIDE DIAMETER OR EQUIVALENT DIAMETER (Inches) | EQUIVALENT AREA (square inches) |
|-----------------------------|-------------------------------------|---|---------------------------------|
| 4 x 8 | 2½ x 6½ | 4.0 | 12.2 |
| | | 5.0 | 19.6 |
| | | 6.0 | 28.3 |
| | | 7.0 | 38.3 |
| 8 x 8 | 6¾ x 6¾ | 7.4 | 42.7 |
| | | 8.0 | 50.3 |
| 8 x 12 | 6½ x 10½ | 9.0 | 63.6 |
| | | 10.0 | 78.5 |
| 12 x 12 | 9¾ x 9¾ | 10.4 | 83.3 |
| | | 11.0 | 95.0 |
| 12 x 16 | 9½ x 13½ | 11.8 | 107.5 |
| | | 12.0 | 113.0 |
| | | 14.0 | 153.9 |
| 16 x 16 | 13¼ x 13¼ | 14.5 | 162.9 |
| | | 15.0 | 176.7 |
| 16 x 20 | 13 x 17 | 16.2 | 206.1 |
| | | 18.0 | 254.4 |
| 20 x 20 | 16¾ x 16¾ | 18.2 | 260.2 |
| | | 20.0 | 314.1 |
| 20 x 24 | 16½ x 20½ | 20.1 | 314.2 |
| | | 22.0 | 380.1 |
| 24 x 24 | 20¼ x 20¼ | 22.1 | 380.1 |
| | | 24.0 | 452.3 |
| 24 x 28 | 20¼ x 24¼ | 24.1 | 456.2 |
| | | 26.4 | 543.3 |
| 28 x 28 | 24¼ x 24¼ | 27.0 | 572.5 |
| | | 27.9 | 607.0 |
| 30 x 30 | 25½ x 25½ | 30.0 | 706.8 |
| | | 30.9 | 749.9 |
| 30 x 36 | 25½ x 31½ | 33.0 | 855.3 |
| | | 34.4 | 929.4 |
| 36 x 36 | 31½ x 31½ | 36.0 | 1017.9 |

For SI units: 1 inch = 25.4 mm, 1 square inch = 0.000645 m²

* Where liner sizes differ dimensionally from those shown in this table, equivalent diameters shall be permitted to be determined from published tables for square and rectangular ducts of equivalent carrying capacity or by other engineering methods.

ter outlets. From Table G 101.8, the equivalent area for an inside diameter of 4 inches (102 mm) is 12.2 square inches (0.008 m²). Seven times 12.2 equals 85.4, which is exceeding 63.6, so this configuration is acceptable.

G 101.9 Example 5(c): Common Venting into an Exterior Masonry Chimney. In this case, the water heater and fan-assisted furnace of Examples 5(a) and 5(b) are to be common-vented into an exterior masonry chimney. The chimney height, clay-tile-liner dimensions, and vent connector heights and laterals are the same as in Example 5(b). This system is being installed in Charlotte, North Carolina. Does this exterior masonry chimney need to be relined? Where so, what corrugated metallic liner size is recommended? What vent connector diameters are recommended? [See Table G 101.8 and Figure 510.1.2(6)]

Solution:

According to Section 510.2.19, Type B vent connectors are required to be used with exterior masonry chimneys. Use Table 510.2(8) and Table 510.2(9) to size FAN+NAT common venting installations involving Type-B double-wall connectors into exterior masonry chimneys.

The local 99 percent winter design temperature needed to use Table 510.2(8) and Table 510.2(9) shall be found in the ASHRAE Handbook – Fundamentals. For Charlotte, North Carolina, this design temperature is 19°F (-7.2°C).

Chimney Liner Requirement. As in Example 5(b), use the 63 square inches (0.04 m²) internal area column for this size clay tile liner. Read down the 63 square inches (0.04 m²) column of Table 510.2(8) to the 30 foot (9144 mm) height row to find that the combined appliance maximum input is 747 000 Btu/h (218.9 kW). The combined input rating of the appliance in this installation, 135 000 Btu/h (40 kW), is less than the maximum value, so this criterion is satisfied. Table 510.2(9), at a 19°F (-7.2°C) design temperature, and at the same vent height and internal area used earlier, shows that the minimum allowable input rating of a space-heating appliance is 470 000 Btu/h (137.7 kW). The furnace input rating of 100 000 Btu/h (29 kW) is less than this minimum value. So this criterion is not satisfied, and an alternative venting design shall be used, such as a Type B vent shown in Example 5(a) or a listed chimney liner system shown in the rest of the example.

According to Section 510.2.18, Table 510.2(1) or Table 510.2(2) are used for sizing corrugated metallic liners in masonry chimneys, with the maximum common vent capacities reduced by 20 percent. This example will be continued assuming Type B vent connectors.

Water Heater Vent Connector Diameter. Using Table 510.2(1) Connector Capacity, read down the total Vent Height (H) column to 30 feet (9144 mm), and read across the 2 feet (610 mm) Connector Rise (R) row to the first Btu/hour rating in the NAT Max column that is equal to or exceeding the water heater input rating. The table shows that a 3 inch (76 mm) vent connector has a maximum capacity of 39 000 Btu/h (11.4 kW). Although this rating is

exceeding the water heater input rating, a 3 inch (76 mm) vent connector is prohibited by Section 510.2.19. A 4 inch (102 mm) vent connector has a maximum input rating of 70 000 Btu/h (20.5 kW) and is equal to the draft hood outlet diameter. A 4 inch (102 mm) vent connector is selected.

Furnace Vent Connector Diameter. Using Table 510.2(1), Vent Connector Capacity, read down the total Vent Height (H) column to 30 feet (9144 mm), and read across the 3 feet (914 mm) Connector Rise (R) row to the first Btu/h rating in the FAN MAX column that is equal to or exceeding the furnace input rating. The 100 000 Btu/h (29 kW) furnace in this example falls within this range, so a 4 inch (102 mm) connector shall be permitted.

Chimney Liner Diameter. The total input to the common vent is 135 000 Btu/h (40 kW). Using the Common Vent Capacity portion of Table 510.2(1), read down the total Vent Height (H) column to 30 feet (9144 mm) and across this row to find the smallest vent diameter in the FAN + NAT column that has a Btu/h rating exceeding 135 000 Btu/h (40 kW). The 4 inch (102 mm) common vent has a capacity of 138 000 Btu/h (40.4 kW). Reducing the maximum capacity by 20 percent results in a maximum capacity for a 4 inch (102 mm) corrugated liner of 110 000 Btu/h (32 kW), less than the total input of 135 000 Btu/h (40 kW). So a larger liner is needed. The 5 inch (127 mm) common vent capacity listed in Table 510.2(1) is 210 000 Btu/h (62 kW), and after reducing by 20 percent is 168 000 Btu/h (49.2 kW). Therefore, a 5 inch (127 mm) corrugated metal liner shall be used in this example.

Single Wall Connectors. Once it has been established that relining the chimney is necessary, Type B double-wall vent connectors are not specifically required. This example shall be permitted to be redone using Table 510.2(2) for single-wall vent connectors. For this case, the vent connector and liner diameters would be the same as found for Type B double-wall connectors.

APPENDIX H

PRIVATE SEWAGE DISPOSAL SYSTEMS

H 101.0 General.

H 101.1 Applicability. This appendix provides general guidelines for the materials, design, and installation of private sewage disposal systems.

» **H 101.2 General Requirements.** Where permitted by Section 713.0, the building sewer shall be permitted to be connected to a private sewage disposal system in accordance with the provisions of this appendix. The type of system shall be determined on the basis of location, soil porosity, and groundwater level, and shall be designed to receive all sewage from the property. The system, except as otherwise approved, shall consist of a septic tank with effluent discharging into a subsurface disposal field, into one or more seepage pits, or into a combination of subsurface disposal field and seepage pits. The Authority Having Jurisdiction shall be permitted to grant exceptions to the provisions of this appendix for permitted structures that have been destroyed due to fire or natural disaster and that cannot be reconstructed in compliance with these provisions provided that such exceptions are the minimum necessary.

» **H 101.3 Quantity and Quality.** Where the quantity or quality of the sewage is such that the above system cannot be expected to function satisfactorily for commercial, agricultural, and industrial plumbing systems; for installations where appreciable amounts of industrial or indigestible wastes are produced; for occupancies producing abnormal quantities of sewage or liquid waste; or where grease interceptors are required by other parts of this code, the method of sewage treatment and disposal shall be first approved by the Authority Having Jurisdiction. Special sewage disposal systems for minor, limited, or temporary uses shall be first approved by the Authority Having Jurisdiction.

» **H 101.4 Septic Tank and Disposal Field Systems.** Disposal systems shall be designed to utilize the most porous or absorptive portions of the soil formation. Where the groundwater level extends to within 12 feet (3658 mm) or less of the ground surface or where the upper soil is porous and the underlying stratum is rock or impervious soil, a septic tank and disposal field system shall be installed.

» **H 101.5 Flood Hazard Areas.** Disposal systems shall be located outside of flood hazard areas.

Exception: Where suitable sites outside of flood hazard areas are not available, disposal systems shall be permitted to be located in flood hazard areas on sites where the effects of inundation under conditions of the design flood are minimized.

» **H 101.6 Design.** Private sewage disposal systems shall be so designed that additional seepage pits or subsurface drain fields, equivalent to not less than 100 percent of the required original system, shall be permitted to be installed where the original system cannot absorb all the sewage. No

division of the lot or erection of structures on the lot shall be made where such division or structure impairs the usefulness of the 100 percent expansion area.

H 101.7 Capacity. No property shall be improved in excess of its capacity to properly absorb sewage effluent by the means provided in this code. «

Exception: The Authority Having Jurisdiction shall be permitted to, at its discretion, approve an alternate system.

H 101.8 Location. No private sewage disposal system, or part thereof, shall be located in any lot other than the lot that is the site of the building or structure served by such private sewage disposal system, nor shall any private sewage disposal system or part thereof be located at any point having less than the minimum distances indicated in Table H 101.8. «

Nothing contained in this code shall be construed to prohibit the use of all or part of an abutting lot to provide additional space for a private sewage disposal system or part thereof where proper cause, transfer of ownership, or change of boundary not in violation of other requirements has been first established to the satisfaction of the Authority Having Jurisdiction. The instrument recording such action shall constitute an agreement with the Authority Having Jurisdiction, which shall clearly state and show that the areas so joined or used shall be maintained as a unit during the time they are so used. Such agreement shall be recorded in the office of the County Recorder as part of the conditions of ownership of said properties and shall be binding on heirs, successors, and assigns to such properties. A copy of the instrument recording such proceedings shall be filed with the Authority Having Jurisdiction.

H 101.9 Building Permit. Where there is insufficient lot area or improper soil conditions for sewage disposal for the building or land use proposed, and the Authority Having Jurisdiction so finds, no building permit shall be issued and no private sewage disposal shall be permitted. Where space or soil conditions are critical, no building permit shall be issued until engineering data and test reports satisfactory to the Authority Having Jurisdiction have been submitted and approved. «

H 101.10 Additional Requirements. Nothing contained in this appendix shall be construed to prevent the Authority Having Jurisdiction from requiring compliance with additional requirements than those contained herein, where such additional requirements are essential to maintain a safe and sanitary condition. «

H 101.11 Alternate Systems. Alternate systems shall be permitted to be used by special permission of the Authority Having Jurisdiction after being satisfied of their adequacy. This authorization is based on extensive field and test data from conditions similar to those at the proposed site, or require such additional data as necessary to provide assurance that the alternate system will produce continuous «

TABLE H 101.8
LOCATION OF SEWAGE DISPOSAL SYSTEM

| MINIMUM HORIZONTAL DISTANCE IN CLEAR REQUIRED FROM | BUILDING SEWER | SEPTIC TANK | DISPOSAL FIELD | SEEPAGE PIT OR CESSPOOL |
|--|----------------------|-------------|-----------------------|-------------------------|
| Building or structures ¹ | 2 feet | 5 feet | 8 feet | 8 feet |
| Property line adjoining private property | Clear ² | 5 feet | 5 feet | 8 feet |
| Water supply wells | 50 feet ³ | 50 feet | 100 feet | 150 feet |
| Streams and other bodies of water | 50 feet | 50 feet | 100 feet ⁷ | 150 feet ⁷ |
| Trees | — | 10 feet | — | 10 feet |
| Seepage pits or cesspools ⁸ | — | 5 feet | 5 feet | 12 feet |
| Disposal field ⁸ | — | 5 feet | 4 feet ⁴ | 5 feet |
| On-site domestic water service line | 1 foot ⁵ | 5 feet | 5 feet | 5 feet |
| Distribution box | — | — | 5 feet | 5 feet |
| Pressure public water main | 10 feet ⁶ | 10 feet | 10 feet | 10 feet |

For SI units: 1 foot = 304.8 mm

Notes:

¹ Including porches and steps, whether covered or uncovered, breezeways, roofed porte cocheres, roofed patios, carports, covered walks, covered driveways, and similar structures or appurtenances.

² See Section 312.3.

³ Drainage piping shall clear domestic water supply wells by not less than 50 feet (15 240 mm). This distance shall be permitted to be reduced to not less than 25 feet (7620 mm) where the drainage piping is constructed of materials approved for use within a building.

⁴ Plus 2 feet (610 mm) for each additional 1 foot (305 mm) of depth in excess of 1 foot (305 mm) below the bottom of the drain line. (See Section H 601.0)

⁵ See Section 720.0.

⁶ For parallel construction – For crossings, approval by the Health Department shall be required.

⁷ These minimum clear horizontal distances shall also apply between disposal fields, seepage pits, and the mean high-tide line.

⁸ Where disposal fields, seepage pits, or both are installed in sloping ground, the minimum horizontal distance between any part of the leaching system and ground surface shall be 15 feet (4572 mm).

and long-range results at the proposed site, not less than equivalent to systems which are specifically authorized.

Where demonstration systems are to be considered for installation, conditions for installation, maintenance, and monitoring at each such site shall first be established by the Authority Having Jurisdiction.

Approved aerobic systems shall be permitted to be substituted for conventional septic tanks provided the Authority Having Jurisdiction is satisfied that such systems will produce results not less than equivalent to septic tanks, whether their aeration systems are operating or not.

H 201.0 Capacity of Septic Tanks.

H 201.1 General. The liquid capacity of septic tanks shall comply with Table H 201.1(1) and Table H 201.1(2) as determined by the number of bedrooms or apartment units in dwelling occupancies and the estimated waste/sewage design flow rate or the number of plumbing fixture units as determined from Table 702.1 of this code, whichever is greater in other building occupancies. The capacity of any one septic tank and its drainage system shall be limited by the soil structure classification in Table H 201.1(3), and as specified in Table H 201.1(4).

H 301.0 Area of Disposal Fields and Seepage Pits.

H 301.1 General. The minimum effective absorption area in disposal fields in square feet (m²), and in seepage pits in

square feet (m²) of sidewall, shall be predicated on the required septic tank capacity in gallons (liters), estimated waste/sewage flow rate, or whichever is greater, and shall be in accordance with Table H 201.1(3) as determined for the type of soil found in the excavation, and shall be as follows:

- (1) Where disposal fields are installed, not less than 150 square feet (13.9 m²) of trench bottom shall be provided for each system exclusive of any hard pan, rock, clay, or other impervious formations. Sidewall area in excess of the required 12 inches (305 mm) and not exceeding 36 inches (914 mm) below the leach line shall be permitted to be added to the trench bottom area where computing absorption areas.
- (2) Where leaching beds are permitted in lieu of trenches, the area of each such bed shall be not less than 50 percent greater than the tabular requirements for trenches. Perimeter sidewall area in excess of the required 12 inches (305 mm) and not exceeding 36 inches (914 mm) below the leach line shall be permitted to be added to the trench bottom area where computing absorption areas.
- (3) No excavation for a leach line or leach bed shall be located within 5 feet (1524 mm) of the water table nor to a depth where sewage is capable of contaminating the underground water stratum that is usable for domestic purposes.

Exception: In areas where the records or data indicate that the groundwaters are grossly degraded, the 5 foot (1524 mm) separation requirement shall be permitted

TABLE H 201.1(1)
CAPACITY OF SEPTIC TANKS^{1, 2, 3, 4}

| SINGLE-FAMILY DWELLINGS - NUMBER OF BEDROOMS | MULTIPLE DWELLING UNITS OR APARTMENTS - ONE BEDROOM EACH | OTHER USES: MAXIMUM FIXTURE UNITS SERVED PER TABLE 702.1 | MINIMUM SEPTIC TANK CAPACITY (gallons) |
|---|---|---|---|
| 1 or 2 | — | 15 | 750 |
| 3 | — | 20 | 1000 |
| 4 | 2 units | 25 | 1200 |
| 5 or 6 | 3 | 33 | 1500 |
| — | 4 | 45 | 2000 |
| — | 5 | 55 | 2250 |
| — | 6 | 60 | 2500 |
| — | 7 | 70 | 2750 |
| — | 8 | 80 | 3000 |
| — | 9 | 90 | 3250 |
| — | 10 | 100 | 3500 |

For SI units: 1 gallon = 3.785 L

Notes:

¹ Extra bedroom, 150 gallons (568 L) each.

² Extra dwelling units over 10: 250 gallons (946 L) each.

³ Extra fixture units over 100: 25 gallons (94.6 L) per fixture unit.

⁴ Septic tank sizes in this table include sludge storage capacity and the connection of domestic food waste disposers without further volume increase.

TABLE H 201.1(2)
ESTIMATED WASTE/SEWAGE FLOW RATES^{1, 2, 3}

| TYPE OF OCCUPANCY | GALLONS PER DAY |
|--|------------------------------------|
| 1. Airports..... | 15 per employee 5 per passenger |
| 2. Auto washers | Check with equipment manufacturer |
| 3. Bowling alleys (snack bar only)..... | 75 per lane |
| 4. Camps: | |
| Campground with central comfort station | 35 per person |
| Campground with flush toilets, no showers..... | 25 per person |
| Day camps (no meals served) | 15 per person |
| Summer and seasonal..... | 50 per person |
| 5. Churches (Sanctuary)..... | 5 per seat |
| with kitchen waste | 7 per seat |
| 6. Dance halls | 5 per person |
| 7. Factories | |
| no showers..... | 25 per employee |
| with showers | 35 per employee |
| Cafeteria, add | 5 per employee |
| 8. Hospitals..... | 250 per bed |
| kitchen waste only..... | 25 per bed |
| laundry waste only | 40 per bed |
| 9. Hotels (no kitchen waste)..... | 60 per bed (2 person) |
| 10. Institutions (Resident) | 75 per person |
| Nursing home..... | 125 per person |
| Rest home..... | 125 per person |
| 11. Laundries, self-service | |
| (minimum 10 hours per day)..... | 50 per wash cycle |
| Commercial | Per manufacturer's specifications |
| 12. Motel | 50 per bed space |
| with kitchen..... | 60 per bed space |
| 13. Offices | 20 per employee |

APPENDIX H

TABLE H 201.1(2) (continued)
ESTIMATED WASTE/SEWAGE FLOW RATES^{1, 2, 3}

| | |
|--|-------------------------------------|
| 14. Parks, mobile homes | 250 per space |
| Picnic parks (toilets only) | 20 per parking space |
| Recreational vehicles | |
| without water hook-up | 75 per space |
| with water and sewer hook-up | 100 per space |
| 15. Restaurants – cafeterias | 20 per employee |
| toilet | 7 per customer |
| kitchen waste | 6 per meal |
| add for garbage disposal | 1 per meal |
| add for cocktail lounge | 2 per customer |
| kitchen waste – disposable service | 2 per meal |
| 16. Schools – Staff and office | 20 per person |
| Elementary students | 15 per person |
| Intermediate and high | 20 per student |
| with gym and showers, add | 5 per student |
| with cafeteria, add | 3 per student |
| Boarding, total waste | 100 per person |
| 17. Service station, toilets | 1000 for 1st bay |
| | 500 for each additional bay |
| 18. Stores | 20 per employee |
| Public restrooms, add | 1 per 10 square feet of floor space |
| 19. Swimming pools, public | 10 per person |
| 20. Theaters, auditoriums | 5 per seat |
| Drive-in | 10 per space |

For SI units: 1 square foot = 0.0929 m², 1 gallon per day = 3.785 L/day

Notes:

¹ Sewage disposal systems sized using the estimated waste/sewage flow rates shall be calculated as follows:

(a) Waste/sewage flow, up to 1500 gallons per day (5678 L/day)

Flow x 1.5 = septic tank size

(b) Waste/sewage flow, over 1500 gallons per day (5678 L/day)

Flow x 0.75 + 1125 = septic tank size

(c) Secondary system shall be sized for total flow per 24 hours.

² See Section H 201.1.

³ Because of the many variables encountered, it is not possible to set absolute values for waste/sewage flow rates for all situations. The designer should evaluate each situation and, where figures in this table need modification, they should be made with the concurrence of the Authority Having Jurisdiction.

TABLE H 201.1(3)
DESIGN CRITERIA OF FIVE TYPICAL SOILS

| TYPE OF SOIL | REQUIRED SQUARE FEET OF LEACHING AREA PER 100 GALLONS | MAXIMUM ABSORPTION CAPACITY IN GALLONS PER SQUARE FEET OF LEACHING AREA FOR A 24 HOUR PERIOD |
|--|---|--|
| Coarse sand or gravel | 20 | 5.0 |
| Fine sand | 25 | 4.0 |
| Sandy loam or sandy clay | 40 | 2.5 |
| Clay with considerable sand or gravel | 90 | 1.1 |
| Clay with small amount of sand or gravel | 120 | 0.8 |

For SI units: 1 square foot = 0.0929 m², 1 gallon = 3.785 L, 1 gallon per square foot = 40.7 L/m²

TABLE H 201.1(4)
LEACHING AREA SIZE BASED ON SEPTIC TANK CAPACITY

| REQUIRED SQUARE FEET OF LEACHING AREA PER 100 GALLONS SEPTIC TANK CAPACITY (square feet per 100 gallons) | MAXIMUM SEPTIC TANK SIZE ALLOWABLE (gallons) |
|--|---|
| 20–25 | 7500 |
| 40 | 5000 |
| 90 | 3500 |
| 120 | 3000 |

For SI units: 1 square foot per 100 gallons = 0.000245 m²/L, 1 gallon = 3.785 L

to be reduced by the Authority Having Jurisdiction. The applicant shall supply evidence of groundwater depth to the satisfaction of the Authority Having Jurisdiction.

- (4) The minimum effective absorption area in any seepage pit shall be calculated as the excavated sidewall area below the inlet exclusive of any hardpan, rock, clay, or other impervious formations. The minimum required area of porous formation shall be provided in one or more seepage pits. No excavation shall extend within 10 feet (3048 mm) of the water table nor to a depth where sewage is capable of contaminating underground water stratum that is usable for domestic purposes.

Exception: In areas where the records or data indicate that the groundwaters are grossly degraded, the 10 foot (3048 mm) separation requirement shall be permitted to be reduced by the Authority Having Jurisdiction.

The applicant shall supply evidence of groundwater depth to the satisfaction of the Authority Having Jurisdiction.

- (5) Leaching chambers that comply with IAPMO PS 63 and bundled expanded polystyrene synthetic aggregate units that comply with IAPMO IGC 276 shall be sized using the required area calculated using Table H 201.1(3) with a 0.70 multiplier.

H 401.0 Percolation Test.

H 401.1 Pit Sizes. Where practicable, disposal field and seepage pit sizes shall be computed from Table H 201.1(3). Seepage pit sizes shall be computed by percolation tests, unless use of Table H 201.1(3) is approved by the Authority Having Jurisdiction.

H 401.2 Absorption Qualities. In order to determine the absorption qualities of seepage pits and of questionable soils other than those listed in Table H 201.1(3), the proposed site shall be subjected to percolation tests acceptable to the Authority Having Jurisdiction.

H 401.3 Absorption Rates. Where a percolation test is required, no private disposal system shall be permitted to serve a building where that test shows the absorption capacity of the soil is less than 0.83 gallons per square foot (gal/ft²) (33.8 L/m²) or more than 5.12 gal/ft² (208.6 L/m²)

of leaching area per 24 hours. Where the percolation test shows an absorption rate greater than 5.12 gal/ft² (208.6 L/m²) per 24 hours, a private disposal system shall be permitted where the site does not overlie groundwaters protected for drinking water supplies, a minimum thickness of 2 feet (610 mm) of the native soil below the entire proposed system is replaced by loamy sand, and the system design is based on percolation tests made in the loamy sand.

H 501.0 Septic Tank Construction.

H 501.1 Plans. Plans for septic tanks shall be submitted to the Authority Having Jurisdiction for approval. Such plans shall show dimensions, reinforcing, structural calculations, and such other pertinent data as required.

H 501.2 Design. Septic tank design shall be such as to produce a clarified effluent consistent with accepted standards and shall provide adequate space for sludge and scum accumulations.

H 501.3 Construction. Septic tanks shall be constructed of solid durable materials not subject to excessive corrosion or decay and shall be watertight.

H 501.4 Compartments. Septic tanks shall have not less than two compartments unless otherwise approved by the Authority Having Jurisdiction. The inlet compartment of any septic tank shall be not less than two-thirds of the total capacity of the tank, nor less than 500 gallons (1892 L) liquid capacity, and shall be not less than 3 feet (914 mm) in width and 5 feet (1524 mm) in length. Liquid depth shall be not less than 2½ feet (762 mm) nor more than 6 feet (1829 mm). The secondary compartment of a septic tank shall have a capacity of not less than 250 gallons (946 L) and a capacity not exceeding one-third of the total capacity of such tank. In septic tanks having a 1500 gallon (5678 L) capacity, the secondary compartment shall be not less than 5 feet (1524 mm) in length.

H 501.5 Access. Access to each septic tank shall be provided by not less than two manholes 20 inches (508 mm) in minimum dimension or by an equivalent removable cover slab. One access manhole shall be located over the inlet and one access manhole shall be located over the outlet. Where a first compartment exceeds 12 feet (3658 mm) in length, an additional manhole shall be provided over the baffle wall.

H 501.6 Pipe Opening Sizes. The inlet and outlet pipe openings shall not be larger in size than the connecting sewer pipe. The vertical leg of round inlet and outlet fittings shall not be less in size than the connecting sewer pipe nor less than 4 inches (102 mm). A baffle-type fitting shall have the equivalent cross-sectional area of the connecting sewer pipe and not less than a 4 inch (102 mm) horizontal dimension where measured at the inlet and outlet pipe inverts.

H 501.7 Pipe Extension. The inlet and outlet pipe or baffle shall extend 4 inches (102 mm) above and not less than 12 inches (305 mm) below the water surface. The invert of the inlet pipe shall be at a level not less than 2 inches (51 mm) above the invert of the outlet pipe.

H 501.8 Free Vent Area. Inlet and outlet pipe fittings or baffles and compartment partitions shall have a free vent area equal to the required cross-sectional area of the house sewer or private sewer discharging therein to provide free ventilation above the water surface from the disposal field or seepage pit through the septic tank, house sewer, and stack to the outer air.

H 501.9 Sidewalls. The sidewalls shall extend not less than 9 inches (229 mm) above the liquid depth. The cover of the septic tank shall be not less than 2 inches (51 mm) above the back vent openings.

H 501.10 Partitions and Baffles. Partitions or baffles between compartments shall be of solid, durable material and shall extend not less than 4 inches (102 mm) above the liquid level. The transfer port between compartments shall be a minimum size equivalent to the tank inlet, but in no case less than 4 inches (102 mm) in size, shall be installed in the inlet compartment side of the baffle so that the entry into the port is placed 65 percent to 75 percent in the depth of the liquid. Wooden baffles are prohibited.

H 501.11 Structural Design. The structural design of septic tanks shall comply with the following requirements:

- (1) Each such tank shall be structurally designed to withstand all anticipated earth or other loads. Septic tank covers shall be capable of supporting an earth load of not less than 500 pounds per square foot (lb/ft²) (2441 kg/m²) where the maximum coverage does not exceed 3 feet (914 mm).
- (2) In flood hazard areas, tanks shall be anchored to counter buoyant forces during conditions of the design flood. The vent termination and service manhole of the tank shall be not less than 2 feet (610 mm) above the design flood elevation or fitted with covers designed to prevent the inflow of floodwater or the outflow of the contents of the tanks during conditions of the design flood.

H 501.12 Manholes. Septic tanks installed under concrete or blacktop paving shall have the required manholes accessible by extending the manhole openings to grade in a manner acceptable to the Authority Having Jurisdiction.

H 501.13 Materials. The materials used for constructing a septic tank shall be in accordance with the following:

- (1) Materials used in constructing a concrete septic tank shall be in accordance with applicable standards in Table 1701.1.
- (2) The minimum wall thickness of a steel septic tank shall be number 12 U.S. gauge (0.109 of an inch) (2.77 mm), and each such tank shall be protected from corrosion both externally and internally by an approved bituminous coating or by other acceptable means.
- (3) Septic tanks constructed of alternate materials shall be permitted to be approved by the Authority Having Jurisdiction where in accordance with approved applicable standards. Wooden septic tanks shall be prohibited.

H 501.14 Prefabricated Septic Tanks. Prefabricated septic tanks shall comply with the following requirements:

- (1) Manufactured or prefabricated septic tanks shall comply with approved applicable standards and be approved by the Authority Having Jurisdiction. Prefabricated bituminous coated septic tanks shall comply with UL 70.
- (2) Independent laboratory tests and engineering calculations certifying the tank capacity and structural stability shall be provided as required by the Authority Having Jurisdiction.

H 601.0 Disposal Fields.

H 601.1 Distribution Lines. Distribution lines shall be constructed of clay tile laid with open joints, perforated clay pipe, perforated bituminous fiber pipe, perforated high-density polyethylene pipe, perforated ABS pipe, perforated PVC pipe, or other approved materials, provided that approved openings are available for distribution of the effluent into the trench area.

H 601.2 Filter Material. Before placing filter material or drain lines in a prepared excavation, smeared or compacted surfaces shall be removed from trenches by raking to a depth of 1 inch (25.4 mm) and the loose material removed. Clean stone, gravel, slag, or similar filter material acceptable to the Authority Having Jurisdiction, varying in size from ¾ of an inch to 2½ inches (19.1 mm to 64 mm), shall be placed in the trench to the depth and grade required by this section. Drain pipe shall be placed on filter material in an approved manner. The drain lines shall then be covered with filter material to the minimum depth required by this section, and this material covered with untreated building paper, straw, or similar porous material to prevent closure of voids with earth backfill. No earth backfill shall be placed over the filter material cover until after inspection and acceptance.

Exception: Listed or approved plastic leaching chambers and bundled expanded polystyrene synthetic aggregate units shall be permitted to be used in lieu of pipe and filter material. Chamber and bundled expanded polystyrene synthetic aggregate unit installations shall follow the rules for disposal fields, where applicable, and shall be in accordance with the manufacturer's instructions.

H 601.3 Grade Board. A grade board staked in the trench to the depth of filter material shall be utilized where

the distribution line is constructed with drain tile or a flexible pipe material that will not maintain alignment without continuous support.

H 601.4 Seepage Pits. Where seepage pits are used in combination with disposal fields, the filter material in the trenches shall terminate not less than 5 feet (1524 mm) from the pit excavation, and the line extending from such points to the seepage pit shall be approved pipe with watertight joints.

H 601.5 Distribution Boxes. Where two or more drain lines are installed, an approved distribution box of sufficient size to receive lateral lines shall be installed at the head of each disposal field. The inverts of outlets shall be level, and the invert of the inlet shall be not less than 1 inch (25.4 mm) above the outlets. Distribution boxes shall be designed to ensure equal flow and shall be installed on a level concrete slab in natural or compacted soil.

H 601.6 Laterals. Laterals from a distribution box to the disposal field shall be approved pipe with watertight joints. Multiple disposal field laterals, where practicable, shall be of uniform length.

H 601.7 Connections. Connections between a septic tank and a distribution box shall be laid with approved pipe with watertight joints on natural ground or compacted fill.

H 601.8 Dosing Tanks. Where the quantity of sewage exceeds the amount that is permitted to be disposed in 500 lineal feet (152.4 m) of leach line, a dosing tank shall be used. Dosing tanks shall be equipped with an automatic siphon or pump that discharges the tank once every 3 or 4 hours. The tank shall have a capacity equal to 60 to 75 percent of the interior capacity of the pipe to be dosed at one time. Where the total length of pipe exceeds 1000 lineal feet (304.8 m), the dosing tank shall be provided with two siphons or pumps dosing alternately and each serving one-half of the leach field.

H 601.9 Construction. Disposal fields shall be constructed in accordance with Table H 601.9.

Minimum spacing between trenches or leaching beds shall be not less than 4 feet (1219 mm) plus 2 feet (610 mm) for each additional foot (305 mm) of depth in excess of 1 foot (305 mm) below the bottom of the drain line. Distribution drain lines in leaching beds shall be not more than 6 feet (1829 mm) apart on centers, and no part of the

perimeter of the leaching bed shall exceed 3 feet (914 mm) from a distribution drain line. Disposal fields, trenches, and leaching beds shall not be paved over or covered by concrete or a material that is capable of reducing or inhibiting a possible evaporation of sewer effluent.

H 601.10 Joints. Where necessary on sloping ground to prevent excessive line slope, leach lines or leach beds shall be stepped. The lines between each horizontal section shall be made with watertight joints and shall be designed so each horizontal leaching trench or bed shall be utilized to the maximum capacity before the effluent shall pass to the next lower leach line or bed. The lines between each horizontal leaching section shall be made with approved watertight joints and installed on natural or unfilled ground.

H 701.0 Seepage Pits.

H 701.1 Capacity. The capacity of seepage pits shall be based on the quantity of liquid waste discharging therein and on the character and porosity of the surrounding soil, and shall be in accordance with Section H 301.0 of this appendix.

H 701.2 Multiple Installations. Multiple seepage pit installations shall be served through an approved distribution box or be connected in series by means of a watertight connection laid on undistributed or compacted soil. The outlet from the pit shall have an approved vented leg fitting extending not less than 12 inches (305 mm) below the inlet fitting.

H 701.3 Construction. A seepage pit shall be circular in shape and shall have an excavated diameter of not less than 4 feet (1219 mm). Each such pit shall be lined with approved-type whole new hard-burned clay brick, concrete brick, concrete circular-type cesspool blocks, or other approved materials. Approval shall be obtained prior to construction for any pit having an excavated diameter greater than 6 feet (1829 mm).

H 701.4 Lining. The lining in a seepage pit shall be laid on a firm foundation. Lining materials shall be placed tight together and laid with joints staggered. Except in the case of approved-type precast concrete circular sections, no brick or block shall be greater in height than its width, and shall be laid flat to form not less than a 4 inch (102 mm)

TABLE H 601.9
GENERAL DISPOSAL FIELD REQUIREMENTS

| | MINIMUM | MAXIMUM |
|--|-----------|-----------------------|
| Number of drain lines per field | 1 | — |
| Length of each line | — | 100 feet |
| Bottom width of trench | 18 inches | 36 inches |
| Spacing of lines, center-to-center | 6 feet | — |
| Depth of earth cover of lines (preferred—18 inches) | 12 inches | — |
| Grade of lines | Level | 3 inches per 100 feet |
| Filter material under drain lines | 12 inches | — |
| Filter material over drain lines | 2 inches | — |

For SI units: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 inch per foot = 83.3 mm/m

wall. Brick or block greater than 12 inches (305 mm) in length shall have chamfered matching ends and be scored to provide for seepage. Excavation voids behind the brick, block, or concrete liner shall have not less than 6 inches (152 mm) of clean $\frac{3}{4}$ of an inch (19.1 mm) gravel or rock.

H 701.5 Brick and Block. Brick or block used in seepage pit construction shall have a compressive strength of not less than 2500 pounds per square inch (lb/in²) (1 757 674 kg/m²).

H 701.6 Sidewall. A seepage pit shall have a minimum sidewall (not including the arch) of 10 feet (3048 mm) below the inlet.

H 701.7 Arch and Dome. The arch or dome of a seepage pit shall be permitted to be constructed in one of three ways:

- (1) Approved-type hard-burned clay brick or solid concrete brick or block laid in cement mortar.
- (2) Approved brick or block laid dry. In both of the above methods, an approved cement mortar covering of not less than 2 inches (51 mm) in thickness shall be applied, said covering to extend not less than 6 inches (152 mm) beyond the sidewalls of the pit.
- (3) Approved-type one or two-piece reinforced concrete slabs of not less than 2500 lb/in² (1 757 674 kg/m²) minimum compressive strength, not less than 5 inches (127 mm) thick, and designed to support an earth load of not less than 400 pounds per square foot (lb/ft²) (1953 kg/m²). Each such cover shall be provided with a 9 inch (229 mm) minimum inspection hole with plug or cover and shall be coated on the underside with an approved bituminous or other nonpermeable protective compound.

H 701.8 Location. The top of the arch or cover shall be not less than 18 inches (457 mm) but not exceed 4 feet (1219 mm) below the surface of the ground.

H 701.9 Inlet Fitting. An approved vented inlet fitting shall be provided in the seepage pit so arranged as to prevent the inflow from damaging the sidewall.

Exception: Where using a one- or two-piece concrete slab cover inlet, fitting shall be permitted to be a one-fourth bend fitting discharging through an opening in the top of the slab cover. On multiple seepage pit installations, the outlet fittings shall comply with Section H 701.2 of this appendix.

H 801.0 Cesspools.

H 801.1 Limitations. A cesspool shall be considered as a temporary expedient pending the construction of a public sewer; as an overflow facility where installed in conjunction with an existing cesspool; or as a means of sewage disposal for limited, minor, or temporary uses, where first approved by the Authority Having Jurisdiction.

H 801.2 Septic Tanks. Where it is established that a public sewer system will be available in less than 2 years, and soil and groundwater conditions are favorable to cesspool disposal, cesspools without septic tanks shall be permitted to be installed for single-family dwellings or for other limited uses where first approved by the Authority Having Jurisdiction.

H 801.3 Construction. Each cesspool, where permitted, shall be in accordance with the construction requirements set forth in Section H 701.0 of this appendix for seepage pits and shall have a sidewall (not including arch) of not less than 20 feet (6096 mm) below the inlet, provided, however, that where a strata of gravel or equally pervious material of 4 feet (1219 mm) in thickness is found, the depth of such sidewall shall not exceed 10 feet (3048 mm) below the inlet.

H 801.4 Existing Installations. Where overflow cesspools or seepage pits are added to existing installations, the effluent shall leave the existing pit through an approved vented leg extending not less than 12 inches (305 mm) downward into such existing pit and having its outlet flow line not less than 6 inches (152 mm) below the inlet. Pipe between pits shall be laid with approved watertight joints.

H 901.0 Commercial or Industrial Special Liquid-Waste Disposal.

H 901.1 Interceptor. Where liquid wastes contain excessive amounts of grease, garbage, flammable wastes, sand, or other ingredients that affect the operation of a private sewage disposal system, an interceptor for such wastes shall be installed.

H 901.2 Installation. Installation of such interceptors shall comply with Section 1009.0 of this code, and their location shall comply with Table H 101.8 of this appendix.

H 901.3 Sampling Box. A sampling box shall be installed where required by the Authority Having Jurisdiction.

H 901.4 Design and Structural Requirement. Interceptors shall be of approved design and be not less than two compartments. Structural requirements shall comply with Section H 501.0 of this appendix.

H 901.5 Location. Interceptors shall be located as close to the source as possible and be accessible for servicing. Necessary manholes for servicing shall be at grade level and be gastight.

H 901.6 Waste Discharge. Waste discharge from interceptors shall be permitted to be connected to a septic tank or other primary system or be disposed into a separate disposal system.

H 901.7 Design Criteria. A formula shall be permitted to be adapted to other types of occupancies with similar wastes. (See Chart H 901.7)

H 1001.0 Inspection and Testing.

H 1001.1 Inspection. Inspection requirements shall comply with the following:

- (1) Applicable provisions of Section 105.0 of this code and this appendix shall be required. Plans shall be required in accordance with Section 103.3 of this code.
- (2) System components shall be properly identified as to manufacturer. Septic tanks or other primary systems shall have the rated capacity permanently marked on the unit.
- (3) Septic tanks or other primary systems shall be installed on dry, level, well-compacted soil.
- (4) Where design is predicated on soil tests, the system shall be installed at the same location and depth as the tested area.

**CHART H 901.7
RECOMMENDED DESIGN CRITERIA**

| GREASE AND GARBAGE, COMMERCIAL KITCHENS | | | | | | | | |
|---|---|------------------------------|---|------------------------------|---|-----------------------------|---|--|
| Number of meals per peak hour | x | Waste flow rate ¹ | x | Retention time ² | x | Storage factor ³ | = | Interceptor size (liquid capacity) |
| SAND-SILT OIL, AUTO WASHERS | | | | | | | | |
| Number of vehicles per hour | x | Waste flow rate ¹ | x | Retention time ² | x | Storage factor ³ | = | Interceptor size (liquid capacity) |
| SILT-LINT GREASE, LAUNDRIES, LAUNDROMATS | | | | | | | | |
| Number of machines | x | 2 cycles per hour | x | Waste flow rate ¹ | x | Retention time ² | = | Storage factor ³ = Interceptor size (liquid capacity) |

Notes:¹ Waste Flow Rate:

See Table H 201.1(2) of this appendix for estimated flow rates.

² Retention Times:

Commercial kitchen waste:

Dishwasher, disposal, or both.....2.5 hours

Single service kitchen:

Single serving with disposal.....1.5 hours

Sand-silt oil.....2.0 hours

Lint-silt (laundry).....2.0 hours

³ Storage Factors:

Fully equipped commercial kitchen.....8 hours operation: 1

16 hours operation: 2

24 hours operation: 3

Single service kitchen.....1.5

Auto washers.....self-serve: 1.5

employee operated: 2

Laundries, laundromats.....1.5 (allows for rock filter)

H 1001.2 Testing. Testing requirements shall comply with the following:

- (1) Septic tanks or other primary components shall be filled with water to flow line prior to requesting inspection. Seams or joints shall be left exposed (except the bottom), and the tank shall remain watertight.
- (2) A flow test shall be performed through the system to the point of effluent disposal. All lines and components shall be watertight. Capacities, required air space, and fittings shall comply with the provisions set forth in this appendix.

H 1101.0 Abandoned Sewers and Sewage Disposal Facilities.

H 1101.1 Plugged and Capped. An abandoned building (house) sewer, or part thereof, shall be plugged or capped in an approved manner within 5 feet (1524 mm) of the property line.

H 1101.2 Fill Material. A cesspool, a septic tank, or a seepage pit that has been abandoned or has been discontinued otherwise from further use, or to which no waste or soil pipe from a plumbing fixture is connected, shall have the sewage removed therefrom and be completely filled with the earth, sand, gravel, concrete, or other approved material.

H 1101.3 Filling Requirements. The top cover or arch over the cesspool, septic tank, or seepage pit shall be removed before filling, and the filling shall not extend above

the top of the vertical portions of the sidewalls or above the level of any outlet pipe until inspection has been called and the cesspool, septic tank, or seepage pit has been inspected. After such inspection, the cesspool, septic tank, or seepage pit shall be filled to the level of the top of the ground.

H 1101.4 Owner. No person owning or controlling a cesspool, septic tank, or seepage pit on the premises of such person or in that portion of any public street, alley, or other public property abutting such premises shall fail, refuse, or neglect to be in accordance with the provisions of this section or upon receipt of notice so to be in accordance with the Authority Having Jurisdiction.

H 1101.5 Permittee. Where disposal facilities are abandoned consequent to connecting any premises with the public sewer, the permittee making the connection shall fill all abandoned facilities in accordance with the Authority Having Jurisdiction within 30 days from the time of connecting to the public sewer.

H 1201.0 Drawings and Specifications.

H 1201.1 General. The Authority Having Jurisdiction, Health Officer, or other department having jurisdiction shall be permitted to require the following information before a permit is issued for a private sewage disposal system or at a time during the construction thereof:

- (1) Plot plan drawn to scale, completely dimensioned, showing direction and approximate slope of surface,

APPENDIX H

location of present or proposed retaining walls, drainage channels, water supply lines or wells, paved areas and structures on the plot, number of bedrooms or plumbing fixtures in each structure, and location of the private sewage disposal system with relation to lot lines and structures.

- (2) Details of construction necessary to ensure compliance with the requirements of this appendix together with a full description of the complete installation including quality, kind, and grade of materials, equipment, construction, workmanship, and methods of assembly and installation.
- (3) A log of soil formations and groundwater levels as determined by test holes dug in close proximity to a proposed seepage pit or disposal field, together with a statement of water absorption characteristics of the soil at the proposed site, as determined by approved percolation tests.

"The information contained in this appendix is not part of this American National Standard (ANS) and has not been processed in accordance with ANSI's requirements for an ANS. As such, this appendix may contain material that has not been subjected to public review or a consensus process. In addition, it does not contain requirements necessary for conformance to the standard."

The following IAPMO Installation Standard is included here for the convenience of the users of the Uniform Plumbing Code. It is not considered as a part of the Uniform Plumbing Code unless formally adopted as such. This Installation Standard is an independent, stand-alone document published by the International Association of Plumbing and Mechanical Officials and is printed herein by the expressed written permission of IAPMO.

APPENDIX I

INSTALLATION STANDARD FOR PEX TUBING SYSTEMS FOR HOT- AND COLD-WATER DISTRIBUTION

IAPMO IS 31-2014

1.0 Scope.

1.1 General.

1.1.1 This Standard specifies requirements for the installation of SDR 9 CTS crosslinked polyethylene (PEX) tubing and fittings, including cold-expansion, crimp, press, and mechanical compression fittings, intended for hot- and cold-water distribution systems within buildings.

1.1.2 This Standard applies to

- (a) SDR 9 CTS PEX tubing complying with ASTM F876 and pressure-rated in accordance with PPI TR-3; and
- (b) PEX fitting systems complying with
 - (i) ASTM F877, for mechanical compression fittings and metal or plastic insert fittings with stainless steel press sleeves;
 - (ii) ASTM F1807 or ASTM F2159, for metal or plastic insert fittings with copper crimp rings;
 - (iii) ASTM F1960, for cold expansion fittings with PEX reinforced rings; or
 - (iv) ASTM F2080, for cold expansion fittings with metal compression sleeves.

1.2 Terminology.

In this Standard,

- (a) "shall" is used to express a requirement, i.e., a provision that the user is obliged to satisfy to comply with the Standard;
- (b) "should" is used to express a recommendation, but not a requirement;
- (c) "may" is used to express an option or something permissible within the scope of the Standard; and
- (d) "can" is used to express a possibility or a capability.

Notes accompanying sections of the Standard do not specify requirements or alternative requirements; their purpose is to separate explanatory or informative material from the text. Notes to tables and figures are considered part of the table or figure and can be written as requirements.

1.3 Amendments.

Proposals for amendments to this Standard will be processed in accordance with the standards-writing procedures of IAPMO.

2.0 Reference Publications.

This Standard refers to the following publications, and where such reference is made, it shall be to the current edition of those publications, including all amendments published thereto.

| | |
|------------|---|
| ASTM F876 | Standard Specification for Crosslinked Polyethylene (PEX) Tubing |
| ASTM F877 | Standard Specification for Crosslinked Polyethylene (PEX) Hot- and Cold-Water Distribution Systems |
| ASTM F1807 | Standard Specification for Metal Insert Fittings Utilizing a Copper Crimp Ring for SDR9 Cross-linked Polyethylene (PEX) Tubing and SDR9 Polyethylene of Raised Temperature (PE-RT) Tubing |
| ASTM F1960 | Standard Specification for Cold Expansion Fittings with PEX Reinforcing Rings for Use with Cross-linked Polyethylene (PEX) Tubing |
| ASTM F2080 | Standard Specification for Cold-Expansion Fittings With Metal Compression-Sleeves for Cross-Linked Polyethylene (PEX) Pipe |

APPENDIX I

| | |
|------------------|---|
| ASTM F2159 | Standard Specification for Plastic Insert Fittings Utilizing a Copper Crimp Ring for SDR9 Cross-linked Polyethylene (PEX) Tubing and SDR9 Polyethylene of Raised Temperature (PE-RT) Tubing |
| ASTM F2657 | Standard Test Method for Outdoor Weathering Exposure of Crosslinked Polyethylene (PEX) Tubing |
| AWWA C904 | Cross-Linked Polyethylene (PEX) Pressure Tubing, ½ In. (12 mm) Through 3 In. (76 mm) for Water Service |
| IAPMO/ANSI UPC-1 | Uniform Plumbing Code |
| PPI TR-3 | Policies and Procedures for Developing Hydrostatic Design Basis (HDB), Pressure Design Basis (PDB), Strength Design Basis (SDB), and Minimum Required Strength (MRS) Ratings for Thermoplastic Tubing Materials or Tubing |

3.0 Abbreviations.

The following abbreviations apply in this Standard:

| | | |
|-------------|---|---------------------------|
| CTS | — | copper tube size |
| HDPE | — | high density polyethylene |
| IC | — | insulation contact |
| NTS | — | nominal tubing size |
| PEX | — | crosslinked polyethylene |
| SDR | — | standard dimension ratio |
| UV | — | ultraviolet light |

4.0 General.

4.1 Tubing.

4.1.1 PEX tubing can be

- (a) pigmented throughout (i.e., with color);
- (b) non-pigmented (e.g., translucent or natural); or
- (c) coated with a pigmented layer.

4.1.2 PEX tubing is typically available in NTS-¹/₄ to NTS-3.

4.1.3 Before installation, the installer shall review the tubing markings and verify that

- (a) the standard designation(s) of the fittings to which the tube can be joined to is included in the markings;
- (b) it bears a certification mark from an accredited certification organization; and
- (c) pressure and temperature ratings meet or exceed that of the intended end-use.

4.2

4.2.1

Fittings.

Cold-Expansion Fittings.

Cold-expansion fittings typically

- (a) are made of brass, stainless steel, or sulfone;
- (b) consist of an insert and a PEX reinforcing ring; and
- (c) are available in NTS-³/₈ to NTS-3.

4.2.2

Crimp or Press Insert Fittings.

Crimp or press insert fittings typically

- (a) are made of brass, stainless steel, or sulfone;
- (b) consist of an insert and a copper crimp ring or a stainless steel press ring
- (c) are available in NTS-³/₈ to NTS-3.

4.2.3

Compression Fittings.

Compression (i.e., transition) fittings typically

- (a) are made of brass; and
- (b) consist of
 - (i) a nut, a compression ring, and an insert; or
 - (ii) an O-ring brass insert with a compression sleeve
- (c) are available in NTS-¹/₄ to NTS-3.

4.3

Installation.

Only fittings systems marked on the tubing shall be used for installation with that particular tubing.

4.4

Tools.

Tools and tool accessories (e.g., tool heads) used for the installation of PEX tubing systems shall be in accordance with the manufacturer's specifications and written instructions.

4.5

Tubing Protection.

4.5.1

Abrasion.

PEX tubing passing through drilled or notched metal studs or metal joists, or hollow-shell masonry walls shall be protected from abrasion by elastomeric or plastic sleeves or grommets.

4.5.2

Puncture.

Steel-plate protection shall be installed in accordance with the local plumbing code.

5.0

Handling.

5.1

Receiving.

When receiving PEX tubing shipments, the receiver shall inspect and inventory each shipment, ensuring that there has been no loss or damage. In addition:

- (a) At the time of unloading, the markings of all tubing, fittings, and accessories shall be verified to ensure that all items have

been manufactured in accordance with the applicable product Standard and appropriately certified.

- (b) An overall examination of the shipment shall be made. If the shipment is intact, ordinary inspection while unloading shall be sufficient to ensure that the items have arrived in good condition.
- (c) If the load has shifted, has broken packaging, or shows evidence of rough treatment, each item shall be carefully inspected for damage.
- (d) The total quantities of each shipment (e.g., tubing, gaskets, fittings, and accessories) shall be checked against shipping records.
- (e) Any damaged or missing items shall be noted on the delivery slip. The carrier shall be notified immediately and a claim made in accordance with its instructions.
- (f) No damaged material shall be disposed of. The carrier shall recommend the procedure to follow.
- (g) Shortages and damaged materials are normally not reshipped without request. If replacement material is needed, it shall be reordered from the manufacturer, the distributor, or a manufacturer's representative.

5.2 Storage and UV Exposure.

5.2.1 PEX tubing and fittings shall be stored indoors and in its original packaging until the time of installation. Appropriate precautions to protect the tubing from damage, impact, and punctures shall be taken.

5.2.2 Accumulative exposure time to UV radiation during storage and installation shall not exceed the UV exposure limits recommended by the manufacturer or specified in ASTM F876.

Note: *ASTM F876 has four categories for UV-resistance, ranging from untested to 6 months of continuous exposure, as listed in the material designation code.*

5.3 Exposure to Heat.

5.3.1 PEX tubing and fittings shall not be exposed to open flames.

5.3.2 PEX tubing shall not be exposed to temperatures exceeding 93°C (200°F).

5.4 Exposure to Chemicals.

5.4.1 Chemical compatibility (e.g., with common construction materials) shall be verified with the manufacturer prior to direct contact.

5.4.2 In general, petroleum- or solvent-based chemicals (e.g., paints, greases, pesticides, or

sealants) shall not be allowed to come in direct contact with PEX tubing or fittings.

6.0

6.1

Thermal Expansion and Contraction.

Horizontal Tubing Runs.

Thermal expansion and contraction forces on suspended horizontal runs of PEX tubing that can experience a 22°C (40°F) or greater change in temperature (operating temperature compared to ambient temperature) shall be controlled by a means of mitigating temperature-induced stresses to other parts of the water distribution system. Means for controlling thermal expansion and contraction include

- (a) loops;
- (b) offsets;
- (c) arms with rigid anchor points; and
- (d) supporting the tubing with continuous runs of CTS support channels with
 - (i) rigid anchor points installed every 20 m (65 ft); and
 - (ii) proper strapping (e.g., 27 kg (60 lb) straps or equivalent) spaced 1 m (3 ft) and rated for the maximum temperature and UV exposure of the PEX tubing application.

6.2

Vertical Tubing Runs.

Thermal expansion and contraction forces on vertical runs of PEX tubing that pass through more than one floor and can experience a 22°C (40°F) or greater change in temperature (operating temperature compared to ambient temperature) shall be controlled by installing

- (a) a riser clamp at the top of every other floor; and
- (b) mid-story guides to maintain the alignment of the vertical tubing.

Note: *Installing riser clamps isolates expansion and contraction to two-floor intervals allowing the PEX tubing to naturally compensate for the expansion and contraction.*

6.3

Clearance.

Adequate clearance shall be provided between PEX tubing and the building structure (e.g., using bored holes and sleeves) to allow for free longitudinal movement of the tubing.

6.4

Expansion Arms and Expansion Loops.

6.4.1

Expansion Arms (See Figure 1).

6.4.1.1

Expansion arms shall be installed as illustrated in Figure 1.

- 6.4.1.2** The minimum length of expansion arms shall be calculated using the following equation:

$$LB = C \times \sqrt{(D \times \Delta L)}$$

where

LB = length of flexible arm

C = material constant (12 for PEX)

D = nominal outside diameter of tubing

ΔL = thermal expansion length

6.4.2 Expansion Loops (See Figure 2).

- 6.4.2.1** Expansion loops shall be installed at the mid-point between anchors, as illustrated in Figure 2.

- 6.4.2.2** The minimum length of expansion loops shall be calculated using the equation in Section 6.4.1.2; however, the distance LB shall be divided into three sections, as illustrated in Figure 2, where

$$L1 = LB \div 5; \text{ and}$$

$$L2 = L1 \times 2$$

7.0 Hangers and Supports.

7.1 Vertical Tubing.

Vertical PEX tubing shall

- (a) be supported at each floor or as specified by the water-distribution system designer to allow for expansion and contraction; and
- (b) have mid-story guides.

7.2 Horizontal Tubing.

Unless otherwise authorized by the authority having jurisdiction, suspended horizontal runs of PEX tubing

- (a) NTS-1 and smaller shall be supported every 0.8 m (32 in), unless continuously supported by metallic CTS or V channels that
 - (i) are supported at intervals not exceeding 1.8 m (6 ft);
 - (ii) have a maximum cantilever, measured from the support to the end of the CTS support channel, of 0.5 m (1.5 ft); and
- (b) NTS-1¼ and larger shall be supported every 1.2 m (4 ft), unless continuously supported by metallic CTS or V channels that
 - (i) are supported at intervals not exceeding 2.4 m (8 ft); and
 - (ii) have a maximum cantilever, measured from the support to the end of the CTS support channel, of 0.5 m (1.5 ft).

7.3

Anchors.

Anchors shall be

- (a) used to restrict PEX tubing movement;
- (b) made of materials that provide rigidity to the support system and utilize pipe clamps designed for plastic tubing capable of restraining the tubing; and
- (c) installed in accordance with Figures 1 or 2, as applicable (i.e., anchor distances and size of arms and offsets).

Note: Anchors are typically installed every 20 m (65 ft). See Section 6.

8.0

Joints and Connections.

8.1

Assembly Procedure.

The procedure for making joints shall be as specified by the manufacturer.

8.2

Concealed Joints.

PEX tubing systems manufactured in accordance with the applicable standards referenced in Section 2 are deemed manufactured joints and may be installed in concealed spaces without the need for access panels.

9.0

Clearances.

9.1

Gas Vents.

Except for double-wall B-vents, which require a 25 mm (1 in) clearance, the clearance between gas appliance vents and PEX tubing shall be at least 150 mm (6 in).

9.2

Recessed Light Fixtures.

Except when the PEX tubing is protected with fiberglass or closed-cell insulation or the recessed light is IC-rated, the clearance between recessed light fixtures and PEX tubing shall be at least 300 mm (12 in).

9.3

Fluorescent Lighting.

When in direct view of the light source, the clearance between fluorescent lighting and PEX tubing shall be at least 1.5 m (5 ft). If the minimum clearance cannot be achieved, the PEX tubing shall be protected with a UV-blocking sleeve.

10.0

Other Considerations.

10.1

Hot-Work Joints.

Hot-work joints (e.g., soldering, brazing, welding, and fusion-welding) shall be

- (a) made at least 500 mm (18 in) from PEX tubing in the same water line; and
- (b) performed prior to completing the PEX joints.

10.2 Bending Radius.

10.2.1 The free (unsupported) bending radius for PEX tubing, measured at the outside of the bend, shall be not less than six times the actual outside diameter of the tubing, unless otherwise specified by the PEX manufacturer. Supports should be used to facilitate rigid bends and to alleviate stress on PEX joints when bends are needed in close proximity to such joints.

10.2.2 Tighter bends may be used when the PEX tubing is uniformly bent (supported) around a curved bracket or other rigid fixture. In this case, the minimum outside radius of the supported bend shall be as specified by the PEX manufacturer.

10.3 Directional Fittings.

Directional fittings (e.g., 90° and 45° elbows) should only be installed where necessary.

Note: *The flexible nature of PEX tubing allows for sweeping bends resulting in less fittings and joints.*

10.4 Direct Burial.

PEX tubing and fittings may be used in direct burial applications when allowed in the manufacturer's written installation instructions.

Note: *AWWA C904 should be consulted for water service applications.*

10.5 Fire-Resistive Construction.

Manufacturer's installation instructions shall be consulted prior to installation of PEX tubing in fire resistive constructions. PEX tubing penetrating a wall or floor-and-ceiling fire-rated assembly shall include a means of passive fire protection in accordance with the local codes.

10.6 Sizing and Flow Velocities.

10.6.1 PEX tubing shall be sized in accordance with IAPMO/ANSI UPC 1.

Note: *Potable water piping sizing is addressed in Section 610.0 and Appendix A of IAPMO/ANSI UPC 1-2012.*

10.6.2 The tubing manufacturer's pressure-loss data should be referenced when using Appendix A of IAPMO/ANSI UPC 1. In absence of such data, Figures 3 and 4 shall be used.

10.6.3 Flow velocities through the water distribution system, used for calculating flush tank and flush valve fixture units depending on the tubing sizes (see Table 1), shall not exceed

- (a) 3.0 m/s (10 ft/s) for cold-water distribution systems; and
- (b) 2.4 m/s (8 ft/s) for hot-water distribution systems.

Note: *The flow velocities in Items (a) and (b) account for the increased velocities through the fittings.*


10.6.4 Hot-water recirculation systems shall

- (a) be balanced to maintain adequate system temperatures; and
- (b) have flow velocities that do not exceed 0.6 m/s (2 ft/s) (see Table 2); and
- (c) use only PEX tubing designated for hot, chlorinated water recirculation systems and rated for the maximum percentage of time during which the system is intended to be operated at elevated temperatures, in accordance with ASTM F876.

10.7 Installation Testing.

Installation of PEX water distribution systems may be tested with air when

- (a) expressly allowed in the written instructions of the manufacturers of all plastic pipe and fittings installed at the time the PEX piping system is being tested; and
- (b) compressed air or other gas testing is not prohibited by the authority having jurisdiction.

**Note:**

$$LB = C \times \sqrt{D \times \Delta L}$$

where

LB = length of flexible arm

C = material constant (12 for PEX)

D = nominal outside diameter of tubing

ΔL = thermal expansion length

**FIGURE 1
EXPANSION ARMS**
(See Sections 6.4.1 and 7.3)


TABLE 1
CALCULATION OF FLUSH TANK AND FLUSH VALVE FIXTURE UNITS
 (See Section 10.6.3)

| Nominal Tubing Size | Flow Velocity: 3.0 m/s (10 ft/s) | | | Flow Velocity: 2.4 m/s (8 ft/s) | | |
|---------------------|----------------------------------|--------------------------|---------------------------|---------------------------------|--------------------------|---------------------------|
| | Flow Volume, L/min (gpm) | Flush Tank Fixture Units | Flush Valve Fixture Units | Flow, L/min (gpm) | Flush Tank Fixture Units | Flush Valve Fixture Units |
| 1/2 | 20.8 (5.5) | 6 | — | 16.7 (4.4) | 4 | — |
| 3/4 | 41.6 (11.0) | 15 | — | 33.3 (8.8) | 11 | — |
| 1 | 68.9 (18.2) | 26 | — | 55.3 (14.6) | 20 | — |
| 1-1/4 | 103.0 (27.2) | 46 | 10 | 82.5 (21.8) | 33 | 5 |
| 1-1/2 | 143.5 (37.9) | 77 | 24 | 114.7 (30.3) | 54 | 13 |
| 2 | 246.1 (65.0) | 200 | 91 | 196.8 (52.0) | 135 | 52 |
| 3 | 533.0 (140.8) | 590 | 495 | 426.2 (112.6) | 443 | 310 |

TABLE 2
TUBING SIZES, FLOWS, AND FRICTION LOSSES FOR
HOT-WATER RECIRCULATION SYSTEMS

(See Section 10.6.4)

| Nominal Tubing Size | Flow Velocity m/s (ft/s) | Flow Volume L/min (gpm) | Friction Losses at 49 °C (120°F) kPa/m (psi/ft) |
|---------------------|--------------------------|-------------------------|---|
| 1/2 | 0.6 (2) | 4.2 (1.1) | 0.4411 (0.0195) |
| 3/4 | 0.6 (2) | 8.3 (2.2) | 0.2850 (0.0126) |
| 1 | 0.6 (2) | 13.6 (3.6) | 0.2081 (0.0092) |
| 1 1/4 | 0.6 (2) | 20.4 (5.4) | 0.1629 (0.0072) |
| 1 1/2 | 0.6 (2) | 28.4 (7.5) | 0.1335 (0.0059) |
| 2 | 0.6 (2) | 48.8 (12.9) | 0.0950 (0.0042) |



Note:

LB shall be calculated as specified in Figure 2 and divided into three sections, as follows:

$$LB = L1 + (2 \times L2)$$

where

$$L1 = LB \div 5; \text{ and}$$

$$L2 = L1 \times 2.$$

FIGURE 2
EXPANSION LOOPS
 (See Sections 6.4.2 and 7.3)




FIGURE 3
PRESSURE LOSS OF PEX TUBING AT 16 °C (60°F)
(See Section 10.6.2)




FIGURE 4
PRESSURE LOSS OF PEX TUBING AT 49 °C (120°F)
 (See Section 10.6.2)

APPENDIX J

COMBINATION OF INDOOR AND OUTDOOR COMBUSTION AND VENTILATION OPENING DESIGN

(The content of this Appendix is based on Annex I of NFPA 54)

J 101.0 General.

J 101.1 Applicability. This appendix provides general guidelines for the sizing of combination indoor and outdoor combustion and ventilation air openings.

» **J 101.2 Example of Combination Indoor and Outdoor Combustion Air Opening.** Determine the required combination of indoor and outdoor combustion air opening sizes for the following appliance installation example.

Example Installation: A fan-assisted furnace and a draft hood-equipped water heater with the following inputs are located in a 15 foot by 30 foot (4572 mm by 9144 mm) basement with an 8 foot (2438 mm) ceiling. No additional indoor spaces shall be used to help meet the appliance combustion air needs.

Fan-Assisted Furnace Input: 100 000 British thermal units per hour (Btu/h) (29 kW)

Draft Hood-Equipped Water Heater Input: 40 000 Btu/h (11.7 kW)

Solution:

- (1) Determine the total available room volume:

Appliance room volume:

15 feet by 30 feet (4572 mm by 9144 mm) with an 8 foot (2438 mm) ceiling = 3600 cubic feet (101.94 m³)

- (2) Determine the total required volume.

The standard method to determine combustion air shall be used to calculate the required volume.

The combined input for the appliances located in the basement is calculated as follows:

100 000 Btu/h (29 kW) + 40 000 Btu/h (11.7 kW) = 140 000 Btu/h (41 kW)

The standard method requires that the required volume be determined based on 50 cubic feet per 1000 Btu/h (4.83 m³/kW).

Using Table J 101.2, the required volume for a 140 000 Btu/h (41 kW) water heater is 7000 cubic feet (198.22 m³).

Conclusion:

Indoor volume is insufficient to supply combustion air since the total of 3600 cubic feet (101.94 m³) does not meet the required volume of 7000 cubic feet (198.22 m³). Therefore, additional combustion air shall be provided from the outdoors.

- (3) Determine ratio of the available volume to the required volume.

$$\frac{3600 \text{ cubic feet}}{7000 \text{ cubic feet}} = 0.51$$

- (4) Determine the reduction factor to be used to reduce the full outdoor air opening size to the minimum required based on ratio of indoor spaces.

$$1.00 - 0.51 \text{ (from Step 3)} = 0.49$$

- (5) Determine the single outdoor combustion air opening size as where combustion air is to come from outdoors. In this example, the combustion air opening directly communicates with the outdoors.

$$\frac{140\,000 \text{ Btu/h}}{3000 \text{ British thermal units per square inch (Btu/in}^2\text{)}} = 47 \text{ square inches (0.03 m}^2\text{)}$$

- (6) Determine the minimum outdoor combustion air opening area.

Outdoor opening area = 0.49 (from Step 4) x 47 square inches (0.03 m²) = 23 square inches (0.01 m²)

Section 506.5.3(3) requires the minimum dimension of the air opening shall be not less than 3 inches (76 mm).



TABLE J 101.2
STANDARD METHOD: REQUIRED VOLUME, ALL APPLIANCES*
[NFPA 54: TABLE A.9.3.2.1]

| APPLIANCE INPUT (Btu/h) | REQUIRED VOLUME (cubic feet) |
|----------------------------|---------------------------------|
| 5000 | 250 |
| 10 000 | 500 |
| 15 000 | 750 |
| 20 000 | 1000 |
| 25 000 | 1250 |
| 30 000 | 1500 |
| 35 000 | 1750 |
| 40 000 | 2000 |
| 45 000 | 2250 |
| 50 000 | 2500 |
| 55 000 | 2750 |
| 60 000 | 3000 |
| 65 000 | 3250 |
| 70 000 | 3500 |
| 75 000 | 3750 |
| 80 000 | 4000 |
| 85 000 | 4250 |
| 90 000 | 4500 |
| 95 000 | 4750 |
| 100 000 | 5000 |
| 105 000 | 5250 |
| 110 000 | 5500 |
| 115 000 | 5750 |
| 120 000 | 6000 |
| 125 000 | 6250 |
| 130 000 | 6500 |
| 135 000 | 6750 |
| 140 000 | 7000 |
| 145 000 | 7250 |
| 150 000 | 7500 |
| 160 000 | 8000 |
| 170 000 | 8500 |
| 180 000 | 9000 |
| 190 000 | 9500 |
| 200 000 | 10 000 |
| 210 000 | 10 500 |
| 220 000 | 11 000 |
| 230 000 | 11 500 |
| 240 000 | 12 000 |
| 250 000 | 12 500 |
| 260 000 | 13 000 |
| 270 000 | 13 500 |
| 280 000 | 14 000 |
| 290 000 | 14 500 |
| 300 000 | 15 000 |

For SI units: 1000 British thermal units per hour = 0.293 kW, 1 cubic foot = 0.0283 m³

* See Section 506.4.1, Section 506.4.1(1), Figure 506.4(1), Figure 506.4(2), Section 506.4.1(2), Figure 506.4(3), Section 506.4.2, and Figure 506.4.2.

APPENDIX K

POTABLE RAINWATER CATCHMENT SYSTEMS

K 101.0 General.

K 101.1 Applicability. The provisions of this appendix shall apply to the installation, construction, alteration, and repair of potable rainwater catchment systems.

K 101.2 System Design. Potable rainwater catchment systems in accordance with this appendix shall be designed by a registered design professional or person deemed competent by the Authority Having Jurisdiction to perform potable rainwater catchment system design work.

K 101.3 Permit. It shall be unlawful for a person to construct, install, or alter, or cause to be constructed, installed, or altered a potable rainwater catchment systems in a building or on a premise without first obtaining a permit to do such work from the Authority Having Jurisdiction.

K 101.3.1 Plumbing Plan Submission. No permit for a rainwater catchment system requiring a permit shall be issued until complete plumbing plans, with data satisfactory to the Authority Having Jurisdiction, have been submitted and approved. No changes or connections shall be made to either the rainfall catchment or the potable water system within a site containing a rainwater catchment water system without approval by the Authority Having Jurisdiction.

K 101.3.2 System Changes. No changes or connections shall be made to either the rainwater catchment system or the potable water system within a site containing a rainwater catchment system requiring a permit without approval by the Authority Having Jurisdiction.

K 101.4 Product and Material Approval. System components shall be properly identified as to the manufacturer.

K 101.4.1 Plumbing Materials and Systems. Pipe, pipe fittings, traps, fixtures, material, and devices used in a potable rainwater system shall be listed or labeled (third-party certified) by a listing agency (accredited conformity assessment body) and shall be in accordance with approved applicable recognized standards referenced within this code, and shall be free from defects. Unless otherwise provided for in this appendix, materials, fixtures, or devices used or entering into the construction of plumbing systems, or parts thereof, shall be submitted to the Authority Having Jurisdiction for approval.

K 101.5 Maintenance and Inspection. Potable rainwater catchment systems and components shall be inspected and maintained in accordance with Section K 101.5.1 through Section K 101.5.3.

K 101.5.1 Frequency. Potable rainwater catchment systems and components shall be inspected and maintained in accordance with Table K 101.5 unless more

frequent inspection and maintenance is required by the manufacturer.

K 101.5.2 Maintenance Log. A maintenance log for potable rainwater catchment systems shall be maintained by the property owner and be available for inspection. The property owner or designated appointee shall ensure that a record of testing, inspection, and maintenance in accordance with Table K 101.5 is maintained in the log. The log will indicate the frequency of inspection, and maintenance for each system. A record of the required water quality tests shall be retained for not less than 2 years.

K 101.5.3 Maintenance Responsibility. The required maintenance and inspection of potable rainwater catchment systems shall be the responsibility of the property owner, unless otherwise required by the Authority Having Jurisdiction.

K 101.6 Operation and Maintenance Manual. An operation and maintenance manual for potable rainwater catchment systems shall be supplied to the building owner by the system designer. The operating and maintenance manual shall include the following:

- (1) Detailed diagram of the entire system and the location of system components.
- (2) Instructions on operating and maintaining the system.
- (3) Details on maintaining the required water quality as determined by the Authority Having Jurisdiction.
- (4) Details on deactivating the system for maintenance, repair, or other purposes.
- (5) Applicable testing, inspection, and maintenance frequencies in accordance with Table K 101.5.
- (6) A method of contacting the manufacturer(s).

K 101.7 Minimum Water Quality Requirements. The minimum water quality for potable rainwater catchment systems shall comply with the applicable water quality requirements as determined by the public health Authority Having Jurisdiction.

K 101.8 Material Compatibility. In addition to the requirements of this appendix, potable rainwater catchment systems shall be constructed of materials that are compatible with the type of pipe and fitting materials and water conditions in the system.

K 101.9 System Controls. Controls for pumps, valves, and other devices that contain mercury that come in contact with the water supply shall not be permitted.

K 102.0 Connection.

K 102.1 General. No water piping supplied by a potable rainwater catchment system shall be connected to a source

TABLE K 101.5
MINIMUM POTABLE RAINWATER CATCHMENT SYSTEM TESTING, INSPECTION, AND MAINTENANCE FREQUENCY

| DESCRIPTION | MINIMUM FREQUENCY |
|---|---|
| Inspect and clean filters and screens, and replace (where necessary). | Every 3 months |
| Inspect and verify that disinfection, filters and water quality treatment devices and systems are operational. Perform water quality tests in accordance with the Authority Having Jurisdiction. | In accordance with the manufacturer's instructions, and the Authority Having Jurisdiction. |
| Perform applicable water quality tests to verify compliance with Section K 104.2 | Every 3 months |
| Perform a water quality test for E. Coli, Total Coliform, and Heterotrophic bacteria. For a system where 25 different people consume water from the system over a 60 day period, a water quality test for cryptosporidium shall be performed. | After initial installation and every 12 months thereafter, or as directed by the Authority Having Jurisdiction. |
| Inspect and clear debris from rainwater gutters, downspouts, and roof washers. | Every 6 months |
| Inspect and clear debris from roof or other aboveground rainwater collection surface. | Every 6 months |
| Remove tree branches and vegetation overhanging roof or other aboveground rainwater collection surface. | As needed |
| Inspect pumps and verify operation. | After initial installation and every 12 months thereafter |
| Inspect valves and verify operation. | After initial installation and every 12 months thereafter |
| Inspect pressure tanks and verify operation. | After initial installation and every 12 months thereafter |
| Clear debris and inspect storage tanks, locking devices, and verify operation. | After initial installation and every 12 months thereafter |
| Inspect caution labels and marking. | After initial installation and every 12 months thereafter |

of supply without the approval of the Authority Having Jurisdiction, Health Department, or other department having jurisdiction.

K 102.2 Connections to Public or Private Potable Water Systems. Potable rainwater catchment systems shall have no direct connection to a public or private potable water supply or alternate water source system. Potable water from a public or private potable water system is permitted to be used as makeup water to the rainwater storage tank provided the public or private potable water supply connection is protected by an air gap or reduced-pressure principle backflow preventer in accordance with this code.

K 102.3 Backflow Prevention. The potable rainwater catchment system shall be protected against backflow in accordance with this code.

K 103.0 Potable Rainfall Catchment System Materials.

K 103.1 Collections Surfaces. The collection surface for potable applications shall be constructed of a hard, impervious material and shall be approved for potable water use. Roof coatings, paints, and liners shall comply with NSF Protocol P151.

K 103.1.1 Prohibited. Roof paints and coatings with lead, chromium, or zinc shall not be permitted. Wood roofing material and lead flashing shall not be permitted.

K 103.2 Rainwater Catchment System Drainage Materials. Materials used in rainwater catchment drainage

systems, including gutters, downspouts, conductors, and leaders shall be in accordance with the requirements of this code for storm drainage.

K 103.3 Storage Tanks. Rainwater storage shall comply with Section K 104.4.

K 103.4 Water Supply and Distribution Materials. Potable rainwater supply and distribution materials shall comply with the requirements of this code for potable water supply and distribution systems.

K 104.0 Design and Installation.

K 104.1 Collection Surfaces. Rainwater shall be collected from roof or other cleanable aboveground surfaces specifically designed for rainwater catchment. A rainwater catchment system shall not collect rainwater from:

- (1) Vehicular parking surfaces
- (2) Surface water runoff
- (3) Bodies of standing water

K 104.1.1 Prohibited Discharges. Overflows, condensate, and bleed-off pipes from roof-mounted equipment and appliances shall not discharge onto roof surfaces that are intended to collect rainwater.

K 104.2 Minimum Water Quality. Upon initial system startup, the quality of the water for the intended application shall be verified at the point(s) of use as determined by the Authority Having Jurisdiction. In the absence of water quality requirements determined by the Authority Having Jurisdiction, the minimum water quality shall be in accordance with Table K 104.2(1).

Normal system maintenance will require system testing every 3 months. Systems shall comply with Table K 104.2(2).

TABLE K 104.2(1)
MINIMUM WATER QUALITY^{1,2}

| | |
|-----------------------------------|-------------------|
| Escherichia coli (fecal coliform) | 99.9 % reduction |
| Protozoan Cysts | 99.99 % reduction |
| Viruses | 99.99 % reduction |
| Turbidity | <0.3 NTU |

Notes:

¹ Upon failure of the fecal coliform test, the system shall be re-commissioned involving cleaning and retesting in accordance with Section K 104.2.

² One sample shall be analyzed for applications serving up to 1000 persons. Where the treated water shall serve 1000 - 2500 persons two samples shall be analyzed, and for 2501 - 3300 persons three samples shall be analyzed.

TABLE K 104.2(2)
MINIMUM SYSTEM MAINTENANCE REQUIREMENTS^{1,2}

| | |
|-----------------------------------|------------------|
| Escherichia coli (fecal coliform) | 99.9 % reduction |
| Turbidity | <0.3 NTU |

Notes:

¹ Upon failure of the fecal coliform test, the system shall be re-commissioned involving cleaning and retesting in accordance with Section K 104.2.

² One sample shall be analyzed for applications serving up to 1000 persons. Where the treated water shall serve 1000 - 2500 persons two samples shall be analyzed, and for 2501 - 3300 persons three samples shall be analyzed.

K 104.2.1 Filtration Devices. Potable water filters shall comply with NSF 53 and shall be installed in accordance with the manufacturer's installation instructions.

K 104.2.2 Disinfection Devices. Chlorination, ozone, ultraviolet, or other disinfection methods approved by the Authority Having Jurisdiction, or the product is listed and certified according to a microbiological reduction performance standard for drinking water, shall be used to treat harvested rainwater to meet the required water quality permitted. The disinfection devices and systems shall be installed in accordance with the manufacturers installation instructions and the conditions of listing. Disinfection devices and systems shall be located downstream of the storage tank.

K 104.3 Overhanging Tree Branches and Vegetation. Tree branches and vegetation shall not be located over the roof or other aboveground rainwater collection surface. Where existing tree branch and vegetation growth extends over the rainwater collection surface, it shall be removed in accordance with Section K 101.5.

K 104.4 Rainwater Storage Tanks. Rainwater storage tanks shall be installed in accordance with Section K 104.4.1 through Section K 104.4.7.

K 104.4.1 Construction. Rainwater storage tanks shall be constructed of solid, durable materials not subject to excessive corrosion or decay and shall be watertight. Storage tanks shall be approved by the Authority Having Jurisdiction for potable water applications, provided such tanks are in accordance with approved applicable standards.

K 104.4.2 Location. Rainwater storage tanks shall be permitted to be installed above or below grade.

K 104.4.2.1 Above Grade. Above grade storage tanks shall be of an opaque material, approved for aboveground use in direct sunlight, or shall be shielded from direct sunlight. Tanks shall be installed in an accessible location to allow for inspection and cleaning. The tank shall be installed on a foundation or platform that is constructed to accommodate loads in accordance with the building code.

K 104.4.2.2 Below Grade. Rainwater storage tanks installed below grade shall be structurally designed to withstand anticipated earth or other loads. Holding tank covers shall be capable of supporting an earth load of not less than 300 pounds per square foot (lb/ft²) (1465 kg/m²) where the tank is designed for underground installation. Below grade rainwater tanks installed underground shall be provided with manholes. The manhole opening shall be not less than 20 inches (508 mm) in diameter and located not less than 4 inches (102 mm) above the surrounding grade. The surrounding grade shall be sloped away from the manhole. Underground tanks shall be ballasted, anchored, or otherwise secured, to prevent the tank from floating out of the ground where empty. The combined weight of the tank and hold down system shall meet or exceed the buoyancy force of the tank.

K 104.4.3 Drainage and Overflow. Rainwater storage tanks shall be provided with a means of draining and cleaning. The overflow drain shall not be equipped with a shutoff valve. The overflow outlet shall discharge in accordance with this code for storm drainage systems. Where discharging to the storm drainage system, the overflow drain shall be protected from backflow of the storm drainage system by a backwater valve or other approved method.

K 104.4.3.1 Overflow Outlet Size. The overflow outlet shall be sized to accommodate the flow of the rainwater entering the tank and not less than the aggregate cross-sectional area of the inflow pipes.

K 104.4.4 Opening and Access Protection.

K 104.4.4.1 Animals and Insects. Rainwater tank openings to the atmosphere shall be protected to prevent the entrance of insects, birds, or rodents into the tank.

» **K 104.4.4.2 Human Access.** Rainwater tank access openings exceeding 12 inches (305 mm) in diameter shall be secured to prevent tampering and unintended entry by either a lockable device or other approved method.

» **K 104.4.4.3 Exposure to Sunlight.** Rainwater tank openings shall not be exposed to direct sunlight.

» **K 104.4.5 Inlets.** A device or arrangement of fittings shall be installed at the inlet of the tank to prevent rainwater from disturbing sediment as it enters the tank.

» **K 104.4.6 Primary Tank Outlets.** The primary tank outlet shall be located not less than 4 inches (102 mm) above the bottom of the tank, or shall be provided with a floating inlet to draw water from the cistern just below the water surface.

K 104.4.7 Storage Tank Venting. Where venting by means of drainage or overflow piping is not provided, or is considered insufficient, a vent shall be installed on each tank. The vent shall extend from the top of the tank and terminate not less than 6 inches (152 mm) above grade and shall be not less than 1½ inches (40 mm) in diameter. The vent terminal shall be directed downward and covered with a ½ of an inch (2.4 mm) mesh screen to prevent the entry of vermin and insect.

K 104.5 Pumps. Pumps serving rainwater catchment systems shall be listed for potable water use. Pumps supplying water to water closets, urinals, and trap primers shall be capable of delivering not less than 15 pounds-force per square inch (psi) (103 kPa) residual pressure at the highest and most remote outlet served. Where the water pressure in the rainwater supply system within the building exceeds 80 psi (552 kPa), a pressure reducing valve reducing the pressure to 80 psi (552 kPa) or less to water outlets in the building shall be installed in accordance with this code.

K 104.6 Roof Drains. Primary and secondary roof drains, conductors, leaders, overflows, and gutters shall be designed and installed in accordance with this code.

K 104.7 Water Quality Devices and Equipment. Devices and equipment used to treat rainwater to maintain the minimum water quality requirements determined by the Authority Having Jurisdiction shall be listed or labeled (third-party certified) by a listing agency (accredited conformity assessment body) and approved for the intended application.

K 104.7.1 Filtration and Disinfection Systems. Filtration and disinfection systems shall be located after the water storage tank. Where a chlorination system is installed, it shall be installed upstream of filtration systems. Where an ultraviolet disinfection system is installed, a filter not more than 5 microns (5 µm) shall be installed upstream of the disinfection system.

K 104.8 Freeze Protection. Tanks and piping installed in locations subject to freezing shall be provided with an approved means of freeze protection.

K 104.9 Roof Washer or Pre-Filtration System. Collected rainwater shall pass through a roof washer or pre-filtration system before the water enters the rainwater storage tank. Roof washer systems shall comply with Section K 104.9.1 through Section K 104.9.4.

K 104.9.1 Size. The roof washer shall be sized to direct rainwater containing debris that has accumulated on the collection surface away from the storage tank. ARCSA/ASPE 63 contains additional guidance on acceptable methods of sizing roof washers.

K 104.9.2 Debris Screen. The inlet to the roof washer shall be provided with a debris screen or other approved means that protects the roof washer from the intrusion of debris and vermin. Where the debris screen is installed, the debris screen shall be corrosion resistant and shall have openings not larger than ½ of an inch (12.7 mm).

K 104.9.3 Drain Discharge. Water drained from the roof washer or pre-filter shall be diverted away from the storage tank and discharged to a disposal area that does not cause property damage or erosion. Roof washer drainage shall not drain over a public way.

K 104.9.4 Automatic Drain. Roof washing systems shall be provided with an automatic means of self draining between rain events.

K 104.10 Filtration and Disinfection Systems. Filtration and disinfection systems shall be located after the water storage tank. Where a chlorination system is installed, it shall be installed upstream of filtration systems. Where an ultraviolet disinfection system is installed, a filter not more than 5 microns (5 µm) shall be installed upstream of the disinfection system.

K 104.11 Roof Gutters. Gutters shall maintain a minimum slope and be sized in accordance with this code.

K 104.12 Drains, Conductors, and Leaders. The design and size of rainwater drains, conductors, and leaders shall comply with this code.

K 104.13 Size of Potable Water Piping. Potable rainwater system distribution piping shall be sized in accordance with this code for sizing potable water piping.

K 105.0 Cleaning.

K 105.1 General. The interior surfaces of tanks and equipment shall be clean before they are put into service.

K 106.0 Supply System Inspection and Test.

K 106.1 General. Rainwater catchment systems shall be inspected and tested in accordance with the applicable provisions of this code for testing of potable water and storm

drainage systems. Storage tanks shall be filled with water to the overflow opening for a period of 24 hours, and during inspection, or by other means as approved by the Authority Having Jurisdiction. Seams and joints shall be exposed during inspection and checked for water tightness.

APPENDIX L

SUSTAINABLE PRACTICES

L 101.0 General.

L 101.1 Applicability. The purpose of this appendix is to provide a comprehensive set of technically sound provisions that encourage sustainable practices and works towards enhancing the design and construction of plumbing systems that result in a positive long-term environmental impact. This appendix is not intended to circumvent the health, safety, and general welfare requirements of this code.

L 101.2 Definition of Terms. For the purposes of this code, the definitions in Section L 201.0 shall apply to this appendix.

No attempt is made to define ordinary words, which are used in accordance with their established dictionary meanings, except where a word has been used loosely and it is necessary to define its meaning as used in this appendix to avoid misunderstanding.

The definitions of terms are arranged alphabetically according to the first word of the term.

L 201.0 Definitions.

Catch Can Test. Method to measure the precipitation rate of an irrigation system by placing catchment containers at various random positions in the irrigation zone for a prescribed amount of time during irrigation application. The volumes of water in the containers are measured, averaged, and calculated to determine precipitation rate. Tests are conducted using irrigation industry accepted practices.

Combination Ovens. A device that combines the function of hot air convection (oven mode) and saturated and superheated steam heating (steam mode), or both, to perform steaming, baking, roasting, rethermalizing, and proofing of various food products. In general, the term combination oven is used to describe this type of equipment, which is self contained. The combination oven is also referred to as a combination oven/steamer, combi or combo.

Energy Star. A joint program of the U.S. Environmental Protection Agency and the U.S. Department of Energy. Energy Star is a voluntary program designed to identify and promote energy-efficient products and practices.

Evapotranspiration (ET). The combination of water transpired from vegetation and evaporated from the soil, water, and plant surfaces. Evapotranspiration rates are expressed in inches (mm) per day, week, month, or year. Evapotranspiration varies by climate and time of year. Common usage includes evapotranspiration as the base rate [water demand of 4 - 6 inch (102 mm - 152 mm) tall cool season grass], with coefficients for specific plant types. Evapotranspiration rates are used as a factor in estimating

the irrigation water needs of landscapes. Local agriculture extension, state departments of agriculture, water agencies, irrigation professionals, and internet websites are common sources for obtaining local evapotranspiration rates.

Food Steamers (Steam Cookers). A cooking appliance wherein heat is imparted to food in a closed compartment by direct contact with steam. The compartment can be at or above atmospheric pressure. The steam can be static or circulated.

Gang Showers (Non-Residential). Shower compartments designed and intended for use by multiple persons simultaneously in non-residential occupancies.

Hydrozone. A grouping of plants with similar water requirements that are irrigated by the same irrigation zone.

Irrigation Emission Device. The various landscape irrigation equipment terminal fittings or outlets that emit water for irrigating vegetation in a landscape.

Irrigation Zone. The landscape area that is irrigated by a set of landscape irrigation emission devices installed on the same water supply line downstream of a single valve.

Kitchen and Bar Sink Faucets. A faucet that discharges into a kitchen or bar sink in domestic or commercial installations. Supply fittings that discharge into other type sinks, including clinical sinks, floor sinks, service sinks and laundry trays are not included.

Lavatory. (1) A basin or vessel for washing. (2) A plumbing fixture, as defined in (1), especially placed for use in personal hygiene. Principally not used for laundry purposes and never used for food preparation, or utensils, in food services. (3) A fixture designed for the washing of the hands and face. Sometimes called a wash basin.

Lavatory Faucet. A faucet that discharges into a lavatory basin in a domestic or commercial installation.

Low Application Rate Irrigation. A means of irrigation using low precipitation rate sprinkler heads or low flow emitters in conjunction with cycling irrigation schedules to apply water at a rate less than the soil absorption rate.

Low Flow Emitter. Low flow irrigation emission device designed to dissipate water pressure and discharge a small uniform flow or trickle of water at a constant flow rate. To be classified as a low flow emitter: drip emitters shall discharge water at less than 4 gallons (15 L) per hour per emitter; micro-spray, micro-jet and misters shall discharge water at a maximum of 30 gallons (114 L) per hour per nozzle.

Low Precipitation Rate Sprinkler Heads. Landscape irrigation emission devices or sprinkler heads with maximum precipitation rate of 1 inch per hour (25.4 mm/h) over the applied irrigation area.

Maintenance. The upkeep of property or equipment by the owner of the property in compliance with the requirements of this appendix.

Metering Faucet. A self-closing faucet that dispenses a specific volume of water for each actuation cycle. The volume or cycle duration can be fixed or adjustable.

Multi-Occupant Spaces. Indoor spaces used for presentations and training, including classrooms and conference rooms.

Precipitation Rate. The sprinkler head application rate of water applied to landscape irrigation zone, measured as inches per hour (mm/h). Precipitation rates of sprinkler heads are calculated according to the flow rate, pattern, and spacing of the sprinkler heads.

Pre-Rinse Spray Valve. A handheld device for use with commercial dishwashing and ware washing equipment that sprays water on dishes, flatware, and other food service items for the purpose of removing food residue before cleaning and sanitizing the items.

Recirculation System. A system of hot water supply and return piping with shutoff valves, balancing valves, circulating pumps, and a method of controlling the circulating system.

Run Out. The developed length of pipe that extends away from the circulating loop system to a fixture(s).

Self Closing Faucet. A faucet that closes itself after the actuation or control mechanism is deactivated. The actuation or control mechanism can be mechanical or electronic.

Single Occupant Spaces. Private offices, workstations in open offices, reception workstations, and ticket booths.

Soil Absorption Rate. The rate of the soil's ability to allow water to percolate or infiltrate the soil and be retained in the root zone of the soil, expressed as inches per hour (mm/h).

Sprinkler Head. Landscape irrigation emission device discharging water in the form of sprays or rotating streams, not including low flow emitters.

Storage Tank. The central component of the rainwater, stormwater, or dry weather runoff catchment system. Also known as a cistern or rain barrel.

Stormwater. Natural precipitation that has contacted a surface at grade or below grade and has not been put to beneficial use.

Stormwater Catchment System. A system that collects and stores stormwater for a beneficial use.

Submeter. A meter installed subordinate to a site meter. Also known as a dedicated meter.

WaterSense. A voluntary program of the U.S. Environmental Protection Agency designed to identify and promote water-efficient products and practices.

Water Closet. A fixture with a water-containing receptor that receives liquid and solid body waste and on actuation conveys the waste through an exposed integral trap into a drainage system. Also referred to as a toilet.

Water Factor (WF). A measurement and rating of appliance water efficiency, most often used for residential and light commercial clothes washers, as follows:

Water Factor (WF), Clothes Washer. The quantity of water in gallons used to complete a full wash and rinse cycle per measured cubic foot capacity of the clothes container.

L 301.0 General Regulations.

L 301.1 Installation. Plumbing systems covered by this appendix shall be installed in accordance with this code, other applicable codes, and the manufacturer's installation instructions.

L 301.2 Qualifications. Where permits are required, the Authority Having Jurisdiction shall have the authority to require contractors, installers, or service technicians to demonstrate competency. Where determined by the Authority Having Jurisdiction, the contractor, installer or service technician shall be licensed to perform such work.

L 302.0 Disposal of Liquid Waste.

L 302.1 Disposal. It shall be unlawful for a person to cause, suffer, or permit the disposal of sewage, human excrement, or other liquid wastes, in a place or manner, except through and by means of an approved drainage system, installed and maintained in accordance with the provisions of this code.

L 302.2 Connections to Plumbing System Required. Equipment and appliances, used to receive or discharge liquid wastes or sewage, shall be connected properly to the drainage system of the building or premises, in accordance with the requirements of this code.

L 303.0 Abandonment.

L 303.1 General. An abandoned system or part thereof covered under the scope of this appendix shall be disconnected from remaining systems, drained, plugged, and capped in an approved manner.

L 401.0 Water Conservation and Efficiency.

L 401.1 Scope. The provisions of this section establish the means of conserving potable and nonpotable water used in and around a building.

L 402.0 Water-Conserving Plumbing Fixtures and Fittings.

L 402.1 General. The maximum water consumption of fixtures and fixture fittings shall comply with the flow rates specified in Table L 402.1, and Section L 402.2 through Section L 402.9.

L 402.2 Water Closets. No water closet shall have a flush volume exceeding 1.6 gallons per flush (gpf) (6.0 Lpf).

L 402.2.1 Gravity, Pressure Assisted, and Electro-Hydraulic Tank Type Water Closets.

Gravity, pressure assisted, and electro-hydraulic tank type water closets shall have a maximum effective flush volume of not more than 1.28 gallons (4.8 Lpf) of water per flush in accordance with ASME A112.19.2/CSA B45.1 or ASME A112.19.14 and shall be listed to the EPA WaterSense Tank-Type Toilet

**TABLE L 402.1
MAXIMUM FIXTURE AND FIXTURE FITTINGS FLOW RATES**

| FIXTURE TYPE | FLOW RATE |
|--|---|
| Showerheads | 2.0 gpm at 80 psi ¹ |
| Kitchen faucets residential ⁵ | 1.8 gpm at 60 psi |
| Lavatory faucets residential | 1.5 gpm at 60 psi |
| Lavatory faucets other than residential | 0.5 gpm at 60 psi |
| Metering faucets | 0.25 gallons/cycle |
| Metering faucets for wash fountains | One 0.25 gallons/cycle fixture fitting for each 20 inches rim space |
| Wash fountains | One 2.2 gpm at 60 psi fixture fitting for each 20 inches rim space |
| Water Closets - other than remote locations ⁴ | 1.28 gallons/flush ² |
| Water Closets - remote locations ⁴ | 1.6 gallons/flush |
| Urinals | 0.5 gallons/flush ³ |
| Commercial Pre-Rinse Spray Valves | 1.3 gpm at 60 psi |

For SI units: 1 gallon per minute = 0.06 L/s, 1 pound-force per square inch = 6.8947 kPa, 1 inch = 25.4 mm, 1 gallon = 3.785 L

Notes:

¹ For multiple showerheads serving one shower compartment see Section L 402.6.1.

² Shall be listed to EPA WaterSense Tank-Type Toilet Specification.

³ Shall be listed to EPA WaterSense Flushing Urinal Specification. Nonwater urinals shall comply with specifications listed in Section L 402.3.1.

⁴ Remote location is where a water closet is located not less than 30 feet (9144 mm) upstream of the nearest drain line connections or fixtures, and is located where less than 1.5 drainage fixture units are upstream of the water closet drain line connection.

⁵ See Section L 402.4.

Specification. The effective flush volume for dual flush toilets is defined as the composite, average flush volume of two reduced flushes and one full flush.

L 402.2.2 Flushometer-Valve Activated Water Closets. Flushometer-valve activated water closets shall have a maximum flush volume of not more than 1.6 gallons (6.0 Lpf) of water per flush in accordance with ASME A112.19.2/CSA B45.1.

L 402.3 Urinals. Urinals shall have a maximum flush volume of not more than 0.5 gallon (1.9 Lpf) of water per flush in accordance with ASME A112.19.2/CSA B45.1 or CSA B45.5/IAPMO Z124. Flushing urinals shall be listed to the EPA WaterSense Flushing Urinal Specification.

L 402.3.1 Nonwater Urinals. Nonwater urinals shall comply with ASME A112.19.3/CSA B45.4, ASME A112.19.19, or CSA B45.5/IAPMO Z124. Nonwater urinals shall be cleaned and maintained in accordance with the manufacturer's instructions after installation. Where nonwater urinals are installed they shall have a water distribution line roughed-in to the urinal location at a height not less than 56 inches (1422 mm) to allow for the installation of an approved backflow prevention device in the event of a retrofit. Such water distribution lines shall be installed with shutoff valves located as close as possible to the distributing main to prevent the creation of dead ends. Where nonwater urinals are installed, not less than one water supplied fixture rated at not less than 1 water supply fixture unit (WSFU) shall be installed upstream on the same drain line to facilitate drain line flow and rinsing.

L 402.4 Residential Kitchen Faucets. The maximum flow rate of residential kitchen faucets shall not exceed 1.8 gallons per minute (gpm) (6.8 L/m) at 60 pounds-force per square inch (psi) (414 kPa). Kitchen faucets are permitted to temporarily increase the flow above the maximum rate, but not to exceed 2.2 gpm (8.3 L/m) at 60 psi (414 kPa), and shall revert to a maximum flow rate of 1.8 gpm (6.8 L/m) at 60 psi (414 kPa) upon valve closure.

L 402.5 Lavatory Faucets. The maximum water flow rate of faucets shall comply with Section L 402.5.1 and Section L 402.5.2. <<

L 402.5.1 Lavatory Faucets in Residences, Apartments, and Private Bathrooms in Lodging Facilities, Hospitals, and Patient Care Facilities. <<

The flow rate for lavatory faucets installed in residences, apartments, and private bathrooms in lodging, hospitals, and patient care facilities (including skilled nursing and long-term care facilities) shall not exceed 1.5 gpm (5.7 L/m) at 60 psi (414 kPa) in accordance with ASME A112.18.1/CSA B125.1 and shall be listed to the EPA WaterSense High Efficiency Lavatory Faucet Specification.

L 402.5.2 Lavatory Faucets in Other Than Residences, Apartments, and Private Bathrooms in Lodging Facilities. Lavatory faucets installed in bathrooms of buildings or occupancies other than those specified in Section L 402.5.1 shall be in accordance with Section L 402.5.2.1 or Section L 402.5.2.2. <<

» **L 402.5.2.1 Maximum Flow Rate.** The flow rate shall not exceed 0.5 gpm (1.9 L/m) at 60 psi (414 kPa) in accordance with ASME A112.18.1/CSA B125.1.

» **L 402.5.2.2 Metering Faucets.** Metering faucets shall deliver not more than 0.25 gallons (1.0 L) of water per cycle.

» **L 402.6 Showerheads.** Showerheads shall comply with the requirements of the Energy Policy Act of 1992, except that the flow rate shall not exceed 2.0 gpm (7.6 L/m) at 80 psi (552 kPa), where listed to ASME A112.18.1/CSA B125.1.

» **L 402.6.1 Multiple Showerheads Serving One Shower Compartment.** The total allowable flow rate of water from multiple showerheads flowing at a given time, with or without a diverter, including rain systems, waterfalls, bodysprays, and jets, shall not exceed 2.0 gpm (7.6 L/m) per shower compartment, where the floor area of the shower compartment is less than 1800 square inches (1.161 m²). For each increment of 1800 square inches (1.161 m²) of floor area thereafter or part thereof, additional showerheads are allowed, provided the total flow rate of water from flowing devices shall not exceed 2.0 gpm (7.6 L/m) for each such increment.

Exceptions:

- (1) Gang showers in non-residential occupancies. Singular showerheads or multiple shower outlets serving one showering position in gang showers shall not have more than 2.0 gpm (7.6 L/m) total flow.
- (2) Where provided, accessible shower compartments shall not be permitted to have more than 4.0 gpm (15 L/m) total flow, where one outlet is the hand shower. The hand shower shall have a control with a nonpositive shutoff feature.

L 402.6.2 Bath and Shower Diverters. The rate of leakage out of the tub spout of bath and shower diverters while operating in the shower mode shall not exceed 0.1 gpm (0.4 L/m) in accordance with ASME A112.18.1/CSA B125.1.

L 402.6.3 Shower Valves. Shower valves shall comply with the temperature control performance requirements of ASSE 1016 or ASME A112.18.1/CSA B125.1 where tested at 2.0 gpm (7.6 L/m).

L 402.7 Commercial Pre-Rinse Spray Valves. The flow rate for a pre-rinse spray valve installed in a commercial kitchen to remove food waste from cookware and dishes prior to cleaning shall not be more than 1.3 gpm (4.9 L/m) at 60 psi (414 kPa). Where pre-rinse spray valves with maximum flow rates of 1.0 gpm (3.8 L/m) or less are installed, the static pressure shall be not less than 30 psi (207 kPa). Commercial kitchen pre-rinse spray valves shall be equipped with an integral automatic shutoff.

L 402.8 Emergency Safety Showers and Eye Wash Stations. Emergency safety showers and emergency eye wash stations shall not be limited in their water supply flow rates.

L 402.9 Drinking Fountains. Drinking fountains shall be self-closing.

L 403.0 Appliances.

L 403.1 Dishwashers. Residential and commercial dishwashers shall comply with the Energy Star program requirements.

L 403.2 Clothes Washers. Residential clothes washers shall comply with the Energy Star program requirements. Commercial clothes washers shall comply with Energy Star program requirements, where such requirements exist.

L 404.0 Occupancy Specific Water Efficiency Requirements.

L 404.1 Commercial Food Service. Commercial food service facilities shall comply with the water efficiency requirements in Section L 404.2 through Section L 404.6.

L 404.2 Ice Makers. Ice makers shall be air cooled and shall be in accordance with Energy Star for commercial ice machines.

L 404.3 Food Steamers. Steamers shall consume not more than 5.0 gallons (19 L) per hour per steamer pan in the full operational mode.

L 404.4 Combination Ovens. Combination ovens shall not consume more than 3.5 gallons per hour (gph) (13.2 L/h) per pan in the full operational mode.

L 404.5 Grease Interceptors. Grease interceptor maintenance procedures shall not include post-pumping/cleaning refill using potable water. Refill shall be by connected appliance accumulated discharge only.

L 404.6 Dipper Well Faucets. Where dipper wells are installed, the water supply to a dipper well shall have a shutoff valve and flow control. The flow of water into a dipper well shall be limited by not less than one of the following methods:

- (1) Water flow shall not exceed the water capacity of the dipper well in one minute at supply pressure of 60 psi (414 kPa), and the maximum flow shall not exceed 2.2 gpm (8.3 L/m) at a supply pressure of 60 psi (414 kPa). The water capacity of a dipper well shall be the maximum amount of water that the fixture can hold before water flows into the drain.
- (2) The volume of water dispensed into a dipper well in each activation cycle of a self closing fixture fitting shall not exceed the water capacity of the dipper well, and the maximum flow shall not exceed 2.2 gpm (8.3 L/m) at a supply pressure of 60 psi (414 kPa).

L 404.7 Medical and Laboratory Facilities. Medical and laboratory facilities shall comply with the water efficiency requirements in Section L 404.8 through Section L 404.10.

L 404.8 Steam Sterilizers. Controls shall be installed to limit the discharge temperature of condensate or water from steam sterilizers to 140°F (60°C) or less. A venturi-type vacuum system shall not be utilized with vacuum sterilizers.

L 404.9 X-Ray Film Processing Units. Processors for X-ray film exceeding 6 inches (152 mm) in any dimension shall be equipped with water recycling units.

L 404.10 Exhaust Hood Liquid Scrubber Systems. Liquid scrubber systems for exhaust hoods and ducts shall be of the recirculation type. Liquid scrubber systems for perchloric acid exhaust hoods and ducts shall be equipped with a timer-controlled water recirculation system. The collection sump for perchloric acid exhaust systems shall be designed to automatically drain after the wash down process has completed.

L 405.0 Leak Detection and Control.

L 405.1 General. Where installed, leak detection and control devices shall be approved by the Authority Having Jurisdiction. Leak detection and control devices help protect property from water damage and also conserve water by shutting off the flow when leaks are detected.

»» L 406.0 Fountains and Other Water Features.

»» L 406.1 Use of Alternate Water Source for Special Water Features. Special water features such as ponds and water fountains shall be provided with reclaimed (recycled) water, rainwater, or on-site treated nonpotable water where the source and capacity is available on the premises and approved by the Authority Having Jurisdiction.

»» L 407.0 Meters.

»» L 407.1 Required. A water meter shall be required for buildings connected to a public water system, including municipally supplied reclaimed (recycled) water. In other than single-family houses, multi-family structures of three stories or fewer above grade, and modular houses, a separate meter or submeter shall be installed in the following locations:

- (1) The water supply for irrigated landscape with an accumulative area exceeding 2500 square feet (232.3 m²).
- (2) The water supply to a water-using process where the consumption exceeds 1000 gallons per day (gal/d) (0.0438 L/s), except for manufacturing processes.
- (3) The water supply to each building on a property with multiple buildings where the water consumption exceeds 500 gal/d (0.021 L/s).
- (4) The water supply to an individual tenant space on a property where one or more of the following applies:
 - (a) Water consumption exceeds 500 gal/d (0.021 L/s) for that tenant.
 - (b) Tenant space is occupied by a commercial laundry, cleaning operation, restaurant, food service, medical office, dental office, laboratory, beauty salon, or barbershop.
 - (c) Total building area exceeds 50 000 square feet (4645 m²).
- (5) A makeup water supply to a swimming pool.

L 407.2 Consumption Data. A means of communicating water consumption data from submeters to the water consumer shall be provided. <<

L 407.3 Access. Meters and submeters shall be accessible. <<

L 408.0 Condensate Recovery.

L 408.1 General. Condensate is permitted to be used as on-site treated non-potable water when collected, stored, and treated in accordance with Section 1504.0.

L 409.0 Water-Powered Sump Pumps.

L 409.1 General. Sump pumps powered by potable or reclaimed (recycled) water pressure shall be used as an emergency backup pump. The water-powered pump shall be equipped with a battery powered alarm having a minimum rating of 85 dBA at 10 feet (3048 mm). Water-powered pumps shall have a water efficiency factor of pumping at least 1.4 gallons (5.3 L) of water to a height of 10 feet (3048 mm) for every gallon of water used to operate the pump, measured at a water pressure of 60 psi (414 kPa). Pumps shall be clearly labeled as to the gallons of water pumped per gallon of potable water consumed. <<

Water-powered stormwater sump pumps shall be equipped with a reduced pressure principle backflow prevention assembly.

L 410.0 Water Softeners and Treatment Devices.

L 410.1 Water Softeners. Actuation of regeneration of water softeners shall be by demand initiation. Water softeners shall be listed to NSF 44. Water softeners shall have a rated salt efficiency exceeding 3400 grains (gr) (0.2199 kg) of total hardness exchange per pound (0.5 kg) of salt, based on sodium chloride (NaCl) equivalency, and shall not generate more than 5 gallons (19 L) of water per 1000 grains (0.0647 kg) of hardness removed during the service cycle.

L 410.2 Water Softener Limitations. In residential buildings, where the supplied potable water hardness is equal to or less than 8 grains per gallon (gr/gal) (137 mg/L) measured as total calcium carbonate equivalents, water softening equipment that discharges water into the wastewater system during the service cycle shall not be allowed, except as required for medical purposes.

L 410.3 Point-of-Use Reverse Osmosis Water Treatment Systems. Reverse osmosis water treatment systems installed in residential occupancies shall be equipped with automatic shutoff valves to prevent discharge when there is no call for producing treated water. Reverse osmosis water treatment systems shall be listed in accordance with NSF 58.

L 411.0 Landscape Irrigation Systems.

L 411.1 General. Where landscape irrigation systems are installed, they shall use low application irrigation methods

and shall be in accordance with Section L 411.2 through Section L 411.12. Requirements limiting the amount or type of plant material used in landscapes shall be established by the Authority Having Jurisdiction.

Exception: Plants grown for food production.

L 411.2 Backflow Protection. Potable water and supplies to landscape irrigation systems shall be protected from backflow in accordance with this code and the Authority Having Jurisdiction.

L 411.3 Use of Alternate Water Sources for Landscape Irrigation. Where available by pre-existing treatment, storage, or distribution network, and where approved by the Authority Having Jurisdiction, alternative water source(s) shall be utilized for landscape irrigation. Where adequate capacity and volumes of pre-existing alternative water sources are available, the irrigation system shall be designed to use a minimum of 75 percent of alternative water for the annual irrigation demand before supplemental potable water is used.

L 411.4 Irrigation Control Systems. Where installed as part of a landscape irrigation system, irrigation control systems shall:

- (1) Automatically adjust the irrigation schedule to respond to plant water needs determined by weather or soil moisture conditions.
- (2) Utilize sensors to suspend irrigation during a rainfall.
- (3) Utilize sensors to suspend irrigation where adequate soil moisture is present for plant growth.
- (4) Have the capability to program multiple and different run times for each irrigation zone to enable cycling of water applications and durations to mitigate water flowing off of the intended irrigation zone.
- (5) The site specific settings of the irrigation control system affecting the irrigation and shall be posted at the control system location. The posted data, where applicable to the settings of the controller, shall include:
 - (a) Precipitation rate for each zone.
 - (b) Plant evapotranspiration coefficients for each zone.
 - (c) Soil absorption rate for each zone.
 - (d) Rain sensor settings.
 - (e) Soil moisture setting.
 - (f) Peak demand schedule including run times for each zone and the number of cycles to mitigate runoff and monthly adjustments or percentage.

L 411.5 Low Flow Irrigation. Irrigation zones using low flow irrigation shall be equipped with filters sized for the irrigation emission devices, and with a pressure regulator installed upstream of the irrigation emission devices as necessary to reduce the operating water pressure in accordance with the manufacturers' equipment requirements.

L 411.6 Mulched Planting Areas. Only low volume emitters are allowed to be installed in mulched planting areas with vegetation taller than 12 inches (305 mm).

L 411.7 System Performance Requirements. The landscape irrigation system shall be designed and installed to:

- (1) Prevent irrigation water from runoff out of the irrigation zone.
- (2) Prevent water in the supply-line drainage from draining out between irrigation events.
- (3) Not allow irrigation water to be applied onto or enter non-targeted areas including: adjacent property and vegetation areas, adjacent hydrozones not requiring the irrigation water to meet its irrigation demand, non-vegetative areas, impermeable surfaces, roadways, and structures.

L 411.8 Narrow or Irregularly Shaped Landscape Areas. Narrow or irregularly shaped landscape areas, less than 4 feet (1219 mm) in any direction across opposing boundaries, shall not be irrigated by an irrigation emission device except low flow emitters.

L 411.9 Sloped Areas. Where soil surface rises more than 1 foot (305 mm) per 4 feet (1219 mm) of length, the irrigation zone system average precipitation rate shall not exceed 0.75 inches (19 mm) per hour as verified through either of the following methods:

- (1) Manufacturer documentation that the precipitation rate for the installed sprinkler head does not exceed 0.75 inches (19 mm) per hour where the sprinkler heads are installed not closer than the specified radius and where the water pressure of the irrigation system is not more than the manufacturer's recommendations.
- (2) Catch can testing in accordance with the requirements of the Authority Having Jurisdiction and where emitted water volume is measured with a minimum of six catchment containers at random places within the irrigation zone for a minimum of 15 minutes to determine the average precipitation rate, expressed as inches per hour (mm/h).

L 411.10 Sprinkler Head Installations. Installed sprinkler heads shall be low precipitation rate sprinkler heads.

L 411.10.1 Sprinkler Heads in Common Irrigation Zones. Sprinkler heads installed in irrigation zones served by a common valve shall be limited to applying water to plants with similar irrigation needs, and shall have matched precipitation rates (identical inches of water application per hour as rated or tested, plus or minus 5 percent).

L 411.10.2 Sprinkler Head Pressure Regulation. Sprinkler heads shall utilize pressure regulating devices (as part of an irrigation system or integral to the sprinkler head) to maintain manufacturer's recommended operating pressure for each sprinkler and nozzle type.

L 411.10.3 Pop-up Type Sprinkler Heads. Where pop-up type sprinkler heads are installed, the sprinkler heads shall rise to a height of not less than 4 inches (102 mm) above the soil level where emitting water.

L 411.11 Irrigation Zone Performance Criteria. Irrigation zones shall be designed and installed to ensure the average precipitation rate of the sprinkler heads over the irrigated area does not exceed 1 inch per hour (25.4 mm/h) as verified through either of the following methods:

- (1) Manufacturer's documentation that the precipitation rate for the installed sprinkler head does not exceed 1 inch per hour (25.4 mm/h) where the sprinkler heads are installed not closer than the specified radius and where the water pressure of the irrigation system is not more than the manufacturer's recommendations.
- (2) Catch can testing in accordance with the requirements of the Authority Having Jurisdiction and where emitted water volume is measured with a minimum of six catchment containers at random places within the irrigation zone for a minimum of 15 minutes to determine the average precipitation rate, expressed as inches per hour (mm/h).

L 411.12 Qualifications. The Authority Having Jurisdiction shall have the authority to require landscape irrigation contractors, installers, or designers to demonstrate competency. Where required by the Authority Having Jurisdiction, the contractor, installer, or designer shall be certified to perform such work.

L 412.0 Trap Seal Protection.

L 412.1 Water Supplied Trap Primers. Water supplied trap primers shall be electronic or pressure activated and shall use not more than 30 gallons (114 L) per year per drain. Where an alternate water source, as defined by this code, is used for fixture flushing or other uses in the same room, the alternate water source shall be used for the trap primer water supply.

Exception: Flushometer tailpiece trap primers in accordance with IAPMO PS 76.

L 412.2 Drainage Type Trap Seal Primer Devices. Drainage type trap seal primer devices shall not be limited in the amount of water they discharge.

L 413.0 Vehicle Wash Facilities.

L 413.1 General. The maximum make-up water use for automobile washing shall not exceed 40 gallons (151 L) per vehicle for in-bay automatic car washes and 35 gallons (132 L) for conveyor and express type car washes. Spray wands and foamy brushes shall use not more than 3.0 gpm (0.19 L/s). Spot-free reverse osmosis discharge (reject) water shall be recycled. Towel ringers shall have a positive shutoff valve. Spray nozzles shall be replaced annually.

Exception: Bus and large commercial vehicle washes.

L 501.0 Alternate Water Sources.

L 501.1 Scope. The provisions of this appendix shall apply to the installation, construction, alteration, and repair of potable rainwater catchment systems. Alternate water source systems for nonpotable applications shall comply with Chapter 15.

L 501.2 System Design. Potable rainwater catchment systems in accordance with this appendix shall be designed by a registered design professional or person deemed com-

petent by the Authority Having Jurisdiction to perform potable rainwater catchment system design work.

L 501.3 Permit. It shall be unlawful for a person to construct, install, or alter, or cause to be constructed, installed, or altered potable rainwater catchment systems in a building or on a premise without first obtaining a permit to do such work from the Authority Having Jurisdiction.

L 501.3.1 Plumbing Plan Submission. No permit shall be issued until complete plumbing plans, with data satisfactory to the Authority Having Jurisdiction, have been submitted and approved. No changes or connections shall be made to either the rainfall catchment or the potable water system within a site containing a rainwater catchment water system without approval by the Authority Having Jurisdiction.

L 501.3.2 System Changes. No changes or connections shall be made to either the rainwater catchment system or the potable water system within a site containing a rainwater catchment system requiring a permit without approval by the Authority Having Jurisdiction.

L 501.4 Product and Material Approval. System components shall be identified as to the manufacturer.

L 501.4.1 Plumbing Materials and Systems. Pipe, pipe fittings, traps, fixtures, material, and devices used in a potable rainwater system shall be listed or labeled (third-party certified) by a listing agency (accredited conformity assessment body) and shall be in accordance with approved applicable recognized standards referenced in this appendix and this code, and shall be free from defects. Unless otherwise provided for in this appendix, materials, fixtures, or devices used or entering into the construction of plumbing systems, or parts thereof, shall be submitted to the Authority Having Jurisdiction for approval.

L 501.5 Maintenance and Inspection. Potable rainwater catchment systems and components shall be inspected and maintained in accordance with Section L 501.5.1 through Section L 501.5.3.

L 501.5.1 Frequency. Potable rainwater catchment systems and components shall be inspected and maintained in accordance with Table L 501.5.1 unless more frequent inspection and maintenance is required by the manufacturer.

L 501.5.2 Maintenance Log. A maintenance log for potable rainwater catchment systems shall be maintained by the property owner and be available for inspection. The property owner or designated appointee shall ensure that a record of testing, inspection, and maintenance in accordance with Table L 501.5.1 is maintained in the log. The log will indicate the frequency of inspection, and maintenance for each system. A record of the required water quality tests shall be retained for not less than 2 years.

TABLE L 501.5.1
MINIMUM POTABLE RAINWATER CATCHMENT SYSTEM TESTING, INSPECTION, AND MAINTENANCE FREQUENCY

| DESCRIPTION | MINIMUM FREQUENCY |
|--|---|
| Inspect and clean filters and screens, and replace (where necessary). | Every 3 month |
| Inspect and verify that disinfection, filters and water quality treatment devices and systems are operational. Perform water quality tests in accordance with the Authority Having Jurisdiction. | In accordance with the manufacturer's instructions, and the Authority Having Jurisdiction. |
| Perform applicable water quality tests to verify compliance with Section L 504.2 | Every 3 months |
| Perform a water quality test for E. Coli, Total Coliform, and Heterotrophic bacteria. For a system where 25 different people consume water from the system over a 60 day period, a water quality test for cryptosporidium shall also be performed. | After initial installation and every 12 months thereafter, or as directed by the Authority Having Jurisdiction. |
| Inspect and clear debris from rainwater gutters, downspouts, and roof washers. | Every 6 months |
| Inspect and clear debris from roof or other aboveground rainwater collection surface. | Every 6 months |
| Remove tree branches and vegetation overhanging roof or other aboveground rainwater collection surface. | As needed |
| Inspect pumps and verify operation. | After initial installation and every 12 months thereafter |
| Inspect valves and verify operation. | After initial installation and every 12 months thereafter |
| Inspect pressure tanks and verify operation. | After initial installation and every 12 months thereafter |
| Clear debris and inspect storage tanks, locking devices, and verify operation. | After initial installation and every 12 months thereafter |
| Inspect caution labels and marking. | After initial installation and every 12 months thereafter |

L 501.5.3 Maintenance Responsibility. The required maintenance and inspection of potable rainwater catchment systems shall be the responsibility of the property owner, unless otherwise required by the Authority Having Jurisdiction.

L 501.6 Operation and Maintenance Manual. An operation and maintenance manual for potable rainwater catchment systems shall be supplied to the building owner by the system designer. The operating and maintenance manual shall include the following:

- (1) Detailed diagram of the entire system and the location of system components.
- (2) Instructions on operating and maintaining the system.
- (3) Details on maintaining the required water quality as determined by the Authority Having Jurisdiction.
- (4) Details on deactivating the system for maintenance, repair, or other purposes.
- (5) Applicable testing, inspection, and maintenance frequencies in accordance with Table L 501.5.1.
- (6) A method of contacting the manufacturer(s).

L 501.7 Minimum Water Quality Requirements. The minimum water quality for potable rainwater catchment systems shall comply with the applicable water quality requirements as determined by the public health Authority Having Jurisdiction.

L 501.8 Material Compatibility. In addition to the requirements of this appendix, potable rainwater catchment systems shall be constructed of materials that are compatible with the type of pipe and fitting materials and water conditions in the system.

L 501.9 System Controls. Controls for pumps, valves, and other devices that contain mercury that come in contact with the water supply shall not be permitted.

L 502.0 Connection.

L 502.1 General. No water piping supplied by a potable rainwater catchment system shall be connected to any other source of supply without the approval of the Authority Having Jurisdiction, Health Department, or other department having jurisdiction.

L 502.2 Connections to Public or Private Potable Water Systems. Potable rainwater catchment systems shall have no direct connection to a public or private potable water supply or alternate water source system. Potable water from a public or private potable water system is permitted to be used as makeup water to the rainwater storage tank provided the public or private potable water supply connection is protected by an air gap or reduced-pressure principle backflow preventer in accordance with this code.

L 502.3 Backflow Prevention. The potable rainwater catchment system shall be protected against backflow in accordance with this code.

L 503.0 Potable Rainfall Catchment System Materials.

L 503.1 Collections Surfaces. The collection surface for potable applications shall be constructed of a hard, impervious material and shall be approved for potable water

use. Roof coatings, paints, and liners shall comply with NSF Protocol P151.

L 503.1.1 Prohibited. Roof paints and coatings with lead, chromium, or zinc shall not be permitted. Wood roofing material and lead flashing shall not be permitted.

L 503.2 Rainwater Catchment System Drainage Materials. Materials used in rainwater catchment drainage systems, including gutters, downspouts, conductors, and leaders shall be in accordance with the requirements of this code for storm drainage.

L 503.3 Storage Tanks. Rainwater storage shall comply with Section L 504.4.

L 503.4 Water Supply and Distribution Materials. Potable rainwater supply and distribution materials shall comply with the requirements of this code for potable water supply and distribution systems.

L 504.0 Design and Installation.

L 504.1 Collection Surfaces. Rainwater shall be collected from roof or other cleanable aboveground surfaces specifically designed for rainwater catchment. A rainwater catchment system shall not collect rainwater from:

- (1) Vehicular parking surfaces
- (2) Surface water runoff
- (3) Bodies of standing water

L 504.1.1 Prohibited Discharges. Overflows, condensate, and bleed-off pipes from roof-mounted equipment and appliances shall not discharge onto roof surfaces that are intended to collect rainwater.

L 504.2 Minimum Water Quality. Upon initial system startup, the quality of the water for the intended application shall be verified at the point(s) of use as determined by the Authority Having Jurisdiction. In the absence of water quality requirements determined by the Authority Having Jurisdiction, the minimum water quality shall be in accordance with Table L 504.2(1).

Normal system maintenance will require system testing every 3 months. Systems shall comply with Table L 504.2(2).

TABLE L 504.2(1)
MINIMUM WATER QUALITY^{1,2}

| | |
|-----------------------------------|------------------|
| Escherichia coli (fecal coliform) | 99.9% reduction |
| Protozoan Cysts | 99.99% reduction |
| Viruses | 99.99% reduction |
| Turbidity | <0.3 NTU |

Notes:

- ¹ Upon failure of the fecal coliform test, the system shall be re-commissioned involving cleaning and retesting in accordance with Section L 504.2.
- ² One sample shall be analyzed for applications serving up to 1000 persons. Where the treated water shall serve 1000 - 2500 persons two samples shall be analyzed, and for 2501 - 3300 persons three samples shall be analyzed.

TABLE L 504.2(2)
MINIMUM SYSTEM MAINTENANCE REQUIREMENTS^{1,2}

| | |
|-----------------------------------|-----------------|
| Escherichia coli (fecal coliform) | 99.9% reduction |
| Turbidity | <0.3 NTU |

Notes:

- ¹ Upon failure of the fecal coliform test, the system shall be re-commissioned involving cleaning and retesting in accordance with Section L 504.2.
- ² One sample shall be analyzed for applications serving up to 1000 persons. Where the treated water shall serve 1000 - 2500 persons two samples shall be analyzed, and for 2501 - 3300 persons three samples shall be analyzed.

L 504.2.1 Filtration Devices. Potable water filters shall comply with NSF 53 and shall be installed in accordance with the manufacturer's installation instructions.

L 504.2.2 Disinfection Devices. Chlorination, ozone, ultraviolet, or other disinfection methods approved by an Authority Having Jurisdiction, or the product is listed and certified according to a microbiological reduction performance standard for drinking water, shall be used to treat harvested rainwater to meet the required water quality permitted. The disinfection devices and systems shall be installed in accordance with the manufacturer's installation instructions and the conditions of listing. Disinfection devices and systems shall be located downstream of the storage tank.

L 504.3 Overhanging Tree Branches and Vegetation. Tree branches and vegetation shall not be located over the roof or other aboveground rainwater collection surface. Where existing tree branch and vegetation growth extends over the rainwater collection surface, it shall be removed in accordance with Section L 501.5.

L 504.4 Rainwater Storage Tanks. Rainwater storage tanks shall be installed in accordance with Section L 504.4.1 through Section L 504.4.7.

L 504.4.1 Construction. Rainwater storage tanks shall be constructed of solid, durable materials not subject to excessive corrosion or decay and shall be watertight. Storage tanks shall be approved by the Authority Having Jurisdiction for potable water applications, provided such tanks are in accordance with approved applicable standards.

L 504.4.2 Location. Rainwater storage tanks shall be permitted to be installed above or below grade.

L 504.4.2.1 Above Grade. Above grade storage tanks shall be of an opaque material, approved for aboveground use in direct sunlight, or shall be shielded from direct sunlight. Tanks shall be installed in an accessible location to allow for inspection and cleaning. The tank shall be installed on a foundation or platform that is constructed to accommodate loads in accordance with the building code.

» **L 504.4.2.2 Below Grade.** Rainwater storage tanks installed below grade shall be structurally designed to withstand anticipated earth or other loads. Holding tank covers shall be capable of supporting an earth load of not less than 300 pounds per square foot (lb/ft²) (1465 kg/m²) where the tank is designed for underground installation. Below grade rainwater tanks installed underground shall be provided with manholes. The manhole opening shall be not less than 20 inches (508 mm) in diameter and located not less than 4 inches (102 mm) above the surrounding grade. The surrounding grade shall be sloped away from the manhole. Underground tanks shall be ballasted, anchored, or otherwise secured, to prevent the tank from floating out of the ground where empty. The combined weight of the tank and hold down system shall meet or exceed the buoyancy force of the tank.

» **L 504.4.3 Drainage and Overflow.** Rainwater storage tanks shall be provided with a means of draining and cleaning. The overflow drain shall not be equipped with a shutoff valve. The overflow outlet shall discharge in accordance with this code for storm drainage systems. Where discharging to the storm drainage system, the overflow drain shall be protected from backflow of the storm drainage system by a backwater valve or other approved method.

» **L 504.4.3.1 Overflow Outlet Size.** The overflow outlet shall be sized to accommodate the flow of the rainwater entering the tank and not less than the aggregate cross-sectional area of the inflow pipes.

» **L 504.4.4 Animals and Insects.** Rainwater tank openings to the atmosphere shall be protected to prevent the entrance of insects, birds, or rodents into the tank.

» **L 504.4.4.1 Human Access.** Rainwater tank access openings exceeding 12 inches (305 mm) in diameter shall be secured to prevent tampering and unintended entry by either a lockable device or other approved method.

» **L 504.4.4.2 Exposure to Sunlight.** Rainwater tank openings shall not be exposed to direct sunlight.

» **L 504.4.5 Inlets.** A device or arrangement of fittings shall be installed at the inlet of the tank to prevent rainwater from disturbing sediment as it enters the tank.

» **L 504.4.6 Primary Tank Outlets.** The primary tank outlet shall be located not less than 4 inches (102 mm) above the bottom of the tank, or shall be provided with a floating inlet to draw water from the cistern just below the water surface.

L 504.4.7 Storage Tank Venting. Where venting by means of drainage or overflow piping is not provided, or is considered insufficient, a vent shall be installed on each tank. The vent shall extend from the top of the tank and terminate not less than 6 inches (152 mm)

above grade and shall be not less than 1½ inches (40 mm) in diameter. The vent terminal shall be directed downward and covered with a ¾ of an inch (2.4 mm) mesh screen to prevent the entry of vermin and insects.

L 504.5 Pumps. Pumps serving rainwater catchment systems shall be listed for potable water use. Pumps supplying water to water closets, urinals, and trap primers shall be capable of delivering not less than 15 pounds-force per square inch (psi) (103 kPa) residual pressure at the highest and most remote outlet served. Where the water pressure in the rainwater supply system within the building exceeds 80 psi (552 kPa), a pressure reducing valve reducing the pressure to 80 psi (552 kPa) or less to water outlets in the building shall be installed in accordance with this code.

L 504.6 Roof Drains. Primary and secondary roof drains, conductors, leaders, overflows, and gutters shall be designed and installed in accordance with this code.

L 504.7 Water Quality Devices and Equipment. Devices and equipment used to treat rainwater to maintain the minimum water quality requirements determined by the Authority Having Jurisdiction shall be listed or labeled (third-party certified) by a listing agency (accredited conformity assessment body) and approved for the intended application.

L 504.7.1 Filtration and Disinfection Systems. Filtration and disinfection systems shall be located after the water storage tank. Where a chlorination system is installed, it shall be installed upstream of filtration systems. Where an ultraviolet disinfection system is installed, a filter not more than 5 microns (5 µm) shall be installed upstream of the disinfection system.

L 504.8 Freeze Protection. Tanks and piping installed in locations subject to freezing shall be provided with an approved means of freeze protection.

L 504.9 Roof Washer or Pre-Filtration System. Collected rainwater shall pass through a roof washer or pre-filtration system before the water enters the rainwater storage tank. Roof washer systems shall comply with Section L 504.9.1 through Section L 504.9.4.

L 504.9.1 Size. The roof washer shall be sized to direct a sufficient volume of rainwater containing debris that has accumulated on the collection surface away from the storage tank. ARCSA/ASPE 63 contains additional guidance on acceptable methods of sizing roof washers.

L 504.9.2 Debris Screen. The inlet to the roof washer shall be provided with a debris screen or other approved means that protects the roof washer from the intrusion of debris and vermin. Where the debris screen is installed, the debris screen shall be corrosion resistant and shall have openings not larger than ½ of an inch (12.7 mm).

L 504.9.3 Drain Discharge. Water drained from the roof washer or pre-filter shall be diverted away from the storage tank and discharged to a disposal area that does not cause property damage or erosion. Roof washer drainage shall not drain over a public way.

L 504.9.4 Automatic Drain. Roof washing systems shall be provided with an automatic means of self draining between rain events.

L 504.10 Filtration and Disinfection Systems.

Filtration and disinfection systems shall be located after the water storage tank. Where a chlorination system is installed, it shall be installed upstream of filtration systems. Where an ultraviolet disinfection system is installed, a filter not more than 5 microns (5 μm) shall be installed upstream of the disinfection system.

L 504.11 Roof Gutters. Gutters shall maintain a minimum slope and be sized in accordance with this code.

L 504.12 Drains, Conductors, and Leaders. The design and size of rainwater drains, conductors, and leaders shall comply with this code.

L 504.13 Size of Potable Water Piping. Potable rainwater system distribution piping shall be sized in accordance with this code for sizing potable water piping.

L 505.0 Cleaning.

L 505.1 General. The interior surfaces of tanks and equipment shall be clean before they are put into service.

L 506.0 Supply System Inspection and Test.

L 506.1 General. Rainwater catchment systems shall be inspected and tested in accordance with the applicable provisions of this code for testing of potable water and storm drainage systems. Storage tanks shall be filled with water to the overflow opening for a period of 24 hours, and during inspection, or by other means as approved by the Authority Having Jurisdiction. Seams and joints shall be exposed during inspection and checked for water tightness.

L 601.0 Water Heating Design, Equipment, and Installation.

L 601.1 Scope. The provisions of this section shall establish the means of conserving potable and nonpotable water and energy associated with the generation and use of hot water in a building. This includes provisions for the hot water distribution system, which is the portion of the potable water distribution system between a water heating device and the plumbing fixtures, including dedicated return piping and appurtenances to the water heating device in a recirculation system.

L 601.2 Insulation. Hot water supply and return piping shall be thermally insulated. The wall thickness of the insulation shall be equal to the nominal diameter of the pipe up to 2 inches (50 mm). The wall thickness shall be not less than 2 inches (51 mm) for nominal pipe diameters exceeding 2 inches (50 mm). The conductivity of the insulation [k -factor ($\text{Btu}\cdot\text{in}/(\text{h}\cdot\text{ft}^2\cdot^\circ\text{F})$)], measured radially, shall not be more than 0.28 [$\text{Btu}\cdot\text{in}/(\text{h}\cdot\text{ft}^2\cdot^\circ\text{F})$] [$0.04 \text{ W}/(\text{m}\cdot\text{k})$]. Hot water piping to be insulated shall be installed such that insulation is continuous. Pipe insulation shall be installed to within $\frac{1}{4}$ of an inch (6.4 mm) of appliances, appurtenances, fixtures, structural members, or a wall where the pipe passes through to connect to a fixture within 24 inches (610

mm). Building cavities shall be large enough to accommodate the combined diameter of the pipe, the insulation, and other objects in the cavity that the piping shall cross. Pipe supports shall be installed on the outside of the pipe insulation.

Exceptions:

- (1) Where the hot water pipe is installed in a wall that is not of a width to accommodate the pipe and insulation, the insulation thickness shall be permitted to have the maximum thickness that the wall is capable of accommodating and not less than $\frac{1}{2}$ of an inch (12.7 mm) thick.
- (2) Hot water supply piping exposed under sinks, lavatories, and similar fixtures.
- (3) Where hot water distribution piping is installed within an attic, crawlspace, or wall insulation.
 - (a) In attics and crawlspaces the insulation shall cover the pipe not less than $5\frac{1}{2}$ inches (140 mm) further away from the conditioned space.
 - (b) In walls, the insulation shall completely surround the pipe with not less than 1 inch (25.4 mm) of insulation.
 - (c) Where burial within the insulation will not completely or continuously surround the pipe, then these exceptions do not apply.

L 601.3 Recirculation Systems. Recirculation systems shall comply with Section L 601.3.1 and Section L 601.3.2.

L 601.3.1 For Low-Rise Residential Buildings.

Circulating hot water systems shall be arranged so that the circulating pump(s) are capable of being turned off (automatically or manually) where the hot water system is not in operation. [ASHRAE 90.2:7.2]

L 601.3.2 For Pumps Between Boilers and Storage Tanks.

Where used to maintain storage tank water temperature, recirculating pumps shall be equipped with controls limiting operation to a period from the start of the heating cycle to a maximum of 5 minutes after the end of the heating cycle. [ASHRAE 90.1:7.4.4.4]

L 601.4 Recirculation Pump Controls. Pump controls shall include on-demand activation or time clocks combined with temperature sensing. Time clock controls for pumps shall not let the pump operate more than 15 minutes every hour. Temperature sensors shall stop circulation where the temperature set point is reached and shall be located on the circulation loop at or near the last fixture. The pump, pump controls, and temperature sensors shall be accessible. Pump operation shall be limited to the building's hours of operation.

L 601.5 Temperature Maintenance Controls.

Systems designed to maintain usage temperatures in hot-water pipes, such as recirculating hot-water systems or heat trace, shall be equipped with automatic time switches or other controls that are capable of being set to switch off the usage temperature maintenance system during extended periods where hot water is not required. [ASHRAE 90.1:7.4.4.2]

L 601.6 System Balancing. Systems with multiple recirculation zones shall be balanced to uniformly distribute hot water, or they shall be operated with a pump for each zone. The circulation pump controls shall comply with the provisions of Section L 601.4.

L 601.7 Flow Balancing Valves. Flow balancing valves shall be a factory preset automatic flow control valve, a flow regulating valve, or a balancing valve with memory stop.

L 601.8 Air Elimination. Provision shall be made for the elimination of air from the return system.

L 601.9 Gravity or Thermosyphon Systems. Gravity or thermosyphon systems are prohibited.

L 602.0 Service Hot Water – Low-Rise Residential Buildings.

L 602.1 General. The service water heating system for single-family houses, multi-family structures of three stories or fewer above grade, and modular houses shall comply with Section L 602.2 through Section L 602.7.3.

The service water heating system of all other buildings shall comply with Section L 603.0.

L 602.2 Water Heaters and Storage Tanks. Residential-type water heaters, pool heaters, and unfired water heater storage tanks shall comply with the minimum performance requirements specified by federal law.

Unfired storage water heating equipment shall have a heat loss through the tank surface area of less than 6.5 British thermal units per square foot hour [Btu/(ft²•h)] (20.5 W/m²). [ASHRAE 90.2:7.1]

L 602.3 Recirculation Systems. Recirculation systems shall comply with the provisions in Section L 601.3.

L 602.4 Central Water Heating Equipment. Service water heating equipment (central systems) that does not fall under the requirements for residential-type service water heating equipment addressed in Section L 602.0 shall comply with the applicable requirements for service water-heating equipment found in Section L 603.0. [ASHRAE 90.2:7.3]

L 602.5 Insulation. Insulation for hot water and return piping shall comply with the provisions of Section L 601.2.

L 602.6 Hard Water. Where water has hardness equal to or exceeding 9 grains per gallon (gr/gal) (154 mg/L) measured as total calcium carbonate equivalents, the water supply line to water heating equipment in new one- and two-family dwellings shall be roughed-in to allow for the installation of water treatment equipment.

L 602.7 Maximum Volume of Hot Water. The maximum volume of water contained in hot water distribution pipes shall be in accordance with Section L 602.7.1 or Section L 602.7.2. The water volume shall be calculated using Table L 602.7.

L 602.7.1 Maximum Volume of Hot Water Without Recirculation or Heat Trace. The maximum volume of water contained in the hot water distribution pipe between the water heater and any fixture fitting shall not exceed 32 ounces (oz) (946 mL). Where a fixture fitting shutoff valve (supply stop) is installed ahead of the fixture fitting, the maximum volume of water is permitted to be calculated between the water heater and the fitting shutoff valve (supply stop).

L 602.7.2 Maximum Volume of Hot Water with Recirculation or Heat Trace. The maximum volume of water contained in the branches between the recirculation loop or electrically heat traced pipe and the fixture fitting shall not exceed 16 oz (473 mL). Where a fixture fitting shutoff valve (supply stop) is installed ahead of the fixture fitting, the maximum volume of water is permitted to be calculated between the recirculation loop or electrically heat traced pipe and the fixture fitting shutoff valve (supply stop).

Exception: Whirlpool bathtubs or bathtubs that are not equipped with a shower are exempted from the requirements of Section L 602.7.

L 602.7.3 Hot Water System Submeters. Where a hot water pipe from a circulation loop or electric heat trace line is equipped with a submeter, the hot water distribution system downstream of the submeter shall have either an end-of-line hot water circulation pump or shall be electrically heat traced. The maximum

TABLE L 602.7
WATER VOLUME FOR DISTRIBUTION PIPING MATERIALS*

| OUNCES OF WATER PER FOOT LENGTH OF PIPING | | | | | | | | | | | | | |
|---|-------------|-------------|-------------|-----------------------|----------------|----------------|--------------|----------------|------------------|----------------|----------|---------------|--------------|
| NOMINAL SIZE (inch) | COPPER M | COPPER L | COPPER K | CPVC CTS SDR 11 | CPVC SCH 40 | PEX-AL- PEX | PE-AL- PE | CPVC SCH 80 | PEX CTS SDR 9 | PE-RT SDR 9 | PP SDR 6 | PP SDR 7.3 | PP SDR 11 |
| 3/8 | 1.06 | 0.97 | 0.84 | NA | 1.17 | 0.63 | 0.63 | NA | 0.64 | 0.64 | 0.91 | 1.09 | 1.24 |
| 1/2 | 1.69 | 1.55 | 1.45 | 1.25 | 1.89 | 1.31 | 1.31 | 1.46 | 1.18 | 1.18 | 1.41 | 1.68 | 2.12 |
| 3/4 | 3.43 | 3.22 | 2.90 | 2.67 | 3.38 | 3.39 | 3.39 | 2.74 | 2.35 | 2.35 | 2.23 | 2.62 | 3.37 |
| 1 | 5.81 | 5.49 | 5.17 | 4.43 | 5.53 | 5.56 | 5.56 | 4.57 | 3.91 | 3.91 | 3.64 | 4.36 | 5.56 |
| 1 1/4 | 8.70 | 8.36 | 8.09 | 6.61 | 9.66 | 8.49 | 8.49 | 8.24 | 5.81 | 5.81 | 5.73 | 6.81 | 8.60 |
| 1 1/2 | 12.18 | 11.83 | 11.45 | 9.22 | 13.20 | 13.88 | 13.88 | 11.38 | 8.09 | 8.09 | 9.03 | 10.61 | 13.47 |
| 2 | 21.08 | 20.58 | 20.04 | 15.79 | 21.88 | 21.48 | 21.48 | 19.11 | 13.86 | 13.86 | 14.28 | 16.98 | 21.39 |

For SI units: 1 ounce = 29.573 mL

* NA: Not Applicable

volume of water in a branch from the circulation loop or electric heat trace line downstream of the submeter shall not exceed 16 oz (473 mL).

Where there is no circulation loop or electric heat traced line downstream of the submeter, the submeter shall be located within 2 feet (610 mm) of the central hot water system; or the branch line to the submeter shall be circulated or heat traced to within 2 feet (610 mm) of the submeter. The maximum volume from the submeter to each fixture shall not exceed 32 oz (946 mL).

The circulation pump controls shall comply with the provisions of Section L 601.4.

L 603.0 Service Hot Water – Other Than Low-Rise Residential Buildings.

L 603.1 General. The service hot water, other than single-family houses, multi-family structures of three stories or fewer above grade, and modular houses, shall comply with this section.

» **L 603.1.1 New Buildings.** Service water heating systems and equipment shall comply with the requirements of this section as described in Section L 603.2. [ASHRAE 90.1:7.1.1.1]

» **L 603.1.2 Additions to Existing Buildings.** Service water heating systems and equipment shall comply with the requirements of this section.

Exception: Where the service water heating to an addition is provided by existing service water heating systems and equipment, such systems and equipment shall not be required to be in accordance with this appendix. However, new systems or equipment installed shall be in accordance with specific requirements applicable to those systems and equipment. [ASHRAE 90.1:7.1.1.2]

» **L 603.1.3 Alterations to Existing Buildings.** Building service water heating equipment installed as a direct replacement for existing building service water heating equipment shall be in accordance with the requirements of Section L 603.0 applicable to the equipment being replaced. New and replacement piping shall comply with Section L 603.3.3.

Exception: Compliance shall not be required where there is insufficient space or access to meet these requirements. [ASHRAE 90.1:7.1.1.3]

» **L 603.2 Compliance Path(s).** Compliance shall be achieved in accordance with the requirements of Section L 603.1, Section L 603.3, Section L 603.4, and Section L 603.5. [ASHRAE 90.1:7.2.1]

» **L 603.2.1 Energy Cost Budget Method.** Projects using the energy cost budget method of ASHRAE 90.1 for demonstrating compliance with the standard shall be in accordance with the requirements of Section L 603.3 in conjunction with the energy cost budget method of ASHRAE 90.1. [ASHRAE 90.1:7.2.2]

» **L 603.3 Mandatory Provisions.** The mandatory provisions of Section L 603.3.1 through Section L 603.3.7 shall be followed.

L 603.3.1 Load Calculations. Service water heating system design loads for the purpose of sizing systems and equipment shall be determined in accordance with manufacturer's published sizing guidelines or accepted engineering standards and handbooks acceptable to the adopting authority (e.g., ASHRAE Handbook – HVAC Applications). [ASHRAE 90.1:7.4.1]

L 603.3.2 Equipment Efficiency. Water heating equipment, hot-water supply boilers used solely for heating potable water, pool heaters, and hot-water storage tanks shall comply with the criteria listed in Table L 603.3.2. Where multiple criteria are listed, all criteria shall be met. Omission of minimum performance requirements for certain classes of equipment does not preclude use of such equipment where appropriate. Equipment not listed in Table L 603.3.2 has no minimum performance requirements.

Exceptions: Water heaters and hot-water supply boilers having more than 140 gallons (530 L) of storage capacity are not required to meet the standby loss (SL) requirements of Table L 603.3.2 where:

- (1) The tank surface is thermally insulated to R-12.5.
- (2) A standing pilot light is not installed.
- (3) Gas- or oil-fired storage water heaters have a flue damper or fan-assisted combustion. [ASHRAE 90.1:7.4.2]

L 603.3.3 Insulation. The following piping shall be insulated in accordance with Table L 603.3.3:

- (1) Recirculating system piping, including the supply and return piping of a circulating tank type water heater.
- (2) The first 8 feet (2438 mm) of outlet piping for a constant temperature nonrecirculating storage system.
- (3) The inlet piping between the storage tank and a heat trap in a nonrecirculating storage system.
- (4) Piping that is externally heated (such as heat trace or impedance heating). [ASHRAE 90.1:7.4.3]

L 603.3.4 Hot Water System Design. Hot water systems shall comply with Section L 603.3.4.1 and Section L 603.3.4.2.

L 603.3.4.1 Recirculation System. Recirculation systems shall comply with the provisions in Section L 601.3.

L 603.3.4.2 Maximum Volume of Hot Water. The maximum volume of water contained in hot water distribution lines between the water heater and the fixture stop or connection to showers, kitchen faucets, and lavatories shall be determined in accordance with Section L 602.7.

L 603.3.5 Service Water Heating System Controls. Service water heating system controls shall comply with Section L 603.3.5.1 and Section L 603.3.5.2.

TABLE L 603.3.2
PERFORMANCE REQUIREMENTS FOR WATER HEATING EQUIPMENT^{5, 6}
[ASHRAE 90.1: TABLE 7.8]

| EQUIPMENT TYPE | SIZE CATEGORY | SUBCATEGORY OR RATING CONDITION (INPUT) | PERFORMANCE REQUIRED ¹ | TEST PROCEDURE ^{2,3} |
|---------------------------------------|--------------------------------------|--|---|--------------------------------------|
| Electric table top water heaters | ≤12 kW | Resistance ≥20 gal | 0.93–0.00035V EF | DOE 10 CFR Part 430 |
| Electric water heaters | ≤12 kW | Resistance ≥20 gal | 0.97–0.00035V EF | DOE 10 CFR Part 430 |
| | >12 kW | Resistance ≥20 gal | $0.3 + 27\sqrt{V_m} \text{ %/h}$ | Section G.2 of CSA Z21.10.3 |
| | ≤24 Amps and ≤250 Volts | Heat Pump | 0.93–0.00035V EF | DOE 10 CFR Part 430 |
| Gas storage water heaters | ≤75 000 Btu/h | ≥20 gal | 0.67–0.0005V EF | DOE 10 CFR Part 430 |
| | >75 000 Btu/h | <4000 (Btu/h)/gal | $80\% E_t (Q/799 + 16.6\sqrt{V}) \text{ SL, Btu/h}$ | Sections G.1 and G.2 of CSA Z21.10.3 |
| Gas instantaneous water heaters | >50 000 Btu/h and <200 000 Btu/h | ≥4000 (Btu/h)/gal and <2 gal | 0.62–0.0005V EF | DOE 10 CFR Part 430 |
| | ≥200 000 Btu/h ⁴ | ≥4000 (Btu/h)/gal and <10 gal | 80% E_t | Sections G.1 and G.2 of CSA Z21.10.3 |
| | ≥200 000 Btu/h | ≥4000 (Btu/h)/gal and ≥10 gal | $80\% E_t (Q/799 + 16.6\sqrt{V}) \text{ SL, Btu/h}$ | |
| Oil storage water heaters | ≤105 000 Btu/h | ≥20 gal | 0.59–0.0005V EF | DOE 10 CFR Part 430 |
| | >105 000 Btu/h | <4000 (Btu/h)/gal | $80\% E_t (Q/799 + 16.6\sqrt{V}) \text{ SL, Btu/h}$ | Sections G.1 and G.2 of CSA Z21.10.3 |
| Oil instantaneous water heaters | ≤210 000 Btu/h | ≥4000 (Btu/h)/gal and <2 gal | 0.59–0.0005V EF | DOE 10 CFR Part 430 |
| | >210 000 Btu/h | ≥4000 (Btu/h)/gal and <10 gal | 80% E_t | Sections G.1 and G.2 of CSA Z21.10.3 |
| | >210 000 Btu/h | ≥4000 (Btu/h)/gal and ≥10 gal | $78\% E_t (Q/799 + 16.6\sqrt{V}) \text{ SL, Btu/h}$ | |
| Hot-water supply boilers, gas and oil | ≥300 000 Btu/h and <12 500 000 Btu/h | ≥4000 (Btu/h)/gal and <10 gal | 80% E_t | Sections G.1 and G.2 of CSA Z21.10.3 |
| Hot-water supply boilers, gas | — | ≥4000 (Btu/h)/gal and ≥10 gal | $80\% E_t (Q/799 + 16.6\sqrt{V}) \text{ SL, Btu/h}$ | |
| Hot-water supply boilers, oil | — | ≥4000 (Btu/h)/gal and ≥10 gal | $78\% E_t (Q/799 + 16.6\sqrt{V}) \text{ SL, Btu/h}$ | |
| Pool heaters, oil and gas | All | — | 78% E_t | ASHRAE 146 |
| Heat pump pool heaters | All | — | 4.0 COP | AHRI 1160 |
| Unfired storage tanks | All | — | R-12.5 | (none) |

For SI units: 1 gallon = 3.785 L, 1000 British thermal units per hour = 0.293 kW, °C = (°F–32)/1.8

Notes:

¹ Energy factor (EF) and thermal efficiency (E_t) are minimum requirements, while standby loss (SL) is maximum Btu/h (kW) based on a 70°F (39°C) temperature difference between stored water and ambient requirements. In the EF equation, V is the rated volume in gallons. In the SL equation, V is the rated volume in gallons and Q is the nameplate input rate in Btu/h (kW). V_m is the measured volume in the tank.

² ASHRAE 90.1 contains a complete specification, including the year version, of the referenced test procedure.

³ Section G.1 is titled “Test Method for Measuring Thermal Efficiency” and Section G.2 is titled “Test Method for Measuring Standby Loss.”

⁴ Instantaneous water heaters with input rates below 200 000 Btu/h (58.6 kW) shall be in accordance with these requirements where the water heater is designed to heat water to temperatures of 180°F (82°C) or higher.

⁵ Electric water heaters with input rates less than 40 946 Btu/h (12 kW) shall be in accordance with these requirements where the water heater is designed to heat water to temperatures of 180°F (82°C) or higher.

⁶ Refer to Section L 603.4.2.1 for additional requirements for gas storage and instantaneous water heaters and gas hot-water supply boilers.

TABLE L 603.3.3
MINIMUM PIPE INSULATION THICKNESS FOR HEATING AND HOT WATER SYSTEMS
(STEAM, STEAM CONDENSATE, HOT WATER HEATING, AND DOMESTIC WATER SYSTEMS)^{1, 2, 3, 4, 5}
[ASHRAE 90.1: TABLE 6.8.3-1]

| FLUID DESIGN OPERATING TEMPERATURE RANGE AND USAGE (°F) | INSULATION CONDUCTIVITY | | ≥NOMINAL PIPE SIZE OR TUBE SIZE (inches) | | | | |
|---|--|------------------------------------|--|----------|----------|---------|-----|
| | CONDUCTIVITY Btu·inch/(h·ft ² ·°F) | MEAN RATING TEMPERATURE (°F) | <1 | 1 to <1½ | 1½ to <4 | 4 to <8 | ≥8 |
| | | | INSULATION THICKNESS (inches) | | | | |
| >350 | 0.32 - 0.34 | 250 | 4.5 | 5.0 | 5.0 | 5.0 | 5.0 |
| 251 - 350 | 0.29 - 0.32 | 200 | 3.0 | 4.0 | 4.5 | 4.5 | 4.5 |
| 201 - 250 | 0.27 - 0.30 | 150 | 2.5 | 2.5 | 2.5 | 3.0 | 3.0 |
| 141 - 200 | 0.25 - 0.29 | 125 | 1.5 | 1.5 | 2.0 | 2.0 | 2.0 |
| 105 - 140 | 0.22 - 0.28 | 100 | 1.0 | 1.0 | 1.5 | 1.5 | 1.5 |

For SI units: °C=(°F-32)/1.8, 1 British thermal unit inch per hour square foot degree Fahrenheit = [0.1 W/(m·K)], 1 inch = 25 mm

Notes:

¹ For insulation outside the stated conductivity range, the minimum thickness (*T*) shall be determined as follows:

$$T = r \{ (1 + t/r)^{K/k} - 1 \}$$

Where:

T = minimum insulation thickness (inches) (mm).

r = actual outside radius of pipe (inches) (mm).

t = insulation thickness listed in this table for applicable fluid temperature and pipe size.

K = conductivity of alternate material at mean rating temperature indicated for the applicable fluid temperature [Btu·in/(h·ft²·°F)] [W/(m·K)].

k = the upper value of the conductivity range listed in this table for the applicable fluid temperature.

² These thicknesses are based on energy efficiency considerations only. Additional insulation is sometimes required relative to safety issues or surface temperature.

³ For piping 1½ inches (40 mm) or less, and located in partitions within conditioned spaces, reduction of insulation thickness by 1 inch (25.4 mm) shall be permitted before thickness adjustment required in Footnote 1, but not a thickness less than 1 inch (25.4 mm).

⁴ For direct-buried heating and hot water system piping, reduction of insulation thickness by 1½ inch (38 mm) shall be permitted before thickness adjustment required in Footnote 1, but not a thickness less than 1 inch (25.4 mm).

⁵ Table L 603.3.3 is based on steel pipe. Non-metallic pipes, less than schedule 80 thickness shall use the table values. For other non-metallic pipes having a thermal resistance more than that of steel pipe, reduced insulation thicknesses shall be permitted where documentation is provided showing that the pipe with the proposed insulation has less heat transfer per foot (mm) than a steel pipe of the same size with the insulation thickness shown in Table L 603.3.3.



L 603.3.5.1 Temperature Controls.

Temperature controls shall be provided that allow for storage temperature adjustment from 120°F (49°C) or lower to a maximum temperature compatible with the intended use.

Exception: Where the manufacturer's installation instructions specify a higher minimum thermostat setting to minimize condensation and resulting corrosion. [ASHRAE 90.1:7.4.4.1]



L 603.3.5.2 Outlet Temperature Controls.

Temperature controlling means shall be provided to limit the maximum temperature of water delivered from lavatory faucets in public facility restrooms to 110°F (43°C). [ASHRAE 90.1:7.4.4.3]



L 603.3.6 Pools. Pool heating systems shall comply with Section L 603.3.6.1 through Section L 603.3.6.3.



L 603.3.6.1 Pool Heaters. Pool heaters shall be equipped with a readily accessible ON/OFF switch

to allow shutting off the heater without adjusting the thermostat setting. Pool heaters fired by natural gas shall not have continuously burning pilot lights. [ASHRAE 90.1:7.4.5.1]

L 603.3.6.2 Pool Covers. Heated pools shall be equipped with a vapor retardant pool cover on or at the water surface. Pools heated to more than 90°F (32°C) shall have a pool cover with a minimum insulation value of R-12. <<

Exception: Pools deriving over 60 percent of the energy for heating from site-recovered energy or solar energy source. [ASHRAE 90.1:7.4.5.2]

L 603.3.6.3 Time Switches. Time switches shall be installed on swimming pool heaters and pumps. <<

Exceptions:

(1) Where public health standards require 24-hour pump operation.

- (2) Where pumps are required to operate solar and waste heat recovery pool heating systems. [ASHRAE 90.1:7.4.5.3]

» **L 603.3.7 Heat Traps.** Vertical pipe risers serving storage water heaters and storage tanks not having integral heat traps and serving a nonrecirculating system shall have heat traps on both the inlet and outlet piping as close as practical to the storage tank. A heat trap is a means to counteract the natural convection of heated water in a vertical pipe run. The means is either a device specifically designed for the purpose or an arrangement of tubing that forms a loop of 360 degrees (6.28 rad) or piping that from the point of connection to the water heater (inlet or outlet) includes a length of piping directed downward before connection to the vertical piping of the supply water or hot-water distribution system, as applicable. [ASHRAE 90.1:7.4.6]

» **L 603.4 Prescriptive Path.** The prescriptive path for space or water heating efficiency shall comply with Section L 603.4.1 through Section L 603.4.3.1.

» **L 603.4.1 Space Heating and Water Heating.** The use of a gas-fired or oil-fired space-heating boiler system, otherwise in accordance with Section L 603.0, to provide the total space heating and water heating for a building is allowed where one of the following conditions is met:

- (1) The single space-heating boiler, or the component of a modular or multiple boiler system that is heating the service water, has a standby loss in Btu/h (kW) not exceeding $(13.3 \times pmd + 400)/n$, where (*pmd*) is the probable maximum demand in gallons per hour, determined in accordance with the procedures described in generally accepted engineering standards and handbooks, and (*n*) is the fraction of the year where the outdoor daily mean temperature exceeds 64.9°F (18.28°C).

The standby loss is to be determined for a test period of 24 hours duration while maintaining a boiler water temperature of not less than 90°F (32°C) above ambient, with an ambient temperature between 60°F (16°C) and 90°F (32°C). For a boiler with a modulating burner, this test shall be conducted at the lowest input.

- (2) It is demonstrated to the satisfaction of the Authority Having Jurisdiction that the use of a single heat source will consume less energy than separate units.
- (3) The energy input of the combined boiler and water heater system is less than 150 000 British thermal units per hour (Btu/h) (44 kW). [ASHRAE 90.1:7.5.1]

» **L 603.4.2 Service Water Heating Equipment.** Service water heating equipment used to provide the additional function of space heating as part of a combination (integrated) system shall satisfy stated requirements for the service water heating equipment. [ASHRAE 90.1:7.5.2]

L 603.4.2.1 Buildings with High-Capacity Service Water Heating Systems. New buildings with gas service hot-water systems with a total installed gas water-heating input capacity of 1 000 000 Btu/h (293 kW) or more, shall have gas service water-heating equipment with a thermal efficiency (E_t) of not less than 90 percent. Multiple units of gas water-heating equipment shall be permitted to comply with this requirement where the water-heating input provided by the equipment, with thermal efficiency (E_t) of more or less than 90 percent, provides an input capacity-weighted average thermal efficiency of not less than 90 percent. The requirements of Section L 603.4.2.1 are effective on July 30, 2015.

Exceptions:

- (1) Where 25 percent of the annual service water-heating requirement is provided by site-solar or site-recovered energy.
- (2) Water heaters installed in individual dwelling units.
- (3) Individual gas water heaters with input capacity not more than 1 000 000 Btu/h (293 kW). [ASHRAE 90.1:7.5.3]

L 603.4.3 Heat Recovery for Service Water Heating. Condenser heat recovery systems shall be installed for heating or preheating of service hot water provided the following are true:

- (1) The facility operates 24 hours a day.
- (2) The total installed heat rejection capacity of the water-cooled systems exceed 6 000 000 Btu/h (1758 kW) of heat rejection.
- (3) The design service water heating load exceeds 1 000 000 Btu/h (293 kW). [ASHRAE 90.1:6.5.6.2.1]

L 603.4.3.1 Capacity. The required heat recovery system shall have the capacity to provide the smaller of:

- (1) Sixty percent of the peak heat rejection load at design conditions.
- (2) Preheat of the peak service hot water draw to 85°F (29°C).

Exceptions:

- (1) Facilities that employ condenser heat recovery for space heating with a heat recovery design exceeding 30 percent of the peak water-cooled condenser load at design conditions.
- (2) Facilities that provide 60 percent of their service water heating from site-solar or site-recovered energy or from other sources. [ASHRAE 90.1:6.5.6.2.2]

L 603.5 Submittals. The Authority Having Jurisdiction shall require submittal of compliance documentation and supplemental information in accordance with Section 104.3.1 of this code.

L 604.0 Solar Water Heating Systems.

L 604.1 General. The erection, installation, alteration, addition to, use or maintenance of solar water heating systems shall be in accordance with this section and the Uniform Solar Energy and Hydronics Code.

L 604.2 Annual Inspection and Maintenance. Solar energy systems that utilize a heat transfer fluid shall be inspected annually, unless inspections are required on a more frequent basis by the solar energy system manufacturer.

L 605.0 Hard Water.

L 605.1 Softening and Treatment. Where water has a hardness equal to or exceeding 10 gr/gal (171 mg/L) measured as total calcium carbonate equivalents, the water supply line to water heating equipment and the circuit of boilers shall be softened or treated to prevent accumulation of lime scale and consequent reduction in energy efficiency.

L 606.0 Drain Water Heat Exchangers.

L 606.1 General. Drain water heat exchangers shall comply with IAPMO PS 92. The heat exchanger shall be accessible.

L 701.0 Installer Qualifications.

L 701.1 Scope. The provisions of this section address minimum qualifications of installers of plumbing and mechanical systems covered within the scope of this appendix.

L 702.0 Qualifications.

L 702.1 General. Where permits are required, the Authority Having Jurisdiction shall have the authority to require contractors, installers, or service technicians to demonstrate competency. Where determined by the Authority Having Jurisdiction, the contractor, installer, or service technician shall be licensed to perform such work.

L 801.0 Method of Calculating Water Savings.

L 801.1 Purpose. The purpose of this section is to provide a means of estimating the water savings where installing plumbing and fixture fittings that use less water than the maximum required by the Energy Policy Act of 1992 and 2005 and this code.

L 801.2 Calculation of Water Savings. Table L 801.2(1) and Table L 801.2(2) shall be permitted to be used to establish a water use baseline in calculating the amount of water saved as a result of using plumbing fixtures and fixture fittings that use less water than the required maximum. Water use is determined by the following equation:

Water use = (flow rate or consumption) x (duration) x (occupants) x (daily uses)

APPENDIX L

**TABLE L 801.2(1)
WATER USE BASELINE⁵**

| FIXTURE TYPE | MAXIMUM FLOW-RATE CONSUMPTION ² | DURATION | ESTIMATED DAILY USES PER PERSON | OCCUPANTS ^{3, 4} |
|--|--|--------------|---------------------------------|---------------------------|
| Showerheads | 2.5 gpm at 80 psi | 8 minutes | 1 | — |
| Private or Private Use Lavatory Faucets | 2.2 gpm at 60 psi | 0.25 minutes | 4 | — |
| Residential Kitchen Faucets | 2.2 gpm at 60 psi | 4 minutes | 1 | — |
| Wash Fountains | One 2.2 gpm at 60 psi fixture fitting for each 20 inches rim space | — | — | — |
| Lavatory Faucets in other than Residences, Apartments, and Private Bathrooms in Lodging Facilities | 0.5 gpm | 0.25 minutes | 4 | — |
| Metering Faucets | 0.25 gallons /cycle | — | 3 | — |
| Metering Faucets for Wash Fountains | One 0.25 gallon per cycle fixture fitting for each 20 inches rim space | — | — | — |
| Water Closets | 1.6 gallons per flush | 1 flush | 1 male ¹ | — |
| | | | 3 female | — |
| Urinals | 1.0 gallons per flush | 1 flush | 2 male | — |

For SI units: 1 gallon per minute = 0.06 L/s, 1 pound-force per square inch = 6.8947 kPa, 1 gallon = 3.785 L, 1 inch = 25.4 mm

Notes:

¹ The daily use number shall be increased to three where urinals are not installed in the room.

² The maximum flow rate or consumption is from the Energy Policy Act.

³ For residential occupancies, the number of occupants shall be based on two persons for the first bedroom and one additional person for each additional bedroom.

⁴ For non-residential occupancies, refer to Table 422.1 for occupant load factors.

⁵ Where determining calculations, assume one use per person for metering or self closing faucets.

TABLE L 801.2(2)
WATER SAVINGS CALCULATOR^{1, 2, 3}

| NON-RESIDENTIAL BUILDINGS | | | | | |
|--|-------------------------------------|------------|-----------------------|-----------|-------------------------------|
| BASELINE CASE: CHANGE OCCUPANT VALUES TO REFLECT ANTICIPATED OCCUPANCY | | | | | |
| FIXTURE TYPE | CONSUMPTION (gallons per minute) | DAILY USES | DURATION (minutes) | OCCUPANTS | DAILY WATER USES (gallons) |
| 1.6 gpf (gallons per flush) toilet - male | 1.6 | 1 | 1 | 150 | 240 |
| 1.6 gpf toilet - female | 1.6 | 3 | 1 | 150 | 720 |
| 1.0 gpf urinal - male | 1 | 2 | 1 | 150 | 300 |
| Commercial lavatory faucet - 0.5 gpm | 0.5 | 3 | 0.25 | 300 | 113 |
| Kitchen sink - 2.2 gpm | 2.2 | 1 | 0.25 | 300 | 165 |
| Showerhead - 2.5 gpm | 2.5 | 0.1 | 8 | 300 | 600 |
| Total Daily Volume | | | | | 2138 |
| Annual Work Days | | | | | 260 |
| Total Annual Usage | | | | | 555 750 |

| FIXTURE TYPE | CONSUMPTION (gallons per minute) | DAILY USES | DURATION (minutes) | OCCUPANTS | DAILY WATER USES (gallons) |
|--------------------------------------|-------------------------------------|------------|-----------------------|-----------|-------------------------------|
| 1.6 gpf toilet - male | 1.28 | 1 | 1 | 150 | 192 |
| 1.6 gpf toilet - female | 1.28 | 3 | 1 | 150 | 576 |
| 1.0 gpf urinal - male | 0.5 | 2 | 1 | 150 | 150 |
| Commercial lavatory faucet - 0.5 gpm | 0.5 | 3 | 0.25 | 300 | 113 |
| Kitchen sink - 2.2 gpm | 2.2 | 1 | 0.25 | 300 | 165 |
| Showerhead - 2.5 gpm | 2.5 | 0.1 | 8 | 300 | 600 |
| Total Daily Volume | | | | | 1796 |
| Annual Work Days | | | | | 260 |
| Total Annual Usage | | | | | 466 830 |
| Annual Savings | | | | | 88 920 |
| % Reduction | | | | | -16.0 percent |

For SI units: 1 gallon per minute = 0.06 L/s, 1 gallon = 3.785 L

Notes:

¹ Consumption values shown as underlined reflect the maximum consumption values associated with the provisions called out in the IAPMO Green Plumbing & Mechanical Code Supplement.

² Where metering faucets are used, insert the flow rate of the faucet in the "Consumption" column and insert the cycle time in the "Duration" column (assume 1 cycle per use).

³ To determine estimated savings, insert occupant values (same as Baseline) and consumption values based on fixtures and fixture fittings installed.

TABLE L 801.2(2)
WATER SAVINGS CALCULATOR (continued)^{1, 2}

| RESIDENTIAL 3 BEDROOM STRUCTURE | | | | | |
|---|-------------------------------------|------------|-----------------------|-----------|-------------------------------|
| BASELINE CASE: CHANGE OCCUPANT VALUES BASED ON NUMBER OF BEDROOMS (EXAMPLE SHOWN IS FOR 3 BEDROOMS) | | | | | |
| FIXTURE TYPE | CONSUMPTION (gallons per minute) | DAILY USES | DURATION (minutes) | OCCUPANTS | DAILY WATER USES (gallons) |
| 1.6 gpf toilets | 1.6 | 5 | 1 | 4 | 32 |
| Lavatory faucet - 2.2 gpm | 2.2 | 8 | 0.25 | 4 | 18 |
| Kitchen sink - 2.2 gpm | 2.2 | 6 | 0.25 | 4 | 13 |
| Showerhead - 2.5 gpm | 2.5 | 0.75 | 8 | 4 | 60 |
| Total Daily Volume | | | | | 123 |
| Annual Work Days | | | | | 44 822 |

| FIXTURE TYPE | CONSUMPTION (gallons per minute) | DAILY USES | DURATION (minutes) | OCCUPANTS | DAILY WATER USES (gallons) |
|---------------------------|-------------------------------------|------------|-----------------------|-----------|-------------------------------|
| 1.6 gpf toilet - male | 1.28 | 5 | 1 | 4 | 26 |
| Lavatory faucet - 1.5 gpm | 1.5 | 8 | 0.25 | 4 | 12 |
| Kitchen sink - 2.2 gpm | 2.2 | 6 | 0.25 | 4 | 13 |
| Showerhead - 2.5 gpm | 2.5 | 0.75 | 8 | 4 | 60 |
| Total Daily Volume | | | | | 111 |
| Annual Usage | | | | | 40 442 |
| Annual Savings | | | | | 4380 |
| % Reduction | | | | | -9.8 percent |

For SI units: 1 gallon per minute = 0.06 L/s, 1 gallon = 3.785 L

Notes:

¹ Consumption values shown as underlined reflect the maximum consumption values associated with the provisions called out in the IAPMO Green Plumbing & Mechanical Code Supplement.

² To determine estimated savings, insert occupant values (same as Baseline) and consumption values based on fixtures and fixture fittings installed.

Notes and instructions for Table L 801.2(2):

Table L 801.2(2) is an example of a calculator that is capable of helping estimate water savings in residential and nonresidential structures. The "Duration" of use and "Daily Uses" values that appear in the table are estimates and based on previous studies. The first example shown below is for a commercial office building with 300 occupants, 150 females, and 150 males. The second example is for a 3 bedroom residential building. To obtain and use a working copy of this calculator, follow the download and use instructions below.

Instructions for download:

1. Go to the IAPMO web site at www.iapmogreen.org in order to download the water-savings calculator. The calculator is a Microsoft Office Excel file (1997 or later), your computer must be capable of running MS Excel.
2. Follow the instructions for downloading and running the file.

Instructions for use:

1. In the Baseline Case section, insert the number of total occupants, male occupants and female occupants that apply for the building in the "Occupants" column. Unless specific gender ratio values are provided, assume a 50/50 gender ratio.
2. Copy and paste these same values in the "Occupants" column of the Calculator section.
3. In the Calculator section, insert the consumption values (flow rates in gpm or gallons per flush or per cycle) in the "Consumption" column.
4. Estimated water savings in terms of percent savings versus baseline values, gallons per day and gallons per year will be automatically calculated.

INDEX

© 2015 International Association of Plumbing and Mechanical Officials. All rights reserved.

The copyright in this index is separate and distinct from the copyright in the document that it indexes. The licensing provisions set forth for the document are not applicable to this index. This index may not be reproduced in whole or in part by any means without the express written permission of IAPMO.

- A -

ABANDONED

- Grease interceptors1014.3.7
- Sewers and sewage disposal722.0, H 1101.0

ACCESS PANELS317.1, 402.10

ACCESS TO

- Appliances507.26, 508.3, 508.4
- Backwater valves710.6, 1101.6.4
1502.2.3
- Chemical waste system piping811.4
- Cleanouts707.8, 719.5
- Drips1210.8.1
- Emergency eyewash and
shower equipment416.4
- Flexible connectors604.5, 1212.4.3
- Flushometers413.2
- Fuel gas meters1208.6.1, E 404.2
- Fuel gas piping1210.2.2.1, 1210.3.4
- Fuel gas pressure regulators1208.7.3, 1210.4.1
- Fullway valves606.2, 710.6
- Grease interceptors1014.3.4
- Indirect waste receptors804.1
- Interceptors1009.3, 1009.5,
1016.4, H 901.5
- Lapped flanges1208.5.10.2
- ManholesH 501.12
- Meters and submetersL 407.3
- Plumbing fixtures402.1
- Pool heaters on/off switchL 603.3.6
- Rainwater storage tanks1602.9.5.3, K 104.4.2.1,
L 504.4.2.1
- Septic tanksH 501.5
- Shutoff valves606.3, 606.6,
1210.11, 1312.1.2, E 410.4
- Sumps710.10, 810.3
- Toilet facilities422.4
- Trap seal primers1007.1
- Vacuum pumpsC 501.2
- Valves for
nonpotable application1502.9.5
- Vent connectors, fuel gas509.10.10
- Water meters and submetersL 407.3
- Water pressure regulators and strainers608.2

ACCESSIBLE, DEFINITION203.0

ACCESSIBLE, READILY, DEFINITION203.0

ACCESSIBLE PLUMBING FACILITIES

- For persons with disabilities403.2

- Protection against contact403.3
- Where required403.1

ACRYLONITRILE-BUTADIENE-STYRENE

- (ABS) PIPE208.0, 312.13, 312.14,
701.2, 705.1, 705.8.4, 903.1,
1101.4, Table 313.3, Table 701.2

AIR GAPS

- Backflow prevention603.2, 603.3.1,
603.4.4, Table 603.2,
Table 603.3.1
- Definition203.0
- Discharge from drinking
water treatment units611.2

AIR TANK710.11

ALTERATIONS AND REPAIRS

- Fuel gas piping1203.1, 1213.1.2, 1213.4.2
- Health care facilities1301.6
- Plumbing systems102.4, 301.2.5

ALTERNATE MATERIALS, DESIGN,

- AND METHODS301.3

ALTERNATE WATER SOURCE

- Definition203.0
- For nonpotable applicationsChapter 15
- For special water featuresL 406.1
- Identification of piping601.3.3
- Nonpotable rainwater
catchment system1602.4, K 102.2
Table 1601.5

APPLIANCES

- Automatically operated509.3.4.1, 509.5.7.1
- Categorized vent
diameter/area, definition203.0
- Connections to building
fuel gas piping1212.0
- Definition203.0
- Direct-vent206.0, 509.2.4, 509.8.2,
509.5.10.1, 509.5.10.1, 509.11
- In attics508.4
- Indirect waste type806.0, 807.0
- In under-floor spaces508.4
- On roofs508.0
- Vent Connectors509.10, 510.2.10
- Venting of509.0

APPLICATION FOR PERMIT104.3

APPROVED, DEFINITION203.0

APPROVED TESTING

- AGENCY, DEFINITION203.0

| | |
|--|--|
| AREA DRAINS | 203.0, 1101.5 |
| ASBESTOS-CEMENT PIPE | Table 510.1.2(5), Table 510.2(5) |
| ASPIRATORS | 203.0, 603.5.9, 1303.5 |
| AUTHORITY HAVING JURISDICTION | 103.0, 203.0 |
| AUTHORITY TO | |
| Disconnect gas | 1206.0 |
| Plumbing system | 106.5 |
| Render gas service | 1205.0 |
| AUTOMATIC | |
| Drains | K 104.9.4, L 504.9.4 |
| Flushometer valves | 413.2 |
| Pressure relief valve | 608.4 |
| Pumps | 612.7.2, 1101.6.2, 1315.3, C 501.2.5, H 601.8 |
| Seat cover dispensers | 411.3 |
| Shutoff | 420.3, 504.6 |
| Siphon, septic tanks | H 601.8 |
| Sprinkler systems | 603.5.14 |
| Sumps and receiving tanks | 710.9 |
| Vent dampers, fuel gas | 509.13 |
| AUTO WASH RACKS | 1011.0 |

- B -

| | |
|---|--|
| BACKFILLING | 314.0, 1210.1.2.1, 1310.6, 1502.11.3, H 601.2 |
| BACKFLOW | |
| Definition | 204.0 |
| Prevention | 602.2, 602.3 |
| Prevention devices or assembly | 603.1, 603.3, Table 603.2 |
| BACKFLOW CONNECTION | 204.0, 603.0 |
| BACKFLOW PREVENTERS | |
| Approved standards | Table 603.2 |
| Definition | 204.0 |
| For hot water | 312.10.2 |
| Integral | 603.4.5 |
| Prohibited locations | 603.4.9 |
| Protection from damage | E 309.1 |
| Required | 603.2 |
| BACKFLOW PREVENTION | 602.3, 603.3 |
| BACK-TO-BACK FIXTURES | 704.2 |
| BACKWATER VALVES | |
| Definition | 204.0 |
| Where Required | 710.6 |
| BALLCOCKS | 603.5.2, Table 603.2 |
| BAPTISTRIES | 406.1 |
| BATHROOM, HALF, DEFINITION | 204.0 |
| BATHROOM GROUP | 204.0, 908.2, C 303.0 |
| BATHTUB, PROHIBITED TYPE | 405.3 |
| BATHTUBS AND | |
| WHIRLPOOL BATHTUBS | 409.0 |
| BIDETS | 402.5, 410.0 |

| | |
|---|---|
| BLOWOFF CONDENSERS | 810.1, Table 810.1 |
| BOARD OF APPEALS | 107.0 |
| BOILER BLOWOFF | |
| Definition | 204.0 |
| Discharge requirements | 810.1 |
| BONDING JUMPER | |
| Bonding of CSST fuel gas piping | 1211.2 |
| Definition | 204.0 |
| BOTTLING ESTABLISHMENTS | 1013.0 |
| BUILDING DRAIN | |
| Definition | 204.0 |
| Existing | 102.4.1 |
| Material | Table 701.2 |
| Sizing | 703.0, 710.5, C 304.2, Table 703.2, Table C 304.2 |
| Testing | 712.0 |
| BUILDING DRAIN (STORM), DEFINITION | 204.0 |
| BUILDING SEWERS | |
| Definition | 204.0 |
| Existing | 102.4.1, 715.3 |
| Location | 721.0 |
| Material | 715.1, 720.0, Table 701.2 |
| Sizing | 710.5, 717.0, C 304.2, Table 717.1 |
| Testing | 723.0 |
| BUILDING SUPPLY | 204.0, Chapter 6 |
| BURRED ENDS | 309.3, 609.1, 701.3.1, 903.3, 1208.5.5, 1309.3.5.2 |

- C -

| | |
|---|---|
| CAPACITY OF | |
| Breathing air cylinders | F 1001.1 |
| Graywater systems | 1502.2.1 |
| Interceptors | 1014.2.1 |
| Irrigation field and mulch basin | 1502.10.2, 1502.11.1.2, 1502.11.2.2, Table 1502.10 |
| Medical air compressors | 1314.2, 1315.4, 1316.2.1 |
| Rectangular scuppers | D 104.0 |
| Sewage ejectors or pumps | 710.3 |
| Sump pump | 1101.6.2 |
| Water heaters | 501.1, Table 501.1(1) |
| CAST-IRON PIPE | |
| Approved standards | 301.2.4 |
| Discharge line from ejectors | 710.4 |
| Drainage piping | 701.2 |
| Fittings | 301.2.3, 604.6, 1208.5.8.4 |
| Flanges | 1208.5.10.1 |
| Joining | 705.2, 705.9.1 |
| Prohibited use | 316.1, 1208.5.2 |
| CAULKED JOINTS | 705.2.1 |
| CAULKING FERRULES | 701.6, Table 701.6 |
| CERTIFICATION | |
| Backflow assembly testers | 205.0, 603.2 |
| Medical gas or medical vacuum installers | 1306.0 |

Medical gas or medical vacuum systems1320.0
 Pipe welder, definition225.0
 Residential fire sprinklers installers612.1
CESSPOOLH 801.1
 Abandoned722.0, H 1101.0
 Connections to sewer prohibited714.3
 Definition205.0
CHECK VALVES
 In drainage systems710.4, 710.12.1, 710.13.2, 1004.2
 In firefighter breathing air replenishment systemsF 501.7, F 601.5.1, F 701.3
 In fuel gas systems1208.8.1
 In medical gas and medical vacuum systems1314.1.4.2, 1315.5.4
 In water supply systems603.3, 608.3, Table 603.2
CHEMICAL RESISTANT GLASS PIPE811.2
CHEMICAL WASTES205.0, 811.0
CHIMNEYS509.5
 Cleanouts509.5.6.2, 509.5.9
 Decorative Shrouds509.5.1.1, 509.5.4.3
 Definition205.0
 Existing509.5.6, 509.5.6.3
 Factory-built509.5.1
 Masonry509.5.3
 Metal509.5.2
 Size509.5.5
 Support509.5.8
 Termination509.5.4
CHLORINATED POLYVINYL CHLORIDE (CPVC) PIPE OR TUBING
 Approved standards, water supplyTable 604.1
 Definition205.0
 Joining and connections(see Joints and connections)
 Medical vacuum system1308.5
 Residential sprinklers612.4.2, Table 612.5.3.2(6), Table 612.5.3.2(7)
CHLORINATED POLYVINYL CHLORIDE/ALUMINUM/CHLORINATED POLYVINYL CHLORIDE (CPVC-AL-CPVC) PIPE OR TUBING
 Approved standards, water supplyTable 604.1
 Joining and connections(see Joints and connections)
CIRCUIT VENTING911.0
CLARIFIERS205.0, 1009.0
CLEANOUT PLUGS OR CAPS707.1–707.3, 707.13, 1106.2
CLEANOUTS
 Access707.8, 719.5, 801.3.2

Building sewer719.0
 Change of direction707.4, 719.1, 801.3.2, 803.3, 1002.3
 Clearances707.8, 707.9
 Condensate drain814.3.1
 Cover plate707.8
 Direction of flow707.5, 719.4
 Horizontal drains707.4, 719.1
 Manholes719.6
 Plugs707.1, 707.2, 707.12
 Prohibited use of316.1
 Size707.1, Table 707.1
 Soil or drain pipes317.1
 Where required707.4, 719.1, 801.3.2, 803.3, 909.1, 910.6, 1002.3, 1008.1, 1017.1, 1101.13.1, E 207.1
CLEARANCE
 Cleanouts707.8, 707.9
 Fuel gas vents509.7.3.4, Table 509.7.3.4(1), Table 509.7.3.4(2)
 Water heaters504.3.1, 504.3.2
CLEAR WATER WASTE
 Definition205.0
 Discharge812.1
CLINICAL SINKS205.0, 413.1, 1303.7
CLOSET BENDS310.3, 402.6.1
CLOSET RINGS402.6.1
CLOSET SCREWS402.6.2
CODE, DEFINITION205.0
COMBINATION WASTE AND VENT SYSTEMS205.0, 910.0, Appendix B
COMBUSTIBLE MATERIAL, DEFINITION205.0
COMBUSTIBLE PIPING INSTALLATIONS1404.0
COMBUSTION AIR506.0
COMMON VENT, FUEL GAS509.6.4
COMPRESSION JOINTS605.7.1.1, 605.10.1.1, 705.2.2, 719.6, 1208.5.9.3
CONCEALED SLIP JOINTS402.10
CONCEALING OF WORK PROHIBITED BEFORE INSPECTION105.1, 105.2.1.1, 105.2.1.2, 503.2, 1203.2
CONDENSATE WASTE AND CONTROL814.0–814.7
CONDENSATE PUMPS814.1.1
CONDENSERS AND SUMPS810.0
CONDUCTORS, STORM WATER205.0, 1101.12.1, 1101.13.1, 1101.16, 1103.0, 1602.6, 1602.7.2, 1602.9.7, K 103.2, K 104.6, K 104.12, L 503.2, L 504.6, L 504.12

| | |
|--|---|
| CONTAMINATION | 205.0, 602.2, 602.3, 603.1, 811.1, 1309.2.6.8, 1309.3.8.4, 1309.3.8.7, C 302.1, F 1101.3 |
| CONTINUOUS VENT, DEFINITION | 205.0 |
| CONTINUOUS WASTES | |
| Definition | 205.0 |
| Materials | 407.5, 701.4 |
| CONTROL VALVES | 408.3, 408.9, 606.5–606.7, 1303.1 |
| COOLING WATER | 808.0 |
| COPPER OR COPPER ALLOY | |
| PIPE OR TUBING | |
| Fuel gas | 1208.5.2.2, 1208.5.3.2 |
| Joining and connections | (see Joints and connections) |
| Medical gas and medical vacuum | 1308.4, 1308.5, 1309.3.7.3, 1310.5.2 |
| Penetrating framing members | 312.9 |
| Prohibited use of | 811.1, 1208.5.3, 1208.5.3.2 |
| Standard weight | 302.1 |
| Underground drainage and vent | 903.2 |
| Water supply | 604.3, 604.4, A 105.2, E 310.1 |
| CRITICAL CARE AREA, DEFINITION | 205.0 |
| CRITICAL LEVEL | 205.0, 603.5.1, 603.5.2, 603.5.5, 603.5.13, C 501.3, Table 603.2 |
| CROSS-CONNECTION CONTROL | 603.0 |
| CROSS-LINKED POLYETHYLENE (PEX) | |
| PIPING OR TUBING | |
| Approved standards, water supply | Table 604.1 |
| Definition | 218.0 |
| Flexible connectors | 604.13 |
| Joining and connections | (see Joints and connections) |
| Residential sprinklers | 612.4.2, Table 612.5.3.2(8), Table 612.5.3.2(9) |
| CROSS-LINKED POLYETHYLENE-ALUMINUM- CROSSLINKED POLYETHYLENE (PEX-AL-PEX) | |
| PIPING OR TUBING | |
| Approved standards, water supply | Table 604.1 |
| Definition | 218.0 |
| Flexible connectors | 604.13 |
| Joining and connections | (see Joints, and connections) |
| Residential sprinklers | 612.4.2 |
| – D – | |
| DESIGN FLOOD ELEVATION | 206.0, 301.4 |

| | |
|---|--|
| DEVELOPED LENGTH | |
| Bar and fountain sink trap | 801.4 |
| Definition | 206.0 |
| DWV piping | 707.4, 710.13.2, C 401.0 |
| Indirect waste piping | 801.3.1 |
| Trap arm | 1002.2, Table 1002.2 |
| Water supply piping | 610.9, A 104.4, A 107.2 |
| Wet vent | 908.1 |
| DIELECTRIC INSULATORS | 507.1 |
| DISHWASHING MACHINES | 414.0 |
| Air gap | 807.3 |
| Approved standards | 414.1 |
| Backflow protection | 414.2 |
| Discharge, drainage | 414.3, 807.3, 1014.3.2 |
| Drainage discharge, prohibited | 419.2, 1014.1.3 |
| Drainage fixture unit (DFU) | Table 610.3 |
| Energy efficiency | L 403.1 |
| Flexible connector length | 604.12 |
| Water supply fixture units (WSFU) | Table 610.3, Table A 103.1, Table C 303.1(1) |
| DISPOSAL FIELDS | 1502.10.3, Appendix H |
| DOSING TANKS | H 601.8 |
| DRAINAGE SYSTEM | |
| Cleanouts | 707.0, 719.0 |
| Change in direction | 706.0 |
| Damage to public sewer or private sewage disposal system | 305.1, 714.0 |
| Definition | 206.0 |
| Fixture units | Table 702.1 |
| Independent systems | 311.0 |
| Indirect waste | Chapter 8 |
| Joints and connections | 705.0 |
| Materials | 701.2, 715.0, Table 701.2 |
| Obstruction of flow | 310.5 |
| Sizing | 702.0, 703.0, 717.0, Table 702.1, Table 703.3, Table 717.1 |
| Slope of piping | 708.1 |
| Sumps and ejectors | 710.0 |
| Testing | 712.0, 723.0 |
| Waste detrimental to | 306.0, 811.1, 1012.1 |
| DRINKING FOUNTAINS | 206.0, 415.0, 809.0, E 803.1 |
| DUCTILE IRON PIPE | 605.4, Table 604.1 |
| DURHAM SYSTEM, DEFINITION | 206.0 |
| – E – | |
| EFFECTIVE GROUND-FAULT | |
| CURRENT PATH, DEFINITION | 207.0 |
| EFFECTIVE OPENING | 207.0, Table 603.3.1 |
| EJECTORS | 710.2–710.5, 710.9–710.12 |

| | |
|--------------------------------------|---|
| Installation | 1210.0 |
| Interconnections | 1208.3, 1214.0 |
| Joints and fittings | 1208.5.4–1208.5.9, 1213.2.1, 1213.2.2 |
| Materials | 1208.5, E 409.0 |
| Obstruction of flow | 1210.12 |
| Purging | 1213.6 |
| Sizing | 1208.4, 1215.1, 1216.0, E 408.0, Table 1216.2(1)–Table 1216.2(36) |
| Supports | 1210.2.4, Table 1210.2.4.1 |
| Underground installation | 1208.5.2.3, 1208.5.3.3, 1210.1, E 401.2, E 409.3, E 410.3 |
| Venting | 1208.7.5 |
| FUEL GAS VENTS | |
| Appliances not requiring vents | 509.2.1 |
| Caps | 509.6.2.5, 509.7.4.3 |
| Clearance | 509.7.3.4, Table 509.7.3(1), Table 509.7.3(2) |
| Dampers | 509.12, 509.13, 509.13.1 |
| Direct vent | 509.2.4 |
| General requirements | 509.0 |
| Insulation shield | 509.6.2.7 |
| Integral | 509.2.5 |
| Listing | 509.1 |
| Mechanical draft | 509.3.3–509.3.3.5 |
| Obstruction of flow | 509.14 |
| Plastic piping | 509.4.1 |
| Special | 509.4.3 |
| Termination | 509.6.2–509.6.2.6, 509.7.2, 509.8 |
| Wall penetrations | 509.8 |
| FUEL GAS VENT, SIZING | |
| Category I appliances | 509.6.3.1, 510.0 |
| Multiple appliances | 510.2, Table 510.2(1)–Table 510.2(9) |
| Multistory | 509.6.4, 509.6.4.2, 510.2.12–510.2.15 |
| Single appliance | 509.7.4.1, 509.10.2.1, 510.1, Table 510.1.2(1)–Table 510.1.2(6) |

– G –

| | |
|--|---------------------------|
| GANG OR GROUP SHOWERS | 209.0, 408.3, 408.8 |
| GARBAGE GRINDER | (see Food waste disposer) |
| GENERAL CARE AREA, DEFINITION | 209.0 |
| GRADE | |
| Building sewer | 718.1 |
| Definition | 209.0 |
| Horizontal drainage | 708.0 |
| GRAVITY DRAINAGE REQUIRED | 709.0 |
| GRAY WATER, DEFINITION | 209.0 |

| | |
|----------------------------------|--|
| GRAY WATER DIVERTER | |
| VALVE, DEFINITION | 209.0 |
| GRAY WATER SYSTEMS | 601.3.3, 1501.5.2, 1501.6, 1502.0, Table 1501.5 |
| GREASE INTERCEPTORS | |
| Approved standards | 1014.1 |
| Definition | 209.0 |
| Capacity | 1014.2.1, Table 1014.2.1 |
| Gravity-type | 1014.3, Table 1014.3.6 |
| Hydromechanical-type | 1014.2 |
| Not required | 1014.1.3 |
| Required | 1010.1, 1014.1, H 101.3 |
| GRINDER PUMPS | 710.12 |

– H –

| | |
|--|---|
| HANDHELD SHOWERS | 417.3 |
| HANGERS | (see Supports) |
| HARMFUL WASTES | (see Wastes, detrimental or harmful) |
| HEALTH AND SAFETY | 101.3, 102.5 |
| HEAT EXCHANGERS | 505.4.1, 603.5.4, C 302.0 |
| HEAT-FUSION WELD JOINTS | 210.0, 605.6.1, 605.11.1, 1208.5.9.2 |
| HORIZONTAL BRANCH, DEFINITION | 210.0 |
| HORIZONTAL PIPE, DEFINITION | 210.0 |
| HORIZONTAL-TO-HORIZONTAL | |
| DRAINAGE FITTINGS | 706.3 |
| HORIZONTAL-TO-VERTICAL | |
| DRAINAGE FITTINGS | 706.2 |
| HOT-MOPPED SHOWER PANS | (see Shower, pans) |
| HOT WATER SUPPLY PIPING | 601.2, 609.1, 609.4, 609.11, 610.3, 610.12.1, 619.11, L 601.0, L 602.0, L 603.0 |
| HOUSE DRAINS | (see Building drain) |
| HOUSE SEWERS | (see Building sewer) |

– I –

| | |
|---|---|
| IDENTIFICATION | |
| Cast-iron soil pipe | 701.2 |
| Copper tubing | 604.4 |
| Fuel gas piping | 1208.6.4 |
| Medical gas and medical vacuum systems | 1308.4, 1310.11–1310.11.2, 1312.9 |
| Piping, fittings, traps, and fixtures | 301.2.1 |
| Water, nonpotable and potable | 601.3 |
| INCREASERS AND REDUCERS | 316.0 |
| INDIRECT-FIRED WATER HEATERS | 211.0, 505.4, 603.5.4, 608.7 |

| | |
|---|---|
| INDIRECT WASTE | Chapter 8 |
| Air gap or break | .801.2 |
| Appliances | .807.0 |
| Approval required | .802.0 |
| Aspirators | .603.5.9, 1303.5 |
| Chemical wastes | .811.0 |
| Cleanouts | .801.3.2, 803.3 |
| Clear water wastes | .812.0 |
| Condensate | .814.1, 814.1.1, 814.5 |
| Food handling fixtures | .801.3.3 |
| High temperature discharge | .810.1 |
| Interceptor | .902.1 |
| Receptors | .801.4, 804.0 |
| Sterile equipment | .801.6, 806.0, 1303.4.1 |
| Swimming pools | .813.0 |
| Traps | .801.3.2, 803.3, 814.5 |
| Vents | .803.3 |
| Where required | .801.2 |
| INDIVIDUAL VENTS | .211.0, 904.1, 908.2.1, C 601.6, Table 703.2 |
| INDUSTRIAL WASTES | |
| Access | .811.4 |
| Approval required | .811.1 |
| Definition | .211.0 |
| Disposal | .306.0, 811.7 |
| Materials | .811.2, 811.3, 903.2.2 |
| Pretreatment required | .306.1, 811.1 |
| Prohibited material | .811.1, 903.2.2 |
| Vents | .811.6 |
| INSANITARY | |
| Defective systems | .105.3.1 |
| Definition | .211.0 |
| Health and safety | .102.5 |
| INSPECTION AND TESTING | .105.0 |
| Alternative engineering design | .301.3.1–301.3.1.2, 301.5.6, |
| Final | .105.2 |
| Reinspection | .105.2.6 |
| Required | .105.1, 105.2, 1203.0, 1213.1, 1309.3.10 |
| Rough-in | .105.2, 1203.3.1 |
| Scheduling of | .105.2.3 |
| Testing | .105.3 |
| INSPECTOR | (see Authority Having Jurisdiction) |
| INSULATION | |
| Domestic hot water supply | .609.11, L 601.2 |
| Fuel gas vent | .509.6.2.7 |
| Penetrating firestop system | .1404.5, 1405.7 |
| Pool covers | .L 603.3.6.2 |
| Service hot water | .L 603.3.3, Table L 603.3.3 |
| Tracer wire | .604.10.1, E 410.3 |
| INTERCEPTING HOPPERS OR SINKS .. | (see Receptors) |
| INTERCEPTOR (CLARIFIER) | |
| Abandoned | .1014.3.7 |
| Auto wash racks | .1011.0 |
| Bottling establishments | .1013.0 |

| | |
|---|---------|
| Cleanouts, location | .707.7 |
| Commercial and industrial laundries | .1012.0 |
| Definition | .211.0 |
| Grease | .1014.0 |
| Industrial | .1009.0 |
| Oil and flammable liquid | .1017.0 |
| Packing establishments | .1010.0 |
| Sand | .1016.0 |
| Slaughterhouses | .1010.0 |
| Vents | .902.1 |

INTERMIXING OF

| | |
|--|---------------|
| METALS PROHIBITED | .310.6, 604.1 |
| INVERT, DEFINITION | .211.0 |
| IRON PIPE SIZE (IPS) PIPE | .302.0 |
| ISLAND FIXTURE, VENTING | .909.0 |

– J –

JOINTS AND

| | |
|--|--|
| CONNECTIONS | .315.0, 605.0, 705.0, 1208.5.8–1208.5.10.2, 1309.0 |
| ABS | .705.1 |
| Asbestos cement pipe | Table 1101.4.6 |
| Brazed joint | .212.0, 605.1.1, 609.3, 705.3.1, 705.9.1, 705.9.2, 1208.5.8.1, 1208.5.8.2 |
| Cast-iron piping | .604.6, 701.2, 705.2, 705.9.1 |
| Caulked joint | .705.2.1 |
| Compression joint | .605.6.2, 605.7.1, 605.8.1, 605.10.1.1, 605.11.2, 705.2.2, 1208.5.9.3 |
| Copper or copper alloy pipe or tubing | .605.1, 705.3, 705.9.1, 705.9.2 |
| CPVC piping | .605.2 |
| CPVC-AL-CPVC piping or tubing | .605.3 |
| Ductile iron piping | .605.4 |
| Expansion joint | .705.8.2, 1101.5, 1213.2.2 |
| Flared | .605.1.2, 1208.5.8.3, 1208.5.8.4 |
| Galvanized steel pipe | .605.5, 705.4 |
| Ground joints | .705.8.3 |
| Heat-fusion joints | .210.0, 605.6.1, 605.11.1, 1208.5.9.2 |
| Lead content | .604.2 |
| Mechanical joints | .605.1.3, 605.2.1, 605.4.1, 605.5.1, 605.6.2, 605.7.1, 605.9.2, 605.10.1, 605.11.2, 605.12.1, 605.13.1, 605.16.3, 705.1.1, 705.2.2, 705.3.2, 705.4.1, 705.5.1, 705.6.1, 705.7.1, 705.9.4, 1208.5.9.3 |
| PE pipe or tubing | .605.6, 1208.5.4 |

| | |
|---|--|
| Cleanouts | 707.1 |
| Drainage piping, joints, and fittings | 701.2, 701.3, 705.0, Table 701.2 |
| Fuel gas piping, joints, and fittings | 1208.5–1208.5.1.1, 1208.5.2–1208.5.4, 1208.5.7, 1208.5.8, 1208.5.9 |
| Marking of | 301.2.1 |
| Medical gas and medical vacuum | 1308.0 |
| Potable water piping, joints, and fittings | 604.0, 605.0 |
| Rainwater catchment system | 1602.7 |
| Septic tanks | H 501.3 |
| Storm drainage pipe | 1101.4 |
| Subsoil drain | 1101.4.6 |
| Sumps or receiving tanks | 710.8 |
| Traps | 1003.1 |
| Vents (DWV) | 903.0, Table 701.2 |
| MAY, DEFINITION | 215.0 |
| MEAT PACKING AND SLAUGHTERHOUSES | 1010.0 |
| MEDICAL GAS AND MEDICAL VACUUM SYSTEMS | Chapter 13 |
| Alarms | 1318.0 |
| Aspirators | 1303.5 |
| Cleaning | 1308.2, 1311.0 |
| Construction documents | 1304.5 |
| Definitions | 215.0 |
| Installation requirements | 1304.0, 1310.0 |
| Joints and connections | 1309.0 |
| Labeling and identification | 1310.11 |
| Materials | 1308.0 |
| Medical air systems | 1314.0 |
| Medical vacuum systems | 1315.0 |
| Pipe sizing | 1310.2, Table 1310.2.1(1)–Table 1310.2.1(4) |
| Pressure-regulating equipment | 1316.0 |
| Shutoff valves | 1312.0 |
| Station outlets/inlets | 1317.0 |
| Sterilizers and bedpan steamers | 1303.4 |
| System certification | 1320.0 |
| Testing and inspection | 1319.0 |
| Warning system | 1318.0 |
| METALS, INTERMIXING PROHIBITED | 310.6, 604.1 |
| METERING FAUCETS | 407.2.2 |
| MINIMUM STANDARDS | 301.2 |
| MULCH, DEFINITION | 215.0 |
| MULCH BASIN | 215.0, 1502.9.4, 1502.10.1, 1502.11 |

– N –

| | |
|--|------------|
| NATURAL GAS, SPECIFIC GRAVITY | 1215.1 |
| NITROGEN, NF, DEFINITION | 216.0 |
| NONCOMBUSTIBLE PIPING INSTALLATIONS | 1405.0 |
| NONPOTABLE WATER | |
| Alternate water source | Chapter 15 |
| Identification | 601.3 |

| | |
|----------------------------------|--------------------|
| Rainwater catchment system | Chapter 16 |
| Unlawful connections to | 603.5.11, E 703.1 |
| NONWATER URINALS | 412.1.1, L 402.3.1 |
| NUISANCE | 102.5, 216.0 |

– O –

| | |
|---|--|
| OBSTRUCTIONS | |
| OF FLOW | 310.5, 315.2 |
| OFFSETS | |
| Definition | 217.0 |
| Drainage | 706.4, C 304.3.1, C 304.3.2, C 304.4, C 401.4, C 601.7 |
| Medical gas | 1309.2, 1309.3 |
| Prohibited use | 402.6.3 |
| Venting (fuel gas) | 509.6.3.2, 510.1.2, 510.2.4, 510.2.15 |
| Venting (plumbing) | 910.5 |
| OIL AND FLAMMABLE INTERCEPTORS | 1017.0 |
| ON-SITE TREATED NONPOTABLE WATER SYSTEMS | 217.0, 601.3.3, 1504.0 |
| OPEN TRENCH WORK | 314.3 |
| OPENING, EFFECTIVE, DEFINITION | 207.0 |
| OVERFLOWS | 404.0, 413.5, 607.4, 1602.9.5.5, 1602.9.5.1 |

– P –

| | |
|---|---|
| PATIENT CARE ROOM, DEFINITION | 218.0 |
| PENALTIES | 106.0 |
| PENETRATION FIRESTOP SYSTEMS | 218.0, 1404.3, 1405.3 |
| PERCOLATION TESTS | 1502.10.2, H 401.0 |
| PERMITS, REQUIRED | 104.1, 502.1, 1501.3, 1503.2, E 311.1, K 101.3, L 501.3 |
| PERMITS FEES | 104.5, Table 104.5 |
| PIPING | |
| Drainage, changes in direction | 706.0 |
| Drainage, existing sewers | 715.3 |
| Drainage, horizontal slope | 708.0, 718.1 |
| Drainage, material | 701.2, 715.1, 720.1, Table 701.2 |
| Exposed to sunlight, ABS and PVC | 312.13, 312.14 |
| Fuel gas | 1208.0, 1210.0 |
| Hangers and supports | 313.0, 1210.2.4, 1210.2.4.1, 1310.5–1310.5.5, Table 313.3, Table 1210.2.4.1, Table 1310.5.4 |
| Identification | 601.3 |
| Indirect waste | 803.0 |
| Joints and connections ... (see Joints and connections) | |
| Medical gas, material | 1308.0 |

Plumbing vent, material903.0, Table 701.2
 Protection of312.0, 718.3, 1210.1.3–1210.1.5
 Rehabilitation of320.0
 Sprinkler system612.4, 612.5
 Storm drainage, materials1101.4–1101.4.6
 Trenching, excavation, and backfill314.0
 Underground314.4.1, 1210.1.6
 Water supply, material604.0, Table 604.1.2
PITS, SEEPAGE221.0, 714.3, 716.1,
 722.2–722.4, Appendix H
PLUGS, CAPS, CLEANOUT707.1, 707.2
PLUMBING
 Additions, alterations,
 renovations or repairs102.4
 Appliances218.0, 304.1, 310.5, 313.1, 417.2,
 603.4.6, 606.5, 801.7, 803.3, 806.1,
 807.0, 808.1, L 302.2,
 Table 610.3, Table 702.1,
 Table A 103.1
 Appurtenances218.0, 304.1, 313.1, 603.4.6,
 L 602.5, Table 610.3,
 Table 702.1, Table A 103.1
 Connected to sewer or private
 disposal systems304.1, 713.1, L 302.2
 Definition218.0
 Inspection of105.0
 Official(see Authority Having Jurisdiction)
 System, definition218.0
 Tests105.3, 105.3.1
 Uncovered for inspection105.2.1
 Vent, definition218.0
 Vent system, definition218.0
PLUMBING FIXTURES
 Access402.1, 413.2, 416.4, 422.4
 Accessibility403.1, 403.2, 408.5, 408.6
 Alternate materials301.3, 406.3
 Approved standards401.2, 408.1, 409.1, 410.1,
 411.1, 412.1, 415.1, 416.1
 417.1–417.4, 418.1, 420.1
 Back-to-back704.2
 Below curb or sewer level710.1, 710.2
 Clearance from wall, toilet, urinal402.5
 Connections, drainage304.1, 406.1, 408.4,
 409.2, 415.3, 416.5,
 419.2, 420.4, 704.0
 Control valves408.3, 408.9, 601.2, 606.5–606.7,
 1303.1, 1503.8, 1504.9
 Definition218.0
 Distance from traps1001.2, 1002.2, Table 1002.2
 Fixture units610.3, 610.7–610.10,
 702.0, 703.0,
 C 501.4, C 501.5,
 Table 610.4, Table 610.10,
 Table 702.1, Table 702.2(1),
 Table 702.2(2), Table 703.2,
 Table A 103.1, Table C 303.1(1),
 Table C 303.1(2)

Floor drains408.7, 414.3, 418.0, 704.3,
 801.3.2, 1003.1, 1006.0, 1007.1,
 1014.3.2, 1016.1, 1017.1, 1101.11,
 1503.1, 1504.1, 1602.1, B 101.5,
 B 101.6.1, E 605.1
 Improper location of308.0
 Indirect wastes804.1
 Installation of402.0, 405.3, 408.3,
 408.7, 409.3, 409.6,
 412.1.1, 413.1–413.3, 413.5,
 415.4, 416.3, 418.3
 Islands909.0
 Joints402.2
 Material of401.0, 406.2–406.4, 408.7
 Minimum number422.0
 Must be connected to sewer304.1, 713.1
 Must be provided with trap1001.2
 Overflows404.0
 Prohibited310.5, 405.0, 910.7
 Quality401.2
 Setting402.5, 402.6
 Size of waste for702.0, 703.0,
 Table 702.1, Table 703.2
 Special fixtures406.0
 Strainers and connections407.5, 408.4
 Supply fittings402.7
 Waste connections407.5, 408.4, 409.2,
 415.3, 416.5, 419.2, 420.4
 Water supply required601.2
POLLUTION218.0, 603.1,
 714.5, Table 603.2

POLYVINYL CHLORIDE (PVC)

PIPE OR TUBING

Approved standards,
 water supply and DWVTable 604.1, Table 701.2
 Definition218.0
 Exposed to sunlight312.14
 Flexible tubing for whirlpool bathtubs409.61
 Joining and connections(see Joints
 and connections)
 Lining for shower receptors408.7
 Roof drains1102.1

POLYETHYLENE (PE) PIPE OR TUBING

Approved standards,
 water supply and DWVTable 604.1,
 Table 701.2
 Definition218.0
 Fuel gas1208.5.4,
 Table 1216.2(19)–Table 1216.2(23),
 Table 1216.2(34)–Table 1216.2(36)
 Joining and connections(see Joints
 and connections)
 Roof drains1102.1

POLYETHYLENE-ALUMINUM-POLYETHYLENE**(PE-AL-PE) PIPE OR TUBING**

| | |
|----------------------------------|------------------------------|
| Approved standards, water supply | Table 604.1 |
| Definition | 218.0 |
| Joining and connections | (see Joints and connections) |

POLYETHYLENE OF RAISED**TEMPERATURE (PE-RT) PIPE OR TUBING**

| | |
|----------------------------------|------------------------------|
| Approved standards, water supply | Table 604.1 |
| Definition | 218.0 |
| Flexible connectors | 604.13 |
| Joining and connections | (see Joints and connections) |

POLYPROPYLENE (PP) PIPE OR TUBING

| | |
|----------------------------------|------------------------------|
| Approved standards, water supply | Table 604.1 |
| Chemical waste | 811.2 |
| Definition | 218.0 |
| Joining and connections | (see Joints and connections) |
| Roof drains | 1102.1 |

POLYVINYLIDENE FLUORIDE (PVDF)**PIPE OR TUBING**

| | |
|----------------|-------|
| Chemical waste | 811.2 |
| Definition | 218.0 |

POTABLE RAINWATER**CATCHMENT SYSTEMS** Appendix K, L 501.0, L 502.0, L 503.4, L 504.13**POTABLE WATER**

| | |
|------------------------|---|
| Connections | 603.4.4, 603.5.6, 603.5.7, 603.5.10–603.5.12, 603.5.14, 603.5.20, 801.5, 1303.5 |
| Definition | 218.0 |
| Devices or assemblies | 603.2 |
| Disinfection | 609.9 |
| Protection from | |
| heat transfer medium | 505.4.1, C 302.2 |
| Heating | 501.1, L 601.1 |
| Identification | 601.3 |
| Joints and fittings | 604.2, 604.6, 605.0 |
| Materials | 604.1, Table 604.1 |
| Outlets | 603.5.17 |
| Protection of | 602.0, 603.0 |
| Sizing piping | 610.0, Appendix A |
| Supply required | 601.2, E 301.1 |
| Tanks | 607.0 |
| Unlawful connection to | 602.0, 603.5.11, 1502.3, 1503.4, 1504.4, 1602.4, K 102.2, L 502.2, E 703.1 |
| Valves | 606.0 |

PRE-RINSE SPRAY VALVES 420.3, L 201.0**PRESSED FITTINGS** 218.0, 605.1.3, 605.1.3.2, 605.13.1, 605.16.1, 705.6.1**PRESSURE DRAINAGE****CONNECTIONS** 805.0**PRESSURE, EXCESSIVE, WATER** 608.2**PRESSURE-LOCK-TYPE****CONNECTION, DEFINITION** 218.0**PRESSURE LOSSES, WATER** 610.2**PRESSURE REGULATORS**

| | |
|---|---|
| Firefighter breathing air replenishment systems | F 501.8 |
| Fuel gas | 507.20, 507.21, 507.22, 1202.1, 1208.8.1, 1210.6, 1210.11, 1216.1.3 |
| Medical gas and medical vacuum | 1309.3.8.2, 1313.1.2 |
| Water | 608.2 |

PRESSURE-RELIEF VALVES

| | |
|---|---------------------------|
| Definition | 224.0 |
| Differential, backflow prevention | 603.3.7, Table 603.2 |
| Discharge | 608.5 |
| Firefighter breathing air replenishment systems | F 501.1, F 501.8, F 701.3 |

| | |
|--------------------------------|-----------------------------------|
| Medical gas and medical vacuum | 1313.1.2, 1314.2, 1316.2–1316.2.3 |
|--------------------------------|-----------------------------------|

| | |
|---------------|---------------------|
| Water Heaters | 504.4, 504.6, 505.2 |
|---------------|---------------------|

| | |
|--------------|----------------------|
| Water Supply | 608.2–608.4, E 308.1 |
|--------------|----------------------|

PRIMARY SETTLING TANKS 902.1**PRIVATE OR PRIVATE USE, DEFINITION** 218.0**PRIVATE SEWAGE**

| | |
|----------------------|--|
| Capacity of system | H 101.7, H 201.0, H 701.1 |
| Construction | H 501.3, H 601.9, H 701.3, H 801.3 |
| Definition | 218.0 |
| Design | H 101.6, H 501.2, H 501.11, H 901.4, H 901.7 |
| Disposal systems | 218.0, 713.2, Appendix H |
| General requirements | H 101.2 |
| Inspections | 105.0 |
| Location | 721.0, H 101.8, Table H 101.8 |

PRIVATE WATER SUPPLY 602.2, 602.4, E 301.1**PROHIBITED**

| | |
|---------------------------------------|--|
| Appliances | 310.5 |
| Concealed gas piping | 1210.3.2, 1212.3.1, 1212.4.3, 1310.7 |
| Concealment of defects | 309.2 |
| Concealment of work before inspection | 105.0, 503.2, 1203.0, 1406.1 |
| Connections | |
| Sewer | 714.3 |
| Waste | 310.3, 404.1, 603.4.4, 805.1, 807.3, 810.1 |
| Water | 602.0, 603.4.4, E 703.1 |
| Copper tubing, use of | 903.2.2, 1208.5.2.2 |
| Damage to drainage system | 305.1, 312.3, 312.6 |

| | |
|---|---|
| Devices | 310.5, 1210.12 |
| Direct drainage | 603.4.4, 805.1, 807.3, 810.1 |
| Discharge | 509.1.2, 714.2, 1602.9.3.2, K 104.1.1, L 504.1.1 |
| Fittings | 310.0, 315.2, 604.2 |
| Fixtures | 310.5, 405.0 |
| Food waste disposal, connection to | 1014.1.3 |
| Fuel gas piping | 1208.5.2.3, 1210.2.3 |
| Industrial waste disposal | 306.2 |
| Installations | 312.2, 602.1 |
| Joints and connections | 315.2, 605.1.4, 605.6.2, 1309.3.10.3, 1309.6 |
| Locations | 415.4, 1210.2.3, 1502.6 |
| Materials | F 801.4, H 501.10, H 501.13, K 103.1.1, L 503.1.1 |
| Medical gas and medical vacuum piping | 1310.4.1 |
| Oxygen | 1213.1.6 |
| Pipes in concrete or masonry | 312.2 |
| Practices | 102.4.1, 104.1, 106.0, 303.1, 305.1, 309.2, 310.0, 312.2, 312.6, 502.1, 602.0, 714.1, 1101.3, 1204.3, 1205.0, 1206.3, 1501.3, 1503.2, K 101.3, L 302.1, L 501.3 |
| Receptors, location of | 804.1 |
| Systems | 310.4 |
| Traps | 1004.0 |
| Trough type urinals | 405.2, E 607.1 |
| Urinals and water closets on a combination waste and vent system | 910.7 |
| Vent termination | 906.3 |
| Water piping | 312.6, 604.2, 720.1 |
| PROPERTY LINE, TERMINATION OF VENT | 906.2 |
| PROTECTION FROM | |
| Corrosion | 312.1, 312.4, 402.3, 402.6.2, 402.6.3, 506.9, 507.5, 508.1.2, 509.5.3, 509.7, 509.10.1, 509.10.1.2, 509.10.1.3, 603.5.14.1, 603.5.14.2, 609.3, 710.4, 710.8, 810.2, 811.2, 814.1, 1004.1, 1208.5.2.3, 1208.5.3.3, 1208.5.6, 1208.6.1.1, 1210.1.3, 1210.2, 1210.3.4, 1212.1, 1310.3, 1310.4, 1314.2, 1502.9.1, 1602.9.5.1, C 501.3, E 204.3, E 405.1, E 409.1, E 409.2, E 410.2.1, E 410.3, E 707.1, F 501.4, H 501.3, H 501.13, K 104.4.1, K 104.9.2, L 504.9.2 |
| Decay | 1502.9.1, 1602.9.5.1, H 501.3, K 104.4.1 |
| Freezing | 312.6, 603.4.7, 1210.1.4, 1210.8.1, 1602.9.9, K 104.8, L 504.8 |
| Seismic | 507.2, 1310.5.5 |

PROTECTION OF

| | |
|---------------------------------------|---|
| Fuel gas meters | 1208.6.1, 1208.6.3 |
| Piping materials and structures | 312.0, 314.4, 1210.1 |
| Potable water supply | 603.0 |
| Trap seals | 1002.0, 1005.1, 1007.0 |
| Water heaters | 504.3–504.6, 505.2, 507.2, 507.12–507.15 |

PUBLIC OR PUBLIC USE, DEFINITION 218.0

PUBLIC SEWER, DEFINITION 218.0

PUBLIC SHOWER FLOORS 408.8

PUSH FIT FITTINGS 218.0, 605.1.3,
605.1.3.3, 605.2.1

– Q –

QUALITY AND WEIGHT OF MATERIALS,

GENERAL REGULATIONS 301.2.1, 301.2.2,
301.3, 301.5

QUALITY OF FIXTURES 401.2

QUICK-DISCONNECT DEVICE, DEFINITION 219.0

– R –

RAINWATER, DEFINITION 220.0

RAINWATER CATCHMENT

SYSTEMS 220.0, 601.3.3, 1501.2, 1501.3,
1501.7, Chapter 16, Appendix K,
L 501.0, L 502.0,
L 503.2, L 504.1, L 504.5

RAINWATER STORAGE TANK, DEFINITION 220.0

REAMING PIPES 309.3, 605.1.1–605.1.2,
605.1.3.2, 605.1.3.3, 605.1.4, 609.1,
701.3.1, 705.3.1, 705.3.3, 903.3

RECEIVING TANKS OR SUMPS 710.2, 710.3,
710.7–710.10, 710.13.1

RECEPTORS

| | |
|----------------------|--|
| Definition | 220.0 |
| Indirect waste | 414.3, 801.2, 801.3.2, 801.3.3, 801.4, 801.6, 801.7, 804.0, 807.1, 810.4, 814.5, 902.2, 1303.4.1 |
| Shower | 408.1, 408.5–408.7 |

RECLAIMED (RECYCLED)

WATER SYSTEMS 220.0, 601.3.3, 1503.0

REDUCED PRESSURE DETECTOR FIRE

PROTECTION BACKFLOW

ASSEMBLY 603.3.9, 603.5.14
Table 603.2

REDUCERS 316.0

REFRIGERATORS 801.3

REGULATORS

| | |
|---------------------------------|--|
| Backpressure | 507.9 |
| Draft | 506.1.2, 509.11.3–509.11.5, 509.14 |
| Firefighter breathing air | F 501.8 |
| Fuel gas supply | 507.20–507.22, 1202.1, 1208.3, 1208.7–1208.8, 1210.4.1, 1210.6, 1210.11, 1213.1.5, 1214.0, 1215.1, 1216.1.3, E 413.3, E 413.4, E 413.5.2 |

| | |
|---|---|
| Medical gas and medical vacuum | 1309.3.8.2, 1313.1.2, 1314.1.2 |
| Water supply | 608.2 |
| RELIEF VENTS | 907.0, 911.4, B 101.4 |
| Connections | 805.1 |
| Definition | 220.0 |
| Interceptors | 1009.4 |
| REMOTE OUTLET, DEFINITION | 220.0 |
| REPAIRING | |
| Defective gas pipe, prohibited | 1208.5.5 |
| REPAIRS AND ALTERATIONS TO PLUMBING AND DRAINAGE SYSTEMS | 102.4 |
| REQUIRED | |
| Air gaps or air breaks | 801.2 |
| Appurtenances | 1503.10, 1504.10.3, 1602.9.2 |
| Area of subsurface irrigation fields and mulch basins | 1502.10.1 |
| Drainage or sewer connections | 304.1, 713.0 |
| Filters | 1504.10.5, 1602.9.11 |
| Flushing devices | 413.1 |
| Fuel gas pipe size | 1216.0 |
| Fuel gas supply | 1215.0 |
| Gravity drainage | 709.0 |
| Hot and cold water | 601.2 |
| Inspections | 1406.0, 1501.11.2.4, 1602.11.2.4 |
| Low-pressure cutoff | 609.8 |
| Medical gas and medical vacuum pipe size | 1310.2 |
| Permits | 104.0 |
| Plans | 103.3 |
| Plumbing fixtures | 422.0, Table 422.1 |
| Tests | 1501.11.2.4, 1503.5, 1504.5, 1602.5 |
| Vents | 901.2 |
| RESPONSIBLE FOR TESTING | 105.2.5 |
| RESTAURANT, GREASE INTERCEPTORS | 1014.1 |
| RETESTING | 105.3.2 |
| RISERS | |
| Fuel gas | 1208.5.4.2, 1210.1.7, 1210.3.4, E 403.1, E 404.1, E 409.2, E 413.3 |
| Medical gas and medical vacuum | 1310.4, 1310.11.2, 1312.4 |
| Sewer | E 1001.1, E 1003.1 |
| Water | 220.0, 408.10, 610.1, 1501.11.2.3, 1602.11.2.3, A 103.1, A 106.1, A 106.2, A 108.1, E 302.1, E 307.1, E 802.1, E 1104.1, L 603.3.7 |
| RODENTPROOFING | 312.12 |
| ROOF DRAINS | 220.0, 1101.12.1, 1101.12.2, 1101.15, 1106.2.1, K 104.6, L 504.6, Table 1101.12 |
| ROOF DRAINAGE | 1101.12, Appendix D |
| Combined | 1101.12.2.2.2 |
| Controlled-flow | 1105.0 |

| | |
|---|--|
| Primary | 1101.12.1 |
| Secondary | 1101.12.2 |
| Separate piping | 1101.12.2.2.1 |
| ROOF GUTTERS | 1101.12.1, 1103.3, 1602.6, 1602.7.2, 1602.9.7, 1602.9.12, K 103.2, K 104.6, K 104.11, L 503.2, L 504.6, L 504.11, Table 1103.3 |
| ROOF, TERMINATION OF VENTS ABOVE | 509.6.2, 905.4, 906.1, 906.3, 906.5, 906.7 |
| ROOF WASHERS | 220.0, K 104.9, L 504.9 |
| ROUGHING-IN, DEFINITION | 220.0 |

- S -

| | |
|---|--|
| SADDLE, SLEEVE, BAND OUTLETS, PROHIBITED | 310.1 |
| SAFETY AND HEALTH | 102.5 |
| SAFETY DEVICES | 504.4-504.6, 505.2, 603.0, 608.0 |
| SAND INTERCEPTORS | 1016.0 |
| Cleanout for | 707.7 |
| Construction and size | 1016.3 |
| Definition | 221.0 |
| Design | 1009.3 |
| Discharge | 1009.7, 1016.1 |
| Location | 1009.5 |
| Maintenance | 1009.6 |
| Required | 1009.1, 1016.1 |
| Vent, required and not required | 902.1, 1002.1, 1016.4 |
| Water seals | 1009.3, 1016.4 |
| SANITARY TEES, PERMISSIBLE USE | 706.2, C 601.3, C 601.4 |
| SCREW JOINTS | 1205.2, 1206.3 |
| SDR, DEFINITION | 221.0 |
| SEAL, TRAP | 222.0, 315.1, 412.1.1, 413.4, 901.3, 912.2, 1005.0, 1007.0, C 601.1, E 605.1 |
| SEAM, WELDED, DEFINITION | 221.0 |
| SECONDARY INTERCEPTORS | 902.1 |
| SECONDARY TEMPERATURE LIMITING DEVICE | 505.2 |
| SEDIMENT TRAPS | 1210.8.2, 1212.8 |
| SEEPAGE PITS | H 701.0 |
| Abandoned | 722.2 |
| Area of disposal | H 301.0 |
| Capacity | H 701.1 |
| Combination with disposal fields | H 601.4 |
| Connection to sewer prohibited | 714.3 |
| Construction | H 701.3 |
| Definition | 221.0 |
| Location | 721.0, H 101.8, Table H 101.8 |
| Markings | 716.1 |
| Multiple installations | H 701.2 |
| Soil absorption | H 301.1, Table H 201.1(3) |

| | |
|---|--|
| SELF-CLEANING TRAPS | 1003.1 |
| SEPARATE PLUMBING AND DRAINAGE SYSTEMS | 311.0 |
| SEPARATE VENTING | 811.6, 906.3 |
| SEPARATORS | 1009.0 |
| SEPTIC TANKS | |
| Abandoned | 722.2 |
| Capacity | H 201.0, Table H 201.1(1) |
| Connections | H 601.7 |
| Connections to sewer prohibited | 714.3 |
| Construction | H 501.0 |
| Definition | 221.0 |
| Location of | H 101.8, Table H 101.8 |
| Markings | 716.1 |
| Vents | H 501.8 |
| SERVICE, AUTHORITY TO RENDER GAS | 1205.0 |
| SETTING FIXTURES | 402.5 |
| SETTLING TANKS | 902.1 |
| SEWAGE | |
| Definition | 221.0 |
| Disposal of | 303.0, 709.0, 713.0, 714.0, 1014.1, 1502.2, E 201.1, E 901.1, L 302.1 |
| SEWAGE DISPOSAL SYSTEMS, PRIVATE | Appendix H |
| Abandoned | 722.2 |
| Commercial food waste grinders | 714.4 |
| Design | H 101.6 |
| Holding tank | 714.5 |
| Inspection and testing | H 1001.0 |
| Location | 307.0, 721.0, H 101.8, Table H 101.8 |
| Materials | 715.0 |
| Vents | 904.1 |
| SEWAGE EJECTOR | 221.0, 710.2, 710.3, 710.10 |
| SEWAGE PUMP | 221.0, 710.2, 710.3, 710.13 |
| SEWERS | Chapter 7 |
| Abandoned | 722.0 |
| Adjacent to walls | 312.3, 715.1, 718.3, Table 721.1 |
| Available | 713.2, 713.4 |
| Building, definition | 204.0 |
| Building, material of | 701.0, 715.0, Table 701.2 |
| Cleanouts | 719.0 |
| Connection to, required | 304.0, 713.0 |
| Construction of | 715.0–719.0 |
| Damage to | 305.1, 306.1, 714.1, 718.3, 811.1, 1009.1 |
| Depth of | 312.3, 718.3, 720.1 |
| Easements for | 721.2 |
| Ejectors | 710.2, 710.3, 710.10 |
| Existing | 102.4.1, 713.6, 715.3 |
| Grade and support of | 708.0, 718.0 |

| | |
|--|--|
| Gray water | 1502.2, 1502.9.1, 1502.9.6, 1502.9.7 |
| Independent system required | 311.0 |
| Inspections | 105.0 |
| Joints and connections | 705.0 |
| Location | 307.0, 312.3, 718.3, 720.0, 721.0, Table 721.1 |
| Materials | 701.0, 715.0, 720.1, Table 701.2 |
| Mobile home and recreational vehicle parks | E 201.1, E 311.1, E 601.1, E 603.1, E 901.1, E 904.0, E 1001.1, E 1002.0, E 1003.0 |
| Must be on same lot as building | 307.1, 721.1 |
| Private sewage disposal systems | 713.0, 714.0 |
| Prohibited connections | 603.4.4, 714.2, 714.3, E 707.1 |
| Reclaimed (recycled) water | 1503.11 |
| Required | 709.1, 713.0 |
| Size of building | 703.2, 710.5, 717.0, C 304.2, C 601.9, Table 702.1, Table 703.2, Table 717.1, Table C 304.2 |
| Storm water | 1101.3, 1101.16.2 |
| Support | 718.2 |
| Testing of | 723.0 |
| Vents | 904.1 |
| Water pipe in trench | 609.2, 720.0 |
| SHALL, DEFINITION | 221.0 |
| SHEET LEAD | 408.7, 408.7.3, 701.5, 906.6 |
| SHIELDED COUPLINGS | 221.0, 705.2.2, Table 313.3 |
| SHOCK ARRESTER, DEFINITION | 221.0 |
| SHORT TURN ¼ BEND, PROHIBITED | 310.5, 706.0 |
| SHOULD, DEFINITION | 221.0 |
| SHOWERS | |
| Approved standards | 408.1 |
| Control valves | 408.3, 601.2 |
| Finished curb or threshold | 408.5 |
| Gang | 209.0, 408.3, L 201.0, L 402.6.1 |
| Mobile home and recreational vehicle parks | E 612.0, E 613.0 |
| Pans | 408.7 |
| Public floors | 408.8 |
| Receptors | 408.6, 408.7 |
| Stall or compartment | 408.6 |
| Tests | 408.7.5 |
| Valve and head location | 408.9 |
| Valves | 417.2, 417.3 |
| Waste outlet or drains | 317.1, 408.4 |
| Water consumption | 408.2, L 402.6 |

SHUTOFF VALVES

| | |
|-----------------------------------|--|
| Fuel gas | .507.8, 509.5.7.1, 1208.10, 1210.2.2.1, 1210.9.1.1, 1210.11, 1212.3.1, 1212.3.2, 1212.4.3, 1212.5, 1212.6, 1212.8, 1213.2.5, 1213.6.1.3, E 403.0, E 404.3, E 410.4, E 412.3, E 413.5 |
| Medical gas and medical vacuum | .1312.1, 1312.1.2, 1312.9, 1312.9.2, 1313.1.2, 1314.1.2.1, 1314.1.2.1, 1315.2, 1315.2 |
| Sewage | .710.12.1, 710.13.2 |
| Water | .504.6, 606.2, 606.3, 608.4, 609.8, 1502.9.1 1602.9.5.5, E 306.0, E 1104.1, E 1201.1, K 104.4.3, L 402.3.1, L 504.4.3 |

SINGLE-FAMILY

| | |
|----------------------|--------|
| DWELLING, DEFINITION | .221.0 |
|----------------------|--------|

| | |
|---------------------------|----------|
| SINGLE-STACK VENT SYSTEMS | .C 601.0 |
|---------------------------|----------|

| | |
|--------------------|-----------------------|
| SINKS | .420.0 |
| Approved standards | .420.1 |
| Clinical | .205.0, 413.1, 1303.7 |
| Floor | .421.0, B 101.2 |
| Island | .909.1 |
| Laundry | .420.4 |
| Prohibited types | .405.3, B 101.2 |
| Service | .420.4 |
| Special use | .406.2 |
| Three-compartment | .1001.1 |

SIZE OF

| | |
|--------------------------------------|--|
| Building sewers | .703.0, 717.0, Table 702.1, Table 703.2, Table 717.1 |
| Cesspools | .Appendix H |
| Chimneys | .509.5.5 |
| Circuit venting | .911.0 |
| Combination waste and vent piping | .910.0, Appendix B |
| Combustion air openings | .506.3–506.5 |
| Condensate pipe | .814.3, Table 814.3 |
| Disposal fields | .Appendix H |
| Drainage piping | .703.0, C 304.0, E 206.0, E 302.0, E 903.0, Table 702.1, Table 703.2 |
| FOG disposal systems | .1015.3 |
| Fuel gas piping systems | .1208.4, 1215.0, 1216.0, E 408.0 |
| Fuel gas vents | .509.6.3, 509.7.4, 509.10.2, 510.0 |

| | |
|---------------------------------------|--|
| Flushometer valves and tanks | .610.10, 610.11 |
| Gray water | .1502.8 |
| Grease interceptors | .1014.2.1, 1014.3.6, Table 1014.2.1, Table 1014.3.6 |
| Hanger rods | .313.6 |
| Indirect waste pipes | .801.3.1, 803.3 |
| Leaders, conductors, and storm drains | .1103.0, Table 1101.12 |
| Louvers, grilles, and screens | .506.8 |
| Medical gas and medical vacuum pipe | .1310.2.1 |
| Mulch basins | .1502.11.2.2 |
| Oil tanks | .E 412.2 |
| Pipe cleanouts | .707.10, Table 707.1 |
| Rainwater catchment systems | .1602.6, K 104.13, L 504.13 |
| Reclaimed (recycled) water piping | .1501.14 |
| Roof drainage | .1101.12, 1105.1, 1602.9.12, Appendix D, K 104.12, L 504.11, Table 1101.8, Table 1103.3 |
| Sand interceptors | .1016.3 |
| Seepage pits and disposal fields | .H 301.0 |
| Septic tanks | .H 201.0 |
| Single-stack vent systems | .C 601.0 |
| Subsoil irrigation field piping | .1502.11.3.1 |
| Traps | .702.1, 910.4, 1003.3, 1006.1, 1101.15.2, Table 702.1 |
| Vacuum drainage systems | .C 501.2.1 |
| Vent pipes | .710.10, 810.1, 904.0, 908.1.1, 908.1.2, 908.2.2, C 401.0, Table 703.2, Table 810.1 |
| Water heaters | .501.1, Table 501.1(1) |
| Water piping | .610.0, Appendix A, E 302.0, Table 610.3, Table 610.4, Table A 103.1 |
| Water softener connections | .611.4 |
| Wet venting | .908.0 |
| SLAUGHTERHOUSES | .1010.0 |
| SLIP JOINTS | .221.0, 402.10, 509.10.9, 605.14, 705.8.1, 705.8.3, 1003.2 |
| SLOPE | .(see Grade) |
| SOIL PIPE | .221.0, 310.2, 310.4, 402.6.1, 402.6.3, 701.2(6), 722.2, 1002.4, Table 701.2 |
| SOIL POROSITY | .H 101.2 |
| SOLDER, BUSHINGS | .701.7, Table 701.7 |
| SOLDER JOINTS | .212.0, 309.2, 402.6, 605.1.3.1, 605.1.4, 605.16.1, 705.3.3, 705.9.1, 705.9.2, 1309.2, Table 313.3 |

SPACING

Pipe supports313.0, 1210.2.4.1,
1310.5, Table 313.3,
Table 1210.2.4.1,
Table 1310.5.4(1),
Table 1310.5.4(2)

Subsoil irrigation fields1502.11.3
Trenching and leaching bedsH 601.9

SPECIAL FIXTURES406.0

SPECIAL VENTING909.0

SPECIAL WASTE PIPE(see Industrial wastes)

SPECIAL WASTES

Acid811.2
Chemical811.0
Definition221.0
Industrial811.0
High temperatures810.1, Table 810.1
Laundries, slaughterhouses,
bottling establishments,
and auto wash racks711.0,
1010.0–1013.0

SPECIFIC GRAVITY,

NATURAL GAS1215.1

SPECIFICATIONS

FOR MATERIALS301.2, Table 1701.1

STACKS221.0, 317.1, 705.8.2,
706.2, 711.1, 906.1,
907.0, 911.4, 1101.16.2,
C 304.3, C 304.4,
C 401.0, C 601.0

STAINLESS STEEL PIPE605.13, 705.6,
Table 313.3,
Table 604.1,
Table 701.2

STANDPIPE, CLOTHES WASHER804.1

STATION INLETS221.0, 1317.0,
Table 1310.2.1(1)

STATION OUTLETS221.0, 1317.0,
Table 1310.2.1(1)

STEAM EXHAUST CONDENSER

OR BLOW OFF810.0, Table 810.1

STERILE EQUIPMENT806.0

STORAGE TANKS

Alternate water sources1502.3, 1503.4, 1504.4
Hot water505.2, 608.6, 608.7, L 602.2,
L 603.3.2, L 603.3.7
Potable waterE 707.0
Rainwater1602.7.3, 1602.9.5,
K 102.2, K 103.3,
K 104.4, K 104.4.1,
L 502.2, L 503.3, L 504.4
Vacuum drainageC 501.2.1

STORM DRAINAGE SYSTEMS ...Chapter 11, Appendix D

STORM DRAINS221.0, 1101.4.4, 1101.6,
1101.11, 1101.12, 1101.13,
1101.15, 1103.0, 1104.1

STORM SEWERS221.0, 715.3,
1101.2, 1101.4.5,
1101.12.2.2.2,
1101.13.1, 1103.2, 1104.1

STRAINERS

AND CONNECTIONS407.5, 408.4,
810.4, 1012.1, 1102.2

S-TRAP PROHIBITED1004.1

STREET MAIN; (SEE WATER MAIN)225.0, 608.1,
608.3, 610.7,
A 104.2, A 104.4,
Table 721.1, Table 1502.4,
Table H 101.8

STRUCTURAL CONDITION SAFETY312.2, 312.11

SUBMITTAL OF PLANS103.3, 104.3,
104.3.2, 104.3.3,
301.5.3, 811.1,
910.2, 1105.1,
1304.5, 1304.5.2,
1503.2.1, 1504.2,
1602.2, C 301.1,
C 501.1, E 102.1, H 501.1,
K 101.3.1, L 501.3.1

SUBSOIL DRAINS221.0, 1101.4.6, 1101.6,
1101.8, 1101.9,
Table 1101.4.6

SUBSOIL IRRIGATION FIELDS221.0, 1502.2.1,
1502.9.3, 1502.10.1,
1502.11.3, Table 1502.4

SUBSTITUTE MATERIALS301.3

SUBSURFACE DISPOSAL FIELDS1502.10, H 101.2

SUBSURFACE IRRIGATION FIELDS221.0, 1502.2.1,
1502.11.1, 1503.1

SUDS RELIEF711.0

SUMPS

Boiler room, installation810.1, 810.3

Building, backwater

devices710.1, 710.3, 710.4, 710.6

Building drainage

systems below sewer level710.2

Condensers810.0, Table 810.1

Construction810.2

Definition221.0

Macerating toilet systems710.13.1

Pump connection permitted710.2–710.5, 710.9,
805.1, 1101.6.2, 1101.7

Pump discharges, conversion

to fixture units702.3, 710.5

Sewage710.2

Sizing, sewage

ejector and pumps710.3

Storm drainage1101.6.2, 1101.6.3, 1101.7,
1101.10, 1101.11, 1101.14

Vents710.7, 710.10, 710.13.3,
810.1, Table 810.1

Water supply inlets603.5.5

SUPPLY, WATER

| | |
|---------------------------------|---|
| Fittings, fixtures | 402.7 |
| Fixture, definition | 208.0 |
| Fixture units | 610.3, 610.7–610.10, C 303.2, C 501.5, E 302.1, E 305.1, L 402.3.1, Table 610.3, Table 610.10, Table A 103.1 |
| Hot water | 601.2, 602.1, 603.4.5, 603.5.10, 608.7, 609.1, 609.4, 610.3, 610.12.1, 610.12.2, L 602.5, L 603.3, Table 610.3, Table A 103.1, Table C 303.1(1) |
| Materials | 604.0, 1502.9.2–1502.9.4, 1503.6, 1504.6, 1602.7, K 103.4, L 503.4, Table 604.1 |
| Nonpotable water | 601.3, 603.5.11, 1504.6 |
| Pipe, size of | 610.0, Table 610.3, Table 610.4, Table A 103.1, Table C 303.1(1) |
| Potable water, protection | 409.5, 410.2, 412.2, 414.2, 419.3, 602.0, 603.0, 1303.5, 1502.3, 1503.4, 1504.4, 1602.4, E 703.1, K 101.9, K 102.2, L 501.9, L 502.2 |
| Pressure | 608.0, 1602.9.6, E 705.1, K 104.5, L 504.5 |
| Quality | 601.2, 1501.7, 1504.7, 1504.10.2, 1602.9.4, 1602.9.8, E 301.1, K 101.7, K 104.2, K 104.7, L 501.7, L 504.2, L 504.7 |
| Quantity | 413.1–413.4, 416.2, 419.3, 610.3, E 301.1 |
| Risers | 408.10, E 302.1 |
| Tanks, water | 603.5.5, 608.1 |
| Testing | 609.4 |
| Valves | 606.0 |
| SUPPORTS | 221.0, 313.0, 402.4, 507.3, 507.3.1, 507.4, 507.19, 509.5.8, 509.6.5, 509.7.5, 509.10.8, 609.1, 718.2, 906.4, 1208.6.2, 1208.11.1, 1210.2, 1210.2.4, 1310.5, E 404.1, E 412.3, E 413.2, F 901.4, H 601.3, L 602.5, Table 313.3, Table 1210.2.4.1, Table 1310.5.4(1) |

| | |
|---------------------------------------|---|
| SURFACE WATER, DISCHARGE | 306.2, 714.2, 811.1, 1101.1, 1101.11 |
|---------------------------------------|---|

| | |
|--------------------------|-------|
| SURGE TANKS | 221.0 |
|--------------------------|-------|

| | |
|---|---|
| SWIMMING POOLS, SPAS, AND HOT TUBS | 603.5.5, 603.5.20, 813.0, L 407.1, L 603.3.6 |
|---|---|

SYSTEMS

| | |
|--|---|
| Chimney venting | 509.5.5, 509.6.3 |
| Circuit venting | 911.0 |
| Combination waste and vent | 205.0, 910.0, Appendix B |
| Defective, testing of | 105.3.1 |
| Dialysis water | 603.5.18.1 |
| Direct-vent | 509.6.2, 509.8.2 |
| Durham, definition | 206.0 |
| Engineered | 509.10.7.1, 912.0, C 201.1 |
| Exhaust | 507.22, 509.3.4, 509.6.2 |
| Fire protection | 603.5.14, 612.0 |
| Firefighter breathing air replenishment | Appendix F |
| Firestop | Chapter 14 |
| FOG disposal | 1015.0 |
| Fuel gas piping | 507.18, Chapter 12, E 401.0–E 415.4 |
| Fuel gas venting | 509.0, 510.0, Table 509.4 |
| Gray water | 601.3.3, 1502.0 |
| Independent | 311.0 |
| Lightning protection | 1211.4 |
| Macerating toilet | 710.13 |
| Mechanical draft | 509.3.3, 509.8, 509.10.3.2, 509.10.6 |
| Medical gas and medical vacuum | 319.0, Chapter 13 |
| Natural draft venting | 509.6.3.1 |
| On-site treated nonpotable | 601.3.3, 1504.0 |
| Plumbing vent, definition | 218.0 |
| Plumbing venting | 710.7, Chapter 9, C 401.0 |
| Potable water | 225.0, Chapter 6, E 301.0–E 312.1, Appendix A |
| Private sewage disposal | 713.2, 713.3, 713.5, 714.0, 716.1, 723.1, 904.1, Appendix H |
| Pure water process | 603.5.18 |
| Rainwater catchment | 220.0, 601.3.3, Chapter 16, Appendix K, L 501.0, |
| Reclaimed (recycled) | 601.3.3, 1503.0 |
| Sanitary drainage | Chapter 7, E 201.0–E 207.2, E 901.0–E 905.1 |
| Single-stack vent | C 601.0 |
| Sprinkler | 612.0 |
| Storm water drainage | Chapter 11, Appendix D |
| Ultraviolet water treatment | 611.1 |

Vacuum drainageC 501.0
 Ventilation506.1.3, 506.7.3
 Wet vent908.2.5

- T -

T RATING222.0, 1404.3,
 1405.3, 1406.4

TAILPIECES

Connection414.3, 419.2, 910.5, 910.6
 Definition222.0
 Maximum length of910.5, 1001.2
 Sizes407.5, 408.4, 409.2, 420.4,
 B 101.3, B 101.5, B 101.6.1

TANKS

DosingH 601.8
 Expansion608.2, 608.3, 812.1
 Flush208.0, 402.4, 404.1, 411.2,
 413.0, 601.2, A 104.1
 Flushometer610.11, A 106.3
 Hot water storage608.3, 608.6, 608.7,
 L 602.2
 Materials710.8, 810.2
 Oil1017.1, E 412.2, E 412.3, E 413.6
 Rainwater storage1602.7.3, 1602.9.5,
 K 102.2, K 103.3,
 K 104.4, K 104.4.1, L 502.2,
 L 503.3, L 504.4
 Reclaimed water storage1503.4, 1503.12
 Septic714.3, 716.1, 722.2-722.4,
 Appendix H
 Sump or receiving710.2, 710.7-710.10,
 810.2, 1101.7
 Surge221.0, 1502.2.1, 1502.9.1,
 1502.9.6, 1502.14, Table 1502.4
 Urinal603.5.2
 Water closet404.1, 405.1, 601.2, 603.5.2,
 603.5.3, L 402.2
 Water supply608.1, 608.6,
 608.7, E 707.0, E 1201.1

TEMPERATURE AND

PRESSURE-RELIEF VALVES504.6, 505.2

TEMPERATURE-LIMITING DEVICES407.3, 408.3,
 409.4, 410.3, 504.5

TEMPORARY USE OF GAS1207.0

TERMINATION OF VENTS509.6.2, 906.0

TESTS

Air105.3, 105.3.1,
 609.4, 712.3,
 723.1, 1106.2.2, 1106.2.3,
 1213.1.6
 Alternate materials and methods301.3
 Building sewer102.4.1, 105.2.1,
 105.2.1.2, 723.0
 Exceptions105.3, 1106.2.3
 Final712.1
 Fuel gas piping1213.0

Gauges318.0, 1203.3.2
 Percolation1502.7, 1502.10.2, H 401.0
 Required105.3
 Responsibility for105.2.5
 Shower receptors408.7.5
 Storm drainage1106.0
 Testing agency301.3.1.1, 505.4,
 610.2, 1406.4

Water609.4, 712.2,
 1106.2.1, 1106.2.3

Water supply systems105.2.1.1, 609.4

THREADED JOINTS605.1.5, 605.2.3,
 605.5.2, 605.11.3,
 605.12.3, 605.16.1,
 705.1.3, 705.3.4,
 705.4.2, 705.5.3,
 705.9.2, 1208.5.7,
 1208.5.8.1, 1309.4.3

THREE-COMPARTMENT SINKS1001.2

TOILETS(see Water closets)

TOILETS, FAMILY

OR ASSISTED - USE FACILITY422.21

TRACER WIRE604.10.1, 1210.1.7.2

TRANSITION GAS RISER222.0, 1210.3.4

TRANSITION JOINTS705.8.4

TRAPSChapter 10

Arms222.0, 707.14, 1002.2, 1002.3,
 Table 702.1, Table 1002.2

Bar and fountain sinks801.4, 902.2

Building1008.0

Bottle1004.1

Condensers and sumps810.1

Crown weir222.0, 409.6,
 905.5, 1001.2,
 1002.2, 1002.4

Definition222.0

Drum1004.1

Floor drains704.3, 1003.1,
 1006.0, 1007.1

Food storage areas418.4, 801.3.2

For three-compartment
 sinks or three lavatories1001.2

From fixture, distance of1001.2

From vent, distance of1002.2, Table 1002.2

Gray water system1502.9.6

Grease interceptors1014.1.1

Indirect wastes803.3

Integral1001.2

Island sinks909.1

Materials807.2, 906.6, 1003.1

Minimum size702.1, 1003.3, Table 702.1,
 Table 702.2(1)

Nonwater urinals412.1.1

Prohibited types1004.0

Required1001.0

VACUUM SYSTEM –**LEVEL 1, DEFINITION**224.0**VALIDITY OF CODE**101.5**VALVES**

Backwater204.0, 710.1, 710.3,
710.6, 904.1,
1006.1, 1502.2.3,
1502.9.1, 1502.9.7,
1602.9.5.5, K 104.4.3,
L 504.4.3

Ball606.1, 606.4, 710.4, 710.6

Bathtub filler409.5

Check603.5.10, 608.3, 710.4,
710.12.1, 710.13.2,
1004.2, 1208.8.1,
1315.5.4, F 701.3

Combination stop-and-waste603.5.17

Combination temperature
and pressure-relief505.2, 608.3

Combination thermostatic/
pressure balancing205.0, 408.3

Control408.9, 601.2,
606.5, 606.6,
1303.1, 1320.2,
C 501.3

Diaphragm-type507.22, 1208.7.6

Excess flow207.0, 1209.0

Flow balancingL 601.7

Flush, definition208.0

Flushometer208.0, 411.2.2,
413.1, 413.2, 601.2,
603.5.1, 610.10,
A 104.1, L 402.2.2,
Table 610.10

Fullway606.2, 710.6

Gate606.1, 606.4,
710.3, 710.4, 710.6

Gray water diverter209.0, 1502.2.2

Installation310.7

Isolation224.0, F 501.7,
F 701.3, F 801.6

Mixing417.5

Pre-rinse spray420.3, L 201.0

Pressure-balancing218.0, 408.3

Pressure-reducing1502.11.1.6, 1602.9.6,
612.7.2, A 107.2, F 501.7,
F 701.3, L 504.5

Pressure-relief504.4, 504.6,
507.9, 608.2–608.6,
1313.1.2, 1316.0,
1317.3, 1314.1.1,
1314.2, 1320.2,
E 308.0, E 309.1,
F 501.7, F 501.8,
F 701.3

Quick-acting609.10

Riser224.0, 1312.4, 1312.9.2

Service224.0, 1312.5

Shutoff504.6, 606.2, 606.3,
606.6, 608.4, 609.8,
710.12.1, 1202.1, 1203.3.2,
1208.9, 1208.10, 1210.2.2.1,
1210.9.1.1, 1210.11, 1212.5,
1213.2.5, 1213.6.1.3,
1312.1, 1312.2, 1312.9,
1312.9.2, 1315.2, 1502.9.1,
1602.9.5.5, E 306.0,
E 403.0, E 404.3, E 410.4,
E 412.3, E 413.5, E 1104.1,
E 1201.1, F 601.1, K 104.4.3,
L 402.3.1, L 404.6, L 410.3,
L 413.1, L 504.4.3

Source224.0, 1312.2, 1312.3,
1312.9.2, 1319.7.2

Temperature relief504.5, 504.6, 505.2

Thermostatic222.0, 408.3

Transfer417.2

Vacuum interfaceC 501.2.4

Vacuum relief224.0, 504.6,
607.5, 608.7, 1503.10,
1504.10.3, 1602.9.2

Zone224.0, 1312.6,
1312.6.2, 1312.6.4,
1312.6.4.1, 1316.3

VENT, PLUMBINGChapter 9

Below trap weir905.5, 1002.4

Branch, definition204.0

Buildings over 10 stories907.1

Changes in direction of903.3

Chemical811.2, 811.5, 811.6

Combination waste and
vent system design205.0, 910.0,
Appendix B

Connections310.2, 805.0,
905.1, 905.2, 908.1.2,
908.2.1, 911.2,
1502.2.2, Table 810.1

Continuous, definition205.0

Distance of trap from1002.2, Table 1002.2

Double fitting for704.2, 905.6

Engineered912.0

Expansion joints705.8.2

Fittings701.2, 903.1, Table 701.2

Fixtures, back-to-back704.2, 905.6

Flagpoling, prohibited906.3

Flashing for312.8, 701.5, 906.1,
906.5, 906.6

Frost or snow closure906.7

Grade of905.1, 905.3, 911.3

Height above fixture905.3

| | |
|---|--|
| Height above grade | .906.4 |
| Horizontal | .904.2, 905.3, Table 703.2 |
| Indirect waste | .803.3, 805.1, 902.1 |
| Individual, definition | .211.0 |
| Interceptors | .902.1, 1009.4, 1014.1.1, 1014.2.2, 1016.4, 1017.1 |
| Island sinks and fixtures | .909.0 |
| Length of | .904.0, Table 702.1, Table 703.2 |
| Material for | .701.0, 811.2, 903.0, 1502.9.2, Table 701.2 |
| Method of installation | .310.5, 903.3, 906.2, 906.4 |
| Not required | .902.0 |
| Not to be used as soil or waste pipe | .310.4 |
| Opening location | .905.5, 1002.4 |
| Parallel | .907.1 |
| Piping, support of | Table 313.3 |
| Prohibited | .310.4, 903.1, 903.2.2 |
| Relief | .220.0, 805.0, 907.0, 911.4, 1009.4 |
| Required | .901.2, 904.1 |
| Required separately on every trap | .901.2, 1002.1, 1002.2 |
| Sizing | .703.0, 904.0, 908.1.1, 908.1.2, 908.2.2, 910.4, C 401.0, C 601.2, Table 702.1, Table 703.2, Table C 401.1 |
| Special | .909.0 |
| Stack | .224.0, 906.1, 907.0, C 401.2, C 601.2 |
| Sump | .710.7, 710.10, 710.13.3, 810.1, Table 810.1 |
| System, definition | .224.0 |
| Termination | .905.4, 906.0 |
| Testing | .712.0, 1502.14 |
| Trap seal protection | .901.3, 1002.0 |
| Undiminished in size through roof | .905.4, 907.1 |
| Unit loading | Table 703.2 |
| Wet, Horizontal | .908.2 |
| Wet, Vertical | .908.1 |
| Yoke | .227.0, 907.0 |
| VENTILATING HOODS | .509.2.2, 509.3.4 |
| VERTICAL-TO-HORIZONTAL DRAINAGE FITTINGS | .706.4, 905.2, 905.3, 909.0 |
| VERTICAL WET VENTING | (see Wet vent) |
| VIOLATION, NOTICES OF | .106.2 |
| VITRIFIED CLAY PIPE | .701.2, 705.7, 811.2, Table 701.2, Table 1101.4.6 |

- W -

| | |
|--|--------------------------|
| WALL, EXTENSION THROUGH . . . | .312.1, 509.6.2.3, 509.8 |
| WALL-HUNG FIXTURES, INSTALLATION OF | .402.4, 402.6 |
| WASH RACKS, AUTO | 1011.0 |

WASTES

| | |
|-------------------------------|--|
| Anesthetic gas disposal | .225.0, 1301.2 |
| Chemical | .205.0, 811.0, 903.2.2 |
| Clear water | .205.0, 812.0 |
| Condensate | .807.2, 814.0 |
| Continuous | .205.0, 407.5, 408.4, 409.2, 419.2 |
| Cooling water | .808.0 |
| Definition | .225.0 |
| Detrimental or harmful | .305.1, 306.1, 714.1, 811.1, 1009.1, H 901.1 |
| Flammable | .1009.1, H 901.1 |
| Indirect | Chapter 8, 1303.4.1 |
| Industrial | .211.0, 306.0, 801.1, 811.1, 903.2.2 |
| Liquid | .214.0, 303.0, 304.0, 710.2, 811.1, 1006.1, 1009.1, H 101.3, H 701.1, H 901.1, L 302.0 |
| Materials, pipe | .701.1, 811.2 |
| Pipe, definition | .225.0 |
| Pretreatment required | .811.1, 1014.1 |
| Process | .1013.1 |
| Special, definition | .221.0 |
| Swimming pools | .813.1 |

WATER

| | |
|------------------------------------|------------------------------|
| Backflow prevention | .603.3, Table 603.2 |
| Cross contamination | .601.2, 602.2, 603.1-603.3.9 |
| Distribution piping material | .604.1, Table 604.1 |
| Distribution system design | .601.1 |
| Excessive pressure | .608.2 |
| Hammer | .609.10 |
| Identification | .601.3 |
| Lead content | .604.2, 604.2.1 |
| Nonpotable | .603.5.11, 1504.6 |
| Pressure booster | .609.8 |
| Rainwater, material | .1101.4 |
| Reclaimed | .1602.4 |
| Storm water | (see Storm drainage) |
| Supply piping material | .604.1, Table 604.1 |
| Treatment units | .611.0 |

WATER CLOSETS

| | |
|----------------------------------|--|
| Approved standards | .411.1 |
| Clearance | .402.5 |
| Compartments | E 609.0, E 610.0 |
| Flanged fixture Connection | .402.6 |
| Floor-mounted, back-outlet | .402.6.3 |
| Seats | .411.3 |
| Manufactured/Mobile home | E 601.1, E, 603.0, E 605.0, E 608.0 |
| Prohibited | .405.1, 910.7 |
| Water consumption | .411.2, L 402.2 |

WATER-CONSERVING

| | |
|---|---|
| FIXTURES AND FITTINGS | L 402.0 |
| WATER HAMMER ARRESTORS | .225.0, 609.10 |
| WATER HEATERS | Chapter 5 |
| Access | .504.3.1, 507.13.2, 507.26, 508.1, 508.3, 508.4, 509.11.5 |
| Approval requirements | .501.1 |
| Approved standards | Table 501.1(2), 505.3, 505.4 |
| Clearances | .504.3–504.3.2, 508.1, 508.2.1 |
| Combustion air required | .506.0 |
| Connectors | .604.13 |
| Definition | .225.0 |
| Garages | .507.13 |
| Inspections | .503.2 |
| Installation | .507.0 |
| Location | .504.1, 507.12–507.15 |
| Oil-burning and other | .505.0 |
| Permits required | .502.0 |
| Pressure-relief valves | .504.4, 504.6, 505.2, 608.2–608.5 |
| Protection | .504.3–504.6, 505.2, 507.2, 507.8, 507.10, 507.14.1, 507.25 |
| Relief valve discharge | .608.5 |
| Seismic provisions | .507.2 |
| Temperature and pressure-relief valves | .504.6, 505.2 |
| Temperature-limiting devices | .504.5 |
| Vents | .509.0, 510.0 |
| WATER SOFTENERS | .611.4, Table 611.4 |
| WATER TESTS | |
| Building sewers | .723.0 |
| Drainage and vent systems | .105.3, 712.2 |
| Storm drainage | .1106.2.1, 1106.2.3 |
| Water supply systems | .105.2.1.1, 105.3, 609.4 |
| WATER TREATMENT DEVICES | (see Water conditioning) |
| WATERPROOFING AND WATERTIGHT | |
| Building sewer | .723.1 |
| Cleanouts | .707.3 |
| Connections | .105.3 |
| Drain pans | .507.5 |
| Fixtures | .402.2, 408.5, 408.7, 418.2 |
| Flashings | .312.8, 906.5, 1102.3 |
| Interceptors | .1016.3 |
| Joints | .105.3, 1502.11.3.3, E 204.2, H 601.4, H 601.6, H 601.7, H 601.10, H 801.4 |
| Openings | .312.8, 312.10.2, 317.1 |
| Sump or receiving tanks | .710.2, 710.8 |
| Tanks | .714.5, 1502.9.1, 1502.14, 1602.9.5.1, E 707.1, H 501.3, H 1001.2, K 104.4.1 |
| Vacuum drainage systems | .C 501.8 |

WATER/WASTEWATER

| | |
|--|---|
| UTILITY, DEFINITION | .225.0 |
| WEEP HOLES, SUBDRAIN OF SHOWER STALLS | .408.7 |
| WEIGHT OF FLASHING, LEAD | .701.5, 906.6, 1102.3.1 |
| WEIGHTS AND QUALITY OF MATERIALS | .301.2, 401.2, 604.1, 701.2, 906.6, 1102.3.1 |
| WELDED JOINTS | .212.0, 605.13.2, 705.6.2, 1208.5.8.1, F 1101.2 |
| WELDER, PIPE, DEFINITION | .225.0 |
| WELL, DISTANCE FROM SEWAGE DISPOSAL | .721.1, H 101.8, Table 721.1, Table H 101.8 |
| WET VENTS | .908.0 |
| Definition | .225.0 |
| Fixtures | .908.2.3, 908.2.4 |
| Horizontal | .908.2, B 101.2, C 601.6 |
| Vent connection | .908.2 |
| Vertical | .908.1 |
| WHIRLPOOL BATHTUBS | .225.0, 409.0 |
| WINDOW, TERMINATION OF VENTS FROM | .906.2 |
| WOODEN SINKS AND TILE WASH TRAYS OR SINKS | .405.3 |
| WORK, CONCEALED | .105.0–105.2.1.2, 309.2, 402.10, 503.0–503.2, 509.7.3.2, 1004.1, 1203.2, 1203.3, 1210.3, 1212.3.1, 1212.4.3, 1213.2.1, 1303.2, 1310.7, 1406.1 |
| WORK, EXISTING | .102.2, 102.4, 207.0 |
| WORKMANSHIP | .309.0, 609.1, 1208.5.5 |
| WRAPPING OF PIPE | .609.3, 1210.2, E 409.2 |
| WROUGHT IRON (GALVANIZED) | .402.6.1, 604.6, 604.7, 701.2, 707.1, 1101.4, 1208.5.2.1, 1208.5.8.4, E 409.1, Table 604.1 |
| WYE CONNECTIONS | .414.3, 419.2, 706.2–706.4, 707.5, 707.6, 710.4, 719.4, 907.2, 909.1, 1101.16.2 |
| – X – | |
| X-RAY DARKROOMS | .811.8 |
| – Y – | |
| YOKE VENTS | .227.0, 907.0 |
| – Z – | |
| ZINC ALLOY COMPONENTS | .406.4, 1208.5.8. |

BOARD of SUPERVISORS



City Hall
Dr. Carlton B. Goodlett Place, Room 244
San Francisco 94102-4689
Tel. No. 554-5184
Fax No. 554-5163
TDD/TTY No. 554-5227

October 6, 2016

Lisa Gibson
Acting Environmental Review Officer
Planning Department
1650 Mission Street, Ste. 400
San Francisco, CA 94103

Dear Ms. Gibson:

On September 6, 2016, Building Inspection Commission introduced the following proposed legislations:

File No. 160944

Ordinance repealing the 2013 Building Code in its entirety and enacting a 2016 Building Code consisting of the 2016 California Building Code and the 2016 California Residential Code, as amended by San Francisco; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing for an operative date of January 1, 2017; and directing the Clerk of the Board to forward the legislation to the California Building Standards Commission as required by State law.

File No. 160945

Ordinance adding the provisions of the 2016 California Residential Code with local amendments into various chapters of the 2016 San Francisco Building Code, and adding Chapter 36 to the Building Code to serve as a directory of where such provisions may be found; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing for an operative date of January 1, 2017; and directing the Clerk of the Board to forward the legislation to the California Building Standards Commission as required by State law.

File No. 160946

Ordinance repealing the 2013 Electrical Code in its entirety and enacting a 2016 Electrical Code consisting of the 2016 California Electrical Code as amended by San Francisco; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing an operative date of January 1, 2017; and directing the Clerk of the Board of Supervisors to forward the legislation to the California Building Standards Commission as required by State law.

File No. 160947

Ordinance enacting a 2016 San Francisco Existing Building Code consisting of the 2016 California Existing Building Code with San Francisco amendments; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing for an operative date of January 1, 2017; and directing the Clerk of the Board to forward the legislation to the California Building Standards Commission as required by State law.

File No. 160948

Ordinance repealing the 2013 Green Building Code in its entirety and enacting a 2016 Green Building Code consisting of the 2016 California Green Building Standards Code as amended by San Francisco; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing for an operative date of January 1, 2017; and directing the Clerk of the Board of Supervisors to forward the legislation to the California Building Standards Commission as required by State law.

File No. 160949


Ordinance repealing the 2013 Mechanical Code in its entirety and enacting a 2016 Mechanical Code consisting of the 2016 California Mechanical Code as amended by San Francisco; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing an operative date of January 1, 2017; and directing the Clerk of the Board of Supervisors to forward the legislation to the California Building Standards Commission as required by State law.

File No. 160950

Ordinance repealing the 2013 Plumbing Code in its entirety and enacting a 2016 Plumbing Code consisting of the 2016 California Plumbing Code as amended by San Francisco; adopting environmental findings and findings of local conditions under the California Health and Safety Code; providing an operative date of January 1, 2017; and directing the Clerk of the Board of Supervisors to forward the legislation to the California Building Standards Commission as required by State law.

This legislation is being transmitted to you for environmental review.

Angela Calvillo, Clerk of the Board

 By: Alisa Somera, Legislative Deputy Director
Land Use and Transportation Committee

Attachment

c: Joy Navarrete, Environmental Planning
Jeanie Poling, Environmental Planning



August 26, 2016

Angela Calvillo, Clerk of the Board
Board of Supervisors
#1 Dr. Carlton B. Goodlett Place, Room 244
San Francisco, CA 94102-4689

RECEIVED
BOARD OF SUPERVISORS
SAN FRANCISCO
2016 AUG 29 AM 11:12
31

Dear Ms. Calvillo:

Attached please find an original and two copies (1 electronic CD) of seven proposed ordinances (approved by the Building Inspection Commission on August 17, 2016) for the Board of Supervisors approval, which repeal the San Francisco amendments to the 2013 California Building Standards Codes and adopt replacement amendments to the new 2016 California Building Standards Codes effective January 1, 2017. (One copy of these 2016 California Building Standards Codes are hereby provided for your reference in the form of each California adopted model code and their associated California amendments to them.)


The following is a list of accompanying documents:

- 1) Approval letter from the Building Inspection Commission
- 2) Exhibit A, Standard Findings
- 3) San Francisco Building Code Ordinance, Legislative Digest (Includes Residential Code below), Findings, proposed amendment text (Building)
- 4) San Francisco Building Code; Residential Building Requirements Ordinance, Legislative Digest (included in Building Code above). Findings, proposed amendment text. (Residential)
- 5) San Francisco Existing Building Code Ordinance, Legislative Digest, Findings, proposed amendment text. (Existing Building)
- 6) San Francisco Electrical Code Ordinance, Legislative Digest, Findings, proposed amendment text (Electrical)
- 7) San Francisco Mechanical Code Ordinance, Legislative Digest, Findings, proposed amendment text (Mechanical)
- 8) San Francisco Plumbing Code Ordinance, Legislative Digest, Findings, proposed amendment text (Plumbing)
- 9) San Francisco Green Building Code Ordinance, Legislative Digest, Findings, proposed amendment text (Green), Cost effectiveness study.

In order for the San Francisco code amendments to coordinate with the California codes, which have an effective date of January 1, 2017, the timeline for approval and adoption requires that the codes be submitted to the Board of Supervisors on or before August 29, 2016 for introduction and assignment to the Land Use Committee (on September 6, 2016), a thirty-day review and comment period follows prior to hearing at the Land Use Committee on October 17, 2016. When approved, it is proposed that

the Board of Supervisor agenda Readings on October 25, 2016 and November 1, 2016. Upon their approval, the ordinances will be forwarded to the Mayor for signature within 10 days, followed by a 30-day wait period (ending approximately December 12, 2016) before filing with the California Building Standards Commission to become effective for an implementation date of January 1, 2017.

The following person may be contacted regarding this matter:



Kirk Means, Building Inspector
Technical Services Division
Department of Building Inspection
Phone: (415) 575-6832
Fax: (415) 558-6401

Attachments: As stated

Table of Contents

1. General
 - a. Approval letter from the Building Inspection Commission
 - b. Exhibit A – Standard Findings
2. Building Code
 - a. Legislative Digest
 - b. San Francisco Building Code Ordinance
 - c. Findings
 - d. San Francisco Building Code Amendments
3. Residential Code
 - a. Legislative Digest (Included in Building Code Digest above)
 - b. San Francisco Building Code; Residential Building Requirements Ordinance
 - c. Findings – See Chapter 36 of the Building Code Findings
 - d. Residential Building Requirements – See Chapter 36 of the San Francisco Building Code
4. Existing Building Code
 - a. Legislative Digest
 - b. San Francisco Existing Building Code Ordinance
 - c. Findings
 - d. San Francisco Existing Building Code Amendments
5. Electrical Code
 - a. Legislative Digest
 - b. San Francisco Electrical Code Ordinance
 - c. Findings
 - d. San Francisco Electrical Code Amendments
6. Mechanical Code
 - a. Legislative Digest
 - b. San Francisco Mechanical Code Ordinance
 - c. Findings
 - d. San Francisco Mechanical Code Amendments
7. Plumbing Code
 - a. Legislative Digest
 - b. San Francisco Plumbing Code Ordinance
 - c. Findings
 - d. San Francisco Plumbing Code Amendments
8. Green Code
 - a. Legislative Digest
 - b. San Francisco Green Building Code Ordinance
 - c. Findings
 - d. San Francisco Green Building Code Amendments
 - e. Cost Effectiveness Study

